TEXAS INSTRUMENTS-PRODUCTION DATA



# Stellaris® LM3S9D96 Microcontroller

DATA SHEET

### Copyright

Copyright © 2007-2012 Texas Instruments Incorporated All rights reserved. Stellaris and StellarisWare® are registered trademarks of Texas Instruments Incorporated. ARM and Thumb are registered trademarks and Cortex is a trademark of ARM Limited. Other names and brands may be claimed as the property of others.

PRODUCTION DATA information is current as of publication date. Products conform to specifications per the terms of Texas Instruments standard warranty. Production processing does not necessarily include testing of all parameters.

NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

A Please be aware that an important notice concerning availability, standard warranty, and use in critical applications of Texas Instruments semiconductor products and disclaimers thereto appears at the end of this data sheet.

Texas Instruments Incorporated
108 Wild Basin, Suite 350
Austin, TX 78746
http://www.ti.com/stellaris
http://www-k.ext.ti.com/sc/technical-support/product-information-centers.htm







### **Table of Contents**

Revision His	story	42
About This I	Document	45
Audience		45
About This Ma	anual	45
	ments	
Documentatio	n Conventions	46
1	Architectural Overview	48
1.1	Overview	48
1.2	Target Applications	50
1.3	Features	
1.3.1	ARM Cortex-M3 Processor Core	
1.3.2	On-Chip Memory	
1.3.3	External Peripheral Interface	53
1.3.4	Serial Communications Peripherals	55
1.3.5	System Integration	
1.3.6	Advanced Motion Control	
1.3.7	Analog	68
1.3.8	JTAG and ARM Serial Wire Debug	
1.3.9	Packaging and Temperature	
1.4	Hardware Details	70
2	The Cortex-M3 Processor	71
2.1	Block Diagram	72
2.2	Overview	73
2.2.1	System-Level Interface	73
2.2.2	Integrated Configurable Debug	73
2.2.3	Trace Port Interface Unit (TPIU)	74
2.2.4	Cortex-M3 System Component Details	74
2.3	Programming Model	75
2.3.1	Processor Mode and Privilege Levels for Software Execution	75
2.3.2	Stacks	75
2.3.3	Register Map	76
2.3.4	Register Descriptions	77
2.3.5	Exceptions and Interrupts	90
2.3.6	Data Types	90
2.4	Memory Model	90
2.4.1	Memory Regions, Types and Attributes	92
2.4.2	Memory System Ordering of Memory Accesses	93
2.4.3	Behavior of Memory Accesses	93
2.4.4	Software Ordering of Memory Accesses	94
2.4.5	Bit-Banding	
2.4.6	Data Storage	97
2.4.7	Synchronization Primitives	
2.5	Exception Model	
2.5.1	Exception States	
2.5.2	Exception Types	

2.5.3	Exception Handlers	103
2.5.4	Vector Table	103
2.5.5	Exception Priorities	104
2.5.6	Interrupt Priority Grouping	105
2.5.7	Exception Entry and Return	105
2.6	Fault Handling	107
2.6.1	Fault Types	108
2.6.2	Fault Escalation and Hard Faults	
2.6.3	Fault Status Registers and Fault Address Registers	
2.6.4	Lockup	
2.7	Power Management	
2.7.1	Entering Sleep Modes	
2.7.2	Wake Up from Sleep Mode	
2.8	Instruction Set Summary	
	•	
3	Cortex-M3 Peripherals	
3.1	Functional Description	
3.1.1	System Timer (SysTick)	
3.1.2	Nested Vectored Interrupt Controller (NVIC)	
3.1.3	System Control Block (SCB)	
3.1.4	Memory Protection Unit (MPU)	
3.2	Register Map	
3.3	System Timer (SysTick) Register Descriptions	
3.4	NVIC Register Descriptions	
3.5	System Control Block (SCB) Register Descriptions	
3.6	Memory Protection Unit (MPU) Register Descriptions	170
4	JTAG Interface	180
4.1	Block Diagram	181
4.2	Signal Description	181
4.3	Functional Description	182
4.3.1	JTAG Interface Pins	182
4.3.2	JTAG TAP Controller	184
4.3.3	Shift Registers	184
4.3.4	Operational Considerations	185
4.4	Initialization and Configuration	187
4.5	Register Descriptions	188
4.5.1	Instruction Register (IR)	188
4.5.2	Data Registers	190
5	System Control	192
5.1	Signal Description	
5.2	Functional Description	
5.2.1	Device Identification	
5.2.2	Reset Control	
5.2.3	Non-Maskable Interrupt	
5.2.4	Power Control	
5.2.5	Clock Control	
5.2.6	System Control	
5.3	•	
ວ.ວ	Initialization and Configuration	207
5.4	Initialization and ConfigurationRegister Map	

5.5	Register Descriptions	209
6	Internal Memory	300
6.1	Block Diagram	300
6.2	Functional Description	300
6.2.1	SRAM	301
6.2.2	ROM	301
6.2.3	Flash Memory	303
6.3	Register Map	309
6.4	Flash Memory Register Descriptions (Flash Control Offset)	310
6.5	Memory Register Descriptions (System Control Offset)	322
7	Micro Direct Memory Access (µDMA)	346
7.1	Block Diagram	
7.2	Functional Description	347
7.2.1	Channel Assignments	348
7.2.2	Priority	349
7.2.3	Arbitration Size	349
7.2.4	Request Types	350
7.2.5	Channel Configuration	351
7.2.6	Transfer Modes	352
7.2.7	Transfer Size and Increment	361
7.2.8	Peripheral Interface	361
7.2.9	Software Request	361
7.2.10	Interrupts and Errors	362
7.3	Initialization and Configuration	362
7.3.1	Module Initialization	362
7.3.2	Configuring a Memory-to-Memory Transfer	363
7.3.3	Configuring a Peripheral for Simple Transmit	364
7.3.4	Configuring a Peripheral for Ping-Pong Receive	366
7.3.5	Configuring Channel Assignments	368
7.4	Register Map	368
7.5	μDMA Channel Control Structure	370
7.6	μDMA Register Descriptions	377
8	General-Purpose Input/Outputs (GPIOs)	407
8.1	Signal Description	407
8.2	Functional Description	412
8.2.1	Data Control	413
8.2.2	Interrupt Control	414
8.2.3	Mode Control	415
8.2.4	Commit Control	415
8.2.5	Pad Control	416
8.2.6	Identification	416
8.3	Initialization and Configuration	416
8.4	Register Map	417
8.5	Register Descriptions	419
9	External Peripheral Interface (EPI)	462
9.1	EPI Block Diagram	
9.2	Signal Description	

9.3	Functional Description	. 466
9.3.1	Non-Blocking Reads	. 467
9.3.2	DMA Operation	. 468
9.4	Initialization and Configuration	. 468
9.4.1	SDRAM Mode	. 469
9.4.2	Host Bus Mode	473
9.4.3	General-Purpose Mode	484
9.5	Register Map	492
9.6	Register Descriptions	493
10	General-Purpose Timers	. 537
10.1	Block Diagram	538
10.2	Signal Description	538
10.3	Functional Description	. 541
10.3.1	GPTM Reset Conditions	. 542
10.3.2	Timer Modes	. 542
10.3.3	DMA Operation	. 548
10.3.4	Accessing Concatenated Register Values	. 549
10.4	Initialization and Configuration	
10.4.1	One-Shot/Periodic Timer Mode	. 549
10.4.2	Real-Time Clock (RTC) Mode	. 550
10.4.3	Input Edge-Count Mode	. 550
10.4.4	Input Edge Timing Mode	. 551
10.4.5	PWM Mode	. 552
10.5	Register Map	552
10.6	Register Descriptions	553
11	Watchdog Timers	584
11.1	Block Diagram	585
11.2	Functional Description	. 585
11.2.1	Register Access Timing	. 586
11.3	Initialization and Configuration	. 586
11.4	Register Map	. 586
11.5	Register Descriptions	587
12	Analog-to-Digital Converter (ADC)	609
12.1	Block Diagram	
12.2	Signal Description	611
12.3	Functional Description	
12.3.1	Sample Sequencers	
12.3.2	Module Control	. 614
12.3.3	Hardware Sample Averaging Circuit	. 616
12.3.4	Analog-to-Digital Converter	. 617
12.3.5	Differential Sampling	621
	Internal Temperature Sensor	
	Digital Comparator Unit	
12.4	Initialization and Configuration	
12.4.1	Module Initialization	
12.4.2	Sample Sequencer Configuration	
12.5	Register Map	

13	Universal Asynchronous Receivers/Transmitters (UARTs)	
13.1	Block Diagram	
13.2	Signal Description	
13.3	Functional Description	693
13.3.1	Transmit/Receive Logic	
13.3.2	Baud-Rate Generation	694
13.3.3	Data Transmission	695
	Serial IR (SIR)	
13.3.5	ISO 7816 Support	696
13.3.6	Modem Handshake Support	697
	LIN Support	
	FIFO Operation	
	Interrupts	
	Loopback Operation	
13.3.11	DMA Operation	
13.4	Initialization and Configuration	701
13.5	Register Map	
13.6	Register Descriptions	704
14	Synchronous Serial Interface (SSI)	754
14.1	Block Diagram	
14.2	Signal Description	
14.3	Functional Description	756
14.3.1	Bit Rate Generation	757
14.3.2	FIFO Operation	757
14.3.3	Interrupts	757
14.3.4	Frame Formats	758
14.3.5	DMA Operation	765
14.4	Initialization and Configuration	766
14.5	Register Map	767
14.6	Register Descriptions	768
15	Inter-Integrated Circuit (I <sup>2</sup> C) Interface	796
15.1	Block Diagram	
15.2	Signal Description	
15.3	Functional Description	
	I <sup>2</sup> C Bus Functional Overview	
	Available Speed Modes	
	Interrupts	
	Loopback Operation	
	Command Sequence Flow Charts	
15.4	Initialization and Configuration	
15.5	Register Map	
15.6	Register Descriptions (I <sup>2</sup> C Master)	
15.7	Register Descriptions (I <sup>2</sup> C Slave)	
16	Inter-Integrated Circuit Sound (I <sup>2</sup> S) Interface	
1 <b>6</b> 16.1		
16.1	Block Diagram Signal Description	
	Signal Description	
16.3	Functional Description	030

16.3.1	Transmit	838
16.3.2	Receive	842
16.4	Initialization and Configuration	844
16.5	Register Map	845
16.6	Register Descriptions	
17	Controller Area Network (CAN) Module	
17.1	Block Diagram	
17.1	Signal Description	
17.2	Functional Description	
17.3.1	Initialization	
17.3.1	Operation	
	·	
	Transmitting Message Objects	
	Configuring a Transmit Message Object	
	Updating a Transmit Message Object	
	Accepting Received Message Objects	
	Receiving a Data Frame	
	Receiving a Remote Frame	
	Receive/Transmit Priority	
	Configuring a Receive Message Object	
	Handling of Received Message Objects	
	Handling of Interrupts	
	Test Mode	
	Bit Timing Configuration Error Considerations	
	Bit Time and Bit Rate	
	Calculating the Bit Timing Parameters	
17.4	Register Map	
17.5	CAN Register Descriptions	891
18	Ethernet Controller	922
18.1	Block Diagram	923
18.2	Signal Description	924
18.3	Functional Description	925
18.3.1	MAC Operation	925
18.3.2	Internal MII Operation	929
18.3.3	PHY Operation	929
18.3.4	Interrupts	931
18.3.5	DMA Operation	932
18.4	Initialization and Configuration	932
18.4.1	Hardware Configuration	932
18.4.2	Software Configuration	933
18.5	Register Map	934
18.6	Ethernet MAC Register Descriptions	936
18.7	MII Management Register Descriptions	962
19	Universal Serial Bus (USB) Controller	983
19.1	Block Diagram	
19.2	Signal Description	
19.3	Functional Description	
19.3.1	Operation as a Device	
	Operation as a Host	

19.3.3	OTG Mode	995
19.3.4	DMA Operation	997
19.4	Initialization and Configuration	998
19.4.1	Pin Configuration	998
19.4.2	Endpoint Configuration	999
19.5	Register Map	
19.6	Register Descriptions	. 1010
20	Analog Comparators	. 1122
20.1	Block Diagram	. 1123
20.2	Signal Description	. 1123
20.3	Functional Description	. 1124
20.3.1	Internal Reference Programming	. 1125
20.4	Initialization and Configuration	. 1126
20.5	Register Map	. 1127
20.6	Register Descriptions	. 1128
21	Pulse Width Modulator (PWM)	. 1136
21.1	Block Diagram	. 1137
21.2	Signal Description	. 1138
21.3	Functional Description	. 1141
21.3.1	PWM Timer	. 1141
21.3.2	PWM Comparators	. 1141
21.3.3	PWM Signal Generator	. 1143
21.3.4	Dead-Band Generator	. 1143
21.3.5	Interrupt/ADC-Trigger Selector	. 1144
21.3.6	Synchronization Methods	. 1144
21.3.7	Fault Conditions	. 1145
21.3.8	Output Control Block	. 1146
21.4	Initialization and Configuration	
21.5	Register Map	
21.6	Register Descriptions	
22	Quadrature Encoder Interface (QEI)	
22.1	Block Diagram	
22.2	Signal Description	
22.3	Functional Description	
22.4	Initialization and Configuration	
22.5	Register Map	
22.6	Register Descriptions	. 1219
23	Pin Diagram	1236
24	Signal Tables	1238
24.1	100-Pin LQFP Package Pin Tables	. 1239
24.1.1	Signals by Pin Number	. 1239
24.1.2	Signals by Signal Name	. 1251
24.1.3	Signals by Function, Except for GPIO	. 1261
24.1.4	GPIO Pins and Alternate Functions	. 1270
24.1.5	Possible Pin Assignments for Alternate Functions	. 1273
24.2	108-Ball BGA Package Pin Tables	
24.2.1	Signals by Pin Number	. 1276

24.2.2	Signals by Signal Name	
24.2.3	Signals by Function, Except for GPIO	1299
24.2.4	GPIO Pins and Alternate Functions	1308
24.2.5	Possible Pin Assignments for Alternate Functions	1311
24.3	Connections for Unused Signals	1314
25	Operating Characteristics	1316
26	Electrical Characteristics	1317
26.1	Maximum Ratings	
26.2	Recommended Operating Conditions	
26.3	Load Conditions	1318
26.4	JTAG and Boundary Scan	1318
26.5	Power and Brown-Out	1320
26.6	Reset	1321
26.7	On-Chip Low Drop-Out (LDO) Regulator	1322
26.8	Clocks	1322
26.8.1	PLL Specifications	1322
26.8.2	PIOSC Specifications	
26.8.3	Internal 30-kHz Oscillator Specifications	
26.8.4	Main Oscillator Specifications	
26.8.5	System Clock Specification with ADC Operation	
26.8.6	System Clock Specification with USB Operation	
26.9	Sleep Modes	
26.10	Flash Memory	
26.11	Input/Output Characteristics	
26.12	External Peripheral Interface (EPI)	
26.13	Analog-to-Digital Converter (ADC)	
26.14 26.15	Synchronous Serial Interface (SSI)	
26.16	Inter-Integrated Circuit (1°C) Interface	
26.17	Ethernet Controller	
26.17	Universal Serial Bus (USB) Controller	
26.19	Analog Comparator	
26.20	Current Consumption	
	Nominal Power Consumption	
	2 Maximum Current Consumption	
A	Register Quick Reference	
В	Ordering and Contact Information	
<b>Б</b> В.1	Ordering Information	
B.2	Part Markings	
B.3	Kits	
B.4	Support Information	
С	Package Information	
C.1	100-Pin LQFP Package	
C.1.1	Package Dimensions	
C.1.2	Tray Dimensions	
C.1.3	Tape and Reel Dimensions	
C.2	108-Ball BGA Package	

# NRND: Not recommended for new designs. Stellaris® LM3S9D96 Microcontroller

C.2.1	Package Dimensions	1405
C.2.2	Tray Dimensions	1407
C.2.3	Tape and Reel Dimensions	1408

# **List of Figures**

Figure 1-1.	Stellaris LM3S9D96 Microcontroller High-Level Block Diagram	49
Figure 2-1.	CPU Block Diagram	73
Figure 2-2.	TPIU Block Diagram	74
Figure 2-3.	Cortex-M3 Register Set	76
Figure 2-4.	Bit-Band Mapping	97
Figure 2-5.	Data Storage	98
Figure 2-6.	Vector Table	104
Figure 2-7.	Exception Stack Frame	. 106
Figure 3-1.	SRD Use Example	. 120
Figure 4-1.	JTAG Module Block Diagram	. 181
Figure 4-2.	Test Access Port State Machine	. 184
Figure 4-3.	IDCODE Register Format	. 190
Figure 4-4.	BYPASS Register Format	. 190
Figure 4-5.	Boundary Scan Register Format	. 191
Figure 5-1.	Basic RST Configuration	. 195
Figure 5-2.	External Circuitry to Extend Power-On Reset	. 195
Figure 5-3.	Reset Circuit Controlled by Switch	. 196
Figure 5-4.	Power Architecture	199
Figure 5-5.	Main Clock Tree	201
Figure 6-1.	Internal Memory Block Diagram	. 300
Figure 7-1.	μDMA Block Diagram	. 347
Figure 7-2.	Example of Ping-Pong µDMA Transaction	. 354
Figure 7-3.	Memory Scatter-Gather, Setup and Configuration	. 356
Figure 7-4.	Memory Scatter-Gather, µDMA Copy Sequence	. 357
Figure 7-5.	Peripheral Scatter-Gather, Setup and Configuration	. 359
Figure 7-6.	Peripheral Scatter-Gather, µDMA Copy Sequence	. 360
Figure 8-1.	Digital I/O Pads	412
Figure 8-2.	Analog/Digital I/O Pads	. 413
Figure 8-3.	GPIODATA Write Example	414
Figure 8-4.	GPIODATA Read Example	. 414
Figure 9-1.	EPI Block Diagram	. 464
Figure 9-2.	SDRAM Non-Blocking Read Cycle	. 472
Figure 9-3.	SDRAM Normal Read Cycle	. 472
Figure 9-4.	SDRAM Write Cycle	. 473
Figure 9-5.	Example Schematic for Muxed Host-Bus 16 Mode	. 479
Figure 9-6.	Host-Bus Read Cycle, MODE = 0x1, WRHIGH = 0, RDHIGH = 0	. 481
Figure 9-7.	Host-Bus Write Cycle, MODE = 0x1, WRHIGH = 0, RDHIGH = 0	. 482
Figure 9-8.	Host-Bus Write Cycle with Multiplexed Address and Data, MODE = 0x0, WRHIGH = 0, RDHIGH = 0	
Figure 9-9.	Host-Bus Write Cycle with Multiplexed Address and Data and ALE with Dual CSn	
Figure 9-10.	Continuous Read Mode Accesses	
Figure 9-11.	Write Followed by Read to External FIFO	
Figure 9-12.	Two-Entry FIFO	
Figure 9-13.	Single-Cycle Write Access, FRM50=0, FRMCNT=0, WRCYC=0	

Figure 9-14.	Two-Cycle Read, Write Accesses, FRM50=0, FRMCNT=0, RDCYC=1, WRCYC=1	488
Figure 9-15.	Read Accesses, FRM50=0, FRMCNT=0, RDCYC=1	
Figure 9-16.	FRAME Signal Operation, FRM50=0 and FRMCNT=0	
Figure 9-17.	FRAME Signal Operation, FRM50=0 and FRMCNT=1	
Figure 9-18.	FRAME Signal Operation, FRM50=0 and FRMCNT=2	
Figure 9-19.	FRAME Signal Operation, FRM50=1 and FRMCNT=0	
Figure 9-20.	FRAME Signal Operation, FRM50=1 and FRMCNT=1	
Figure 9-21.	FRAME Signal Operation, FRM50=1 and FRMCNT=2	
Figure 9-22.	iRDY Signal Operation, FRM50=0, FRMCNT=0, and RD2CYC=1	
Figure 9-23.	EPI Clock Operation, CLKGATE=1, WR2CYC=0	
Figure 9-24.	EPI Clock Operation, CLKGATE=1, WR2CYC=1	
Figure 10-1.	GPTM Module Block Diagram	
Figure 10-2.	Timer Daisy Chain	
Figure 10-3.	Input Edge-Count Mode Example	
Figure 10-4.	16-Bit Input Edge-Time Mode Example	
Figure 10-5.	16-Bit PWM Mode Example	
Figure 11-1.	WDT Module Block Diagram	
Figure 12-1.	Implementation of Two ADC Blocks	
Figure 12-2.	ADC Module Block Diagram	
Figure 12-3.	ADC Sample Phases	
Figure 12-4.	Doubling the ADC Sample Rate	
Figure 12-5.	Skewed Sampling	
Figure 12-6.	Sample Averaging Example	
Figure 12-7.	ADC Input Equivalency Diagram	
Figure 12-8.	Internal Voltage Conversion Result	
Figure 12-9.	External Voltage Conversion Result with 3.0-V Setting	
•	External Voltage Conversion Result with 1.0-V Setting	
	Differential Sampling Range, V <sub>IN_ODD</sub> = 1.5 V	
Figure 12-12.	Differential Sampling Range, V <sub>IN_ODD</sub> = 0.75 V	622
	Differential Sampling Range, V <sub>IN_ODD</sub> = 2.25 V	
Figure 12-14.	Internal Temperature Sensor Characteristic	624
-	Low-Band Operation (CIC=0x0 and/or CTC=0x0)	
	Mid-Band Operation (CIC=0x1 and/or CTC=0x1)	
•	High-Band Operation (CIC=0x3 and/or CTC=0x3)	
Figure 13-1.	UART Module Block Diagram	
Figure 13-2.	UART Character Frame	
Figure 13-3.	IrDA Data Modulation	
Figure 13-4.	LIN Message	
Figure 13-5.	LIN Synchronization Field	
Figure 14-1.	SSI Module Block Diagram	
Figure 14-2.	TI Synchronous Serial Frame Format (Single Transfer)	
Figure 14-3.	TI Synchronous Serial Frame Format (Continuous Transfer)	
Figure 14-4.	Freescale SPI Format (Single Transfer) with SPO=0 and SPH=0	
Figure 14-5.	Freescale SPI Format (Continuous Transfer) with SPO=0 and SPH=0	
Figure 14-6.	Freescale SPI Frame Format with SPO=0 and SPH=1	
Figure 14-7.	Freescale SPI Frame Format (Single Transfer) with SPO=1 and SPH=0	
Figure 14-8.	Freescale SPI Frame Format (Continuous Transfer) with SPO=1 and SPH=0	

Figure 14-9.	Freescale SPI Frame Format with SPO=1 and SPH=1	763
Figure 14-10.	MICROWIRE Frame Format (Single Frame)	764
Figure 14-11.	MICROWIRE Frame Format (Continuous Transfer)	765
Figure 14-12.	MICROWIRE Frame Format, SSIFss Input Setup and Hold Requirements	765
Figure 15-1.	I <sup>2</sup> C Block Diagram	797
Figure 15-2.	I <sup>2</sup> C Bus Configuration	798
Figure 15-3.	START and STOP Conditions	799
Figure 15-4.	Complete Data Transfer with a 7-Bit Address	799
Figure 15-5.	R/S Bit in First Byte	
Figure 15-6.	Data Validity During Bit Transfer on the I <sup>2</sup> C Bus	800
Figure 15-7.	Master Single TRANSMIT	804
Figure 15-8.	Master Single RECEIVE	805
Figure 15-9.	Master TRANSMIT with Repeated START	806
Figure 15-10.	Master RECEIVE with Repeated START	807
Figure 15-11.	Master RECEIVE with Repeated START after TRANSMIT with Repeated START	808
Figure 15-12.	Master TRANSMIT with Repeated START after RECEIVE with Repeated START	809
Figure 15-13.	Slave Command Sequence	810
Figure 16-1.	I <sup>2</sup> S Block Diagram	835
Figure 16-2.	I <sup>2</sup> S Data Transfer	838
Figure 16-3.	Left-Justified Data Transfer	838
Figure 16-4.	Right-Justified Data Transfer	838
Figure 17-1.	CAN Controller Block Diagram	
Figure 17-2.	CAN Data/Remote Frame	
Figure 17-3.	Message Objects in a FIFO Buffer	882
Figure 17-4.	CAN Bit Time	886
Figure 18-1.	Ethernet Controller	923
Figure 18-2.	Ethernet Controller Block Diagram	923
Figure 18-3.	Ethernet Frame	925
Figure 18-4.	Interface to an Ethernet Jack	933
Figure 19-1.	USB Module Block Diagram	984
Figure 20-1.	Analog Comparator Module Block Diagram	1123
Figure 20-2.	Structure of Comparator Unit	1125
Figure 20-3.	Comparator Internal Reference Structure	1125
Figure 21-1.	PWM Module Diagram	
Figure 21-2.	PWM Generator Block Diagram	1138
Figure 21-3.	PWM Count-Down Mode	1142
Figure 21-4.	PWM Count-Up/Down Mode	
Figure 21-5.	PWM Generation Example In Count-Up/Down Mode	1143
Figure 21-6.	PWM Dead-Band Generator	1144
Figure 22-1.	QEI Block Diagram	
Figure 22-2.	Quadrature Encoder and Velocity Predivider Operation	1216
Figure 23-1.	100-Pin LQFP Package Pin Diagram	1236
Figure 23-2.	108-Ball BGA Package Pin Diagram (Top View)	1237
Figure 26-1.	Load Conditions	
Figure 26-2.	JTAG Test Clock Input Timing	
Figure 26-3.	JTAG Test Access Port (TAP) Timing	1319

Figure 26-4.	Power-On Reset Timing	1320
Figure 26-5.	Brown-Out Reset Timing	
Figure 26-6.	Power-On Reset and Voltage Parameters	1321
Figure 26-7.	External Reset Timing (RST)	1321
Figure 26-8.	Software Reset Timing	1321
Figure 26-9.	Watchdog Reset Timing	1322
Figure 26-10.	MOSC Failure Reset Timing	1322
Figure 26-11.	SDRAM Initialization and Load Mode Register Timing	1327
Figure 26-12.	SDRAM Read Timing	1327
Figure 26-13.	SDRAM Write Timing	1328
Figure 26-14.	Host-Bus 8/16 Mode Read Timing	1329
Figure 26-15.	Host-Bus 8/16 Mode Write Timing	1329
Figure 26-16.	Host-Bus 8/16 Mode Muxed Read Timing	1330
	Host-Bus 8/16 Mode Muxed Write Timing	
Figure 26-18.	General-Purpose Mode Read and Write Timing	1331
Figure 26-19.	General-Purpose Mode iRDY Timing	1331
Figure 26-20.	ADC Input Equivalency Diagram	1333
Figure 26-21.	SSI Timing for TI Frame Format (FRF=01), Single Transfer Timing	
	Measurement	
•	SSI Timing for MICROWIRE Frame Format (FRF=10), Single Transfer	
•	SSI Timing for SPI Frame Format (FRF=00), with SPH=1	
•	I <sup>2</sup> C Timing	
Figure 26-25.	I <sup>2</sup> S Master Mode Transmit Timing	1336
Figure 26-26.	I <sup>2</sup> S Master Mode Receive Timing	1337
Figure 26-27.	I <sup>2</sup> S Slave Mode Transmit Timing	1337
Figure 26-28.	I <sup>2</sup> S Slave Mode Receive Timing	1337
Figure 26-29.	External XTLP Oscillator Characteristics	1340
Figure C-1.	Stellaris LM3S9D96 100-Pin LQFP Package Dimensions	1401
Figure C-2.	100-Pin LQFP Tray Dimensions	1403
Figure C-3.	100-Pin LQFP Tape and Reel Dimensions	
Figure C-4.	Stellaris LM3S9D96 108-Ball BGA Package Dimensions	
Figure C-5.	108-Ball BGA Tray Dimensions	
Figure C-6.	108-Ball BGA Tape and Reel Dimensions	1408

## **List of Tables**

Table 1.	Revision History	42
Table 2.	Documentation Conventions	
Table 2-1.	Summary of Processor Mode, Privilege Level, and Stack Use	76
Table 2-2.	Processor Register Map	77
Table 2-3.	PSR Register Combinations	82
Table 2-4.	Memory Map	90
Table 2-5.	Memory Access Behavior	93
Table 2-6.	SRAM Memory Bit-Banding Regions	95
Table 2-7.	Peripheral Memory Bit-Banding Regions	95
Table 2-8.	Exception Types	101
Table 2-9.	Interrupts	102
Table 2-10.	Exception Return Behavior	107
Table 2-11.	Faults	108
Table 2-12.	Fault Status and Fault Address Registers	109
Table 2-13.	Cortex-M3 Instruction Summary	111
Table 3-1.	Core Peripheral Register Regions	114
Table 3-2.	Memory Attributes Summary	117
Table 3-3.	TEX, S, C, and B Bit Field Encoding	120
Table 3-4.	Cache Policy for Memory Attribute Encoding	
Table 3-5.	AP Bit Field Encoding	121
Table 3-6.	Memory Region Attributes for Stellaris Microcontrollers	
Table 3-7.	Peripherals Register Map	
Table 3-8.	Interrupt Priority Levels	149
Table 3-9.	Example SIZE Field Values	
Table 4-1.	JTAG_SWD_SWO Signals (100LQFP)	181
Table 4-2.	JTAG_SWD_SWO Signals (108BGA)	182
Table 4-3.	JTAG Port Pins State after Power-On Reset or RST assertion	183
Table 4-4.	JTAG Instruction Register Commands	188
Table 5-1.	System Control & Clocks Signals (100LQFP)	192
Table 5-2.	System Control & Clocks Signals (108BGA)	192
Table 5-3.	Reset Sources	193
Table 5-4.	Clock Source Options	200
Table 5-5.	Possible System Clock Frequencies Using the SYSDIV Field	202
Table 5-6.	Examples of Possible System Clock Frequencies Using the SYSDIV2 Field	
Table 5-7.	Examples of Possible System Clock Frequencies with DIV400=1	203
Table 5-8.	System Control Register Map	207
Table 5-9.	RCC2 Fields that Override RCC Fields	229
Table 6-1.	Flash Memory Protection Policy Combinations	304
Table 6-2.	User-Programmable Flash Memory Resident Registers	308
Table 6-3.	Flash Register Map	309
Table 7-1.	μDMA Channel Assignments	348
Table 7-2.	Request Type Support	350
Table 7-3.	Control Structure Memory Map	
Table 7-4.	Channel Control Structure	351
Table 7-5.	μDMA Read Example: 8-Bit Peripheral	361
Table 7-6.	μDMA Interrupt Assignments	362

Table 7-7.	Channel Control Structure Offsets for Channel 30	363
Table 7-8.	Channel Control Word Configuration for Memory Transfer Example	363
Table 7-9.	Channel Control Structure Offsets for Channel 7	
Table 7-10.	Channel Control Word Configuration for Peripheral Transmit Example	365
Table 7-11.	Primary and Alternate Channel Control Structure Offsets for Channel 8	366
Table 7-12.	Channel Control Word Configuration for Peripheral Ping-Pong Receive	
	Example	367
Table 7-13.	μDMA Register Map	369
Table 8-1.	GPIO Pins With Non-Zero Reset Values	408
Table 8-2.	GPIO Pins and Alternate Functions (100LQFP)	408
Table 8-3.	GPIO Pins and Alternate Functions (108BGA)	410
Table 8-4.	GPIO Pad Configuration Examples	416
Table 8-5.	GPIO Interrupt Configuration Example	417
Table 8-6.	GPIO Pins With Non-Zero Reset Values	418
Table 8-7.	GPIO Register Map	418
Table 8-8.	GPIO Pins With Non-Zero Reset Values	430
Table 8-9.	GPIO Pins With Non-Zero Reset Values	436
Table 8-10.	GPIO Pins With Non-Zero Reset Values	438
Table 8-11.	GPIO Pins With Non-Zero Reset Values	441
Table 8-12.	GPIO Pins With Non-Zero Reset Values	448
Table 9-1.	External Peripheral Interface Signals (100LQFP)	464
Table 9-2.	External Peripheral Interface Signals (108BGA)	
Table 9-3.	EPI SDRAM Signal Connections	
Table 9-4.	Capabilities of Host Bus 8 and Host Bus 16 Modes	
Table 9-5.	EPI Host-Bus 8 Signal Connections	
Table 9-6.	EPI Host-Bus 16 Signal Connections	477
Table 9-7.	EPI General Purpose Signal Connections	486
Table 9-8.	External Peripheral Interface (EPI) Register Map	
Table 10-1.	Available CCP Pins	
Table 10-2.	General-Purpose Timers Signals (100LQFP)	539
Table 10-3.	General-Purpose Timers Signals (108BGA)	540
Table 10-4.	General-Purpose Timer Capabilities	
Table 10-5.	Counter Values When the Timer is Enabled in Periodic or One-Shot Modes	542
Table 10-6.	16-Bit Timer With Prescaler Configurations	
Table 10-7.	Counter Values When the Timer is Enabled in RTC Mode	544
Table 10-8.	Counter Values When the Timer is Enabled in Input Edge-Count Mode	545
Table 10-9.	Counter Values When the Timer is Enabled in Input Event-Count Mode	
Table 10-10.	Counter Values When the Timer is Enabled in PWM Mode	
Table 10-11.	Timers Register Map	552
Table 11-1.	Watchdog Timers Register Map	
Table 12-1.	ADC Signals (100LQFP)	
Table 12-2.	ADC Signals (108BGA)	
Table 12-3.	Samples and FIFO Depth of Sequencers	
Table 12-4.	Differential Sampling Pairs	
Table 12-5.	ADC Register Map	
Table 13-1.	UART Signals (100LQFP)	
Table 13-2.	UART Signals (108BGA)	
Table 13-3.	Flow Control Mode	

Table 13-4.	UART Register Map	703
Table 14-1.	SSI Signals (100LQFP)	756
Table 14-2.	SSI Signals (108BGA)	756
Table 14-3.	SSI Register Map	767
Table 15-1.	I2C Signals (100LQFP)	797
Table 15-2.	I2C Signals (108BGA)	797
Table 15-3.	Examples of I <sup>2</sup> C Master Timer Period versus Speed Mode	801
Table 15-4.	Inter-Integrated Circuit (I <sup>2</sup> C) Interface Register Map	811
Table 15-5.	Write Field Decoding for I2CMCS[3:0] Field	817
Table 16-1.	I2S Signals (100LQFP)	836
Table 16-2.	I2S Signals (108BGA)	836
Table 16-3.	I <sup>2</sup> S Transmit FIFO Interface	839
Table 16-4.	Crystal Frequency (Values from 3.5795 MHz to 5 MHz)	840
Table 16-5.	Crystal Frequency (Values from 5.12 MHz to 8.192 MHz)	840
Table 16-6.	Crystal Frequency (Values from 10 MHz to 14.3181 MHz)	841
Table 16-7.	Crystal Frequency (Values from 16 MHz to 16.384 MHz)	841
Table 16-8.	I <sup>2</sup> S Receive FIFO Interface	843
Table 16-9.	Audio Formats Configuration	845
Table 16-10.	Inter-Integrated Circuit Sound (I <sup>2</sup> S) Interface Register Map	846
Table 17-1.	Controller Area Network Signals (100LQFP)	873
Table 17-2.	Controller Area Network Signals (108BGA)	873
Table 17-3.	Message Object Configurations	879
Table 17-4.	CAN Protocol Ranges	
Table 17-5.	CANBIT Register Values	886
Table 17-6.	CAN Register Map	
Table 18-1.	Ethernet Signals (100LQFP)	924
Table 18-2.	Ethernet Signals (108BGA)	924
Table 18-3.	TX & RX FIFO Organization	927
Table 18-4.	Ethernet Register Map	934
Table 19-1.	USB Signals (100LQFP)	985
Table 19-2.	USB Signals (108BGA)	
Table 19-3.	Remainder (MAXLOAD/4)	997
Table 19-4.	Actual Bytes Read	997
Table 19-5.	Packet Sizes That Clear RXRDY	998
Table 19-6.	Universal Serial Bus (USB) Controller Register Map	999
Table 20-1.	Analog Comparators Signals (100LQFP)	1123
Table 20-2.	Analog Comparators Signals (108BGA)	1124
Table 20-3.	Internal Reference Voltage and ACREFCTL Field Values	1126
Table 20-4.	Analog Comparators Register Map	1127
Table 21-1.	PWM Signals (100LQFP)	1139
Table 21-2.	PWM Signals (108BGA)	1140
Table 21-3.	PWM Register Map	1147
Table 22-1.	QEI Signals (100LQFP)	1214
Table 22-2.	QEI Signals (108BGA)	1215
Table 22-3.	QEI Register Map	1218
Table 24-1.	GPIO Pins With Default Alternate Functions	1238
Table 24-2.	Signals by Pin Number	1239
Table 24-3.	Signals by Signal Name	

Table 24-4.	Signals by Function, Except for GPIO	1261
Table 24-5.	GPIO Pins and Alternate Functions	1270
Table 24-6.	Possible Pin Assignments for Alternate Functions	1273
Table 24-7.	Signals by Pin Number	1276
Table 24-8.	Signals by Signal Name	1288
Table 24-9.	Signals by Function, Except for GPIO	1299
Table 24-10.	GPIO Pins and Alternate Functions	1308
Table 24-11.	Possible Pin Assignments for Alternate Functions	1311
Table 24-12.	Connections for Unused Signals (100-Pin LQFP)	1314
Table 24-13.	Connections for Unused Signals (108-Ball BGA)	1315
Table 25-1.	Temperature Characteristics	1316
Table 25-2.	Thermal Characteristics	1316
Table 25-3.	ESD Absolute Maximum Ratings	1316
Table 26-1.	Maximum Ratings	1317
Table 26-2.	Recommended DC Operating Conditions	1317
Table 26-3.	JTAG Characteristics	1318
Table 26-4.	Power Characteristics	1320
Table 26-5.	Reset Characteristics	1321
Table 26-6.	LDO Regulator Characteristics	1322
Table 26-7.	Phase Locked Loop (PLL) Characteristics	1322
Table 26-8.	Actual PLL Frequency	1323
Table 26-9.	PIOSC Clock Characteristics	1323
Table 26-10.	30-kHz Clock Characteristics	1323
Table 26-11.	Main Oscillator Clock Characteristics	1324
Table 26-12.	Supported MOSC Crystal Frequencies	1324
Table 26-13.	System Clock Characteristics with ADC Operation	1325
Table 26-14.	System Clock Characteristics with USB Operation	1325
Table 26-15.	Sleep Modes AC Characteristics	1325
Table 26-16.	Flash Memory Characteristics	1325
Table 26-17.	GPIO Module Characteristics	1326
Table 26-18.	EPI SDRAM Characteristics	
Table 26-19.	EPI SDRAM Interface Characteristics	
Table 26-20.	EPI Host-Bus 8 and Host-Bus 16 Interface Characteristics	1328
Table 26-21.	EPI General-Purpose Interface Characteristics	1330
Table 26-22.	ADC Characteristics	
Table 26-23.	ADC Module External Reference Characteristics	
Table 26-24.	ADC Module Internal Reference Characteristics	
Table 26-25.	SSI Characteristics	
Table 26-26.	I <sup>2</sup> C Characteristics	
Table 26-27.	I <sup>2</sup> S Master Clock (Receive and Transmit)	1336
Table 26-28.	I <sup>2</sup> S Slave Clock (Receive and Transmit)	1336
Table 26-29.	I <sup>2</sup> S Master Mode	1336
Table 26-30.	I <sup>2</sup> S Slave Mode	1337
Table 26-31.	Ethernet Controller DC Characteristics	1337
Table 26-32.	100BASE-TX Transmitter Characteristics	
Table 26-33.	100BASE-TX Transmitter Characteristics (informative)	1338
Table 26-34.	100BASE-TX Receiver Characteristics	
Table 26-35.	10BASE-T Transmitter Characteristics	1338

Table 26-36.	10BASE-T Transmitter Characteristics (informative)	1338
Table 26-37.	10BASE-T Receiver Characteristics	1339
Table 26-38.	Isolation Transformers	1339
Table 26-39.	Ethernet Reference Crystal	1339
Table 26-40.	External XTLP Oscillator Characteristics	1340
Table 26-41.	USB Controller Characteristics	1340
Table 26-42.	Analog Comparator Characteristics	1340
Table 26-43.	Analog Comparator Voltage Reference Characteristics	1341
Table 26-44.	Nominal Power Consumption	1341
Table 26-45.	Detailed Current Specifications	1342
Table B-1.	Part Ordering Information	1399

# **List of Registers**

The Cortex	-M3 Processor	
Register 1:	Cortex General-Purpose Register 0 (R0)	78
Register 2:	Cortex General-Purpose Register 1 (R1)	78
Register 3:	Cortex General-Purpose Register 2 (R2)	78
Register 4:	Cortex General-Purpose Register 3 (R3)	
Register 5:	Cortex General-Purpose Register 4 (R4)	78
Register 6:	Cortex General-Purpose Register 5 (R5)	
Register 7:	Cortex General-Purpose Register 6 (R6)	
Register 8:	Cortex General-Purpose Register 7 (R7)	
Register 9:	Cortex General-Purpose Register 8 (R8)	
Register 10:	Cortex General-Purpose Register 9 (R9)	
Register 11:	Cortex General-Purpose Register 10 (R10)	
Register 12:	Cortex General-Purpose Register 11 (R11)	
Register 13:	Cortex General-Purpose Register 12 (R12)	
Register 14:	Stack Pointer (SP)	
Register 15:	Link Register (LR)	
Register 16:	Program Counter (PC)	
Register 17:	Program Status Register (PSR)	
Register 18:	Priority Mask Register (PRIMASK)	
Register 19:	Fault Mask Register (FAULTMASK)	
Register 20:	Base Priority Mask Register (BASEPRI)	
Register 21:	Control Register (CONTROL)	89
Cortex-M3	Peripherals	114
Register 1:	SysTick Control and Status Register (STCTRL), offset 0x010	
Register 2:	SysTick Reload Value Register (STRELOAD), offset 0x014	
Register 3:	SysTick Current Value Register (STCURRENT), offset 0x018	
Register 4:	Interrupt 0-31 Set Enable (EN0), offset 0x100	400
Register 5:	metrape of the Enable (Ervo), one of extree	129
	Interrupt 32-54 Set Enable (EN1), offset 0x104	130
Register 6:	Interrupt 32-54 Set Enable (EN1), offset 0x104	130 131
Register 6: Register 7:	Interrupt 32-54 Set Enable (EN1), offset 0x104	130 131 132
-	Interrupt 32-54 Set Enable (EN1), offset 0x104	130 131 132 133
Register 7:	Interrupt 32-54 Set Enable (EN1), offset 0x104	130 131 132 133
Register 7: Register 8: Register 9: Register 10:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280	130131132133134
Register 7: Register 8: Register 9: Register 10: Register 11:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15: Register 16:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 13: Register 14: Register 15: Register 16: Register 17:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408 Interrupt 12-15 Priority (PRI3), offset 0x40C	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15: Register 16: Register 17: Register 18:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408 Interrupt 12-15 Priority (PRI3), offset 0x40C Interrupt 16-19 Priority (PRI4), offset 0x410	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15: Register 16: Register 17: Register 17: Register 18: Register 19:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408 Interrupt 12-15 Priority (PRI3), offset 0x40C Interrupt 16-19 Priority (PRI4), offset 0x414 Interrupt 20-23 Priority (PRI5), offset 0x414	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15: Register 16: Register 17: Register 17: Register 18: Register 19: Register 20:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408 Interrupt 12-15 Priority (PRI3), offset 0x40C Interrupt 16-19 Priority (PRI4), offset 0x410 Interrupt 20-23 Priority (PRI5), offset 0x414 Interrupt 24-27 Priority (PRI6), offset 0x418	
Register 7: Register 8: Register 9: Register 10: Register 11: Register 12: Register 13: Register 14: Register 15: Register 16: Register 17: Register 17: Register 18: Register 19:	Interrupt 32-54 Set Enable (EN1), offset 0x104 Interrupt 0-31 Clear Enable (DIS0), offset 0x180 Interrupt 32-54 Clear Enable (DIS1), offset 0x184 Interrupt 0-31 Set Pending (PEND0), offset 0x200 Interrupt 32-54 Set Pending (PEND1), offset 0x204 Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280 Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284 Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300 Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304 Interrupt 0-3 Priority (PRI0), offset 0x400 Interrupt 4-7 Priority (PRI1), offset 0x404 Interrupt 8-11 Priority (PRI2), offset 0x408 Interrupt 12-15 Priority (PRI3), offset 0x40C Interrupt 16-19 Priority (PRI4), offset 0x414 Interrupt 20-23 Priority (PRI5), offset 0x414	

Register 23:	Interrupt 36-39 Priority (PRI9), offset 0x424	139
Register 24:	Interrupt 40-43 Priority (PRI10), offset 0x428	139
Register 25:	Interrupt 44-47 Priority (PRI11), offset 0x42C	139
Register 26:	Interrupt 48-51 Priority (PRI12), offset 0x430	139
Register 27:	Interrupt 52-54 Priority (PRI13), offset 0x434	139
Register 28:	Software Trigger Interrupt (SWTRIG), offset 0xF00	141
Register 29:	Auxiliary Control (ACTLR), offset 0x008	142
Register 30:	CPU ID Base (CPUID), offset 0xD00	144
Register 31:	Interrupt Control and State (INTCTRL), offset 0xD04	145
Register 32:	Vector Table Offset (VTABLE), offset 0xD08	
Register 33:	Application Interrupt and Reset Control (APINT), offset 0xD0C	149
Register 34:	System Control (SYSCTRL), offset 0xD10	
Register 35:	Configuration and Control (CFGCTRL), offset 0xD14	153
Register 36:	System Handler Priority 1 (SYSPRI1), offset 0xD18	
Register 37:	System Handler Priority 2 (SYSPRI2), offset 0xD1C	156
Register 38:	System Handler Priority 3 (SYSPRI3), offset 0xD20	
Register 39:	System Handler Control and State (SYSHNDCTRL), offset 0xD24	158
Register 40:	Configurable Fault Status (FAULTSTAT), offset 0xD28	
Register 41:	Hard Fault Status (HFAULTSTAT), offset 0xD2C	168
Register 42:	Memory Management Fault Address (MMADDR), offset 0xD34	
Register 43:	Bus Fault Address (FAULTADDR), offset 0xD38	
Register 44:	MPU Type (MPUTYPE), offset 0xD90	
Register 45:	MPU Control (MPUCTRL), offset 0xD94	
Register 46:	MPU Region Number (MPUNUMBER), offset 0xD98	
Register 47:	MPU Region Base Address (MPUBASE), offset 0xD9C	
Register 48:	MPU Region Base Address Alias 1 (MPUBASE1), offset 0xDA4	
Register 49:	MPU Region Base Address Alias 2 (MPUBASE2), offset 0xDAC	
Register 50:	MPU Region Base Address Alias 3 (MPUBASE3), offset 0xDB4	
Register 51:	MPU Region Attribute and Size (MPUATTR), offset 0xDA0	
Register 52:	MPU Region Attribute and Size Alias 1 (MPUATTR1), offset 0xDA8	
Register 53:	MPU Region Attribute and Size Alias 2 (MPUATTR2), offset 0xDB0	
Register 54:	MPU Region Attribute and Size Alias 3 (MPUATTR3), offset 0xDB8	177
System Co	ntrol	192
Register 1:	Device Identification 0 (DID0), offset 0x000	210
Register 2:	Brown-Out Reset Control (PBORCTL), offset 0x030	212
Register 3:	Raw Interrupt Status (RIS), offset 0x050	
Register 4:	Interrupt Mask Control (IMC), offset 0x054	215
Register 5:	Masked Interrupt Status and Clear (MISC), offset 0x058	217
Register 6:	Reset Cause (RESC), offset 0x05C	
Register 7:	Run-Mode Clock Configuration (RCC), offset 0x060	221
Register 8:	XTAL to PLL Translation (PLLCFG), offset 0x064	226
Register 9:	GPIO High-Performance Bus Control (GPIOHBCTL), offset 0x06C	
Register 10:	Run-Mode Clock Configuration 2 (RCC2), offset 0x070	
Register 11:	Main Oscillator Control (MOSCCTL), offset 0x07C	
Register 12:	Deep Sleep Clock Configuration (DSLPCLKCFG), offset 0x144	
Register 13:	Precision Internal Oscillator Calibration (PIOSCCAL), offset 0x150	235
Register 14:	I <sup>2</sup> S MCLK Configuration (I2SMCLKCFG), offset 0x170	236
Register 15:	Device Identification 1 (DID1), offset 0x004	238

Register 16:	Device Capabilities 0 (DC0), offset 0x008	240
Register 17:	Device Capabilities 1 (DC1), offset 0x010	241
Register 18:	Device Capabilities 2 (DC2), offset 0x014	244
Register 19:	Device Capabilities 3 (DC3), offset 0x018	246
Register 20:	Device Capabilities 4 (DC4), offset 0x01C	249
Register 21:	Device Capabilities 5 (DC5), offset 0x020	251
Register 22:	Device Capabilities 6 (DC6), offset 0x024	253
Register 23:	Device Capabilities 7 (DC7), offset 0x028	
Register 24:	Device Capabilities 8 ADC Channels (DC8), offset 0x02C	258
Register 25:	Device Capabilities 9 ADC Digital Comparators (DC9), offset 0x190	261
Register 26:	Non-Volatile Memory Information (NVMSTAT), offset 0x1A0	263
Register 27:	Run Mode Clock Gating Control Register 0 (RCGC0), offset 0x100	264
Register 28:	Sleep Mode Clock Gating Control Register 0 (SCGC0), offset 0x110	267
Register 29:	Deep Sleep Mode Clock Gating Control Register 0 (DCGC0), offset 0x120	270
Register 30:	Run Mode Clock Gating Control Register 1 (RCGC1), offset 0x104	
Register 31:	Sleep Mode Clock Gating Control Register 1 (SCGC1), offset 0x114	
Register 32:	Deep-Sleep Mode Clock Gating Control Register 1 (DCGC1), offset 0x124	280
Register 33:	Run Mode Clock Gating Control Register 2 (RCGC2), offset 0x108	284
Register 34:	Sleep Mode Clock Gating Control Register 2 (SCGC2), offset 0x118	287
Register 35:	Deep Sleep Mode Clock Gating Control Register 2 (DCGC2), offset 0x128	290
Register 36:	Software Reset Control 0 (SRCR0), offset 0x040	293
Register 37:	Software Reset Control 1 (SRCR1), offset 0x044	295
Register 38:	Software Reset Control 2 (SRCR2), offset 0x048	298
Internal Me	mory	300
Register 1:	Flash Memory Address (FMA), offset 0x000	
Register 2:	Flash Memory Data (FMD), offset 0x004	312
Register 3:	Flash Memory Control (FMC), offset 0x008	313
Register 4:	Flash Controller Raw Interrupt Status (FCRIS), offset 0x00C	316
Register 5:	Flash Controller Interrupt Mask (FCIM), offset 0x010	317
Register 6:	Flash Controller Masked Interrupt Status and Clear (FCMISC), offset 0x014	318
Register 7:	Flash Memory Control 2 (FMC2), offset 0x020	319
Register 8:	Flash Write Buffer Valid (FWBVAL), offset 0x030	320
Register 9:	Flash Control (FCTL), offset 0x0F8	321
Register 10:	Flash Write Buffer n (FWBn), offset 0x100 - 0x17C	322
Register 11:	ROM Control (RMCTL), offset 0x0F0	323
Register 12:	Flash Memory Protection Read Enable 0 (FMPRE0), offset 0x130 and 0x200	324
Register 13:	Flash Memory Protection Program Enable 0 (FMPPE0), offset 0x134 and 0x400	325
Register 14:	Boot Configuration (BOOTCFG), offset 0x1D0	326
Register 15:	User Register 0 (USER_REG0), offset 0x1E0	328
Register 16:	User Register 1 (USER_REG1), offset 0x1E4	329
Register 17:	User Register 2 (USER_REG2), offset 0x1E8	330
Register 18:	User Register 3 (USER_REG3), offset 0x1EC	331
Register 19:	Flash Memory Protection Read Enable 1 (FMPRE1), offset 0x204	332
Register 20:	Flash Memory Protection Read Enable 2 (FMPRE2), offset 0x208	333
Register 21:	Flash Memory Protection Read Enable 3 (FMPRE3), offset 0x20C	
Register 22:	Flash Memory Protection Read Enable 4 (FMPRE4), offset 0x210	335
Register 23:	Flash Memory Protection Read Enable 5 (FMPRE5), offset 0x214	
Register 24:	Flash Memory Protection Read Enable 6 (FMPRE6), offset 0x218	227

Register 25:	Flash Memory Protection Read Enable 7 (FMPRE7), offset 0x21C	338
Register 26:	Flash Memory Protection Program Enable 1 (FMPPE1), offset 0x404	
Register 27:	Flash Memory Protection Program Enable 2 (FMPPE2), offset 0x408	
Register 28:	Flash Memory Protection Program Enable 3 (FMPPE3), offset 0x40C	
Register 29:	Flash Memory Protection Program Enable 4 (FMPPE4), offset 0x410	
Register 30:	Flash Memory Protection Program Enable 5 (FMPPE5), offset 0x414	343
Register 31:	Flash Memory Protection Program Enable 6 (FMPPE6), offset 0x418	
Register 32:	Flash Memory Protection Program Enable 7 (FMPPE7), offset 0x41C	345
Micro Direc	t Memory Access (µDMA)	346
Register 1:	DMA Channel Source Address End Pointer (DMASRCENDP), offset 0x000	371
Register 2:	DMA Channel Destination Address End Pointer (DMADSTENDP), offset 0x004	
Register 3:	DMA Channel Control Word (DMACHCTL), offset 0x008	
Register 4:	DMA Status (DMASTAT), offset 0x000	378
Register 5:	DMA Configuration (DMACFG), offset 0x004	380
Register 6:	DMA Channel Control Base Pointer (DMACTLBASE), offset 0x008	381
Register 7:	DMA Alternate Channel Control Base Pointer (DMAALTBASE), offset 0x00C	382
Register 8:	DMA Channel Wait-on-Request Status (DMAWAITSTAT), offset 0x010	383
Register 9:	DMA Channel Software Request (DMASWREQ), offset 0x014	384
Register 10:	DMA Channel Useburst Set (DMAUSEBURSTSET), offset 0x018	385
Register 11:	DMA Channel Useburst Clear (DMAUSEBURSTCLR), offset 0x01C	386
Register 12:	DMA Channel Request Mask Set (DMAREQMASKSET), offset 0x020	387
Register 13:	DMA Channel Request Mask Clear (DMAREQMASKCLR), offset 0x024	
Register 14:	DMA Channel Enable Set (DMAENASET), offset 0x028	389
Register 15:	DMA Channel Enable Clear (DMAENACLR), offset 0x02C	390
Register 16:	DMA Channel Primary Alternate Set (DMAALTSET), offset 0x030	391
Register 17:	DMA Channel Primary Alternate Clear (DMAALTCLR), offset 0x034	392
Register 18:	DMA Channel Priority Set (DMAPRIOSET), offset 0x038	393
Register 19:	DMA Channel Priority Clear (DMAPRIOCLR), offset 0x03C	394
Register 20:	DMA Bus Error Clear (DMAERRCLR), offset 0x04C	
Register 21:	DMA Channel Assignment (DMACHASGN), offset 0x500	396
Register 22:	DMA Channel Interrupt Status (DMACHIS), offset 0x504	
Register 23:	DMA Peripheral Identification 0 (DMAPeriphID0), offset 0xFE0	
Register 24:	DMA Peripheral Identification 1 (DMAPeriphID1), offset 0xFE4	399
Register 25:	DMA Peripheral Identification 2 (DMAPeriphID2), offset 0xFE8	400
Register 26:	DMA Peripheral Identification 3 (DMAPeriphID3), offset 0xFEC	401
Register 27:	DMA Peripheral Identification 4 (DMAPeriphID4), offset 0xFD0	402
Register 28:	DMA PrimeCell Identification 0 (DMAPCelIID0), offset 0xFF0	403
Register 29:	DMA PrimeCell Identification 1 (DMAPCelIID1), offset 0xFF4	
Register 30:	DMA PrimeCell Identification 2 (DMAPCelIID2), offset 0xFF8	405
Register 31:	DMA PrimeCell Identification 3 (DMAPCellID3), offset 0xFFC	406
General-Pu	rpose Input/Outputs (GPIOs)	407
Register 1:	GPIO Data (GPIODATA), offset 0x000	420
Register 2:	GPIO Direction (GPIODIR), offset 0x400	
Register 3:	GPIO Interrupt Sense (GPIOIS), offset 0x404	
Register 4:	GPIO Interrupt Both Edges (GPIOIBE), offset 0x408	
Register 5:	GPIO Interrupt Event (GPIOIEV), offset 0x40C	
Register 6:	GPIO Interrupt Mask (GPIOIM), offset 0x410	
Register 7:	GPIO Raw Interrupt Status (GPIORIS), offset 0x414	

Register 8:	GPIO Masked Interrupt Status (GPIOMIS), offset 0x418	. 427
Register 9:	GPIO Interrupt Clear (GPIOICR), offset 0x41C	
Register 10:	GPIO Alternate Function Select (GPIOAFSEL), offset 0x420	430
Register 11:	GPIO 2-mA Drive Select (GPIODR2R), offset 0x500	432
Register 12:	GPIO 4-mA Drive Select (GPIODR4R), offset 0x504	433
Register 13:	GPIO 8-mA Drive Select (GPIODR8R), offset 0x508	
Register 14:	GPIO Open Drain Select (GPIOODR), offset 0x50C	435
Register 15:	GPIO Pull-Up Select (GPIOPUR), offset 0x510	436
Register 16:	GPIO Pull-Down Select (GPIOPDR), offset 0x514	
Register 17:	GPIO Slew Rate Control Select (GPIOSLR), offset 0x518	440
Register 18:	GPIO Digital Enable (GPIODEN), offset 0x51C	. 441
Register 19:	GPIO Lock (GPIOLOCK), offset 0x520	
Register 20:	GPIO Commit (GPIOCR), offset 0x524	. 444
Register 21:	GPIO Analog Mode Select (GPIOAMSEL), offset 0x528	446
Register 22:	GPIO Port Control (GPIOPCTL), offset 0x52C	448
Register 23:	GPIO Peripheral Identification 4 (GPIOPeriphID4), offset 0xFD0	450
Register 24:	GPIO Peripheral Identification 5 (GPIOPeriphID5), offset 0xFD4	451
Register 25:	GPIO Peripheral Identification 6 (GPIOPeriphID6), offset 0xFD8	452
Register 26:	GPIO Peripheral Identification 7 (GPIOPeriphID7), offset 0xFDC	453
Register 27:	GPIO Peripheral Identification 0 (GPIOPeriphID0), offset 0xFE0	454
Register 28:	GPIO Peripheral Identification 1 (GPIOPeriphID1), offset 0xFE4	455
Register 29:	GPIO Peripheral Identification 2 (GPIOPeriphID2), offset 0xFE8	456
Register 30:	GPIO Peripheral Identification 3 (GPIOPeriphID3), offset 0xFEC	457
Register 31:	GPIO PrimeCell Identification 0 (GPIOPCelIID0), offset 0xFF0	458
Register 32:	GPIO PrimeCell Identification 1 (GPIOPCelIID1), offset 0xFF4	459
Register 33:	GPIO PrimeCell Identification 2 (GPIOPCelIID2), offset 0xFF8	460
Register 34:	GPIO PrimeCell Identification 3 (GPIOPCellID3), offset 0xFFC	461
External Pe	ripheral Interface (EPI)	462
Register 1:	EPI Configuration (EPICFG), offset 0x000	
Register 2:	EPI Main Baud Rate (EPIBAUD), offset 0x004	
Register 3:	EPI SDRAM Configuration (EPISDRAMCFG), offset 0x010	
Register 4:	EPI Host-Bus 8 Configuration (EPIHB8CFG), offset 0x010	
Register 5:	EPI Host-Bus 16 Configuration (EPIHB16CFG), offset 0x010	
Register 6:	EPI General-Purpose Configuration (EPIGPCFG), offset 0x010	
Register 7:	EPI Host-Bus 8 Configuration 2 (EPIHB8CFG2), offset 0x014	
Register 8:	EPI Host-Bus 16 Configuration 2 (EPIHB16CFG2), offset 0x014	
Register 9:	EPI General-Purpose Configuration 2 (EPIGPCFG2), offset 0x014	
Register 10:	EPI Address Map (EPIADDRMAP), offset 0x01C	
Register 11:	EPI Read Size 0 (EPIRSIZE0), offset 0x020	
Register 12:	EPI Read Size 1 (EPIRSIZE1), offset 0x030	
Register 13:	EPI Read Address 0 (EPIRADDR0), offset 0x024	
Register 14:	EPI Read Address 1 (EPIRADDR1), offset 0x034	
Register 15:	EPI Non-Blocking Read Data 0 (EPIRPSTD0), offset 0x028	
Register 16:	EPI Non-Blocking Read Data 1 (EPIRPSTD1), offset 0x038	
Register 17:	EPI Status (EPISTAT), offset 0x060	
Register 18:	EPI Read FIFO Count (EPIRFIFOCNT), offset 0x06C	
Register 19:	EPI Read FIFO (EPIREADFIFO), offset 0x070	
Register 20:	EPI Read FIFO Alias 1 (EPIREADFIFO1), offset 0x074	

Register 21:	EPI Read FIFO Alias 2 (EPIREADFIFO2), offset 0x078	527
Register 22:	EPI Read FIFO Alias 3 (EPIREADFIFO3), offset 0x07C	527
Register 23:	EPI Read FIFO Alias 4 (EPIREADFIFO4), offset 0x080	527
Register 24:	EPI Read FIFO Alias 5 (EPIREADFIFO5), offset 0x084	527
Register 25:	EPI Read FIFO Alias 6 (EPIREADFIFO6), offset 0x088	527
Register 26:	EPI Read FIFO Alias 7 (EPIREADFIFO7), offset 0x08C	527
Register 27:	EPI FIFO Level Selects (EPIFIFOLVL), offset 0x200	528
Register 28:	EPI Write FIFO Count (EPIWFIFOCNT), offset 0x204	530
Register 29:	EPI Interrupt Mask (EPIIM), offset 0x210	531
Register 30:	EPI Raw Interrupt Status (EPIRIS), offset 0x214	532
Register 31:	EPI Masked Interrupt Status (EPIMIS), offset 0x218	
Register 32:	EPI Error and Interrupt Status and Clear (EPIEISC), offset 0x21C	535
General-Pu	rpose Timers	537
Register 1:	GPTM Configuration (GPTMCFG), offset 0x000	
Register 2:	GPTM Timer A Mode (GPTMTAMR), offset 0x004	
Register 3:	GPTM Timer B Mode (GPTMTBMR), offset 0x008	
Register 4:	GPTM Control (GPTMCTL), offset 0x00C	
Register 5:	GPTM Interrupt Mask (GPTMIMR), offset 0x018	562
Register 6:	GPTM Raw Interrupt Status (GPTMRIS), offset 0x01C	
Register 7:	GPTM Masked Interrupt Status (GPTMMIS), offset 0x020	
Register 8:	GPTM Interrupt Clear (GPTMICR), offset 0x024	
Register 9:	GPTM Timer A Interval Load (GPTMTAILR), offset 0x028	572
Register 10:	GPTM Timer B Interval Load (GPTMTBILR), offset 0x02C	
Register 11:	GPTM Timer A Match (GPTMTAMATCHR), offset 0x030	
Register 12:	GPTM Timer B Match (GPTMTBMATCHR), offset 0x034	575
Register 13:	GPTM Timer A Prescale (GPTMTAPR), offset 0x038	576
Register 14:	GPTM Timer B Prescale (GPTMTBPR), offset 0x03C	577
Register 15:	GPTM TimerA Prescale Match (GPTMTAPMR), offset 0x040	578
Register 16:	GPTM TimerB Prescale Match (GPTMTBPMR), offset 0x044	579
Register 17:	GPTM Timer A (GPTMTAR), offset 0x048	580
Register 18:	GPTM Timer B (GPTMTBR), offset 0x04C	581
Register 19:	GPTM Timer A Value (GPTMTAV), offset 0x050	582
Register 20:	GPTM Timer B Value (GPTMTBV), offset 0x054	583
Watchdog 1	Timers	584
Register 1:	Watchdog Load (WDTLOAD), offset 0x000	588
Register 2:	Watchdog Value (WDTVALUE), offset 0x004	
Register 3:	Watchdog Control (WDTCTL), offset 0x008	
Register 4:	Watchdog Interrupt Clear (WDTICR), offset 0x00C	
Register 5:	Watchdog Raw Interrupt Status (WDTRIS), offset 0x010	
Register 6:	Watchdog Masked Interrupt Status (WDTMIS), offset 0x014	
Register 7:	Watchdog Test (WDTTEST), offset 0x418	595
Register 8:	Watchdog Lock (WDTLOCK), offset 0xC00	
Register 9:	Watchdog Peripheral Identification 4 (WDTPeriphID4), offset 0xFD0	
Register 10:	Watchdog Peripheral Identification 5 (WDTPeriphID5), offset 0xFD4	
Register 11:	Watchdog Peripheral Identification 6 (WDTPeriphID6), offset 0xFD8	
Register 12:	Watchdog Peripheral Identification 7 (WDTPeriphID7), offset 0xFDC	
Register 13:	Watchdog Peripheral Identification 0 (WDTPeriphID0), offset 0xFE0	
Register 14:	Watchdog Peripheral Identification 1 (WDTPeriphID1), offset 0xFE4	

Register 15:	Watchdog Peripheral Identification 2 (WDTPeriphID2), offset 0xFE8	603
Register 16:	Watchdog Peripheral Identification 3 (WDTPeriphID3), offset 0xFEC	604
Register 17:	Watchdog PrimeCell Identification 0 (WDTPCellID0), offset 0xFF0	605
Register 18:	Watchdog PrimeCell Identification 1 (WDTPCellID1), offset 0xFF4	606
Register 19:	Watchdog PrimeCell Identification 2 (WDTPCellID2), offset 0xFF8	607
Register 20:	Watchdog PrimeCell Identification 3 (WDTPCellID3 ), offset 0xFFC	608
Analog-to-E	Digital Converter (ADC)	609
Register 1:	ADC Active Sample Sequencer (ADCACTSS), offset 0x000	
Register 2:	ADC Raw Interrupt Status (ADCRIS), offset 0x004	
Register 3:	ADC Interrupt Mask (ADCIM), offset 0x008	
Register 4:	ADC Interrupt Status and Clear (ADCISC), offset 0x00C	
Register 5:	ADC Overflow Status (ADCOSTAT), offset 0x010	
Register 6:	ADC Event Multiplexer Select (ADCEMUX), offset 0x014	
Register 7:	ADC Underflow Status (ADCUSTAT), offset 0x018	
Register 8:	ADC Sample Sequencer Priority (ADCSSPRI), offset 0x020	648
Register 9:	ADC Sample Phase Control (ADCSPC), offset 0x024	650
Register 10:	ADC Processor Sample Sequence Initiate (ADCPSSI), offset 0x028	652
Register 11:	ADC Sample Averaging Control (ADCSAC), offset 0x030	
Register 12:	ADC Digital Comparator Interrupt Status and Clear (ADCDCISC), offset 0x034	655
Register 13:	ADC Control (ADCCTL), offset 0x038	
Register 14:	ADC Sample Sequence Input Multiplexer Select 0 (ADCSSMUX0), offset 0x040	658
Register 15:	ADC Sample Sequence Control 0 (ADCSSCTL0), offset 0x044	660
Register 16:	ADC Sample Sequence Result FIFO 0 (ADCSSFIFO0), offset 0x048	663
Register 17:	ADC Sample Sequence Result FIFO 1 (ADCSSFIFO1), offset 0x068	663
Register 18:	ADC Sample Sequence Result FIFO 2 (ADCSSFIFO2), offset 0x088	663
Register 19:	ADC Sample Sequence Result FIFO 3 (ADCSSFIFO3), offset 0x0A8	663
Register 20:	ADC Sample Sequence FIFO 0 Status (ADCSSFSTAT0), offset 0x04C	664
Register 21:	ADC Sample Sequence FIFO 1 Status (ADCSSFSTAT1), offset 0x06C	664
Register 22:	ADC Sample Sequence FIFO 2 Status (ADCSSFSTAT2), offset 0x08C	
Register 23:	ADC Sample Sequence FIFO 3 Status (ADCSSFSTAT3), offset 0x0AC	664
Register 24:	ADC Sample Sequence 0 Operation (ADCSSOP0), offset 0x050	666
Register 25:	ADC Sample Sequence 0 Digital Comparator Select (ADCSSDC0), offset 0x054	668
Register 26:	ADC Sample Sequence Input Multiplexer Select 1 (ADCSSMUX1), offset 0x060	670
Register 27:	ADC Sample Sequence Input Multiplexer Select 2 (ADCSSMUX2), offset 0x080	
Register 28:	ADC Sample Sequence Control 1 (ADCSSCTL1), offset 0x064	
Register 29:	ADC Sample Sequence Control 2 (ADCSSCTL2), offset 0x084	
Register 30:	ADC Sample Sequence 1 Operation (ADCSSOP1), offset 0x070	
Register 31:	ADC Sample Sequence 2 Operation (ADCSSOP2), offset 0x090	
Register 32:	ADC Sample Sequence 1 Digital Comparator Select (ADCSSDC1), offset 0x074	
Register 33:	ADC Sample Sequence 2 Digital Comparator Select (ADCSSDC2), offset 0x094	
Register 34:	ADC Sample Sequence Input Multiplexer Select 3 (ADCSSMUX3), offset 0x0A0	
Register 35:	ADC Sample Sequence Control 3 (ADCSSCTL3), offset 0x0A4	
Register 36:	ADC Sample Sequence 3 Operation (ADCSSOP3), offset 0x0B0	
Register 37:	ADC Sample Sequence 3 Digital Comparator Select (ADCSSDC3), offset 0x0B4	
Register 38:	ADC Digital Comparator Reset Initial Conditions (ADCDCRIC), offset 0xD00	
Register 39:	ADC Digital Comparator Control 0 (ADCDCCTL0), offset 0xE00	
Register 40:	ADC Digital Comparator Control 1 (ADCDCCTL1), offset 0xE04	
Register 41:	ADC Digital Comparator Control 2 (ADCDCCTL2), offset 0xE08	685

Register 42:	: ADC Digital Comparator Control 3 (ADCDCCTL3), offset 0xE0C	685
Register 43:	ADC Digital Comparator Control 4 (ADCDCCTL4), offset 0xE10	685
Register 44	ADC Digital Comparator Control 5 (ADCDCCTL5), offset 0xE14	685
Register 45	ADC Digital Comparator Control 6 (ADCDCCTL6), offset 0xE18	685
Register 46	ADC Digital Comparator Control 7 (ADCDCCTL7), offset 0xE1C	685
Register 47:	: ADC Digital Comparator Range 0 (ADCDCCMP0), offset 0xE40	688
Register 48:	: ADC Digital Comparator Range 1 (ADCDCCMP1), offset 0xE44	688
Register 49:	: ADC Digital Comparator Range 2 (ADCDCCMP2), offset 0xE48	688
Register 50:	ADC Digital Comparator Range 3 (ADCDCCMP3), offset 0xE4C	688
Register 51:	ADC Digital Comparator Range 4 (ADCDCCMP4), offset 0xE50	688
Register 52:	ADC Digital Comparator Range 5 (ADCDCCMP5), offset 0xE54	688
Register 53:	ADC Digital Comparator Range 6 (ADCDCCMP6), offset 0xE58	688
Register 54:	ADC Digital Comparator Range 7 (ADCDCCMP7), offset 0xE5C	688
Universal	Asynchronous Receivers/Transmitters (UARTs)	690
Register 1:	UART Data (UARTDR), offset 0x000	
Register 2:	UART Receive Status/Error Clear (UARTRSR/UARTECR), offset 0x004	
Register 3:	UART Flag (UARTFR), offset 0x018	
Register 4:	UART IrDA Low-Power Register (UARTILPR), offset 0x020	713
Register 5:	UART Integer Baud-Rate Divisor (UARTIBRD), offset 0x024	714
Register 6:	UART Fractional Baud-Rate Divisor (UARTFBRD), offset 0x028	
Register 7:	UART Line Control (UARTLCRH), offset 0x02C	716
Register 8:	UART Control (UARTCTL), offset 0x030	718
Register 9:	UART Interrupt FIFO Level Select (UARTIFLS), offset 0x034	722
Register 10:	: UART Interrupt Mask (UARTIM), offset 0x038	724
Register 11:	UART Raw Interrupt Status (UARTRIS), offset 0x03C	728
Register 12:	: UART Masked Interrupt Status (UARTMIS), offset 0x040	732
Register 13:	: UART Interrupt Clear (UARTICR), offset 0x044	736
Register 14:	: UART DMA Control (UARTDMACTL), offset 0x048	738
Register 15:	: UART LIN Control (UARTLCTL), offset 0x090	739
Register 16:	: UART LIN Snap Shot (UARTLSS), offset 0x094	740
Register 17:	: UART LIN Timer (UARTLTIM), offset 0x098	741
Register 18:	: UART Peripheral Identification 4 (UARTPeriphID4), offset 0xFD0	742
Register 19:	: UART Peripheral Identification 5 (UARTPeriphID5), offset 0xFD4	743
Register 20:	: UART Peripheral Identification 6 (UARTPeriphID6), offset 0xFD8	744
Register 21:	: UART Peripheral Identification 7 (UARTPeriphID7), offset 0xFDC	745
Register 22:	• • • • • • • • • • • • • • • • • • • •	
Register 23:	: UART Peripheral Identification 1 (UARTPeriphID1), offset 0xFE4	747
Register 24:	: UART Peripheral Identification 2 (UARTPeriphID2), offset 0xFE8	748
Register 25:	: UART Peripheral Identification 3 (UARTPeriphID3), offset 0xFEC	749
Register 26:	: UART PrimeCell Identification 0 (UARTPCellID0), offset 0xFF0	750
Register 27:	: UART PrimeCell Identification 1 (UARTPCellID1), offset 0xFF4	751
Register 28:	: UART PrimeCell Identification 2 (UARTPCellID2), offset 0xFF8	752
Register 29:	: UART PrimeCell Identification 3 (UARTPCellID3), offset 0xFFC	753
Synchrone	ous Serial Interface (SSI)	754
Register 1:	SSI Control 0 (SSICR0), offset 0x000	769
Register 2:	SSI Control 1 (SSICR1), offset 0x004	
Register 3:	SSI Data (SSIDR), offset 0x008	
Register 4:	SSI Status (SSISR), offset 0x00C	

Register 5:	SSI Clock Prescale (SSICPSR), offset 0x010	776
Register 6:	SSI Interrupt Mask (SSIIM), offset 0x014	777
Register 7:	SSI Raw Interrupt Status (SSIRIS), offset 0x018	
Register 8:	SSI Masked Interrupt Status (SSIMIS), offset 0x01C	780
Register 9:	SSI Interrupt Clear (SSIICR), offset 0x020	
Register 10:	SSI DMA Control (SSIDMACTL), offset 0x024	
Register 11:	SSI Peripheral Identification 4 (SSIPeriphID4), offset 0xFD0	
Register 12:	SSI Peripheral Identification 5 (SSIPeriphID5), offset 0xFD4	
Register 13:	SSI Peripheral Identification 6 (SSIPeriphID6), offset 0xFD8	
Register 14:	SSI Peripheral Identification 7 (SSIPeriphID7), offset 0xFDC	
Register 15:	SSI Peripheral Identification 0 (SSIPeriphID0), offset 0xFE0	
Register 16:	SSI Peripheral Identification 1 (SSIPeriphID1), offset 0xFE4	
Register 17:	SSI Peripheral Identification 2 (SSIPeriphID2), offset 0xFE8	
Register 18:	SSI Peripheral Identification 3 (SSIPeriphID3), offset 0xFEC	
Register 19:	SSI PrimeCell Identification 0 (SSIPCellID0), offset 0xFF0	
Register 20:	SSI PrimeCell Identification 1 (SSIPCellID1), offset 0xFF4	
Register 21:	SSI PrimeCell Identification 2 (SSIPCellID2), offset 0xFF8	
Register 22:	SSI PrimeCell Identification 3 (SSIPCellID3), offset 0xFFC	795
Inter-Integra	ated Circuit (I <sup>2</sup> C) Interface	796
Register 1:	I <sup>2</sup> C Master Slave Address (I2CMSA), offset 0x000	813
Register 2:	I <sup>2</sup> C Master Control/Status (I2CMCS), offset 0x004	814
Register 3:	I <sup>2</sup> C Master Data (I2CMDR), offset 0x008	819
Register 4:	I <sup>2</sup> C Master Timer Period (I2CMTPR), offset 0x00C	820
Register 5:	I <sup>2</sup> C Master Interrupt Mask (I2CMIMR), offset 0x010	821
Register 6:	I <sup>2</sup> C Master Raw Interrupt Status (I2CMRIS), offset 0x014	822
Register 7:	I <sup>2</sup> C Master Masked Interrupt Status (I2CMMIS), offset 0x018	823
Register 8:	I <sup>2</sup> C Master Interrupt Clear (I2CMICR), offset 0x01C	824
Register 9:	I <sup>2</sup> C Master Configuration (I2CMCR), offset 0x020	825
Register 10:	I <sup>2</sup> C Slave Own Address (I2CSOAR), offset 0x800	
Register 11:	I <sup>2</sup> C Slave Control/Status (I2CSCSR), offset 0x804	827
Register 12:	I <sup>2</sup> C Slave Data (I2CSDR), offset 0x808	
Register 13:	I <sup>2</sup> C Slave Interrupt Mask (I2CSIMR), offset 0x80C	
Register 14:	I <sup>2</sup> C Slave Raw Interrupt Status (I2CSRIS), offset 0x810	
Register 15:	I <sup>2</sup> C Slave Masked Interrupt Status (I2CSMIS), offset 0x814	832
Register 16:	I <sup>2</sup> C Slave Interrupt Clear (I2CSICR), offset 0x818	
•	ated Circuit Sound (I <sup>2</sup> S) Interface	
Register 1:	I <sup>2</sup> S Transmit FIFO Data (I2STXFIFO), offset 0x000	847
Register 2:	I <sup>2</sup> S Transmit FIFO Configuration (I2STXFIFOCFG), offset 0x004	
Register 3:	I <sup>2</sup> S Transmit Module Configuration (I2STXCFG), offset 0x008	
Register 4:	I <sup>2</sup> S Transmit FIFO Limit (I2STXLIMIT), offset 0x00C	
Register 5:	I <sup>2</sup> S Transmit Interrupt Status and Mask (I2STXISM), offset 0x010	
Register 5:	I <sup>2</sup> S Transmit FIFO Level (I2STXLEV), offset 0x018	
•	I <sup>2</sup> S Receive FIFO Data (I2SRXFIFO), offset 0x800	
Register 7:		
Register 8:	I <sup>2</sup> S Receive FIFO Configuration (I2SRXFIFOCFG), offset 0x804	
Register 9:	I <sup>2</sup> S Receive Module Configuration (I2SRXCFG), offset 0x808	
Register 10:	I <sup>2</sup> S Receive FIFO Limit (I2SRXLIMIT), offset 0x80C	859

Register 11:	I <sup>2</sup> S Receive Interrupt Status and Mask (I2SRXISM), offset 0x810	860
Register 12:	I <sup>2</sup> S Receive FIFO Level (I2SRXLEV), offset 0x818	861
Register 13:	I <sup>2</sup> S Module Configuration (I2SCFG), offset 0xC00	862
Register 14:	I <sup>2</sup> S Interrupt Mask (I2SIM), offset 0xC10	864
Register 15:	I <sup>2</sup> S Raw Interrupt Status (I2SRIS), offset 0xC14	866
Register 16:	I <sup>2</sup> S Masked Interrupt Status (I2SMIS), offset 0xC18	868
Register 17:	I <sup>2</sup> S Interrupt Clear (I2SIC), offset 0xC1C	
Controller A	Area Network (CAN) Module	871
Register 1:	CAN Control (CANCTL), offset 0x000	
Register 2:	CAN Status (CANSTS), offset 0x004	
Register 3:	CAN Error Counter (CANERR), offset 0x008	
Register 4:	CAN Bit Timing (CANBIT), offset 0x00C	
Register 5:	CAN Interrupt (CANINT), offset 0x010	
Register 6:	CAN Test (CANTST), offset 0x014	
Register 7:	CAN Baud Rate Prescaler Extension (CANBRPE), offset 0x018	
Register 8:	CAN IF1 Command Request (CANIF1CRQ), offset 0x020	
Register 9:	CAN IF2 Command Request (CANIF2CRQ), offset 0x080	
Register 10:	CAN IF1 Command Mask (CANIF1CMSK), offset 0x024	
Register 11:	CAN IF2 Command Mask (CANIF2CMSK), offset 0x084	
Register 12:	CAN IF1 Mask 1 (CANIF1MSK1), offset 0x028	
Register 13:	CAN IF2 Mask 1 (CANIF2MSK1), offset 0x088	
Register 14:	CAN IF1 Mask 2 (CANIF1MSK2), offset 0x02C	
Register 15:	CAN IF2 Mask 2 (CANIF2MSK2), offset 0x08C	
Register 16:	CAN IF1 Arbitration 1 (CANIF1ARB1), offset 0x030	
Register 17:	CAN IF2 Arbitration 1 (CANIF2ARB1), offset 0x090	
Register 18:	CAN IF1 Arbitration 2 (CANIF1ARB2), offset 0x034	
Register 19:	CAN IF2 Arbitration 2 (CANIF2ARB2), offset 0x094	
Register 20:	CAN IF1 Message Control (CANIF1MCTL), offset 0x038	914
Register 21:	CAN IF2 Message Control (CANIF2MCTL), offset 0x098	
Register 22:	CAN IF1 Data A1 (CANIF1DA1), offset 0x03C	917
Register 23:	CAN IF1 Data A2 (CANIF1DA2), offset 0x040	917
Register 24:	CAN IF1 Data B1 (CANIF1DB1), offset 0x044	917
Register 25:	CAN IF1 Data B2 (CANIF1DB2), offset 0x048	917
Register 26:	CAN IF2 Data A1 (CANIF2DA1), offset 0x09C	917
Register 27:	CAN IF2 Data A2 (CANIF2DA2), offset 0x0A0	917
Register 28:	CAN IF2 Data B1 (CANIF2DB1), offset 0x0A4	917
Register 29:	CAN IF2 Data B2 (CANIF2DB2), offset 0x0A8	917
Register 30:	CAN Transmission Request 1 (CANTXRQ1), offset 0x100	918
Register 31:	CAN Transmission Request 2 (CANTXRQ2), offset 0x104	918
Register 32:	CAN New Data 1 (CANNWDA1), offset 0x120	919
Register 33:	CAN New Data 2 (CANNWDA2), offset 0x124	919
Register 34:	CAN Message 1 Interrupt Pending (CANMSG1INT), offset 0x140	
Register 35:	CAN Message 2 Interrupt Pending (CANMSG2INT), offset 0x144	920
Register 36:	CAN Message 1 Valid (CANMSG1VAL), offset 0x160	921
Register 37:	CAN Message 2 Valid (CANMSG2VAL), offset 0x164	921
Ethernet Co	ontroller	922
Register 1:	Ethernet MAC Raw Interrupt Status/Acknowledge (MACRIS/MACIACK), offset 0x000	
Register 2:	Ethernet MAC Interrupt Mask (MACIM), offset 0x004	

Register 3:	Ethernet MAC Receive Control (MACRCTL), offset 0x008	. 942
Register 4:	Ethernet MAC Transmit Control (MACTCTL), offset 0x00C	. 944
Register 5:	Ethernet MAC Data (MACDATA), offset 0x010	. 946
Register 6:	Ethernet MAC Individual Address 0 (MACIA0), offset 0x014	. 948
Register 7:	Ethernet MAC Individual Address 1 (MACIA1), offset 0x018	. 949
Register 8:	Ethernet MAC Threshold (MACTHR), offset 0x01C	. 950
Register 9:	Ethernet MAC Management Control (MACMCTL), offset 0x020	. 952
Register 10:	Ethernet MAC Management Divider (MACMDV), offset 0x024	. 954
Register 11:	Ethernet MAC Management Transmit Data (MACMTXD), offset 0x02C	. 955
Register 12:	Ethernet MAC Management Receive Data (MACMRXD), offset 0x030	. 956
Register 13:	Ethernet MAC Number of Packets (MACNP), offset 0x034	. 957
Register 14:	Ethernet MAC Transmission Request (MACTR), offset 0x038	. 958
Register 15:	Ethernet MAC Timer Support (MACTS), offset 0x03C	. 959
Register 16:	Ethernet MAC LED Encoding (MACLED), offset 0x040	. 960
Register 17:	Ethernet PHY MDIX (MDIX), offset 0x044	. 962
Register 18:	Ethernet PHY Management Register 0 – Control (MR0), address 0x00	. 963
Register 19:	Ethernet PHY Management Register 1 – Status (MR1), address 0x01	
Register 20:	Ethernet PHY Management Register 2 – PHY Identifier 1 (MR2), address 0x02	
Register 21:	Ethernet PHY Management Register 3 – PHY Identifier 2 (MR3), address 0x03	
Register 22:	Ethernet PHY Management Register 4 – Auto-Negotiation Advertisement (MR4), address 0x04	
Register 23:	Ethernet PHY Management Register 5 – Auto-Negotiation Link Partner Base Page Ability (MR5), address 0x05	
Register 24:	Ethernet PHY Management Register 6 – Auto-Negotiation Expansion (MR6), address 0x06	
Register 25:	Ethernet PHY Management Register 16 – Vendor-Specific (MR16), address 0x10	
Register 26:	Ethernet PHY Management Register 17 – Mode Control/Status (MR17), address 0x11	
Register 27:	Ethernet PHY Management Register 27 – Special Control/Status (MR27), address 0x1B	
Register 28:	Ethernet PHY Management Register 29 – Interrupt Status (MR29), address 0x1D	
Register 29:	Ethernet PHY Management Register 30 – Interrupt Mask (MR30), address 0x1E	
Register 30:	Ethernet PHY Management Register 31 – PHY Special Control/Status (MR31), address 0x1F	
Universal S	erial Bus (USB) Controller	. 983
Register 1:	` ,	1011
Register 2:	USB Power (USBPOWER), offset 0x001	
Register 3:	USB Transmit Interrupt Status (USBTXIS), offset 0x002	
Register 4:	USB Receive Interrupt Status (USBRXIS), offset 0x004	
Register 5:	USB Transmit Interrupt Enable (USBTXIE), offset 0x006	
Register 6:	USB Receive Interrupt Enable (USBRXIE), offset 0x008	
Register 7:	USB General Interrupt Status (USBIS), offset 0x00A	
Register 8:	USB Interrupt Enable (USBIE), offset 0x00B	
Register 9:	USB Frame Value (USBFRAME), offset 0x00C	
Register 10:	USB Endpoint Index (USBEPIDX), offset 0x00E	
Register 11:	USB Test Mode (USBTEST), offset 0x00F	
Register 12:	USB FIFO Endpoint 0 (USBFIFO0), offset 0x020	
Register 13:	USB FIFO Endpoint 1 (USBFIFO1), offset 0x024	
Register 14:	USB FIFO Endpoint 2 (USBFIFO2), offset 0x028	

Register 15:	USB FIFO Endpoint 3 (USBFIFO3), offset 0x02C	1033
Register 16:	USB FIFO Endpoint 4 (USBFIFO4), offset 0x030	1033
Register 17:	USB FIFO Endpoint 5 (USBFIFO5), offset 0x034	. 1033
Register 18:	USB FIFO Endpoint 6 (USBFIFO6), offset 0x038	. 1033
Register 19:	USB FIFO Endpoint 7 (USBFIFO7), offset 0x03C	1033
Register 20:	USB FIFO Endpoint 8 (USBFIFO8), offset 0x040	. 1033
Register 21:	USB FIFO Endpoint 9 (USBFIFO9), offset 0x044	. 1033
Register 22:	USB FIFO Endpoint 10 (USBFIFO10), offset 0x048	. 1033
Register 23:	USB FIFO Endpoint 11 (USBFIFO11), offset 0x04C	. 1033
Register 24:	USB FIFO Endpoint 12 (USBFIFO12), offset 0x050	. 1033
Register 25:	USB FIFO Endpoint 13 (USBFIFO13), offset 0x054	. 1033
Register 26:	USB FIFO Endpoint 14 (USBFIFO14), offset 0x058	. 1033
Register 27:	USB FIFO Endpoint 15 (USBFIFO15), offset 0x05C	1033
Register 28:	USB Device Control (USBDEVCTL), offset 0x060	. 1035
Register 29:	USB Transmit Dynamic FIFO Sizing (USBTXFIFOSZ), offset 0x062	1037
Register 30:	USB Receive Dynamic FIFO Sizing (USBRXFIFOSZ), offset 0x063	1037
Register 31:	USB Transmit FIFO Start Address (USBTXFIFOADD), offset 0x064	1038
Register 32:	USB Receive FIFO Start Address (USBRXFIFOADD), offset 0x066	1038
Register 33:	USB Connect Timing (USBCONTIM), offset 0x07A	. 1039
Register 34:	USB OTG VBUS Pulse Timing (USBVPLEN), offset 0x07B	
Register 35:	USB Full-Speed Last Transaction to End of Frame Timing (USBFSEOF), offset 0x07D	
Register 36:	USB Low-Speed Last Transaction to End of Frame Timing (USBLSEOF), offset 0x07E	
Register 37:	USB Transmit Functional Address Endpoint 0 (USBTXFUNCADDR0), offset 0x080	1043
Register 38:	USB Transmit Functional Address Endpoint 1 (USBTXFUNCADDR1), offset 0x088	1043
Register 39:	USB Transmit Functional Address Endpoint 2 (USBTXFUNCADDR2), offset 0x090	1043
Register 40:	USB Transmit Functional Address Endpoint 3 (USBTXFUNCADDR3), offset 0x098	1043
Register 41:	USB Transmit Functional Address Endpoint 4 (USBTXFUNCADDR4), offset 0x0A0	
Register 42:	USB Transmit Functional Address Endpoint 5 (USBTXFUNCADDR5), offset 0x0A8	1043
Register 43:	USB Transmit Functional Address Endpoint 6 (USBTXFUNCADDR6), offset 0x0B0	
Register 44:	USB Transmit Functional Address Endpoint 7 (USBTXFUNCADDR7), offset 0x0B8	1043
Register 45:	USB Transmit Functional Address Endpoint 8 (USBTXFUNCADDR8), offset 0x0C0	1043
Register 46:	USB Transmit Functional Address Endpoint 9 (USBTXFUNCADDR9), offset 0x0C8	1043
Register 47:	USB Transmit Functional Address Endpoint 10 (USBTXFUNCADDR10), offset 0x0D0	
Register 48:	USB Transmit Functional Address Endpoint 11 (USBTXFUNCADDR11), offset 0x0D8	
Register 49:	USB Transmit Functional Address Endpoint 12 (USBTXFUNCADDR12), offset 0x0E0	1043
Register 50:	USB Transmit Functional Address Endpoint 13 (USBTXFUNCADDR13), offset 0x0E8	1043
Register 51:	USB Transmit Functional Address Endpoint 14 (USBTXFUNCADDR14), offset 0x0F0	1043
Register 52:	USB Transmit Functional Address Endpoint 15 (USBTXFUNCADDR15), offset 0x0F8	1043
Register 53:	USB Transmit Hub Address Endpoint 0 (USBTXHUBADDR0), offset 0x082	
Register 54:	USB Transmit Hub Address Endpoint 1 (USBTXHUBADDR1), offset 0x08A	1045
Register 55:	USB Transmit Hub Address Endpoint 2 (USBTXHUBADDR2), offset 0x092	1045
Register 56:	USB Transmit Hub Address Endpoint 3 (USBTXHUBADDR3), offset 0x09A	
Register 57:	USB Transmit Hub Address Endpoint 4 (USBTXHUBADDR4), offset 0x0A2	1045
Register 58:	USB Transmit Hub Address Endpoint 5 (USBTXHUBADDR5), offset 0x0AA	
Register 59:	USB Transmit Hub Address Endpoint 6 (USBTXHUBADDR6), offset 0x0B2	
Register 60:	USB Transmit Hub Address Endpoint 7 (USBTXHUBADDR7), offset 0x0BA	
Register 61:	USB Transmit Hub Address Endpoint 8 (USBTXHUBADDR8), offset 0x0C2	1045
Register 62:	USB Transmit Hub Address Endpoint 9 (USBTXHUBADDR9), offset 0x0CA	1045

Register 63:	USB Transmit Hub Address Endpoint 10 (USBTXHUBADDR10), offset 0x0D2	1045
Register 64:	USB Transmit Hub Address Endpoint 11 (USBTXHUBADDR11), offset 0x0DA	1045
Register 65:	USB Transmit Hub Address Endpoint 12 (USBTXHUBADDR12), offset 0x0E2	1045
Register 66:	USB Transmit Hub Address Endpoint 13 (USBTXHUBADDR13), offset 0x0EA	1045
Register 67:	USB Transmit Hub Address Endpoint 14 (USBTXHUBADDR14), offset 0x0F2	
Register 68:	USB Transmit Hub Address Endpoint 15 (USBTXHUBADDR15), offset 0x0FA	
Register 69:	USB Transmit Hub Port Endpoint 0 (USBTXHUBPORT0), offset 0x083	
Register 70:	USB Transmit Hub Port Endpoint 1 (USBTXHUBPORT1), offset 0x08B	
Register 71:	USB Transmit Hub Port Endpoint 2 (USBTXHUBPORT2), offset 0x093	
Register 72:	USB Transmit Hub Port Endpoint 3 (USBTXHUBPORT3), offset 0x09B	
Register 73:	USB Transmit Hub Port Endpoint 4 (USBTXHUBPORT4), offset 0x0A3	
Register 74:	USB Transmit Hub Port Endpoint 5 (USBTXHUBPORT5), offset 0x0AB	
Register 75:	USB Transmit Hub Port Endpoint 6 (USBTXHUBPORT6), offset 0x0B3	
Register 76:	USB Transmit Hub Port Endpoint 7 (USBTXHUBPORT7), offset 0x0BB	
Register 77:	USB Transmit Hub Port Endpoint 8 (USBTXHUBPORT8), offset 0x0C3	
Register 78:	USB Transmit Hub Port Endpoint 9 (USBTXHUBPORT9), offset 0x0CB	
Register 79:	USB Transmit Hub Port Endpoint 10 (USBTXHUBPORT10), offset 0x0D3	
Register 80:	USB Transmit Hub Port Endpoint 11 (USBTXHUBPORT11), offset 0x0DB	
Register 81:	USB Transmit Hub Port Endpoint 12 (USBTXHUBPORT12), offset 0x0E3	
Register 82:	USB Transmit Hub Port Endpoint 13 (USBTXHUBPORT13), offset 0x0EB	
Register 83:	USB Transmit Hub Port Endpoint 14 (USBTXHUBPORT14), offset 0x0F3	
Register 84:	USB Transmit Hub Port Endpoint 15 (USBTXHUBPORT15), offset 0x0FB	
Register 85:	USB Receive Functional Address Endpoint 1 (USBRXFUNCADDR1), offset 0x08C	
Register 86:	USB Receive Functional Address Endpoint 2 (USBRXFUNCADDR2), offset 0x094	
Register 87:	USB Receive Functional Address Endpoint 3 (USBRXFUNCADDR3), offset 0x09C	
Register 88:	USB Receive Functional Address Endpoint 4 (USBRXFUNCADDR4), offset 0x0A4	
Register 89:	USB Receive Functional Address Endpoint 5 (USBRXFUNCADDR5), offset 0x0AC	
Register 90:	USB Receive Functional Address Endpoint 6 (USBRXFUNCADDR6), offset 0x0B4	
Register 91:	USB Receive Functional Address Endpoint 7 (USBRXFUNCADDR7), offset 0x0BC	
Register 92:	USB Receive Functional Address Endpoint 8 (USBRXFUNCADDR8), offset 0x0C4	
Register 93:	USB Receive Functional Address Endpoint 9 (USBRXFUNCADDR9), offset 0x0CC	
Register 94:	USB Receive Functional Address Endpoint 10 (USBRXFUNCADDR10), offset 0x0D4	
Register 95:	USB Receive Functional Address Endpoint 11 (USBRXFUNCADDR11), offset 0x0DC	
Register 96:		1049
Register 97:	USB Receive Functional Address Endpoint 13 (USBRXFUNCADDR13), offset 0x0EC	1049
U	USB Receive Functional Address Endpoint 14 (USBRXFUNCADDR14), offset 0x0F4	
•	USB Receive Functional Address Endpoint 15 (USBRXFUNCADDR15), offset 0x0FC	
-	USB Receive Hub Address Endpoint 1 (USBRXHUBADDR1), offset 0x08E	
•	USB Receive Hub Address Endpoint 2 (USBRXHUBADDR2), offset 0x096	
_	USB Receive Hub Address Endpoint 3 (USBRXHUBADDR3), offset 0x09E	
•	USB Receive Hub Address Endpoint 4 (USBRXHUBADDR4), offset 0x0A6	
•	USB Receive Hub Address Endpoint 5 (USBRXHUBADDR5), offset 0x0AE	
•	USB Receive Hub Address Endpoint 6 (USBRXHUBADDR6), offset 0x0B6	
-	USB Receive Hub Address Endpoint 7 (USBRXHUBADDR7), offset 0x0BE	
	USB Receive Hub Address Endpoint 8 (USBRXHUBADDR8), offset 0x0C6	
•	USB Receive Hub Address Endpoint 9 (USBRXHUBADDR9), offset 0x0CE	
-	USB Receive Hub Address Endpoint 10 (USBRXHUBADDR10), offset 0x0D6	
•	USB Receive Hub Address Endpoint 11 (USBRXHUBADDR11), offset 0x0DE	

Register 111: U	JSB Receive Hub Address Endpoint 12 (USBRXHUBADDR12), offset 0x0E6	1051
Register 112: U	JSB Receive Hub Address Endpoint 13 (USBRXHUBADDR13), offset 0x0EE	1051
Register 113: U	JSB Receive Hub Address Endpoint 14 (USBRXHUBADDR14), offset 0x0F6	1051
Register 114: U	JSB Receive Hub Address Endpoint 15 (USBRXHUBADDR15), offset 0x0FE	1051
Register 115: U	JSB Receive Hub Port Endpoint 1 (USBRXHUBPORT1), offset 0x08F	1053
Register 116: U	JSB Receive Hub Port Endpoint 2 (USBRXHUBPORT2), offset 0x097	1053
•	JSB Receive Hub Port Endpoint 3 (USBRXHUBPORT3), offset 0x09F	
_	JSB Receive Hub Port Endpoint 4 (USBRXHUBPORT4), offset 0x0A7	
•	JSB Receive Hub Port Endpoint 5 (USBRXHUBPORT5), offset 0x0AF	
Register 120: U	JSB Receive Hub Port Endpoint 6 (USBRXHUBPORT6), offset 0x0B7	1053
Register 121: U	JSB Receive Hub Port Endpoint 7 (USBRXHUBPORT7), offset 0x0BF	1053
Register 122: U	JSB Receive Hub Port Endpoint 8 (USBRXHUBPORT8), offset 0x0C7	1053
Register 123: U	JSB Receive Hub Port Endpoint 9 (USBRXHUBPORT9), offset 0x0CF	1053
Register 124: U	JSB Receive Hub Port Endpoint 10 (USBRXHUBPORT10), offset 0x0D7	1053
Register 125: U	JSB Receive Hub Port Endpoint 11 (USBRXHUBPORT11), offset 0x0DF	1053
Register 126: U	JSB Receive Hub Port Endpoint 12 (USBRXHUBPORT12), offset 0x0E7	1053
-	JSB Receive Hub Port Endpoint 13 (USBRXHUBPORT13), offset 0x0EF	
Register 128: U	JSB Receive Hub Port Endpoint 14 (USBRXHUBPORT14), offset 0x0F7	1053
	JSB Receive Hub Port Endpoint 15 (USBRXHUBPORT15), offset 0x0FF	
	JSB Maximum Transmit Data Endpoint 1 (USBTXMAXP1), offset 0x110	
-	JSB Maximum Transmit Data Endpoint 2 (USBTXMAXP2), offset 0x120	
Register 132: U	JSB Maximum Transmit Data Endpoint 3 (USBTXMAXP3), offset 0x130	1055
•	JSB Maximum Transmit Data Endpoint 4 (USBTXMAXP4), offset 0x140	
-	JSB Maximum Transmit Data Endpoint 5 (USBTXMAXP5), offset 0x150	
Register 135: U	JSB Maximum Transmit Data Endpoint 6 (USBTXMAXP6), offset 0x160	1055
-	JSB Maximum Transmit Data Endpoint 7 (USBTXMAXP7), offset 0x170	
Register 137: U	JSB Maximum Transmit Data Endpoint 8 (USBTXMAXP8), offset 0x180	1055
	JSB Maximum Transmit Data Endpoint 9 (USBTXMAXP9), offset 0x190	
•	JSB Maximum Transmit Data Endpoint 10 (USBTXMAXP10), offset 0x1A0	
•	JSB Maximum Transmit Data Endpoint 11 (USBTXMAXP11), offset 0x1B0	
_	JSB Maximum Transmit Data Endpoint 12 (USBTXMAXP12), offset 0x1C0	
•	JSB Maximum Transmit Data Endpoint 13 (USBTXMAXP13), offset 0x1D0	
_	JSB Maximum Transmit Data Endpoint 14 (USBTXMAXP14), offset 0x1E0	
Register 144: U	JSB Maximum Transmit Data Endpoint 15 (USBTXMAXP15), offset 0x1F0	1055
-	JSB Control and Status Endpoint 0 Low (USBCSRL0), offset 0x102	
Register 146: U	JSB Control and Status Endpoint 0 High (USBCSRH0), offset 0x103	1061
	JSB Receive Byte Count Endpoint 0 (USBCOUNT0), offset 0x108	
_	JSB Type Endpoint 0 (USBTYPE0), offset 0x10A	
	JSB NAK Limit (USBNAKLMT), offset 0x10B	
Register 150: U	JSB Transmit Control and Status Endpoint 1 Low (USBTXCSRL1), offset 0x112	1066
-	JSB Transmit Control and Status Endpoint 2 Low (USBTXCSRL2), offset 0x122	
•	JSB Transmit Control and Status Endpoint 3 Low (USBTXCSRL3), offset 0x132	
-	JSB Transmit Control and Status Endpoint 4 Low (USBTXCSRL4), offset 0x142	
•	JSB Transmit Control and Status Endpoint 5 Low (USBTXCSRL5), offset 0x152	
-	JSB Transmit Control and Status Endpoint 6 Low (USBTXCSRL6), offset 0x162	
-	JSB Transmit Control and Status Endpoint 7 Low (USBTXCSRL7), offset 0x172	
-	JSB Transmit Control and Status Endpoint 8 Low (USBTXCSRL8), offset 0x182	
•	JSB Transmit Control and Status Endpoint 9 Low (USBTXCSRL9), offset 0x192	

Register 159:	USB Transmit Control and Status Endpoint 10 Low (USBTXCSRL10), offset 0x1A2	. 1066
Register 160:	USB Transmit Control and Status Endpoint 11 Low (USBTXCSRL11), offset 0x1B2	. 1066
Register 161:	USB Transmit Control and Status Endpoint 12 Low (USBTXCSRL12), offset 0x1C2	. 1066
Register 162:	USB Transmit Control and Status Endpoint 13 Low (USBTXCSRL13), offset 0x1D2	1066
	USB Transmit Control and Status Endpoint 14 Low (USBTXCSRL14), offset 0x1E2	
-	USB Transmit Control and Status Endpoint 15 Low (USBTXCSRL15), offset 0x1F2	
_	USB Transmit Control and Status Endpoint 1 High (USBTXCSRH1), offset 0x113	
	USB Transmit Control and Status Endpoint 2 High (USBTXCSRH2), offset 0x123	
	USB Transmit Control and Status Endpoint 3 High (USBTXCSRH3), offset 0x133	
	USB Transmit Control and Status Endpoint 4 High (USBTXCSRH4), offset 0x143	
	USB Transmit Control and Status Endpoint 5 High (USBTXCSRH5), offset 0x153	
	USB Transmit Control and Status Endpoint 6 High (USBTXCSRH6), offset 0x163	
_	USB Transmit Control and Status Endpoint 7 High (USBTXCSRH7), offset 0x173	
-	USB Transmit Control and Status Endpoint 8 High (USBTXCSRH8), offset 0x183	
	USB Transmit Control and Status Endpoint 9 High (USBTXCSRH9), offset 0x193	
	USB Transmit Control and Status Endpoint 10 High (USBTXCSRH10), offset 0x1A3	
_	USB Transmit Control and Status Endpoint 11 High (USBTXCSRH11), offset 0x1B3	
-	USB Transmit Control and Status Endpoint 12 High (USBTXCSRH12), offset 0x1C3	
_	USB Transmit Control and Status Endpoint 13 High (USBTXCSRH13), offset 0x1D3	
	USB Transmit Control and Status Endpoint 14 High (USBTXCSRH14), offset 0x1E3	
_	USB Transmit Control and Status Endpoint 15 High (USBTXCSRH15), offset 0x1F3	
_	USB Maximum Receive Data Endpoint 1 (USBRXMAXP1), offset 0x114	
	USB Maximum Receive Data Endpoint 2 (USBRXMAXP2), offset 0x124	
_	USB Maximum Receive Data Endpoint 3 (USBRXMAXP3), offset 0x134	
_	USB Maximum Receive Data Endpoint 4 (USBRXMAXP4), offset 0x144	
-	USB Maximum Receive Data Endpoint 5 (USBRXMAXP5), offset 0x154	
•	USB Maximum Receive Data Endpoint 6 (USBRXMAXP6), offset 0x164	
-	USB Maximum Receive Data Endpoint 7 (USBRXMAXP7), offset 0x174	
	USB Maximum Receive Data Endpoint 8 (USBRXMAXP8), offset 0x184	
_	USB Maximum Receive Data Endpoint 9 (USBRXMAXP9), offset 0x194	
-	USB Maximum Receive Data Endpoint 10 (USBRXMAXP10), offset 0x1A4	
	USB Maximum Receive Data Endpoint 11 (USBRXMAXP11), offset 0x1B4	
	USB Maximum Receive Data Endpoint 12 (USBRXMAXP12), offset 0x1C4	
	USB Maximum Receive Data Endpoint 13 (USBRXMAXP13), offset 0x1D4	
_	USB Maximum Receive Data Endpoint 14 (USBRXMAXP14), offset 0x1E4	
Register 194:	USB Maximum Receive Data Endpoint 15 (USBRXMAXP15), offset 0x1F4	1075
_	USB Receive Control and Status Endpoint 1 Low (USBRXCSRL1), offset 0x116	
-	USB Receive Control and Status Endpoint 2 Low (USBRXCSRL2), offset 0x126	
-	USB Receive Control and Status Endpoint 3 Low (USBRXCSRL3), offset 0x136	
_	USB Receive Control and Status Endpoint 4 Low (USBRXCSRL4), offset 0x146	
•	USB Receive Control and Status Endpoint 5 Low (USBRXCSRL5), offset 0x156	
-	USB Receive Control and Status Endpoint 6 Low (USBRXCSRL6), offset 0x166	
_	USB Receive Control and Status Endpoint 7 Low (USBRXCSRL7), offset 0x176	
-	USB Receive Control and Status Endpoint 8 Low (USBRXCSRL8), offset 0x186	
	USB Receive Control and Status Endpoint 9 Low (USBRXCSRL9), offset 0x196	
	USB Receive Control and Status Endpoint 10 Low (USBRXCSRL10), offset 0x1A6	
-	USB Receive Control and Status Endpoint 11 Low (USBRXCSRL11), offset 0x1B6	
_	USB Receive Control and Status Endpoint 12 Low (USBRXCSRL12), offset 0x1C6	

Register 207: USB Receive Control and Status Endpoint 13 Low (USBRXCSRL13), offset 0x1D6	1077
Register 208: USB Receive Control and Status Endpoint 14 Low (USBRXCSRL14), offset 0x1E6	1077
Register 209: USB Receive Control and Status Endpoint 15 Low (USBRXCSRL15), offset 0x1F6	1077
Register 210: USB Receive Control and Status Endpoint 1 High (USBRXCSRH1), offset 0x117	1082
Register 211: USB Receive Control and Status Endpoint 2 High (USBRXCSRH2), offset 0x127	1082
Register 212: USB Receive Control and Status Endpoint 3 High (USBRXCSRH3), offset 0x137	1082
Register 213: USB Receive Control and Status Endpoint 4 High (USBRXCSRH4), offset 0x147	1082
Register 214: USB Receive Control and Status Endpoint 5 High (USBRXCSRH5), offset 0x157	1082
Register 215: USB Receive Control and Status Endpoint 6 High (USBRXCSRH6), offset 0x167	
Register 216: USB Receive Control and Status Endpoint 7 High (USBRXCSRH7), offset 0x177	
Register 217: USB Receive Control and Status Endpoint 8 High (USBRXCSRH8), offset 0x187	
Register 218: USB Receive Control and Status Endpoint 9 High (USBRXCSRH9), offset 0x197	
Register 219: USB Receive Control and Status Endpoint 10 High (USBRXCSRH10), offset 0x1A7	
Register 220: USB Receive Control and Status Endpoint 11 High (USBRXCSRH11), offset 0x1B7	
Register 221: USB Receive Control and Status Endpoint 12 High (USBRXCSRH12), offset 0x1C7	
Register 222: USB Receive Control and Status Endpoint 13 High (USBRXCSRH13), offset 0x1D7	
Register 223: USB Receive Control and Status Endpoint 14 High (USBRXCSRH14), offset 0x1E7	
Register 224: USB Receive Control and Status Endpoint 15 High (USBRXCSRH15), offset 0x1F7	
Register 225: USB Receive Byte Count Endpoint 1 (USBRXCOUNT1), offset 0x118	
Register 226: USB Receive Byte Count Endpoint 2 (USBRXCOUNT2), offset 0x128	
Register 227: USB Receive Byte Count Endpoint 3 (USBRXCOUNT3), offset 0x138	
Register 228: USB Receive Byte Count Endpoint 4 (USBRXCOUNT4), offset 0x148	
Register 229: USB Receive Byte Count Endpoint 5 (USBRXCOUNT5), offset 0x158	
Register 230: USB Receive Byte Count Endpoint 6 (USBRXCOUNT6), offset 0x168	
Register 231: USB Receive Byte Count Endpoint 7 (USBRXCOUNT7), offset 0x178	
Register 232: USB Receive Byte Count Endpoint 8 (USBRXCOUNT8), offset 0x188	
Register 233: USB Receive Byte Count Endpoint 9 (USBRXCOUNT9), offset 0x198	
Register 234: USB Receive Byte Count Endpoint 10 (USBRXCOUNT10), offset 0x1A8	
Register 235: USB Receive Byte Count Endpoint 11 (USBRXCOUNT11), offset 0x1B8	
Register 236: USB Receive Byte Count Endpoint 12 (USBRXCOUNT12), offset 0x1C8	
Register 237: USB Receive Byte Count Endpoint 13 (USBRXCOUNT13), offset 0x1D8	
Register 238: USB Receive Byte Count Endpoint 14 (USBRXCOUNT14), offset 0x1E8	
Register 239: USB Receive Byte Count Endpoint 15 (USBRXCOUNT15), offset 0x1F8	
Register 240: USB Host Transmit Configure Type Endpoint 1 (USBTXTYPE1), offset 0x11A	
Register 241: USB Host Transmit Configure Type Endpoint 2 (USBTXTYPE2), offset 0x12A	
Register 242: USB Host Transmit Configure Type Endpoint 3 (USBTXTYPE3), offset 0x13A	
Register 243: USB Host Transmit Configure Type Endpoint 4 (USBTXTYPE4), offset 0x14A	
Register 244: USB Host Transmit Configure Type Endpoint 5 (USBTXTYPE5), offset 0x15A	
Register 245: USB Host Transmit Configure Type Endpoint 6 (USBTXTYPE6), offset 0x16A	
Register 246: USB Host Transmit Configure Type Endpoint 7 (USBTXTYPE7), offset 0x17A	
Register 247: USB Host Transmit Configure Type Endpoint 8 (USBTXTYPE8), offset 0x18A	
Register 248: USB Host Transmit Configure Type Endpoint 9 (USBTXTYPE9), offset 0x19A	
Register 249: USB Host Transmit Configure Type Endpoint 10 (USBTXTYPE10), offset 0x1AA	
Register 250: USB Host Transmit Configure Type Endpoint 11 (USBTXTYPE11), offset 0x1BA	
Register 251: USB Host Transmit Configure Type Endpoint 12 (USBTXTYPE12), offset 0x1CA	
Register 252: USB Host Transmit Configure Type Endpoint 13 (USBTXTYPE13), offset 0x1DA	
Register 253: USB Host Transmit Configure Type Endpoint 14 (USBTXTYPE14), offset 0x1EA	
Register 254: USB Host Transmit Configure Type Endpoint 15 (USBTXTYPE15), offset 0x1EA	

Register 255:	USB Host Transmit Interval Endpoint 1 (USBTXINTERVAL1), offset 0x11B	1091
Register 256:	USB Host Transmit Interval Endpoint 2 (USBTXINTERVAL2), offset 0x12B	1091
Register 257:	USB Host Transmit Interval Endpoint 3 (USBTXINTERVAL3), offset 0x13B	1091
Register 258:	USB Host Transmit Interval Endpoint 4 (USBTXINTERVAL4), offset 0x14B	1091
Register 259:	USB Host Transmit Interval Endpoint 5 (USBTXINTERVAL5), offset 0x15B	1091
Register 260:	USB Host Transmit Interval Endpoint 6 (USBTXINTERVAL6), offset 0x16B	1091
Register 261:	USB Host Transmit Interval Endpoint 7 (USBTXINTERVAL7), offset 0x17B	1091
Register 262:	USB Host Transmit Interval Endpoint 8 (USBTXINTERVAL8), offset 0x18B	1091
Register 263:	USB Host Transmit Interval Endpoint 9 (USBTXINTERVAL9), offset 0x19B	1091
Register 264:	USB Host Transmit Interval Endpoint 10 (USBTXINTERVAL10), offset 0x1AB	1091
Register 265:	USB Host Transmit Interval Endpoint 11 (USBTXINTERVAL11), offset 0x1BB	1091
Register 266:	USB Host Transmit Interval Endpoint 12 (USBTXINTERVAL12), offset 0x1CB	1091
Register 267:	USB Host Transmit Interval Endpoint 13 (USBTXINTERVAL13), offset 0x1DB	1091
Register 268:	USB Host Transmit Interval Endpoint 14 (USBTXINTERVAL14), offset 0x1EB	1091
Register 269:	USB Host Transmit Interval Endpoint 15 (USBTXINTERVAL15), offset 0x1FB	1091
Register 270:	USB Host Configure Receive Type Endpoint 1 (USBRXTYPE1), offset 0x11C	1093
Register 271:	USB Host Configure Receive Type Endpoint 2 (USBRXTYPE2), offset 0x12C	1093
Register 272:	USB Host Configure Receive Type Endpoint 3 (USBRXTYPE3), offset 0x13C	1093
Register 273:	USB Host Configure Receive Type Endpoint 4 (USBRXTYPE4), offset 0x14C	1093
Register 274:	USB Host Configure Receive Type Endpoint 5 (USBRXTYPE5), offset 0x15C	1093
Register 275:	USB Host Configure Receive Type Endpoint 6 (USBRXTYPE6), offset 0x16C	1093
Register 276:	USB Host Configure Receive Type Endpoint 7 (USBRXTYPE7), offset 0x17C	1093
Register 277:	USB Host Configure Receive Type Endpoint 8 (USBRXTYPE8), offset 0x18C	1093
Register 278:	USB Host Configure Receive Type Endpoint 9 (USBRXTYPE9), offset 0x19C	1093
Register 279:	USB Host Configure Receive Type Endpoint 10 (USBRXTYPE10), offset 0x1AC	1093
Register 280:	USB Host Configure Receive Type Endpoint 11 (USBRXTYPE11), offset 0x1BC	1093
Register 281:	USB Host Configure Receive Type Endpoint 12 (USBRXTYPE12), offset 0x1CC	1093
Register 282:	USB Host Configure Receive Type Endpoint 13 (USBRXTYPE13), offset 0x1DC	1093
Register 283:	USB Host Configure Receive Type Endpoint 14 (USBRXTYPE14), offset 0x1EC	1093
Register 284:	USB Host Configure Receive Type Endpoint 15 (USBRXTYPE15), offset 0x1FC	1093
Register 285:	USB Host Receive Polling Interval Endpoint 1 (USBRXINTERVAL1), offset 0x11D	1095
Register 286:	USB Host Receive Polling Interval Endpoint 2 (USBRXINTERVAL2), offset 0x12D	1095
Register 287:	USB Host Receive Polling Interval Endpoint 3 (USBRXINTERVAL3), offset 0x13D	1095
-	USB Host Receive Polling Interval Endpoint 4 (USBRXINTERVAL4), offset 0x14D	
Register 289:	USB Host Receive Polling Interval Endpoint 5 (USBRXINTERVAL5), offset 0x15D	1095
Register 290:	USB Host Receive Polling Interval Endpoint 6 (USBRXINTERVAL6), offset 0x16D	1095
•	USB Host Receive Polling Interval Endpoint 7 (USBRXINTERVAL7), offset 0x17D	
•	USB Host Receive Polling Interval Endpoint 8 (USBRXINTERVAL8), offset 0x18D	
Register 293:	USB Host Receive Polling Interval Endpoint 9 (USBRXINTERVAL9), offset 0x19D	1095
Register 294:	USB Host Receive Polling Interval Endpoint 10 (USBRXINTERVAL10), offset 0x1AD	1095
Register 295:	USB Host Receive Polling Interval Endpoint 11 (USBRXINTERVAL11), offset 0x1BD	1095
Register 296:	USB Host Receive Polling Interval Endpoint 12 (USBRXINTERVAL12), offset 0x1CD	1095
Register 297:	USB Host Receive Polling Interval Endpoint 13 (USBRXINTERVAL13), offset 0x1DD	1095
Register 298:	USB Host Receive Polling Interval Endpoint 14 (USBRXINTERVAL14), offset 0x1ED	1095
Register 299:	USB Host Receive Polling Interval Endpoint 15 (USBRXINTERVAL15), offset 0x1FD	1095
Register 300:	USB Request Packet Count in Block Transfer Endpoint 1 (USBRQPKTCOUNT1), offset	
	0v304	1007

Register 301:	USB Request Packet Count in Block Transfer Endpoint 2 (USBRQPKTCOUNT2), offset 0x308	1097
Register 302:	USB Request Packet Count in Block Transfer Endpoint 3 (USBRQPKTCOUNT3), offset	1097
Register 303:	USB Request Packet Count in Block Transfer Endpoint 4 (USBRQPKTCOUNT4), offset	1097
Register 304:	USB Request Packet Count in Block Transfer Endpoint 5 (USBRQPKTCOUNT5), offset	1097
Register 305:	USB Request Packet Count in Block Transfer Endpoint 6 (USBRQPKTCOUNT6), offset	1097
Register 306:	USB Request Packet Count in Block Transfer Endpoint 7 (USBRQPKTCOUNT7), offset	1097
Register 307:	USB Request Packet Count in Block Transfer Endpoint 8 (USBRQPKTCOUNT8), offset 0x320	
Register 308:	USB Request Packet Count in Block Transfer Endpoint 9 (USBRQPKTCOUNT9), offset	1097
Register 309:	USB Request Packet Count in Block Transfer Endpoint 10 (USBRQPKTCOUNT10), offset 0x328	
Register 310:	USB Request Packet Count in Block Transfer Endpoint 11 (USBRQPKTCOUNT11), offset 0x32C	
Register 311:	USB Request Packet Count in Block Transfer Endpoint 12 (USBRQPKTCOUNT12), offset 0x330	
Register 312:	USB Request Packet Count in Block Transfer Endpoint 13 (USBRQPKTCOUNT13), offset 0x334	
Register 313:	USB Request Packet Count in Block Transfer Endpoint 14 (USBRQPKTCOUNT14), offset 0x338	
Register 314:	USB Request Packet Count in Block Transfer Endpoint 15 (USBRQPKTCOUNT15), offset 0x33C	
Register 315:	USB Receive Double Packet Buffer Disable (USBRXDPKTBUFDIS), offset 0x340	
-	USB Transmit Double Packet Buffer Disable (USBTXDPKTBUFDIS), offset 0x342	
•	USB External Power Control (USBEPC), offset 0x400	
	USB External Power Control Raw Interrupt Status (USBEPCRIS), offset 0x404	
	USB External Power Control Interrupt Mask (USBEPCIM), offset 0x408	
•	USB External Power Control Interrupt Status and Clear (USBEPCISC), offset 0x40C	
	USB Device RESUME Raw Interrupt Status (USBDRRIS), offset 0x410	
-	· · · · · · · · · · · · · · · · · · ·	1110
-	USB Device RESUME Interrupt Status and Clear (USBDRISC), offset 0x418	1111
•	USB General-Purpose Control and Status (USBGPCS), offset 0x41C	
	USB VBUS Droop Control (USBVDC), offset 0x430	
-	USB VBUS Droop Control Raw Interrupt Status (USBVDCRIS), offset 0x434	
•	USB VBUS Droop Control Interrupt Mask (USBVDCIM), offset 0x438	
	USB VBUS Droop Control Interrupt Status and Clear (USBVDCISC), offset 0x43C	
-	USB ID Valid Detect Raw Interrupt Status (USBIDVRIS), offset 0x444	
-	USB ID Valid Detect Interrupt Mask (USBIDVIM), offset 0x448	
-	USB ID Valid Detect Interrupt Status and Clear (USBIDVISC), offset 0x44C	
-	USB DMA Select (USBDMASEL), offset 0x450	
•	nparators	
Register 1:	Analog Comparator Masked Interrupt Status (ACMIS), offset 0x000	
Register 1:	Analog Comparator Raw Interrupt Status (ACRIS), offset 0x000	
reusiel Z.	Anaiog Comparator Raw Interrupt Status (ACRIS), UIISEL UXUU4	1136

Register 3:	Analog Comparator Interrupt Enable (ACINTEN), offset 0x008	1131
Register 4:	Analog Comparator Reference Voltage Control (ACREFCTL), offset 0x010	1132
Register 5:	Analog Comparator Status 0 (ACSTAT0), offset 0x020	1133
Register 6:	Analog Comparator Status 1 (ACSTAT1), offset 0x040	1133
Register 7:	Analog Comparator Status 2 (ACSTAT2), offset 0x060	1133
Register 8:	Analog Comparator Control 0 (ACCTL0), offset 0x024	1134
Register 9:	Analog Comparator Control 1 (ACCTL1), offset 0x044	1134
Register 10:	Analog Comparator Control 2 (ACCTL2), offset 0x064	1134
Pulse Width	n Modulator (PWM)	1136
Register 1:	PWM Master Control (PWMCTL), offset 0x000	
Register 2:	PWM Time Base Sync (PWMSYNC), offset 0x004	
Register 3:	PWM Output Enable (PWMENABLE), offset 0x008	
Register 4:	PWM Output Inversion (PWMINVERT), offset 0x00C	
Register 5:	PWM Output Fault (PWMFAULT), offset 0x010	
Register 6:	PWM Interrupt Enable (PWMINTEN), offset 0x014	
Register 7:	PWM Raw Interrupt Status (PWMRIS), offset 0x018	
Register 8:	PWM Interrupt Status and Clear (PWMISC), offset 0x01C	
Register 9:	PWM Status (PWMSTATUS), offset 0x020	
Register 10:	PWM Fault Condition Value (PWMFAULTVAL), offset 0x024	
Register 11:	PWM Enable Update (PWMENUPD), offset 0x028	
Register 12:	PWM0 Control (PWM0CTL), offset 0x040	
Register 13:	PWM1 Control (PWM1CTL), offset 0x080	
Register 14:	PWM2 Control (PWM2CTL), offset 0x0C0	
Register 15:	PWM3 Control (PWM3CTL), offset 0x100	
Register 16:	PWM0 Interrupt and Trigger Enable (PWM0INTEN), offset 0x044	
Register 17:	PWM1 Interrupt and Trigger Enable (PWM1INTEN), offset 0x084	
Register 18:	PWM2 Interrupt and Trigger Enable (PWM2INTEN), offset 0x0C4	
Register 19:	PWM3 Interrupt and Trigger Enable (PWM3INTEN), offset 0x104	
Register 20:	PWM0 Raw Interrupt Status (PWM0RIS), offset 0x048	
Register 21:	PWM1 Raw Interrupt Status (PWM1RIS), offset 0x088	1184
Register 22:	PWM2 Raw Interrupt Status (PWM2RIS), offset 0x0C8	1184
Register 23:	PWM3 Raw Interrupt Status (PWM3RIS), offset 0x108	1184
Register 24:	PWM0 Interrupt Status and Clear (PWM0ISC), offset 0x04C	1186
Register 25:	PWM1 Interrupt Status and Clear (PWM1ISC), offset 0x08C	1186
Register 26:	PWM2 Interrupt Status and Clear (PWM2ISC), offset 0x0CC	1186
Register 27:	PWM3 Interrupt Status and Clear (PWM3ISC), offset 0x10C	1186
Register 28:	PWM0 Load (PWM0LOAD), offset 0x050	1188
Register 29:	PWM1 Load (PWM1LOAD), offset 0x090	1188
Register 30:	PWM2 Load (PWM2LOAD), offset 0x0D0	1188
Register 31:	PWM3 Load (PWM3LOAD), offset 0x110	1188
Register 32:	PWM0 Counter (PWM0COUNT), offset 0x054	
Register 33:	PWM1 Counter (PWM1COUNT), offset 0x094	1189
Register 34:	PWM2 Counter (PWM2COUNT), offset 0x0D4	1189
Register 35:	PWM3 Counter (PWM3COUNT), offset 0x114	1189
Register 36:	PWM0 Compare A (PWM0CMPA), offset 0x058	1190
Register 37:	PWM1 Compare A (PWM1CMPA), offset 0x098	1190
Register 38:	PWM2 Compare A (PWM2CMPA), offset 0x0D8	
Register 39:	PWM3 Compare A (PWM3CMPA), offset 0x118	

PWM0 Compare B (PWM0CMPB), offset 0x05C	1191
PWM1 Compare B (PWM1CMPB), offset 0x09C	1191
PWM2 Compare B (PWM2CMPB), offset 0x0DC	1191
PWM3 Compare B (PWM3CMPB), offset 0x11C	1191
· · · · · · · · · · · · · · · · · · ·	
PWM2 Generator A Control (PWM2GENA), offset 0x0E0	1192
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
· · · · · · · · · · · · · · · · · · ·	
PWM1 Fault Source 1 (PWM1FLTSRC1), offset 0x0B8	
· · · · · · · · · · · · · · · · · · ·	
PWM3 Fault Source 1 (PWM3FLTSRC1), offset 0x138	1203
PWM0 Minimum Fault Period (PWM0MINFLTPER), offset 0x07C	1206
PWM1 Minimum Fault Period (PWM1MINFLTPER), offset 0x0BC	
PWM2 Minimum Fault Period (PWM2MINFLTPER), offset 0x0FC	1206
PWM3 Minimum Fault Period (PWM3MINFLTPER), offset 0x13C	
PWM0 Fault Pin Logic Sense (PWM0FLTSEN), offset 0x800	1207
PWM1 Fault Pin Logic Sense (PWM1FLTSEN), offset 0x880	1207
· · · · · · · · · · · · · · · · · · ·	
PWM1 Fault Status 0 (PWM1FLTSTAT0), offset 0x884	
PWM2 Fault Status 0 (PWM2FLTSTAT0), offset 0x904	1208
PWM3 Fault Status 0 (PWM3FLTSTAT0), offset 0x984	
PWM0 Fault Status 1 (PWM0FLTSTAT1), offset 0x808	
PWM1 Fault Status 1 (PWM1FLTSTAT1), offset 0x888	
PWM2 Fault Status 1 (PWM2FLTSTAT1), offset 0x908	
PWM3 Fault Status 1 (PWM3FLTSTAT1), offset 0x988	
	PWM1 Compare B (PWM1CMPB), offset 0x09C PWM2 Compare B (PWM3CMPB), offset 0x01C PWM3 Compare B (PWM3CMPB), offset 0x01C PWM3 Compare B (PWM3CMPB), offset 0x01C PWM0 Generator A Control (PWM0GENA), offset 0x060 PWM1 Generator A Control (PWM1GENA), offset 0x0E0 PWM3 Generator A Control (PWM3GENA), offset 0x0E0 PWM3 Generator B Control (PWM3GENA), offset 0x0E0 PWM3 Generator B Control (PWM3GENB), offset 0x064 PWM1 Generator B Control (PWM3GENB), offset 0x0A4 PWM2 Generator B Control (PWM3GENB), offset 0x0A4 PWM3 Generator B Control (PWM3GENB), offset 0x0A4 PWM3 Generator B Control (PWM3GENB), offset 0x0A4 PWM3 Generator B Control (PWM3GENB), offset 0x0A4 PWM0 Dead-Band Control (PWM1DBCTL), offset 0x068 PWM1 Dead-Band Control (PWM1DBCTL), offset 0x0A8 PWM2 Dead-Band Control (PWM2DBCTL), offset 0x0E8 PWM3 Dead-Band Rising-Edge Delay (PWM0DBRISE), offset 0x0AC PWM1 Dead-Band Rising-Edge Delay (PWM1DBRISE), offset 0x0AC PWM2 Dead-Band Rising-Edge Delay (PWM2DBRISE), offset 0x0AC PWM3 Dead-Band Falling-Edge-Delay (PWM3DBRISE), offset 0x0AC PWM3 Dead-Band Falling-Edge-Delay (PWM3DBRISE), offset 0x0CC PWM3 Dead-Band Falling-Edge-Delay (PWM3DBRALL), offset 0x0B0 PWM2 Dead-Band Falling-Edge-Delay (PWM3DBFALL), offset 0x0B0 PWM3 Fault Source 0 (PWM5PLTSRC0), offset 0x0F4 PWM3 Fault Source 1 (PWM5PLTSRC0), offset 0x0F4 PWM3 Fault Source 1 (PWM5PLTSRC1), offset 0x0B4 PWM4 Fault Source 1 (PWM5PLTSRC1), offset 0x0B4 PWM4 Fault Source 1 (PWM5PLTSRC1), offset 0x0B8 PWM3 Fault Source 1 (PWM5PLTSRC1), offset 0x0B8 PWM3 Fault Source 1 (PWM5PLTSRC1), offset 0x0B8 PWM4 Fault Source 1 (PWM5PLTSRC1), offset 0x0B8 PWM5 Fault Fin Logic Sense (PWM5PLTSRC1), offset 0x980 PWM6 Fault Fin Logic Sense (PWM5PLTSRN), offset 0x980 PWM6 Fault Fin Logic Sense (PWM5PLTSRN), offset 0x980 PWM7 Fault Status 0 (PWM

Quadrature	Encoder Interface (QEI)	1213
Register 1:	QEI Control (QEICTL), offset 0x000	. 1220
Register 2:	QEI Status (QEISTAT), offset 0x004	. 1223
Register 3:	QEI Position (QEIPOS), offset 0x008	. 1224
Register 4:	QEI Maximum Position (QEIMAXPOS), offset 0x00C	. 1225
Register 5:	QEI Timer Load (QEILOAD), offset 0x010	. 1226
Register 6:	QEI Timer (QEITIME), offset 0x014	. 1227
Register 7:	QEI Velocity Counter (QEICOUNT), offset 0x018	. 1228
Register 8:	QEI Velocity (QEISPEED), offset 0x01C	. 1229
Register 9:	QEI Interrupt Enable (QEIINTEN), offset 0x020	. 1230
Register 10:	QEI Raw Interrupt Status (QEIRIS), offset 0x024	. 1232
Register 11:	QEI Interrupt Status and Clear (QEIISC), offset 0x028	. 1234

# **Revision History**

The revision history table notes changes made between the indicated revisions of the LM3S9D96 data sheet.

**Table 1. Revision History** 

Date	Revision	Description
October 2012	13440.2549	Marked LM3S9D96 device as not recommended for new designs (NRND). Device is in production to support existing customers, but TI does not recommend using this part in a new design.
		■ In the uDMA chapter, in the "µDMA Channel Assignments" and "Request Type Support" tables, corrected to show uDMA support for burst requests from the general-purpose timer, not single requests.
		■ In the Watchdog Timers chapter, added information on servicing the watchdog timer to the Initialization and Configuration section.
		■ In the General-Purpose Timers chapter, added note to the <b>GPTMTnV</b> registers that in 16-bit mode, only the lower 16-bits of the register can be written with a new value. Writes to the prescaler bits have no effect.
		■ Corrected reset for the UART Raw Interrupt Status (UARTRIS) register.
		■ In the USB chapter, clarified that the USB PHY has internal termination resistors, and thus there is no need for external resistors.
		■ In the Electrical Characteristics chapter, added clarifying footnote to the GPIO Module Characteristics table.
		Additional minor data sheet clarifications and corrections.
January 2012	11425	■ In System Control chapter:
		Clarified that an external LDO cannot be used.
		Clarified system clock requirements when the ADC module is in operation.
		<ul> <li>Added important note to write the RCC register before the RCC2 register.</li> </ul>
		■ In Internal Memory chapter, clarified programming and use of the non-volatile registers.
		■ In GPIO chapter, corrected "GPIO Pins With Non-Zero Reset Values" table and added note that if the same signal is assigned to two different GPIO port pins, the signal is assigned to the port with the lowest letter.
		■ In EPI chapter:
		Clarified table "Capabilities of Host Bus 8 and Host Bus 16 Modes".
		<ul> <li>Corrected bit and register resets for FREQ (Frequency Range) in EPI SDRAM Configuration (EPISDRAMCFG) register.</li> </ul>
		<ul> <li>Corrected bit and register resets for MAXWAIT (Maximum Wait) in EPI Host-Bus 8 Configuration (EPIHB8CFG) and EPI Host-Bus 16 Configuration (EPIHB16CFG) registers. Also clarified bit descriptions in these registers.</li> </ul>
		<ul> <li>Corrected bit definitions for the EPSZ and ERSZ bits in the EPI Address Map (EPIADDRMAP) register.</li> </ul>
		Corrected size of COUNT bit field in EDI Dood EIEO Count (EDIDEIEOCNIT) register
		<ul> <li>Corrected size of COUNT bit field in EPI Read FIFO Count (EPIRFIFOCNT) register.</li> </ul>

Table 1. Revision History (continued)

Data	Povision	Description
Date	Revision	■ In ADC chapter, added "ADC Input Equivalency Diagram".
		In UART chapter, clarified interrupt behavior.
		In SSI chapter, corrected SSICIk in the figure "Synchronous Serial Frame Format (Single Transfer)" and clarified behavior of transmit bits in interrupt registers.
		■ In I <sup>2</sup> C chapter, corrected bit and register reset values for IDLE bit in I <sup>2</sup> C Master Control/Status (I2CMCS) register.
		■ In USB chapter:
		<ul> <li>Clarified that when the USB module is in operation, MOSC must be provided with a clock source, and the system clock must be at least 30 MHz.</li> </ul>
		<ul> <li>Removed MULTTRAN bit from USB Transmit Hub Address Endpoint n (USBTXHUBADDRn) and USB Receive Hub Address Endpoint n (USBRXHUBADDRn) registers.</li> </ul>
		Corrected description for the USB Device RESUME Interrupt Mask (USBDRIM) register.
		■ In Analog Comparators chapter, clarified internal reference programming.
		■ In PWM chapter, clarified <b>PWM Interrupt Enable (PWMINTEN)</b> register description.
		■ In Signal Tables chapter, clarified VDDC and LDO pin descriptions.
		■ In Electrical Characteristics chapter:
		<ul> <li>In Maximum Ratings table, deleted parameter "Input voltage for a GPIO configured as an analog input".</li> </ul>
		<ul> <li>In Recommended DC Operating Conditions table, corrected values for I<sub>OH</sub> parameter.</li> </ul>
		<ul> <li>In JTAG Characteristics, table, corrected values for parameters "TCK clock Low time" and "TCK clock High time".</li> </ul>
		<ul> <li>In LDO Regulator Characteristics table, added clarifying footnote to C<sub>LDO</sub> parameter.</li> </ul>
		<ul> <li>In System Clock Characteristics with ADC Operation table, added clarifying footnote to F<sub>sysadc</sub> parameter.</li> </ul>
		Added "System Clock Characteristics with USB Operation" table.
		<ul> <li>In Sleep Modes AC Characteristics table, split parameter "Time to wake from interrupt" into sleep mode and deep-sleep mode parameters.</li> </ul>
		In SSI Characteristics table, corrected value for parameter "SSICIk cycle time".
		<ul> <li>In Analog Comparator Characteristics table, added parameter "Input voltage range" and corrected values for parameter "Input common mode voltage range".</li> </ul>
		<ul> <li>In Analog Comparator Voltage Reference Characteristics table, corrected values for absolute accuracy parameters.</li> </ul>
		Deleted table "USB Controller DC Characteristics".
		In Nominal Power Consumption table, added parameter for sleep mode.
		<ul> <li>In Maximum Current Consumption section, changed reference value for MOSC and temperature in tables that follow.</li> </ul>
		Deleted table "External VDDC Source Current Specifications".
		Additional minor data sheet clarifications and corrections.

# Table 1. Revision History (continued)

Date	Revision	Description
July 2011	9970	■ Corrected "Reset Sources" table.
		■ Added Important Note that RCC register must be written before RCC2 register.
		■ Added a note that all GPIO signals are 5-V tolerant when configured as inputs except for PB0 and PB1, which are limited to 3.6 V.
		■ Corrected LIN Mode bit names in <b>UART Interrupt Clear (UARTICR)</b> register.
		■ Corrected pin number for RST and added missing pin number for ERBIAS in table "Connections for Unused Signals" (other pin tables were correct).
		■ In the "Operating Characteristics" chapter:
		In the "Thermal Characteristics" table, the Thermal resistance value was changed.
		$-$ In the "ESD Absolute Maximum Ratings" table, the $V_{ESDCDM}$ parameter was changed and the $V_{ESDMM}$ parameter was deleted.
		■ The "Electrical Characteristics" chapter was reorganized by module. In addition, some of the Recommended DC Operating Conditions, LDO Regulator, Clock, GPIO, EPI, ADC, and SSI characteristics were finalized.
		■ Additional minor data sheet clarifications and corrections.
March 2011	9538	Started tracking revision history.

# **About This Document**

This data sheet provides reference information for the LM3S9D96 microcontroller, describing the functional blocks of the system-on-chip (SoC) device designed around the ARM® Cortex™-M3 core.

## **Audience**

This manual is intended for system software developers, hardware designers, and application developers.

# **About This Manual**

This document is organized into sections that correspond to each major feature.

## **Related Documents**

The following related documents are available on the Stellaris® web site at www.ti.com/stellaris:

- Stellaris® Errata
- ARM® Cortex™-M3 Errata
- Cortex™-M3/M4 Instruction Set Technical User's Manual
- SafeRTOS User's Manual
- Stellaris® Boot Loader User's Guide
- Stellaris® Graphics Library User's Guide
- Stellaris® Peripheral Driver Library User's Guide
- Stellaris® ROM User's Guide
- Stellaris® USB Library User's Guide

The following related documents are also referenced:

- ARM® Debug Interface V5 Architecture Specification
- ARM® Embedded Trace Macrocell Architecture Specification
- IEEE Standard 1149.1-Test Access Port and Boundary-Scan Architecture

This documentation list was current as of publication date. Please check the web site for additional documentation, including application notes and white papers.

# **Documentation Conventions**

This document uses the conventions shown in Table 2 on page 46.

**Table 2. Documentation Conventions** 

Notation	Meaning
General Register Nota	tion
REGISTER	APB registers are indicated in uppercase bold. For example, <b>PBORCTL</b> is the Power-On and Brown-Out Reset Control register. If a register name contains a lowercase n, it represents more than one register. For example, <b>SRCRn</b> represents any (or all) of the three Software Reset Control registers: <b>SRCR0</b> , <b>SRCR1</b> , and <b>SRCR2</b> .
bit	A single bit in a register.
bit field	Two or more consecutive and related bits.
offset 0xnnn	A hexadecimal increment to a register's address, relative to that module's base address as specified in Table 2-4 on page 90.
Register N	Registers are numbered consecutively throughout the document to aid in referencing them. The register number has no meaning to software.
reserved	Register bits marked <i>reserved</i> are reserved for future use. In most cases, reserved bits are set to 0; however, user software should not rely on the value of a reserved bit. To provide software compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
yy:xx	The range of register bits inclusive from xx to yy. For example, 31:15 means bits 15 through 31 in that register.
Register Bit/Field Types	This value in the register bit diagram indicates whether software running on the controller can change the value of the bit field.
RC	Software can read this field. The bit or field is cleared by hardware after reading the bit/field.
RO	Software can read this field. Always write the chip reset value.
R/W	Software can read or write this field.
R/WC	Software can read or write this field. Writing to it with any value clears the register.
R/W1C	Software can read or write this field. A write of a 0 to a W1C bit does not affect the bit value in the register. A write of a 1 clears the value of the bit in the register; the remaining bits remain unchanged.
	This register type is primarily used for clearing interrupt status bits where the read operation provides the interrupt status and the write of the read value clears only the interrupts being reported at the time the register was read.
R/W1S	Software can read or write a 1 to this field. A write of a 0 to a R/W1S bit does not affect the bit value in the register.
W1C	Software can write this field. A write of a 0 to a W1C bit does not affect the bit value in the register. A write of a 1 clears the value of the bit in the register; the remaining bits remain unchanged. A read of the register returns no meaningful data.
	This register is typically used to clear the corresponding bit in an interrupt register.
WO	Only a write by software is valid; a read of the register returns no meaningful data.
Register Bit/Field Reset Value	This value in the register bit diagram shows the bit/field value after any reset, unless noted.
0	Bit cleared to 0 on chip reset.
1	Bit set to 1 on chip reset.
-	Nondeterministic.
Pin/Signal Notation	
[]	Pin alternate function; a pin defaults to the signal without the brackets.
pin	Refers to the physical connection on the package.
signal	Refers to the electrical signal encoding of a pin.

# Table 2. Documentation Conventions (continued)

Notation	Meaning
assert a signal	Change the value of the signal from the logically False state to the logically True state. For active High signals, the asserted signal value is 1 (High); for active Low signals, the asserted signal value is 0 (Low). The active polarity (High or Low) is defined by the signal name (see SIGNAL and SIGNAL below).
deassert a signal	Change the value of the signal from the logically True state to the logically False state.
SIGNAL	Signal names are in uppercase and in the Courier font. An overbar on a signal name indicates that it is active Low. To assert SIGNAL is to drive it Low; to deassert SIGNAL is to drive it High.
SIGNAL	Signal names are in uppercase and in the Courier font. An active High signal has no overbar. To assert Signal is to drive it High; to deassert Signal is to drive it Low.
Numbers	
Х	An uppercase X indicates any of several values is allowed, where X can be any legal pattern. For example, a binary value of 0X00 can be either 0100 or 0000, a hex value of 0xX is 0x0 or 0x1, and so on.
0x	Hexadecimal numbers have a prefix of 0x. For example, 0x00FF is the hexadecimal number FF.
	All other numbers within register tables are assumed to be binary. Within conceptual information, binary numbers are indicated with a b suffix, for example, 1011b, and decimal numbers are written without a prefix or suffix.

# 1 Architectural Overview

Texas Instruments is the industry leader in bringing 32-bit capabilities and the full benefits of ARM<sup>®</sup> Cortex<sup>™</sup>-M-based microcontrollers to the broadest reach of the microcontroller market. For current users of 8- and 16-bit MCUs, Stellaris<sup>®</sup> with Cortex-M offers a direct path to the strongest ecosystem of development tools, software and knowledge in the industry. Designers who migrate to Stellaris benefit from great tools, small code footprint and outstanding performance. Even more important, designers can enter the ARM ecosystem with full confidence in a compatible roadmap from \$1 to 1 GHz. For users of current 32-bit MCUs, the Stellaris family offers the industry's first implementation of Cortex-M3 and the Thumb-2 instruction set. With blazingly-fast responsiveness, Thumb-2 technology combines both 16-bit and 32-bit instructions to deliver the best balance of code density and performance. Thumb-2 uses 26 percent less memory than pure 32-bit code to reduce system cost while delivering 25 percent better performance. The Texas Instruments Stellaris family of microcontrollers—the first ARM Cortex-M3 based controllers— brings high-performance 32-bit computing to cost-sensitive embedded microcontroller applications.

# 1.1 Overview

The Stellaris LM3S9D96 microcontroller combines complex integration and high performance with the following feature highlights:

- ARM Cortex-M3 Processor Core
- High Performance: 80-MHz operation; 100 DMIPS performance
- 512 KB single-cycle Flash memory
- 96 KB single-cycle SRAM
- Internal ROM loaded with StellarisWare<sup>®</sup> software
- External Peripheral Interface (EPI)
- Advanced Communication Interfaces: UART, SSI, I2C, I2S, CAN, Ethernet MAC and PHY, USB
- System Integration: general-purpose timers, watchdog timers, DMA, general-purpose I/Os
- Advanced motion control using PWMs, fault inputs, and quadrature encoder inputs
- Analog support: analog and digital comparators, Analog-to-Digital Converters (ADC), on-chip voltage regulator
- JTAG and ARM Serial Wire Debug (SWD)
- 100-pin LQFP package
- 108-ball BGA package
- Industrial (-40°C to 85°C) temperature range

Figure 1-1 on page 49 depicts the features on the Stellaris LM3S9D96 microcontroller. Note that there are two on-chip buses that connect the core to the peripherals. The Advanced Peripheral Bus (APB) bus is the legacy bus. The Advanced High-Performance Bus (AHB) bus provides better back-to-back access performance than the APB bus.




Figure 1-1. Stellaris LM3S9D96 Microcontroller High-Level Block Diagram

In addition, the LM3S9D96 microcontroller offers the advantages of ARM's widely available development tools, System-on-Chip (SoC) infrastructure IP applications, and a large user community. Additionally, the microcontroller uses ARM's Thumb®-compatible Thumb-2 instruction set to reduce memory requirements and, thereby, cost. Finally, the LM3S9D96 microcontroller is code-compatible to all members of the extensive Stellaris family; providing flexibility to fit precise needs.

Texas Instruments offers a complete solution to get to market quickly, with evaluation and development boards, white papers and application notes, an easy-to-use peripheral driver library, and a strong support, sales, and distributor network.

# 1.2 Target Applications

The Stellaris family is positioned for cost-conscious applications requiring significant control processing and connectivity capabilities such as:

- Gaming equipment
- Network appliances and switches
- Home and commercial site monitoring and control
- Electronic point-of-sale (POS) machines
- Motion control
- Medical instrumentation
- Remote connectivity and monitoring
- Test and measurement equipment
- Factory automation
- Fire and security
- Lighting control
- Transportation

# 1.3 Features

The LM3S9D96 microcontroller component features and general function are discussed in more detail in the following section.

## 1.3.1 ARM Cortex-M3 Processor Core

All members of the Stellaris product family, including the LM3S9D96 microcontroller, are designed around an ARM Cortex-M3 processor core. The ARM Cortex-M3 processor provides the core for a high-performance, low-cost platform that meets the needs of minimal memory implementation, reduced pin count, and low power consumption, while delivering outstanding computational performance and exceptional system response to interrupts.

#### 1.3.1.1 Processor Core (see page 71)

- 32-bit ARM Cortex-M3 architecture optimized for small-footprint embedded applications
- 80-MHz operation; 100 DMIPS performance
- Outstanding processing performance combined with fast interrupt handling
- Thumb-2 mixed 16-/32-bit instruction set delivers the high performance expected of a 32-bit ARM core in a compact memory size usually associated with 8- and 16-bit devices, typically in the range of a few kilobytes of memory for microcontroller-class applications
  - Single-cycle multiply instruction and hardware divide

- Atomic bit manipulation (bit-banding), delivering maximum memory utilization and streamlined peripheral control
- Unaligned data access, enabling data to be efficiently packed into memory
- Fast code execution permits slower processor clock or increases sleep mode time
- Harvard architecture characterized by separate buses for instruction and data
- Efficient processor core, system and memories
- Hardware division and fast digital-signal-processing orientated multiply accumulate
- Saturating arithmetic for signal processing
- Deterministic, high-performance interrupt handling for time-critical applications
- Memory protection unit (MPU) to provide a privileged mode for protected operating system functionality
- Enhanced system debug with extensive breakpoint and trace capabilities
- Serial Wire Debug and Serial Wire Trace reduce the number of pins required for debugging and tracing
- Migration from the ARM7 processor family for better performance and power efficiency
- Optimized for single-cycle Flash memory usage
- Ultra-low power consumption with integrated sleep modes

#### 1.3.1.2 System Timer (SysTick) (see page 114)

ARM Cortex-M3 includes an integrated system timer, SysTick. SysTick provides a simple, 24-bit, clear-on-write, decrementing, wrap-on-zero counter with a flexible control mechanism. The counter can be used in several different ways, for example:

- An RTOS tick timer that fires at a programmable rate (for example, 100 Hz) and invokes a SysTick routine
- A high-speed alarm timer using the system clock
- A variable rate alarm or signal timer—the duration is range-dependent on the reference clock used and the dynamic range of the counter
- A simple counter used to measure time to completion and time used
- An internal clock-source control based on missing/meeting durations.

## 1.3.1.3 Nested Vectored Interrupt Controller (NVIC) (see page 115)

The LM3S9D96 controller includes the ARM Nested Vectored Interrupt Controller (NVIC). The NVIC and Cortex-M3 prioritize and handle all exceptions in Handler Mode. The processor state is automatically stored to the stack on an exception and automatically restored from the stack at the end of the Interrupt Service Routine (ISR). The interrupt vector is fetched in parallel to the state saving, enabling efficient interrupt entry. The processor supports tail-chaining, meaning that

back-to-back interrupts can be performed without the overhead of state saving and restoration. Software can set eight priority levels on 7 exceptions (system handlers) and 53 interrupts.

- Deterministic, fast interrupt processing: always 12 cycles, or just 6 cycles with tail-chaining
- External non-maskable interrupt signal (NMI) available for immediate execution of NMI handler for safety critical applications
- Dynamically reprioritizable interrupts
- Exceptional interrupt handling via hardware implementation of required register manipulations

## 1.3.1.4 System Control Block (SCB) (see page 117)

The SCB provides system implementation information and system control, including configuration, control, and reporting of system exceptions.

## 1.3.1.5 Memory Protection Unit (MPU) (see page 117)

The MPU supports the standard ARM7 Protected Memory System Architecture (PMSA) model. The MPU provides full support for protection regions, overlapping protection regions, access permissions, and exporting memory attributes to the system.

# 1.3.2 On-Chip Memory

The LM3S9D96 microcontroller is integrated with the following set of on-chip memory and features:

- 96 KB single-cycle SRAM
- 512 KB single-cycle Flash memory up to 50 MHz; a prefetch buffer improves performance above
   50 MHz
- Internal ROM loaded with StellarisWare software:
  - Stellaris Peripheral Driver Library
  - Stellaris Boot Loader
  - SafeRTOS™ kernel
  - Advanced Encryption Standard (AES) cryptography tables
  - Cyclic Redundancy Check (CRC) error detection functionality

#### 1.3.2.1 SRAM (see page 301)

The LM3S9D96 microcontroller provides 96 KB of single-cycle on-chip SRAM. The internal SRAM of the Stellaris devices is located at offset 0x2000.0000 of the device memory map.

Because read-modify-write (RMW) operations are very time consuming, ARM has introduced *bit-banding* technology in the Cortex-M3 processor. With a bit-band-enabled processor, certain regions in the memory map (SRAM and peripheral space) can use address aliases to access individual bits in a single, atomic operation.

Data can be transferred to and from the SRAM using the Micro Direct Memory Access Controller (µDMA).

#### 1.3.2.2 Flash Memory (see page 303)

The LM3S9D96 microcontroller provides 512 KB of single-cycle on-chip Flash memory (above 50 MHz, the Flash memory can be accessed in a single cycle as long as the code is linear; branches incur a one-cycle stall). The Flash memory is organized as a set of 1-KB blocks that can be

individually erased. Erasing a block causes the entire contents of the block to be reset to all 1s. These blocks are paired into a set of 2-KB blocks that can be individually protected. The blocks can be marked as read-only or execute-only, providing different levels of code protection. Read-only blocks cannot be erased or programmed, protecting the contents of those blocks from being modified. Execute-only blocks cannot be erased or programmed, and can only be read by the controller instruction fetch mechanism, protecting the contents of those blocks from being read by either the controller or by a debugger.

## 1.3.2.3 ROM (see page 301)

The LM3S9D96 ROM is preprogrammed with the following software and programs:

- Stellaris Peripheral Driver Library
- Stellaris Boot Loader
- SafeRTOS<sup>™</sup> preemptive real-time kernel
- Advanced Encryption Standard (AES) cryptography tables
- Cyclic Redundancy Check (CRC) error-detection functionality

The Stellaris Peripheral Driver Library is a royalty-free software library for controlling on-chip peripherals with a boot-loader capability. The library performs both peripheral initialization and control functions, with a choice of polled or interrupt-driven peripheral support. In addition, the library is designed to take full advantage of the stellar interrupt performance of the ARM Cortex-M3 core. No special pragmas or custom assembly code prologue/epilogue functions are required. For applications that require in-field programmability, the royalty-free Stellaris Boot Loader can act as an application loader and support in-field firmware updates.

Also included in the ROM is SafeRTOS™ preemptive real-time kernel. This small-footprint kernel is designed for easy use in applications where a specified level of dependability is required. SafeRTOS™ allows you to bring design-assured products to market rapidly with reduced risk and cost.

The Advanced Encryption Standard (AES) is a publicly defined encryption standard used by the U.S. Government. AES is a strong encryption method with reasonable performance and size. In addition, it is fast in both hardware and software, is fairly easy to implement, and requires little memory. The Texas Instruments encryption package is available with full source code, and is based on lesser general public license (LGPL) source. An LGPL means that the code can be used within an application without any copyleft implications for the application (the code does not automatically become open source). Modifications to the package source, however, must be open source.

CRC (Cyclic Redundancy Check) is a technique to validate a span of data has the same contents as when previously checked. This technique can be used to validate correct receipt of messages (nothing lost or modified in transit), to validate data after decompression, to validate that Flash memory contents have not been changed, and for other cases where the data needs to be validated. A CRC is preferred over a simple checksum (e.g. XOR all bits) because it catches changes more readily.

# 1.3.3 External Peripheral Interface (see page 462)

The External Peripheral Interface (EPI) provides access to external devices using a parallel path. Unlike communications peripherals such as SSI, UART, and I<sup>2</sup>C, the EPI is designed to act like a bus to external peripherals and memory.

The EPI has the following features:

- 8/16/32-bit dedicated parallel bus for external peripherals and memory
- Memory interface supports contiguous memory access independent of data bus width, thus enabling code execution directly from SDRAM, SRAM and Flash memory
- Blocking and non-blocking reads
- Separates processor from timing details through use of an internal write FIFO
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Separate channels for read and write
  - Read channel request asserted by programmable levels on the internal non-blocking read FIFO (NBRFIFO)
  - Write channel request asserted by empty on the internal write FIFO (WFIFO)

The EPI supports three primary functional modes: Synchronous Dynamic Random Access Memory (SDRAM) mode, Traditional Host-Bus mode, and General-Purpose mode. The EPI module also provides custom GPIOs; however, unlike regular GPIOs, the EPI module uses a FIFO in the same way as a communication mechanism and is speed-controlled using clocking.

- Synchronous Dynamic Random Access Memory (SDRAM) mode
  - Supports x16 (single data rate) SDRAM at up to 50 MHz
  - Supports low-cost SDRAMs up to 64 MB (512 megabits)
  - Includes automatic refresh and access to all banks/rows
  - Includes a Sleep/Standby mode to keep contents active with minimal power draw
  - Multiplexed address/data interface for reduced pin count
- Host-Bus mode
  - Traditional x8 and x16 MCU bus interface capabilities
  - Similar device compatibility options as PIC, ATmega, 8051, and others
  - Access to SRAM, NOR Flash memory, and other devices, with up to 1 MB of addressing in unmultiplexed mode and 256 MB in multiplexed mode (512 MB in Host-Bus 16 mode with no byte selects)
  - Support of both muxed and de-muxed address and data
  - Access to a range of devices supporting the non-address FIFO x8 and x16 interface variant, with support for external FIFO (XFIFO) EMPTY and FULL signals
  - Speed controlled, with read and write data wait-state counters
  - Chip select modes include ALE, CSn, Dual CSn and ALE with dual CSn

- Manual chip-enable (or use extra address pins)
- General-Purpose mode
  - Wide parallel interfaces for fast communications with CPLDs and FPGAs
  - Data widths up to 32 bits
  - Data rates up to 150 MB/second
  - Optional "address" sizes from 4 bits to 20 bits
  - Optional clock output, read/write strobes, framing (with counter-based size), and clock-enable input
- General parallel GPIO
  - 1 to 32 bits, FIFOed with speed control
  - Useful for custom peripherals or for digital data acquisition and actuator controls

# 1.3.4 Serial Communications Peripherals

The LM3S9D96 controller supports both asynchronous and synchronous serial communications with:

- 10/100 Ethernet MAC and PHY with IEEE 1588 PTP hardware support
- Two CAN 2.0 A/B controllers
- USB 2.0 OTG/Host/Device
- Three UARTs with IrDA and ISO 7816 support (one UART with modem flow control and status)
- Two I<sup>2</sup>C modules
- Two Synchronous Serial Interface modules (SSI)
- Integrated Interchip Sound (I<sup>2</sup>S) module

The following sections provide more detail on each of these communications functions.

## 1.3.4.1 Ethernet Controller (see page 922)

Ethernet is a frame-based computer networking technology for local area networks (LANs). Ethernet has been standardized as IEEE 802.3. This specification defines a number of wiring and signaling standards for the physical layer, two means of network access at the Media Access Control (MAC)/Data Link Layer, and a common addressing format.

The Stellaris Ethernet Controller consists of a fully integrated media access controller (MAC) and network physical (PHY) interface and has the following features:

- Conforms to the IEEE 802.3-2002 specification
  - 10BASE-T/100BASE-TX IEEE-802.3 compliant. Requires only a dual 1:1 isolation transformer interface to the line

- 10BASE-T/100BASE-TX ENDEC, 100BASE-TX scrambler/descrambler
- Full-featured auto-negotiation
- Multiple operational modes
  - Full- and half-duplex 100 Mbps
  - Full- and half-duplex 10 Mbps
  - Power-saving and power-down modes
- Highly configurable
  - Programmable MAC address
  - LED activity selection
  - Promiscuous mode support
  - CRC error-rejection control
  - User-configurable interrupts
- Physical media manipulation
  - MDI/MDI-X cross-over support through software assist
  - Register-programmable transmit amplitude
  - Automatic polarity correction and 10BASE-T signal reception
- IEEE 1588 Precision Time Protocol: Provides highly accurate time stamps for individual packets
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Receive channel request asserted on packet receipt
  - Transmit channel request asserted on empty transmit FIFO

# 1.3.4.2 Controller Area Network (see page 871)

Controller Area Network (CAN) is a multicast shared serial-bus standard for connecting electronic control units (ECUs). CAN was specifically designed to be robust in electromagnetically noisy environments and can utilize a differential balanced line like RS-485 or twisted-pair wire. Originally created for automotive purposes, it is now used in many embedded control applications (for example, industrial or medical). Bit rates up to 1 Mbps are possible at network lengths below 40 meters. Decreased bit rates allow longer network distances (for example, 125 Kbps at 500m).

A transmitter sends a message to all CAN nodes (broadcasting). Each node decides on the basis of the identifier received whether it should process the message. The identifier also determines the priority that the message enjoys in competition for bus access. Each CAN message can transmit from 0 to 8 bytes of user information.

The LM3S9D96 microcontroller includes two CAN units with the following features:

- CAN protocol version 2.0 part A/B
- Bit rates up to 1 Mbps
- 32 message objects with individual identifier masks
- Maskable interrupt
- Disable Automatic Retransmission mode for Time-Triggered CAN (TTCAN) applications
- Programmable Loopback mode for self-test operation
- Programmable FIFO mode enables storage of multiple message objects
- Gluelessly attaches to an external CAN transceiver through the CANnTX and CANnRX signals

#### 1.3.4.3 USB (see page 983)

Universal Serial Bus (USB) is a serial bus standard designed to allow peripherals to be connected and disconnected using a standardized interface without rebooting the system.

The LM3S9D96 microcontroller supports three configurations in USB 2.0 full and low speed: USB Device, USB Host, and USB On-The-Go (negotiated on-the-go as host or device when connected to other USB-enabled systems).

The USB module has the following features:

- Complies with USB-IF certification standards
- USB 2.0 full-speed (12 Mbps) and low-speed (1.5 Mbps) operation with integrated PHY
- 4 transfer types: Control, Interrupt, Bulk, and Isochronous
- 32 endpoints
  - 1 dedicated control IN endpoint and 1 dedicated control OUT endpoint
  - 15 configurable IN endpoints and 15 configurable OUT endpoints
- 4 KB dedicated endpoint memory: one endpoint may be defined for double-buffered 1023-byte isochronous packet size
- VBUS droop and valid ID detection and interrupt
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive for up to three IN endpoints and three OUT endpoints
  - Channel requests asserted when FIFO contains required amount of data

# 1.3.4.4 UART (see page 690)

A Universal Asynchronous Receiver/Transmitter (UART) is an integrated circuit used for RS-232C serial communications, containing a transmitter (parallel-to-serial converter) and a receiver (serial-to-parallel converter), each clocked separately.

The LM3S9D96 microcontroller includes three fully programmable 16C550-type UARTs. Although the functionality is similar to a 16C550 UART, this UART design is not register compatible. The UART can generate individually masked interrupts from the Rx, Tx, modem flow control, modem status, and error conditions. The module generates a single combined interrupt when any of the interrupts are asserted and are unmasked.

The three UARTs have the following features:

- Programmable baud-rate generator allowing speeds up to 5 Mbps for regular speed (divide by 16) and 10 Mbps for high speed (divide by 8)
- Separate 16x8 transmit (TX) and receive (RX) FIFOs to reduce CPU interrupt service loading
- Programmable FIFO length, including 1-byte deep operation providing conventional double-buffered interface
- FIFO trigger levels of 1/8, 1/4, 1/2, 3/4, and 7/8
- Standard asynchronous communication bits for start, stop, and parity
- Line-break generation and detection
- Fully programmable serial interface characteristics
  - 5, 6, 7, or 8 data bits
  - Even, odd, stick, or no-parity bit generation/detection
  - 1 or 2 stop bit generation
- IrDA serial-IR (SIR) encoder/decoder providing
  - Programmable use of IrDA Serial Infrared (SIR) or UART input/output
  - Support of IrDA SIR encoder/decoder functions for data rates up to 115.2 Kbps half-duplex
  - Support of normal 3/16 and low-power (1.41-2.23 μs) bit durations
  - Programmable internal clock generator enabling division of reference clock by 1 to 256 for low-power mode bit duration
- Support for communication with ISO 7816 smart cards
- Full modem handshake support (on UART1)
- LIN protocol support
- Standard FIFO-level and End-of-Transmission interrupts
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Receive single request asserted when data is in the FIFO; burst request asserted at programmed FIFO level

 Transmit single request asserted when there is space in the FIFO; burst request asserted at programmed FIFO level

# 1.3.4.5 $I^2C$ (see page 796)

The Inter-Integrated Circuit ( $I^2C$ ) bus provides bi-directional data transfer through a two-wire design (a serial data line SDA and a serial clock line SCL). The  $I^2C$  bus interfaces to external  $I^2C$  devices such as serial memory (RAMs and ROMs), networking devices, LCDs, tone generators, and so on. The  $I^2C$  bus may also be used for system testing and diagnostic purposes in product development and manufacture.

Each device on the I<sup>2</sup>C bus can be designated as either a master or a slave. Each I<sup>2</sup>C module supports both sending and receiving data as either a master or a slave and can operate simultaneously as both a master and a slave. Both the I<sup>2</sup>C master and slave can generate interrupts.

The LM3S9D96 microcontroller includes two I<sup>2</sup>C modules with the following features:

- Devices on the I<sup>2</sup>C bus can be designated as either a master or a slave
  - Supports both transmitting and receiving data as either a master or a slave
  - Supports simultaneous master and slave operation
- Four I<sup>2</sup>C modes
  - Master transmit
  - Master receive
  - Slave transmit
  - Slave receive
- Two transmission speeds: Standard (100 Kbps) and Fast (400 Kbps)
- Master and slave interrupt generation
  - Master generates interrupts when a transmit or receive operation completes (or aborts due to an error)
  - Slave generates interrupts when data has been transferred or requested by a master or when a START or STOP condition is detected
- Master with arbitration and clock synchronization, multimaster support, and 7-bit addressing mode

#### 1.3.4.6 SSI (see page 754)

Synchronous Serial Interface (SSI) is a four-wire bi-directional communications interface that converts data between parallel and serial. The SSI module performs serial-to-parallel conversion on data received from a peripheral device, and parallel-to-serial conversion on data transmitted to a peripheral device. The SSI module can be configured as either a master or slave device. As a slave device, the SSI module can also be configured to disable its output, which allows a master device to be coupled with multiple slave devices. The TX and RX paths are buffered with separate internal FIFOs.

The SSI module also includes a programmable bit rate clock divider and prescaler to generate the output serial clock derived from the SSI module's input clock. Bit rates are generated based on the input clock and the maximum bit rate is determined by the connected peripheral.

The LM3S9D96 microcontroller includes two SSI modules with the following features:

- Programmable interface operation for Freescale SPI, MICROWIRE, or Texas Instruments synchronous serial interfaces
- Master or slave operation
- Programmable clock bit rate and prescaler
- Separate transmit and receive FIFOs, each 16 bits wide and 8 locations deep
- Programmable data frame size from 4 to 16 bits
- Internal loopback test mode for diagnostic/debug testing
- Standard FIFO-based interrupts and End-of-Transmission interrupt
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Separate channels for transmit and receive
  - Receive single request asserted when data is in the FIFO; burst request asserted when FIFO contains 4 entries
  - Transmit single request asserted when there is space in the FIFO; burst request asserted when FIFO contains 4 entries

# 1.3.4.7 Inter-Integrated Circuit Sound (I<sup>2</sup>S) Interface (see page 834)

The I<sup>2</sup>S interface is a configurable serial audio core that contains a transmit module and a receive module. The module is configurable for the I<sup>2</sup>S as well as Left-Justified and Right-Justified serial audio formats. Data can be in one of four modes: Stereo, Mono, Compact 16-bit Stereo and Compact 8-Bit Stereo.

The transmit and receive modules each have an 8-entry audio-sample FIFO. An audio sample can consist of a Left and Right Stereo sample, a Mono sample, or a Left and Right Compact Stereo sample. In Compact 16-Bit Stereo, each FIFO entry contains both the 16-bit left and 16-bit right samples, allowing efficient data transfers and requiring less memory space. In Compact 8-bit Stereo, each FIFO entry contains an 8-bit left and an 8-bit right sample, reducing memory requirements further.

Both the transmitter and receiver are capable of being a master or a slave.

The Stellaris I<sup>2</sup>S interface has the following features:

- Configurable audio format supporting I<sup>2</sup>S, Left-justification, and Right-justification
- Configurable sample size from 8 to 32 bits
- Mono and Stereo support
- 8-, 16-, and 32-bit FIFO interface for packing memory

- Independent transmit and receive 8-entry FIFOs
- Configurable FIFO-level interrupt and µDMA requests
- Independent transmit and receive MCLK direction control
- Transmit and receive internal MCLK sources
- Independent transmit and receive control for serial clock and word select
- MCLK and SCLK can be independently set to master or slave
- Configurable transmit zero or last sample when FIFO empty
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Burst requests
  - Channel requests asserted when FIFO contains required amount of data

# 1.3.5 System Integration

The LM3S9D96 microcontroller provides a variety of standard system functions integrated into the device, including:

- Direct Memory Access Controller (DMA)
- System control and clocks including on-chip precision 16-MHz oscillator
- Four 32-bit timers (up to eight 16-bit), with real-time clock capability
- Eight Capture Compare PWM (CCP) pins
- Two Watchdog Timers
  - One timer runs off the main oscillator
  - One timer runs off the precision internal oscillator
- Up to 65 GPIOs, depending on configuration
  - Highly flexible pin muxing allows use as GPIO or one of several peripheral functions
  - Independently configurable to 2, 4 or 8 mA drive capability
  - Up to 4 GPIOs can have 18 mA drive capability

The following sections provide more detail on each of these functions.

#### 1.3.5.1 Direct Memory Access (see page 346)

The LM3S9D96 microcontroller includes a Direct Memory Access (DMA) controller, known as micro-DMA ( $\mu$ DMA). The  $\mu$ DMA controller provides a way to offload data transfer tasks from the Cortex-M3 processor, allowing for more efficient use of the processor and the available bus bandwidth. The  $\mu$ DMA controller can perform transfers between memory and peripherals. It has dedicated channels for each supported on-chip module and can be programmed to automatically perform transfers between peripherals and memory as the peripheral is ready to transfer more data. The  $\mu$ DMA controller provides the following features:

- ARM PrimeCell® 32-channel configurable µDMA controller
- Support for memory-to-memory, memory-to-peripheral, and peripheral-to-memory in multiple transfer modes
  - Basic for simple transfer scenarios
  - Ping-pong for continuous data flow
  - Scatter-gather for a programmable list of arbitrary transfers initiated from a single request
- Highly flexible and configurable channel operation
  - Independently configured and operated channels
  - Dedicated channels for supported on-chip modules
  - Primary and secondary channel assignments
  - One channel each for receive and transmit path for bidirectional modules
  - Dedicated channel for software-initiated transfers
  - Per-channel configurable priority scheme
  - Optional software-initiated requests for any channel
- Two levels of priority
- Design optimizations for improved bus access performance between µDMA controller and the processor core
  - µDMA controller access is subordinate to core access
  - RAM striping
  - Peripheral bus segmentation
- Data sizes of 8, 16, and 32 bits
- Transfer size is programmable in binary steps from 1 to 1024
- Source and destination address increment size of byte, half-word, word, or no increment
- Maskable peripheral requests
- Interrupt on transfer completion, with a separate interrupt per channel

# 1.3.5.2 System Control and Clocks (see page 192)

System control determines the overall operation of the device. It provides information about the device, controls power-saving features, controls the clocking of the device and individual peripherals, and handles reset detection and reporting.

 Device identification information: version, part number, SRAM size, Flash memory size, and so on

#### Power control

- On-chip fixed Low Drop-Out (LDO) voltage regulator
- Low-power options for microcontroller: Sleep and Deep-sleep modes with clock gating
- Low-power options for on-chip modules: software controls shutdown of individual peripherals and memory
- 3.3-V supply brown-out detection and reporting via interrupt or reset
- Multiple clock sources for microcontroller system clock
  - Precision Oscillator (PIOSC): On-chip resource providing a 16 MHz ±1% frequency at room temperature
    - 16 MHz ±3% across temperature
    - Can be recalibrated with 7-bit trim resolution
    - Software power down control for low power modes
  - Main Oscillator (MOSC): A frequency-accurate clock source by one of two means: an external single-ended clock source is connected to the OSC0 input pin, or an external crystal is connected across the OSC0 input and OSC1 output pins.
    - External crystal used with or without on-chip PLL: select supported frequencies from 1 MHz to 16.384 MHz.
    - · External oscillator: from DC to maximum device speed
  - Internal 30-kHz Oscillator: on chip resource providing a 30 kHz ± 50% frequency, used during power-saving modes
- Flexible reset sources
  - Power-on reset (POR)
  - Reset pin assertion
  - Brown-out reset (BOR) detector alerts to system power drops
  - Software reset
  - Watchdog timer reset
  - MOSC failure

## 1.3.5.3 Programmable Timers (see page 537)

Programmable timers can be used to count or time external events that drive the Timer input pins. Each GPTM block provides two 16-bit timers/counters that can be configured to operate independently as timers or event counters, or configured to operate as one 32-bit timer or one 32-bit Real-Time Clock (RTC). Timers can also be used to trigger analog-to-digital (ADC) conversions.

The General-Purpose Timer Module (GPTM) contains four GPTM blocks with the following functional options:

- Operating modes:
  - 16- or 32-bit programmable one-shot timer

- 16- or 32-bit programmable periodic timer
- 16-bit general-purpose timer with an 8-bit prescaler
- 32-bit Real-Time Clock (RTC) when using an external 32.768-KHz clock as the input
- 16-bit input-edge count- or time-capture modes
- 16-bit PWM mode with software-programmable output inversion of the PWM signal
- Count up or down
- Eight Capture Compare PWM pins (CCP)
- Daisy chaining of timer modules to allow a single timer to initiate multiple timing events
- ADC event trigger
- User-enabled stalling when the microcontroller asserts CPU Halt flag during debug (excluding RTC mode)
- Ability to determine the elapsed time between the assertion of the timer interrupt and entry into the interrupt service routine.
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Dedicated channel for each timer
  - Burst request generated on timer interrupt

#### 1.3.5.4 CCP Pins (see page 545)

Capture Compare PWM pins (CCP) can be used by the General-Purpose Timer Module to time/count external events using the CCP pin as an input. Alternatively, the GPTM can generate a simple PWM output on the CCP pin.

The LM3S9D96 microcontroller includes eight Capture Compare PWM pins (CCP) that can be programmed to operate in the following modes:

- Capture: The GP Timer is incremented/decremented by programmed events on the CCP input. The GP Timer captures and stores the current timer value when a programmed event occurs.
- Compare: The GP Timer is incremented/decremented by programmed events on the CCP input. The GP Timer compares the current value with a stored value and generates an interrupt when a match occurs.
- PWM: The GP Timer is incremented/decremented by the system clock. A PWM signal is generated based on a match between the counter value and a value stored in a match register and is output on the CCP pin.

#### 1.3.5.5 Watchdog Timers (see page 584)

A watchdog timer is used to regain control when a system has failed due to a software error or to the failure of an external device to respond in the expected way. The Stellaris Watchdog Timer can generate an interrupt or a reset when a time-out value is reached. In addition, the Watchdog Timer is ARM FiRM-compliant and can be configured to generate an interrupt to the microcontroller on its first time-out, and to generate a reset signal on its second time-out. Once the Watchdog Timer has

been configured, the lock register can be written to prevent the timer configuration from being inadvertently altered.

The LM3S9D96 microcontroller has two Watchdog Timer modules: Watchdog Timer 0 uses the system clock for its timer clock; Watchdog Timer 1 uses the PIOSC as its timer clock. The Stellaris Watchdog Timer module has the following features:

- 32-bit down counter with a programmable load register
- Separate watchdog clock with an enable
- Programmable interrupt generation logic with interrupt masking
- Lock register protection from runaway software
- Reset generation logic with an enable/disable
- User-enabled stalling when the microcontroller asserts the CPU Halt flag during debug

# 1.3.5.6 Programmable GPIOs (see page 407)

General-purpose input/output (GPIO) pins offer flexibility for a variety of connections. The Stellaris GPIO module is comprised of nine physical GPIO blocks, each corresponding to an individual GPIO port. The GPIO module is FiRM-compliant (compliant to the ARM Foundation IP for Real-Time Microcontrollers specification) and supports 0-65 programmable input/output pins. The number of GPIOs available depends on the peripherals being used (see "Signal Tables" on page 1238 for the signals available to each GPIO pin).

- Up to 65 GPIOs, depending on configuration
- Highly flexible pin muxing allows use as GPIO or one of several peripheral functions
- 5-V-tolerant in input configuration
- Two means of port access: either Advanced High-Performance Bus (AHB) with better back-to-back access performance, or the legacy Advanced Peripheral Bus (APB) for backwards-compatibility with existing code
- Fast toggle capable of a change every clock cycle for ports on AHB, every two clock cycles for ports on APB
- Programmable control for GPIO interrupts
  - Interrupt generation masking
  - Edge-triggered on rising, falling, or both
  - Level-sensitive on High or Low values
- Bit masking in both read and write operations through address lines
- Can be used to initiate an ADC sample sequence
- Pins configured as digital inputs are Schmitt-triggered
- Programmable control for GPIO pad configuration

- Weak pull-up or pull-down resistors
- 2-mA, 4-mA, and 8-mA pad drive for digital communication; up to four pads can sink 18-mA for high-current applications
- Slew rate control for the 8-mA drive
- Open drain enables
- Digital input enables

## 1.3.6 Advanced Motion Control

The LM3S9D96 microcontroller provides motion control functions integrated into the device, including:

- Eight advanced PWM outputs for motion and energy applications
- Four fault inputs to promote low-latency shutdown
- Two Quadrature Encoder Inputs (QEI)

The following provides more detail on these motion control functions.

#### 1.3.6.1 PWM (see page 1136)

Pulse width modulation (PWM) is a powerful technique for digitally encoding analog signal levels. High-resolution counters are used to generate a square wave, and the duty cycle of the square wave is modulated to encode an analog signal. Typical applications include switching power supplies and motor control. The LM3S9D96 PWM module consists of four PWM generator blocks and a control block. Each PWM generator block contains one timer (16-bit down or up/down counter), two comparators, a PWM signal generator, a dead-band generator, and an interrupt/ADC-trigger selector. Each PWM generator block produces two PWM signals that can either be independent signals or a single pair of complementary signals with dead-band delays inserted.

Each PWM generator has the following features:

- Four fault-condition handling inputs to quickly provide low-latency shutdown and prevent damage to the motor being controlled
- One 16-bit counter
  - Runs in Down or Up/Down mode
  - Output frequency controlled by a 16-bit load value
  - Load value updates can be synchronized
  - Produces output signals at zero and load value
- Two PWM comparators
  - Comparator value updates can be synchronized
  - Produces output signals on match
- PWM signal generator

- Output PWM signal is constructed based on actions taken as a result of the counter and PWM comparator output signals
- Produces two independent PWM signals
- Dead-band generator
  - Produces two PWM signals with programmable dead-band delays suitable for driving a half-H bridge
  - Can be bypassed, leaving input PWM signals unmodified
- Can initiate an ADC sample sequence

The control block determines the polarity of the PWM signals and which signals are passed through to the pins. The output of the PWM generation blocks are managed by the output control block before being passed to the device pins. The PWM control block has the following options:

- PWM output enable of each PWM signal
- Optional output inversion of each PWM signal (polarity control)
- Optional fault handling for each PWM signal
- Synchronization of timers in the PWM generator blocks
- Synchronization of timer/comparator updates across the PWM generator blocks
- Extended PWM synchronization of timer/comparator updates across the PWM generator blocks
- Interrupt status summary of the PWM generator blocks
- Extended PWM fault handling, with multiple fault signals, programmable polarities, and filtering
- PWM generators can be operated independently or synchronized with other generators

#### 1.3.6.2 QEI (see page 1213)

A quadrature encoder, also known as a 2-channel incremental encoder, converts linear displacement into a pulse signal. By monitoring both the number of pulses and the relative phase of the two signals, the position, direction of rotation, and speed can be tracked. In addition, a third channel, or index signal, can be used to reset the position counter. The Stellaris quadrature encoder with index (QEI) module interprets the code produced by a quadrature encoder wheel to integrate position over time and determine direction of rotation. In addition, it can capture a running estimate of the velocity of the encoder wheel. The input frequency of the QEI inputs may be as high as 1/4 of the processor frequency (for example, 20 MHz for a 80-MHz system).

The LM3S9D96 microcontroller includes two QEI modules providing control of two motors at the same time with the following features:

- Position integrator that tracks the encoder position
- Programmable noise filter on the inputs
- Velocity capture using built-in timer

- The input frequency of the QEI inputs may be as high as 1/4 of the processor frequency (for example, 12.5 MHz for a 50-MHz system)
- Interrupt generation on:
  - Index pulse
  - Velocity-timer expiration
  - Direction change
  - Quadrature error detection

# 1.3.7 Analog

The LM3S9D96 microcontroller provides analog functions integrated into the device, including:

- Two 12-bit Analog-to-Digital Converters (ADC) with 16 analog input channels and a sample rate of one million samples/second
- Three analog comparators
- 16 digital comparators
- On-chip voltage regulator

The following provides more detail on these analog functions.

# 1.3.7.1 ADC (see page 609)

An analog-to-digital converter (ADC) is a peripheral that converts a continuous analog voltage to a discrete digital number. The Stellaris ADC module features 12-bit conversion resolution and supports 16 input channels plus an internal temperature sensor. Four buffered sample sequencers allow rapid sampling of up to 16 analog input sources without controller intervention. Each sample sequencer provides flexible programming with fully configurable input source, trigger events, interrupt generation, and sequencer priority. Each ADC module has a digital comparator function that allows the conversion value to be diverted to a comparison unit that provides eight digital comparators.

The LM3S9D96 microcontroller provides two ADC modules with the following features:

- 16 shared analog input channels
- 12-bit precision ADC with an accurate 10-bit data compatibility mode
- Single-ended and differential-input configurations
- On-chip internal temperature sensor
- Maximum sample rate of one million samples/second
- Optional phase shift in sample time programmable from 22.5° to 337.5°
- Four programmable sample conversion sequencers from one to eight entries long, with corresponding conversion result FIFOs
- Flexible trigger control

- Controller (software)
- Timers
- Analog Comparators
- PWM
- GPIO
- Hardware averaging of up to 64 samples
- Digital comparison unit providing eight digital comparators
- Converter uses an internal 3-V reference or an external reference
- Power and ground for the analog circuitry is separate from the digital power and ground
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Dedicated channel for each sample sequencer
  - ADC module uses burst requests for DMA

## 1.3.7.2 Analog Comparators (see page 1122)

An analog comparator is a peripheral that compares two analog voltages and provides a logical output that signals the comparison result. The LM3S9D96 microcontroller provides three independent integrated analog comparators that can be configured to drive an output or generate an interrupt or ADC event.

The comparator can provide its output to a device pin, acting as a replacement for an analog comparator on the board, or it can be used to signal the application via interrupts or triggers to the ADC to cause it to start capturing a sample sequence. The interrupt generation and ADC triggering logic is separate. This means, for example, that an interrupt can be generated on a rising edge and the ADC triggered on a falling edge.

The LM3S9D96 microcontroller provides three independent integrated analog comparators with the following functions:

- Compare external pin input to external pin input or to internal programmable voltage reference
- Compare a test voltage against any one of the following voltages:
  - An individual external reference voltage
  - A shared single external reference voltage
  - A shared internal reference voltage

#### 1.3.8 JTAG and ARM Serial Wire Debug (see page 180)

The Joint Test Action Group (JTAG) port is an IEEE standard that defines a Test Access Port and Boundary Scan Architecture for digital integrated circuits and provides a standardized serial interface for controlling the associated test logic. The TAP, Instruction Register (IR), and Data Registers (DR) can be used to test the interconnections of assembled printed circuit boards and obtain manufacturing information on the components. The JTAG Port also provides a means of accessing and controlling

design-for-test features such as I/O pin observation and control, scan testing, and debugging. Texas Instruments replaces the ARM SW-DP and JTAG-DP with the ARM Serial Wire JTAG Debug Port (SWJ-DP) interface. The SWJ-DP interface combines the SWD and JTAG debug ports into one module providing all the normal JTAG debug and test functionality plus real-time access to system memory without halting the core or requiring any target resident code. The SWJ-DP interface has the following features:

- IEEE 1149.1-1990 compatible Test Access Port (TAP) controller
- Four-bit Instruction Register (IR) chain for storing JTAG instructions
- IEEE standard instructions: BYPASS, IDCODE, SAMPLE/PRELOAD, EXTEST and INTEST
- ARM additional instructions: APACC, DPACC and ABORT
- Integrated ARM Serial Wire Debug (SWD)
  - Serial Wire JTAG Debug Port (SWJ-DP)
  - Flash Patch and Breakpoint (FPB) unit for implementing breakpoints
  - Data Watchpoint and Trace (DWT) unit for implementing watchpoints, trigger resources, and system profiling
  - Instrumentation Trace Macrocell (ITM) for support of printf style debugging
  - Trace Port Interface Unit (TPIU) for bridging to a Trace Port Analyzer

# 1.3.9 Packaging and Temperature

- Industrial-range (-40°C to 85°C) 100-pin RoHS-compliant LQFP package
- Industrial-range (-40°C to 85°C) 108-ball RoHS-compliant BGA package

#### 1.4 Hardware Details

Details on the pins and package can be found in the following sections:

- "Pin Diagram" on page 1236
- "Signal Tables" on page 1238
- "Operating Characteristics" on page 1316
- "Electrical Characteristics" on page 1317
- "Package Information" on page 1401

# 2 The Cortex-M3 Processor

The ARM® Cortex<sup>™</sup>-M3 processor provides a high-performance, low-cost platform that meets the system requirements of minimal memory implementation, reduced pin count, and low power consumption, while delivering outstanding computational performance and exceptional system response to interrupts. Features include:

- 32-bit ARM® Cortex™-M3 architecture optimized for small-footprint embedded applications
- 80-MHz operation; 100 DMIPS performance
- Outstanding processing performance combined with fast interrupt handling
- Thumb-2 mixed 16-/32-bit instruction set delivers the high performance expected of a 32-bit ARM core in a compact memory size usually associated with 8- and 16-bit devices, typically in the range of a few kilobytes of memory for microcontroller-class applications
  - Single-cycle multiply instruction and hardware divide
  - Atomic bit manipulation (bit-banding), delivering maximum memory utilization and streamlined peripheral control
  - Unaligned data access, enabling data to be efficiently packed into memory
- Fast code execution permits slower processor clock or increases sleep mode time
- Harvard architecture characterized by separate buses for instruction and data
- Efficient processor core, system and memories
- Hardware division and fast digital-signal-processing orientated multiply accumulate
- Saturating arithmetic for signal processing
- Deterministic, high-performance interrupt handling for time-critical applications
- Memory protection unit (MPU) to provide a privileged mode for protected operating system functionality
- Enhanced system debug with extensive breakpoint and trace capabilities
- Serial Wire Debug and Serial Wire Trace reduce the number of pins required for debugging and tracing
- Migration from the ARM7 processor family for better performance and power efficiency
- Optimized for single-cycle Flash memory usage
- Ultra-low power consumption with integrated sleep modes

The Stellaris<sup>®</sup> family of microcontrollers builds on this core to bring high-performance 32-bit computing to cost-sensitive embedded microcontroller applications, such as factory automation and control, industrial control power devices, building and home automation, and stepper motor control.

This chapter provides information on the Stellaris implementation of the Cortex-M3 processor, including the programming model, the memory model, the exception model, fault handling, and power management.

For technical details on the instruction set, see the  $Cortex^{TM}$ -M3/M4 Instruction Set Technical User's Manual.

# 2.1 Block Diagram

The Cortex-M3 processor is built on a high-performance processor core, with a 3-stage pipeline Harvard architecture, making it ideal for demanding embedded applications. The processor delivers exceptional power efficiency through an efficient instruction set and extensively optimized design, providing high-end processing hardware including a range of single-cycle and SIMD multiplication and multiply-with-accumulate capabilities, saturating arithmetic and dedicated hardware division.

To facilitate the design of cost-sensitive devices, the Cortex-M3 processor implements tightly coupled system components that reduce processor area while significantly improving interrupt handling and system debug capabilities. The Cortex-M3 processor implements a version of the Thumb® instruction set based on Thumb-2 technology, ensuring high code density and reduced program memory requirements. The Cortex-M3 instruction set provides the exceptional performance expected of a modern 32-bit architecture, with the high code density of 8-bit and 16-bit microcontrollers.

The Cortex-M3 processor closely integrates a nested interrupt controller (NVIC), to deliver industry-leading interrupt performance. The Stellaris NVIC includes a non-maskable interrupt (NMI) and provides eight interrupt priority levels. The tight integration of the processor core and NVIC provides fast execution of interrupt service routines (ISRs), dramatically reducing interrupt latency. The hardware stacking of registers and the ability to suspend load-multiple and store-multiple operations further reduce interrupt latency. Interrupt handlers do not require any assembler stubs which removes code overhead from the ISRs. Tail-chaining optimization also significantly reduces the overhead when switching from one ISR to another. To optimize low-power designs, the NVIC integrates with the sleep modes, including Deep-sleep mode, which enables the entire device to be rapidly powered down.




Figure 2-1. CPU Block Diagram

## 2.2 Overview

# 2.2.1 System-Level Interface

The Cortex-M3 processor provides multiple interfaces using AMBA® technology to provide high-speed, low-latency memory accesses. The core supports unaligned data accesses and implements atomic bit manipulation that enables faster peripheral controls, system spinlocks, and thread-safe Boolean data handling.

The Cortex-M3 processor has a memory protection unit (MPU) that provides fine-grain memory control, enabling applications to implement security privilege levels and separate code, data and stack on a task-by-task basis.

## 2.2.2 Integrated Configurable Debug

The Cortex-M3 processor implements a complete hardware debug solution, providing high system visibility of the processor and memory through either a traditional JTAG port or a 2-pin Serial Wire Debug (SWD) port that is ideal for microcontrollers and other small package devices. The Stellaris implementation replaces the ARM SW-DP and JTAG-DP with the ARM CoreSight™-compliant Serial Wire JTAG Debug Port (SWJ-DP) interface. The SWJ-DP interface combines the SWD and JTAG debug ports into one module. See the *ARM® Debug Interface V5 Architecture Specification* for details on SWJ-DP.

For system trace, the processor integrates an Instrumentation Trace Macrocell (ITM) alongside data watchpoints and a profiling unit. To enable simple and cost-effective profiling of the system trace events, a Serial Wire Viewer (SWV) can export a stream of software-generated messages, data trace, and profiling information through a single pin.


The Flash Patch and Breakpoint Unit (FPB) provides up to eight hardware breakpoint comparators that debuggers can use. The comparators in the FPB also provide remap functions of up to eight words in the program code in the CODE memory region. This enables applications stored in a read-only area of Flash memory to be patched in another area of on-chip SRAM or Flash memory. If a patch is required, the application programs the FPB to remap a number of addresses. When those addresses are accessed, the accesses are redirected to a remap table specified in the FPB configuration.

For more information on the Cortex-M3 debug capabilities, see the ARM® Debug Interface V5 Architecture Specification.

## 2.2.3 Trace Port Interface Unit (TPIU)

The TPIU acts as a bridge between the Cortex-M3 trace data from the ITM, and an off-chip Trace Port Analyzer, as shown in Figure 2-2 on page 74.

Figure 2-2. TPIU Block Diagram



# 2.2.4 Cortex-M3 System Component Details

The Cortex-M3 includes the following system components:

■ SysTick

A 24-bit count-down timer that can be used as a Real-Time Operating System (RTOS) tick timer or as a simple counter (see "System Timer (SysTick)" on page 114).

Nested Vectored Interrupt Controller (NVIC)

An embedded interrupt controller that supports low latency interrupt processing (see "Nested Vectored Interrupt Controller (NVIC)" on page 115).

■ System Control Block (SCB)

The programming model interface to the processor. The SCB provides system implementation information and system control, including configuration, control, and reporting of system exceptions (see "System Control Block (SCB)" on page 117).

■ Memory Protection Unit (MPU)

Improves system reliability by defining the memory attributes for different memory regions. The MPU provides up to eight different regions and an optional predefined background region (see "Memory Protection Unit (MPU)" on page 117).

# 2.3 Programming Model

This section describes the Cortex-M3 programming model. In addition to the individual core register descriptions, information about the processor modes and privilege levels for software execution and stacks is included.

### 2.3.1 Processor Mode and Privilege Levels for Software Execution

The Cortex-M3 has two modes of operation:

Thread mode

Used to execute application software. The processor enters Thread mode when it comes out of reset.

■ Handler mode

Used to handle exceptions. When the processor has finished exception processing, it returns to Thread mode.

In addition, the Cortex-M3 has two privilege levels:

Unprivileged

In this mode, software has the following restrictions:

- Limited access to the MSR and MRS instructions and no use of the CPS instruction
- No access to the system timer, NVIC, or system control block
- Possibly restricted access to memory or peripherals
- Privileged

In this mode, software can use all the instructions and has access to all resources.

In Thread mode, the **CONTROL** register (see page 89) controls whether software execution is privileged or unprivileged. In Handler mode, software execution is always privileged.

Only privileged software can write to the **CONTROL** register to change the privilege level for software execution in Thread mode. Unprivileged software can use the SVC instruction to make a supervisor call to transfer control to privileged software.

#### 2.3.2 Stacks

The processor uses a full descending stack, meaning that the stack pointer indicates the last stacked item on the memory. When the processor pushes a new item onto the stack, it decrements the stack pointer and then writes the item to the new memory location. The processor implements two stacks:

the main stack and the process stack, with a pointer for each held in independent registers (see the **SP** register on page 79).

In Thread mode, the **CONTROL** register (see page 89) controls whether the processor uses the main stack or the process stack. In Handler mode, the processor always uses the main stack. The options for processor operations are shown in Table 2-1 on page 76.

Table 2-1. Summary of Processor Mode, Privilege Level, and Stack Use

Processor Mode	Use	Privilege Level	Stack Used
Thread	Applications	Privileged or unprivileged <sup>a</sup>	Main stack or process stack a
Handler	Exception handlers	Always privileged	Main stack

a. See CONTROL (page 89).

## 2.3.3 Register Map

Figure 2-3 on page 76 shows the Cortex-M3 register set. Table 2-2 on page 77 lists the Core registers. The core registers are not memory mapped and are accessed by register name, so the base address is n/a (not applicable) and there is no offset.

Figure 2-3. Cortex-M3 Register Set




Table 2-2. Processor Register Map

Offset	Name	Туре	Reset	Description	See page
-	R0	R/W	-	Cortex General-Purpose Register 0	78
-	R1	R/W	-	Cortex General-Purpose Register 1	78
-	R2	R/W	-	Cortex General-Purpose Register 2	78
-	R3	R/W	-	Cortex General-Purpose Register 3	78
-	R4	R/W	-	Cortex General-Purpose Register 4	78
-	R5	R/W	-	Cortex General-Purpose Register 5	78
-	R6	R/W	-	Cortex General-Purpose Register 6	78
-	R7	R/W	-	Cortex General-Purpose Register 7	78
-	R8	R/W	-	Cortex General-Purpose Register 8	78
-	R9	R/W	-	Cortex General-Purpose Register 9	78
-	R10	R/W	-	Cortex General-Purpose Register 10	78
-	R11	R/W	-	Cortex General-Purpose Register 11	78
-	R12	R/W	-	Cortex General-Purpose Register 12	78
-	SP	R/W	-	Stack Pointer	79
-	LR	R/W	0xFFFF.FFFF	Link Register	80
-	PC	R/W	-	Program Counter	81
-	PSR	R/W	0x0100.0000	Program Status Register	82
-	PRIMASK	R/W	0x0000.0000	Priority Mask Register	86
-	FAULTMASK	R/W	0x0000.0000	Fault Mask Register	87
-	BASEPRI	R/W	0x0000.0000	Base Priority Mask Register	88
-	CONTROL	R/W	0x0000.0000	Control Register	89

# 2.3.4 Register Descriptions

This section lists and describes the Cortex-M3 registers, in the order shown in Figure 2-3 on page 76. The core registers are not memory mapped and are accessed by register name rather than offset.

**Note:** The register type shown in the register descriptions refers to type during program execution in Thread mode and Handler mode. Debug access can differ.

Register 1: Cortex General-Purpose Register 0 (R0)

Register 2: Cortex General-Purpose Register 1 (R1)

Register 3: Cortex General-Purpose Register 2 (R2)

Register 4: Cortex General-Purpose Register 3 (R3)

Register 5: Cortex General-Purpose Register 4 (R4)

Register 6: Cortex General-Purpose Register 5 (R5)

Register 7: Cortex General-Purpose Register 6 (R6)

Register 8: Cortex General-Purpose Register 7 (R7)

Register 9: Cortex General-Purpose Register 8 (R8)

Register 10: Cortex General-Purpose Register 9 (R9)

Register 11: Cortex General-Purpose Register 10 (R10)


Register 12: Cortex General-Purpose Register 11 (R11)

Register 13: Cortex General-Purpose Register 12 (R12)

The **Rn** registers are 32-bit general-purpose registers for data operations and can be accessed from either privileged or unprivileged mode.

#### Cortex General-Purpose Register 0 (R0)






Bit/Field Name Type Reset Description

31:0 DATA R/W - Register data.

### Register 14: Stack Pointer (SP)

The **Stack Pointer (SP)** is register R13. In Thread mode, the function of this register changes depending on the ASP bit in the **Control Register (CONTROL)** register. When the ASP bit is clear, this register is the **Main Stack Pointer (MSP)**. When the ASP bit is set, this register is the **Process Stack Pointer (PSP)**. On reset, the ASP bit is clear, and the processor loads the **MSP** with the value from address 0x0000.0000. The **MSP** can only be accessed in privileged mode; the **PSP** can be accessed in either privileged or unprivileged mode.




### Register 15: Link Register (LR)

The **Link Register (LR)** is register R14, and it stores the return information for subroutines, function calls, and exceptions. **LR** can be accessed from either privileged or unprivileged mode.

 ${\tt EXC\_RETURN}$  is loaded into **LR** on exception entry. See Table 2-10 on page 107 for the values and description.

#### Link Register (LR)

Type R/W, reset 0xFFFF.FFF



Bit/Field Name Type Reset Description


31:0 LINK R/W 0xFFF.FFF This field is the return address.

## **Register 16: Program Counter (PC)**

The **Program Counter (PC)** is register R15, and it contains the current program address. On reset, the processor loads the **PC** with the value of the reset vector, which is at address 0x0000.0004. Bit 0 of the reset vector is loaded into the THUMB bit of the **EPSR** at reset and must be 1. The **PC** register can be accessed in either privileged or unprivileged mode.

#### Program Counter (PC)





Bit/Field Name Type Reset Description

31:0 PC R/W - This field is the current program address.

#### Register 17: Program Status Register (PSR)

**Note:** This register is also referred to as **xPSR**.

The **Program Status Register (PSR)** has three functions, and the register bits are assigned to the different functions:

- Application Program Status Register (APSR), bits 31:27,
- Execution Program Status Register (EPSR), bits 26:24, 15:10
- Interrupt Program Status Register (IPSR), bits 6:0

The **PSR**, **IPSR**, and **EPSR** registers can only be accessed in privileged mode; the **APSR** register can be accessed in either privileged or unprivileged mode.

**APSR** contains the current state of the condition flags from previous instruction executions.

**EPSR** contains the Thumb state bit and the execution state bits for the If-Then (IT) instruction or the Interruptible-Continuable Instruction (ICI) field for an interrupted load multiple or store multiple instruction. Attempts to read the **EPSR** directly through application software using the MSR instruction always return zero. Attempts to write the **EPSR** using the MSR instruction in application software are always ignored. Fault handlers can examine the **EPSR** value in the stacked **PSR** to determine the operation that faulted (see "Exception Entry and Return" on page 105).

IPSR contains the exception type number of the current Interrupt Service Routine (ISR).

These registers can be accessed individually or as a combination of any two or all three registers, using the register name as an argument to the MSR or MRS instructions. For example, all of the registers can be read using **PSR** with the MRS instruction, or **APSR** only can be written to using **APSR** with the MSR instruction. page 82 shows the possible register combinations for the **PSR**. See the MRS and MSR instruction descriptions in the *Cortex™-M3/M4 Instruction Set Technical User's Manual* for more information about how to access the program status registers.


Table 2-3. PSR Register Combinations

Register	Туре	Combination
PSR	R/W <sup>a, b</sup>	APSR, EPSR, and IPSR
IEPSR	RO	EPSR and IPSR
IAPSR	R/W <sup>a</sup>	APSR and IPSR
EAPSR	R/W <sup>b</sup>	APSR and EPSR

- a. The processor ignores writes to the IPSR bits.
- b. Reads of the EPSR bits return zero, and the processor ignores writes to these bits.

#### Program Status Register (PSR)

Type R/W, reset 0x0100.0000



Bit/Field	Name	Туре	Reset	Description
31	N	R/W	0	APSR Negative or Less Flag
				Value Description
				1 The previous operation result was negative or less than.
				The previous operation result was positive, zero, greater than, or equal.
				The value of this bit is only meaningful when accessing <b>PSR</b> or <b>APSR</b> .
30	Z	R/W	0	APSR Zero Flag
				Value Description
				1 The previous operation result was zero.
				0 The previous operation result was non-zero.
				The value of this bit is only meaningful when accessing <b>PSR</b> or <b>APSR</b> .
29	С	R/W	0	APSR Carry or Borrow Flag
				Value Description
				1 The previous add operation resulted in a carry bit or the previous subtract operation did not result in a borrow bit.
				The previous add operation did not result in a carry bit or the previous subtract operation resulted in a borrow bit.
				The value of this bit is only meaningful when accessing <b>PSR</b> or <b>APSR</b> .
28	V	R/W	0	APSR Overflow Flag
				Value Description
				1 The previous operation resulted in an overflow.
				O The previous operation did not result in an overflow.
				The value of this bit is only meaningful when accessing <b>PSR</b> or <b>APSR</b> .
27	Q	R/W	0	APSR DSP Overflow and Saturation Flag
				Value Description
				1 DSP Overflow or saturation has occurred.
				0 DSP overflow or saturation has not occurred since reset or since the bit was last cleared.
				The value of this bit is only meaningful when accessing <b>PSR</b> or <b>APSR</b> .

This bit is cleared by software using an  ${\tt MRS}$  instruction.

Bit/Field	Name	Туре	Reset	Description
26:25	ICI / IT	RO	0x0	EPSR ICI / IT status  These bits, along with bits 15:10, contain the Interruptible-Continuable Instruction (ICI) field for an interrupted load multiple or store multiple instruction or the execution state bits of the IT instruction.  When EPSR holds the ICI execution state, bits 26:25 are zero.  The If-Then block contains up to four instructions following an IT instruction. Each instruction in the block is conditional. The conditions for the instructions are either all the same, or some can be the inverse of others. See the Cortex™-M3/M4 Instruction Set Technical User's Manual for more information.  The value of this field is only meaningful when accessing PSR or EPSR.
24	THUMB	RO	1	EPSR Thumb State This bit indicates the Thumb state and should always be set. The following can clear the THUMB bit:  The BLX, BX and POP{PC} instructions  Restoration from the stacked xPSR value on an exception return  Bit 0 of the vector value on an exception entry or reset  Attempting to execute instructions when this bit is clear results in a fault or lockup. See "Lockup" on page 109 for more information. The value of this bit is only meaningful when accessing PSR or EPSR.
23:16	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:10	ICI / IT	RO	0x0	EPSR ICI / IT status  These bits, along with bits 26:25, contain the Interruptible-Continuable Instruction (ICI) field for an interrupted load multiple or store multiple instruction or the execution state bits of the IT instruction.  When an interrupt occurs during the execution of an LDM, STM, PUSH or POP instruction, the processor stops the load multiple or store multiple instruction operation temporarily and stores the next register operand in the multiple operation to bits 15:12. After servicing the interrupt, the processor returns to the register pointed to by bits 15:12 and resumes execution of the multiple load or store instruction. When EPSR holds the ICI execution state, bits 11:10 are zero.  The If-Then block contains up to four instructions following a 16-bit IT instruction. Each instruction in the block is conditional. The conditions for the instructions are either all the same, or some can be the inverse of others. See the Cortex™-M3/M4 Instruction Set Technical User's Manual for more information.  The value of this field is only meaningful when accessing PSR or EPSR.
9:7	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

		_	_		
Bit/Field	Name	Type	Reset	Description	
6:0	ISRNUM	RO	0x00	IPSR ISR N	umber
				This field co Service Rou	ntains the exception type number of the current Interrupt tine (ISR).
				Value	Description
				0x00	Thread mode
				0x01	Reserved
				0x02	NMI
				0x03	Hard fault
				0x04	Memory management fault
				0x05	Bus fault
				0x06	Usage fault
				0x07-0x0A	Reserved
				0x0B	SVCall
				0x0C	Reserved for Debug
				0x0D	Reserved
				0x0E	PendSV
				0x0F	SysTick
				0x10	Interrupt Vector 0
				0x11	Interrupt Vector 1
				0x46	Interrupt Vector 54
				0x47-0x7F	Reserved
				See "Excent	tion Types" on page 100 for more information

See "Exception Types" on page 100 for more information.


The value of this field is only meaningful when accessing **PSR** or **IPSR**.

### Register 18: Priority Mask Register (PRIMASK)

The **PRIMASK** register prevents activation of all exceptions with programmable priority. Reset, non-maskable interrupt (NMI), and hard fault are the only exceptions with fixed priority. Exceptions should be disabled when they might impact the timing of critical tasks. This register is only accessible in privileged mode. The MSR and MRS instructions are used to access the **PRIMASK** register, and the CPS instruction may be used to change the value of the **PRIMASK** register. See the Cortex™-M3/M4 Instruction Set Technical User's Manual for more information on these instructions. For more information on exception priority levels, see "Exception Types" on page 100.

#### Priority Mask Register (PRIMASK)

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	PRIMASK	R/W	0	Priority Mask

#### Value Description


- Prevents the activation of all exceptions with configurable priority.
- 0 No effect.

### Register 19: Fault Mask Register (FAULTMASK)

The **FAULTMASK** register prevents activation of all exceptions except for the Non-Maskable Interrupt (NMI). Exceptions should be disabled when they might impact the timing of critical tasks. This register is only accessible in privileged mode. The MSR and MRS instructions are used to access the **FAULTMASK** register, and the CPS instruction may be used to change the value of the **FAULTMASK** register. See the *Cortex™-M3/M4 Instruction Set Technical User's Manual* for more information on these instructions. For more information on exception priority levels, see "Exception Types" on page 100.

#### Fault Mask Register (FAULTMASK)

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	FAULTMASK	R/W	0	Fault Mask

Value Description


- 1 Prevents the activation of all exceptions except for NMI.
- 0 No effect.

The processor clears the  ${\tt FAULTMASK}$  bit on exit from any exception handler except the NMI handler.

### Register 20: Base Priority Mask Register (BASEPRI)

The **BASEPRI** register defines the minimum priority for exception processing. When **BASEPRI** is set to a nonzero value, it prevents the activation of all exceptions with the same or lower priority level as the **BASEPRI** value. Exceptions should be disabled when they might impact the timing of critical tasks. This register is only accessible in privileged mode. For more information on exception priority levels, see "Exception Types" on page 100.

#### Base Priority Mask Register (BASEPRI)




4:0

reserved

RO

0x0



Bit/Field	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:5	BASEPRI	R/W	0x0	Base Priority

Any exception that has a programmable priority level with the same or lower priority as the value of this field is masked. The **PRIMASK** register can be used to mask all exceptions with programmable priority levels. Higher priority exceptions have lower priority levels.

Value Description 0x0 All exceptions are unmasked. 0x1 All exceptions with priority level 1-7 are masked. 0x2 All exceptions with priority level 2-7 are masked. 0x3 All exceptions with priority level 3-7 are masked. All exceptions with priority level 4-7 are masked. 0x4 All exceptions with priority level 5-7 are masked. 0x5 All exceptions with priority level 6-7 are masked. 0x60x7 All exceptions with priority level 7 are masked.

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 21: Control Register (CONTROL)


The **CONTROL** register controls the stack used and the privilege level for software execution when the processor is in Thread mode. This register is only accessible in privileged mode.

Handler mode always uses **MSP**, so the processor ignores explicit writes to the ASP bit of the **CONTROL** register when in Handler mode. The exception entry and return mechanisms automatically update the **CONTROL** register based on the EXC\_RETURN value (see Table 2-10 on page 107). In an OS environment, threads running in Thread mode should use the process stack and the kernel and exception handlers should use the main stack. By default, Thread mode uses **MSP**. To switch the stack pointer used in Thread mode to **PSP**, either use the MSR instruction to set the ASP bit, as detailed in the *Cortex*<sup>™</sup>-*M3/M4 Instruction Set Technical User's Manual*, or perform an exception return to Thread mode with the appropriate EXC\_RETURN value, as shown in Table 2-10 on page 107.

**Note:** When changing the stack pointer, software must use an ISB instruction immediately after the MSR instruction, ensuring that instructions after the ISB execute use the new stack pointer. See the *Cortex*<sup>TM</sup>-*M3/M4 Instruction Set Technical User's Manual*.

#### Control Register (CONTROL)

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	ASP	R/W	0	Active Stack Pointer
				Value Description
				1 <b>PSP</b> is the current stack pointer.
				0 MSP is the current stack pointer
				In Handler mode, this bit reads as zero and ignores writes. The Cortex-M3 updates this bit automatically on exception return.
0	TMPL	R/W	0	Thread Mode Privilege Level
				Value Description

Value Description

- 1 Unprivileged software can be executed in Thread mode.
- Only privileged software can be executed in Thread mode.

## 2.3.5 Exceptions and Interrupts

The Cortex-M3 processor supports interrupts and system exceptions. The processor and the Nested Vectored Interrupt Controller (NVIC) prioritize and handle all exceptions. An exception changes the normal flow of software control. The processor uses Handler mode to handle all exceptions except for reset. See "Exception Entry and Return" on page 105 for more information.

The NVIC registers control interrupt handling. See "Nested Vectored Interrupt Controller (NVIC)" on page 115 for more information.

## 2.3.6 Data Types

The Cortex-M3 supports 32-bit words, 16-bit halfwords, and 8-bit bytes. The processor also supports 64-bit data transfer instructions. All instruction and data memory accesses are little endian. See "Memory Regions, Types and Attributes" on page 92 for more information.

# 2.4 Memory Model

This section describes the processor memory map, the behavior of memory accesses, and the bit-banding features. The processor has a fixed memory map that provides up to 4 GB of addressable memory.

The memory map for the LM3S9D96 controller is provided in Table 2-4 on page 90. In this manual, register addresses are given as a hexadecimal increment, relative to the module's base address as shown in the memory map.

The regions for SRAM and peripherals include bit-band regions. Bit-banding provides atomic operations to bit data (see "Bit-Banding" on page 95).

The processor reserves regions of the Private peripheral bus (PPB) address range for core peripheral registers (see "Cortex-M3 Peripherals" on page 114).

Note: Within the memory map, all reserved space returns a bus fault when read or written.

Table 2-4. Memory Map

Start	End	Description	For details, see page
Memory			
0x0000.0000	0x0007.FFFF	On-chip Flash	310
0x0008.0000	0x00FF.FFFF	Reserved	-
0x0100.0000	0x1FFF.FFFF	Reserved for ROM	301
0x2000.0000	0x2001.FFFF	Bit-banded on-chip SRAM	301
0x2002.0000	0x21FF.FFFF	Reserved	-
0x2200.0000	0x222F.FFFF	Bit-band alias of bit-banded on-chip SRAM starting at 0x2000.0000	301
0x2230.0000	0x3FFF.FFFF	Reserved	-
FiRM Peripherals		·	
0x4000.0000	0x4000.0FFF	Watchdog timer 0	587
0x4000.1000	0x4000.1FFF	Watchdog timer 1	587
0x4000.2000	0x4000.3FFF	Reserved	-
0x4000.4000	0x4000.4FFF	GPIO Port A	419
0x4000.5000	0x4000.5FFF	GPIO Port B	419
0x4000.6000	0x4000.6FFF	GPIO Port C	419

Table 2-4. Memory Map (continued)

Start	End	Description	For details, see page
0x4000.7000	0x4000.7FFF	GPIO Port D	419
0x4000.8000	0x4000.8FFF	SSI0	768
0x4000.9000	0x4000.9FFF	SSI1	768
0x4000.A000	0x4000.BFFF	Reserved	-
0x4000.C000	0x4000.CFFF	UART0	704
0x4000.D000	0x4000.DFFF	UART1	704
0x4000.E000	0x4000.EFFF	UART2	704
0x4000.F000	0x4001.FFFF	Reserved	-
Peripherals	<u>'</u>	'	<u>'</u>
0x4002.0000	0x4002.0FFF	I <sup>2</sup> C 0	812
0x4002.1000	0x4002.1FFF	I <sup>2</sup> C 1	812
0x4002.2000	0x4002.3FFF	Reserved	-
0x4002.4000	0x4002.4FFF	GPIO Port E	419
0x4002.5000	0x4002.5FFF	GPIO Port F	419
0x4002.6000	0x4002.6FFF	GPIO Port G	419
0x4002.7000	0x4002.7FFF	GPIO Port H	419
0x4002.8000	0x4002.8FFF	PWM	1150
0x4002.9000	0x4002.BFFF	Reserved	-
0x4002.C000	0x4002.CFFF	QEI0	1219
0x4002.D000	0x4002.DFFF	QEI1	1219
0x4002.E000	0x4002.FFFF	Reserved	-
0x4003.0000	0x4003.0FFF	Timer 0	553
0x4003.1000	0x4003.1FFF	Timer 1	553
0x4003.2000	0x4003.2FFF	Timer 2	553
0x4003.3000	0x4003.3FFF	Timer 3	553
0x4003.4000	0x4003.7FFF	Reserved	-
0x4003.8000	0x4003.8FFF	ADC0	631
0x4003.9000	0x4003.9FFF	ADC1	631
0x4003.A000	0x4003.BFFF	Reserved	-
0x4003.C000	0x4003.CFFF	Analog Comparators	1122
0x4003.D000	0x4003.DFFF	GPIO Port J	419
0x4003.E000	0x4003.FFFF	Reserved	-
0x4004.0000	0x4004.0FFF	CAN0 Controller	891
0x4004.1000	0x4004.1FFF	CAN1 Controller	891
0x4004.2000	0x4004.7FFF	Reserved	-
0x4004.8000	0x4004.8FFF	Ethernet Controller	936
0x4004.9000	0x4004.FFFF	Reserved	-
0x4005.0000	0x4005.0FFF	USB	1010
0x4005.1000	0x4005.3FFF	Reserved	-
0x4005.4000	0x4005.4FFF	l <sup>2</sup> S0	846
0x4005.5000	0x4005.7FFF	Reserved	-

Table 2-4. Memory Map (continued)

Start	End	Description	For details, see page
0x4005.8000	0x4005.8FFF	GPIO Port A (AHB aperture)	419
0x4005.9000	0x4005.9FFF	GPIO Port B (AHB aperture)	419
0x4005.A000	0x4005.AFFF	GPIO Port C (AHB aperture)	419
0x4005.B000	0x4005.BFFF	GPIO Port D (AHB aperture)	419
0x4005.C000	0x4005.CFFF	GPIO Port E (AHB aperture)	419
0x4005.D000	0x4005.DFFF	GPIO Port F (AHB aperture)	419
0x4005.E000	0x4005.EFFF	GPIO Port G (AHB aperture)	419
0x4005.F000	0x4005.FFFF	GPIO Port H (AHB aperture)	419
0x4006.0000	0x4006.0FFF	GPIO Port J (AHB aperture)	419
0x4006.1000	0x400C.FFFF	Reserved	-
0x400D.0000	0x400D.0FFF	EPI 0	493
0x400D.1000	0x400F.CFFF	Reserved	-
0x400F.D000	0x400F.DFFF	Flash memory control	310
0x400F.E000	0x400F.EFFF	System control	209
0x400F.F000	0x400F.FFFF	μDMA	368
0x4010.0000	0x41FF.FFFF	Reserved	-
0x4200.0000	0x43FF.FFFF	Bit-banded alias of 0x4000.0000 through 0x400F.FFFF	-
0x4400.0000	0x5FFF.FFFF	Reserved	-
0x6000.0000	0xDFFF.FFFF	EPI0 mapped peripheral and RAM	-
Private Peripheral Bus	S		
0xE000.0000	0xE000.0FFF	Instrumentation Trace Macrocell (ITM)	73
0xE000.1000	0xE000.1FFF	Data Watchpoint and Trace (DWT)	73
0xE000.2000	0xE000.2FFF	Flash Patch and Breakpoint (FPB)	73
0xE000.3000	0xE000.DFFF	Reserved	-
0xE000.E000	0xE000.EFFF	Cortex-M3 Peripherals (SysTick, NVIC, MPU and SCB)	122
0xE000.F000	0xE003.FFFF	Reserved	-
0xE004.0000	0xE004.0FFF	Trace Port Interface Unit (TPIU)	74
0xE004.1000	0xFFFF.FFFF	Reserved	-

## 2.4.1 Memory Regions, Types and Attributes

The memory map and the programming of the MPU split the memory map into regions. Each region has a defined memory type, and some regions have additional memory attributes. The memory type and attributes determine the behavior of accesses to the region.

The memory types are:

- Normal: The processor can re-order transactions for efficiency and perform speculative reads.
- Device: The processor preserves transaction order relative to other transactions to Device or Strongly Ordered memory.
- Strongly Ordered: The processor preserves transaction order relative to all other transactions.

The different ordering requirements for Device and Strongly Ordered memory mean that the memory system can buffer a write to Device memory but must not buffer a write to Strongly Ordered memory.

An additional memory attribute is Execute Never (XN), which means the processor prevents instruction accesses. A fault exception is generated only on execution of an instruction executed from an XN region.

## 2.4.2 Memory System Ordering of Memory Accesses

For most memory accesses caused by explicit memory access instructions, the memory system does not guarantee that the order in which the accesses complete matches the program order of the instructions, providing the order does not affect the behavior of the instruction sequence. Normally, if correct program execution depends on two memory accesses completing in program order, software must insert a memory barrier instruction between the memory access instructions (see "Software Ordering of Memory Accesses" on page 94).

However, the memory system does guarantee ordering of accesses to Device and Strongly Ordered memory. For two memory access instructions A1 and A2, if both A1 and A2 are accesses to either Device or Strongly Ordered memory, and if A1 occurs before A2 in program order, A1 is always observed before A2.

### 2.4.3 Behavior of Memory Accesses

Table 2-5 on page 93 shows the behavior of accesses to each region in the memory map. See "Memory Regions, Types and Attributes" on page 92 for more information on memory types and the XN attribute. Stellaris devices may have reserved memory areas within the address ranges shown below (refer to Table 2-4 on page 90 for more information).

<b>Table 2-5.</b>	Memory	y Access	<b>Behavior</b>
-------------------	--------	----------	-----------------

Address Range	Memory Region	Memory Type	Execute Never (XN)	Description
0x0000.0000 - 0x1FFF.FFF	Code	Normal	-	This executable region is for program code. Data can also be stored here.
0x2000.0000 - 0x3FFF.FFFF	SRAM	Normal	-	This executable region is for data. Code can also be stored here. This region includes bit band and bit band alias areas (see Table 2-6 on page 95).
0x4000.0000 - 0x5FFF.FFFF	Peripheral	Device	XN	This region includes bit band and bit band alias areas (see Table 2-7 on page 95).
0x6000.0000 - 0x9FFF.FFFF	External RAM	Normal	-	This executable region is for data.
0xA000.0000 - 0xDFFF.FFFF	External device	Device	XN	This region is for external device memory.
0xE000.0000- 0xE00F.FFFF	Private peripheral bus	Strongly Ordered	XN	This region includes the NVIC, system timer, and system control block.
0xE010.0000- 0xFFFF.FFFF	Reserved	-	_	-

The Code, SRAM, and external RAM regions can hold programs. However, it is recommended that programs always use the Code region because the Cortex-M3 has separate buses that can perform instruction fetches and data accesses simultaneously.

The MPU can override the default memory access behavior described in this section. For more information, see "Memory Protection Unit (MPU)" on page 117.

The Cortex-M3 prefetches instructions ahead of execution and speculatively prefetches from branch target addresses.

### 2.4.4 Software Ordering of Memory Accesses

The order of instructions in the program flow does not always guarantee the order of the corresponding memory transactions for the following reasons:

- The processor can reorder some memory accesses to improve efficiency, providing this does not affect the behavior of the instruction sequence.
- The processor has multiple bus interfaces.
- Memory or devices in the memory map have different wait states.
- Some memory accesses are buffered or speculative.

"Memory System Ordering of Memory Accesses" on page 93 describes the cases where the memory system guarantees the order of memory accesses. Otherwise, if the order of memory accesses is critical, software must include memory barrier instructions to force that ordering. The Cortex-M3 has the following memory barrier instructions:

- The Data Memory Barrier (DMB) instruction ensures that outstanding memory transactions complete before subsequent memory transactions.
- The Data Synchronization Barrier (DSB) instruction ensures that outstanding memory transactions complete before subsequent instructions execute.
- The Instruction Synchronization Barrier (ISB) instruction ensures that the effect of all completed memory transactions is recognizable by subsequent instructions.

Memory barrier instructions can be used in the following situations:

- MPU programming
  - If the MPU settings are changed and the change must be effective on the very next instruction, use a DSB instruction to ensure the effect of the MPU takes place immediately at the end of context switching.
  - Use an ISB instruction to ensure the new MPU setting takes effect immediately after
    programming the MPU region or regions, if the MPU configuration code was accessed using
    a branch or call. If the MPU configuration code is entered using exception mechanisms, then
    an ISB instruction is not required.

#### Vector table

If the program changes an entry in the vector table and then enables the corresponding exception, use a DMB instruction between the operations. The DMB instruction ensures that if the exception is taken immediately after being enabled, the processor uses the new exception vector.

Self-modifying code

If a program contains self-modifying code, use an ISB instruction immediately after the code modification in the program. The ISB instruction ensures subsequent instruction execution uses the updated program.

Memory map switching

If the system contains a memory map switching mechanism, use a DSB instruction after switching the memory map in the program. The DSB instruction ensures subsequent instruction execution uses the updated memory map.

Dynamic exception priority change

When an exception priority has to change when the exception is pending or active, use DSB instructions after the change. The change then takes effect on completion of the DSB instruction.

Memory accesses to Strongly Ordered memory, such as the System Control Block, do not require the use of DMB instructions.

For more information on the memory barrier instructions, see the *Cortex™-M3/M4 Instruction Set Technical User's Manual*.

### 2.4.5 Bit-Banding

A bit-band region maps each word in a bit-band alias region to a single bit in the bit-band region. The bit-band regions occupy the lowest 1 MB of the SRAM and peripheral memory regions. Accesses to the 32-MB SRAM alias region map to the 1-MB SRAM bit-band region, as shown in Table 2-6 on page 95. Accesses to the 32-MB peripheral alias region map to the 1-MB peripheral bit-band region, as shown in Table 2-7 on page 95. For the specific address range of the bit-band regions, see Table 2-4 on page 90.

**Note:** A word access to the SRAM or the peripheral bit-band alias region maps to a single bit in the SRAM or peripheral bit-band region.

A word access to a bit band address results in a word access to the underlying memory, and similarly for halfword and byte accesses. This allows bit band accesses to match the access requirements of the underlying peripheral.

Table 2-6. SRAM Memory Bit-Banding Regions

Address Range		Memory Region	Instruction and Data Accesses
Start	End	Memory Region	ilistruction and Data Accesses
0x2000.0000	0x2001.FFFF	SRAM bit-band region	Direct accesses to this memory range behave as SRAM memory accesses, but this region is also bit addressable through bit-band alias.
0x2200.0000	0x222F.FFFF	SRAM bit-band alias	Data accesses to this region are remapped to bit band region. A write operation is performed as read-modify-write. Instruction accesses are not remapped.

Table 2-7. Peripheral Memory Bit-Banding Regions

Address Range		- Memory Region	Instruction and Data Accesses	
Start	End	- Memory Region	instruction and Data Accesses	
0x4000.0000	0x400F.FFFF	Peripheral bit-band region	Direct accesses to this memory range behave as peripheral memory accesses, but this region is also bit addressable through bit-band alias.	
0x4200.0000	0x43FF.FFFF	Peripheral bit-band alias	Data accesses to this region are remapped to bit band region. A write operation is performed as read-modify-write. Instruction accesses are not permitted.	

The following formula shows how the alias region maps onto the bit-band region:

bit\_word\_offset = (byte\_offset x 32) + (bit\_number x 4)

```
bit_word_addr = bit_band_base + bit_word_offset
```

where:

#### bit\_word\_offset

The position of the target bit in the bit-band memory region.

#### bit word addr

The address of the word in the alias memory region that maps to the targeted bit.

#### bit band base

The starting address of the alias region.

#### byte offset

The number of the byte in the bit-band region that contains the targeted bit.

#### bit number

The bit position, 0-7, of the targeted bit.

Figure 2-4 on page 97 shows examples of bit-band mapping between the SRAM bit-band alias region and the SRAM bit-band region:

■ The alias word at 0x23FF.FFE0 maps to bit 0 of the bit-band byte at 0x200F.FFFF:

```
0x23FF.FFE0 = 0x2200.0000 + (0x000F.FFFF*32) + (0*4)
```

■ The alias word at 0x23FF.FFFC maps to bit 7 of the bit-band byte at 0x200F.FFFF:

```
0x23FF.FFFC = 0x2200.0000 + (0x000F.FFFF*32) + (7*4)
```

■ The alias word at 0x2200.0000 maps to bit 0 of the bit-band byte at 0x2000.0000:

```
0x2200.0000 = 0x2200.0000 + (0*32) + (0*4)
```

■ The alias word at 0x2200.001C maps to bit 7 of the bit-band byte at 0x2000.0000:

```
0x2200.001C = 0x2200.0000+ (0*32) + (7*4)
```




Figure 2-4. Bit-Band Mapping

### 2.4.5.1 Directly Accessing an Alias Region

Writing to a word in the alias region updates a single bit in the bit-band region.

Bit 0 of the value written to a word in the alias region determines the value written to the targeted bit in the bit-band region. Writing a value with bit 0 set writes a 1 to the bit-band bit, and writing a value with bit 0 clear writes a 0 to the bit-band bit.

Bits 31:1 of the alias word have no effect on the bit-band bit. Writing 0x01 has the same effect as writing 0xFF. Writing 0x00 has the same effect as writing 0x0E.

When reading a word in the alias region, 0x0000.0000 indicates that the targeted bit in the bit-band region is clear and 0x0000.0001 indicates that the targeted bit in the bit-band region is set.


#### 2.4.5.2 Directly Accessing a Bit-Band Region

"Behavior of Memory Accesses" on page 93 describes the behavior of direct byte, halfword, or word accesses to the bit-band regions.

#### 2.4.6 Data Storage

The processor views memory as a linear collection of bytes numbered in ascending order from zero. For example, bytes 0-3 hold the first stored word, and bytes 4-7 hold the second stored word. Data is stored in little-endian format, with the least-significant byte (Isbyte) of a word stored at the lowest-numbered byte, and the most-significant byte (msbyte) stored at the highest-numbered byte. Figure 2-5 on page 98 illustrates how data is stored.

Figure 2-5. Data Storage



### 2.4.7 Synchronization Primitives

The Cortex-M3 instruction set includes pairs of synchronization primitives which provide a non-blocking mechanism that a thread or process can use to obtain exclusive access to a memory location. Software can use these primitives to perform a guaranteed read-modify-write memory update sequence or for a semaphore mechanism.

A pair of synchronization primitives consists of:

- A Load-Exclusive instruction, which is used to read the value of a memory location and requests exclusive access to that location.
- A Store-Exclusive instruction, which is used to attempt to write to the same memory location and returns a status bit to a register. If this status bit is clear, it indicates that the thread or process gained exclusive access to the memory and the write succeeds; if this status bit is set, it indicates that the thread or process did not gain exclusive access to the memory and no write was performed.

The pairs of Load-Exclusive and Store-Exclusive instructions are:

- The word instructions LDREX and STREX
- The halfword instructions LDREXH and STREXH
- The byte instructions LDREXB and STREXB

Software must use a Load-Exclusive instruction with the corresponding Store-Exclusive instruction.

To perform an exclusive read-modify-write of a memory location, software must:

- 1. Use a Load-Exclusive instruction to read the value of the location.
- **2.** Modify the value, as required.
- **3.** Use a Store-Exclusive instruction to attempt to write the new value back to the memory location.
- 4. Test the returned status bit.

If the status bit is clear, the read-modify-write completed successfully. If the status bit is set, no write was performed, which indicates that the value returned at step 1 might be out of date. The software must retry the entire read-modify-write sequence.

Software can use the synchronization primitives to implement a semaphore as follows:

- 1. Use a Load-Exclusive instruction to read from the semaphore address to check whether the semaphore is free.
- 2. If the semaphore is free, use a Store-Exclusive to write the claim value to the semaphore address.
- **3.** If the returned status bit from step 2 indicates that the Store-Exclusive succeeded, then the software has claimed the semaphore. However, if the Store-Exclusive failed, another process might have claimed the semaphore after the software performed step 1.

The Cortex-M3 includes an exclusive access monitor that tags the fact that the processor has executed a Load-Exclusive instruction. The processor removes its exclusive access tag if:

- It executes a CLREX instruction.
- It executes a Store-Exclusive instruction, regardless of whether the write succeeds.
- An exception occurs, which means the processor can resolve semaphore conflicts between different threads.

For more information about the synchronization primitive instructions, see the *Cortex*™-*M3/M4 Instruction Set Technical User's Manual.* 

# 2.5 Exception Model

The ARM Cortex-M3 processor and the Nested Vectored Interrupt Controller (NVIC) prioritize and handle all exceptions in Handler Mode. The processor state is automatically stored to the stack on an exception and automatically restored from the stack at the end of the Interrupt Service Routine (ISR). The vector is fetched in parallel to the state saving, enabling efficient interrupt entry. The processor supports tail-chaining, which enables back-to-back interrupts to be performed without the overhead of state saving and restoration.

Table 2-8 on page 101 lists all exception types. Software can set eight priority levels on seven of these exceptions (system handlers) as well as on 53 interrupts (listed in Table 2-9 on page 102).

Priorities on the system handlers are set with the NVIC **System Handler Priority n (SYSPRIn)** registers. Interrupts are enabled through the NVIC **Interrupt Set Enable n (ENn)** register and prioritized with the NVIC **Interrupt Priority n (PRIn)** registers. Priorities can be grouped by splitting priority levels into preemption priorities and subpriorities. All the interrupt registers are described in "Nested Vectored Interrupt Controller (NVIC)" on page 115.

Internally, the highest user-programmable priority (0) is treated as fourth priority, after a Reset, Non-Maskable Interrupt (NMI), and a Hard Fault, in that order. Note that 0 is the default priority for all the programmable priorities.

Important: After a write to clear an interrupt source, it may take several processor cycles for the NVIC to see the interrupt source de-assert. Thus if the interrupt clear is done as the last action in an interrupt handler, it is possible for the interrupt handler to complete while the NVIC sees the interrupt as still asserted, causing the interrupt handler to be re-entered errantly. This situation can be avoided by either clearing the interrupt source at the beginning of the interrupt handler or by performing a read or write after the write to clear the interrupt source (and flush the write buffer).

See "Nested Vectored Interrupt Controller (NVIC)" on page 115 for more information on exceptions and interrupts.

## 2.5.1 Exception States

Each exception is in one of the following states:

- **Inactive.** The exception is not active and not pending.
- **Pending.** The exception is waiting to be serviced by the processor. An interrupt request from a peripheral or from software can change the state of the corresponding interrupt to pending.
- **Active.** An exception that is being serviced by the processor but has not completed.

**Note:** An exception handler can interrupt the execution of another exception handler. In this case, both exceptions are in the active state.

■ **Active and Pending.** The exception is being serviced by the processor, and there is a pending exception from the same source.

## 2.5.2 Exception Types

The exception types are:

- Reset. Reset is invoked on power up or a warm reset. The exception model treats reset as a special form of exception. When reset is asserted, the operation of the processor stops, potentially at any point in an instruction. When reset is deasserted, execution restarts from the address provided by the reset entry in the vector table. Execution restarts as privileged execution in Thread mode.
- NMI. A non-maskable Interrupt (NMI) can be signaled using the NMI signal or triggered by software using the Interrupt Control and State (INTCTRL) register. This exception has the highest priority other than reset. NMI is permanently enabled and has a fixed priority of -2. NMIs cannot be masked or prevented from activation by any other exception or preempted by any exception other than reset.
- Hard Fault. A hard fault is an exception that occurs because of an error during exception processing, or because an exception cannot be managed by any other exception mechanism. Hard faults have a fixed priority of -1, meaning they have higher priority than any exception with configurable priority.
- Memory Management Fault. A memory management fault is an exception that occurs because of a memory protection related fault, including access violation and no match. The MPU or the fixed memory protection constraints determine this fault, for both instruction and data memory transactions. This fault is used to abort instruction accesses to Execute Never (XN) memory regions, even if the MPU is disabled.
- **Bus Fault.** A bus fault is an exception that occurs because of a memory-related fault for an instruction or data memory transaction such as a prefetch fault or a memory access fault. This fault can be enabled or disabled.
- **Usage Fault.** A usage fault is an exception that occurs because of a fault related to instruction execution, such as:
  - An undefined instruction
  - An illegal unaligned access
  - Invalid state on instruction execution

An error on exception return

An unaligned address on a word or halfword memory access or division by zero can cause a usage fault when the core is properly configured.

- **SVCall.** A supervisor call (SVC) is an exception that is triggered by the SVC instruction. In an OS environment, applications can use SVC instructions to access OS kernel functions and device drivers.
- **Debug Monitor.** This exception is caused by the debug monitor (when not halting). This exception is only active when enabled. This exception does not activate if it is a lower priority than the current activation.
- **PendSV.** PendSV is a pendable, interrupt-driven request for system-level service. In an OS environment, use PendSV for context switching when no other exception is active. PendSV is triggered using the **Interrupt Control and State (INTCTRL)** register.
- SysTick. A SysTick exception is an exception that the system timer generates when it reaches zero when it is enabled to generate an interrupt. Software can also generate a SysTick exception using the Interrupt Control and State (INTCTRL) register. In an OS environment, the processor can use this exception as system tick.
- Interrupt (IRQ). An interrupt, or IRQ, is an exception signaled by a peripheral or generated by a software request and fed through the NVIC (prioritized). All interrupts are asynchronous to instruction execution. In the system, peripherals use interrupts to communicate with the processor. Table 2-9 on page 102 lists the interrupts on the LM3S9D96 controller.

For an asynchronous exception, other than reset, the processor can execute another instruction between when the exception is triggered and when the processor enters the exception handler.

Privileged software can disable the exceptions that Table 2-8 on page 101 shows as having configurable priority (see the **SYSHNDCTRL** register on page 158 and the **DIS0** register on page 131).

For more information about hard faults, memory management faults, bus faults, and usage faults, see "Fault Handling" on page 107.

Table 2-8. Exception Types

Exception Type	Vector Number	Priority <sup>a</sup>	Vector Address or Offset <sup>b</sup>	Activation
-	0	-	0x0000.0000	Stack top is loaded from the first entry of the vector table on reset.
Reset	1	-3 (highest)	0x0000.0004	Asynchronous
Non-Maskable Interrupt (NMI)	2	-2	0x0000.0008	Asynchronous
Hard Fault	3	-1	0x0000.000C	-
Memory Management	4	programmable <sup>c</sup>	0x0000.0010	Synchronous
Bus Fault	5	programmable <sup>c</sup>	0x0000.0014	Synchronous when precise and asynchronous when imprecise
Usage Fault	6	programmable <sup>c</sup>	0x0000.0018	Synchronous
-	7-10	-	-	Reserved
SVCall	11	programmable <sup>c</sup>	0x0000.002C	Synchronous
Debug Monitor	12	programmable <sup>c</sup>	0x0000.0030	Synchronous
-	13	-	-	Reserved

Table 2-8. Exception Types (continued)

Exception Type	Vector Number	Priority <sup>a</sup>	Vector Address or Offset <sup>b</sup>	Activation
PendSV	14	programmable <sup>c</sup>	0x0000.0038	Asynchronous
SysTick	15	programmable <sup>c</sup>	0x0000.003C	Asynchronous
Interrupts	16 and above	programmable <sup>d</sup>	0x0000.0040 and above	Asynchronous

a. 0 is the default priority for all the programmable priorities.

Table 2-9. Interrupts

Vector Number	Interrupt Number (Bit in Interrupt Registers)	Vector Address or Offset	Description
0-15	-	0x0000.0000 - 0x0000.003C	Processor exceptions
16	0	0x0000.0040	GPIO Port A
17	1	0x0000.0044	GPIO Port B
18	2	0x0000.0048	GPIO Port C
19	3	0x0000.004C	GPIO Port D
20	4	0x0000.0050	GPIO Port E
21	5	0x0000.0054	UART0
22	6	0x0000.0058	UART1
23	7	0x0000.005C	SSI0
24	8	0x0000.0060	I <sup>2</sup> C0
25	9	0x0000.0064	PWM Fault
26	10	0x0000.0068	PWM Generator 0
27	11	0x0000.006C	PWM Generator 1
28	12	0x0000.0070	PWM Generator 2
29	13	0x0000.0074	QEI0
30	14	0x0000.0078	ADC0 Sequence 0
31	15	0x0000.007C	ADC0 Sequence 1
32	16	0x0000.0080	ADC0 Sequence 2
33	17	0x0000.0084	ADC0 Sequence 3
34	18	0x0000.0088	Watchdog Timers 0 and 1
35	19	0x0000.008C	Timer 0A
36	20	0x0000.0090	Timer 0B
37	21	0x0000.0094	Timer 1A
38	22	0x0000.0098	Timer 1B
39	23	0x0000.009C	Timer 2A
40	24	0x0000.00A0	Timer 2B
41	25	0x0000.00A4	Analog Comparator 0
42	26	0x0000.00A8	Analog Comparator 1
43	27	0x0000.00AC	Analog Comparator 2
44	28	0x0000.00B0	System Control

b. See "Vector Table" on page 103.

c. See SYSPRI1 on page 155.

d. See **PRIn** registers on page 139.

Table 2-9. Interrupts (continued)

Vector Number	Interrupt Number (Bit in Interrupt Registers)	Vector Address or Offset	Description
45	29	0x0000.00B4	Flash Memory Control
46	30	0x0000.00B8	GPIO Port F
47	31	0x0000.00BC	GPIO Port G
48	32	0x0000.00C0	GPIO Port H
49	33	0x0000.00C4	UART2
50	34	0x0000.00C8	SSI1
51	35	0x0000.00CC	Timer 3A
52	36	0x0000.00D0	Timer 3B
53	37	0x0000.00D4	I <sup>2</sup> C1
54	38	0x0000.00D8	QEI1
55	39	0x0000.00DC	CAN0
56	40	0x0000.00E0	CAN1
57	41	-	Reserved
58	42	0x0000.00E8	Ethernet Controller
59	43	-	Reserved
60	44	0x0000.00F0	USB
61	45	0x0000.00F4	PWM Generator 3
62	46	0x0000.00F8	μDMA Software
63	47	0x0000.00FC	μDMA Error
64	48	0x0000.0100	ADC1 Sequence 0
65	49	0x0000.0104	ADC1 Sequence 1
66	50	0x0000.0108	ADC1 Sequence 2
67	51	0x0000.010C	ADC1 Sequence 3
68	52	0x0000.0110	I <sup>2</sup> S0
69	53	0x0000.0114	EPI
70	54	0x0000.0118	GPIO Port J

## 2.5.3 Exception Handlers

The processor handles exceptions using:

- Interrupt Service Routines (ISRs). Interrupts (IRQx) are the exceptions handled by ISRs.
- Fault Handlers. Hard fault, memory management fault, usage fault, and bus fault are fault exceptions handled by the fault handlers.
- **System Handlers.** NMI, PendSV, SVCall, SysTick, and the fault exceptions are all system exceptions that are handled by system handlers.

#### 2.5.4 Vector Table

The vector table contains the reset value of the stack pointer and the start addresses, also called exception vectors, for all exception handlers. The vector table is constructed using the vector address or offset shown in Table 2-8 on page 101. Figure 2-6 on page 104 shows the order of the exception

vectors in the vector table. The least-significant bit of each vector must be 1, indicating that the exception handler is Thumb code

Figure 2-6. Vector Table

Exception number	IRQ number	Offset	Vector
70	54	0x0118	IRQ54
18 17 16 15 14 13 12 11 10 9	2 1 0 -1 -2	0x0118 0x004C 0x0048 0x0044 0x0040 0x003C 0x003S	IRQ2 IRQ1 IRQ0 Systick PendSV Reserved Reserved for Debug SVCall
7 6 5 4 3 2	-10 -11 -12 -13 -14	0x0018 0x0014 0x0010 0x000C 0x0008 0x0004 0x0000	Usage fault  Bus fault  Memory management fault  Hard fault  NMI  Reset  Initial SP value

On system reset, the vector table is fixed at address 0x0000.0000. Privileged software can write to the **Vector Table Offset (VTABLE)** register to relocate the vector table start address to a different memory location, in the range 0x0000.0200 to 0x3FFF.FE00 (see "Vector Table" on page 103). Note that when configuring the **VTABLE** register, the offset must be aligned on a 512-byte boundary.

#### 2.5.5 Exception Priorities

As Table 2-8 on page 101 shows, all exceptions have an associated priority, with a lower priority value indicating a higher priority and configurable priorities for all exceptions except Reset, Hard fault, and NMI. If software does not configure any priorities, then all exceptions with a configurable priority have a priority of 0. For information about configuring exception priorities, see page 155 and page 139.

**Note:** Configurable priority values for the Stellaris implementation are in the range 0-7. This means that the Reset, Hard fault, and NMI exceptions, with fixed negative priority values, always have higher priority than any other exception.

For example, assigning a higher priority value to IRQ[0] and a lower priority value to IRQ[1] means that IRQ[1] has higher priority than IRQ[0]. If both IRQ[1] and IRQ[0] are asserted, IRQ[1] is processed before IRQ[0].

If multiple pending exceptions have the same priority, the pending exception with the lowest exception number takes precedence. For example, if both IRQ[0] and IRQ[1] are pending and have the same priority, then IRQ[0] is processed before IRQ[1].

When the processor is executing an exception handler, the exception handler is preempted if a higher priority exception occurs. If an exception occurs with the same priority as the exception being handled, the handler is not preempted, irrespective of the exception number. However, the status of the new interrupt changes to pending.

### 2.5.6 Interrupt Priority Grouping

To increase priority control in systems with interrupts, the NVIC supports priority grouping. This grouping divides each interrupt priority register entry into two fields:

- An upper field that defines the group priority
- A lower field that defines a subpriority within the group

Only the group priority determines preemption of interrupt exceptions. When the processor is executing an interrupt exception handler, another interrupt with the same group priority as the interrupt being handled does not preempt the handler.

If multiple pending interrupts have the same group priority, the subpriority field determines the order in which they are processed. If multiple pending interrupts have the same group priority and subpriority, the interrupt with the lowest IRQ number is processed first.

For information about splitting the interrupt priority fields into group priority and subpriority, see page 149.

## 2.5.7 Exception Entry and Return

Descriptions of exception handling use the following terms:

- **Preemption.** When the processor is executing an exception handler, an exception can preempt the exception handler if its priority is higher than the priority of the exception being handled. See "Interrupt Priority Grouping" on page 105 for more information about preemption by an interrupt. When one exception preempts another, the exceptions are called nested exceptions. See "Exception Entry" on page 106 more information.
- Return. Return occurs when the exception handler is completed, and there is no pending exception with sufficient priority to be serviced and the completed exception handler was not handling a late-arriving exception. The processor pops the stack and restores the processor state to the state it had before the interrupt occurred. See "Exception Return" on page 107 for more information.
- **Tail-Chaining.** This mechanism speeds up exception servicing. On completion of an exception handler, if there is a pending exception that meets the requirements for exception entry, the stack pop is skipped and control transfers to the new exception handler.
- Late-Arriving. This mechanism speeds up preemption. If a higher priority exception occurs during state saving for a previous exception, the processor switches to handle the higher priority exception and initiates the vector fetch for that exception. State saving is not affected by late

arrival because the state saved is the same for both exceptions. Therefore, the state saving continues uninterrupted. The processor can accept a late arriving exception until the first instruction of the exception handler of the original exception enters the execute stage of the processor. On return from the exception handler of the late-arriving exception, the normal tail-chaining rules apply.

### 2.5.7.1 Exception Entry

Exception entry occurs when there is a pending exception with sufficient priority and either the processor is in Thread mode or the new exception is of higher priority than the exception being handled, in which case the new exception preempts the original exception.

When one exception preempts another, the exceptions are nested.

Sufficient priority means the exception has more priority than any limits set by the mask registers (see **PRIMASK** on page 86, **FAULTMASK** on page 87, and **BASEPRI** on page 88). An exception with less priority than this is pending but is not handled by the processor.

When the processor takes an exception, unless the exception is a tail-chained or a late-arriving exception, the processor pushes information onto the current stack. This operation is referred to as *stacking* and the structure of eight data words is referred to as *stack frame*.

Figure 2-7. Exception Stack Frame

Immediately after stacking, the stack pointer indicates the lowest address in the stack frame.

The stack frame includes the return address, which is the address of the next instruction in the interrupted program. This value is restored to the **PC** at exception return so that the interrupted program resumes.

In parallel to the stacking operation, the processor performs a vector fetch that reads the exception handler start address from the vector table. When stacking is complete, the processor starts executing the exception handler. At the same time, the processor writes an EXC\_RETURN value to the **LR**, indicating which stack pointer corresponds to the stack frame and what operation mode the processor was in before the entry occurred.

If no higher-priority exception occurs during exception entry, the processor starts executing the exception handler and automatically changes the status of the corresponding pending interrupt to active.

If another higher-priority exception occurs during exception entry, known as late arrival, the processor starts executing the exception handler for this exception and does not change the pending status of the earlier exception.

#### 2.5.7.2 Exception Return

Exception return occurs when the processor is in Handler mode and executes one of the following instructions to load the EXC\_RETURN value into the **PC**:

- An LDM or POP instruction that loads the PC
- A BX instruction using any register
- An LDR instruction with the **PC** as the destination

EXC\_RETURN is the value loaded into the **LR** on exception entry. The exception mechanism relies on this value to detect when the processor has completed an exception handler. The lowest four bits of this value provide information on the return stack and processor mode. Table 2-10 on page 107 shows the EXC\_RETURN values with a description of the exception return behavior.

EXC\_RETURN bits 31:4 are all set. When this value is loaded into the **PC**, it indicates to the processor that the exception is complete, and the processor initiates the appropriate exception return sequence.

Table 2-10. Exception Return Behavior

EXC_RETURN[31:0]	Description
0xFFFF.FFF0	Reserved
0xFFFF.FFF1	Return to Handler mode.
	Exception return uses state from MSP.
	Execution uses MSP after return.
0xFFFF.FFF2 - 0xFFFF.FFF8	Reserved
0xFFFF.FFF9	Return to Thread mode.
	Exception return uses state from MSP.
	Execution uses MSP after return.
0xFFFF.FFFA - 0xFFFF.FFFC	Reserved
0xFFFF.FFFD	Return to Thread mode.
	Exception return uses state from PSP.
	Execution uses <b>PSP</b> after return.
0xFFFF.FFFE - 0xFFFF.FFFF	Reserved

# 2.6 Fault Handling

Faults are a subset of the exceptions (see "Exception Model" on page 99). The following conditions generate a fault:

- A bus error on an instruction fetch or vector table load or a data access.
- An internally detected error such as an undefined instruction or an attempt to change state with a BX instruction.
- Attempting to execute an instruction from a memory region marked as Non-Executable (XN).
- An MPU fault because of a privilege violation or an attempt to access an unmanaged region.

# 2.6.1 Fault Types

Table 2-11 on page 108 shows the types of fault, the handler used for the fault, the corresponding fault status register, and the register bit that indicates the fault has occurred. See page 162 for more information about the fault status registers.

Table 2-11. Faults

Fault	Handler	Fault Status Register	Bit Name
Bus error on a vector read	Hard fault	Hard Fault Status (HFAULTSTAT)	VECT
Fault escalated to a hard fault	Hard fault	Hard Fault Status (HFAULTSTAT)	FORCED
MPU or default memory mismatch on instruction access	Memory management fault	Memory Management Fault Status (MFAULTSTAT)	IERR <sup>a</sup>
MPU or default memory mismatch on data access	Memory management fault	Memory Management Fault Status (MFAULTSTAT)	DERR
MPU or default memory mismatch on exception stacking	Memory management fault	Memory Management Fault Status (MFAULTSTAT)	MSTKE
MPU or default memory mismatch on exception unstacking	Memory management fault	Memory Management Fault Status (MFAULTSTAT)	MUSTKE
Bus error during exception stacking	Bus fault	Bus Fault Status (BFAULTSTAT)	BSTKE
Bus error during exception unstacking	Bus fault	Bus Fault Status (BFAULTSTAT)	BUSTKE
Bus error during instruction prefetch	Bus fault	Bus Fault Status (BFAULTSTAT)	IBUS
Precise data bus error	Bus fault	Bus Fault Status (BFAULTSTAT)	PRECISE
Imprecise data bus error	Bus fault	Bus Fault Status (BFAULTSTAT)	IMPRE
Attempt to access a coprocessor	Usage fault	Usage Fault Status (UFAULTSTAT)	NOCP
Undefined instruction	Usage fault	Usage Fault Status (UFAULTSTAT)	UNDEF
Attempt to enter an invalid instruction set state <sup>b</sup>	Usage fault	Usage Fault Status (UFAULTSTAT)	INVSTAT
Invalid EXC_RETURN value	Usage fault	Usage Fault Status (UFAULTSTAT)	INVPC
Illegal unaligned load or store	Usage fault	Usage Fault Status (UFAULTSTAT)	UNALIGN
Divide by 0	Usage fault	Usage Fault Status (UFAULTSTAT)	DIV0

a. Occurs on an access to an XN region even if the MPU is disabled.

#### 2.6.2 Fault Escalation and Hard Faults

All fault exceptions except for hard fault have configurable exception priority (see **SYSPRI1** on page 155). Software can disable execution of the handlers for these faults (see **SYSHNDCTRL** on page 158).

Usually, the exception priority, together with the values of the exception mask registers, determines whether the processor enters the fault handler, and whether a fault handler can preempt another fault handler as described in "Exception Model" on page 99.

In some situations, a fault with configurable priority is treated as a hard fault. This process is called priority escalation, and the fault is described as *escalated to hard fault*. Escalation to hard fault occurs when:

A fault handler causes the same kind of fault as the one it is servicing. This escalation to hard fault occurs because a fault handler cannot preempt itself because it must have the same priority as the current priority level.

b. Attempting to use an instruction set other than the Thumb instruction set, or returning to a non load-store-multiple instruction with ICI continuation.

- A fault handler causes a fault with the same or lower priority as the fault it is servicing. This situation happens because the handler for the new fault cannot preempt the currently executing fault handler.
- An exception handler causes a fault for which the priority is the same as or lower than the currently executing exception.
- A fault occurs and the handler for that fault is not enabled.

If a bus fault occurs during a stack push when entering a bus fault handler, the bus fault does not escalate to a hard fault. Thus if a corrupted stack causes a fault, the fault handler executes even though the stack push for the handler failed. The fault handler operates but the stack contents are corrupted.

**Note:** Only Reset and NMI can preempt the fixed priority hard fault. A hard fault can preempt any exception other than Reset, NMI, or another hard fault.

## 2.6.3 Fault Status Registers and Fault Address Registers

The fault status registers indicate the cause of a fault. For bus faults and memory management faults, the fault address register indicates the address accessed by the operation that caused the fault, as shown in Table 2-12 on page 109.

Table 2-12. Fault Status and Fault Address Registers

Handler	Status Register Name	Address Register Name	Register Description
Hard fault	Hard Fault Status (HFAULTSTAT)	-	page 168
Memory management	Memory Management Fault Status	Memory Management Fault	page 162
fault	(MFAULTSTAT)	Address (MMADDR)	page 169
Bus fault	Bus Fault Status (BFAULTSTAT)	Bus Fault Address	page 162
		(FAULTADDR)	page 170
Usage fault	Usage Fault Status (UFAULTSTAT)	-	page 162

### 2.6.4 **Lockup**

The processor enters a lockup state if a hard fault occurs when executing the NMI or hard fault handlers. When the processor is in the lockup state, it does not execute any instructions. The processor remains in lockup state until it is reset, an NMI occurs, or it is halted by a debugger.

**Note:** If the lockup state occurs from the NMI handler, a subsequent NMI does not cause the processor to leave the lockup state.

# 2.7 Power Management

The Cortex-M3 processor sleep modes reduce power consumption:

- Sleep mode stops the processor clock.
- Deep-sleep mode stops the system clock and switches off the PLL and Flash memory.

The SLEEPDEEP bit of the **System Control (SYSCTRL)** register selects which sleep mode is used (see page 151). For more information about the behavior of the sleep modes, see "System Control" on page 205.

This section describes the mechanisms for entering sleep mode and the conditions for waking up from sleep mode, both of which apply to Sleep mode and Deep-sleep mode.

## 2.7.1 Entering Sleep Modes

This section describes the mechanisms software can use to put the processor into one of the sleep modes.

The system can generate spurious wake-up events, for example a debug operation wakes up the processor. Therefore, software must be able to put the processor back into sleep mode after such an event. A program might have an idle loop to put the processor back to sleep mode.

## 2.7.1.1 Wait for Interrupt

The wait for interrupt instruction, WFI, causes immediate entry to sleep mode unless the wake-up condition is true (see "Wake Up from WFI or Sleep-on-Exit" on page 110). When the processor executes a WFI instruction, it stops executing instructions and enters sleep mode. See the Cortex™-M3/M4 Instruction Set Technical User's Manual for more information.

### 2.7.1.2 Wait for Event

The wait for event instruction, WFE, causes entry to sleep mode conditional on the value of a one-bit event register. When the processor executes a WFE instruction, it checks the event register. If the register is 0, the processor stops executing instructions and enters sleep mode. If the register is 1, the processor clears the register and continues executing instructions without entering sleep mode.

If the event register is 1, the processor must not enter sleep mode on execution of a WFE instruction. Typically, this situation occurs if an SEV instruction has been executed. Software cannot access this register directly.

See the Cortex™-M3/M4 Instruction Set Technical User's Manual for more information.

### 2.7.1.3 Sleep-on-Exit

If the SLEEPEXIT bit of the **SYSCTRL** register is set, when the processor completes the execution of all exception handlers, it returns to Thread mode and immediately enters sleep mode. This mechanism can be used in applications that only require the processor to run when an exception occurs.

### 2.7.2 Wake Up from Sleep Mode

The conditions for the processor to wake up depend on the mechanism that cause it to enter sleep mode.

### 2.7.2.1 Wake Up from WFI or Sleep-on-Exit

Normally, the processor wakes up only when the NVIC detects an exception with sufficient priority to cause exception entry. Some embedded systems might have to execute system restore tasks after the processor wakes up and before executing an interrupt handler. Entry to the interrupt handler can be delayed by setting the PRIMASK bit and clearing the FAULTMASK bit. If an interrupt arrives that is enabled and has a higher priority than current exception priority, the processor wakes up but does not execute the interrupt handler until the processor clears PRIMASK. For more information about **PRIMASK** and **FAULTMASK**, see page 86 and page 87.

### 2.7.2.2 Wake Up from WFE

The processor wakes up if it detects an exception with sufficient priority to cause exception entry.

In addition, if the SEVONPEND bit in the **SYSCTRL** register is set, any new pending interrupt triggers an event and wakes up the processor, even if the interrupt is disabled or has insufficient priority to cause exception entry. For more information about **SYSCTRL**, see page 151.

# 2.8 Instruction Set Summary

The processor implements a version of the Thumb instruction set. Table 2-13 on page 111 lists the supported instructions.

**Note:** In Table 2-13 on page 111:

- Angle brackets, <>, enclose alternative forms of the operand
- Braces, {}, enclose optional operands
- The Operands column is not exhaustive
- Op2 is a flexible second operand that can be either a register or a constant
- Most instructions can use an optional condition code suffix

For more information on the instructions and operands, see the instruction descriptions in the *Cortex*™-*M3/M4 Instruction Set Technical User's Manual*.

Table 2-13. Cortex-M3 Instruction Summary

Mnemonic	Operands	Brief Description	Flags
ADC, ADCS	{Rd,} Rn, Op2	Add with carry	N,Z,C,V
ADD, ADDS	{Rd,} Rn, Op2	Add	N,Z,C,V
ADD, ADDW	{Rd,} Rn , #imm12	Add	N,Z,C,V
ADR	Rd, label	Load PC-relative address	-
AND, ANDS	{Rd,} Rn, Op2	Logical AND	N,Z,C
ASR, ASRS	Rd, Rm, <rs #n></rs #n>	Arithmetic shift right	N,Z,C
В	label	Branch	-
BFC	Rd, #lsb, #width	Bit field clear	-
BFI	Rd, Rn, #lsb, #width	Bit field insert	-
BIC, BICS	{Rd,} Rn, Op2	Bit clear	N,Z,C
BKPT	#imm	Breakpoint	-
BL	label	Branch with link	-
BLX	Rm	Branch indirect with link	-
BX	Rm	Branch indirect	-
CBNZ	Rn, label	Compare and branch if non-zero	-
CBZ	Rn, label	Compare and branch if zero	
CLREX	-	Clear exclusive	-
CLZ	Rd, Rm	Count leading zeros	-
CMN	Rn, Op2	Compare negative	N,Z,C,V
CMP	Rn, Op2	Compare	N,Z,C,V
CPSID	i	Change processor state, disable interrupts	
CPSIE	i	Change processor state, enable interrupts	
DMB	-	Data memory barrier	-
DSB	-	Data synchronization barrier -	

Table 2-13. Cortex-M3 Instruction Summary (continued)

Mnemonic	Operands	Brief Description	Flags
EOR, EORS	{Rd,} Rn, Op2	Exclusive OR	N,Z,C
ISB	-	Instruction synchronization barrier	-
IT	-	If-Then condition block	-
LDM	Rn{!}, reglist	Load multiple registers, increment after	-
LDMDB, LDMEA	Rn{!}, reglist	Load multiple registers, decrement before	-
LDMFD, LDMIA	Rn{!}, reglist	Load multiple registers, increment after	-
LDR	Rt, [Rn, #offset]	Load register with word	-
LDRB, LDRBT	Rt, [Rn, #offset]	Load register with byte	-
LDRD	Rt, Rt2, [Rn, #offset]	Load register with two bytes	-
LDREX	Rt, [Rn, #offset]	Load register exclusive	-
LDREXB	Rt, [Rn]	Load register exclusive with byte	-
LDREXH	Rt, [Rn]	Load register exclusive with halfword	-
LDRH, LDRHT	Rt, [Rn, #offset]	Load register with halfword	-
LDRSB, LDRSBT	Rt, [Rn, #offset]	Load register with signed byte	-
LDRSH, LDRSHT	Rt, [Rn, #offset]	Load register with signed halfword	-
LDRT	Rt, [Rn, #offset]	Load register with word	-
LSL, LSLS	Rd, Rm, <rs #n></rs #n>	Logical shift left	N,Z,C
LSR, LSRS	Rd, Rm, <rs #n></rs #n>	Logical shift right	
MLA	Rd, Rn, Rm, Ra	Multiply with accumulate, 32-bit result	-
MLS	Rd, Rn, Rm, Ra	Multiply and subtract, 32-bit result	-
MOV, MOVS	Rd, Op2	Move	N,Z,C
MOV, MOVW	Rd, #imm16	Move 16-bit constant	N,Z,C
MOVT	Rd, #imm16	Move top	-
MRS	Rd, spec_reg	Move from special register to general register	-
MSR	spec_reg, Rm	Move from general register to special register	N,Z,C,V
MUL, MULS	{Rd,} Rn, Rm	Multiply, 32-bit result	N,Z
MVN, MVNS	Rd, Op2	Move NOT	N,Z,C
NOP	-	No operation	-
ORN, ORNS	{Rd,} Rn, Op2	Logical OR NOT	N,Z,C
ORR, ORRS	{Rd,} Rn, Op2	Logical OR	N,Z,C
POP	reglist	Pop registers from stack	-
PUSH	reglist	Push registers onto stack	
RBIT	Rd, Rn	Reverse bits	-
REV	Rd, Rn	Reverse byte order in a word	-
REV16	Rd, Rn	Reverse byte order in each halfword	-
REVSH	Rd, Rn	Reverse byte order in bottom halfword and sign extend	-
ROR, RORS	Rd, Rm, <rs #n></rs #n>	Rotate right	N,Z,C
RRX, RRXS	Rd, Rm	Rotate right with extend	N,Z,C

Table 2-13. Cortex-M3 Instruction Summary (continued)

Mnemonic	Operands	Brief Description	Flags
RSB, RSBS	{Rd,} Rn, Op2	Reverse subtract	N,Z,C,V
SBC, SBCS	{Rd,} Rn, Op2	Subtract with carry	N,Z,C,V
SBFX	Rd, Rn, #lsb, #width	Signed bit field extract	-
SDIV	{Rd,} Rn, Rm	Signed divide	-
SEV	-	Send event	-
SMLAL	RdLo, RdHi, Rn, Rm	Signed multiply with accumulate (32x32+64), 64-bit result	-
SMULL	RdLo, RdHi, Rn, Rm	Signed multiply (32x32), 64-bit result	-
SSAT	Rd, #n, Rm {,shift #s}	Signed saturate	Q
STM	Rn{!}, reglist	Store multiple registers, increment after	-
STMDB, STMEA	Rn{!}, reglist	Store multiple registers, decrement before	-
STMFD, STMIA	Rn{!}, reglist	Store multiple registers, increment after	-
STR	Rt, [Rn {, #offset}]	Store register word	-
STRB, STRBT	Rt, [Rn {, #offset}]	Store register byte	-
STRD	Rt, Rt2, [Rn {, #offset}]	Store register two words	-
STREX	Rt, Rt, [Rn {, #offset}]	Store register exclusive	-
STREXB	Rd, Rt, [Rn]	Store register exclusive byte	-
STREXH	Rd, Rt, [Rn]	Store register exclusive halfword	-
STRH, STRHT	Rt, [Rn {, #offset}]	Store register halfword	-
STRSB, STRSBT	Rt, [Rn {, #offset}]	Store register signed byte	-
STRSH, STRSHT	Rt, [Rn {, #offset}]	Store register signed halfword	-
STRT	Rt, [Rn {, #offset}]	[Rn {, #offset}] Store register word	
SUB, SUBS	{Rd,} Rn, Op2	Subtract	N,Z,C,V
SUB, SUBW	{Rd,} Rn, #imm12	Subtract 12-bit constant	N,Z,C,V
SVC	#imm	Supervisor call	-
SXTB	{Rd,} Rm {,ROR #n}	Sign extend a byte	-
SXTH	{Rd,} Rm {,ROR #n}	Sign extend a halfword	-
ГВВ	[Rn, Rm]	Table branch byte	-
ГВН	[Rn, Rm, LSL #1]	Table branch halfword	-
ΓEQ	Rn, Op2	Test equivalence	N,Z,C
rst	Rn, Op2	Test	N,Z,C
JBFX	Rd, Rn, #lsb, #width	Unsigned bit field extract	-
JDIV	{Rd,} Rn, Rm	Unsigned divide	-
JMLAL	RdLo, RdHi, Rn, Rm	Unsigned multiply with accumulate (32x32+32+32), 64-bit result	-
UMULL	RdLo, RdHi, Rn, Rm	Unsigned multiply (32x 2), 64-bit result	-
USAT	Rd, #n, Rm {,shift #s}	Unsigned Saturate	Q
JXTB	{Rd,} Rm, {,ROR #n}	Zero extend a Byte	-
JXTH	{Rd,} Rm, {,ROR #n}	·	
NFE	-	Wait for event	-
WFI	-	Wait for interrupt	-

# 3 Cortex-M3 Peripherals

This chapter provides information on the Stellaris<sup>®</sup> implementation of the Cortex-M3 processor peripherals, including:

■ SysTick (see page 114)

Provides a simple, 24-bit clear-on-write, decrementing, wrap-on-zero counter with a flexible control mechanism.

- Nested Vectored Interrupt Controller (NVIC) (see page 115)
  - Facilitates low-latency exception and interrupt handling
  - Controls power management
  - Implements system control registers
- System Control Block (SCB) (see page 117)

Provides system implementation information and system control, including configuration, control, and reporting of system exceptions.

■ Memory Protection Unit (MPU) (see page 117)

Supports the standard ARMv7 Protected Memory System Architecture (PMSA) model. The MPU provides full support for protection regions, overlapping protection regions, access permissions, and exporting memory attributes to the system.

Table 3-1 on page 114 shows the address map of the Private Peripheral Bus (PPB). Some peripheral register regions are split into two address regions, as indicated by two addresses listed.

Table 3-1. Core Peripheral Register Region	Γable 3-1. Core Pe⊦	ripheral Re	gister Regions
--	---------------------	-------------	----------------

Address	Core Peripheral	Description (see page)
0xE000.E010-0xE000.E01F	System Timer	114
0xE000.E100-0xE000.E4EF	Nested Vectored Interrupt Controller	115
0xE000.EF00-0xE000.EF03		
0xE000.E008-0xE000.E00F	System Control Block	117
0xE000.ED00-0xE000.ED3F		
0xE000.ED90-0xE000.EDB8	Memory Protection Unit	117

# 3.1 Functional Description

This chapter provides information on the Stellaris implementation of the Cortex-M3 processor peripherals: SysTick, NVIC, SCB and MPU.

## 3.1.1 System Timer (SysTick)

Cortex-M3 includes an integrated system timer, SysTick, which provides a simple, 24-bit clear-on-write, decrementing, wrap-on-zero counter with a flexible control mechanism. The counter can be used in several different ways, for example as:

- An RTOS tick timer that fires at a programmable rate (for example, 100 Hz) and invokes a SysTick routine.
- A high-speed alarm timer using the system clock.

- A variable rate alarm or signal timer—the duration is range-dependent on the reference clock used and the dynamic range of the counter.
- A simple counter used to measure time to completion and time used.
- An internal clock source control based on missing/meeting durations. The COUNT bit in the STCTRL control and status register can be used to determine if an action completed within a set duration, as part of a dynamic clock management control loop.

The timer consists of three registers:

- SysTick Control and Status (STCTRL): A control and status counter to configure its clock, enable the counter, enable the SysTick interrupt, and determine counter status.
- SysTick Reload Value (STRELOAD): The reload value for the counter, used to provide the counter's wrap value.
- SysTick Current Value (STCURRENT): The current value of the counter.

When enabled, the timer counts down on each clock from the reload value to zero, reloads (wraps) to the value in the **STRELOAD** register on the next clock edge, then decrements on subsequent clocks. Clearing the **STRELOAD** register disables the counter on the next wrap. When the counter reaches zero, the COUNT status bit is set. The COUNT bit clears on reads.

Writing to the **STCURRENT** register clears the register and the COUNT status bit. The write does not trigger the SysTick exception logic. On a read, the current value is the value of the register at the time the register is accessed.

The SysTick counter runs on the system clock. If this clock signal is stopped for low power mode, the SysTick counter stops. Ensure software uses aligned word accesses to access the SysTick registers.

**Note:** When the processor is halted for debugging, the counter does not decrement.

### 3.1.2 Nested Vectored Interrupt Controller (NVIC)

This section describes the Nested Vectored Interrupt Controller (NVIC) and the registers it uses. The NVIC supports:

- 53 interrupts.
- A programmable priority level of 0-7 for each interrupt. A higher level corresponds to a lower priority, so level 0 is the highest interrupt priority.
- Low-latency exception and interrupt handling.
- Level and pulse detection of interrupt signals.
- Dynamic reprioritization of interrupts.
- Grouping of priority values into group priority and subpriority fields.
- Interrupt tail-chaining.
- An external Non-maskable interrupt (NMI).

The processor automatically stacks its state on exception entry and unstacks this state on exception exit, with no instruction overhead, providing low latency exception handling.

## 3.1.2.1 Level-Sensitive and Pulse Interrupts

The processor supports both level-sensitive and pulse interrupts. Pulse interrupts are also described as edge-triggered interrupts.

A level-sensitive interrupt is held asserted until the peripheral deasserts the interrupt signal. Typically this happens because the ISR accesses the peripheral, causing it to clear the interrupt request. A pulse interrupt is an interrupt signal sampled synchronously on the rising edge of the processor clock. To ensure the NVIC detects the interrupt, the peripheral must assert the interrupt signal for at least one clock cycle, during which the NVIC detects the pulse and latches the interrupt.

When the processor enters the ISR, it automatically removes the pending state from the interrupt (see "Hardware and Software Control of Interrupts" on page 116 for more information). For a level-sensitive interrupt, if the signal is not deasserted before the processor returns from the ISR, the interrupt becomes pending again, and the processor must execute its ISR again. As a result, the peripheral can hold the interrupt signal asserted until it no longer needs servicing.

### 3.1.2.2 Hardware and Software Control of Interrupts

The Cortex-M3 latches all interrupts. A peripheral interrupt becomes pending for one of the following reasons:

- The NVIC detects that the interrupt signal is High and the interrupt is not active.
- The NVIC detects a rising edge on the interrupt signal.
- Software writes to the corresponding interrupt set-pending register bit, or to the **Software Trigger Interrupt (SWTRIG)** register to make a Software-Generated Interrupt pending. See the INT bit in the **PEND0** register on page 133 or **SWTRIG** on page 141.

A pending interrupt remains pending until one of the following:

- The processor enters the ISR for the interrupt, changing the state of the interrupt from pending to active. Then:
  - For a level-sensitive interrupt, when the processor returns from the ISR, the NVIC samples
    the interrupt signal. If the signal is asserted, the state of the interrupt changes to pending,
    which might cause the processor to immediately re-enter the ISR. Otherwise, the state of the
    interrupt changes to inactive.
  - For a pulse interrupt, the NVIC continues to monitor the interrupt signal, and if this is pulsed
    the state of the interrupt changes to pending and active. In this case, when the processor
    returns from the ISR the state of the interrupt changes to pending, which might cause the
    processor to immediately re-enter the ISR.
    - If the interrupt signal is not pulsed while the processor is in the ISR, when the processor returns from the ISR the state of the interrupt changes to inactive.
- Software writes to the corresponding interrupt clear-pending register bit
  - For a level-sensitive interrupt, if the interrupt signal is still asserted, the state of the interrupt does not change. Otherwise, the state of the interrupt changes to inactive.

For a pulse interrupt, the state of the interrupt changes to inactive, if the state was pending
or to active, if the state was active and pending.

## 3.1.3 System Control Block (SCB)

The System Control Block (SCB) provides system implementation information and system control, including configuration, control, and reporting of the system exceptions.

## 3.1.4 Memory Protection Unit (MPU)

This section describes the Memory protection unit (MPU). The MPU divides the memory map into a number of regions and defines the location, size, access permissions, and memory attributes of each region. The MPU supports independent attribute settings for each region, overlapping regions, and export of memory attributes to the system.

The memory attributes affect the behavior of memory accesses to the region. The Cortex-M3 MPU defines eight separate memory regions, 0-7, and a background region.

When memory regions overlap, a memory access is affected by the attributes of the region with the highest number. For example, the attributes for region 7 take precedence over the attributes of any region that overlaps region 7.

The background region has the same memory access attributes as the default memory map, but is accessible from privileged software only.

The Cortex-M3 MPU memory map is unified, meaning that instruction accesses and data accesses have the same region settings.

If a program accesses a memory location that is prohibited by the MPU, the processor generates a memory management fault, causing a fault exception and possibly causing termination of the process in an OS environment. In an OS environment, the kernel can update the MPU region setting dynamically based on the process to be executed. Typically, an embedded OS uses the MPU for memory protection.

Configuration of MPU regions is based on memory types (see "Memory Regions, Types and Attributes" on page 92 for more information).

Table 3-2 on page 117 shows the possible MPU region attributes. See the section called "MPU Configuration for a Stellaris Microcontroller" on page 121 for guidelines for programming a microcontroller implementation.

**Table 3-2. Memory Attributes Summary** 

Memory Type	Description	
Strongly Ordered	All accesses to Strongly Ordered memory occur in program order.	
Device	Memory-mapped peripherals	
Normal	Normal memory	

To avoid unexpected behavior, disable the interrupts before updating the attributes of a region that the interrupt handlers might access.

Ensure software uses aligned accesses of the correct size to access MPU registers:

- Except for the MPU Region Attribute and Size (MPUATTR) register, all MPU registers must be accessed with aligned word accesses.
- The MPUATTR register can be accessed with byte or aligned halfword or word accesses.

The processor does not support unaligned accesses to MPU registers.

When setting up the MPU, and if the MPU has previously been programmed, disable unused regions to prevent any previous region settings from affecting the new MPU setup.

#### 3.1.4.1 Updating an MPU Region

To update the attributes for an MPU region, the MPU Region Number (MPUNUMBER), MPU Region Base Address (MPUBASE) and MPUATTR registers must be updated. Each register can be programmed separately or with a multiple-word write to program all of these registers. You can use the MPUBASEx and MPUATTRx aliases to program up to four regions simultaneously using an STM instruction.

### Updating an MPU Region Using Separate Words

This example simple code configures one region:

Disable a region before writing new region settings to the MPU if you have previously enabled the region being changed. For example:

```
; R1 = region number
; R2 = size/enable
; R3 = attributes
; R4 = address
                        ; 0xE000ED98, MPU region number register ; Region Number
LDR R0,=MPUNUMBER
STR R1, [R0, #0x0]
BIC R2, R2, #1
                           ; Disable
STRH R2, [R0, #0x8]
STR R4, [R0, #0x4]
STRH R3, [R0, #0xA]
                           ; Region Size and Enable
                           ; Region Base Address
                           ; Region Attribute
ORR R2, #1
                            ; Enable
STRH R2, [R0, #0x8]
                           ; Region Size and Enable
```

Software must use memory barrier instructions:

- Before MPU setup, if there might be outstanding memory transfers, such as buffered writes, that might be affected by the change in MPU settings.
- After MPU setup, if it includes memory transfers that must use the new MPU settings.

However, memory barrier instructions are not required if the MPU setup process starts by entering an exception handler, or is followed by an exception return, because the exception entry and exception return mechanism cause memory barrier behavior.

Software does not need any memory barrier instructions during MPU setup, because it accesses the MPU through the Private Peripheral Bus (PPB), which is a Strongly Ordered memory region.

For example, if all of the memory access behavior is intended to take effect immediately after the programming sequence, then a DSB instruction and an ISB instruction should be used. A DSB is required after changing MPU settings, such as at the end of context switch. An ISB is required if the code that programs the MPU region or regions is entered using a branch or call. If the programming sequence is entered using a return from exception, or by taking an exception, then an ISB is not required.

### Updating an MPU Region Using Multi-Word Writes

The MPU can be programmed directly using multi-word writes, depending how the information is divided. Consider the following reprogramming:

```
; R1 = region number
; R2 = address
; R3 = size, attributes in one
LDR R0, =MPUNUMBER ; 0xE000ED98, MPU region number register
STR R1, [R0, #0x0] ; Region Number
STR R2, [R0, #0x4] ; Region Base Address
STR R3, [R0, #0x8] ; Region Attribute, Size and Enable
```

An STM instruction can be used to optimize this:

```
; R1 = region number
; R2 = address
; R3 = size, attributes in one
LDR R0, =MPUNUMBER ; 0xE000ED98, MPU region number register
STM R0, {R1-R3} ; Region number, address, attribute, size and enable
```

This operation can be done in two words for pre-packed information, meaning that the **MPU Region Base Address (MPUBASE)** register (see page 175) contains the required region number and has the VALID bit set. This method can be used when the data is statically packed, for example in a boot loader:

#### Subregions


Regions of 256 bytes or more are divided into eight equal-sized subregions. Set the corresponding bit in the SRD field of the **MPU Region Attribute and Size (MPUATTR)** register (see page 177) to disable a subregion. The least-significant bit of the SRD field controls the first subregion, and the most-significant bit controls the last subregion. Disabling a subregion means another region overlapping the disabled range matches instead. If no other enabled region overlaps the disabled subregion, the MPU issues a fault.

Regions of 32, 64, and 128 bytes do not support subregions. With regions of these sizes, the SRD field must be configured to  $0 \times 0.0$ , otherwise the MPU behavior is unpredictable.

### Example of SRD Use

Two regions with the same base address overlap. Region one is 128 KB, and region two is 512 KB. To ensure the attributes from region one apply to the first 128 KB region, configure the SRD field for region two to 0x03 to disable the first two subregions, as Figure 3-1 on page 120 shows.

Figure 3-1. SRD Use Example



#### 3.1.4.2 MPU Access Permission Attributes

The access permission bits, TEX, S, C, B, AP, and XN of the **MPUATTR** register, control access to the corresponding memory region. If an access is made to an area of memory without the required permissions, then the MPU generates a permission fault.

Table 3-3 on page 120 shows the encodings for the TEX, C, B, and S access permission bits. All encodings are shown for completeness, however the current implementation of the Cortex-M3 does not support the concept of cacheability or shareability. Refer to the section called "MPU Configuration for a Stellaris Microcontroller" on page 121 for information on programming the MPU for Stellaris implementations.

Table 3-3. TEX, S, C, and B Bit Field Encoding

TEX	S	С	В	Memory Type	Shareability	Other Attributes
000b	x <sup>a</sup>	0	0	Strongly Ordered	Shareable	-
000	x <sup>a</sup>	0	1	Device	Shareable	-
000	0	1	0	Normal	Not shareable	
000	1	1	0	Normal	Shareable	Outer and inner write-through. No write
000	0	1	1	Normal	Not shareable	allocate.
000	1	1	1	Normal	Shareable	
001	0	0	0	Normal	Not shareable	Outer and inner
001	1	0	0	Normal	Shareable	noncacheable.
001	x <sup>a</sup>	0	1	Reserved encoding	-	-
001	x <sup>a</sup>	1	0	Reserved encoding	-	-
001	0	1	1	Normal	Not shareable	Outer and inner
001	1	1	1	Normal	Shareable	write-back. Write and read allocate.
010	x <sup>a</sup>	0	0	Device	Not shareable	Nonshared Device.
010	x <sup>a</sup>	0	1	Reserved encoding	-	-
010	x <sup>a</sup>	1	x <sup>a</sup>	Reserved encoding	-	-

Table 3-3. TEX, S, C, and B Bit Field Encoding (continued)

TEX	s	С	В	Memory Type	Shareability	Other Attributes
1BB	0	A	A	Normal	Not shareable	Cached memory (BB =
1BB	1	А	А	Normal	Shareable	outer policy, AA = inner policy).
						See Table 3-4 for the encoding of the AA and BB bits.

a. The MPU ignores the value of this bit.

Table 3-4 on page 121 shows the cache policy for memory attribute encodings with a TEX value in the range of 0x4-0x7.

Table 3-4. Cache Policy for Memory Attribute Encoding

Encoding, AA or BB	Corresponding Cache Policy	
00	Non-cacheable	
01	Write back, write and read allocate	
10	Write through, no write allocate	
11	Write back, no write allocate	

Table 3-5 on page 121 shows the AP encodings in the **MPUATTR** register that define the access permissions for privileged and unprivileged software.

Table 3-5. AP Bit Field Encoding

AP Bit Field	Privileged Permissions	Unprivileged Permissions	Description
000	No access	No access	All accesses generate a permission fault.
001	R/W	No access	Access from privileged software only.
010	R/W	RO	Writes by unprivileged software generate a permission fault.
011	R/W	R/W	Full access.
100	Unpredictable	Unpredictable	Reserved.
101	RO	No access	Reads by privileged software only.
110	RO	RO	Read-only, by privileged or unprivileged software.
111	RO	RO	Read-only, by privileged or unprivileged software.

### MPU Configuration for a Stellaris Microcontroller

Stellaris microcontrollers have only a single processor and no caches. As a result, the MPU should be programmed as shown in Table 3-6 on page 121.

**Table 3-6. Memory Region Attributes for Stellaris Microcontrollers** 

Memory Region	TEX	S	С	В	Memory Type and Attributes
Flash memory	000b	0	1	0	Normal memory, non-shareable, write-through
Internal SRAM	000b	1	1	0	Normal memory, shareable, write-through
External SRAM	000b	1	1	1	Normal memory, shareable, write-back, write-allocate
Peripherals	000b	1	0	1	Device memory, shareable

In current Stellaris microcontroller implementations, the shareability and cache policy attributes do not affect the system behavior. However, using these settings for the MPU regions can make the application code more portable. The values given are for typical situations.

### 3.1.4.3 MPU Mismatch

When an access violates the MPU permissions, the processor generates a memory management fault (see "Exceptions and Interrupts" on page 90 for more information). The **MFAULTSTAT** register indicates the cause of the fault. See page 162 for more information.

# 3.2 Register Map

Table 3-7 on page 122 lists the Cortex-M3 Peripheral SysTick, NVIC, MPU and SCB registers. The offset listed is a hexadecimal increment to the register's address, relative to the Core Peripherals base address of 0xE000.E000.

**Note:** Register spaces that are not used are reserved for future or internal use. Software should not modify any reserved memory address.

Table 3-7. Peripherals Register Map

Offset	Name	Туре	Reset	Description	See page
System T	imer (SysTick) Registers	3			·
0x010	STCTRL	R/W	0x0000.0004	SysTick Control and Status Register	125
0x014	STRELOAD	R/W	0x0000.0000	SysTick Reload Value Register	127
0x018	STCURRENT	R/WC	0x0000.0000	SysTick Current Value Register	128
Nested V	ectored Interrupt Contro	ller (NVIC)	Registers		
0x100	EN0	R/W	0x0000.0000	Interrupt 0-31 Set Enable	129
0x104	EN1	R/W	0x0000.0000	Interrupt 32-54 Set Enable	130
0x180	DIS0	R/W	0x0000.0000	Interrupt 0-31 Clear Enable	131
0x184	DIS1	R/W	0x0000.0000	Interrupt 32-54 Clear Enable	132
0x200	PEND0	R/W	0x0000.0000	Interrupt 0-31 Set Pending	133
0x204	PEND1	R/W	0x0000.0000	Interrupt 32-54 Set Pending	134
0x280	UNPEND0	R/W	0x0000.0000	Interrupt 0-31 Clear Pending	135
0x284	UNPEND1	R/W	0x0000.0000	Interrupt 32-54 Clear Pending	136
0x300	ACTIVE0	RO	0x0000.0000	Interrupt 0-31 Active Bit	137
0x304	ACTIVE1	RO	0x0000.0000	Interrupt 32-54 Active Bit	138
0x400	PRI0	R/W	0x0000.0000	Interrupt 0-3 Priority	139
0x404	PRI1	R/W	0x0000.0000	Interrupt 4-7 Priority	139
0x408	PRI2	R/W	0x0000.0000	Interrupt 8-11 Priority	139
0x40C	PRI3	R/W	0x0000.0000	Interrupt 12-15 Priority	139
0x410	PRI4	R/W	0x0000.0000	Interrupt 16-19 Priority	139

Table 3-7. Peripherals Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x414	PRI5	R/W	0x0000.0000	Interrupt 20-23 Priority	139
0x418	PRI6	R/W	0x0000.0000	Interrupt 24-27 Priority	139
0x41C	PRI7	R/W	0x0000.0000	Interrupt 28-31 Priority	139
0x420	PRI8	R/W	0x0000.0000	Interrupt 32-35 Priority	139
0x424	PRI9	R/W	0x0000.0000	Interrupt 36-39 Priority	139
0x428	PRI10	R/W	0x0000.0000	Interrupt 40-43 Priority	139
0x42C	PRI11	R/W	0x0000.0000	Interrupt 44-47 Priority	139
0x430	PRI12	R/W	0x0000.0000	Interrupt 48-51 Priority	139
0x434	PRI13	R/W	0x0000.0000	Interrupt 52-54 Priority	139
0xF00	SWTRIG	WO	0x0000.0000	Software Trigger Interrupt	141
System C	ontrol Block (SCB) R	egisters			
0x008	ACTLR	R/W	0x0000.0000	Auxiliary Control	142
0xD00	CPUID	RO	0x412F.C230	CPU ID Base	144
0xD04	INTCTRL	R/W	0x0000.0000	Interrupt Control and State	145
0xD08	VTABLE	R/W	0x0000.0000	Vector Table Offset	148
0xD0C	APINT	R/W	0xFA05.0000	Application Interrupt and Reset Control	149
0xD10	SYSCTRL	R/W	0x0000.0000	System Control	151
0xD14	CFGCTRL	R/W	0x0000.0200	Configuration and Control	153
0xD18	SYSPRI1	R/W	0x0000.0000	System Handler Priority 1	155
0xD1C	SYSPRI2	R/W	0x0000.0000	System Handler Priority 2	156
0xD20	SYSPRI3	R/W	0x0000.0000	System Handler Priority 3	157
0xD24	SYSHNDCTRL	R/W	0x0000.0000	System Handler Control and State	158
0xD28	FAULTSTAT	R/W1C	0x0000.0000	Configurable Fault Status	162
0xD2C	HFAULTSTAT	R/W1C	0x0000.0000	Hard Fault Status	168
0xD34	MMADDR	R/W	-	Memory Management Fault Address	169
0xD38	FAULTADDR	R/W	-	Bus Fault Address	170
Memory I	Protection Unit (MPU)	Registers			
0xD90	MPUTYPE	RO	0x0000.0800	MPU Type	171
0xD94	MPUCTRL	R/W	0x0000.0000	MPU Control	172
0xD98	MPUNUMBER	R/W	0x0000.0000	MPU Region Number	174
0xD9C	MPUBASE	R/W	0x0000.0000	MPU Region Base Address	175
0xDA0	MPUATTR	R/W	0x0000.0000	MPU Region Attribute and Size	177

Table 3-7. Peripherals Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0xDA4	MPUBASE1	R/W	0x0000.0000	MPU Region Base Address Alias 1	175
0xDA8	MPUATTR1	R/W	0x0000.0000	MPU Region Attribute and Size Alias 1	177
0xDAC	MPUBASE2	R/W	0x0000.0000	MPU Region Base Address Alias 2	175
0xDB0	MPUATTR2	R/W	0x0000.0000	MPU Region Attribute and Size Alias 2	177
0xDB4	MPUBASE3	R/W	0x0000.0000	MPU Region Base Address Alias 3	175
0xDB8	MPUATTR3	R/W	0x0000.0000	MPU Region Attribute and Size Alias 3	177

# 3.3 System Timer (SysTick) Register Descriptions

This section lists and describes the System Timer registers, in numerical order by address offset.

# Register 1: SysTick Control and Status Register (STCTRL), offset 0x010

Note: This register can only be accessed from privileged mode.

The SysTick STCTRL register enables the SysTick features.

SysTick Control and Status Register (STCTRL)

Base 0xE000.E000 Offset 0x010 Type R/W, reset 0x0000.0004

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
							' '	reserved		•	'	•	! !	' '		COUNT
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0
110001	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
[	13	17	15		"		reserved	-	· ·				·	CLK_SRC	INTEN	ENABLE
<b>[</b> Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	1	0	0
В	Bit/Field		Nam	ne	Ту	ре	Reset	Des	cription							
	31:17		reserv	ved	R	0	0x000	Soft	ware sh	ould not	rely on t	he value	of a re	served bit.	To pro	vide
								com	patibility	with fut	ure prod		value o	of a reserv		
	16		COU	NT	R	0	0	Cou	nt Flag							
								Valu	ue	Descrip	otion					
								0		,	sTick tim was rea		ot coun	ted to 0 sir	nce the I	ast time
								1			sTick tin was rea		counted	to 0 since	the las	st time
										ared by a		the regis	ster or if	the <b>STCU</b>	RRENT	register
										•		the DA	P, this b	it is cleare	ed only	if the
								Mas	terTyp	e bit in tl	ne AHB-	AP Con	trol Re	<b>gister</b> is c	lear. Ot	herwise,
								Deb		face V5				er read. Se n for more		
								nas	CCLIAD	<b>.</b>						
	15:3		reser	ved	R	0	0x000	com	patibility	with fut	ure prodi		value o	served bit. of a reservi ion.		
	2		CLK_S	SRC	R/	W	1	Cloc	ck Sourc	e						
								Valu	ue Desc	ription						
								0	Exte	rnal refe	rence clo	ock. (Not	implen	nented for	most S	tellaris

Because an external reference clock is not implemented, this bit must be set in order for SysTick to operate.

microcontrollers.) System clock

1

Bit/Field	Name	Туре	Reset	Description	on
1	INTEN	R/W	0	Interrupt Enable	
				Value	Description
				0	Interrupt generation is disabled. Software can use the COUNT bit to determine if the counter has ever reached 0.
				1	An interrupt is generated to the NVIC when SysTick counts to 0. $ \\$
0	ENABLE	R/W	0	Enable	
				Value	Description
				0	The counter is disabled.
				1	Enables SysTick to operate in a multi-shot way. That is, the counter loads the RELOAD value and begins counting down. On reaching 0, the COUNT bit is set and an interrupt is generated if enabled by INTEN. The counter then loads the RELOAD value again and begins counting.

# Register 2: SysTick Reload Value Register (STRELOAD), offset 0x014

Note: This register can only be accessed from privileged mode.


The **STRELOAD** register specifies the start value to load into the **SysTick Current Value** (**STCURRENT**) register when the counter reaches 0. The start value can be between 0x1 and 0x00FF.FFFF. A start value of 0 is possible but has no effect because the SysTick interrupt and the COUNT bit are activated when counting from 1 to 0.

SysTick can be configured as a multi-shot timer, repeated over and over, firing every N+1 clock pulses, where N is any value from 1 to 0x00FF.FFFF. For example, if a tick interrupt is required every 100 clock pulses, 99 must be written into the RELOAD field.

SysTick Reload Value Register (STRELOAD)

Base 0xE000.E000

Offset 0x014
Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:24	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23:0	RELOAD	R/W	0x00.0000	Reload Value

Value to load into the  ${\bf SysTick}$  Current Value (STCURRENT) register when the counter reaches 0.

## Register 3: SysTick Current Value Register (STCURRENT), offset 0x018


**Note:** This register can only be accessed from privileged mode.

The **STCURRENT** register contains the current value of the SysTick counter.

SysTick Current Value Register (STCURRENT)

Base 0xE000.E000 Offset 0x018

Type R/WC, reset 0x0000.0000



No read-modify-write protection is provided, so change with care.

This register is write-clear. Writing to it with any value clears the register.

Clearing this register also clears the COUNT bit of the STCTRL register.

# 3.4 NVIC Register Descriptions

This section lists and describes the NVIC registers, in numerical order by address offset.

The NVIC registers can only be fully accessed from privileged mode, but interrupts can be pended while in unprivileged mode by enabling the **Configuration and Control (CFGCTRL)** register. Any other unprivileged mode access causes a bus fault.

Ensure software uses correctly aligned register accesses. The processor does not support unaligned accesses to NVIC registers.

An interrupt can enter the pending state even if it is disabled.

Before programming the **VTABLE** register to relocate the vector table, ensure the vector table entries of the new vector table are set up for fault handlers, NMI, and all enabled exceptions such as interrupts. For more information, see page 148.

## Register 4: Interrupt 0-31 Set Enable (EN0), offset 0x100

Note: This register can only be accessed from privileged mode.


See Table 2-9 on page 102 for interrupt assignments.

If a pending interrupt is enabled, the NVIC activates the interrupt based on its priority. If an interrupt is not enabled, asserting its interrupt signal changes the interrupt state to pending, but the NVIC never activates the interrupt, regardless of its priority.

### Interrupt 0-31 Set Enable (EN0)

Base 0xE000.E000 Offset 0x100

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:0	INT	R/W	0x0000.0000	Interrupt Enable

Value	Description
0	On a read, indicates the interrupt is disabled.
	On a write, no effect.
1	On a read, indicates the interrupt is enabled.
	On a write, enables the interrupt.

A bit can only be cleared by setting the corresponding  ${\tt INT[n]}$  bit in the **DISn** register.

# Register 5: Interrupt 32-54 Set Enable (EN1), offset 0x104

Note: This register can only be accessed from privileged mode.


The **EN1** register enables interrupts and shows which interrupts are enabled. Bit 0 corresponds to Interrupt 32; bit 22 corresponds to Interrupt 54. See Table 2-9 on page 102 for interrupt assignments.

If a pending interrupt is enabled, the NVIC activates the interrupt based on its priority. If an interrupt is not enabled, asserting its interrupt signal changes the interrupt state to pending, but the NVIC never activates the interrupt, regardless of its priority.

Interrupt 32-54 Set Enable (EN1)

Base 0xE000.E000 Offset 0x104

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:23	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22:0	INT	R/W	0x00.0000	Interrupt Enable

Value	Description
0	On a read, indicates the interrupt is disabled.
	On a write, no effect.
1	On a read, indicates the interrupt is enabled.
	On a write, enables the interrupt

A bit can only be cleared by setting the corresponding  ${\tt INT[n]}$  bit in the **DIS1** register.

## Register 6: Interrupt 0-31 Clear Enable (DIS0), offset 0x180


Note: This register can only be accessed from privileged mode.

See Table 2-9 on page 102 for interrupt assignments.

Interrupt 0-31 Clear Enable (DIS0)

Base 0xE000.E000

Offset 0x180 Type R/W, reset 0x0000.0000



Value Description

On a read, indicates the interrupt is disabled.

On a write, no effect.

On a read, indicates the interrupt is enabled.

On a write, clears the corresponding INT[n] bit in the EN0 register, disabling interrupt [n].

# Register 7: Interrupt 32-54 Clear Enable (DIS1), offset 0x184


Note: This register can only be accessed from privileged mode.

The **DIS1** register disables interrupts. Bit 0 corresponds to Interrupt 32; bit 22 corresponds to Interrupt 54. See Table 2-9 on page 102 for interrupt assignments.

Interrupt 32-54 Clear Enable (DIS1)

Base 0xE000.E000

Offset 0x184
Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:23	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22:0	INT	R/W	0x00.0000	Interrupt Disable

- On a read, indicates the interrupt is disabled.
  - On a write, no effect.
- On a read, indicates the interrupt is enabled. On a write, clears the corresponding INT[n] bit in the EN1 register, disabling interrupt [n].

# Register 8: Interrupt 0-31 Set Pending (PEND0), offset 0x200


**Note:** This register can only be accessed from privileged mode.

See Table 2-9 on page 102 for interrupt assignments.

Interrupt 0-31 Set Pending (PEND0)

Base 0xE000.E000 Offset 0x200

Type R/W, reset 0x0000.0000



Value Description

On a read, indicates that the interrupt is not pending.
On a write, no effect.

On a read, indicates that the interrupt is pending.
On a write, the corresponding interrupt is set to pending even if it is disabled.

If the corresponding interrupt is already pending, setting a bit has no effect.

A bit can only be cleared by setting the corresponding  ${\tt INT[n]}$  bit in the <code>UNPENDO</code> register.

# Register 9: Interrupt 32-54 Set Pending (PEND1), offset 0x204


Note: This register can only be accessed from privileged mode.

The **PEND1** register forces interrupts into the pending state and shows which interrupts are pending. Bit 0 corresponds to Interrupt 32; bit 22 corresponds to Interrupt 54. See Table 2-9 on page 102 for interrupt assignments.

### Interrupt 32-54 Set Pending (PEND1)

Base 0xE000.E000 Offset 0x204

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:23	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22:0	INT	R/W	0x00.0000	Interrupt Set Pending

Value	Description
0	On a read, indicates that the interrupt is not pending.
	On a write, no effect.
1	On a read, indicates that the interrupt is pending.
	On a write, the corresponding interrupt is set to pending even if it is disabled.

If the corresponding interrupt is already pending, setting a bit has no effect.

A bit can only be cleared by setting the corresponding  ${\tt INT[n]}$  bit in the <code>UNPEND1</code> register.

## Register 10: Interrupt 0-31 Clear Pending (UNPEND0), offset 0x280


Note: This register can only be accessed from privileged mode.

See Table 2-9 on page 102 for interrupt assignments.

Interrupt 0-31 Clear Pending (UNPEND0)

Base 0xE000.E000 Offset 0x280

Type R/W, reset 0x0000.0000



1

- On a read, indicates that the interrupt is not pending. On a write, no effect.
  - On a read, indicates that the interrupt is pending.

    On a write, clears the corresponding <code>INT[n]</code> bit in the **PEND0** register, so that interrupt [n] is no longer pending.

    Setting a bit does not affect the active state of the corresponding interrupt.

# Register 11: Interrupt 32-54 Clear Pending (UNPEND1), offset 0x284


**Note:** This register can only be accessed from privileged mode.

The UNPEND1 register shows which interrupts are pending and removes the pending state from interrupts. Bit 0 corresponds to Interrupt 32; bit 22 corresponds to Interrupt 54. See Table 2-9 on page 102 for interrupt assignments.

### Interrupt 32-54 Clear Pending (UNPEND1)

Base 0xE000.E000 Offset 0x284

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:23	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22:0	INT	R/W	0x00.0000	Interrupt Clear Pending

- On a read, indicates that the interrupt is not pending. On a write, no effect.
- On a read, indicates that the interrupt is pending. 1 On a write, clears the corresponding INT[n] bit in the PEND1 register, so that interrupt [n] is no longer pending. Setting a bit does not affect the active state of the corresponding interrupt.

## Register 12: Interrupt 0-31 Active Bit (ACTIVE0), offset 0x300

Note: This register can only be accessed from privileged mode.


See Table 2-9 on page 102 for interrupt assignments.

### Caution – Do not manually set or clear the bits in this register.

Interrupt 0-31 Active Bit (ACTIVE0)

Base 0xE000.E000 Offset 0x300

Type RO, reset 0x0000.0000



Bit/Field Name Type Reset Description

31:0 INT RO 0x0000.0000 Interrupt Active

- 0 The corresponding interrupt is not active.
- 1 The corresponding interrupt is active, or active and pending.

# Register 13: Interrupt 32-54 Active Bit (ACTIVE1), offset 0x304


Note: This register can only be accessed from privileged mode.

The ACTIVE1 register indicates which interrupts are active. Bit 0 corresponds to Interrupt 32; bit 22 corresponds to Interrupt 54. See Table 2-9 on page 102 for interrupt assignments.

### Caution – Do not manually set or clear the bits in this register.

#### Interrupt 32-54 Active Bit (ACTIVE1)

Base 0xE000.E000 Offset 0x304 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:23	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22:0	INT	RO	0x00.0000	Interrupt Active

- 0 The corresponding interrupt is not active.
- 1 The corresponding interrupt is active, or active and pending.

Register 14: Interrupt 0-3 Priority (PRI0), offset 0x400
Register 15: Interrupt 4-7 Priority (PRI1), offset 0x404
Register 16: Interrupt 8-11 Priority (PRI2), offset 0x408
Register 17: Interrupt 12-15 Priority (PRI3), offset 0x40C
Register 18: Interrupt 16-19 Priority (PRI4), offset 0x410
Register 19: Interrupt 20-23 Priority (PRI5), offset 0x414
Register 20: Interrupt 24-27 Priority (PRI6), offset 0x418
Register 21: Interrupt 28-31 Priority (PRI7), offset 0x41C
Register 22: Interrupt 32-35 Priority (PRI8), offset 0x420
Register 23: Interrupt 36-39 Priority (PRI9), offset 0x424
Register 24: Interrupt 40-43 Priority (PRI10), offset 0x428
Register 25: Interrupt 44-47 Priority (PRI11), offset 0x42C
Register 26: Interrupt 48-51 Priority (PRI12), offset 0x430
Register 27: Interrupt 52-54 Priority (PRI13), offset 0x434

**Note:** This register can only be accessed from privileged mode.

The **PRIn** registers provide 3-bit priority fields for each interrupt. These registers are byte accessible. Each register holds four priority fields that are assigned to interrupts as follows:

PRIn Register Bit Field	Interrupt
Bits 31:29	Interrupt [4n+3]
Bits 23:21	Interrupt [4n+2]
Bits 15:13	Interrupt [4n+1]
Bits 7:5	Interrupt [4n]

See Table 2-9 on page 102 for interrupt assignments.

Each priority level can be split into separate group priority and subpriority fields. The PRIGROUP field in the **Application Interrupt and Reset Control (APINT)** register (see page 149) indicates the position of the binary point that splits the priority and subpriority fields.

These registers can only be accessed from privileged mode.

## Interrupt 0-3 Priority (PRI0)

Base 0xE000.E000 Offset 0x400 Type R/W, reset 0x0000.0000

туре	R/vv, res	et uxuuut	0.0000													
	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		INTD	ı <u> </u>			reserved	INTC					reserved				
Type Reset	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	RO 0	RO 0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		INTB				reserved				INTA	ı			reserved		
Type Reset	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	RO 0	RO 0
_					_			_								
E	Bit/Field	ield Name Type Reset		Reset	Des	cription										
	31:29		INT	D	R	/W	0x0		•	ority for I	•					
														terrupt wi : <b>Priority</b>		
														eater the		
								corr	espondi	ng interru	upt.					
	28:24	4 reserved RO 0x0				0x0	Software should not rely on the value of a reserved bit. To provide									
							compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.									
												•	орстан	JII.		
	23:21		INT	С	R	/W	0x0		•	ority for I	•		41 1		41- 41	
												terrupt wi : <b>Priority</b>				
							PRI	<b>PRIO</b> , and so on). The lower the value, the greater the priority of the corresponding interrupt.								
								corr	esponai	ng interri	upt.					
	20:16		reser	ved	R	RO	0x0							erved bit f a reserv		
												dify-write			eu bit si	iouiu be
	15:13		INT	R	R	/W	0x0	Inte	rrunt Pri	ority for I	nterrunt	[4n+1]				
	10.10			_	10	, , ,	OXO			•			or the in	terrupt wi	th the nu	ımber
								[4n+	+1], wher	e n is the	e numbe	r of the Ir	nterrupt	Priority	register	(n=0 for
										ng interru		tne value	e, the gr	eater the	priority	or the
	12:8		reser	ved	R	RO	0x0	Soft	ware sh	ould not	rely on t	he value	of a res	erved bit	. To prov	ride
	1333.132						com	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.								
								pres	served a	cross a r	eau-mo	uiry-Write	operation	UI1.		
	7:5		INT	Α	R	/W	0x0		•	ority for I						
														terrupt wi <b>Priority</b> re		
								PRI	<b>0</b> , and s	on). Th	e lower			eater the		
								corr	espondi	ng interru	upt.					
	4:0		reser	ved	R	RO	0x0				-			erved bit	•	
								com	npatibility	with futu	ure prod	ucts, the	value of	f a reserv	ed bit sh	ould be

preserved across a read-modify-write operation.

# Register 28: Software Trigger Interrupt (SWTRIG), offset 0xF00

Note: Only privileged software can enable unprivileged access to the SWTRIG register.


Writing an interrupt number to the **SWTRIG** register generates a Software Generated Interrupt (SGI). See Table 2-9 on page 102 for interrupt assignments.

When the MAINPEND bit in the **Configuration and Control (CFGCTRL)** register (see page 153) is set, unprivileged software can access the **SWTRIG** register.

### Software Trigger Interrupt (SWTRIG)

Base 0xE000.E000 Offset 0xF00

Type WO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:0	INTID	WO	0x00	Interrupt ID

This field holds the interrupt ID of the required SGI. For example, a value of 0x3 generates an interrupt on IRQ3.

# 3.5 System Control Block (SCB) Register Descriptions

This section lists and describes the System Control Block (SCB) registers, in numerical order by address offset. The SCB registers can only be accessed from privileged mode.

All registers must be accessed with aligned word accesses except for the **FAULTSTAT** and **SYSPRI1-SYSPRI3** registers, which can be accessed with byte or aligned halfword or word accesses. The processor does not support unaligned accesses to system control block registers.

# Register 29: Auxiliary Control (ACTLR), offset 0x008


**Note:** This register can only be accessed from privileged mode.

The ACTLR register provides disable bits for IT folding, write buffer use for accesses to the default memory map, and interruption of multi-cycle instructions. By default, this register is set to provide optimum performance from the Cortex-M3 processor and does not normally require modification.

### Auxiliary Control (ACTLR)

Base 0xE000.E000 Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

2 **DISFOLD** R/W 0 Disable IT Folding

Value Description

0 No effect.

1 Disables IT folding.

In some situations, the processor can start executing the first instruction in an IT block while it is still executing the IT instruction. This behavior is called IT folding, and improves performance, However, IT folding can cause jitter in looping. If a task must avoid jitter, set the <code>DISFOLD</code> bit before executing the task, to disable IT folding.

**DISWBUF** Disable Write Buffer 1 R/W 0

Value Description

0 No effect.

1 Disables write buffer use during default memory map accesses. In this situation, all bus faults are precise bus faults but performance is decreased because any store to memory must complete before the processor can execute the next instruction.

This bit only affects write buffers implemented in the Note: Cortex-M3 processor.

Bit/Field	Name	Type	Reset	Description
0	DISMCYC	R/W	0	Disable Interrupts of Multiple Cycle Instructions
				Value Description
				0 No effect.
				Disables interruption of load multiple and store multiple instructions. In this situation, the interrupt latency of the processor is increased because any LDM or STM must complete before the processor can stack the current state and enter the interrupt handler.

# Register 30: CPU ID Base (CPUID), offset 0xD00

Note: This register can only be accessed from privileged mode.

The CPUID register contains the ARM® Cortex™-M3 processor part number, version, and implementation information.

#### CPU ID Base (CPUID)

Base 0xE000.E000


3:0

**REV** 

RO

0x0

Offset 0xD00 Type RO, reset 0x412F.C230



Value Description

**Revision Number** 

Value Description

0xC23 Cortex-M3 processor.

The pn value in the rnpn product revision identifier, for example, the 0 in r2p0.

### Register 31: Interrupt Control and State (INTCTRL), offset 0xD04

**Note:** This register can only be accessed from privileged mode.

The **INCTRL** register provides a set-pending bit for the NMI exception, and set-pending and clear-pending bits for the PendSV and SysTick exceptions. In addition, bits in this register indicate the exception number of the exception being processed, whether there are preempted active exceptions, the exception number of the highest priority pending exception, and whether any interrupts are pending.


When writing to **INCTRL**, the effect is unpredictable when writing a 1 to both the PENDSV and UNPENDSV bits, or writing a 1 to both the PENDSTSET and PENDSTCLR bits.

#### Interrupt Control and State (INTCTRL)

Base 0xE000.E000

28

Offset 0xD04 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description	
31	NMISET	R/W	0	NMI Set Pendin	g

R/W

#### Value Description

- On a read, indicates an NMI exception is not pending. On a write, no effect.
- On a read, indicates an NMI exception is pending.
   On a write, changes the NMI exception state to pending.

Because NMI is the highest-priority exception, normally the processor enters the NMI exception handler as soon as it registers the setting of this bit, and clears this bit on entering the interrupt handler. A read of this bit by the NMI exception handler returns 1 only if the  ${\tt NMI}$  signal is reasserted while the processor is executing that handler.

30:29	reserved	RO	0x0		

**PENDSV** 

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

0 PendSV Set Pending

#### Value Description

- On a read, indicates a PendSV exception is not pending.
   On a write, no effect.
- On a read, indicates a PendSV exception is pending.On a write, changes the PendSV exception state to pending.

Setting this bit is the only way to set the PendSV exception state to pending. This bit is cleared by writing a 1 to the  ${\tt UNPENDSV}$  bit.

Bit/Field	Name	Туре	Reset	Description
27	UNPENDSV	WO	0	PendSV Clear Pending
				Value Description
				0 On a write, no effect.
				On a write, removes the pending state from the PendSV exception.
				This bit is write only; on a register read, its value is unknown.
26	PENDSTSET	R/W	0	SysTick Set Pending
				Value Description
				<ul> <li>On a read, indicates a SysTick exception is not pending.</li> <li>On a write, no effect.</li> </ul>
				1 On a read, indicates a SysTick exception is pending.
				On a write, changes the SysTick exception state to pending.
				This bit is cleared by writing a 1 to the PENDSTCLR bit.
25	PENDSTCLR	WO	0	SysTick Clear Pending
				Value Description
				0 On a write, no effect.
				On a write, removes the pending state from the SysTick exception.
				This bit is write only; on a register read, its value is unknown.
24	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23	ISRPRE	RO	0	Debug Interrupt Handling
				Value Description
				The release from halt does not take an interrupt.
				1 The release from halt takes an interrupt.
				This bit is only meaningful in Debug mode and reads as zero when the processor is not in Debug mode.
22	ISRPEND	RO	0	Interrupt Pending
				Value Description
				0 No interrupt is pending.
				1 An interrupt is pending.
				This bit provides status for all interrupts excluding NMI and Faults.
21:19	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
18:12	VECPEND	RO	0x00	Interrupt Pending Vector Number  This field contains the exception number of the highest priority pending enabled exception. The value indicated by this field includes the effect of the BASEPRI and FAULTMASK registers, but not any effect of the PRIMASK register.
				Value Description
				0x00 No exceptions are pending
				0x01 Reserved
				0x02 NMI
				0x03 Hard fault
				0x04 Memory management fault
				0x05 Bus fault
				0x06 Usage fault
				0x07-0x0A Reserved
				0x0B SVCall
				0x0C Reserved for Debug
				0x0D Reserved
				0x0E PendSV
				0x0F SysTick
				0x10 Interrupt Vector 0
				0x11 Interrupt Vector 1
				0x46 Interrupt Vector 54
				0x47-0x7F Reserved
				OKTI OKTI TKOGOTOG
11	RETBASE	RO	0	Return to Base
				Value Description
				O There are preempted active exceptions to execute.
				1 There are no active exceptions, or the currently executing exception is the only active exception.
				This bit provides status for all interrupts excluding NMI and Faults. This bit only has meaning if the processor is currently executing an ISR (the Interrupt Program Status (IPSR) register is non-zero).
10:7	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	VECACT	RO	0x00	Interrupt Pending Vector Number
				This field contains the active exception number. The exception numbers can be found in the description for the VECPEND field. If this field is clear, the processor is in Thread mode. This field contains the same value as the ISRNUM field in the <b>IPSR</b> register.
				Subtract 16 from this value to obtain the IRQ number required to index into the Interrupt Set Enable (ENn), Interrupt Clear Enable (DISn), Interrupt Set Pending (PENDn), Interrupt Clear Pending (UNPENDn), and Interrupt Priority (PRIn) registers (see page 82).

# Register 32: Vector Table Offset (VTABLE), offset 0xD08


**Note:** This register can only be accessed from privileged mode.

The VTABLE register indicates the offset of the vector table base address from memory address 0x0000.0000.

Vector Table Offset (VTABLE)

reserved

Base 0xE000.E000 Offset 0xD08



compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

# Register 33: Application Interrupt and Reset Control (APINT), offset 0xD0C

Note: This register can only be accessed from privileged mode.

The **APINT** register provides priority grouping control for the exception model, endian status for data accesses, and reset control of the system. To write to this register, 0x05FA must be written to the VECTKEY field, otherwise the write is ignored.

The PRIGROUP field indicates the position of the binary point that splits the INTx fields in the Interrupt Priority (PRIx) registers into separate group priority and subpriority fields. Table 3-8 on page 149 shows how the PRIGROUP value controls this split. The bit numbers in the Group Priority Field and Subpriority Field columns in the table refer to the bits in the INTA field. For the INTB field, the corresponding bits are 15:13; for INTC, 23:21; and for INTD, 31:29.

**Note:** Determining preemption of an exception uses only the group priority field.

Table 3-8. Interrupt Priority Levels


PRIGROUP Bit Field	Binary Point <sup>a</sup>	Group Priority Field		Group Priorities	Subpriorities
0x0 - 0x4	bxxx.	[7:5]	None	8	1
0x5	bxx.y	[7:6]	[5]	4	2
0x6	bx.yy	[7]	[6:5]	2	4
0x7	b.yyy	None	[7:5]	1	8

a. INTx field showing the binary point. An x denotes a group priority field bit, and a y denotes a subpriority field bit.

#### Application Interrupt and Reset Control (APINT)

Base 0xE000.E000 Offset 0xD0C

Type R/W, reset 0xFA05.0000



Bit/Field	Name	Туре	Reset	Description
31:16	VECTKEY	R/W	0xFA05	Register Key
				This field is used to guard against accidental writes to this register. 0x05FA must be written to this field in order to change the bits in this register. On a read, 0xFA05 is returned.
15	ENDIANESS	RO	0	Data Endianess
				The Stellaris implementation uses only little-endian mode so this is cleared to $0. \  \  $
14:11	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
10:8	PRIGROUP	R/W	0x0	Interrupt Priority Grouping This field determines the split of group priority from subpriority (see Table 3-8 on page 149 for more information).
7:3	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	SYSRESREQ	WO	0	System Reset Request
				Value Description
				0 No effect.
				1 Resets the core and all on-chip peripherals except the Debug interface.
				This bit is automatically cleared during the reset of the core and reads as 0.
1	VECTCLRACT	WO	0	Clear Active NMI / Fault
				This bit is reserved for Debug use and reads as 0. This bit must be written as a 0, otherwise behavior is unpredictable.
0	VECTRESET	WO	0	System Reset
				This bit is reserved for Debug use and reads as 0. This bit must be written as a 0, otherwise behavior is unpredictable.

# Register 34: System Control (SYSCTRL), offset 0xD10

**Note:** This register can only be accessed from privileged mode.

The **SYSCTRL** register controls features of entry to and exit from low-power state.

### System Control (SYSCTRL)

Base 0xE000.E000 Offset 0xD10 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	,		1		, T		, ,	rese	rved	1		•				
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	•		•	' '		reserve	ed I		 	•		SEVONPEND	reserved	SLEEPDEEP	SLEEPEXIT	reserved
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	RO	R/W	R/W	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
В	it/Field		Nam	ne	Тур	e	Reset	Des	cription							
	31:5		reserv	/ed	RO	)	0x0000.00	com	patibility	with futu	re prod	the value ucts, the dify-write	value of	a reserv		
	4		SEVON	PEND	RΛ	N	0	Wak	e Up on	Pending						
								Valu	ie Desc	ription						
								0	•			ots or eve e exclude		wake up	the prod	cessor;
								1		led even vake up t		all interrup cessor.	ots, inclu	iding disa	abled into	errupts,
								wak	es up the	process	sor from	enters the NWFE. If the d and affe	he proce	essor is n	ot waitin	
									process rnal eve		akes u <sub>l</sub>	p on exec	cution of	a sev in	struction	or an
	3		reserv	/ed	RO	)	0	com	patibility	with futu	re prod	the value ucts, the dify-write	value of	a reserv		
	2		SLEEPE	DEEP	RΛ	N	0	Dee	p Sleep	Enable						

Value Description

- 0 Use Sleep mode as the low power mode.
- Use Deep-sleep mode as the low power mode.

Bit/Field	Name	Туре	Reset	Description
1	SLEEPEXIT	R/W	0	Sleep on ISR Exit
				Value Description
				When returning from Handler mode to Thread mode, do not sleep when returning to Thread mode.
				When returning from Handler mode to Thread mode, enter sleep or deep sleep on return from an ISR.
				Setting this bit enables an interrupt-driven application to avoid returning to an empty main application.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 35: Configuration and Control (CFGCTRL), offset 0xD14


Note: This register can only be accessed from privileged mode.

The **CFGCTRL** register controls entry to Thread mode and enables: the handlers for NMI, hard fault and faults escalated by the **FAULTMASK** register to ignore bus faults; trapping of divide by zero and unaligned accesses; and access to the **SWTRIG** register by unprivileged software (see page 141).

Configuration and Control (CFGCTRL)

Base 0xE000.E000 Offset 0xD14

Type R/W, reset 0x0000.0200



Bit/Field	Name	Type	Reset	Description
31:10	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	STKALIGN	R/W	1	Stack Alignment on Exception Entry
				Value Description  The stack is 4-byte aligned.  The stack is 8-byte aligned.
				On exception entry, the processor uses bit 9 of the stacked <b>PSR</b> to indicate the stack alignment. On return from the exception, it uses this stacked bit to restore the correct stack alignment.
8	BFHFNMIGN	R/W	0	Ignore Bus Fault in NMI and Fault
				This bit enables handlers with priority -1 or -2 to ignore data bus faults caused by load and store instructions. The setting of this bit applies to the hard fault, NMI, and <b>FAULTMASK</b> escalated handlers.
				Value Description
				0 Data bus faults caused by load and store instructions cause a lock-up.
				1 Handlers running at priority -1 and -2 ignore data bus faults caused by load and store instructions.
				Set this bit only when the handler and its data are in absolutely safe memory. The normal use of this bit is to probe system devices and bridges to detect control path problems and fix them.
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Type	Reset	Description
4	DIV0	R/W	0	Trap on Divide by 0  This bit enables faulting or halting when the processor executes an SDIV or UDIV instruction with a divisor of 0.
				Value Description
				O Do not trap on divide by 0. A divide by zero returns a quotient of 0.
				1 Trap on divide by 0.
3	UNALIGNED	R/W	0	Trap on Unaligned Access
				Value Description
				0 Do not trap on unaligned halfword and word accesses.
				1 Trap on unaligned halfword and word accesses. An unaligned access generates a usage fault.
				Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of whether <code>UNALIGNED</code> is set.
2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	MAINPEND	R/W	0	Allow Main Interrupt Trigger
				Value Description
				0 Disables unprivileged software access to the <b>SWTRIG</b> register.
				1 Enables unprivileged software access to the SWTRIG register (see page 141).
0	BASETHR	R/W	0	Thread State Control
				Value Description
				The processor can enter Thread mode only when no exception is active.
				The processor can enter Thread mode from any level under the control of an EXC_RETURN value (see "Exception Return" on page 107 for more information).

### Register 36: System Handler Priority 1 (SYSPRI1), offset 0xD18

**Note:** This register can only be accessed from privileged mode.

The **SYSPRI1** register configures the priority level, 0 to 7 of the usage fault, bus fault, and memory management fault exception handlers. This register is byte-accessible.

System Handler Priority 1 (SYSPRI1)

Base 0xE000.E000 Offset 0xD18


4:0

reserved

RO

0x0

Type R/W, reset 0x0000.0000



having higher priority.

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.


# Register 37: System Handler Priority 2 (SYSPRI2), offset 0xD1C

Note: This register can only be accessed from privileged mode.

The SYSPRI2 register configures the priority level, 0 to 7 of the SVCall handler. This register is byte-accessible.

System Handler Priority 2 (SYSPRI2)

Base 0xE000.E000 Offset 0xD1C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:29	SVC	R/W	0x0	SVCall Priority
				This field configures the priority level of SVCall. Configurable priority values are in the range 0-7, with lower values having higher priority.
28:0	reserved	RO	0x000.0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

### Register 38: System Handler Priority 3 (SYSPRI3), offset 0xD20


**Note:** This register can only be accessed from privileged mode.

The **SYSPRI3** register configures the priority level, 0 to 7 of the SysTick exception and PendSV handlers. This register is byte-accessible.

System Handler Priority 3 (SYSPRI3)

Base 0xE000.E000 Offset 0xD20

Type R/W, reset 0x0000.0000



## Register 39: System Handler Control and State (SYSHNDCTRL), offset 0xD24

**Note:** This register can only be accessed from privileged mode.

The **SYSHNDCTRL** register enables the system handlers, and indicates the pending status of the usage fault, bus fault, memory management fault, and SVC exceptions as well as the active status of the system handlers.

If a system handler is disabled and the corresponding fault occurs, the processor treats the fault as a hard fault.

This register can be modified to change the pending or active status of system exceptions. An OS kernel can write to the active bits to perform a context switch that changes the current exception type.


Caution – Software that changes the value of an active bit in this register without correct adjustment to the stacked content can cause the processor to generate a fault exception. Ensure software that writes to this register retains and subsequently restores the current active status.

If the value of a bit in this register must be modified after enabling the system handlers, a read-modify-write procedure must be used to ensure that only the required bit is modified.

System Handler Control and State (SYSHNDCTRL)

Base 0xE000.E000 Offset 0xD24

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:19	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
18	USAGE	R/W	0	Usage Fault Enable
				Value Description
				0 Disables the usage fault exception.
				1 Enables the usage fault exception.
17	BUS	R/W	0	Bus Fault Enable
				Value Description
				Disables the bus fault exception.

Enables the bus fault exception.

Bit/Field	Name	Туре	Reset	Description
16	MEM	R/W	0	Memory Management Fault Enable
				Value Description
				0 Disables the memory management fault exception.
				1 Enables the memory management fault exception.
15	SVC	R/W	0	SVC Call Pending
				Value Description
				O An SVC call exception is not pending.
				1 An SVC call exception is pending.
				This bit can be modified to change the pending status of the SVC call exception.
14	BUSP	R/W	0	Bus Fault Pending
				Value Description
				0 A bus fault exception is not pending.
				1 A bus fault exception is pending.
				This bit can be modified to change the pending status of the bus fault exception.
13	MEMP	R/W	0	Memory Management Fault Pending
				Value Description
				O A memory management fault exception is not pending.
				1 A memory management fault exception is pending.
				This bit can be modified to change the pending status of the memory management fault exception.
12	USAGEP	R/W	0	Usage Fault Pending
				Value Description
				0 A usage fault exception is not pending.
				1 A usage fault exception is pending.
				This bit can be modified to change the pending status of the usage fault exception.
11	TICK	R/W	0	SysTick Exception Active
				Value Description
				0 A SysTick exception is not active.
				1 A SysTick exception is active.
				This bit can be modified to change the active status of the SysTick exception, however, see the Caution above before setting this bit.

Bit/Field	Name	Туре	Reset	Description
10	PNDSV	R/W	0	PendSV Exception Active
				Value Description
				0 A PendSV exception is not active.
				1 A PendSV exception is active.
				This bit can be modified to change the active status of the PendSV exception, however, see the Caution above before setting this bit.
9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	MON	R/W	0	Debug Monitor Active
				Value Description
				0 The Debug monitor is not active.
				1 The Debug monitor is active.
7	SVCA	R/W	0	SVC Call Active
				Value Description
				0 SVC call is not active.
				1 SVC call is active.
				This bit can be modified to change the active status of the SVC call exception, however, see the Caution above before setting this bit.
6:4	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	USGA	R/W	0	Usage Fault Active
				Value Description
				0 Usage fault is not active.
				1 Usage fault is active.
				This bit can be modified to change the active status of the usage fault exception, however, see the Caution above before setting this bit.
2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	BUSA	R/W	0	Bus Fault Active
				Value Description
				0 Bus fault is not active.
				1 Bus fault is active.
				This bit can be modified to change the active status of the bus fault exception, however, see the Caution above before setting this bit.

Bit/Field	Name	Туре	Reset	Description
0	MEMA	R/W	0	Memory Management Fault Active
				Value Description  0 Memory management fault is not active.  1 Memory management fault is active.  This bit can be modified to change the active status of the memory
				management fault exception, however, see the Caution above before setting this bit.

### Register 40: Configurable Fault Status (FAULTSTAT), offset 0xD28

**Note:** This register can only be accessed from privileged mode.

The **FAULTSTAT** register indicates the cause of a memory management fault, bus fault, or usage fault. Each of these functions is assigned to a subregister as follows:

- Usage Fault Status (UFAULTSTAT), bits 31:16
- Bus Fault Status (BFAULTSTAT), bits 15:8
- Memory Management Fault Status (MFAULTSTAT), bits 7:0

**FAULTSTAT** is byte accessible. **FAULTSTAT** or its subregisters can be accessed as follows:

- The complete **FAULTSTAT** register, with a word access to offset 0xD28
- The **MFAULTSTAT**, with a byte access to offset 0xD28
- The MFAULTSTAT and BFAULTSTAT, with a halfword access to offset 0xD28
- The **BFAULTSTAT**, with a byte access to offset 0xD29
- The **UFAULTSTAT**, with a halfword access to offset 0xD2A

Bits are cleared by writing a 1 to them.

In a fault handler, the true faulting address can be determined by:


- Read and save the Memory Management Fault Address (MMADDR) or Bus Fault Address (FAULTADDR) value.
- 2. Read the MMARV bit in **MFAULTSTAT**, or the BFARV bit in **BFAULTSTAT** to determine if the **MMADDR** or **FAULTADDR** contents are valid.

Software must follow this sequence because another higher priority exception might change the **MMADDR** or **FAULTADDR** value. For example, if a higher priority handler preempts the current fault handler, the other fault might change the **MMADDR** or **FAULTADDR** value.

#### Configurable Fault Status (FAULTSTAT)

Base 0xE000.E000 Offset 0xD28

Type R/W1C, reset 0x0000.0000



25 DIVO RW1C 0 Divide-by-Zero Usage Fault  Value Description  0 No divide-by-Zero fault has occurred, or divide-by-Zero trapp is not enabled.  1 The processor has executed an SDIV or UDIV instruction we a divisor of 0.  When this bit is set, the PC value stacked for the exception return porton the instruction that performed the divide by zero.  Trapping on divide-by-zero is enabled by setting the DIVO bit in the Configuration and Control (CFGCTRL) register (see page 153). This bit is cleared by writing a 1 to it.  24 UNALIGN R/W1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	rith
0 No divide-by-zero fault has occurred, or divide-by-zero trapp is not enabled.  1 The processor has executed an SDIV or UDIV instruction wand divisor of 0.  When this bit is set, the PC value stacked for the exception return poto to the instruction that performed the divide by zero.  Trapping on divide-by-zero is enabled by setting the DIVO bit in the Configuration and Control (CFGCTRL) register (see page 153).  This bit is cleared by writing a 1 to it.  24 UNALIGN RW1C 0 Unaligned Access Usage Fault  Value Description 0 No unaligned access fault has occurred, or unaligned access trapping is not enabled. 1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP RW1C 0 No Coprocessor Usage Fault  Value Description 0 A usage fault has not been caused by attempting to access	rith
is not enabled.  1 The processor has executed an SDIV or UDIV instruction was a divisor of 0.  When this bit is set, the PC value stacked for the exception return pote to the instruction that performed the divide by zero.  Trapping on divide-by-zero is enabled by setting the DIV0 bit in the Configuration and Control (CFGCTRL) register (see page 153).  This bit is cleared by writing a 1 to it.  24 UNALIGN R/W1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP RW1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	rith
a divisor of 0.  When this bit is set, the PC value stacked for the exception return po to the instruction that performed the divide by zero.  Trapping on divide-by-zero is enabled by setting the DIVO bit in the Configuration and Control (CFGCTRL) register (see page 153).  This bit is cleared by writing a 1 to it.  24 UNALIGN RW1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP RW1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	ints
to the instruction that performed the divide by zero.  Trapping on divide-by-zero is enabled by setting the DIV0 bit in the Configuration and Control (CFGCTRL) register (see page 153).  This bit is cleared by writing a 1 to it.  24 UNALIGN R/W1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
Configuration and Control (CFGCTRL) register (see page 153).  This bit is cleared by writing a 1 to it.  24 UNALIGN RW1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP RW1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	•
24 UNALIGN R/W1C 0 Unaligned Access Usage Fault  Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
Value Description  0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
0 No unaligned access fault has occurred, or unaligned access trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
trapping is not enabled.  1 The processor has made an unaligned memory access.  Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
Unaligned LDM, STM, LDRD, and STRD instructions always fault regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20  reserved  RO  0x00  Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19  NOCP  R/W1C  0  No Coprocessor Usage Fault  Value Description  0  A usage fault has not been caused by attempting to access	ss
regardless of the configuration of this bit.  Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20  reserved  RO  0x00  Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19  NOCP  R/W1C  0  No Coprocessor Usage Fault  Value  Description  0  A usage fault has not been caused by attempting to access	
Trapping on unaligned access is enabled by setting the UNALIGNED in the CFGCTRL register (see page 153).  This bit is cleared by writing a 1 to it.  23:20  reserved  RO  0x00  Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19  NOCP  R/W1C  0  No Coprocessor Usage Fault  Value Description  0  A usage fault has not been caused by attempting to access	
23:20 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	bit
compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.  19 NOCP R/W1C 0 No Coprocessor Usage Fault  Value Description  0 A usage fault has not been caused by attempting to access	
Value Description  O A usage fault has not been caused by attempting to access	be
0 A usage fault has not been caused by attempting to access	
· · · · · · · · · · · · · · · · · · ·	
coprocessor.	а
1 The processor has attempted to access a coprocessor.	
This bit is cleared by writing a 1 to it.	
18 INVPC R/W1C 0 Invalid PC Load Usage Fault	
Value Description	
O A usage fault has not been caused by attempting to load an invalid PC value.	l
The processor has attempted an illegal load of EXC_RETUI to the <b>PC</b> as a result of an invalid context or an invalid EXC_RETURN value.	٦N
When this bit is set, the <b>PC</b> value stacked for the exception return po to the instruction that tried to perform the illegal load of the <b>PC</b> .	
This bit is cleared by writing a 1 to it.	ints

Bit/Field	Name	Type	Reset	Description
17	INVSTAT	R/W1C	0	Invalid State Usage Fault
				Value Description
				O A usage fault has not been caused by an invalid state.
				1 The processor has attempted to execute an instruction that makes illegal use of the EPSR register.
				When this bit is set, the <b>PC</b> value stacked for the exception return points to the instruction that attempted the illegal use of the <b>Execution Program Status Register (EPSR)</b> register.
				This bit is not set if an undefined instruction uses the <b>EPSR</b> register.
				This bit is cleared by writing a 1 to it.
16	UNDEF	R/W1C	0	Undefined Instruction Usage Fault
				Value Description
				0 A usage fault has not been caused by an undefined instruction.
				1 The processor has attempted to execute an undefined instruction.
				When this bit is set, the <b>PC</b> value stacked for the exception return points to the undefined instruction.
				An undefined instruction is an instruction that the processor cannot decode.
				This bit is cleared by writing a 1 to it.
15	BFARV	R/W1C	0	Bus Fault Address Register Valid
				Value Description
				The value in the Bus Fault Address (FAULTADDR) register is not a valid fault address.
				1 The <b>FAULTADDR</b> register is holding a valid fault address.
				This bit is set after a bus fault, where the address is known. Other faults can clear this bit, such as a memory management fault occurring later.
				If a bus fault occurs and is escalated to a hard fault because of priority, the hard fault handler must clear this bit. This action prevents problems if returning to a stacked active bus fault handler whose <b>FAULTADDR</b> register value has been overwritten.
				This bit is cleared by writing a 1 to it.
14:13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
12	BSTKE	R/W1C	0	Stack Bus Fault
				Value Description
				0 No bus fault has occurred on stacking for exception entry.
				Stacking for an exception entry has caused one or more bus faults.
				When this bit is set, the <b>SP</b> is still adjusted but the values in the context area on the stack might be incorrect. A fault address is not written to the <b>FAULTADDR</b> register.
				This bit is cleared by writing a 1 to it.
11	BUSTKE	R/W1C	0	Unstack Bus Fault
				Value Description
				No bus fault has occurred on unstacking for a return from exception.
				1 Unstacking for a return from exception has caused one or more bus faults.
				This fault is chained to the handler. Thus, when this bit is set, the original return stack is still present. The <b>SP</b> is not adjusted from the failing return, a new save is not performed, and a fault address is not written to the <b>FAULTADDR</b> register.
				This bit is cleared by writing a 1 to it.
10	IMPRE	R/W1C	0	Imprecise Data Bus Error
				Value Description
				O An imprecise data bus error has not occurred.
				A data bus error has occurred, but the return address in the stack frame is not related to the instruction that caused the error.
				When this bit is set, a fault address is not written to the <b>FAULTADDR</b> register.
				This fault is asynchronous. Therefore, if the fault is detected when the priority of the current process is higher than the bus fault priority, the bus fault becomes pending and becomes active only when the processor returns from all higher-priority processes. If a precise fault occurs before the processor enters the handler for the imprecise bus fault, the handler detects that both the IMPRE bit is set and one of the precise fault status bits is set.
				This bit is cleared by writing a 1 to it.
9	PRECISE	R/W1C	0	Precise Data Bus Error
				Value Description
				O A precise data bus error has not occurred.
				A data bus error has occurred, and the PC value stacked for the exception return points to the instruction that caused the fault.
				When this bit is set, the fault address is written to the <b>FAULTADDR</b> register.
				This hit is alread hyperities and to it

October 06, 2012 165

This bit is cleared by writing a 1 to it.

Bit/Field	Name	Туре	Reset	Description
8	IBUS	R/W1C	0	Instruction Bus Error
				Value Description
				O An instruction bus error has not occurred.
				1 An instruction bus error has occurred.
				The processor detects the instruction bus error on prefetching an instruction, but sets this bit only if it attempts to issue the faulting instruction.
				When this bit is set, a fault address is not written to the <b>FAULTADDR</b> register.
				This bit is cleared by writing a 1 to it.
7	MMARV	R/W1C	0	Memory Management Fault Address Register Valid
				Value Description
				The value in the Memory Management Fault Address (MMADDR) register is not a valid fault address.
				1 The <b>MMADDR</b> register is holding a valid fault address.
				If a memory management fault occurs and is escalated to a hard fault because of priority, the hard fault handler must clear this bit. This action prevents problems if returning to a stacked active memory management fault handler whose <b>MMADDR</b> register value has been overwritten.
				This bit is cleared by writing a 1 to it.
6:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	MSTKE	R/W1C	0	Stack Access Violation
				Value Description
				No memory management fault has occurred on stacking for exception entry.
				Stacking for an exception entry has caused one or more access violations.
				When this bit is set, the <b>SP</b> is still adjusted but the values in the context area on the stack might be incorrect. A fault address is not written to the <b>MMADDR</b> register.
				This bit is cleared by writing a 1 to it.

Bit/Field	Name	Туре	Reset	Description
3	MUSTKE	R/W1C	0	Unstack Access Violation
				Value Description
				No memory management fault has occurred on unstacking for a return from exception.
				1 Unstacking for a return from exception has caused one or more access violations.
				This fault is chained to the handler. Thus, when this bit is set, the original return stack is still present. The <b>SP</b> is not adjusted from the failing return, a new save is not performed, and a fault address is not written to the <b>MMADDR</b> register.
				This bit is cleared by writing a 1 to it.
2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	DERR	R/W1C	0	Data Access Violation
				Value Description
				0 A data access violation has not occurred.
				1 The processor attempted a load or store at a location that does not permit the operation.
				When this bit is set, the <b>PC</b> value stacked for the exception return points to the faulting instruction and the address of the attempted access is written to the <b>MMADDR</b> register.
				This bit is cleared by writing a 1 to it.
0	IERR	R/W1C	0	Instruction Access Violation
				Value Description
				O An instruction access violation has not occurred.
				1 The processor attempted an instruction fetch from a location that does not permit execution.
				This fault occurs on any access to an XN region, even when the MPU is disabled or not present.
				When this bit is set, the <b>PC</b> value stacked for the exception return points to the faulting instruction and the address of the attempted access is not written to the <b>MMADDR</b> register.

not written to the **MMADDR** register.

This bit is cleared by writing a 1 to it.

### Register 41: Hard Fault Status (HFAULTSTAT), offset 0xD2C

**Note:** This register can only be accessed from privileged mode.

The **HFAULTSTAT** register gives information about events that activate the hard fault handler.

Bits are cleared by writing a 1 to them.

Hard Fault Status (HFAULTSTAT)

Base 0xE000.E000


0

reserved

RO

0

Offset 0xD2C Type R/W1C, reset 0x0000.0000



This error is always handled by the hard fault handler.

to the instruction that was preempted by the exception.

preserved across a read-modify-write operation.

This bit is cleared by writing a 1 to it.

When this bit is set, the PC value stacked for the exception return points

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be


### Register 42: Memory Management Fault Address (MMADDR), offset 0xD34

**Note:** This register can only be accessed from privileged mode.

The MMADDR register contains the address of the location that generated a memory management fault. When an unaligned access faults, the address in the MMADDR register is the actual address that faulted. Because a single read or write instruction can be split into multiple aligned accesses, the fault address can be any address in the range of the requested access size. Bits in the Memory Management Fault Status (MFAULTSTAT) register indicate the cause of the fault and whether the value in the MMADDR register is valid (see page 162).

Memory Management Fault Address (MMADDR)

Base 0xE000.E000 Offset 0xD34 Type R/W, reset -




When the MMARV bit of **MFAULTSTAT** is set, this field holds the address of the location that generated the memory management fault.


### Register 43: Bus Fault Address (FAULTADDR), offset 0xD38

**Note:** This register can only be accessed from privileged mode.

The **FAULTADDR** register contains the address of the location that generated a bus fault. When an unaligned access faults, the address in the **FAULTADDR** register is the one requested by the instruction, even if it is not the address of the fault. Bits in the **Bus Fault Status (BFAULTSTAT)** register indicate the cause of the fault and whether the value in the **FAULTADDR** register is valid (see page 162).



Base 0xE000.E000 Offset 0xD38 Type R/W, reset -



When the FAULTADDRV bit of **BFAULTSTAT** is set, this field holds the address of the location that generated the bus fault.

# 3.6 Memory Protection Unit (MPU) Register Descriptions

This section lists and describes the Memory Protection Unit (MPU) registers, in numerical order by address offset.

The MPU registers can only be accessed from privileged mode.


# Register 44: MPU Type (MPUTYPE), offset 0xD90

**Note:** This register can only be accessed from privileged mode.

The **MPUTYPE** register indicates whether the MPU is present, and if so, how many regions it supports.

### MPU Type (MPUTYPE)

Base 0xE000.E000 Offset 0xD90 Type RO, reset 0x0000.0800



Bit/Field	Name	Type	Reset	Description
31:24	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23:16	IREGION	RO	0x00	Number of I Regions
				This field indicates the number of supported MPU instruction regions. This field always contains 0x00. The MPU memory map is unified and is described by the DREGION field.
15:8	DREGION	RO	0x08	Number of D Regions
				Value Description
				0x08 Indicates there are eight supported MPU data regions.
7:1	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide
	10001100	110	CAGG	compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	SEPARATE	RO	0	Separate or Unified MPU

Value Description

0 Indicates the MPU is unified.

### Register 45: MPU Control (MPUCTRL), offset 0xD94

**Note:** This register can only be accessed from privileged mode.

The **MPUCTRL** register enables the MPU, enables the default memory map background region, and enables use of the MPU when in the hard fault, Non-maskable Interrupt (NMI), and **Fault Mask Register (FAULTMASK)** escalated handlers.

When the ENABLE and PRIVDEFEN bits are both set:

- For privileged accesses, the default memory map is as described in "Memory Model" on page 90. Any access by privileged software that does not address an enabled memory region behaves as defined by the default memory map.
- Any access by unprivileged software that does not address an enabled memory region causes a memory management fault.

Execute Never (XN) and Strongly Ordered rules always apply to the System Control Space regardless of the value of the ENABLE bit.

When the ENABLE bit is set, at least one region of the memory map must be enabled for the system to function unless the PRIVDEFEN bit is set. If the PRIVDEFEN bit is set and no regions are enabled, then only privileged software can operate.

When the ENABLE bit is clear, the system uses the default memory map, which has the same memory attributes as if the MPU is not implemented (see Table 2-5 on page 93 for more information). The default memory map applies to accesses from both privileged and unprivileged software.


When the MPU is enabled, accesses to the System Control Space and vector table are always permitted. Other areas are accessible based on regions and whether PRIVDEFEN is set.

Unless HFNMIENA is set, the MPU is not enabled when the processor is executing the handler for an exception with priority -1 or -2. These priorities are only possible when handling a hard fault or NMI exception or when **FAULTMASK** is enabled. Setting the HFNMIENA bit enables the MPU when operating with these two priorities.

#### MPU Control (MPUCTRL)

Base 0xE000.E000 Offset 0xD94

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
2	PRIVDEFEN	R/W	0	MPU Default Region  This bit enables privileged software access to the default memory map.
				Value Description
				0 If the MPU is enabled, this bit disables use of the default memory map. Any memory access to a location not covered by any enabled region causes a fault.
				1 If the MPU is enabled, this bit enables use of the default memory map as a background region for privileged software accesses.
				When this bit is set, the background region acts as if it is region number -1. Any region that is defined and enabled has priority over this default map.
				If the MPU is disabled, the processor ignores this bit.
1	HFNMIENA	R/W	0	MPU Enabled During Faults
				This bit controls the operation of the MPU during hard fault, NMI, and <b>FAULTMASK</b> handlers.
				Value Description
				The MPU is disabled during hard fault, NMI, and <b>FAULTMASK</b> handlers, regardless of the value of the ENABLE bit.
				1 The MPU is enabled during hard fault, NMI, and FAULTMASK handlers.
				When the MPU is disabled and this bit is set, the resulting behavior is unpredictable.
0	ENABLE	R/W	0	MPU Enable
				Value Description
				0 The MPU is disabled.
				1 The MPU is enabled.
				When the MPU is disabled and the HFNMIENA bit is set, the resulting behavior is unpredictable.

# Register 46: MPU Region Number (MPUNUMBER), offset 0xD98


**Note:** This register can only be accessed from privileged mode.

The MPUNUMBER register selects which memory region is referenced by the MPU Region Base Address (MPUBASE) and MPU Region Attribute and Size (MPUATTR) registers. Normally, the required region number should be written to this register before accessing the MPUBASE or the MPUATTR register. However, the region number can be changed by writing to the MPUBASE register with the VALID bit set (see page 175). This write updates the value of the REGION field.

#### MPU Region Number (MPUNUMBER)

Base 0xE000.E000 Offset 0xD98

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2:0	NUMBER	R/W	0x0	MPU Region to Access

This field indicates the MPU region referenced by the **MPUBASE** and **MPUATTR** registers. The MPU supports eight memory regions.

Register 47: MPU Region Base Address (MPUBASE), offset 0xD9C

Register 48: MPU Region Base Address Alias 1 (MPUBASE1), offset 0xDA4

Register 49: MPU Region Base Address Alias 2 (MPUBASE2), offset 0xDAC

Register 50: MPU Region Base Address Alias 3 (MPUBASE3), offset 0xDB4

**Note:** This register can only be accessed from privileged mode.

The MPUBASE register defines the base address of the MPU region selected by the MPU Region Number (MPUNUMBER) register and can update the value of the MPUNUMBER register. To change the current region number and update the MPUNUMBER register, write the MPUBASE register with the VALID bit set.

The ADDR field is bits 31:*N* of the **MPUBASE** register. Bits (*N*-1):5 are reserved. The region size, as specified by the SIZE field in the **MPU Region Attribute and Size (MPUATTR)** register, defines the value of *N* where:


 $N = Log_2$  (Region size in bytes)

If the region size is configured to 4 GB in the **MPUATTR** register, there is no valid ADDR field. In this case, the region occupies the complete memory map, and the base address is 0x0000.0000.

The base address is aligned to the size of the region. For example, a 64-KB region must be aligned on a multiple of 64 KB, for example, at 0x0001.0000 or 0x0002.0000.

#### MPU Region Base Address (MPUBASE)

Base 0xE000.E000 Offset 0xD9C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:5	ADDR	R/W	0x0000.000	Base Address Mask

Bits 31:N in this field contain the region base address. The value of N depends on the region size, as shown above. The remaining bits (N-1):5 are reserved.

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
4	VALID	WO	0	Region Number Valid
				Value Description
				The MPUNUMBER register is not changed and the processor updates the base address for the region specified in the MPUNUMBER register and ignores the value of the REGION field.
				The <b>MPUNUMBER</b> register is updated with the value of the REGION field and the base address is updated for the region specified in the REGION field.
				This bit is always read as 0.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2:0	REGION	R/W	0x0	Region Number On a write, contains the value to be written to the <b>MPUNUMBER</b> register. On a read, returns the current region number in the <b>MPUNUMBER</b> register.

Register 51: MPU Region Attribute and Size (MPUATTR), offset 0xDA0

Register 52: MPU Region Attribute and Size Alias 1 (MPUATTR1), offset 0xDA8

Register 53: MPU Region Attribute and Size Alias 2 (MPUATTR2), offset 0xDB0

Register 54: MPU Region Attribute and Size Alias 3 (MPUATTR3), offset 0xDB8

**Note:** This register can only be accessed from privileged mode.

The **MPUATTR** register defines the region size and memory attributes of the MPU region specified by the **MPU Region Number (MPUNUMBER)** register and enables that region and any subregions.

The **MPUATTR** register is accessible using word or halfword accesses with the most-significant halfword holding the region attributes and the least-significant halfword holds the region size and the region and subregion enable bits.

The MPU access permission attribute bits, XN, AP, TEX, S, C, and B, control access to the corresponding memory region. If an access is made to an area of memory without the required permissions, then the MPU generates a permission fault.

The SIZE field defines the size of the MPU memory region specified by the **MPUNUMBER** register as follows:

(Region size in bytes) =  $2^{(SIZE+1)}$ 

The smallest permitted region size is 32 bytes, corresponding to a SIZE value of 4. Table 3-9 on page 177 gives example SIZE values with the corresponding region size and value of N in the MPU Region Base Address (MPUBASE) register.

Table 3-9. Example SIZE Field Values


SIZE Encoding	Region Size	Value of N <sup>a</sup>	Note
00100b (0x4)	32 B	5	Minimum permitted size
01001b (0x9)	1 KB	10	-
10011b (0x13)	1 MB	20	-
11101b (0x1D)	1 GB	30	-
11111b (0x1F)	4 GB	No valid ADDR field in <b>MPUBASE</b> ; the region occupies the complete memory map.	Maximum possible size

a. Refers to the N parameter in the MPUBASE register (see page 175).

#### MPU Region Attribute and Size (MPUATTR)

Base 0xE000.E000 Offset 0xDA0

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:29	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	XN	R/W	0	Instruction Access Disable
				Value Description
				0 Instruction fetches are enabled.
				1 Instruction fetches are disabled.
27	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
26:24	AP	R/W	0	Access Privilege
				For information on using this bit field, see Table 3-5 on page 121.
23:22	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
21:19	TEX	R/W	0x0	Type Extension Mask
				For information on using this bit field, see Table 3-3 on page 120.
18	S	R/W	0	Shareable For information on using this bit, see Table 3-3 on page 120.
17	С	R/W	0	Cacheable
				For information on using this bit, see Table 3-3 on page 120.
16	В	R/W	0	Bufferable
				For information on using this bit, see Table 3-3 on page 120.
15:8	SRD	R/W	0x00	Subregion Disable Bits
				Value Description
				The corresponding subregion is enabled.
				1 The corresponding subregion is disabled.
				Region sizes of 128 bytes and less do not support subregions. When writing the attributes for such a region, configure the SRD field as 0x00. See the section called "Subregions" on page 119 for more information.
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:1	SIZE	R/W	0x0	Region Size Mask
				The SIZE field defines the size of the MPU memory region specified by the <b>MPUNUMBER</b> register. Refer to Table 3-9 on page 177 for more information.

Bit/Field	Name	Туре	Reset	Description
0	ENABLE	R/W	0	Region Enable
				Value Description  The region is disabled.  The region is enabled.

# 4 JTAG Interface

The Joint Test Action Group (JTAG) port is an IEEE standard that defines a Test Access Port and Boundary Scan Architecture for digital integrated circuits and provides a standardized serial interface for controlling the associated test logic. The TAP, Instruction Register (IR), and Data Registers (DR) can be used to test the interconnections of assembled printed circuit boards and obtain manufacturing information on the components. The JTAG Port also provides a means of accessing and controlling design-for-test features such as I/O pin observation and control, scan testing, and debugging.

The JTAG port is comprised of four pins: TCK, TMS, TDI, and TDO. Data is transmitted serially into the controller on TDI and out of the controller on TDO. The interpretation of this data is dependent on the current state of the TAP controller. For detailed information on the operation of the JTAG port and TAP controller, please refer to the *IEEE Standard 1149.1-Test Access Port and Boundary-Scan Architecture*.

The Stellaris<sup>®</sup> JTAG controller works with the ARM JTAG controller built into the Cortex-M3 core by multiplexing the TDO outputs from both JTAG controllers. ARM JTAG instructions select the ARM TDO output while Stellaris JTAG instructions select the Stellaris TDO output. The multiplexer is controlled by the Stellaris JTAG controller, which has comprehensive programming for the ARM, Stellaris, and unimplemented JTAG instructions.


The Stellaris JTAG module has the following features:

- IEEE 1149.1-1990 compatible Test Access Port (TAP) controller
- Four-bit Instruction Register (IR) chain for storing JTAG instructions
- IEEE standard instructions: BYPASS, IDCODE, SAMPLE/PRELOAD, EXTEST and INTEST
- ARM additional instructions: APACC, DPACC and ABORT
- Integrated ARM Serial Wire Debug (SWD)
  - Serial Wire JTAG Debug Port (SWJ-DP)
  - Flash Patch and Breakpoint (FPB) unit for implementing breakpoints
  - Data Watchpoint and Trace (DWT) unit for implementing watchpoints, trigger resources, and system profiling
  - Instrumentation Trace Macrocell (ITM) for support of printf style debugging
  - Trace Port Interface Unit (TPIU) for bridging to a Trace Port Analyzer

See the ARM® Debug Interface V5 Architecture Specification for more information on the ARM JTAG controller.

## 4.1 Block Diagram

Figure 4-1. JTAG Module Block Diagram



## 4.2 Signal Description

The following table lists the external signals of the JTAG/SWD controller and describes the function of each. The JTAG/SWD controller signals are alternate functions for some GPIO signals, however note that the reset state of the pins is for the JTAG/SWD function. The JTAG/SWD controller signals are under commit protection and require a special process to be configured as GPIOs, see "Commit Control" on page 415. The column in the table below titled "Pin Mux/Pin Assignment" lists the GPIO pin placement for the JTAG/SWD controller signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) is set to choose the JTAG/SWD function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the JTAG/SWD controller signals to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 4-1. JTAG\_SWD\_SWO Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SWCLK	80	PC0 (3)	1	TTL	JTAG/SWD CLK.
SWDIO	79	PC1 (3)	I/O	TTL	JTAG TMS and SWDIO.
SWO	77	PC3 (3)	0	TTL	JTAG TDO and SWO.
TCK	80	PC0 (3)	1	TTL	JTAG/SWD CLK.
TDI	78	PC2 (3)	1	TTL	JTAG TDI.
TDO	77	PC3 (3)	0	TTL	JTAG TDO and SWO.

Table 4-1. JTAG\_SWD\_SWO Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
TMS	79	PC1 (3)	I	TTL	JTAG TMS and SWDIO.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 4-2. JTAG\_SWD\_SWO Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SWCLK	A9	PC0 (3)	1	TTL	JTAG/SWD CLK.
SWDIO	В9	PC1 (3)	I/O	TTL	JTAG TMS and SWDIO.
SWO	A10	PC3 (3)	0	TTL	JTAG TDO and SWO.
TCK	A9	PC0 (3)	I	TTL	JTAG/SWD CLK.
TDI	B8	PC2 (3)	I	TTL	JTAG TDI.
TDO	A10	PC3 (3)	0	TTL	JTAG TDO and SWO.
TMS	В9	PC1 (3)	I	TTL	JTAG TMS and SWDIO.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

## 4.3 Functional Description

A high-level conceptual drawing of the JTAG module is shown in Figure 4-1 on page 181. The JTAG module is composed of the Test Access Port (TAP) controller and serial shift chains with parallel update registers. The TAP controller is a simple state machine controlled by the TCK and TMS inputs. The current state of the TAP controller depends on the sequence of values captured on TMS at the rising edge of TCK. The TAP controller determines when the serial shift chains capture new data, shift data from TDI towards TDO, and update the parallel load registers. The current state of the TAP controller also determines whether the Instruction Register (IR) chain or one of the Data Register (DR) chains is being accessed.

The serial shift chains with parallel load registers are comprised of a single Instruction Register (IR) chain and multiple Data Register (DR) chains. The current instruction loaded in the parallel load register determines which DR chain is captured, shifted, or updated during the sequencing of the TAP controller.

Some instructions, like EXTEST and INTEST, operate on data currently in a DR chain and do not capture, shift, or update any of the chains. Instructions that are not implemented decode to the BYPASS instruction to ensure that the serial path between TDI and TDO is always connected (see Table 4-4 on page 188 for a list of implemented instructions).

See "JTAG and Boundary Scan" on page 1318 for JTAG timing diagrams.

Note: Of all the possible reset sources, only Power-On reset (POR) and the assertion of the RST input have any effect on the JTAG module. The pin configurations are reset by both the RST input and POR, whereas the internal JTAG logic is only reset with POR. See "Reset Sources" on page 193 for more information on reset.

#### 4.3.1 JTAG Interface Pins

The JTAG interface consists of four standard pins: TCK, TMS, TDI, and TDO. These pins and their associated state after a power-on reset or reset caused by the RST input are given in Table 4-3. Detailed information on each pin follows. Refer to "General-Purpose Input/Outputs (GPIOs)" on page 407 for information on how to reprogram the configuration of these pins.

Table 4-3. JTAG Port Pins State after Power-On Reset or RST assertion

Pin Name	Data Direction	Internal Pull-Up	Internal Pull-Down	Drive Strength	Drive Value
TCK	Input	Enabled	Disabled	N/A	N/A
TMS	Input	Enabled	Disabled	N/A	N/A
TDI	Input	Enabled	Disabled	N/A	N/A
TDO	Output	Enabled	Disabled	2-mA driver	High-Z

## 4.3.1.1 Test Clock Input (TCK)

The  ${ t TCK}$  pin is the clock for the JTAG module. This clock is provided so the test logic can operate independently of any other system clocks and to ensure that multiple JTAG TAP controllers that are daisy-chained together can synchronously communicate serial test data between components. During normal operation,  ${ t TCK}$  is driven by a free-running clock with a nominal 50% duty cycle. When necessary,  ${ t TCK}$  can be stopped at 0 or 1 for extended periods of time. While  ${ t TCK}$  is stopped at 0 or 1, the state of the TAP controller does not change and data in the JTAG Instruction and Data Registers is not lost.

By default, the internal pull-up resistor on the  ${\tt TCK}$  pin is enabled after reset, assuring that no clocking occurs if the pin is not driven from an external source. The internal pull-up and pull-down resistors can be turned off to save internal power as long as the  ${\tt TCK}$  pin is constantly being driven by an external source (see page 436 and page 438).

### 4.3.1.2 Test Mode Select (TMS)

The TMS pin selects the next state of the JTAG TAP controller. TMS is sampled on the rising edge of TCK. Depending on the current TAP state and the sampled value of TMS, the next state may be entered. Because the TMS pin is sampled on the rising edge of TCK, the *IEEE Standard 1149.1* expects the value on TMS to change on the falling edge of TCK.

Holding TMS high for five consecutive TCK cycles drives the TAP controller state machine to the Test-Logic-Reset state. When the TAP controller enters the Test-Logic-Reset state, the JTAG module and associated registers are reset to their default values. This procedure should be performed to initialize the JTAG controller. The JTAG Test Access Port state machine can be seen in its entirety in Figure 4-2 on page 184.

By default, the internal pull-up resistor on the TMS pin is enabled after reset. Changes to the pull-up resistor settings on GPIO Port C should ensure that the internal pull-up resistor remains enabled on PC1/TMS; otherwise JTAG communication could be lost (see page 436).

#### 4.3.1.3 Test Data Input (TDI)

The TDI pin provides a stream of serial information to the IR chain and the DR chains. TDI is sampled on the rising edge of TCK and, depending on the current TAP state and the current instruction, may present this data to the proper shift register chain. Because the TDI pin is sampled on the rising edge of TCK, the *IEEE Standard 1149.1* expects the value on TDI to change on the falling edge of TCK.

By default, the internal pull-up resistor on the TDI pin is enabled after reset. Changes to the pull-up resistor settings on GPIO Port C should ensure that the internal pull-up resistor remains enabled on PC2/TDI; otherwise JTAG communication could be lost (see page 436).

## 4.3.1.4 Test Data Output (TDO)

The TDO pin provides an output stream of serial information from the IR chain or the DR chains. The value of TDO depends on the current TAP state, the current instruction, and the data in the

chain being accessed. In order to save power when the JTAG port is not being used, the TDO pin is placed in an inactive drive state when not actively shifting out data. Because TDO can be connected to the TDI of another controller in a daisy-chain configuration, the *IEEE Standard 1149.1* expects the value on TDO to change on the falling edge of TCK.

By default, the internal pull-up resistor on the TDO pin is enabled after reset, assuring that the pin remains at a constant logic level when the JTAG port is not being used. The internal pull-up and pull-down resistors can be turned off to save internal power if a High-Z output value is acceptable during certain TAP controller states (see page 436 and page 438).

#### 4.3.2 JTAG TAP Controller

The JTAG TAP controller state machine is shown in Figure 4-2. The TAP controller state machine is reset to the Test-Logic-Reset state on the assertion of a Power-On-Reset (POR). In order to reset the JTAG module after the microcontroller has been powered on, the TMS input must be held HIGH for five TCK clock cycles, resetting the TAP controller and all associated JTAG chains. Asserting the correct sequence on the TMS pin allows the JTAG module to shift in new instructions, shift in data, or idle during extended testing sequences. For detailed information on the function of the TAP controller and the operations that occur in each state, please refer to *IEEE Standard 1149.1*.

Test Logic Reset 0 Run Test Idle Select DR Scar Select IR Scar 0 0 Capture DR Capture IR 0 0 Shift DR Shift IR 1 1 Exit 1 DR Exit 1 IR 0 0 Pause DR Pause IR 1 Exit 2 DR Exit 2 IR 1 Update DR Update IR 1 0 1 0

Figure 4-2. Test Access Port State Machine

## 4.3.3 Shift Registers

The Shift Registers consist of a serial shift register chain and a parallel load register. The serial shift register chain samples specific information during the TAP controller's CAPTURE states and allows

this information to be shifted out on TDO during the TAP controller's SHIFT states. While the sampled data is being shifted out of the chain on TDO, new data is being shifted into the serial shift register on TDI. This new data is stored in the parallel load register during the TAP controller's UPDATE states. Each of the shift registers is discussed in detail in "Register Descriptions" on page 188.

## 4.3.4 Operational Considerations

Certain operational parameters must be considered when using the JTAG module. Because the JTAG pins can be programmed to be GPIOs, board configuration and reset conditions on these pins must be considered. In addition, because the JTAG module has integrated ARM Serial Wire Debug, the method for switching between these two operational modes is described below.

#### 4.3.4.1 **GPIO** Functionality

When the microcontroller is reset with either a POR or RST, the JTAG/SWD port pins default to their JTAG/SWD configurations. The default configuration includes enabling digital functionality (DEN[3:0] set in the Port C GPIO Digital Enable (GPIODEN) register), enabling the pull-up resistors (PUE[3:0] set in the Port C GPIO Pull-Up Select (GPIOPUR) register), disabling the pull-down resistors (PDE[3:0] cleared in the Port C GPIO Pull-Down Select (GPIOPDR) register) and enabling the alternate hardware function (AFSEL[3:0] set in the Port C GPIO Alternate Function Select (GPIOAFSEL) register) on the JTAG/SWD pins. See page 430, page 436, page 438, and page 441.

It is possible for software to configure these pins as GPIOs after reset by clearing AFSEL[3:0] in the **Port C GPIOAFSEL** register. If the user does not require the JTAG/SWD port for debugging or board-level testing, this provides four more GPIOs for use in the design.

Caution – It is possible to create a software sequence that prevents the debugger from connecting to the Stellaris microcontroller. If the program code loaded into flash immediately changes the JTAG pins to their GPIO functionality, the debugger may not have enough time to connect and halt the controller before the JTAG pin functionality switches. As a result, the debugger may be locked out of the part. This issue can be avoided with a software routine that restores JTAG functionality based on an external or software trigger.

The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see page 441) are not committed to storage unless the GPIO Lock (GPIOLOCK) register (see page 443) has been unlocked and the appropriate bits of the GPIO Commit (GPIOCR) register (see page 444) have been set.

#### 4.3.4.2 Communication with JTAG/SWD

Because the debug clock and the system clock can be running at different frequencies, care must be taken to maintain reliable communication with the JTAG/SWD interface. In the Capture-DR state, the result of the previous transaction, if any, is returned, together with a 3-bit ACK response. Software should check the ACK response to see if the previous operation has completed before initiating a new transaction. Alternatively, if the system clock is at least 8 times faster than the debug clock ( ${\tt TCK}$  or  ${\tt SWCLK}$ ), the previous operation has enough time to complete and the ACK bits do not have to be checked.

#### 4.3.4.3 Recovering a "Locked" Microcontroller

**Note:** Performing the sequence below restores the non-volatile registers discussed in "Non-Volatile Register Programming" on page 307 to their factory default values. The mass erase of the Flash memory caused by the sequence below occurs prior to the non-volatile registers being restored.

If software configures any of the JTAG/SWD pins as GPIO and loses the ability to communicate with the debugger, there is a debug port unlock sequence that can be used to recover the microcontroller. Performing a total of ten JTAG-to-SWD and SWD-to-JTAG switch sequences while holding the microcontroller in reset mass erases the Flash memory. The debug port unlock sequence is:

- 1. Assert and hold the  $\overline{\mathtt{RST}}$  signal.
- **2.** Apply power to the device.
- **3.** Perform steps 1 and 2 of the JTAG-to-SWD switch sequence on the section called "JTAG-to-SWD Switching" on page 187.
- **4.** Perform steps 1 and 2 of the SWD-to-JTAG switch sequence on the section called "SWD-to-JTAG Switching" on page 187.
- **5.** Perform steps 1 and 2 of the JTAG-to-SWD switch sequence.
- **6.** Perform steps 1 and 2 of the SWD-to-JTAG switch sequence.
- **7.** Perform steps 1 and 2 of the JTAG-to-SWD switch sequence.
- **8.** Perform steps 1 and 2 of the SWD-to-JTAG switch sequence.
- **9.** Perform steps 1 and 2 of the JTAG-to-SWD switch sequence.
- **10.** Perform steps 1 and 2 of the SWD-to-JTAG switch sequence.
- **11.** Perform steps 1 and 2 of the JTAG-to-SWD switch sequence.
- **12.** Perform steps 1 and 2 of the SWD-to-JTAG switch sequence.
- **13.** Release the  $\overline{RST}$  signal.
- 14. Wait 400 ms.
- **15.** Power-cycle the microcontroller.

#### 4.3.4.4 ARM Serial Wire Debug (SWD)

In order to seamlessly integrate the ARM Serial Wire Debug (SWD) functionality, a serial-wire debugger must be able to connect to the Cortex-M3 core without having to perform, or have any knowledge of, JTAG cycles. This integration is accomplished with a SWD preamble that is issued before the SWD session begins.

The switching preamble used to enable the SWD interface of the SWJ-DP module starts with the TAP controller in the Test-Logic-Reset state. From here, the preamble sequences the TAP controller through the following states: Run Test Idle, Select DR, Select IR, Test Logic Reset, Test Logic Reset, Run Test Idle, Run Test Idle, Select DR, Select IR, Test Logic Reset, Test Logic Reset, Run Test Idle, Select DR, Select IR, and Test Logic Reset states.

Stepping through this sequence of the TAP state machine enables the SWD interface and disables the JTAG interface. For more information on this operation and the SWD interface, see the *ARM® Debug Interface V5 Architecture Specification*.

Because this sequence is a valid series of JTAG operations that could be issued, the ARM JTAG TAP controller is not fully compliant to the *IEEE Standard 1149.1*. This instance is the only one where the ARM JTAG TAP controller does not meet full compliance with the specification. Due to the low probability of this sequence occurring during normal operation of the TAP controller, it should not affect normal performance of the JTAG interface.

#### JTAG-to-SWD Switching

To switch the operating mode of the Debug Access Port (DAP) from JTAG to SWD mode, the external debug hardware must send the switching preamble to the microcontroller. The 16-bit TMS command for switching to SWD mode is defined as b1110.0111.1001.1110, transmitted LSB first. This command can also be represented as 0xE79E when transmitted LSB first. The complete switch sequence should consist of the following transactions on the TCK/SWCLK and TMS/SWDIO signals:

- 1. Send at least 50 TCK/SWCLK cycles with TMS/SWDIO High to ensure that both JTAG and SWD are in their reset/idle states.
- 2. Send the 16-bit JTAG-to-SWD switch command, 0xE79E, on TMS.
- 3. Send at least 50 TCK/SWCLK cycles with TMS/SWDIO High to ensure that if SWJ-DP was already in SWD mode, the SWD goes into the line reset state before sending the switch sequence.

#### SWD-to-JTAG Switching

To switch the operating mode of the Debug Access Port (DAP) from SWD to JTAG mode, the external debug hardware must send a switch command to the microcontroller. The 16-bit TMS command for switching to JTAG mode is defined as b1110.0111.0011.1100, transmitted LSB first. This command can also be represented as 0xE73C when transmitted LSB first. The complete switch sequence should consist of the following transactions on the TCK/SWCLK and TMS/SWDIO signals:

- 1. Send at least 50 TCK/SWCLK cycles with TMS/SWDIO High to ensure that both JTAG and SWD are in their reset/idle states.
- 2. Send the 16-bit SWD-to-JTAG switch command, 0xE73C, on TMS.
- 3. Send at least 50 TCK/SWCLK cycles with TMS/SWDIO High to ensure that if SWJ-DP was already in JTAG mode, the JTAG goes into the Test Logic Reset state before sending the switch sequence.

## 4.4 Initialization and Configuration

After a Power-On-Reset or an external reset ( $\overline{RST}$ ), the JTAG pins are automatically configured for JTAG communication. No user-defined initialization or configuration is needed. However, if the user application changes these pins to their GPIO function, they must be configured back to their JTAG functionality before JTAG communication can be restored. To return the pins to their JTAG functions, enable the four JTAG pins (PC[3:0]) for their alternate function using the **GPIOAFSEL** register. In addition to enabling the alternate functions, any other changes to the GPIO pad configurations on the four JTAG pins (PC[3:0]) should be returned to their default settings.

## 4.5 Register Descriptions

The registers in the JTAG TAP Controller or Shift Register chains are not memory mapped and are not accessible through the on-chip Advanced Peripheral Bus (APB). Instead, the registers within the JTAG controller are all accessed serially through the TAP Controller. These registers include the Instruction Register and the six Data Registers.

## 4.5.1 Instruction Register (IR)

The JTAG TAP Instruction Register (IR) is a four-bit serial scan chain connected between the JTAG TDI and TDO pins with a parallel load register. When the TAP Controller is placed in the correct states, bits can be shifted into the IR. Once these bits have been shifted into the chain and updated, they are interpreted as the current instruction. The decode of the IR bits is shown in Table 4-4. A detailed explanation of each instruction, along with its associated Data Register, follows.

IR[3:0]	Instruction	Description
0x0	EXTEST	Drives the values preloaded into the Boundary Scan Chain by the SAMPLE/PRELOAD instruction onto the pads.
0x1	INTEST	Drives the values preloaded into the Boundary Scan Chain by the SAMPLE/PRELOAD instruction into the controller.
0x2	SAMPLE / PRELOAD	Captures the current I/O values and shifts the sampled values out of the Boundary Scan Chain while new preload data is shifted in.
0x8	ABORT	Shifts data into the ARM Debug Port Abort Register.
0xA	DPACC	Shifts data into and out of the ARM DP Access Register.
0xB	APACC	Shifts data into and out of the ARM AC Access Register.
0xE	IDCODE	Loads manufacturing information defined by the <i>IEEE Standard 1149.1</i> into the IDCODE chain and shifts it out.
0xF	BYPASS	Connects TDI to TDO through a single Shift Register chain.
All Others	Reserved	Defaults to the BYPASS instruction to ensure that $\mathtt{TDI}$ is always connected to $\mathtt{TDO}$ .

#### 4.5.1.1 EXTEST Instruction

The EXTEST instruction is not associated with its own Data Register chain. Instead, the EXTEST instruction uses the data that has been preloaded into the Boundary Scan Data Register using the SAMPLE/PRELOAD instruction. When the EXTEST instruction is present in the Instruction Register, the preloaded data in the Boundary Scan Data Register associated with the outputs and output enables are used to drive the GPIO pads rather than the signals coming from the core. With tests that drive known values out of the controller, this instruction can be used to verify connectivity. While the EXTEST instruction is present in the Instruction Register, the Boundary Scan Data Register can be accessed to sample and shift out the current data and load new data into the Boundary Scan Data Register.

#### 4.5.1.2 INTEST Instruction

The INTEST instruction is not associated with its own Data Register chain. Instead, the INTEST instruction uses the data that has been preloaded into the Boundary Scan Data Register using the SAMPLE/PRELOAD instruction. When the INTEST instruction is present in the Instruction Register, the preloaded data in the Boundary Scan Data Register associated with the inputs are used to drive the signals going into the core rather than the signals coming from the GPIO pads. With tests that drive known values into the controller, this instruction can be used for testing. It is important to note that although the RST input pin is on the Boundary Scan Data Register chain, it is only observable.

While the INTEST instruction is present in the Instruction Register, the Boundary Scan Data Register can be accessed to sample and shift out the current data and load new data into the Boundary Scan Data Register.

#### 4.5.1.3 SAMPLE/PRELOAD Instruction

The SAMPLE/PRELOAD instruction connects the Boundary Scan Data Register chain between TDI and TDO. This instruction samples the current state of the pad pins for observation and preloads new test data. Each GPIO pad has an associated input, output, and output enable signal. When the TAP controller enters the Capture DR state during this instruction, the input, output, and output-enable signals to each of the GPIO pads are captured. These samples are serially shifted out on TDO while the TAP controller is in the Shift DR state and can be used for observation or comparison in various tests.

While these samples of the inputs, outputs, and output enables are being shifted out of the Boundary Scan Data Register, new data is being shifted into the Boundary Scan Data Register from TDI. Once the new data has been shifted into the Boundary Scan Data Register, the data is saved in the parallel load registers when the TAP controller enters the Update DR state. This update of the parallel load register preloads data into the Boundary Scan Data Register that is associated with each input, output, and output enable. This preloaded data can be used with the EXTEST and INTEST instructions to drive data into or out of the controller. See "Boundary Scan Data Register" on page 190 for more information.

## 4.5.1.4 ABORT Instruction

The ABORT instruction connects the associated ABORT Data Register chain between TDI and TDO. This instruction provides read and write access to the ABORT Register of the ARM Debug Access Port (DAP). Shifting the proper data into this Data Register clears various error bits or initiates a DAP abort of a previous request. See the "ABORT Data Register" on page 191 for more information.

#### 4.5.1.5 DPACC Instruction

The DPACC instruction connects the associated DPACC Data Register chain between TDI and TDO. This instruction provides read and write access to the DPACC Register of the ARM Debug Access Port (DAP). Shifting the proper data into this register and reading the data output from this register allows read and write access to the ARM debug and status registers. See "DPACC Data Register" on page 191 for more information.

#### 4.5.1.6 APACC Instruction

The APACC instruction connects the associated APACC Data Register chain between TDI and TDO. This instruction provides read and write access to the APACC Register of the ARM Debug Access Port (DAP). Shifting the proper data into this register and reading the data output from this register allows read and write access to internal components and buses through the Debug Port. See "APACC Data Register" on page 191 for more information.

## 4.5.1.7 IDCODE Instruction

The IDCODE instruction connects the associated IDCODE Data Register chain between TDI and TDO. This instruction provides information on the manufacturer, part number, and version of the ARM core. This information can be used by testing equipment and debuggers to automatically configure input and output data streams. IDCODE is the default instruction loaded into the JTAG Instruction Register when a Power-On-Reset (POR) is asserted, or the Test-Logic-Reset state is entered. See "IDCODE Data Register" on page 190 for more information.

#### 4.5.1.8 BYPASS Instruction

The BYPASS instruction connects the associated BYPASS Data Register chain between TDI and TDO. This instruction is used to create a minimum length serial path between the TDI and TDO ports. The BYPASS Data Register is a single-bit shift register. This instruction improves test efficiency by allowing components that are not needed for a specific test to be bypassed in the JTAG scan chain by loading them with the BYPASS instruction. See "BYPASS Data Register" on page 190 for more information.

## 4.5.2 Data Registers

The JTAG module contains six Data Registers. These serial Data Register chains include: IDCODE, BYPASS, Boundary Scan, APACC, DPACC, and ABORT and are discussed in the following sections.

## 4.5.2.1 IDCODE Data Register

The format for the 32-bit IDCODE Data Register defined by the *IEEE Standard 1149.1* is shown in Figure 4-3. The standard requires that every JTAG-compliant microcontroller implement either the IDCODE instruction or the BYPASS instruction as the default instruction. The LSB of the IDCODE Data Register is defined to be a 1 to distinguish it from the BYPASS instruction, which has an LSB of 0. This definition allows auto-configuration test tools to determine which instruction is the default instruction.

The major uses of the JTAG port are for manufacturer testing of component assembly and program development and debug. To facilitate the use of auto-configuration debug tools, the IDCODE instruction outputs a value of 0x4BA0.0477. This value allows the debuggers to automatically configure themselves to work correctly with the Cortex-M3 during debug.

Figure 4-3. IDCODE Register Format



### 4.5.2.2 BYPASS Data Register

The format for the 1-bit BYPASS Data Register defined by the *IEEE Standard 1149.1* is shown in Figure 4-4. The standard requires that every JTAG-compliant microcontroller implement either the BYPASS instruction or the IDCODE instruction as the default instruction. The LSB of the BYPASS Data Register is defined to be a 0 to distinguish it from the IDCODE instruction, which has an LSB of 1. This definition allows auto-configuration test tools to determine which instruction is the default instruction.

Figure 4-4. BYPASS Register Format


#### 4.5.2.3 Boundary Scan Data Register

The format of the Boundary Scan Data Register is shown in Figure 4-5. Each GPIO pin, starting with a GPIO pin next to the JTAG port pins, is included in the Boundary Scan Data Register. Each

GPIO pin has three associated digital signals that are included in the chain. These signals are input, output, and output enable, and are arranged in that order as shown in the figure.

When the Boundary Scan Data Register is accessed with the SAMPLE/PRELOAD instruction, the input, output, and output enable from each digital pad are sampled and then shifted out of the chain to be verified. The sampling of these values occurs on the rising edge of TCK in the Capture DR state of the TAP controller. While the sampled data is being shifted out of the Boundary Scan chain in the Shift DR state of the TAP controller, new data can be preloaded into the chain for use with the EXTEST and INTEST instructions. The EXTEST instruction forces data out of the controller, and the INTEST instruction forces data into the controller.

Figure 4-5. Boundary Scan Register Format



#### 4.5.2.4 APACC Data Register

The format for the 35-bit APACC Data Register defined by ARM is described in the *ARM® Debug Interface V5 Architecture Specification*.

#### 4.5.2.5 DPACC Data Register

The format for the 35-bit DPACC Data Register defined by ARM is described in the *ARM® Debug Interface V5 Architecture Specification*.

#### 4.5.2.6 ABORT Data Register

The format for the 35-bit ABORT Data Register defined by ARM is described in the *ARM® Debug Interface V5 Architecture Specification*.

# 5 System Control

System control configures the overall operation of the device and provides information about the device. Configurable features include reset control, NMI operation, power control, clock control, and low-power modes.

## 5.1 Signal Description

The following table lists the external signals of the System Control module and describes the function of each. The NMI signal is the alternate function for the GPIO PB7 signal and functions as a GPIO after reset. PB7 is under commit protection and requires a special process to be configured as any alternate function or to subsequently return to the GPIO function, see "Commit Control" on page 415. The column in the table below titled "Pin Mux/Pin Assignment" lists the GPIO pin placement for the NMI signal. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the NMI function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the NMI signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407. The remaining signals (with the word "fixed" in the Pin Mux/Pin Assignment column) have a fixed pin assignment and function.

Table 5-1. System Control & Clocks Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
NMI	89	PB7 (4)	1	TTL	Non-maskable interrupt.
osc0	48	fixed	I	Analog	Main oscillator crystal input or an external clock reference input.
OSC1	49	fixed	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
RST	64	fixed	1	TTL	System reset input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 5-2. System Control & Clocks Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
NMI	A8	PB7 (4)	1	TTL	Non-maskable interrupt.
OSC0	L11	fixed	I	Analog	Main oscillator crystal input or an external clock reference input.
OSC1	M11	fixed	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
RST	H11	fixed	1	TTL	System reset input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

## **5.2** Functional Description

The System Control module provides the following capabilities:

- Device identification, see "Device Identification" on page 193
- Local control, such as reset (see "Reset Control" on page 193), power (see "Power Control" on page 198) and clock control (see "Clock Control" on page 199)

■ System control (Run, Sleep, and Deep-Sleep modes), see "System Control" on page 205

## 5.2.1 Device Identification

Several read-only registers provide software with information on the microcontroller, such as version, part number, SRAM size, Flash memory size, and other features. See the **DID0** (page 210), **DID1** (page 238), **DC0-DC9** (page 240) and **NVMSTAT** (page 263) registers.

## 5.2.2 Reset Control

This section discusses aspects of hardware functions during reset as well as system software requirements following the reset sequence.

#### 5.2.2.1 Reset Sources

The LM3S9D96 microcontroller has six sources of reset:

- 1. Power-on reset (POR) (see page 194).
- **2.** External reset input pin  $(\overline{RST})$  assertion (see page 194).
- 3. Internal brown-out (BOR) detector (see page 196).
- **4.** Software-initiated reset (with the software reset registers) (see page 196).
- **5.** A watchdog timer reset condition violation (see page 197).
- 6. MOSC failure (see page 198).

Table 5-3 provides a summary of results of the various reset operations.

Table 5-3. Reset Sources

Reset Source	Core Reset?	JTAG Reset?	On-Chip Peripherals Reset?
Power-On Reset	Yes	Yes	Yes
RST	Yes	Yes	Yes
Brown-Out Reset	Yes	Yes	Yes
Software System Request Reset using the SYSRESREQ bit in the <b>APINT</b> register.	Yes	Yes	Yes
Software System Request Reset using the VECTRESET bit in the <b>APINT</b> register.	Yes	No	No
Software Peripheral Reset	No	Yes	Yes <sup>a</sup>
Watchdog Reset	Yes	Yes	Yes
MOSC Failure Reset	Yes	Yes	Yes

a. Programmable on a module-by-module basis using the Software Reset Control Registers.

After a reset, the **Reset Cause (RESC)** register is set with the reset cause. The bits in this register are sticky and maintain their state across multiple reset sequences, except when an internal POR is the cause, in which case, all the bits in the **RESC** register are cleared except for the POR indicator. A bit in the **RESC** register can be cleared by writing a 0.

At any reset that resets the core, the user has the opportunity to direct the core to execute the ROM Boot Loader or the application in Flash memory by using any GPIO signal as configured in the **Boot Configuration (BOOTCFG)** register.

At reset, the ROM is mapped over the Flash memory so that the ROM boot sequence is always executed. The boot sequence executed from ROM is as follows:

- 1. The BA bit (below) is cleared such that ROM is mapped to 0x01xx.xxxx and Flash memory is mapped to address 0x0.
- 2. The **BOOTCFG** register is read. If the EN bit is clear, the status of the specified GPIO pin is compared with the specified polarity. If the status matches the specified polarity, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- 3. If the status doesn't match the specified polarity, the data at address 0x0000.0004 is read, and if the data at this address is 0xFFFF.FFFF, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- **4.** If there is valid data at address 0x0000.0004, the stack pointer (**SP**) is loaded from Flash memory at address 0x0000.0000 and the program counter (**PC**) is loaded from address 0x0000.0004. The user application begins executing.

For example, if the **BOOTCFG** register is written and committed with the value of 0x0000.3C01, then PB7 is examined at reset to determine if the ROM Boot Loader should be executed. If PB7 is Low, the core unconditionally begins executing the ROM boot loader. If PB7 is High, then the application in Flash memory is executed if the reset vector at location 0x0000.0004 is not 0xFFFF.FFFF. Otherwise, the ROM boot loader is executed.

#### 5.2.2.2 Power-On Reset (POR)

The internal Power-On Reset (POR) circuit monitors the power supply voltage ( $V_{DD}$ ) and generates a reset signal to all of the internal logic including JTAG when the power supply ramp reaches a threshold value ( $V_{TH}$ ). The microcontroller must be operating within the specified operating parameters when the on-chip power-on reset pulse is complete (see "Power and Brown-Out" on page 1320). For applications that require the use of an external reset signal to hold the microcontroller in reset longer than the internal POR, the  $\overline{RST}$  input may be used as discussed in "External  $\overline{RST}$  Pin" on page 194.

The Power-On Reset sequence is as follows:

- 1. The microcontroller waits for internal POR to go inactive.
- 2. The internal reset is released and the core loads from memory the initial stack pointer, the initial program counter, and the first instruction designated by the program counter, and then begins execution.


The internal POR is only active on the initial power-up of the microcontroller. The Power-On Reset timing is shown in Figure 26-4 on page 1320.

#### 5.2.2.3 External RST Pin

**Note:** It is recommended that the trace for the  $\overline{\mathtt{RST}}$  signal must be kept as short as possible. Be sure to place any components connected to the  $\overline{\mathtt{RST}}$  signal as close to the microcontroller as possible.

If the application only uses the internal POR circuit, the  $\overline{\text{RST}}$  input must be connected to the power supply  $(V_{DD})$  through an optional pull-up resistor (0 to 100K  $\Omega$ ) as shown in Figure 5-1 on page 195.

Figure 5-1. Basic RST Configuration




 $R_{PIJ}$  = 0 to 100 k $\Omega$ 

The external reset pin (RST) resets the microcontroller including the core and all the on-chip peripherals except the JTAG TAP controller (see "JTAG Interface" on page 180). The external reset sequence is as follows:

- 1. The external reset pin ( $\overline{RST}$ ) is asserted for the duration specified by  $T_{MIN}$  and then de-asserted (see "Reset" on page 1321).
- 2. The internal reset is released and the core loads from memory the initial stack pointer, the initial program counter, and the first instruction designated by the program counter, and then begins execution.

To improve noise immunity and/or to delay reset at power up, the  $\overline{RST}$  input may be connected to an RC network as shown in Figure 5-2 on page 195.

Figure 5-2. External Circuitry to Extend Power-On Reset




 $R_{PU}$  = 1 k $\Omega$  to 100 k $\Omega$ 

 $C_1 = 1 \text{ nF to } 10 \mu\text{F}$ 

If the application requires the use of an external reset switch, Figure 5-3 on page 196 shows the proper circuitry to use.

Figure 5-3. Reset Circuit Controlled by Switch



Typical  $R_{PU}$  = 10  $k\Omega$ 

Typical  $R_S = 470 \Omega$ 

 $C_1 = 10 \text{ nF}$ 

The R<sub>PLI</sub> and C<sub>1</sub> components define the power-on delay.

The external reset timing is shown in Figure 26-7 on page 1321.

### 5.2.2.4 Brown-Out Reset (BOR)

The microcontroller provides a brown-out detection circuit that triggers if the power supply  $(V_{DD})$  drops below a brown-out threshold voltage  $(V_{BTH})$ . If a brown-out condition is detected, the system may generate an interrupt or a system reset. The default condition is to reset the microcontroller. Brown-out resets are controlled with the **Power-On and Brown-Out Reset Control (PBORCTL)** register. The BORIOR bit in the **PBORCTL** register must be set for a brown-out condition to trigger a reset; if BORIOR is clear, an interrupt is generated. When a Brown-out condition occurs during a Flash PROGRAM or ERASE operation, a full system reset is always triggered without regard to the setting in the **PBORCTL** register.

The brown-out reset sequence is as follows:

- **1.** When  $V_{DD}$  drops below  $V_{BTH}$ , an internal BOR condition is set.
- 2. If the BOR condition exists, an internal reset is asserted.
- 3. The internal reset is released and the microcontroller fetches and loads the initial stack pointer, the initial program counter, the first instruction designated by the program counter, and begins execution.
- **4.** The internal BOR condition is reset after 500 µs to prevent another BOR condition from being set before software has a chance to investigate the original cause.

The result of a brown-out reset is equivalent to that of an assertion of the external  $\overline{\mathtt{RST}}$  input, and the reset is held active until the proper  $V_{DD}$  level is restored. The **RESC** register can be examined in the reset interrupt handler to determine if a Brown-Out condition was the cause of the reset, thus allowing software to determine what actions are required to recover.

The internal Brown-Out Reset timing is shown in Figure 26-5 on page 1320.

#### 5.2.2.5 Software Reset

Software can reset a specific peripheral or generate a reset to the entire microcontroller.

Peripherals can be individually reset by software via three registers that control reset signals to each on-chip peripheral (see the **SRCRn** registers, page 293). If the bit position corresponding to a peripheral is set and subsequently cleared, the peripheral is reset. The encoding of the reset registers is consistent with the encoding of the clock gating control for peripherals and on-chip functions (see "System Control" on page 205).

The entire microcontroller, including the core, can be reset by software by setting the SYSRESREQ bit in the **Application Interrupt and Reset Control (APINT)** register. The software-initiated system reset sequence is as follows:

- A software microcontroller reset is initiated by setting the SYSRESREQ bit.
- 2. An internal reset is asserted.
- **3.** The internal reset is deasserted and the microcontroller loads from memory the initial stack pointer, the initial program counter, and the first instruction designated by the program counter, and then begins execution.

The core only can be reset by software by setting the VECTRESET bit in the APINT register. The software-initiated core reset sequence is as follows:

- 1. A core reset is initiated by setting the VECTRESET bit.
- 2. An internal reset is asserted.
- **3.** The internal reset is deasserted and the microcontroller loads from memory the initial stack pointer, the initial program counter, and the first instruction designated by the program counter, and then begins execution.

The software-initiated system reset timing is shown in Figure 26-8 on page 1321.

#### 5.2.2.6 Watchdog Timer Reset

The Watchdog Timer module's function is to prevent system hangs. The LM3S9D96 microcontroller has two Watchdog Timer modules in case one watchdog clock source fails. One watchdog is run off the system clock and the other is run off the Precision Internal Oscillator (PIOSC). Each module operates in the same manner except that because the PIOSC watchdog timer module is in a different clock domain, register accesses must have a time delay between them. The watchdog timer can be configured to generate an interrupt to the microcontroller on its first time-out and to generate a reset on its second time-out.

After the watchdog's first time-out event, the 32-bit watchdog counter is reloaded with the value of the **Watchdog Timer Load (WDTLOAD)** register and resumes counting down from that value. If the timer counts down to zero again before the first time-out interrupt is cleared, and the reset signal has been enabled, the watchdog timer asserts its reset signal to the microcontroller. The watchdog timer reset sequence is as follows:

- 1. The watchdog timer times out for the second time without being serviced.
- 2. An internal reset is asserted.
- **3.** The internal reset is released and the microcontroller loads from memory the initial stack pointer, the initial program counter, and the first instruction designated by the program counter, and then begins execution.

For more information on the Watchdog Timer module, see "Watchdog Timers" on page 584.

The watchdog reset timing is shown in Figure 26-9 on page 1322.

## 5.2.3 Non-Maskable Interrupt

The microcontroller has three sources of non-maskable interrupt (NMI):

- The assertion of the NMI signal
- A main oscillator verification error
- The NMISET bit in the Interrupt Control and State (INTCTRL) register in the Cortex<sup>™</sup>-M3 (see page 145).

Software must check the cause of the interrupt in order to distinguish among the sources.

#### 5.2.3.1 NMI Pin

The NMI signal is the alternate function for GPIO port pin PB7. The alternate function must be enabled in the GPIO for the signal to be used as an interrupt, as described in "General-Purpose Input/Outputs (GPIOs)" on page 407. Note that enabling the NMI alternate function requires the use of the GPIO lock and commit function just like the GPIO port pins associated with JTAG/SWD functionality, see page 444. The active sense of the NMI signal is High; asserting the enabled NMI signal above  $V_{\text{IH}}$  initiates the NMI interrupt sequence.

#### 5.2.3.2 Main Oscillator Verification Failure

The LM3S9D96 microcontroller provides a main oscillator verification circuit that generates an error condition if the oscillator is running too fast or too slow. If the main oscillator verification circuit is enabled and a failure occurs, a power-on reset is generated and control is transferred to the NMI handler. The NMI handler is used to address the main oscillator verification failure because the necessary code can be removed from the general reset handler, speeding up reset processing. The detection circuit is enabled by setting the CVAL bit in the **Main Oscillator Control (MOSCCTL)** register. The main oscillator verification error is indicated in the main oscillator fail status (MOSCFAIL) bit in the **Reset Cause (RESC)** register. The main oscillator verification circuit action is described in more detail in "Main Oscillator Verification Circuit" on page 205.

#### 5.2.4 Power Control

The Stellaris<sup>®</sup> microcontroller provides an integrated LDO regulator that is used to provide power to the majority of the microcontroller's internal logic. Figure 5-4 shows the power architecture.

An external LDO may not be used.

**Note:** VDDA must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, or the microcontroller does not function properly. VDDA is the supply for all of the analog circuitry on the device, including the clock circuitry.




Figure 5-4. Power Architecture

#### 5.2.5 Clock Control

System control determines the control of clocks in this part.

### 5.2.5.1 Fundamental Clock Sources

There are multiple clock sources for use in the microcontroller:

- Precision Internal Oscillator (PIOSC). The precision internal oscillator is an on-chip clock source that is the clock source the microcontroller uses during and following POR. It does not require the use of any external components and provides a clock that is 16 MHz ±1% at room temperature and ±3% across temperature. The PIOSC allows for a reduced system cost in applications that require an accurate clock source. If the main oscillator is required, software must enable the main oscillator following reset and allow the main oscillator to stabilize before changing the clock reference.
- Main Oscillator (MOSC). The main oscillator provides a frequency-accurate clock source by one of two means: an external single-ended clock source is connected to the OSC0 input pin, or an external crystal is connected across the OSC0 input and OSC1 output pins. If the PLL is being used, the crystal value must be one of the supported frequencies between 3.579545 MHz to 16.384 MHz (inclusive). If the PLL is not being used, the crystal may be any one of the supported frequencies between 1 MHz to 16.384 MHz. The single-ended clock source range is from DC

through the specified speed of the microcontroller. The supported crystals are listed in the XTAL bit field in the **RCC** register (see page 221). Note that the MOSC provides the clock source for the USB PLL and must be connected to a crystal or an oscillator.

■ Internal 30-kHz Oscillator. The internal 30-kHz oscillator provides an operational frequency of 30 kHz ± 50%. It is intended for use during Deep-Sleep power-saving modes. This power-savings mode benefits from reduced internal switching and also allows the MOSC to be powered down.

The internal system clock (SysClk), is derived from any of the above sources plus two others: the output of the main internal PLL and the precision internal oscillator divided by four (4 MHz  $\pm$  1%). The frequency of the PLL clock reference must be in the range of 3.579545 MHz to 16.384 MHz (inclusive). Table 5-4 on page 200 shows how the various clock sources can be used in a system.

**Table 5-4. Clock Source Options** 

Clock Source	Drive PLL?		Used as SysClk?	
Precision Internal Oscillator	Yes	BYPASS = 0, OSCSRC = 0x1	Yes	BYPASS = 1, OSCSRC = 0x1
Precision Internal Oscillator divide by 4 (4 MHz ± 1%)	No	-	Yes	BYPASS = 1, OSCSRC = 0x2
Main Oscillator	Yes	BYPASS = 0, OSCSRC = 0x0	Yes	BYPASS = 1, OSCSRC = 0x0
Internal 30-kHz Oscillator	No	-	Yes	BYPASS = 1, OSCSRC = 0x3

## 5.2.5.2 Clock Configuration

The Run-Mode Clock Configuration (RCC) and Run-Mode Clock Configuration 2 (RCC2) registers provide control for the system clock. The RCC2 register is provided to extend fields that offer additional encodings over the RCC register. When used, the RCC2 register field values are used by the logic over the corresponding field in the RCC register. In particular, RCC2 provides for a larger assortment of clock configuration options. These registers control the following clock functionality:


- Source of clocks in sleep and deep-sleep modes
- System clock derived from PLL or other clock source
- Enabling/disabling of oscillators and PLL
- Clock divisors
- Crystal input selection

**Important:** Write the **RCC** register prior to writing the **RCC2** register. If a subsequent write to the **RCC** register is required, include another register access after writing the **RCC** register and before writing the **RCC2** register.

Figure 5-5 shows the logic for the main clock tree. The peripheral blocks are driven by the system clock signal and can be individually enabled/disabled. When the PLL is enabled, the ADC clock signal is automatically divided down to 16 MHz from the PLL output for proper ADC operation. The PWM clock signal is a synchronous divide of the system clock to provide the PWM circuit with more range (set with PWMDIV in **RCC**).

**Note:** When the ADC module is in operation, the system clock must be at least 16 MHz. When the USB module is in operation, MOSC must be the clock source, either with or without using the PLL, and the system clock must be at least 30 MHz.

Figure 5-5. Main Clock Tree



- a. Control provided by RCC register bit/field.
- b. Control provided by RCC register bit/field or RCC2 register bit/field, if overridden with RCC2 register bit USERCC2.
- c. Control provided by RCC2 register bit/field.
- d. Also may be controlled by **DSLPCLKCFG** when in deep sleep mode.
- e. Control provided by **RCC** register SYSDIV field, **RCC2** register SYSDIV2 field if overridden with USERCC2 bit, or [SYSDIV2,SYSDIV2LSB] if both USERCC2 and DIV400 bits are set.

**Note:** The figure above shows all features available on all Stellaris® Firestorm-class microcontrollers. Not all peripherals may be available on this device.

#### Using the SYSDIV and SYSDIV2 Fields

In the RCC register, the SYSDIV field specifies which divisor is used to generate the system clock from either the PLL output or the oscillator source (depending on how the BYPASS bit in this register is configured). When using the PLL, the VCO frequency of 400 MHz is predivided by 2 before the divisor is applied. Table 5-5 shows how the SYSDIV encoding affects the system clock frequency, depending on whether the PLL is used (BYPASS=0) or another clock source is used (BYPASS=1). The divisor is equivalent to the SYSDIV encoding plus 1. For a list of possible clock sources, see Table 5-4 on page 200.

Table 5-5. Possible System Clock Frequencies Using the SYSDIV Field

SYSDIV	Divisor	Frequency (BYPASS=0)	Frequency (BYPASS=1)	StellarisWare <sup>®</sup> Parameter <sup>a</sup>
0x0	/1	reserved	Clock source frequency/1	SYSCTL_SYSDIV_1
0x1	/2	reserved	Clock source frequency/2	SYSCTL_SYSDIV_2
0x2	/3	66.67 MHz	Clock source frequency/3	SYSCTL_SYSDIV_3
0x3	/4	50 MHz	Clock source frequency/4	SYSCTL_SYSDIV_4
0x4	/5	40 MHz	Clock source frequency/5	SYSCTL_SYSDIV_5
0x5	/6	33.33 MHz	Clock source frequency/6	SYSCTL_SYSDIV_6
0x6	/7	28.57 MHz	Clock source frequency/7	SYSCTL_SYSDIV_7
0x7	/8	25 MHz	Clock source frequency/8	SYSCTL_SYSDIV_8
0x8	/9	22.22 MHz	Clock source frequency/9	SYSCTL_SYSDIV_9
0x9	/10	20 MHz	Clock source frequency/10	SYSCTL_SYSDIV_10
0xA	/11	18.18 MHz	Clock source frequency/11	SYSCTL_SYSDIV_11
0xB	/12	16.67 MHz	Clock source frequency/12	SYSCTL_SYSDIV_12
0xC	/13	15.38 MHz	Clock source frequency/13	SYSCTL_SYSDIV_13
0xD	/14	14.29 MHz	Clock source frequency/14	SYSCTL_SYSDIV_14
0xE	/15	13.33 MHz	Clock source frequency/15	SYSCTL_SYSDIV_15
0xF	/16	12.5 MHz (default)	Clock source frequency/16	SYSCTL_SYSDIV_16

a. This parameter is used in functions such as SysCtlClockSet() in the Stellaris Peripheral Driver Library.

The SYSDIV2 field in the **RCC2** register is 2 bits wider than the SYSDIV field in the **RCC** register so that additional larger divisors up to /64 are possible, allowing a lower system clock frequency for improved Deep Sleep power consumption. When using the PLL, the VCO frequency of 400 MHz is predivided by 2 before the divisor is applied. The divisor is equivalent to the SYSDIV2 encoding plus 1. Table 5-6 shows how the SYSDIV2 encoding affects the system clock frequency, depending on whether the PLL is used (BYPASS2=0) or another clock source is used (BYPASS2=1). For a list of possible clock sources, see Table 5-4 on page 200.

Table 5-6. Examples of Possible System Clock Frequencies Using the SYSDIV2 Field

SYSDIV2	Divisor	Frequency (BYPASS2=0)	Frequency (BYPASS2=1)	StellarisWare Parameter <sup>a</sup>
0x00	/1	reserved	Clock source frequency/1	SYSCTL_SYSDIV_1
0x01	/2	reserved	Clock source frequency/2	SYSCTL_SYSDIV_2
0x02	/3	66.67 MHz	Clock source frequency/3	SYSCTL_SYSDIV_3
0x03	/4	50 MHz	Clock source frequency/4	SYSCTL_SYSDIV_4
0x04	/5	40 MHz	Clock source frequency/5	SYSCTL_SYSDIV_5

Table 5-6. Examples of Possible System Clock Frequencies Using the SYSDIV2 Field (continued)

SYSDIV2	Divisor	Frequency (BYPASS2=0)	Frequency (BYPASS2=1)	StellarisWare Parameter <sup>a</sup>
0x09	/10	20 MHz	Clock source frequency/10	SYSCTL_SYSDIV_10
0x3F	/64	3.125 MHz	Clock source frequency/64	SYSCTL_SYSDIV_64

a. This parameter is used in functions such as SysCtlClockSet() in the Stellaris Peripheral Driver Library.

To allow for additional frequency choices when using the PLL, the DIV400 bit is provided along with the SYSDIV2LSB bit. When the DIV400 bit is set, bit 22 becomes the LSB for SYSDIV2. In this situation, the divisor is equivalent to the (SYSDIV2 encoding with SYSDIV2LSB appended) plus one. Table 5-7 shows the frequency choices when DIV400 is set. When the DIV400 bit is clear, SYSDIV2LSB is ignored, and the system clock frequency is determined as shown in Table 5-6 on page 202.

Table 5-7. Examples of Possible System Clock Frequencies with DIV400=1

SYSDIV2	SYSDIV2LSB	Divisor	Frequency (BYPASS2=0) <sup>a</sup>	StellarisWare Parameter <sup>b</sup>
0x00	reserved	/2	reserved	-
0x01	0	/3	reserved	-
0.001	1	/4	reserved	-
0x02 0 /5 8		80 MHz	SYSCTL_SYSDIV_2_5	
0.002	1	/6	66.67 MHz	SYSCTL_SYSDIV_3
0 /7	reserved	-		
0.000	1	/8	50 MHz	SYSCTL_SYSDIV_4
0x04	0	/9	44.44 MHz	SYSCTL_SYSDIV_4_5
0.04	1	/10	40 MHz	SYSCTL_SYSDIV_5
0x3F	0	/127	3.15 MHz	SYSCTL_SYSDIV_63_5
UASI	1	/128	3.125 MHz	SYSCTL_SYSDIV_64

a. Note that  ${\tt DIV400}$  and  ${\tt SYSDIV2LSB}$  are only valid when  ${\tt BYPASS2=0}$ .

## 5.2.5.3 Precision Internal Oscillator Operation (PIOSC)

The microcontroller powers up with the PIOSC running. If another clock source is desired, the PIOSC must remain enabled as it is used for internal functions. The PIOSC can only be disabled during Deep-Sleep mode. It can be powered down by setting the IOSCDIS bit in the **RCC** register.

The PIOSC generates a 16-MHz clock with a  $\pm 1\%$  accuracy at room temperatures. Across the extended temperature range, the accuracy is  $\pm 3\%$ . At the factory, the PIOSC is set to 16 MHz at room temperature, however, the frequency can be trimmed for other voltage or temperature conditions using software in one of two ways:

- Default calibration: clear the UTEN bit and set the UPDATE bit in the Precision Internal Oscillator Calibration (PIOSCCAL) register.
- User-defined calibration: The user can program the UT value to adjust the PIOSC frequency. As the UT value increases, the generated period increases. To commit a new UT value, first set the

b. This parameter is used in functions such as SysCtlClockSet() in the Stellaris Peripheral Driver Library.

UTEN bit, then program the UT field, and then set the UPDATE bit. The adjustment finishes within a few clock periods and is glitch free.

## 5.2.5.4 Crystal Configuration for the Main Oscillator (MOSC)

The main oscillator supports the use of a select number of crystals. If the main oscillator is used by the PLL as a reference clock, the supported range of crystals is 3.579545 to 16.384 MHz, otherwise, the range of supported crystals is 1 to 16.384 MHz.

The XTAL bit in the **RCC** register (see page 221) describes the available crystal choices and default programming values.

Software configures the **RCC** register XTAL field with the crystal number. If the PLL is used in the design, the XTAL field value is internally translated to the PLL settings.

#### 5.2.5.5 Main PLL Frequency Configuration

The main PLL is disabled by default during power-on reset and is enabled later by software if required. Software specifies the output divisor to set the system clock frequency and enables the main PLL to drive the output. The PLL operates at 400 MHz, but is divided by two prior to the application of the output divisor, unless the DIV400 bit in the **RCC2** register is set.

To configure the PIOSC to be the clock source for the main PLL, program the OSCRC2 field in the Run-Mode Clock Configuration 2 (RCC2) register to be 0x1.

If the main oscillator provides the clock reference to the main PLL, the translation provided by hardware and used to program the PLL is available for software in the **XTAL** to **PLL Translation** (**PLLCFG**) register (see page 226). The internal translation provides a translation within  $\pm$  1% of the targeted PLL VCO frequency. Table 26-8 on page 1323 shows the actual PLL frequency and error for a given crystal choice.

The Crystal Value field (XTAL) in the **Run-Mode Clock Configuration (RCC)** register (see page 221) describes the available crystal choices and default programming of the **PLLCFG** register. Any time the XTAL field changes, the new settings are translated and the internal PLL settings are updated.

## 5.2.5.6 USB PLL Frequency Configuration

The USB PLL is disabled by default during power-on reset and is enabled later by software. The USB PLL must be enabled and running for proper USB function. The main oscillator is the only clock reference for the USB PLL. The USB PLL is enabled by clearing the USBPWRDN bit of the RCC2 register. The XTAL bit field (Crystal Value) of the RCC register describes the available crystal choices. The main oscillator must be connected to one of the following crystal values in order to correctly generate the USB clock: 4, 5, 6, 8, 10, 12, or 16 MHz. Only these crystals provide the necessary USB PLL VCO frequency to conform with the USB timing specifications.

#### 5.2.5.7 PLL Modes

Both PLLs have two modes of operation: Normal and Power-Down

- Normal: The PLL multiplies the input clock reference and drives the output.
- Power-Down: Most of the PLL internal circuitry is disabled and the PLL does not drive the output.

The modes are programmed using the RCC/RCC2 register fields (see page 221 and page 229).

## 5.2.5.8 PLL Operation

If a PLL configuration is changed, the PLL output frequency is unstable until it reconverges (relocks) to the new setting. The time between the configuration change and relock is T<sub>READY</sub> (see Table 26-7 on page 1322). During the relock time, the affected PLL is not usable as a clock reference.

Either PLL is changed by one of the following:

- Change to the XTAL value in the **RCC** register—writes of the same value do not cause a relock.
- Change in the PLL from Power-Down to Normal mode.

A counter clocked by the system clock is used to measure the  $T_{READY}$  requirement. If the system clock is the main oscillator and it is running off an 8.192 MHz or slower external oscillator clock, the down counter is set to 0x1200 (that is, ~600  $\mu$ s at an 8.192 MHz). If the system clock is running off the PIOSC or an external oscillator clock that is faster than 8.192 MHz, the down counter is set to 0x2400. Hardware is provided to keep the PLL from being used as a system clock until the  $T_{READY}$  condition is met after one of the two changes above. It is the user's responsibility to have a stable clock source (like the main oscillator) before the **RCC/RCC2** register is switched to use the PLL.

If the main PLL is enabled and the system clock is switched to use the PLL in one step, the system control hardware continues to clock the microcontroller from the oscillator selected by the RCC/RCC2 register until the main PLL is stable (T<sub>READY</sub> time met), after which it changes to the PLL. Software can use many methods to ensure that the system is clocked from the main PLL, including periodically polling the PLLLRIS bit in the Raw Interrupt Status (RIS) register, and enabling the PLL Lock interrupt.

The USB PLL is not protected during the lock time ( $T_{READY}$ ), and software should ensure that the USB PLL has locked before using the interface. Software can use many methods to ensure the  $T_{READY}$  period has passed, including periodically polling the USBPLLLRIS bit in the **Raw Interrupt Status (RIS)** register, and enabling the USB PLL Lock interrupt.

#### 5.2.5.9 Main Oscillator Verification Circuit

The clock control includes circuitry to ensure that the main oscillator is running at the appropriate frequency. The circuit monitors the main oscillator frequency and signals if the frequency is outside of the allowable band of attached crystals.

The detection circuit is enabled using the CVAL bit in the **Main Oscillator Control (MOSCCTL)** register. If this circuit is enabled and detects an error, the following sequence is performed by the hardware:

- 1. The MOSCFAIL bit in the Reset Cause (RESC) register is set.
- 2. If the internal oscillator (PIOSC) is disabled, it is enabled.
- 3. The system clock is switched from the main oscillator to the PIOSC.
- **4.** An internal power-on reset is initiated that lasts for 32 PIOSC periods.
- 5. Reset is de-asserted and the processor is directed to the NMI handler during the reset sequence.

## 5.2.6 System Control

For power-savings purposes, the **RCGCn**, **SCGCn**, and **DCGCn** registers control the clock gating logic for each peripheral or block in the system while the microcontroller is in Run, Sleep, and Deep-Sleep mode, respectively. These registers are located in the System Control register map

starting at offsets 0x600, 0x700, and 0x800, respectively. There must be a delay of 3 system clocks after a peripheral module clock is enabled in the **RCGC** register before any module registers are accessed.

There are three levels of operation for the microcontroller defined as:

- Run mode
- Sleep mode
- Deep-Sleep mode

The following sections describe the different modes in detail.

Caution – If the Cortex-M3 Debug Access Port (DAP) has been enabled, and the device wakes from a low power sleep or deep-sleep mode, the core may start executing code before all clocks to peripherals have been restored to their Run mode configuration. The DAP is usually enabled by software tools accessing the JTAG or SWD interface when debugging or flash programming. If this condition occurs, a Hard Fault is triggered when software accesses a peripheral with an invalid clock.

A software delay loop can be used at the beginning of the interrupt routine that is used to wake up a system from a WFI (Wait For Interrupt) instruction. This stalls the execution of any code that accesses a peripheral register that might cause a fault. This loop can be removed for production software as the DAP is most likely not enabled during normal execution.

Because the DAP is disabled by default (power on reset), the user can also power cycle the device. The DAP is not enabled unless it is enabled through the JTAG or SWD interface.

#### 5.2.6.1 Run Mode

In Run mode, the microcontroller actively executes code. Run mode provides normal operation of the processor and all of the peripherals that are currently enabled by the **RCGCn** registers. The system clock can be any of the available clock sources including the PLL.

## 5.2.6.2 Sleep Mode

In Sleep mode, the clock frequency of the active peripherals is unchanged, but the processor and the memory subsystem are not clocked and therefore no longer execute code. Sleep mode is entered by the Cortex-M3 core executing a WFI (Wait for Interrupt) instruction. Any properly configured interrupt event in the system brings the processor back into Run mode. See "Power Management" on page 109 for more details.

Peripherals are clocked that are enabled in the **SCGCn** registers when auto-clock gating is enabled (see the **RCC** register) or the **RCGCn** registers when the auto-clock gating is disabled. The system clock has the same source and frequency as that during Run mode.

#### 5.2.6.3 Deep-Sleep Mode

In Deep-Sleep mode, the clock frequency of the active peripherals may change (depending on the Run mode clock configuration) in addition to the processor clock being stopped. An interrupt returns the microcontroller to Run mode from one of the sleep modes; the sleep modes are entered on request from the code. Deep-Sleep mode is entered by first setting the SLEEPDEEP bit in the **System Control (SYSCTRL)** register (see page 151) and then executing a WFI instruction. Any properly configured interrupt event in the system brings the processor back into Run mode. See "Power Management" on page 109 for more details.

The Cortex-M3 processor core and the memory subsystem are not clocked in Deep-Sleep mode. Peripherals are clocked that are enabled in the **DCGCn** registers when auto-clock gating is enabled (see the **RCC** register) or the **RCGCn** registers when auto-clock gating is disabled. The system clock source is specified in the **DSLPCLKCFG** register. When the **DSLPCLKCFG** register is used, the internal oscillator source is powered up, if necessary, and other clocks are powered down. If the PLL is running at the time of the WFI instruction, hardware powers the PLL down and overrides the SYSDIV field of the active **RCC/RCC2** register, to be determined by the DSDIVORIDE setting in the **DSLPCLKCFG** register, up to /16 or /64 respectively. When the Deep-Sleep exit event occurs, hardware brings the system clock back to the source and frequency it had at the onset of Deep-Sleep mode before enabling the clocks that had been stopped during the Deep-Sleep duration. If the PIOSC is used as the PLL reference clock source, it may continue to provide the clock during Deep-Sleep. See page 233.

## 5.3 Initialization and Configuration

The PLL is configured using direct register writes to the RCC/RCC2 register. If the RCC2 register is being used, the USERCC2 bit must be set and the appropriate RCC2 bit/field is used. The steps required to successfully change the PLL-based system clock are:

- 1. Bypass the PLL and system clock divider by setting the BYPASS bit and clearing the USESYS bit in the RCC register, thereby configuring the microcontroller to run off a "raw" clock source and allowing for the new PLL configuration to be validated before switching the system clock to the PLL.
- 2. Select the crystal value (XTAL) and oscillator source (OSCSRC), and clear the PWRDN bit in RCC/RCC2. Setting the XTAL field automatically pulls valid PLL configuration data for the appropriate crystal, and clearing the PWRDN bit powers and enables the PLL and its output.
- 3. Select the desired system divider (SYSDIV) in RCC/RCC2 and set the USESYS bit in RCC. The SYSDIV field determines the system frequency for the microcontroller.
- 4. Wait for the PLL to lock by polling the PLLLRIS bit in the Raw Interrupt Status (RIS) register.
- 5. Enable use of the PLL by clearing the BYPASS bit in RCC/RCC2.

## 5.4 Register Map

Table 5-8 on page 207 lists the System Control registers, grouped by function. The offset listed is a hexadecimal increment to the register's address, relative to the System Control base address of 0x400F.E000.

**Note:** Spaces in the System Control register space that are not used are reserved for future or internal use. Software should not modify any reserved memory address.

Additional Flash and ROM registers defined in the System Control register space are described in the "Internal Memory" on page 300.

Table 5-8. System Control Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	DID0	RO	-	Device Identification 0	210
0x004	DID1	RO	-	Device Identification 1	238

Table 5-8. System Control Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x008	DC0	RO	0x017F.00FF	Device Capabilities 0	240
0x010	DC1	RO	-	Device Capabilities 1	241
0x014	DC2	RO	0x570F.5337	Device Capabilities 2	244
0x018	DC3	RO	0xBFFF.FFFF	Device Capabilities 3	246
0x01C	DC4	RO	0x5104.F1FF	Device Capabilities 4	249
0x020	DC5	RO	0x0F30.00FF	Device Capabilities 5	251
0x024	DC6	RO	0x0000.0013	Device Capabilities 6	253
0x028	DC7	RO	0xFFFF.FFFF	Device Capabilities 7	254
0x02C	DC8	RO	0xFFFF.FFFF	Device Capabilities 8 ADC Channels	258
0x030	PBORCTL	R/W	0x0000.0002	Brown-Out Reset Control	212
0x040	SRCR0	R/W	0x00000000	Software Reset Control 0	293
0x044	SRCR1	R/W	0x00000000	Software Reset Control 1	295
0x048	SRCR2	R/W	0x00000000	Software Reset Control 2	298
0x050	RIS	RO	0x0000.0000	Raw Interrupt Status	213
0x054	IMC	R/W	0x0000.0000	Interrupt Mask Control	215
0x058	MISC	R/W1C	0x0000.0000	Masked Interrupt Status and Clear	217
0x05C	RESC	R/W	-	Reset Cause	219
0x060	RCC	R/W	0x078E.3AD1	Run-Mode Clock Configuration	221
0x064	PLLCFG	RO	-	XTAL to PLL Translation	226
0x06C	GPIOHBCTL	R/W	0x0000.0000	GPIO High-Performance Bus Control	227
0x070	RCC2	R/W	0x07C0.6810	Run-Mode Clock Configuration 2	229
0x07C	MOSCCTL	R/W	0x0000.0000	Main Oscillator Control	232
0x100	RCGC0	R/W	0x00000040	Run Mode Clock Gating Control Register 0	264
0x104	RCGC1	R/W	0x00000000	Run Mode Clock Gating Control Register 1	272
0x108	RCGC2	R/W	0x00000000	Run Mode Clock Gating Control Register 2	284
0x110	SCGC0	R/W	0x00000040	Sleep Mode Clock Gating Control Register 0	267
0x114	SCGC1	R/W	0x00000000	Sleep Mode Clock Gating Control Register 1	276
0x118	SCGC2	R/W	0x00000000	Sleep Mode Clock Gating Control Register 2	287
0x120	DCGC0	R/W	0x00000040	Deep Sleep Mode Clock Gating Control Register 0	270
0x124	DCGC1	R/W	0x00000000	Deep-Sleep Mode Clock Gating Control Register 1	280
0x128	DCGC2	R/W	0x00000000	Deep Sleep Mode Clock Gating Control Register 2	290
0x144	DSLPCLKCFG	R/W	0x0780.0000	Deep Sleep Clock Configuration	233

Table 5-8. System Control Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x150	PIOSCCAL	R/W	0x0000.0000	Precision Internal Oscillator Calibration	235
0x170	I2SMCLKCFG	R/W	0x0000.0000	I2S MCLK Configuration	236
0x190	DC9	RO	0x00FF.00FF	Device Capabilities 9 ADC Digital Comparators	261
0x1A0	NVMSTAT	RO	0x0000.0011	Non-Volatile Memory Information	263

# 5.5 Register Descriptions

All addresses given are relative to the System Control base address of 0x400F.E000.

## Register 1: Device Identification 0 (DID0), offset 0x000

This register identifies the version of the microcontroller. Each microcontroller is uniquely identified by the combined values of the CLASS field in the **DID0** register and the PARTNO field in the **DID1** register.

Device Identification 0 (DID0)


Name

Type

Reset

Base 0x400F.E000 Offset 0x000 Type RO, reset -

Bit/Field



Description

31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30:28	VER	RO	0x1	DID0 Version This field defines the <b>DID0</b> register format version. The version number is numeric. The value of the VER field is encoded as follows (all other encodings are reserved):  Value Description 0x1 Second version of the <b>DID0</b> register format.
27:24	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23:16	CLASS	RO	0x06	Device Class

The CLASS field value identifies the internal design from which all mask sets are generated for all microcontrollers in a particular product line. The CLASS field value is changed for new product lines, for changes in fab process (for example, a remap or shrink), or any case where the MAJOR or MINOR fields require differentiation from prior microcontrollers. The value of the CLASS field is encoded as follows (all other encodings are reserved):

Value Description

0x06 Stellaris® Firestorm-class microcontrollers

Bit/Field	Name	Туре	Reset	Description
15:8	MAJOR	RO	-	Major Revision  This field specifies the major revision number of the microcontroller.  The major revision reflects changes to base layers of the design. The major revision number is indicated in the part number as a letter (A for first revision, B for second, and so on). This field is encoded as follows:
				Value Description
				0x0 Revision A (initial device)
				0x1 Revision B (first base layer revision)
				0x2 Revision C (second base layer revision)
				and so on.
7:0	MINOR	RO	-	Minor Revision
				This field specifies the minor revision number of the microcontroller. The minor revision reflects changes to the metal layers of the design. The MINOR field value is reset when the MAJOR field is changed. This field is numeric and is encoded as follows:
				Value Description
				0x0 Initial device, or a major revision update.
				0x1 First metal layer change.
				0x2 Second metal layer change.
				and so on.


## Register 2: Brown-Out Reset Control (PBORCTL), offset 0x030

This register is responsible for controlling reset conditions after initial power-on reset.

## Brown-Out Reset Control (PBORCTL)

Base 0x400F.E000

Offset 0x030 Type R/W, reset 0x0000.0002



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	BORIOR	R/W	1	BOR Interrupt or Reset
				Value Description
				O A Brown Out Event causes an interrupt to be generated to the interrupt controller.
				1 A Brown Out Event causes a reset of the microcontroller.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 3: Raw Interrupt Status (RIS), offset 0x050

This register indicates the status for system control raw interrupts. An interrupt is sent to the interrupt controller if the corresponding bit in the Interrupt Mask Control (IMC) register is set. Writing a 1 to the corresponding bit in the Masked Interrupt Status and Clear (MISC) register clears an interrupt status bit.

Raw Interrupt Status (RIS)

Base 0x400F.E000


6

**PLLLRIS** 

RO

0

Offset 0x050 Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:9	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	MOSCPUPRIS	RO	0	MOSC Power Up Raw Interrupt Status
				Value Description
				Sufficient time has passed for the MOSC to reach the expected frequency. The value for this power-up time is indicated by T <sub>MOSC_START</sub> .
				Sufficient time has not passed for the MOSC to reach the expected frequency.
				This bit is cleared by writing a 1 to the MOSCPUPMIS bit in the MISC register.
7	USBPLLLRIS	RO	0	USB PLL Lock Raw Interrupt Status
				Value Description
				The USB PLL timer has reached T <sub>READY</sub> indicating that sufficient time has passed for the USB PLL to lock.
				0 The USB PLL timer has not reached T <sub>READY</sub> .
				This bit is cleared by writing a 1 to the <code>USBPLLLMIS</code> bit in the MISC register.

#### Value Description

PLL Lock Raw Interrupt Status

- The PLL timer has reached  $T_{\mbox{\scriptsize READY}}$  indicating that sufficient time has passed for the PLL to lock.
- The PLL timer has not reached T<sub>READY</sub>.

This bit is cleared by writing a 1 to the PLLLMIS bit in the MISC register.

Bit/Field	Name	Type	Reset	Description
5:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	BORRIS	RO	0	Brown-Out Reset Raw Interrupt Status
				Value Description
				1 A brown-out condition is currently active.
				0 A brown-out condition is not currently active.
				Note the BORIOR bit in the <b>PBORCTL</b> register must be cleared to cause an interrupt due to a Brown Out Event.
				This bit is cleared by writing a 1 to the BORMIS bit in the MISC register.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.


## Register 4: Interrupt Mask Control (IMC), offset 0x054

This register contains the mask bits for system control raw interrupts. A raw interrupt, indicated by a bit being set in the **Raw Interrupt Status (RIS)** register, is sent to the interrupt controller if the corresponding bit in this register is set.

Interrupt Mask Control (IMC)

Base 0x400F.E000

Offset 0x054 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:9	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	MOSCPUPIM	R/W	0	MOSC Power Up Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the MOSCPUPRIS bit in the <b>RIS</b> register is set.
				O The MOSCPUPRIS interrupt is suppressed and not sent to the interrupt controller.
7	USBPLLLIM	R/W	0	USB PLL Lock Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the USBPLLLRIS bit in the <b>RIS</b> register is set.
				O The USBPLLLRIS interrupt is suppressed and not sent to the interrupt controller.
6	PLLLIM	R/W	0	PLL Lock Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the PLLLRIS bit in the <b>RIS</b> register is set.
				O The PLLLRIS interrupt is suppressed and not sent to the interrupt controller.
5:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
1	BORIM	R/W	0	Brown-Out Reset Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the BORRIS bit in the <b>RIS</b> register is set.
				O The BORRIS interrupt is suppressed and not sent to the interrupt controller.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.


# Register 5: Masked Interrupt Status and Clear (MISC), offset 0x058

On a read, this register gives the current masked status value of the corresponding interrupt in the **Raw Interrupt Status (RIS)** register. All of the bits are R/W1C, thus writing a 1 to a bit clears the corresponding raw interrupt bit in the **RIS** register (see page 213).

Masked Interrupt Status and Clear (MISC)

Base 0x400F.E000 Offset 0x058

Type R/W1C, reset 0x0000.0000



Bit/Field	Name	туре	Reset	Description
31:9	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	MOSCPUPMIS	R/W1C	0	MOSC Power Up Masked Interrupt Status

#### Value Description

1 When read, a 1 indicates that an unmasked interrupt was signaled because sufficient time has passed for the MOSC PLL to lock

Writing a 1 to this bit clears it and also the  ${\tt MOSCPUPRIS}$  bit in the RIS register.

When read, a 0 indicates that sufficient time has not passed for the MOSC PLL to lock.

A write of 0 has no effect on the state of this bit.

#### 7 USBPLLLMIS R/W1C 0 USB PLL Lock Masked Interrupt Status

#### Value Description

When read, a 1 indicates that an unmasked interrupt was signaled because sufficient time has passed for the USB PLL to lock.

Writing a 1 to this bit clears it and also the  ${\tt USBPLLLRIS}$  bit in the  ${\textbf {RIS}}$  register.

When read, a 0 indicates that sufficient time has not passed for the USB PLL to lock.

A write of 0 has no effect on the state of this bit.

Bit/Field	Name	Туре	Reset	Description
6	PLLLMIS	R/W1C	0	PLL Lock Masked Interrupt Status
				Value Description
				When read, a 1 indicates that an unmasked interrupt was signaled because sufficient time has passed for the PLL to lock.
				Writing a 1 to this bit clears it and also the PLLLRIS bit in the <b>RIS</b> register.
				When read, a 0 indicates that sufficient time has not passed for the PLL to lock.
				A write of 0 has no effect on the state of this bit.
5:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	BORMIS	R/W1C	0	BOR Masked Interrupt Status
				Value Description
				When read, a 1 indicates that an unmasked interrupt was signaled because of a brown-out condition.
				Writing a 1 to this bit clears it and also the BORRIS bit in the RIS register.
				When read, a 0 indicates that a brown-out condition has not occurred.
				A write of 0 has no effect on the state of this bit.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 6: Reset Cause (RESC), offset 0x05C

This register is set with the reset cause after reset. The bits in this register are sticky and maintain their state across multiple reset sequences, except when an power-on reset is the cause, in which case, all bits other than POR in the **RESC** register are cleared.


Reset Cause (RESC)

WDT1

5

R/W

Base 0x400F.E000 Offset 0x05C Type R/W, reset -



Bit/Field	Name	Type	Reset	Description
31:17	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
16	MOSCFAIL	R/W	-	MOSC Failure Reset
				Value Description
				When read, this bit indicates that the MOSC circuit was enabled for clock validation and failed, generating a reset event.
				When read, this bit indicates that a MOSC failure has not generated a reset since the previous power-on reset.
				Writing a 0 to this bit clears it.
15:6	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Value Description

Watchdog Timer 1 Reset

- 1 When read, this bit indicates that Watchdog Timer 1 timed out and generated a reset.
- When read, this bit indicates that Watchdog Timer 1 has not generated a reset since the previous power-on reset.
   Writing a 0 to this bit clears it.

Bit/Field	Name	Туре	Reset	Description
4	SW	R/W	-	Software Reset
				Value Description
				When read, this bit indicates that a software reset has caused a reset event.
				When read, this bit indicates that a software reset has not generated a reset since the previous power-on reset.
				Writing a 0 to this bit clears it.
3	WDT0	R/W	-	Watchdog Timer 0 Reset
				Value Description
				When read, this bit indicates that Watchdog Timer 0 timed out and generated a reset.
				When read, this bit indicates that Watchdog Timer 0 has not generated a reset since the previous power-on reset.
				Writing a 0 to this bit clears it.
2	BOR	R/W	-	Brown-Out Reset
				Value Description
				When read, this bit indicates that a brown-out reset has caused a reset event.
				When read, this bit indicates that a brown-out reset has not generated a reset since the previous power-on reset.
				Writing a 0 to this bit clears it.
1	POR	R/W	-	Power-On Reset
				Value Description
				When read, this bit indicates that a power-on reset has caused a reset event.
				When read, this bit indicates that a power-on reset has not generated a reset.
				Writing a 0 to this bit clears it.
0	EXT	R/W	-	External Reset
				Value Description
				1 When read, this bit indicates that an external reset (RST assertion) has caused a reset event.
				When read, this bit indicates that an external reset (RST assertion) has not caused a reset event since the previous power-on reset.
				Writing a 0 to this bit clears it.

### Register 7: Run-Mode Clock Configuration (RCC), offset 0x060

The bits in this register configure the system clock and oscillators.

**Important:** Write the **RCC** register prior to writing the **RCC2** register. If a subsequent write to the **RCC** register is required, include another register access after writing the **RCC** register and before writing the **RCC2** register.

Run-Mode Clock Configuration (RCC)

Base 0x400F.E000 Offset 0x060

Type R/W, reset 0x078E.3AD1

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	ı	rese	erved	1	ACG		SYS	SDIV		USESYSDIV	reserved	USEPWMDIV		PWMDIV	ı	reserved
Type	RO	RO	RO	RO	R/W	R/W	R/W	R/W	R/W	R/W	RO	R/W	R/W	R/W	R/W	RO
Reset	0	0	0	0	0	1	1	1	1	0	0	0	1	1	1	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	rese	rved	PWRDN	reserved	BYPASS	I		XTAL		Ī	osc	SRC	rese	erved	IOSCDIS	MOSCDIS
Type	RO	RO	R/W	RO	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO	RO	R/W	R/W
Reset	0	0	1	1	1	0	1	0	1	1	0	1	0	0	0	1

Bit/Field	Name	Type	Reset	Description
31:28	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
27	ACG	R/W	0	Auto Clock Gating

This bit specifies whether the system uses the Sleep-Mode Clock Gating Control (SCGCn) registers and Deep-Sleep-Mode Clock Gating Control (DCGCn) registers if the microcontroller enters a Sleep

or Deep-Sleep mode (respectively).

Value Description

- The SCGCn or DCGCn registers are used to control the clocks distributed to the peripherals when the microcontroller is in a sleep mode. The SCGCn and DCGCn registers allow unused peripherals to consume less power when the microcontroller is in a sleep mode.
- The Run-Mode Clock Gating Control (RCGCn) registers are used when the microcontroller enters a sleep mode.

The **RCGCn** registers are always used to control the clocks in Run mode.

26:23 SYSDIV R/W 0xF

System Clock Divisor

Specifies which divisor is used to generate the system clock from either the PLL output or the oscillator source (depending on how the BYPASS bit in this register is configured). See Table 5-5 on page 202 for bit encodings.

If the  ${\tt SYSDIV}$  value is less than  ${\tt MINSYSDIV}$  (see page 241), and the PLL is being used, then the  ${\tt MINSYSDIV}$  value is used as the divisor.

If the PLL is not being used, the  ${\tt SYSDIV}$  value can be less than  ${\tt MINSYSDIV}.$ 

Bit/Field	Name	Туре	Reset	Description
22	USESYSDIV	R/W	0	Enable System Clock Divider
				Value Description
				1 The system clock divider is the source for the system clock. The system clock divider is forced to be used when the PLL is selected as the source.
				If the USERCC2 bit in the RCC2 register is set, then the SYSDIV2 field in the RCC2 register is used as the system clock divider rather than the SYSDIV field in this register.
				0 The system clock is used undivided.
21	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
20	USEPWMDIV	R/W	0	Enable PWM Clock Divisor
				Value Description
				1 The PWM clock divider is the source for the PWM clock.
				0 The system clock is the source for the PWM clock.
				Note that when the PWM divisor is used, it is applied to the clock for both PWM modules.
19:17	PWMDIV	R/W	0x7	PWM Unit Clock Divisor
				This field specifies the binary divisor used to predivide the system clock down for use as the timing reference for the PWM module. The rising edge of this clock is synchronous with the system clock.
				Value Divisor
				0x0 /2
				0x1 /4
				0x2 /8
				0x3 /16
				0x4 /32
				0x5 /64
				0x6 /64
				0x7 /64 (default)
16:14	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	PWRDN	R/W	1	PLL Power Down
				Value Description
				The PLL is powered down. Care must be taken to ensure that another clock source is functioning and that the BYPASS bit is set before setting this bit.
				0 The PLL is operating normally.

Bit/Field	Name	Туре	Reset	Description
12	reserved	RO	1	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	BYPASS	R/W	1	PLL Bypass
				Value Description
				The system clock is derived from the OSC source and divided by the divisor specified by SYSDIV.
				0 The system clock is the PLL output clock divided by the divisor

See Table 5-5 on page 202 for programming guidelines.

specified by SYSDIV.

**Note:** The ADC must be clocked from the PLL or directly from a 16-MHz clock source to operate properly.

Bit/Field	Name	Type	Reset	Description
10:6	XTAL	R/W	0x0B	Crvstal Value

This field specifies the crystal value attached to the main oscillator. The encoding for this field is provided below. Depending on the crystal used, the PLL frequency may not be exactly 400 MHz, see Table 26-8 on page 1323 for more information.

Frequencies that may be used with the USB interface are indicated in the table. To function within the clocking requirements of the USB specification, a crystal of 4, 5, 6, 8, 10, 12, or 16 MHz must be used.

Value	Crystal Frequency (MHz) Not Using the PLL	Crystal Frequency (MHz) Using the PLL				
0x00	1.000 MHz	reserved				
0x01	1.8432 MHz	reserved				
0x02	2.000 MHz	reserved				
0x03	2.4576 MHz	reserved				
0x04	3.5795	45 MHz				
0x05	3.686	4 MHz				
0x06	4 MHz	(USB)				
0x07	4.096	6 MHz				
80x0	4.9152 MHz					
0x09	5 MHz (USB)					
0x0A	5.12 MHz					
0x0B	6 MHz (rese	t value)(USB)				
0x0C	6.144	ł MHz				
0x0D	7.372	8 MHz				
0x0E	8 MHz	(USB)				
0x0F	8.192	2 MHz				
0x10	10.0 MF	łz (USB)				
0x11	12.0 MF	łz (USB)				
0x12	12.28	8 MHz				
0x13	13.56	6 MHz				
0x14	14.318	18 MHz				
0x15	16.0 MH	łz (USB)				
0x16	16.38	4 MHz				

Bit/Field	Name	Туре	Reset	Description
5:4	OSCSRC	R/W	0x1	Oscillator Source Selects the input source for the OSC. The values are:
				Value Input Source  0x0 MOSC     Main oscillator  0x1 PIOSC     Precision internal oscillator     (default)  0x2 PIOSC/4     Precision internal oscillator / 4  0x3 30 kHz     30-kHz internal oscillator
3:2	reserved	RO	0x0	For additional oscillator sources, see the RCC2 register.  Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be
1	IOSCDIS	R/W	0	preserved across a read-modify-write operation.  Precision Internal Oscillator Disable  Value Description  1 The precision internal oscillator (PIOSC) is disabled.  0 The precision internal oscillator is enabled.
0	MOSCDIS	R/W	1	Main Oscillator Disable  Value Description  1 The main oscillator is disabled (default).  0 The main oscillator is enabled.

# Register 8: XTAL to PLL Translation (PLLCFG), offset 0x064


This register provides a means of translating external crystal frequencies into the appropriate PLL settings. This register is initialized during the reset sequence and updated anytime that the XTAL field changes in the **Run-Mode Clock Configuration (RCC)** register (see page 221).

The PLL frequency is calculated using the PLLCFG field values, as follows:

PLLFreq = OSCFreq \* F / (R + 1)

#### XTAL to PLL Translation (PLLCFG)

Base 0x400F.E000 Offset 0x064 Type RO, reset -



Bit/Field	Name	Type	Reset	Description
31:14	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13:5	F	RO	-	PLL F Value This field specifies the value supplied to the PLL's F input.
4:0	R	RO	-	PLL R Value This field specifies the value supplied to the PLL's R input.


### Register 9: GPIO High-Performance Bus Control (GPIOHBCTL), offset 0x06C

This register controls which internal bus is used to access each GPIO port. When a bit is clear, the corresponding GPIO port is accessed across the legacy Advanced Peripheral Bus (APB) bus and through the APB memory aperture. When a bit is set, the corresponding port is accessed across the Advanced High-Performance Bus (AHB) bus and through the AHB memory aperture. Each GPIO port can be individually configured to use AHB or APB, but may be accessed only through one aperture. The AHB bus provides better back-to-back access performance than the APB bus. The address aperture in the memory map changes for the ports that are enabled for AHB access (see Table 8-7 on page 418).

GPIO High-Performance Bus Control (GPIOHBCTL)

Base 0x400F.E000 Offset 0x06C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:9	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	PORTJ	R/W	0	Port J Advanced High-Performance Bus
				This bit defines the memory aperture for Port J.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.
7	PORTH	R/W	0	Port H Advanced High-Performance Bus
				This bit defines the memory aperture for Port H.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.
6	PORTG	R/W	0	Port G Advanced High-Performance Bus
				This bit defines the memory aperture for Port G.
				Value Description

1

0

Advanced High-Performance Bus (AHB)

Advanced Peripheral Bus (APB). This bus is the legacy bus.

Bit/Field	Name	Туре	Reset	Description
5	PORTF	R/W	0	Port F Advanced High-Performance Bus This bit defines the memory aperture for Port F.
				Value Description  1 Advanced High-Performance Bus (AHB)
				O Advanced Peripheral Bus (APB). This bus is the legacy bus.
4	PORTE	R/W	0	Port E Advanced High-Performance Bus This bit defines the memory aperture for Port E.
				Value Description
				Advanced High-Performance Bus (AHB)
				O Advanced Peripheral Bus (APB). This bus is the legacy bus.
3	PORTD	R/W	0	Port D Advanced High-Performance Bus
				This bit defines the memory aperture for Port D.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.
2	PORTC	R/W	0	Port C Advanced High-Performance Bus
				This bit defines the memory aperture for Port C.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.
1	PORTB	R/W	0	Port B Advanced High-Performance Bus
				This bit defines the memory aperture for Port B.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.
0	PORTA	R/W	0	Port A Advanced High-Performance Bus
				This bit defines the memory aperture for Port A.
				Value Description
				1 Advanced High-Performance Bus (AHB)
				0 Advanced Peripheral Bus (APB). This bus is the legacy bus.

### Register 10: Run-Mode Clock Configuration 2 (RCC2), offset 0x070

This register overrides the RCC equivalent register fields, as shown in Table 5-9, when the USERCC2 bit is set, allowing the extended capabilities of the RCC2 register to be used while also providing a means to be backward-compatible to previous parts. Each RCC2 field that supersedes an RCC field is located at the same LSB bit position; however, some RCC2 fields are larger than the corresponding RCC field.

Table 5-9. RCC2 Fields that Override RCC Fields


RCC2 Field	Overrides RCC Field
SYSDIV2, bits[28:23]	SYSDIV, bits[26:23]
PWRDN2, bit[13]	PWRDN, bit[13]
BYPASS2, bit[11]	BYPASS, bit[11]
oscsrc2, bits[6:4]	OSCSRC, bits[5:4]

**Important:** Write the **RCC** register prior to writing the **RCC2** register. If a subsequent write to the **RCC** register is required, include another register access after writing the **RCC** register and before writing the **RCC2** register.

Run-Mode Clock Configuration 2 (RCC2)

Base 0x400F.E000 Offset 0x070

Type R/W, reset 0x07C0.6810



Bit/Field	Name	Туре	Reset	Description	
31	USERCC2	R/W	0	Use RCC2	
				Value Description  The RCC2 register fields override the RCC register fields.  The RCC register fields are used, and the fields in RCC2 are ignored.	
30	DIV400	R/W	0	Divide PLL as 400 MHz vs. 200 MHz This bit, along with the SYSDIV2LSB bit, allows additional frequency	

choices.

Value Description

- Append the SYSDIV2LSB bit to the SYSDIV2 field to create a 7 bit divisor using the 400 MHz PLL output, see Table 5-7 on page 203.
- 0 Use SYSDIV2 as is and apply to 200 MHz predivided PLL output. See Table 5-6 on page 202 for programming guidelines.

Bit/Field	Name	Туре	Reset	Description
29	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28:23	SYSDIV2	R/W	0x0F	System Clock Divisor 2  Specifies which divisor is used to generate the system clock from either the PLL output or the oscillator source (depending on how the BYPASS2 bit is configured). SYSDIV2 is used for the divisor when both the USESYSDIV bit in the RCC register and the USERCC2 bit in this register are set. See Table 5-6 on page 202 for programming guidelines.
22	SYSDIV2LSB	R/W	1	Additional LSB for SYSDIV2  When DIV400 is set, this bit becomes the LSB of SYSDIV2. If DIV400 is clear, this bit is not used. See Table 5-6 on page 202 for programming guidelines.  This bit can only be set or cleared when DIV400 is set.
21:15	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	USBPWRDN	R/W	1	Power-Down USB PLL  Value Description  1 The USB PLL is powered down.  0 The USB PLL operates normally.
13	PWRDN2	R/W	1	Power-Down PLL 2  Value Description  1 The PLL is powered down.  0 The PLL operates normally.
12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	BYPASS2	R/W	1	PLL Bypass 2  Value Description  1 The system clock is derived from the OSC source and divided by the divisor specified by SYSDIV2.  0 The system clock is the PLL output clock divided by the divisor specified by SYSDIV2.  See Table 5-6 on page 202 for programming guidelines.  Note: The ADC must be clocked from the PLL or directly from a 16-MHz clock source to operate properly.
10:7	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
6:4	OSCSRC2	R/W	0x1	Oscillator Source 2
				Selects the input source for the OSC. The values are:
				Value Description
				0x0 MOSC
				Main oscillator
				0x1 PIOSC
				Precision internal oscillator
				0x2 PIOSC/4
				Precision internal oscillator / 4
				0x3 30 kHz
				30-kHz internal oscillator
				0x4-0x7 Reserved
3:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.


# Register 11: Main Oscillator Control (MOSCCTL), offset 0x07C

This register provides the ability to enable the MOSC clock verification circuit. When enabled, this circuit monitors the frequency of the MOSC to verify that the oscillator is operating within specified limits. If the clock goes invalid after being enabled, the microcontroller issues a power-on reset and reboots to the NMI handler.

Main Oscillator Control (MOSCCTL)

Base 0x400F.E000

Offset 0x07C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	CVAL	R/W	0	Clock Validation for MOSC

Value Description

- 1 The MOSC monitor circuit is enabled.
- 0 The MOSC monitor circuit is disabled.

# Register 12: Deep Sleep Clock Configuration (DSLPCLKCFG), offset 0x144


This register provides configuration information for the hardware control of Deep Sleep Mode.

Deep Sleep Clock Configuration (DSLPCLKCFG)

Base 0x400F.E000 Offset 0x144

Bit/Field

Type R/W, reset 0x0780.0000



Bit/Field	Name	Type	Reset	Description
31:29	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

28:23 **DSDIVORIDE** R/W 0x0F Divider Field Override

If Deep-Sleep mode is enabled when the PLL is running, the PLL is disabled. This 6-bit field contains a system divider field that overrides the  ${\tt SYSDIV}$  field in the RCC register or the  ${\tt SYSDIV2}$  field in the RCC2 register during Deep Sleep. This divider is applied to the source selected by the **DSOSCSRC** field.

Value Description 0x0 /1 0x1 /2 0x2 /3 /4 0x30x3F /64

22:7 RO 0x000 reserved Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description		
6:4	DSOSCSRC	R/W	0x0	Clock Source Specifies the clock source during Deep-Sleep mode.		
				Value Description		
				0x0 MOSC		
				Use the main oscillator as the source.		
				Note: If the PIOSC is being used as the clock reference for the PLL, the PIOSC is the clock source instead of MOSC in Deep-Sleep mode.		
				0x1 PIOSC		
				Use the precision internal 16-MHz oscillator as the source.		
				0x2 Reserved		
				0x3 30 kHz		
				Use the 30-kHz internal oscillator as the source.		
				0x4-0x7 Reserved		
3:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should b preserved across a read-modify-write operation.		

### Register 13: Precision Internal Oscillator Calibration (PIOSCCAL), offset 0x150

This register provides the ability to update or recalibrate the precision internal oscillator.

Precision Internal Oscillator Calibration (PIOSCCAL)

Name

Type

Reset

Base 0x400F.E000 Offset 0x150

Bit/Field

Type R/W, reset 0x0000.0000



Description

		. 7   -		
31	UTEN	R/W	0	Use User Trim Value
				Value Description
				1 The trim value in bits[6:0] of this register are used for any update trim operation.
				The factory calibration value is used for an update trim operation.
30:9	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	UPDATE	R/W	0	Update Trim
				Value Description  1 Updates the PIOSC trim value with the UT bit. Used with UTEN.  0 No action.
				This bit is auto-cleared after the update.
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	UT	R/W	0x0	User Trim Value
				User trim value that can be loaded into the PIOSC.

Refer to "Main PLL Frequency Configuration" on page 204 for more

information on calibrating the PIOSC.


# Register 14: I<sup>2</sup>S MCLK Configuration (I2SMCLKCFG), offset 0x170

This register configures the receive and transmit fractional clock dividers for the for the I<sup>2</sup>S master transmit and receive clocks (I2S0TXMCLK and I2S0RXMCLK). Varying the integer and fractional inputs for the clocks allows greater accuracy in hitting the target I<sup>2</sup>S clock frequencies. Refer to "Clock Control" on page 839 for combinations of the TXI and TXF bits and the RXI and RXF bits that provide MCLK frequencies within acceptable error limits.

### I2S MCLK Configuration (I2SMCLKCFG)

Base 0x400F.E000 Offset 0x170

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31	RXEN	R/W	0	RX Clock Enable

#### Value Description

- 1 The I<sup>2</sup>S receive clock generator is enabled.
- 0 The I<sup>2</sup>S receive clock generator is disabled. If the RXSLV bit in the I2S Module Configuration (I2SCFG) register is set, then the I2SORXMCLK must be externally generated.

30	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
29:20	RXI	R/W	0x0	RX Clock Integer Input This field contains the integer input for the receive clock generator.
19:16	RXF	R/W	0x0	RX Clock Fractional Input This field contains the fractional input for the receive clock generator.
15	TXEN	R/W	0	TX Clock Enable

#### Value Description

- The I<sup>2</sup>S transmit clock generator is enabled.
- 0 The I<sup>2</sup>S transmit clock generator is disabled. If the  ${\tt TXSLV}$  bit in the I<sup>2</sup>S Module Configuration (I2SCFG) register is set, then the I2SOTXMCLK must be externally generated.

Bit/Field	Name	Туре	Reset	Description
14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13:4	TXI	R/W	0x00	TX Clock Integer Input  This field contains the integer input for the transmit clock generator.
3:0	TXF	R/W	0x0	TX Clock Fractional Input  This field contains the fractional input for the transmit clock generator.

# Register 15: Device Identification 1 (DID1), offset 0x004

This register identifies the device family, part number, temperature range, pin count, and package type. Each microcontroller is uniquely identified by the combined values of the CLASS field in the DID0 register and the PARTNO field in the DID1 register.

Device Identification 1 (DID1)


Base 0x400F.E000 Offset 0x004 Type RO, reset -

15:13

**PINCOUNT** 

RO

0x2



Bit/Field	Name	Туре	Reset	Description
31:28	VER	RO	0x1	DID1 Version  This field defines the <b>DID1</b> register format version. The version number is numeric. The value of the VER field is encoded as follows (all other encodings are reserved):
				Value Description
				0x1 Second version of the <b>DID1</b> register format.
27:24	FAM	RO	0x0	Family
				This field provides the family identification of the device within the Luminary Micro product portfolio. The value is encoded as follows (all other encodings are reserved):
				Value Description
				0x0 Stellaris family of microcontollers, that is, all devices with external part numbers starting with LM3S.
23:16	PARTNO	RO	0x9D	Part Number
				This field provides the part number of the device within the family. The value is encoded as follows (all other encodings are reserved):
				Value Description
				0x9D LM3S9D96

This field specifies the number of pins on the device package. The value is encoded as follows (all other encodings are reserved):

Value Description 0x2 100-pin package

Package Pin Count

Bit/Field	Name	Туре	Reset	Description
12:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:5	TEMP	RO	-	Temperature Range This field specifies the temperature rating of the device. The value is encoded as follows (all other encodings are reserved):  Value Description  0x0 Commercial temperature range (0°C to 70°C)  0x1 Industrial temperature range (-40°C to 85°C)  0x2 Extended temperature range (-40°C to 105°C)
4:3	PKG	RO	-	Package Type This field specifies the package type. The value is encoded as follows (all other encodings are reserved):  Value Description  0x0 SOIC package  0x1 LQFP package  0x2 BGA package
2	ROHS	RO	1	RoHS-Compliance This bit specifies whether the device is RoHS-compliant. A 1 indicates the part is RoHS-compliant.
1:0	QUAL	RO	-	Qualification Status  This field specifies the qualification status of the device. The value is encoded as follows (all other encodings are reserved):  Value Description  0x0 Engineering Sample (unqualified)  0x1 Pilot Production (unqualified)  0x2 Fully Qualified


# Register 16: Device Capabilities 0 (DC0), offset 0x008

This register is predefined by the part and can be used to verify features.

Device Capabilities 0 (DC0)

Base 0x400F.E000 Offset 0x008

Type RO, reset 0x017F.00FF



Bit/Field	Name	Type	Reset	Description
31:16	SRAMSZ	RO	0x017F	SRAM Size Indicates the size of the on-chip SRAM memory.  Value Description 0x017F 96 KB of SRAM
15:0	FLASHSZ	RO	0x00FF	Flash Size

Indicates the size of the on-chip flash memory.

Value Description

0x00FF 512 KB of Flash

# Register 17: Device Capabilities 1 (DC1), offset 0x010

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 1 (DC1)

Base 0x400F.E000 Offset 0x010 Type RO, reset -

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		reserved		WDT1	rese	rved	CAN1	CAN0		reserved		PWM	rese	rved	ADC1	ADC0
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	1	0	0	1	1	0	0	0	1	0	0	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		MINSY	SDIV		MAXAD	C1SPD	MAXAD	C0SPD	MPU	reserved	TEMPSNS	PLL	WDT0	SWO	SWD	JTAG
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	-	-	-	-	1	1	1	1	1	0	1	1	1	1	1	1

Bit/Field	Name	Туре	Reset	Description
31:29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	WDT1	RO	1	Watchdog Timer 1 Present When set, indicates that watchdog timer 1 is present.
27:26	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
25	CAN1	RO	1	CAN Module 1 Present When set, indicates that CAN unit 1 is present.
24	CAN0	RO	1	CAN Module 0 Present When set, indicates that CAN unit 0 is present.
23:21	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
20	PWM	RO	1	PWM Module Present When set, indicates that the PWM module is present.
19:18	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
17	ADC1	RO	1	ADC Module 1 Present When set, indicates that ADC module 1 is present.
16	ADC0	RO	1	ADC Module 0 Present When set, indicates that ADC module 0 is present

Bit/Field	Name	Туре	Reset	Description
15:12	MINSYSDIV	RO	-	System Clock Divider  Minimum 4-bit divider value for system clock. The reset value is hardware-dependent. See the RCC register for how to change the system clock divisor using the SYSDIV bit.
				Value Description  0x1 Specifies an 80-MHz CPU clock with a PLL divider of 2.5.  0x2 Specifies a 66.67-MHz CPU clock with a PLL divider of 3.  0x3 Specifies a 50-MHz CPU clock with a PLL divider of 4.  0x7 Specifies a 25-MHz clock with a PLL divider of 8.  0x9 Specifies a 20-MHz clock with a PLL divider of 10.
11:10	MAXADC1SPD	RO	0x3	Max ADC1 Speed This field indicates the maximum rate at which the ADC samples data.  Value Description  0x3 1M samples/second
9:8	MAXADC0SPD	RO	0x3	Max ADC0 Speed This field indicates the maximum rate at which the ADC samples data.  Value Description 0x3 1M samples/second
7	MPU	RO	1	MPU Present When set, indicates that the Cortex-M3 Memory Protection Unit (MPU) module is present. See the "Cortex-M3 Peripherals" chapter for details on the MPU.
6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	TEMPSNS	RO	1	Temp Sensor Present When set, indicates that the on-chip temperature sensor is present.
4	PLL	RO	1	PLL Present When set, indicates that the on-chip Phase Locked Loop (PLL) is present.
3	WDT0	RO	1	Watchdog Timer 0 Present When set, indicates that watchdog timer 0 is present.
2	SWO	RO	1	SWO Trace Port Present When set, indicates that the Serial Wire Output (SWO) trace port is present.
1	SWD	RO	1	SWD Present When set, indicates that the Serial Wire Debugger (SWD) is present.

Bit/Field	Name	Type	Reset	Description
0	JTAG	RO	1	JTAG Present
				When set, indicates that the JTAG debugger interface is present.

# Register 18: Device Capabilities 2 (DC2), offset 0x014

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 2 (DC2)

Base 0x400F.E000 Offset 0x014 Type RO, reset 0x570F.5337

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPI0	reserved	12S0	reserved	COMP2	COMP1	COMP0		rese	rved		TIMER3	TIMER2	TIMER1	TIMER0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	1	0	1	0	1	1	1	0	0	0	0	1	1	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved	I2C1	reserved	I2C0	rese	rved	QEI1	QEI0	rese	rved	SSI1	SSI0	reserved	UART2	UART1	UART0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	1	0	1	0	0	1	1	0	0	1	1	0	1	1	1
		RO 1		RO 1	RO 0		RO 1	RO 1		RO 0	RO 1	RO 1	RO 0	RO 1	RO 1	RO 1

Bit/Field	Name	Type	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPI0	RO	1	EPI Module 0 Present When set, indicates that EPI module 0 is present.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	12S0	RO	1	I2S Module 0 Present When set, indicates that I2S module 0 is present.
27	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
26	COMP2	RO	1	Analog Comparator 2 Present When set, indicates that analog comparator 2 is present.
25	COMP1	RO	1	Analog Comparator 1 Present When set, indicates that analog comparator 1 is present.
24	COMP0	RO	1	Analog Comparator 0 Present When set, indicates that analog comparator 0 is present.
23:20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	TIMER3	RO	1	Timer Module 3 Present When set, indicates that General-Purpose Timer module 3 is present.
18	TIMER2	RO	1	Timer Module 2 Present  When set, indicates that General-Purpose Timer module 2 is present.

Bit/Field	Name	Туре	Reset	Description
17	TIMER1	RO	1	Timer Module 1 Present When set, indicates that General-Purpose Timer module 1 is present.
16	TIMER0	RO	1	Timer Module 0 Present When set, indicates that General-Purpose Timer module 0 is present.
15	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	I2C1	RO	1	I2C Module 1 Present When set, indicates that I2C module 1 is present.
13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	I2C0	RO	1	I2C Module 0 Present When set, indicates that I2C module 0 is present.
11:10	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	QEI1	RO	1	QEI Module 1 Present When set, indicates that QEI module 1 is present.
8	QEI0	RO	1	QEI Module 0 Present When set, indicates that QEI module 0 is present.
7:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SSI1	RO	1	SSI Module 1 Present When set, indicates that SSI module 1 is present.
4	SSI0	RO	1	SSI Module 0 Present When set, indicates that SSI module 0 is present.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	UART2	RO	1	UART Module 2 Present When set, indicates that UART module 2 is present.
1	UART1	RO	1	UART Module 1 Present When set, indicates that UART module 1 is present.
0	UART0	RO	1	UART Module 0 Present When set, indicates that UART module 0 is present.

# Register 19: Device Capabilities 3 (DC3), offset 0x018

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 3 (DC3)

Base 0x400F.E000 Offset 0x018 Type RO, reset 0xBFFF.FFFF

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	32KHZ	reserved	CCP5	CCP4	CCP3	CCP2	CCP1	CCP0	ADC0AIN7	ADC0AIN6	ADC0AIN5	ADC0AIN4	ADC0AIN3	ADC0AIN2	ADC0AIN1	ADC0AIN0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	0	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	PWMFAULT	C2O	C2PLUS	C2MINUS	C10	C1PLUS	C1MINUS	C0O	C0PLUS	C0MINUS	PWM5	PWM4	PWM3	PWM2	PWM1	PWM0
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

Bit/Field	Name	Туре	Reset	Description
31	32KHZ	RO	1	32KHz Input Clock Available When set, indicates an even CCP pin is present and can be used as a 32-KHz input clock.
30	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
29	CCP5	RO	1	CCP5 Pin Present When set, indicates that Capture/Compare/PWM pin 5 is present.
28	CCP4	RO	1	CCP4 Pin Present When set, indicates that Capture/Compare/PWM pin 4 is present.
27	CCP3	RO	1	CCP3 Pin Present When set, indicates that Capture/Compare/PWM pin 3 is present.
26	CCP2	RO	1	CCP2 Pin Present When set, indicates that Capture/Compare/PWM pin 2 is present.
25	CCP1	RO	1	CCP1 Pin Present When set, indicates that Capture/Compare/PWM pin 1 is present.
24	CCP0	RO	1	CCP0 Pin Present When set, indicates that Capture/Compare/PWM pin 0 is present.
23	ADC0AIN7	RO	1	ADC Module 0 AIN7 Pin Present When set, indicates that ADC module 0 input pin 7 is present.
22	ADC0AIN6	RO	1	ADC Module 0 AIN6 Pin Present When set, indicates that ADC module 0 input pin 6 is present.
21	ADC0AIN5	RO	1	ADC Module 0 AIN5 Pin Present When set, indicates that ADC module 0 input pin 5 is present.

Bit/Field	Name	Туре	Reset	Description
20	ADC0AIN4	RO	1	ADC Module 0 AIN4 Pin Present When set, indicates that ADC module 0 input pin 4 is present.
19	ADC0AIN3	RO	1	ADC Module 0 AIN3 Pin Present When set, indicates that ADC module 0 input pin 3 is present.
18	ADC0AIN2	RO	1	ADC Module 0 AIN2 Pin Present When set, indicates that ADC module 0 input pin 2 is present.
17	ADC0AIN1	RO	1	ADC Module 0 AIN1 Pin Present When set, indicates that ADC module 0 input pin 1 is present.
16	ADC0AIN0	RO	1	ADC Module 0 AIN0 Pin Present When set, indicates that ADC module 0 input pin 0 is present.
15	PWMFAULT	RO	1	PWM Fault Pin Present When set, indicates that a PWM Fault pin is present. See DC5 for specific Fault pins on this device.
14	C2O	RO	1	C2o Pin Present When set, indicates that the analog comparator 2 output pin is present.
13	C2PLUS	RO	1	C2+ Pin Present When set, indicates that the analog comparator 2 (+) input pin is present.
12	C2MINUS	RO	1	C2- Pin Present When set, indicates that the analog comparator 2 (-) input pin is present.
11	C10	RO	1	C1o Pin Present When set, indicates that the analog comparator 1 output pin is present.
10	C1PLUS	RO	1	C1+ Pin Present When set, indicates that the analog comparator 1 (+) input pin is present.
9	C1MINUS	RO	1	C1- Pin Present When set, indicates that the analog comparator 1 (-) input pin is present.
8	C0O	RO	1	C0o Pin Present When set, indicates that the analog comparator 0 output pin is present.
7	C0PLUS	RO	1	C0+ Pin Present When set, indicates that the analog comparator 0 (+) input pin is present.
6	COMINUS	RO	1	C0- Pin Present When set, indicates that the analog comparator 0 (-) input pin is present.
5	PWM5	RO	1	PWM5 Pin Present When set, indicates that the PWM pin 5 is present.
4	PWM4	RO	1	PWM4 Pin Present When set, indicates that the PWM pin 4 is present.
3	PWM3	RO	1	PWM3 Pin Present When set, indicates that the PWM pin 3 is present.

Bit/Field	Name	Type	Reset	Description
2	PWM2	RO	1	PWM2 Pin Present When set, indicates that the PWM pin 2 is present.
1	PWM1	RO	1	PWM1 Pin Present When set, indicates that the PWM pin 1 is present.
0	PWM0	RO	1	PWM0 Pin Present When set, indicates that the PWM pin 0 is present.

# Register 20: Device Capabilities 4 (DC4), offset 0x01C

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 4 (DC4)

Base 0x400F.E000 Offset 0x01C Type RO, reset 0x5104.F1FF

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPHY0	reserved	EMAC0		reserved		E1588			reserved			PICAL	rese	erved
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	1	0	1	0	0	0	1	0	0	0	0	0	1	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	CCP7	CCP6	UDMA	ROM		reserved		GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	()	0	0	1	1	1	1	1	1	1	1	1

		_		
Bit/Field	Name	Type	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPHY0	RO	1	Ethernet PHY Layer 0 Present
				When set, indicates that Ethernet PHY layer 0 is present.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	EMAC0	RO	1	Ethernet MAC Layer 0 Present
				When set, indicates that Ethernet MAC layer 0 is present.
27:25	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
24	E1588	RO	1	1588 Capable
				When set, indicates that that Ethernet MAC layer 0 is 1588 capable.
23:19	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
18	PICAL	RO	1	PIOSC Calibrate
				When set, indicates that the PIOSC can be calibrated.
17:16	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15	CCP7	RO	1	CCP7 Pin Present
				When set, indicates that Capture/Compare/PWM pin 7 is present.

Bit/Field	Name	Туре	Reset	Description
14	CCP6	RO	1	CCP6 Pin Present When set, indicates that Capture/Compare/PWM pin 6 is present.
13	UDMA	RO	1	Micro-DMA Module Present When set, indicates that the micro-DMA module present.
12	ROM	RO	1	Internal Code ROM Present When set, indicates that internal code ROM is present.
11:9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	GPIOJ	RO	1	GPIO Port J Present When set, indicates that GPIO Port J is present.
7	GPIOH	RO	1	GPIO Port H Present When set, indicates that GPIO Port H is present.
6	GPIOG	RO	1	GPIO Port G Present When set, indicates that GPIO Port G is present.
5	GPIOF	RO	1	GPIO Port F Present When set, indicates that GPIO Port F is present.
4	GPIOE	RO	1	GPIO Port E Present When set, indicates that GPIO Port E is present.
3	GPIOD	RO	1	GPIO Port D Present When set, indicates that GPIO Port D is present.
2	GPIOC	RO	1	GPIO Port C Present When set, indicates that GPIO Port C is present.
1	GPIOB	RO	1	GPIO Port B Present When set, indicates that GPIO Port B is present.
0	GPIOA	RO	1	GPIO Port A Present When set, indicates that GPIO Port A is present.


### Register 21: Device Capabilities 5 (DC5), offset 0x020

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 5 (DC5)

Base 0x400F.E000

Offset 0x020 Type RO, reset 0x0F30.00FF



Bit/Field	Name	Туре	Reset	Description
31:28	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
27	PWMFAULT3	RO	1	PWM Fault 3 Pin Present When set, indicates that the PWM Fault 3 pin is present.
26	PWMFAULT2	RO	1	PWM Fault 2 Pin Present When set, indicates that the PWM Fault 2 pin is present.
25	PWMFAULT1	RO	1	PWM Fault 1 Pin Present When set, indicates that the PWM Fault 1 pin is present.
24	PWMFAULT0	RO	1	PWM Fault 0 Pin Present When set, indicates that the PWM Fault 0 pin is present.
23:22	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
21	PWMEFLT	RO	1	PWM Extended Fault Active When set, indicates that the PWM Extended Fault feature is active.
20	PWMESYNC	RO	1	PWM Extended SYNC Active When set, indicates that the PWM Extended SYNC feature is active.
19:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	PWM7	RO	1	PWM7 Pin Present When set, indicates that the PWM pin 7 is present.
6	PWM6	RO	1	PWM6 Pin Present When set, indicates that the PWM pin 6 is present.

Bit/Field	Name	Туре	Reset	Description
5	PWM5	RO	1	PWM5 Pin Present When set, indicates that the PWM pin 5 is present.
4	PWM4	RO	1	PWM4 Pin Present When set, indicates that the PWM pin 4 is present.
3	PWM3	RO	1	PWM3 Pin Present When set, indicates that the PWM pin 3 is present.
2	PWM2	RO	1	PWM2 Pin Present When set, indicates that the PWM pin 2 is present.
1	PWM1	RO	1	PWM1 Pin Present When set, indicates that the PWM pin 1 is present.
0	PWM0	RO	1	PWM0 Pin Present When set, indicates that the PWM pin 0 is present.


#### Register 22: Device Capabilities 6 (DC6), offset 0x024

This register is predefined by the part and can be used to verify features. If any bit is clear in this register, the module is not present. The corresponding bit in the RCGC0, SCGC0, and DCGC0 registers cannot be set.

Device Capabilities 6 (DC6)

Base 0x400F.E000

Offset 0x024 Type RO, reset 0x0000.0013



Bit/Field	Name	Type	Reset	Description
31:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	USB0PHY	RO	1	USB Module 0 PHY Present When set, indicates that the USB module 0 PHY is present.
3:2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1:0	USB0	RO	0x3	USB Module 0 Present

Thie field indicates that USB module 0 is present and specifies its capability.

Value Description
0x3 USB0 is OTG.

#### Register 23: Device Capabilities 7 (DC7), offset 0x028

This register is predefined by the part and can be used to verify uDMA channel features. A 1 indicates the channel is available on this device; a 0 that the channel is only available on other devices in the family. Most channels have primary and secondary assignments. If the primary function is not available on this microcontroller, the secondary function becomes the primary function. If the secondary function is not available, the primary function is the only option.

#### Device Capabilities 7 (DC7)

Base 0x400F.E000 Offset 0x028 Type RO, reset 0xFFFF.FFF

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	DMACH30	DMACH29	DMACH28	DMACH27	DMACH26	DMACH25	DMACH24	DMACH23	DMACH22	DMACH21	DMACH20	DMACH19	DMACH18	DMACH17	DMACH16
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	DMACH15	DMACH14	DMACH13	DMACH12	DMACH11	DMACH10	DMACH9	DMACH8	DMACH7	DMACH6	DMACH5	DMACH4	DMACH3	DMACH2	DMACH1	DMACH0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	1	Reserved Reserved for uDMA channel 31.
30	DMACH30	RO	1	SW When set, indicates uDMA channel 30 is available for software transfers.
29	DMACH29	RO	1	I2S0_TX / CAN1_TX When set, indicates uDMA channel 29 is available and connected to the transmit path of I2S module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of CAN module 1 transmit.
28	DMACH28	RO	1	I2S0_RX / CAN1_RX When set, indicates uDMA channel 28 is available and connected to the receive path of I2S module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of CAN module 1 receive.
27	DMACH27	RO	1	CAN1_TX / ADC1_SS3 When set, indicates uDMA channel 27 is available and connected to the transmit path of CAN module 1. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of ADC module 1 Sample Sequencer 3.
26	DMACH26	RO	1	CAN1_RX / ADC1_SS2 When set, indicates uDMA channel 26 is available and connected to

the receive path of CAN module 1. If the corresponding bit in the **DMACHASGN** register is set, the channel is connected instead to the secondary channel assignment of ADC module 1 Sample Sequencer

Bit/Field	Name	Туре	Reset	Description
25	DMACH25	RO	1	SSI1_TX / ADC1_SS1 When set, indicates uDMA channel 25 is available and connected to the transmit path of SSI module 1. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of ADC module 1 Sample Sequencer 1.
24	DMACH24	RO	1	SSI1_RX / ADC1_SS0 When set, indicates uDMA channel 24 is available and connected to the receive path of SSI module 1. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of ADC module 1 Sample Sequencer 0.
23	DMACH23	RO	1	UART1_TX / CAN2_TX When set, indicates uDMA channel 23 is available and connected to the transmit path of UART module 1. If the corresponding bit in the DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of CAN module 2 transmit.
22	DMACH22	RO	1	UART1_RX / CAN2_RX When set, indicates uDMA channel 22 is available and connected to the receive path of UART module 1. If the corresponding bit in the DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of CAN module 2 receive.
21	DMACH21	RO	1	Timer1B / EPI0_WFIFO When set, indicates uDMA channel 21 is available and connected to Timer 1B. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of EPI module 0 write FIFO (WRIFO).
20	DMACH20	RO	1	Timer1A / EPI0_NBRFIFO When set, indicates uDMA channel 20 is available and connected to Timer 1A. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of EPI module 0 non-blocking read FIFO (NBRFIFO).
19	DMACH19	RO	1	Timer0B / Timer1B  When set, indicates uDMA channel 19 is available and connected to Timer 0B. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 1B.
18	DMACH18	RO	1	Timer0A / Timer1A When set, indicates uDMA channel 18 is available and connected to Timer 0A. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 1A.
17	DMACH17	RO	1	ADC0_SS3  When set, indicates uDMA channel 17 is available and connected to ADC module 0 Sample Sequencer 3.
16	DMACH16	RO	1	ADC0_SS2 When set, indicates uDMA channel 16 is available and connected to ADC module 0 Sample Sequencer 2.

Bit/Field	Name	Туре	Reset	Description
15	DMACH15	RO	1	ADC0_SS1 / Timer2B
				When set, indicates uDMA channel 15 is available and connected to ADC module 0 Sample Sequencer 1. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 2B.
14	DMACH14	RO	1	ADC0_SS0 / Timer2A
				When set, indicates uDMA channel 14 is available and connected to ADC module 0 Sample Sequencer 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 2A.
13	DMACH13	RO	1	CAN0_TX / UART2_TX
				When set, indicates uDMA channel 13 is available and connected to the transmit path of CAN module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of UART module 2 transmit.
12	DMACH12	RO	1	CAN0_RX / UART2_RX
				When set, indicates uDMA channel 12 is available and connected to the receive path of CAN module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of UART module 2 receive.
11	DMACH11	RO	1	SSI0_TX/SSI1_TX
				When set, indicates uDMA channel 11 is available and connected to the transmit path of SSI module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of SSI module 1 transmit.
10	DMACH10	RO	1	SSI0_RX / SSI1_RX
				When set, indicates uDMA channel 10 is available and connected to the receive path of SSI module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of SSI module 1 receive.
9	DMACH9	RO	1	UART0_TX / UART1_TX
				When set, indicates uDMA channel 9 is available and connected to the transmit path of UART module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of UART module 1 transmit.
8	DMACH8	RO	1	UART0_RX / UART1_RX
				When set, indicates uDMA channel 8 is available and connected to the receive path of UART module 0. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of UART module 1 receive.
7	DMACH7	RO	1	ETH_TX / Timer2B
				When set, indicates uDMA channel 7 is available and connected to the transmit path of the Ethernet module. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 2B.

Bit/Field	Name	Туре	Reset	Description
6	DMACH6	RO	1	ETH_RX / Timer2A When set, indicates uDMA channel 6 is available and connected to the receive path of the Ethernet module. If the corresponding bit in the DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of Timer 2A.
5	DMACH5	RO	1	USB_EP3_TX / Timer2B  When set, indicates uDMA channel 5 is available and connected to the transmit path of USB endpoint 3. If the corresponding bit in the  DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of Timer 2B.
4	DMACH4	RO	1	USB_EP3_RX / Timer2A When set, indicates uDMA channel 4 is available and connected to the receive path of USB endpoint 3. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of Timer 2A.
3	DMACH3	RO	1	USB_EP2_TX / Timer3B  When set, indicates uDMA channel 3 is available and connected to the transmit path of USB endpoint 2. If the corresponding bit in the  DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of Timer 3B.
2	DMACH2	RO	1	USB_EP2_RX / Timer3A When set, indicates uDMA channel 2 is available and connected to the receive path of USB endpoint 2. If the corresponding bit in the DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of Timer 3A.
1	DMACH1	RO	1	USB_EP1_TX / UART2_TX When set, indicates uDMA channel 1 is available and connected to the transmit path of USB endpoint 1. If the corresponding bit in the DMACHASGN register is set, the channel is connected instead to the secondary channel assignment of UART module 2 transmit.
0	DMACH0	RO	1	USB_EP1_RX / UART2_RX When set, indicates uDMA channel 0 is available and connected to the receive path of USB endpoint 1. If the corresponding bit in the <b>DMACHASGN</b> register is set, the channel is connected instead to the secondary channel assignment of UART module 2 receive.

## Register 24: Device Capabilities 8 ADC Channels (DC8), offset 0x02C

This register is predefined by the part and can be used to verify features.

Device Capabilities 8 ADC Channels (DC8)

Base 0x400F.E000

Offset 0x02C Type RO, reset 0xFFFF.FFF

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	ADC1AIN15	ADC1AIN14	ADC1AIN13	ADC1AIN12	ADC1AIN11	ADC1AIN10	ADC1AIN9	ADC1AIN8	ADC1AIN7	ADC1AIN6	ADC1AIN5	ADC1AIN4	ADC1AIN3	ADC1AIN2	ADC1AIN1	ADC1AIN0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	ADC0AIN15	ADC0AIN14	ADC0AIN13	ADC0AIN12	ADC0AIN11	ADC0AIN10	ADC0AIN9	ADC0AIN8	ADC0AIN7	ADC0AIN6	ADC0AIN5	ADC0AIN4	ADC0AIN3	ADC0AIN2	ADC0AIN1	ADC0AIN0
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Docot	- 1	1	- 1	1	1	1	1	- 1	1	- 1	1	1	1	1	1	1

Bit/Field	Name	Туре	Reset	Description
31	ADC1AIN15	RO	1	ADC Module 1 AIN15 Pin Present When set, indicates that ADC module 1 input pin 15 is present.
30	ADC1AIN14	RO	1	ADC Module 1 AIN14 Pin Present When set, indicates that ADC module 1 input pin 14 is present.
29	ADC1AIN13	RO	1	ADC Module 1 AIN13 Pin Present When set, indicates that ADC module 1 input pin 13 is present.
28	ADC1AIN12	RO	1	ADC Module 1 AIN12 Pin Present When set, indicates that ADC module 1 input pin 12 is present.
27	ADC1AIN11	RO	1	ADC Module 1 AIN11 Pin Present When set, indicates that ADC module 1 input pin 11 is present.
26	ADC1AIN10	RO	1	ADC Module 1 AIN10 Pin Present When set, indicates that ADC module 1 input pin 10 is present.
25	ADC1AIN9	RO	1	ADC Module 1 AIN9 Pin Present When set, indicates that ADC module 1 input pin 9 is present.
24	ADC1AIN8	RO	1	ADC Module 1 AIN8 Pin Present When set, indicates that ADC module 1 input pin 8 is present.
23	ADC1AIN7	RO	1	ADC Module 1 AIN7 Pin Present When set, indicates that ADC module 1 input pin 7 is present.
22	ADC1AIN6	RO	1	ADC Module 1 AIN6 Pin Present When set, indicates that ADC module 1 input pin 6 is present.
21	ADC1AIN5	RO	1	ADC Module 1 AIN5 Pin Present When set, indicates that ADC module 1 input pin 5 is present.
20	ADC1AIN4	RO	1	ADC Module 1 AIN4 Pin Present When set, indicates that ADC module 1 input pin 4 is present.

Bit/Field	Name	Туре	Reset	Description
19	ADC1AIN3	RO	1	ADC Module 1 AIN3 Pin Present When set, indicates that ADC module 1 input pin 3 is present.
18	ADC1AIN2	RO	1	ADC Module 1 AIN2 Pin Present When set, indicates that ADC module 1 input pin 2 is present.
17	ADC1AIN1	RO	1	ADC Module 1 AIN1 Pin Present When set, indicates that ADC module 1 input pin 1 is present.
16	ADC1AIN0	RO	1	ADC Module 1 AIN0 Pin Present When set, indicates that ADC module 1 input pin 0 is present.
15	ADC0AIN15	RO	1	ADC Module 0 AIN15 Pin Present When set, indicates that ADC module 0 input pin 15 is present.
14	ADC0AIN14	RO	1	ADC Module 0 AIN14 Pin Present When set, indicates that ADC module 0 input pin 14 is present.
13	ADC0AIN13	RO	1	ADC Module 0 AIN13 Pin Present When set, indicates that ADC module 0 input pin 13 is present.
12	ADC0AIN12	RO	1	ADC Module 0 AIN12 Pin Present When set, indicates that ADC module 0 input pin 12 is present.
11	ADC0AIN11	RO	1	ADC Module 0 AIN11 Pin Present When set, indicates that ADC module 0 input pin 11 is present.
10	ADC0AIN10	RO	1	ADC Module 0 AIN10 Pin Present When set, indicates that ADC module 0 input pin 10 is present.
9	ADC0AIN9	RO	1	ADC Module 0 AIN9 Pin Present When set, indicates that ADC module 0 input pin 9 is present.
8	ADC0AIN8	RO	1	ADC Module 0 AIN8 Pin Present When set, indicates that ADC module 0 input pin 8 is present.
7	ADC0AIN7	RO	1	ADC Module 0 AIN7 Pin Present When set, indicates that ADC module 0 input pin 7 is present.
6	ADC0AIN6	RO	1	ADC Module 0 AIN6 Pin Present When set, indicates that ADC module 0 input pin 6 is present.
5	ADC0AIN5	RO	1	ADC Module 0 AIN5 Pin Present When set, indicates that ADC module 0 input pin 5 is present.
4	ADC0AIN4	RO	1	ADC Module 0 AIN4 Pin Present When set, indicates that ADC module 0 input pin 4 is present.
3	ADC0AIN3	RO	1	ADC Module 0 AIN3 Pin Present When set, indicates that ADC module 0 input pin 3 is present.
2	ADC0AIN2	RO	1	ADC Module 0 AIN2 Pin Present When set, indicates that ADC module 0 input pin 2 is present.

Bit/Field	Name	Type	Reset	Description
1	ADC0AIN1	RO	1	ADC Module 0 AIN1 Pin Present When set, indicates that ADC module 0 input pin 1 is present.
0	ADC0AIN0	RO	1	ADC Module 0 AIN0 Pin Present When set, indicates that ADC module 0 input pin 0 is present.


#### Register 25: Device Capabilities 9 ADC Digital Comparators (DC9), offset 0x190

This register is predefined by the part and can be used to verify features.

Device Capabilities 9 ADC Digital Comparators (DC9)

Base 0x400F.E000

Offset 0x190 Type RO, reset 0x00FF.00FF



Bit/Field	Name	Туре	Reset	Description
6	ADC0DC6	RO	1	ADC0 DC6 Present When set, indicates that ADC module 0 Digital Comparator 6 is present.
5	ADC0DC5	RO	1	ADC0 DC5 Present When set, indicates that ADC module 0 Digital Comparator 5 is present.
4	ADC0DC4	RO	1	ADC0 DC4 Present When set, indicates that ADC module 0 Digital Comparator 4 is present.
3	ADC0DC3	RO	1	ADC0 DC3 Present When set, indicates that ADC module 0 Digital Comparator 3 is present.
2	ADC0DC2	RO	1	ADC0 DC2 Present When set, indicates that ADC module 0 Digital Comparator 2 is present.
1	ADC0DC1	RO	1	ADC0 DC1 Present When set, indicates that ADC module 0 Digital Comparator 1 is present.
0	ADC0DC0	RO	1	ADC0 DC0 Present When set, indicates that ADC module 0 Digital Comparator 0 is present.


## Register 26: Non-Volatile Memory Information (NVMSTAT), offset 0x1A0

This register is predefined by the part and can be used to verify features.

Non-Volatile Memory Information (NVMSTAT)

Base 0x400F.E000 Offset 0x1A0

Type RO, reset 0x0000.0011



Bit/Field	Name	Type	Reset	Description
31:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	TPSW	RO	1	Third Party Software Present When set, indicates that the ROM contains third party software.
3:1	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	FWB	RO	1	32 Word Flash Write Buffer Active When set, indicates that the 32 word Flash memory write buffer feature

is active.


### Register 27: Run Mode Clock Gating Control Register 0 (RCGC0), offset 0x100

This register controls the clock gating logic in normal Run mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC0** is the clock configuration register for running operation, **SCGC0** for Sleep operation, and **DCGC0** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Run Mode Clock Gating Control Register 0 (RCGC0)

Base 0x400F.E000

Offset 0x100 Type R/W, reset 0x00000040



Bit/Field	Name	Type	Reset	Description
31:29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	WDT1	R/W	0	WDT1 Clock Gating Control
				This bit controls the clock gating for the Watchdog Timer module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:26	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
25	CAN1	R/W	0	CAN1 Clock Gating Control
				This bit controls the clock gating for CAN module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	CAN0	R/W	0	CAN0 Clock Gating Control
				This bit controls the clock gating for CAN module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and

generates a bus fault.

disabled. If the module is unclocked, a read or write to the module

Bit/Field	Name	Туре	Reset	Description
23:21	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
20	PWM	R/W	0	PWM Clock Gating Control
				This bit controls the clock gating for the PWM module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
19:18	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
17	ADC1	R/W	0	ADC1 Clock Gating Control
				This bit controls the clock gating for SAR ADC module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	ADC0	R/W	0	ADC0 Clock Gating Control
				This bit controls the clock gating for ADC module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11:10	MAXADC1SPD	R/W	0	ADC1 Sample Speed
				This field sets the rate at which ADC module 1 samples data. You cannot set the rate higher than the maximum rate. You can set the sample rate by setting the MAXADC1SPD bit as follows (all other encodings are reserved):
				Value Description
				0x3 1M samples/second
				0x2 500K samples/second
				0x1 250K samples/second
				0x0 125K samples/second
9:8	MAXADC0SPD	R/W	0	ADC0 Sample Speed
				This field sets the rate at which ADC0 samples data. You cannot set the rate higher than the maximum rate. You can set the sample rate by setting the MAXADC0SPD bit as follows (all other encodings are reserved):
				Value Description
				0x3 1M samples/second
				0x2 500K samples/second
				0x1 250K samples/second
				0x0 125K samples/second

Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	reserved	RO	1	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	WDT0	R/W	0	WDT0 Clock Gating Control
				This bit controls the clock gating for the Watchdog Timer module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
2:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 28: Sleep Mode Clock Gating Control Register 0 (SCGC0), offset 0x110

This register controls the clock gating logic in Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC0** is the clock configuration register for running operation, **SCGC0** for Sleep operation, and **DCGC0** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Sleep Mode Clock Gating Control Register 0 (SCGC0)

Base 0x400F.E000 Offset 0x110

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		reserved		WDT1	rese	rved	CAN1	CAN0		reserved		PWM	rese	rved	ADC1	ADC0
Type	RO	RO	RO	R/W	RO	RO	R/W	R/W	RO	RO	RO	R/W	RO	RO	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	45	44	40	40	44	40	0		-	0	_		0	2	4	0
	15	14	13	12	11	10	9	- 8		6	5	4	3		1	0
		reser	ved		MAXAD	C1SPD	MAXAD	COSPD	reserved	reserved	rese	rved	WDT0		reserved	
Туре	RO	RO	RO	RO	R/W	R/W	R/W	R/W	RO	RO	RO	RO	R/W	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	WDT1	R/W	0	WDT1 Clock Gating Control
				This bit controls the clock gating for Watchdog Timer module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:26	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
25	CAN1	R/W	0	CAN1 Clock Gating Control
				This bit controls the clock gating for CAN module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	CAN0	R/W	0	CAN0 Clock Gating Control
				This bit controls the clock gating for CAN module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
23:21	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
20	PWM	R/W	0	PWM Clock Gating Control  This hit controls the clock gating for the DWM module. If get, the module
				This bit controls the clock gating for the PWM module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
19:18	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
17	ADC1	R/W	0	ADC1 Clock Gating Control
				This bit controls the clock gating for ADC module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	ADC0	R/W	0	ADC0 Clock Gating Control
				This bit controls the clock gating for ADC module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11:10	MAXADC1SPD	R/W	0	ADC1 Sample Speed
				This field sets the rate at which ADC module 1 samples data. You cannot set the rate higher than the maximum rate. You can set the sample rate by setting the MAXADC1SPD bit as follows (all other encodings are reserved):
				Value Description
				0x3 1M samples/second
				0x2 500K samples/second
				0x1 250K samples/second
				0x0 125K samples/second
9:8	MAXADC0SPD	R/W	0	ADC0 Sample Speed
				This field sets the rate at which ADC module 0 samples data. You cannot set the rate higher than the maximum rate. You can set the sample rate by setting the MAXADCOSPD bit as follows (all other encodings are reserved):
				Value Description
				0x3 1M samples/second
				0x2 500K samples/second
				0x1 250K samples/second
				0x0 125K samples/second

Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	reserved	RO	1	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	WDT0	R/W	0	WDT0 Clock Gating Control  This bit controls the clock gating for the Watchdog Timer module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
2:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 29: Deep Sleep Mode Clock Gating Control Register 0 (DCGC0), offset 0x120

This register controls the clock gating logic in Deep-Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC0** is the clock configuration register for running operation, **SCGC0** for Sleep operation, and **DCGC0** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Deep Sleep Mode Clock Gating Control Register 0 (DCGC0)

Base 0x400F.E000 Offset 0x120

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		reserved		WDT1	rese	rved	CAN1	CAN0		reserved		PWM	rese	rved	ADC1	ADC0
Type	RO	RO	RO	R/W	RO	RO	R/W	R/W	RO	RO	RO	R/W	RO	RO	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
				1	reserved		1			reserved	rese	rved	WDT0		reserved	
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	RO	RO	RO
Reset	Ω	0	Ω	Ω	0	0	0	Ω	Ω	1	Ω	0	0	0	0	Ω

Bit/Field	Name	Туре	Reset	Description
31:29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	WDT1	R/W	0	WDT1 Clock Gating Control
				This bit controls the clock gating for the Watchdog Timer module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:26	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
25	CAN1	R/W	0	CAN1 Clock Gating Control
				This bit controls the clock gating for CAN module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	CAN0	R/W	0	CAN0 Clock Gating Control  This bit controls the clock gating for CAN module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
23:21	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
20	PWM	R/W	0	PWM Clock Gating Control
				This bit controls the clock gating for the PWM module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
19:18	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
17	ADC1	R/W	0	ADC1 Clock Gating Control
				This bit controls the clock gating for ADC module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	ADC0	R/W	0	ADC0 Clock Gating Control
				This bit controls the clock gating for ADC module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	reserved	RO	1	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	WDT0	R/W	0	WDT0 Clock Gating Control
				This bit controls the clock gating for the Watchdog Timer module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
2:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 30: Run Mode Clock Gating Control Register 1 (RCGC1), offset 0x104

This register controls the clock gating logic in normal Run mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC1** is the clock configuration register for running operation, **SCGC1** for Sleep operation, and **DCGC1** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Run Mode Clock Gating Control Register 1 (RCGC1)

Base 0x400F.E000 Offset 0x104

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPI0	reserved	1280	reserved	COMP2	COMP1	COMP0		rese	rved		TIMER3	TIMER2	TIMER1	TIMER0
Type	RO	R/W	RO	R/W	RO	R/W	R/W	R/W	RO	RO	RO	RO	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved	I2C1	reserved	I2C0	rese	rved	QEI1	QEI0	rese	rved	SSI1	SSI0	reserved	UART2	UART1	UART0
Type	RO	R/W	RO	R/W	RO	RO	R/W	R/W	RO	RO	R/W	R/W	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPI0	R/W	0	EPI0 Clock Gating  This bit controls the clock gating for EPI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	12S0	R/W	0	I2S0 Clock Gating This bit controls the clock gating for I2S module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
26	COMP2	R/W	0	Analog Comparator 2 Clock Gating  This bit controls the clock gating for analog comparator 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
25	COMP1	R/W	0	Analog Comparator 1 Clock Gating  This bit controls the clock gating for analog comparator 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	COMP0	R/W	0	Analog Comparator 0 Clock Gating  This bit controls the clock gating for analog comparator 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
23:20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	TIMER3	R/W	0	Timer 3 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 3. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
18	TIMER2	R/W	0	Timer 2 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 2.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
17	TIMER1	R/W	0	Timer 1 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 1.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	TIMER0	R/W	0	Timer 0 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 0.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	I2C1	R/W	0	I2C1 Clock Gating Control  This bit controls the clock gating for I2C module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	I2C0	R/W	0	I2C0 Clock Gating Control  This bit controls the clock gating for I2C module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
11:10	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	QEI1	R/W	0	QEI1 Clock Gating Control  This bit controls the clock gating for QEI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
8	QEI0	R/W	0	QEI0 Clock Gating Control  This bit controls the clock gating for QEI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SSI1	R/W	0	SSI1 Clock Gating Control  This bit controls the clock gating for SSI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	SSI0	R/W	0	SSI0 Clock Gating Control  This bit controls the clock gating for SSI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	UART2	R/W	0	UART2 Clock Gating Control  This bit controls the clock gating for UART module 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	UART1	R/W	0	UART1 Clock Gating Control  This bit controls the clock gating for UART module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Type	Reset	Description
0	UART0	R/W	0	UARTO Clock Gating Control  This bit controls the clock gating for UART module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

## Register 31: Sleep Mode Clock Gating Control Register 1 (SCGC1), offset 0x114

This register controls the clock gating logic in Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC1** is the clock configuration register for running operation, **SCGC1** for Sleep operation, and **DCGC1** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Sleep Mode Clock Gating Control Register 1 (SCGC1)

Base 0x400F.E000 Offset 0x114

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPI0	reserved	1280	reserved	COMP2	COMP1	COMP0	'	rese	rved		TIMER3	TIMER2	TIMER1	TIMER0
Type	RO	R/W	RO	R/W	RO	R/W	R/W	R/W	RO	RO	RO	RO	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved	I2C1	reserved	I2C0	rese	rved	QEI1	QEI0	rese	rved	SSI1	SSI0	reserved	UART2	UART1	UART0
Туре	RO	R/W	RO	R/W	RO	RO	R/W	R/W	RO	RO	R/W	R/W	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPI0	R/W	0	EPI0 Clock Gating
				This bit controls the clock gating for EPI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	12S0	R/W	0	I2S0 Clock Gating
				This bit controls the clock gating for I2S module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
26	COMP2	R/W	0	Analog Comparator 2 Clock Gating  This bit controls the clock gating for analog comparator 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
25	COMP1	R/W	0	Analog Comparator 1 Clock Gating  This bit controls the clock gating for analog comparator 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	COMP0	R/W	0	Analog Comparator 0 Clock Gating  This bit controls the clock gating for analog comparator 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
23:20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	TIMER3	R/W	0	Timer 3 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 3. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
18	TIMER2	R/W	0	Timer 2 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
17	TIMER1	R/W	0	Timer 1 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 1.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	TIMER0	R/W	0	Timer 0 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	I2C1	R/W	0	I2C1 Clock Gating Control  This bit controls the clock gating for I2C module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	I2C0	R/W	0	I2C0 Clock Gating Control
				This bit controls the clock gating for I2C module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
11:10	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	QEI1	R/W	0	QEI1 Clock Gating Control
				This bit controls the clock gating for QEI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
8	QEI0	R/W	0	QEI0 Clock Gating Control
				This bit controls the clock gating for QEI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SSI1	R/W	0	SSI1 Clock Gating Control
				This bit controls the clock gating for SSI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	SSI0	R/W	0	SSI0 Clock Gating Control
				This bit controls the clock gating for SSI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	UART2	R/W	0	UART2 Clock Gating Control
				This bit controls the clock gating for UART module 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	UART1	R/W	0	UART1 Clock Gating Control
				This bit controls the clock gating for UART module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
0	UART0	R/W	0	UART0 Clock Gating Control  This bit controls the clock gating for UART module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

## Register 32: Deep-Sleep Mode Clock Gating Control Register 1 (DCGC1), offset 0x124

This register controls the clock gating logic in Deep-Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC1** is the clock configuration register for running operation, **SCGC1** for Sleep operation, and **DCGC1** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Deep-Sleep Mode Clock Gating Control Register 1 (DCGC1)

Base 0x400F.E000 Offset 0x124 Type R/W, reset 0x00000000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPI0	reserved	1280	reserved	COMP2	COMP1	COMP0		rese	rved		TIMER3	TIMER2	TIMER1	TIMER0
Type	RO	R/W	RO	R/W	RO	R/W	R/W	R/W	RO	RO	RO	RO	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	- 8	7	6	5	4	3	2	1	0
	reserved	I2C1	reserved	I2C0	rese	rved	QEI1	QEI0	rese	rved	SSI1	SSI0	reserved	UART2	UART1	UART0
Туре	RO	R/W	RO	R/W	RO	RO	R/W	R/W	RO	RO	R/W	R/W	RO	R/W	R/W	R/W

Bit/Field	Name	Type	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPI0	R/W	0	EPI0 Clock Gating
				This bit controls the clock gating for EPI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	12S0	R/W	0	I2S0 Clock Gating
				This bit controls the clock gating for I2S module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
26	COMP2	R/W	0	Analog Comparator 2 Clock Gating  This bit controls the clock gating for analog comparator 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
25	COMP1	R/W	0	Analog Comparator 1 Clock Gating  This bit controls the clock gating for analog comparator 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
24	COMP0	R/W	0	Analog Comparator 0 Clock Gating  This bit controls the clock gating for analog comparator 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
23:20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	TIMER3	R/W	0	Timer 3 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 3. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
18	TIMER2	R/W	0	Timer 2 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 2.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
17	TIMER1	R/W	0	Timer 1 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 1.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
16	TIMER0	R/W	0	Timer 0 Clock Gating Control  This bit controls the clock gating for General-Purpose Timer module 0.  If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	I2C1	R/W	0	I2C1 Clock Gating Control  This bit controls the clock gating for I2C module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	I2C0	R/W	0	I2C0 Clock Gating Control
				This bit controls the clock gating for I2C module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
11:10	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	QEI1	R/W	0	QEI1 Clock Gating Control
				This bit controls the clock gating for QEI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
8	QEI0	R/W	0	QEI0 Clock Gating Control
				This bit controls the clock gating for QEI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SSI1	R/W	0	SSI1 Clock Gating Control
				This bit controls the clock gating for SSI module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	SSI0	R/W	0	SSI0 Clock Gating Control
				This bit controls the clock gating for SSI module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	UART2	R/W	0	UART2 Clock Gating Control
				This bit controls the clock gating for UART module 2. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	UART1	R/W	0	UART1 Clock Gating Control
				This bit controls the clock gating for UART module 1. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
0	UART0	R/W	0	UARTO Clock Gating Control  This bit controls the clock gating for UART module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.


### Register 33: Run Mode Clock Gating Control Register 2 (RCGC2), offset 0x108

This register controls the clock gating logic in normal Run mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. RCGC2 is the clock configuration register for running operation, SCGC2 for Sleep operation, and DCGC2 for Deep-Sleep operation. Setting the ACG bit in the Run-Mode Clock Configuration (RCC) register specifies that the system uses sleep modes.

Run Mode Clock Gating Control Register 2 (RCGC2)

Base 0x400F.E000

Offset 0x108
Type R/W, reset 0x00000000



Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPHY0	R/W	0	PHY0 Clock Gating Control  This bit controls the clock gating for Ethernet PHY layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	EMAC0	R/W	0	MAC0 Clock Gating Control  This bit controls the clock gating for Ethernet MAC layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:17	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
16	USB0	R/W	0	USB0 Clock Gating Control
				This bit controls the clock gating for USB module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	UDMA	R/W	0	Micro-DMA Clock Gating Control
				This bit controls the clock gating for micro-DMA. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
12:9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	GPIOJ	R/W	0	Port J Clock Gating Control
				This bit controls the clock gating for Port J. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7	GPIOH	R/W	0	Port H Clock Gating Control
				This bit controls the clock gating for Port H. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
6	GPIOG	R/W	0	Port G Clock Gating Control
				This bit controls the clock gating for Port G. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
5	GPIOF	R/W	0	Port F Clock Gating Control
				This bit controls the clock gating for Port F. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	GPIOE	R/W	0	Port E Clock Gating Control
				Port E Clock Gating Control. This bit controls the clock gating for Port E. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	GPIOD	R/W	0	Port D Clock Gating Control
				Port D Clock Gating Control. This bit controls the clock gating for Port D. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.


Bit/Field	Name	Type	Reset	Description
2	GPIOC	R/W	0	Port C Clock Gating Control  This bit controls the clock gating for Port C. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	GPIOB	R/W	0	Port B Clock Gating Control  This bit controls the clock gating for Port B. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
0	GPIOA	R/W	0	Port A Clock Gating Control  This bit controls the clock gating for Port A. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

# Register 34: Sleep Mode Clock Gating Control Register 2 (SCGC2), offset 0x118

This register controls the clock gating logic in Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC2** is the clock configuration register for running operation, **SCGC2** for Sleep operation, and **DCGC2** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Sleep Mode Clock Gating Control Register 2 (SCGC2)

Base 0x400F.E000 Offset 0x118



Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPHY0	R/W	0	PHY0 Clock Gating Control
				This bit controls the clock gating for Ethernet PHY layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	EMAC0	R/W	0	MAC0 Clock Gating Control
				This bit controls the clock gating for Ethernet MAC layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:17	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
16	USB0	R/W	0	USB0 Clock Gating Control  This bit controls the clock gating for USB module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	UDMA	R/W	0	Micro-DMA Clock Gating Control  This bit controls the clock gating for micro-DMA. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
12:9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	GPIOJ	R/W	0	Port J Clock Gating Control  This bit controls the clock gating for Port J. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7	GPIOH	R/W	0	Port H Clock Gating Control  This bit controls the clock gating for Port H. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
6	GPIOG	R/W	0	Port G Clock Gating Control  This bit controls the clock gating for Port G. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
5	GPIOF	R/W	0	Port F Clock Gating Control  This bit controls the clock gating for Port F. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	GPIOE	R/W	0	Port E Clock Gating Control  Port E Clock Gating Control. This bit controls the clock gating for Port  E. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	GPIOD	R/W	0	Port D Clock Gating Control  Port D Clock Gating Control. This bit controls the clock gating for Port  D. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Туре	Reset	Description
2	GPIOC	R/W	0	Port C Clock Gating Control
				This bit controls the clock gating for Port C. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	GPIOB	R/W	0	Port B Clock Gating Control
				This bit controls the clock gating for Port B. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
0	GPIOA	R/W	0	Port A Clock Gating Control
				This bit controls the clock gating for Port A. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

# Register 35: Deep Sleep Mode Clock Gating Control Register 2 (DCGC2), offset 0x128

This register controls the clock gating logic in Deep-Sleep mode. Each bit controls a clock enable for a given interface, function, or module. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled (saving power). If the module is unclocked, reads or writes to the module generate a bus fault. The reset state of these bits is 0 (unclocked) unless otherwise noted, so that all functional modules are disabled. It is the responsibility of software to enable the ports necessary for the application. Note that these registers may contain more bits than there are interfaces, functions, or modules to control. This configuration is implemented to assure reasonable code compatibility with other family and future parts. **RCGC2** is the clock configuration register for running operation, **SCGC2** for Sleep operation, and **DCGC2** for Deep-Sleep operation. Setting the ACG bit in the **Run-Mode Clock Configuration (RCC)** register specifies that the system uses sleep modes.

Deep Sleep Mode Clock Gating Control Register 2 (DCGC2)

Base 0x400F.E000 Offset 0x128

Type R/W, reset 0x00000000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	reserved	EPHY0	reserved	EMAC0				1		reserved						USB0
Type	RO	R/W	RO	R/W	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	rese	rved	UDMA		rese	rved		GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
Type	RO	RO	R/W	RO	RO	RO	RO	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPHY0	R/W	0	PHY0 Clock Gating Control
				This bit controls the clock gating for Ethernet PHY layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	EMAC0	R/W	0	MAC0 Clock Gating Control
				This bit controls the clock gating for Ethernet MAC layer 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
27:17	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
16	USB0	R/W	0	USB0 Clock Gating Control
				This bit controls the clock gating for USB module 0. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
15:14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	UDMA	R/W	0	Micro-DMA Clock Gating Control
				This bit controls the clock gating for micro-DMA. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
12:9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	GPIOJ	R/W	0	Port J Clock Gating Control
				This bit controls the clock gating for Port J. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
7	GPIOH	R/W	0	Port H Clock Gating Control
				This bit controls the clock gating for Port H. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
6	GPIOG	R/W	0	Port G Clock Gating Control
				This bit controls the clock gating for Port G. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
5	GPIOF	R/W	0	Port F Clock Gating Control
				This bit controls the clock gating for Port F. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
4	GPIOE	R/W	0	Port E Clock Gating Control
				Port E Clock Gating Control. This bit controls the clock gating for Port E. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
3	GPIOD	R/W	0	Port D Clock Gating Control
				Port D Clock Gating Control. This bit controls the clock gating for Port D. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

Bit/Field	Name	Type	Reset	Description
2	GPIOC	R/W	0	Port C Clock Gating Control
				This bit controls the clock gating for Port C. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
1	GPIOB	R/W	0	Port B Clock Gating Control
				This bit controls the clock gating for Port B. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.
0	GPIOA	R/W	0	Port A Clock Gating Control
				This bit controls the clock gating for Port A. If set, the module receives a clock and functions. Otherwise, the module is unclocked and disabled. If the module is unclocked, a read or write to the module generates a bus fault.

### Register 36: Software Reset Control 0 (SRCR0), offset 0x040


This register allows individual modules to be reset. Writes to this register are masked by the bits in the Device Capabilities 1 (DC1) register.

Software Reset Control 0 (SRCR0)

Base 0x400F.E000

19:18

Offset 0x040 Type R/W, reset 0x00000000



Software should not rely on the value of a reserved bit. To provide

preserved across a read-modify-write operation.

compatibility with future products, the value of a reserved bit should be

RO

reserved

0

Bit/Field	Name	Туре	Reset	Description
17	ADC1	R/W	0	ADC1 Reset Control When this bit is set, ADC module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
16	ADC0	R/W	0	ADC0 Reset Control When this bit is set, ADC module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
15:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	WDT0	R/W	0	WDT0 Reset Control
				When this bit is set, Watchdog Timer module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
2:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 37: Software Reset Control 1 (SRCR1), offset 0x044

This register allows individual modules to be reset. Writes to this register are masked by the bits in the Device Capabilities 2 (DC2) register.

Software Reset Control 1 (SRCR1)

Base 0x400F.E000 Offset 0x044 Type R/W, reset 0x00000000

	31	30	23	20	- 21									10	- 17	10
	reserved	EPI0	reserved	1280	reserved	COMP2	COMP1	COMP0		rese	rved		TIMER3	TIMER2	TIMER1	TIMER0
Type Reset	RO 0	R/W 0	RO 0	R/W 0	RO 0	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	R/W 0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved	I2C1	reserved	I2C0	rese	rved	QEI1	QEI0	rese	erved	SSI1	SSI0	reserved	UART2	UART1	UART0
Type Reset	RO 0	R/W 0	RO 0	R/W 0	RO 0	RO 0	R/W 0	R/W 0	RO 0	RO 0	R/W 0	R/W 0	RO 0	R/W 0	R/W 0	R/W 0
E	Bit/Field		Nam	е	Ту	ре	Reset	Des	cription							
	31		reserv	red	R	0	0	com	patibility	ould not i with futu cross a re	ıre produ	ıcts, the	value of	a reserv	•	
	30		EPI	)	R/	W	0	EPI	Reset	Control						
								the r	egisters	it is set, E are retur r being se	ned to th					
	29		reserv	red	R	0	0	com	patibility	ould not i with futu cross a re	ıre produ	ucts, the	value of	a reserv	•	
	28		1280	)	R/	W	0	1280	Reset (	Control						
								the r	egisters	it is set, la are retur r being se	ned to th					
	27		reserv	ed .	R	0	0	com	patibility	ould not i with futu cross a re	ıre produ	ıcts, the	value of	a reserv	•	
	26		COM	P2	R/	W	0	Ana	log Com	p 2 Rese	et Contro	ol				
								data	is lost a	it is set, A and the re nually cle	egisters a	are retur	ned to th			
	25		COM	P1	R/	W	0	Ana	log Com	p 1 Rese	et Contro	ol				
								data	is lost a	it is set, A and the re nually cle	egisters a	are retur	ned to th			
	24		COM	P0	R/	W	0	Ana	log Com	p 0 Rese	et Contro	ol				
								data	is lost a	it is set, A and the re nually cle	egisters a	are retur	ned to th			

Bit/Field	Name	Туре	Reset	Description
23:20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	TIMER3	R/W	0	Timer 3 Reset Control  Timer 3 Reset Control. When this bit is set, General-Purpose Timer module 3 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
18	TIMER2	R/W	0	Timer 2 Reset Control When this bit is set, General-Purpose Timer module 2 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
17	TIMER1	R/W	0	Timer 1 Reset Control  When this bit is set, General-Purpose Timer module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
16	TIMER0	R/W	0	Timer 0 Reset Control  When this bit is set, General-Purpose Timer module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
15	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	I2C1	R/W	0	I2C1 Reset Control When this bit is set, I2C module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
13	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	I2C0	R/W	0	I2C0 Reset Control When this bit is set, I2C module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
11:10	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	QEI1	R/W	0	QEI1 Reset Control When this bit is set, QEI module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
8	QEI0	R/W	0	QEI0 Reset Control When this bit is set, QEI module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.


Bit/Field	Name	Туре	Reset	Description
7:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SSI1	R/W	0	SSI1 Reset Control
				When this bit is set, SSI module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
4	SSI0	R/W	0	SSI0 Reset Control
				When this bit is set, SSI module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	UART2	R/W	0	UART2 Reset Control
				When this bit is set, UART module 2 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
1	UART1	R/W	0	UART1 Reset Control
				When this bit is set, UART module 1 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
0	UART0	R/W	0	UART0 Reset Control
				When this bit is set, UART module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.

### Register 38: Software Reset Control 2 (SRCR2), offset 0x048

This register allows individual modules to be reset. Writes to this register are masked by the bits in the **Device Capabilities 4 (DC4)** register.

Software Reset Control 2 (SRCR2)

Base 0x400F.E000 Offset 0x048 Type R/W, reset 0x00000000



Bit/Field	Name	Туре	Reset	Description
31	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
30	EPHY0	R/W	0	PHY0 Reset Control When this bit is set, Ethernet PHY layer 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	EMAC0	R/W	0	MAC0 Reset Control  When this bit is set, Ethernet MAC layer 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
27:17	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
16	USB0	R/W	0	USB0 Reset Control When this bit is set, USB module 0 is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
15:14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	UDMA	R/W	0	Micro-DMA Reset Control When this bit is set, uDMA module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.

Bit/Field	Name	Туре	Reset	Description
12:9	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	GPIOJ	R/W	0	Port J Reset Control  When this bit is set, Port J module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
7	GPIOH	R/W	0	Port H Reset Control When this bit is set, Port H module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
6	GPIOG	R/W	0	Port G Reset Control  When this bit is set, Port G module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
5	GPIOF	R/W	0	Port F Reset Control  When this bit is set, Port F module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
4	GPIOE	R/W	0	Port E Reset Control  When this bit is set, Port E module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
3	GPIOD	R/W	0	Port D Reset Control  When this bit is set, Port D module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
2	GPIOC	R/W	0	Port C Reset Control When this bit is set, Port C module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
1	GPIOB	R/W	0	Port B Reset Control When this bit is set, Port B module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.
0	GPIOA	R/W	0	Port A Reset Control  When this bit is set, Port A module is reset. All internal data is lost and the registers are returned to their reset states. This bit must be manually cleared after being set.


### 6 Internal Memory

The LM3S9D96 microcontroller comes with 96 KB of bit-banded SRAM, internal ROM, and 512 KB of Flash memory. The Flash memory controller provides a user-friendly interface, making Flash memory programming a simple task. Flash memory protection can be applied to the Flash memory on a 2-KB block basis.

### 6.1 Block Diagram

Figure 6-1 on page 300 illustrates the internal memory blocks and control logic. The dashed boxes in the figure indicate registers residing in the System Control module.

Figure 6-1. Internal Memory Block Diagram



## **6.2** Functional Description

This section describes the functionality of the SRAM, ROM, and Flash memories.

**Note:** The μDMA controller can transfer data to and from the on-chip SRAM. However, because the Flash memory and ROM are located on a separate internal bus, it is not possible to transfer data from the Flash memory or ROM with the μDMA controller.

#### 6.2.1 SRAM

The internal SRAM of the Stellaris<sup>®</sup> devices is located at address 0x2000.0000 of the device memory map. To reduce the number of time consuming read-modify-write (RMW) operations, ARM provides bit-banding technology in the processor. With a bit-band-enabled processor, certain regions in the memory map (SRAM and peripheral space) can use address aliases to access individual bits in a single, atomic operation. The bit-band base is located at address 0x2200.0000.

The bit-band alias is calculated by using the formula:

```
bit-band alias = bit-band base + (byte offset * 32) + (bit number * 4)
```

For example, if bit 3 at address 0x2000.1000 is to be modified, the bit-band alias is calculated as:

```
0x2200.0000 + (0x1000 * 32) + (3 * 4) = 0x2202.000C
```

With the alias address calculated, an instruction performing a read/write to address 0x2202.000C allows direct access to only bit 3 of the byte at address 0x2000.1000.

For details about bit-banding, see "Bit-Banding" on page 95.

**Note:** The SRAM is implemented using two 32-bit wide SRAM banks (separate SRAM arrays). The banks are partitioned such that one bank contains all even words (the even bank) and the other contains all odd words (the odd bank). A write access that is followed immediately by a read access to the same bank incurs a stall of a single clock cycle. However, a write to one bank followed by a read of the other bank can occur in successive clock cycles without incurring any delay.

#### 6.2.2 ROM

The internal ROM of the Stellaris device is located at address 0x0100.0000 of the device memory map. Detailed information on the ROM contents can be found in the *Stellaris® ROM User's Guide*.

The ROM contains the following components:

- Stellaris Boot Loader and vector table
- Stellaris Peripheral Driver Library (DriverLib) release for product-specific peripherals and interfaces
- SafeRTOS code
- Advanced Encryption Standard (AES) cryptography tables
- Cyclic Redundancy Check (CRC) error detection functionality

The boot loader is used as an initial program loader (when the Flash memory is empty) as well as an application-initiated firmware upgrade mechanism (by calling back to the boot loader). The Peripheral Driver Library APIs in ROM can be called by applications, reducing Flash memory requirements and freeing the Flash memory to be used for other purposes (such as additional features in the application). SafeRTOS is a low-overhead, mini, pre-emptive real-time scheduler. Advance Encryption Standard (AES) is a publicly defined encryption standard used by the U.S. Government and Cyclic Redundancy Check (CRC) is a technique to validate a span of data has the same contents as when previously checked.

#### 6.2.2.1 Boot Loader Overview

The Stellaris Boot Loader is used to download code to the Flash memory of a device without the use of a debug interface. When the core is reset, the user has the opportunity to direct the core to

execute the ROM Boot Loader or the application in Flash memory by using any GPIO signal in Ports A-H as configured in the **Boot Configuration (BOOTCFG)** register.

At reset, the ROM is mapped over the Flash memory so that the ROM boot sequence is always executed. The boot sequence executed from ROM is as follows:

- 1. The BA bit (below) is cleared such that ROM is mapped to 0x01xx.xxxx and Flash memory is mapped to address 0x0.
- 2. The **BOOTCFG** register is read. If the EN bit is clear, the status of the specified GPIO pin is compared with the specified polarity. If the status matches the specified polarity, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- 3. If the status doesn't match the specified polarity, the data at address 0x0000.0004 is read, and if the data at this address is 0xFFFF.FFFF, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- **4.** If there is data at address 0x0000.0004 that is not 0xFFFF.FFF, the stack pointer (**SP**) is loaded from Flash memory at address 0x0000.0000 and the program counter (**PC**) is loaded from address 0x0000.0004. The user application begins executing.

The boot loader uses a simple packet interface to provide synchronous communication with the device. The speed of the boot loader is determined by the internal oscillator (PIOSC) frequency as it does not enable the PLL. The following serial interfaces can be used:

- UART0
- SSI0
- I<sup>2</sup>C0
- Ethernet

For simplicity, both the data format and communication protocol are identical for all serial interfaces.

Note: The Flash-memory-resident version of the Boot Loader also supports CAN and USB.

See the Stellaris® Boot Loader User's Guide for information on the boot loader software.

#### 6.2.2.2 Stellaris Peripheral Driver Library

The Stellaris Peripheral Driver Library contains a file called driverlib/rom.h that assists with calling the peripheral driver library functions in the ROM. The detailed description of each function is available in the Stellaris® ROM User's Guide. See the "Using the ROM" chapter of the Stellaris® Peripheral Driver Library User's Guide for more details on calling the ROM functions and using driverlib/rom.h.

A table at the beginning of the ROM points to the entry points for the APIs that are provided in the ROM. Accessing the API through these tables provides scalability; while the API locations may change in future versions of the ROM, the API tables will not. The tables are split into two levels; the main table contains one pointer per peripheral which points to a secondary table that contains one pointer per API that is associated with that peripheral. The main table is located at 0x0100.0010, right after the Cortex-M3 vector table in the ROM.

DriverLib functions are described in detail in the Stellaris® Peripheral Driver Library User's Guide.

Additional APIs are available for graphics and USB functions, but are not preloaded into ROM. The Stellaris Graphics Library provides a set of graphics primitives and a widget set for creating graphical user interfaces on Stellaris microcontroller-based boards that have a graphical display (for more information, see the *Stellaris*® *Graphics Library User's Guide*). The Stellaris USB Library is a set of data types and functions for creating USB Device, Host or On-The-Go (OTG) applications on Stellaris microcontroller-based boards (for more information, see the *Stellaris*® *USB Library User's Guide*).

#### 6.2.2.3 SafeRTOS

SafeRTOS is a SIL3 RTOS version that has been certified for use in safety-critical applications. It is functionally similar to FreeRTOS, but has extended safety functionality. Complete IEC 61508-compliant development and safety lifecycle documentation is available (conformance certified by TÜV SÜD, including compiler verification evidence).

SafeRTOS is produced by WITTENSTEIN high-integrity systems for IEC 61508-compliant systems.

SafeRTOS is available in the integrated ROM of the LM3S9D96 microcontroller and is used with the SafeRTOS header files and initialization code and examples. For full SIL certification, the compliance specifications may be purchased from WITTENSTEIN.

For more information, refer to the SafeRTOS User's Manual.

#### 6.2.2.4 Advanced Encryption Standard (AES) Cryptography Tables

AES is a strong encryption method with reasonable performance and size. AES is fast in both hardware and software, is fairly easy to implement, and requires little memory. AES is ideal for applications that can use pre-arranged keys, such as setup during manufacturing or configuration. Four data tables used by the XySSL AES implementation are provided in the ROM. The first is the forward S-box substitution table, the second is the reverse S-box substitution table, the third is the forward polynomial table, and the final is the reverse polynomial table. See the *Stellaris® ROM User's Guide* for more information on AES.

#### 6.2.2.5 Cyclic Redundancy Check (CRC) Error Detection

The CRC technique can be used to validate correct receipt of messages (nothing lost or modified in transit), to validate data after decompression, to validate that Flash memory contents have not been changed, and for other cases where the data needs to be validated. A CRC is preferred over a simple checksum (e.g. XOR all bits) because it catches changes more readily. See the *Stellaris® ROM User's Guide* for more information on CRC.

#### 6.2.3 Flash Memory

At system clock speeds of 50 MHz and below, the Flash memory is read in a single cycle. The Flash memory is organized as a set of 1-KB blocks that can be individually erased. An individual 32-bit word can be programmed to change bits from 1 to 0. In addition, a write buffer provides the ability to concurrently program 32 continuous words in Flash memory. Erasing a block causes the entire contents of the block to be reset to all 1s. The 1-KB blocks are paired into sets of 2-KB blocks that can be individually protected. The protection allows blocks to be marked as read-only or execute-only, providing different levels of code protection. Read-only blocks cannot be erased or programmed, protecting the contents of those blocks from being modified. Execute-only blocks cannot be erased or programmed and can only be read by the controller instruction fetch mechanism, protecting the contents of those blocks from being read by either the controller or by a debugger.

Caution – The Stellaris Flash memory array has ECC which uses a test port into the Flash memory to continually scan the array for ECC errors and to correct any that are detected. This operation is transparent to the microcontroller. The BIST must scan the entire memory array occasionally to ensure integrity, taking about five minutes to do so. In systems where the microcontroller is frequently powered for less than five minutes, power should be removed from the microcontroller in a controlled manner to ensure proper operation. Software can request permission to power down the part using the USDREQ bit in the Flash Control (FCTL) register and wait to receive an acknowledge from the USDACK bit prior to removing power. If the microcontroller is powered down using this controlled method, the BIST engine keeps track of where it was in the memory array and it always scans the complete array after any aggregate of five minutes powered-on, regardless of the number of intervening power cycles. If the microcontroller is powered down before five minutes of being powered up, BIST starts again from wherever it left off before the last controlled power-down or from 0 if there never was a controlled power down. An occasional short power down is not a concern, but the microcontroller should not always be powered down frequently in an uncontrolled manner. The microcontroller can be power-cycled as frequently as necessary if it is powered-down in a controlled manner.

#### 6.2.3.1 Prefetch Buffer

The Flash memory controller has a prefetch buffer that is automatically used when the CPU frequency is greater than 50 MHz. In this mode, the Flash memory operates at half of the system clock. The prefetch buffer fetches two 32-bit words per clock allowing instructions to be fetched with no wait states while code is executing linearly. The fetch buffer includes a branch speculation mechanism that recognizes a branch and avoids extra wait states by not reading the next word pair. Also, short loop branches often stay in the buffer. As a result, some branches can be executed with no wait states. Other branches incur a single wait state.

#### 6.2.3.2 Flash Memory Protection

The user is provided two forms of Flash memory protection per 2-KB Flash memory block in eight pairs of 32-bit wide registers. The policy for each protection form is controlled by individual bits (per policy per block) in the **FMPPEn** and **FMPREn** registers.

- Flash Memory Protection Program Enable (FMPPEn): If a bit is set, the corresponding block may be programmed (written) or erased. If a bit is cleared, the corresponding block may not be changed.
- Flash Memory Protection Read Enable (FMPREn): If a bit is set, the corresponding block may be executed or read by software or debuggers. If a bit is cleared, the corresponding block may only be executed, and contents of the memory block are prohibited from being read as data.

The policies may be combined as shown in Table 6-1 on page 304.

**Table 6-1. Flash Memory Protection Policy Combinations** 

FMPPEn	FMPREn	Protection
0	0	Execute-only protection. The block may only be executed and may not be written or erased. This mode is used to protect code.
1	0	The block may be written, erased or executed, but not read. This combination is unlikely to be used.
0	1	Read-only protection. The block may be read or executed but may not be written or erased. This mode is used to lock the block from further modification while allowing any read or execute access.
1	1	No protection. The block may be written, erased, executed or read.

A Flash memory access that attempts to read a read-protected block (**FMPREn** bit is set) is prohibited and generates a bus fault. A Flash memory access that attempts to program or erase a program-protected block (**FMPPEn** bit is set) is prohibited and can optionally generate an interrupt (by setting the AMASK bit in the **Flash Controller Interrupt Mask (FCIM)** register) to alert software developers of poorly behaving software during the development and debug phases. Note that if a **FMPREn** bit is cleared, all read accesses to the Flash memory block are disallowed, including any data accesses. Care must be taken not to store required data in a Flash memory block that has the associated **FMPREn** bit cleared.

The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. These settings create a policy of open access and programmability. The register bits may be changed by clearing the specific register bit. The changes are effective immediately, but are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing any type of reset sequence. The changes are committed using the **Flash Memory Control (FMC)** register. Details on programming these bits are discussed in "Non-Volatile Register Programming" on page 307.

#### 6.2.3.3 Interrupts

The Flash memory controller can generate interrupts when the following conditions are observed:

- Programming Interrupt signals when a program or erase action is complete.
- Access Interrupt signals when a program or erase action has been attempted on a 2-kB block of memory that is protected by its corresponding FMPPEn bit.

The interrupt events that can trigger a controller-level interrupt are defined in the **Flash Controller Masked Interrupt Status (FCMIS)** register (see page 317) by setting the corresponding MASK bits. If interrupts are not used, the raw interrupt status is always visible via the **Flash Controller Raw Interrupt Status (FCRIS)** register (see page 316).

Interrupts are always cleared (for both the FCMIS and FCRIS registers) by writing a 1 to the corresponding bit in the Flash Controller Masked Interrupt Status and Clear (FCMISC) register (see page 318).

#### 6.2.3.4 Flash Memory Programming

The Stellaris devices provide a user-friendly interface for Flash memory programming. All erase/program operations are handled via three registers: **Flash Memory Address (FMA)**, **Flash Memory Data (FMD)**, and **Flash Memory Control (FMC)**. Note that if the debug capabilities of the microcontroller have been deactivated, resulting in a "locked" state, a recovery sequence must be performed in order to reactivate the debug module. See "Recovering a "Locked" Microcontroller" on page 186.

During a Flash memory operation (write, page erase, or mass erase) access to the Flash memory is inhibited. As a result, instruction and literal fetches are held off until the Flash memory operation is complete. If instruction execution is required during a Flash memory operation, the code that is executing must be placed in SRAM and executed from there while the flash operation is in progress.

Caution – The Flash memory is divided into sectors of electrically separated address ranges of 4 KB each, aligned on 4 KB boundaries. Erase/program operations on a 1-KB page have an electrical effect on the other three 1-KB pages within the sector. A specific 1-KB page must be erased after 6 total erase/program cycles occur to the other pages within its 4-KB sector. The following sequence of operations on a 4-KB sector of Flash memory (Page 0..3) provides an example:

- Page 3 is erase and programmed with values.
- Page 0, Page 1, and Page 2 are erased and then programmed with values. At this point Page 3 has been affected by 3 erase/program cycles.
- Page 0, Page 1, and Page 2 are again erased and then programmed with values. At this point Page 3 has been affected by 6 erase/program cycles.
- If the contents of Page 3 must continue to be valid, Page 3 must be erased and reprogrammed before any other page in this sector has another erase or program operation.

#### To program a 32-bit word

- 1. Write source data to the **FMD** register.
- 2. Write the target address to the **FMA** register.
- Write the Flash memory write key and the WRITE bit (a value of 0xA442.0001) to the FMC register.
- 4. Poll the FMC register until the WRITE bit is cleared.

**Important:** To ensure proper operation, two writes to the same word must be separated by an ERASE. The following two sequences are allowed:

- ERASE -> PROGRAM value -> PROGRAM 0x0000.0000
- ERASE -> PROGRAM value -> ERASE

The following sequence is NOT allowed:

■ ERASE -> PROGRAM value -> PROGRAM value

#### To perform an erase of a 1-KB page

- 1. Write the page address to the **FMA** register.
- Write the Flash memory write key and the ERASE bit (a value of 0xA442.0002) to the FMC register.
- 3. Poll the FMC register until the ERASE bit is cleared or, alternatively, enable the programming interrupt using the PMASK bit in the FCIM register.

#### To perform a mass erase of the Flash memory

Write the Flash memory write key and the MERASE bit (a value of 0xA442.0004) to the FMC register.

2. Poll the FMC register until the MERASE bit is cleared or, alternatively, enable the programming interrupt using the PMASK bit in the FCIM register.

#### 6.2.3.5 32-Word Flash Memory Write Buffer

A 32-word write buffer provides the capability to perform faster write accesses to the Flash memory by concurrently programing 32 words with a single buffered Flash memory write operation. The buffered Flash memory write operation takes the same amount of time as the single word write operation controlled by bit 0 in the **FMC** register. The data for the buffered write is written to the **Flash Write Buffer (FWBn)** registers.

The registers are 32-word aligned with Flash memory, and therefore the register **FWB0** corresponds with the address in **FMA** where bits [6:0] of **FMA** are all 0. **FWB1** corresponds with the address in **FMA** + 0x4 and so on. Only the **FWBn** registers that have been updated since the previous buffered Flash memory write operation are written. The **Flash Write Buffer Valid (FWBVAL)** register shows which registers have been written since the last buffered Flash memory write operation. This register contains a bit for each of the 32 **FWBn** registers, where bit[n] of **FWBVAL** corresponds to **FWBn**. The **FWBn** register has been updated if the corresponding bit in the **FWBVAL** register is set.

#### To program 32 words with a single buffered Flash memory write operation

- 1. Write the source data to the **FWBn** registers.
- 2. Write the target address to the **FMA** register. This must be a 32-word aligned address (that is, bits [6:0] in **FMA** must be 0s).
- 3. Write the Flash memory write key and the WRBUF bit (a value of 0xA442.0001) to the **FMC2** register.
- 4. Poll the FMC2 register until the WRBUF bit is cleared or wait for the PMIS interrupt to be signaled.

#### 6.2.3.6 Non-Volatile Register Programming

This section discusses how to update the registers shown in Table 6-2 on page 308 that are resident within the Flash memory itself. These registers exist in a separate space from the main Flash memory array and are not affected by an ERASE or MASS ERASE operation. With the exception of the **Boot Configuration (BOOTCFG)** register, the settings in these registers can be written, their functions verified, and their values read back before they are committed, at which point they become non-volatile. If a value in one of these registers has not been committed, any type of reset restores the last committed value or the default value if the register has never been committed. Once the register contents are committed, the only way to restore the factory default values is to perform the sequence described in "Recovering a "Locked" Microcontroller" on page 186.

To write to a non-volatile register:

- Bits can only be changed from 1 to 0.
- For all registers except the **BOOTCFG** register, write the data to the register address provided in the register description. For the **BOOTCFG** register, write the data to the **FMD** register.
- The registers can be read to verify their contents. To verify what is to be stored in the **BOOTCFG** register, read the **FMD** register. Reading the **BOOTCFG** register returns the previously committed value or the default value if the register has never been committed.
- The new values are effectively immediately for all registers except BOOTCFG, as the new value for the register is not stored in the register until it has been committed.

■ Prior to committing the register value, any type of reset restores the last committed value or the default value if the register has never been committed.

To commit a new value to a non-volatile register:

- Write the data as described above.
- Write to the **FMA** register the value shown in Table 6-2 on page 308.
- Write the Flash memory write key and set the COMT bit in the **FMC** register. These values must be written to the **FMC** register at the same time.
- Committing a non-volatile register has the same timing as a write to regular Flash memory, defined by T<sub>PROG</sub>, as shown in Table 26-16 on page 1325. Software can poll the COMT bit in the **FMC** register to determine when the operation is complete, or an interrupt can be enabled by setting the PMASK bit in the **FCIM** register.
- When committing the **BOOTCFG** register, the INVDRIS bit in the **FCRIS** register is set if a bit that has already been committed as a 0 is attempted to be committed as a 1.
- Once the value has been committed, any type of reset has no effect on the register contents.
- Changes to the BOOTCFG register are effective after the next reset.
- The NW bit in the USER\_REG0, USER\_REG1, USER\_REG2, USER\_REG3, and BOOTCFG registers is cleared when the register is committed. Once this bit is cleared, additional changes to the register are not allowed.

**Important:** After being committed, these registers can only be restored to their factory default values by performing the sequence described in "Recovering a "Locked" Microcontroller" on page 186. The mass erase of the main Flash memory array caused by the sequence is performed prior to restoring these registers.

Table 6-2. User-Programmable Flash Memory Resident Registers

Register to be Committed	FMA Value	Data Source
FMPRE0	0x0000.0000	FMPRE0
FMPRE1	0x0000.0002	FMPRE1
FMPRE2	0x0000.0004	FMPRE2
FMPRE3	0x0000.0006	FMPRE3
FMPRE4	0x0000.0008	FMPRE4
FMPRE5	0x0000.000A	FMPRE5
FMPRE6	0x0000.000C	FMPRE6
FMPRE7	0x0000.000E	FMPRE7
FMPPE0	0x0000.0001	FMPPE0
FMPPE1	0x0000.0003	FMPPE1
FMPPE2	0x0000.0005	FMPPE2
FMPPE3	0x0000.0007	FMPPE3
FMPRE4	0x0000.0009	FMPRE4
FMPRE5	0x0000.000B	FMPRE5
FMPRE6	0x0000.000D	FMPRE6

Table 6-2. User-Programmable Flash Memory Resident Registers (continued)

Register to be Committed	FMA Value	Data Source
FMPRE7	0x0000.000F	FMPRE7
USER_REG0	0x8000.0000	USER_REG0
USER_REG1	0x8000.0001	USER_REG1
USER_REG2	0x8000.0002	USER_REG2
USER_REG3	0x8000.0003	USER_REG3
BOOTCFG	0x7510.0000	FMD

### 6.3 Register Map

Table 6-3 on page 309 lists the ROM Controller register and the Flash memory and control registers. The offset listed is a hexadecimal increment to the register's address. The Flash memory register offsets are relative to the Flash memory control base address of 0x400F.D000. The ROM and Flash memory protection register offsets are relative to the System Control base address of 0x400F.E000.

Table 6-3. Flash Register Map

Offset	Name	Туре	Reset	Description	See page
Flash Me	mory Registers (Flash C	ontrol Offs	et)	,	
0x000	FMA	R/W	0x0000.0000	Flash Memory Address	311
0x004	FMD	R/W	0x0000.0000	Flash Memory Data	312
0x008	FMC	R/W	0x0000.0000	Flash Memory Control	313
0x00C	FCRIS	RO	0x0000.0000	Flash Controller Raw Interrupt Status	316
0x010	FCIM	R/W	0x0000.0000	Flash Controller Interrupt Mask	317
0x014	FCMISC	R/W1C	0x0000.0000	Flash Controller Masked Interrupt Status and Clear	318
0x020	FMC2	R/W	0x0000.0000	Flash Memory Control 2	319
0x030	FWBVAL	R/W	0x0000.0000	Flash Write Buffer Valid	320
0x0F8	FCTL	R/W	0x0000.0000	Flash Control	321
0x100 - 0x17C	FWBn	R/W	0x0000.0000	Flash Write Buffer n	322
Memory I	Registers (System Contr	ol Offset)			
0x0F0	RMCTL	R/W1C	-	ROM Control	323
0x130	FMPRE0	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 0	324
0x200	FMPRE0	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 0	324
0x134	FMPPE0	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 0	325
0x400	FMPPE0	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 0	325
0x1D0	BOOTCFG	R/W	0xFFFF.FFFE	Boot Configuration	326
0x1E0	USER_REG0	R/W	0xFFFF.FFFF	User Register 0	328
0x1E4	USER_REG1	R/W	0xFFFF.FFFF	User Register 1	329

Table 6-3. Flash Register Map (continued)

Offset	Name	Type	Reset	Description	See page
0x1E8	USER_REG2	R/W	0xFFFF.FFFF	User Register 2	330
0x1EC	USER_REG3	R/W	0xFFFF.FFFF	User Register 3	331
0x204	FMPRE1	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 1	332
0x208	FMPRE2	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 2	333
0x20C	FMPRE3	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 3	334
0x210	FMPRE4	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 4	335
0x214	FMPRE5	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 5	336
0x218	FMPRE6	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 6	337
0x21C	FMPRE7	R/W	0xFFFF.FFFF	Flash Memory Protection Read Enable 7	338
0x404	FMPPE1	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 1	339
0x408	FMPPE2	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 2	340
0x40C	FMPPE3	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 3	341
0x410	FMPPE4	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 4	342
0x414	FMPPE5	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 5	343
0x418	FMPPE6	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 6	344
0x41C	FMPPE7	R/W	0xFFFF.FFFF	Flash Memory Protection Program Enable 7	345

### 6.4 Flash Memory Register Descriptions (Flash Control Offset)

This section lists and describes the Flash Memory registers, in numerical order by address offset. Registers in this section are relative to the Flash control base address of 0x400F.D000.


### Register 1: Flash Memory Address (FMA), offset 0x000

During a write operation, this register contains a 4-byte-aligned address and specifies where the data is written. During erase operations, this register contains a 1 KB-aligned CPU byte address and specifies which block is erased. Note that the alignment requirements must be met by software or the results of the operation are unpredictable.

Flash Memory Address (FMA)

Base 0x400F.D000

Offset 0x000 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:19	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
18:0	OFFSET	R/W	0x0	Address Offset

Address offset in Flash memory where operation is performed, except for non-volatile registers (see "Non-Volatile Register Programming" on page 307 for details on values for this field).


### Register 2: Flash Memory Data (FMD), offset 0x004

This register contains the data to be written during the programming cycle or read during the read cycle. Note that the contents of this register are undefined for a read access of an execute-only block. This register is not used during erase cycles.

#### Flash Memory Data (FMD)

Base 0x400F.D000

Offset 0x004 Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset Description
31:0 DATA R/W 0x0000.0000 Data Value

Data value for write operation.

### Register 3: Flash Memory Control (FMC), offset 0x008

When this register is written, the Flash memory controller initiates the appropriate access cycle for the location specified by the **Flash Memory Address (FMA)** register (see page 311). If the access is a write access, the data contained in the **Flash Memory Data (FMD)** register (see page 312) is written to the specified address.

This register must be the final register written and initiates the memory operation. The four control bits in the lower byte of this register are used to initiate memory operations.


Care must be taken not to set multiple control bits as the results of such an operation are unpredictable.

Caution – If any of bits [15:4] are written to 1, the device may become inoperable. These bits should always be written to 0. In all registers, the value of a reserved bit should be preserved across a read-modify-write operation.

#### Flash Memory Control (FMC)

Base 0x400F.D000 Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	WRKEY	WO	0x0000	Flash Memory Write Key
				This field contains a write key, which is used to minimize the incidence of accidental Flash memory writes. The value 0xA442 must be written into this field for a Flash memory write to occur. Writes to the <b>FMC</b> register without this WRKEY value are ignored. A read of this field returns the value 0.
15:4	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
3	COMT	R/W	0	Commit Register Value
				This bit is used to commit writes to Flash-memory-resident registers and to monitor the progress of that process.
				Value Description
				Set this bit to commit (write) the register value to a Flash-memory-resident register.
				When read, a 1 indicates that the previous commit access is not complete.
				0 A write of 0 has no effect on the state of this bit.
				When read, a 0 indicates that the previous commit access is complete.
				See "Non-Volatile Register Programming" on page 307 for more information on programming Flash-memory-resident registers.
2	MERASE	R/W	0	Mass Erase Flash Memory
				This bit is used to mass erase the Flash main memory and to monitor the progress of that process.
				Value Description
				1 Set this bit to erase the Flash main memory.
				When read, a 1 indicates that the previous mass erase access is not complete.
				0 A write of 0 has no effect on the state of this bit.
				When read, a 0 indicates that the previous mass erase access is complete.
				For information on erase time, see "Flash Memory" on page 1325.
1	ERASE	R/W	0	Erase a Page of Flash Memory
				This bit is used to erase a page of Flash memory and to monitor the progress of that process.
				Value Description
				Set this bit to erase the Flash memory page specified by the contents of the FMA register.
				When read, a 1 indicates that the previous page erase access is not complete.
				0 A write of 0 has no effect on the state of this bit.
				When read, a 0 indicates that the previous page erase access is complete.
				For information on erase time, see "Flash Memory" on page 1325.

Bit/Field	Name	Туре	Reset	Description
0	WRITE	R/W	0	Write a Word into Flash Memory
				This bit is used to write a word into Flash memory and to monitor the progress of that process.
				Value Description
				Set this bit to write the data stored in the FMD register into the Flash memory location specified by the contents of the FMA register.
				When read, a 1 indicates that the write update access is not complete.
				0 A write of 0 has no effect on the state of this bit.
				When read, a 0 indicates that the previous write update access is complete.
				For information on programming time, see "Flash Memory" on page 1325.


### Register 4: Flash Controller Raw Interrupt Status (FCRIS), offset 0x00C

This register indicates that the Flash memory controller has an interrupt condition. An interrupt is sent to the interrupt controller only if the corresponding **FCIM** register bit is set.

Flash Controller Raw Interrupt Status (FCRIS)

Base 0x400F.D000

Offset 0x00C Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	PRIS	RO	0	Programming Raw Interrupt Status  This bit provides status on programming cycles which are write or erase actions generated through the <b>FMC</b> or <b>FMC2</b> register bits (see page 313 and page 319).

#### Value Description

- 1 The programming or erase cycle has completed.
- 0 The programming or erase cycle has not completed.

This status is sent to the interrupt controller when the PMASK bit in the FCIM register is set.

This bit is cleared by writing a 1 to the PMISC bit in the FCMISC register.

0 **ARIS** RO Access Raw Interrupt Status 0

#### Value Description

- A program or erase action was attempted on a block of Flash memory that contradicts the protection policy for that block as set in the FMPPEn registers.
- 0 No access has tried to improperly program or erase the Flash

This status is sent to the interrupt controller when the AMASK bit in the FCIM register is set.

This bit is cleared by writing a 1 to the AMISC bit in the FCMISC register.


### Register 5: Flash Controller Interrupt Mask (FCIM), offset 0x010

This register controls whether the Flash memory controller generates interrupts to the controller.

Flash Controller Interrupt Mask (FCIM)

Base 0x400F.D000 Offset 0x010

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	PMASK	R/W	0	Programming Interrupt Mask
				This bit controls the reporting of the programming raw interrupt status to the interrupt controller.
				Value Description
				1 An interrupt is sent to the interrupt controller when the PRIS bit is set.
				O The PRIS interrupt is suppressed and not sent to the interrupt controller.
0	AMASK	R/W	0	Access Interrupt Mask

This bit controls the reporting of the access raw interrupt status to the interrupt controller.

#### Value Description

- An interrupt is sent to the interrupt controller when the ARIS bit
- 0 The ARIS interrupt is suppressed and not sent to the interrupt controller.


### Register 6: Flash Controller Masked Interrupt Status and Clear (FCMISC), offset 0x014

This register provides two functions. First, it reports the cause of an interrupt by indicating which interrupt source or sources are signalling the interrupt. Second, it serves as the method to clear the interrupt reporting.

Flash Controller Masked Interrupt Status and Clear (FCMISC)

Base 0x400F.D000

Offset 0x014
Type R/W1C, reset 0x0000.0000



2.0		.,,,,		2000.191.011
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	PMISC	R/W1C	0	Programming Masked Interrupt Status and Clear

#### Value Description

- 1 When read, a 1 indicates that an unmasked interrupt was signaled because a programming cycle completed.
  - Writing a 1 to this bit clears PMISC and also the PRIS bit in the FCRIS register (see page 316).
- When read, a 0 indicates that a programming cycle complete 0 interrupt has not occurred.

A write of 0 has no effect on the state of this bit.

0	AMISC	R/W1C	0	Access Masked Interrupt Status and Clear
---	-------	-------	---	--

#### Value Description

- When read, a 1 indicates that an unmasked interrupt was signaled because a program or erase action was attempted on a block of Flash memory that contradicts the protection policy for that block as set in the FMPPEn registers.
  - Writing a 1 to this bit clears AMISC and also the ARIS bit in the FCRIS register (see page 316).
- When read, a 0 indicates that no improper accesses have 0 occurred.

A write of 0 has no effect on the state of this bit.

### Register 7: Flash Memory Control 2 (FMC2), offset 0x020

When this register is written, the Flash memory controller initiates the appropriate access cycle for the location specified by the **Flash Memory Address (FMA)** register (see page 311). If the access is a write access, the data contained in the **Flash Write Buffer (FWB)** registers is written.

This register must be the final register written as it initiates the memory operation.

#### Flash Memory Control 2 (FMC2)

Name


Type

Reset

Base 0x400F.D000 Offset 0x020

Bit/Field

Type R/W, reset 0x0000.0000



				•
31:16	WRKEY	WO	0x0000	Flash Memory Write Key
				This field contains a write key, which is used to minimize the incidence of accidental Flash memory writes. The value 0xA442 must be written into this field for a write to occur. Writes to the <b>FMC2</b> register without this WRKEY value are ignored. A read of this field returns the value 0.
15:1	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	WRBUF	R/W	0	Buffered Flash Memory Write

Description

#### Value Description

Set this bit to write the data stored in the FWBn registers to the location specified by the contents of the FMA register.
 When read, a 1 indicates that the previous buffered Flash memory write access is not complete.

This bit is used to start a buffered write to Flash memory.

O A write of 0 has no effect on the state of this bit.
When read, a 0 indicates that the previous buffered Flash memory write access is complete.

For information on programming time, see "Flash Memory" on page 1325.

### Register 8: Flash Write Buffer Valid (FWBVAL), offset 0x030


This register provides a bitwise status of which **FWBn** registers have been written by the processor since the last write of the Flash memory write buffer. The entries with a 1 are written on the next write of the Flash memory write buffer. This register is cleared after the write operation by hardware. A protection violation on the write operation also clears this status.

Software can program the same 32 words to various Flash memory locations by setting the FWB[n] bits after they are cleared by the write operation. The next write operation then uses the same data as the previous one. In addition, if a **FWBn** register change should not be written to Flash memory, software can clear the corresponding FWB[n] bit to preserve the existing data when the next write operation occurs.

Flash Write Buffer Valid (FWBVAL)

Base 0x400F.D000 Offset 0x030

Type R/W, reset 0x0000.0000



#### Value Description

- The corresponding FWBn register has been updated since the last buffer write operation and is ready to be written to Flash memory.
- The corresponding **FWBn** register has no new data to be written.

Bit 0 corresponds to **FWB0**, offset 0x100, and bit 31 corresponds to **FWB31**, offset 0x13C.


#### Register 9: Flash Control (FCTL), offset 0x0F8

This register is used to ensure that the microcontroller is powered down in a controlled fashion in systems where power is cycled more frequently than once every five minutes. The USDREQ bit should be set to indicate that power is going to be turned off. Software should poll the USDACK bit to determine when it is acceptable to power down.

Flash Control (FCTL)

Base 0x400F.D000

Offset 0x0F8
Type R/W, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description	
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.	
1	USDACK	RO	0	User Shut Down Acknowledge	
				Value Description  The microcontroller can be powered down.  The microcontroller cannot yet be powered down.	
				This bit should be set within 50 ms of setting the USDREQ bit.	
0	USDREQ	R/W	0	User Shut Down Request	
				Value Description	

Value Description

- 1 Requests permission to power down the microcontroller.
- 0 No effect.

### Register 10: Flash Write Buffer n (FWBn), offset 0x100 - 0x17C

These 32 registers hold the contents of the data to be written into the Flash memory on a buffered Flash memory write operation. The offset selects one of the 32-bit registers. Only **FWBn** registers that have been updated since the preceding buffered Flash memory write operation are written into the Flash memory, so it is not necessary to write the entire bank of registers in order to write 1 or 2 words. The **FWBn** registers are written into the Flash memory with the **FWB0** register corresponding to the address contained in **FMA**. **FWB1** is written to the address **FMA**+0x4 etc. Note that only data bits that are 0 result in the Flash memory being modified. A data bit that is 1 leaves the content of the Flash memory bit at its previous value.



### 6.5 Memory Register Descriptions (System Control Offset)

The remainder of this section lists and describes the registers that reside in the System Control address space, in numerical order by address offset. Registers in this section are relative to the System Control base address of 0x400F.E000.

#### Register 11: ROM Control (RMCTL), offset 0x0F0


This register provides control of the ROM controller state. This register offset is relative to the System Control base address of 0x400F.E000.

At reset, the ROM is mapped over the Flash memory so that the ROM boot sequence is always executed. The boot sequence executed from ROM is as follows:

- 1. The BA bit (below) is cleared such that ROM is mapped to 0x01xx.xxxx and Flash memory is mapped to address 0x0.
- 2. The **BOOTCFG** register is read. If the EN bit is clear, the status of the specified GPIO pin is compared with the specified polarity. If the status matches the specified polarity, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- 3. If the status doesn't match the specified polarity, the data at address 0x0000.0004 is read, and if the data at this address is 0xFFFF.FFFF, the ROM is mapped to address 0x0000.0000 and execution continues out of the ROM Boot Loader.
- **4.** If there is data at address 0x0000.0004 that is not 0xFFF.FFFF, the stack pointer (**SP**) is loaded from Flash memory at address 0x0000.0000 and the program counter (**PC**) is loaded from address 0x0000.0004. The user application begins executing.

#### ROM Control (RMCTL)

Base 0x400F.E000 Offset 0x0F0 Type R/W1C, reset -



Bit/Field	Name	Туре	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ВА	R/W1C	1	Boot Alias

Value Description

- 1 The microcontroller's ROM appears at address 0x0.
- 0 The Flash memory is at address 0x0.

This bit is cleared by writing a 1 to this bit position.

# Register 12: Flash Memory Protection Read Enable 0 (FMPRE0), offset 0x130 and 0x200


Note: This register is aliased for backwards compatability.

**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. For additional information, see "Flash Memory Protection" on page 304.

#### Flash Memory Protection Read Enable 0 (FMPRE0)

Base 0x400F.E000 Offset 0x130 and 0x200 Type R/W, reset 0xFFF.FFFF



Bit/Field	Name	Type	Reset	Description
31:0	READ ENABLE	R/W	0xFFFFFFF	Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory up to the total of 64 KB.

# Register 13: Flash Memory Protection Program Enable 0 (FMPPE0), offset 0x134 and 0x400


**Note:** This register is aliased for backwards compatability.

**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 0 (FMPPE0)

Base 0x400F.E000 Offset 0x134 and 0x400 Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory up to the total of 64 KB.

## Register 14: Boot Configuration (BOOTCFG), offset 0x1D0

**Note:** Offset is relative to System Control base address of 0x400FE000.

This register provides configuration of a GPIO pin to enable the ROM Boot Loader as well as a write-once mechanism to disable external debugger access to the device. Upon reset, the user has the opportunity to direct the core to execute the ROM Boot Loader or the application in Flash memory by using any GPIO signal from Ports A-H as configured by the bits in this register. If the EN bit is set or the specified pin does not have the required polarity, the system control module checks address 0x000.0004 to see if the Flash memory has a valid reset vector. If the data at address 0x0000.0004 is 0xFFFF.FFFF, then it is assumed that the Flash memory has not yet been programmed, and the core executes the ROM Boot Loader. The DBG0 bit (bit 0) is set to 0 from the factory and the DBG1 bit (bit 1) is set to 1, which enables external debuggers. Clearing the DBG1 bit disables any external debugger access to the device permanently, starting with the next power-up cycle of the device. The NW bit (bit 31) indicates that the register has not yet been committed and is controlled through hardware to ensure that the register is only committed once. Prior to being committed, bits can only be changed from 1 to 0. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186.

### Boot Configuration (BOOTCFG)

Name

Type

Base 0x400F.E000 Offset 0x1D0

Bit/Field

Type R/W, reset 0xFFFF.FFFE

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
ſ	NW			1	1	1	1	1	reserved				1		1	
Type	R/W	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		PORT			PIN	1	POL	EN			rese	rved	1		DBG1	DBG0
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO	RO	RO	RO	RO	RO	R/W	R/W
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0

		,,		'
31	NW	R/W	1	Not Written
				When set, this bit indicates that this 32-bit register has not been committed. When clear, this bit specifies that this register has been committed and may not be committed again.
30:16	reserved	RO	0x7FFF	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

Reset

Description

preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
15:13	PORT	R/W	0x7	Boot GPIO Port This field selects the port of the GPIO port pin that enables the ROM boot loader at reset.
				Value Description
				0x0 Port A
				0x1 Port B
				0x2 Port C
				0x3 Port D
				0x4 Port E
				0x5 Port F
				0x6 Port G
				0x7 Port H
12:10	PIN	R/W	0x7	Boot GPIO Pin
				This field selects the pin number of the GPIO port pin that enables the ROM boot loader at reset.
				Value Description
				0x0 Pin 0
				0x1 Pin 1
				0x2 Pin 2
				0x3 Pin 3
				0x4 Pin 4
				0x5 Pin 5
				0x6 Pin 6
				0x7 Pin 7
9	POL	R/W	0x1	Boot GPIO Polarity
				When set, this bit selects a high level for the GPIO port pin to enable the ROM boot loader at reset. When clear, this bit selects a low level for the GPIO port pin.
8	EN	R/W	0x1	Boot GPIO Enable
				Clearing this bit enables the use of a GPIO pin to enable the ROM Boot Loader at reset. When this bit is set, the contents of address 0x0000.0004 are checked to see if the Flash memory has been programmed. If the contents are not 0xFFF.FFFF, the core executes out of Flash memory. If the Flash has not been programmed, the core executes out of ROM.
7:2	reserved	RO	0x3F	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	DBG1	R/W	1	Debug Control 1  The DBG1 bit must be 1 and DBG0 must be 0 for debug to be available.
0	DBG0	R/W	0x0	Debug Control 0 The DBG1 bit must be 1 and DBG0 must be 0 for debug to be available.

# Register 15: User Register 0 (USER\_REG0), offset 0x1E0


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register provides 31 bits of user-defined data that is non-volatile and can only be committed once. Bit 31 indicates that the register is available to be committed and is controlled through hardware to ensure that the register is only committed once. Prior to being committed, bits can only be changed from 1 to 0. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. The write-once characteristics of this register are useful for keeping static information like communication addresses that need to be unique per part and would otherwise require an external EEPROM or other non-volatile device. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186.

### User Register 0 (USER\_REG0)

Base 0x400F.E000 Offset 0x1E0

Type R/W, reset 0xFFFF.FFF



Bit/Field	Name	Туре	Reset	Description
31	NW	R/W	1	Not Written
				When set, this bit indicates that this 32-bit register has not been committed. When clear, this bit specifies that this register has been committed and may not be committed again.
30:0	DATA	R/W 0x	7FFFFFFF	User Data

Contains the user data value. This field is initialized to all 1s and can only be committed once.

# Register 16: User Register 1 (USER\_REG1), offset 0x1E4


Note: Offset is relative to System Control base address of 0x400FE000.

This register provides 31 bits of user-defined data that is non-volatile and can only be written once. Bit 31 indicates that the register is available to be written and is controlled through hardware to ensure that the register is only written once. The write-once characteristics of this register are useful for keeping static information like communication addresses that need to be unique per part and would otherwise require an external EEPROM or other non-volatile device.

User Register 1 (USER\_REG1)

Base 0x400F.E000 Offset 0x1E4

Type R/W, reset 0xFFFF.FFF



Bit/Field	Name	Туре	Reset	Description
31	NW	R/W	1	Not Written When set, this bit indicates that this 32-bit register has not been
				committed. When clear, this bit specifies that this register has been committed and may not be committed again.
30:0	DATA	R/W 0x	7FFFFFF	User Data

Contains the user data value. This field is initialized to all 1s and can only be committed once.

# Register 17: User Register 2 (USER\_REG2), offset 0x1E8


Note: Offset is relative to System Control base address of 0x400FE000.

This register provides 31 bits of user-defined data that is non-volatile and can only be written once. Bit 31 indicates that the register is available to be written and is controlled through hardware to ensure that the register is only written once. The write-once characteristics of this register are useful for keeping static information like communication addresses that need to be unique per part and would otherwise require an external EEPROM or other non-volatile device.

User Register 2 (USER\_REG2)

Base 0x400F.E000 Offset 0x1E8

Type R/W, reset 0xFFFF.FFFF



Bit/Field	Name	Туре	Reset	Description
31	NW	R/W	1	Not Written
				When set, this bit indicates that this 32-bit register has not been committed. When clear, this bit specifies that this register has been committed and may not be committed again.
30:0	DATA	R/W 0	x7FFFFFF	User Data

Contains the user data value. This field is initialized to all 1s and can only be committed once.

### Register 18: User Register 3 (USER REG3), offset 0x1EC


Note: Offset is relative to System Control base address of 0x400FE000.

This register provides 31 bits of user-defined data that is non-volatile and can only be written once. Bit 31 indicates that the register is available to be written and is controlled through hardware to ensure that the register is only written once. The write-once characteristics of this register are useful for keeping static information like communication addresses that need to be unique per part and would otherwise require an external EEPROM or other non-volatile device.

User Register 3 (USER\_REG3)

Base 0x400F.E000 Offset 0x1EC

Type R/W, reset 0xFFFF.FFFF



Bit/Field	Name	Туре	Reset	Description
31	NW	R/W	1	Not Written When set, this bit indicates that this 32-bit register has not been
				committed. When clear, this bit specifies that this register has been committed and may not be committed again.
30:0	DATA	R/W 0x	7FFFFFF	User Data

Contains the user data value. This field is initialized to all 1s and can only be committed once.

## Register 19: Flash Memory Protection Read Enable 1 (FMPRE1), offset 0x204


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 64 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 1 (FMPRE1)

Base 0x400F.E000 Offset 0x204

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in memory range from 65 to 128 KB.

### Register 20: Flash Memory Protection Read Enable 2 (FMPRE2), offset 0x208


Note: Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 128 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 2 (FMPRE2)

Base 0x400F.E000 Offset 0x208

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 129 to 192 KB.

# Register 21: Flash Memory Protection Read Enable 3 (FMPRE3), offset 0x20C


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 3 (FMPRE3)

Base 0x400F.E000 Offset 0x20C

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 193 to 256 KB.

## Register 22: Flash Memory Protection Read Enable 4 (FMPRE4), offset 0x210


Note: Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 4 (FMPRE4)

Base 0x400F.E000 Offset 0x210

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 257 to 320 KB.

## Register 23: Flash Memory Protection Read Enable 5 (FMPRE5), offset 0x214


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 5 (FMPRE5)

Base 0x400F.E000 Offset 0x214

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 321 to 384 KB.

## Register 24: Flash Memory Protection Read Enable 6 (FMPRE6), offset 0x218


Note: Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 6 (FMPRE6)

Base 0x400F.E000 Offset 0x218

Type R/W, reset 0xFFF.FFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 385 to 448 KB.

# Register 25: Flash Memory Protection Read Enable 7 (FMPRE7), offset 0x21C


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the read-only protection bits for each 2-KB flash block (**FMPPEn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPREn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Read Enable 7 (FMPRE7)

Base 0x400F.E000 Offset 0x21C

Type R/W, reset 0xFFFF.FFF



Bit/Field Name Type Reset Description

31:0 READ ENABLE R/W 0xFFFFFFF Flash Read Enable

Configures 2-KB flash blocks to be read or executed only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 449 to 512 KB.

# Register 26: Flash Memory Protection Program Enable 1 (FMPPE1), offset 0x404


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 64 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 1 (FMPPE1)

Base 0x400F.E000 Offset 0x404

Type R/W, reset 0xFFFF.FFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in memory range from 65 to 128 KB.

# Register 27: Flash Memory Protection Program Enable 2 (FMPPE2), offset 0x408


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 128 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 2 (FMPPE2)

Base 0x400F.E000 Offset 0x408

Type R/W, reset 0xFFFF.FFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 129 to 192 KB.

# Register 28: Flash Memory Protection Program Enable 3 (FMPPE3), offset 0x40C


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 3 (FMPPE3)

Base 0x400F.E000 Offset 0x40C

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 193 to 256 KB.

# Register 29: Flash Memory Protection Program Enable 4 (FMPPE4), offset 0x410


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 4 (FMPPE4)

Base 0x400F.E000 Offset 0x410

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 257 to 320 KB.

# Register 30: Flash Memory Protection Program Enable 5 (FMPPE5), offset 0x414


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 5 (FMPPE5)

Base 0x400F.E000 Offset 0x414

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 321 to 384 KB.

# Register 31: Flash Memory Protection Program Enable 6 (FMPPE6), offset 0x418

**Note:** Offset is relative to System Control base address of 0x400FE000.


This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 6 (FMPPE6)

Base 0x400F.E000

Offset 0x418

Type R/W, reset 0xFFF.FFF



Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 385 to 448 KB.


# Register 32: Flash Memory Protection Program Enable 7 (FMPPE7), offset 0x41C


**Note:** Offset is relative to System Control base address of 0x400FE000.

This register stores the execute-only protection bits for each 2-KB flash block (**FMPREn** stores the execute-only bits). Flash memory up to a total of 64 KB is controlled by this register. Other **FMPPEn** registers (if any) provide protection for other 64K blocks. This register is loaded during the power-on reset sequence. The factory settings for the **FMPREn** and **FMPPEn** registers are a value of 1 for all implemented banks. This achieves a policy of open access and programmability. The register bits may be changed by writing the specific register bit. However, this register is R/W0; the user can only change the protection bit from a 1 to a 0 (and may NOT change a 0 to a 1). The changes are not permanent until the register is committed (saved), at which point the bit change is permanent. If a bit is changed from a 1 to a 0 and not committed, it may be restored by executing a power-on reset sequence. The reset value shown only applies to power-on reset; any other type of reset does not affect this register. Once committed, the only way to restore the factory default value of this register is to perform the sequence detailed in "Recovering a "Locked" Microcontroller" on page 186. If the Flash memory size on the device is less than 192 KB, this register usually reads as zeroes, but software should not rely on these bits to be zero. For additional information, see "Flash Memory Protection" on page 304.

Flash Memory Protection Program Enable 7 (FMPPE7)

Base 0x400F.E000 Offset 0x41C





Bit/Field Name Type Reset Description

31:0 PROG\_ENABLE R/W 0xFFFFFFF Flash Programming Enable

Configures 2-KB flash blocks to be execute only. The policies may be combined as shown in Table 6-1 on page 304.

Value Description

0xFFFFFFF Bits [31:0] each enable protection on a 2-KB block of Flash memory in the range from 449 to 512 KB.

# 7 Micro Direct Memory Access (µDMA)


The LM3S9D96 microcontroller includes a Direct Memory Access (DMA) controller, known as micro-DMA ( $\mu$ DMA). The  $\mu$ DMA controller provides a way to offload data transfer tasks from the Cortex <sup>TM</sup>-M3 processor, allowing for more efficient use of the processor and the available bus bandwidth. The  $\mu$ DMA controller can perform transfers between memory and peripherals. It has dedicated channels for each supported on-chip module and can be programmed to automatically perform transfers between peripherals and memory as the peripheral is ready to transfer more data. The  $\mu$ DMA controller provides the following features:

- ARM<sup>®</sup> PrimeCell<sup>®</sup> 32-channel configurable µDMA controller
- Support for memory-to-memory, memory-to-peripheral, and peripheral-to-memory in multiple transfer modes
  - Basic for simple transfer scenarios
  - Ping-pong for continuous data flow
  - Scatter-gather for a programmable list of arbitrary transfers initiated from a single request
- Highly flexible and configurable channel operation
  - Independently configured and operated channels
  - Dedicated channels for supported on-chip modules
  - Primary and secondary channel assignments
  - One channel each for receive and transmit path for bidirectional modules
  - Dedicated channel for software-initiated transfers
  - Per-channel configurable priority scheme
  - Optional software-initiated requests for any channel
- Two levels of priority
- Design optimizations for improved bus access performance between µDMA controller and the processor core
  - µDMA controller access is subordinate to core access
  - RAM striping
  - Peripheral bus segmentation
- Data sizes of 8, 16, and 32 bits
- Transfer size is programmable in binary steps from 1 to 1024
- Source and destination address increment size of byte, half-word, word, or no increment
- Maskable peripheral requests

■ Interrupt on transfer completion, with a separate interrupt per channel

# 7.1 Block Diagram

Figure 7-1. µDMA Block Diagram



# 7.2 Functional Description

The  $\mu$ DMA controller is a flexible and highly configurable DMA controller designed to work efficiently with the microcontroller's Cortex-M3 processor core. It supports multiple data sizes and address increment schemes, multiple levels of priority among DMA channels, and several transfer modes to allow for sophisticated programmed data transfers. The  $\mu$ DMA controller's usage of the bus is always subordinate to the processor core, so it never holds up a bus transaction by the processor. Because the  $\mu$ DMA controller is only using otherwise-idle bus cycles, the data transfer bandwidth it provides is essentially free, with no impact on the rest of the system. The bus architecture has been optimized to greatly enhance the ability of the processor core and the  $\mu$ DMA controller to efficiently share the on-chip bus, thus improving performance. The optimizations include RAM striping and peripheral bus segmentation, which in many cases allow both the processor core and the  $\mu$ DMA controller to access the bus and perform simultaneous data transfers.

The  $\mu$ DMA controller can transfer data to and from the on-chip SRAM. However, because the Flash memory and ROM are located on a separate internal bus, it is not possible to transfer data from the Flash memory or ROM with the  $\mu$ DMA controller.

Each peripheral function that is supported has a dedicated channel on the  $\mu DMA$  controller that can be configured independently. The  $\mu DMA$  controller implements a unique configuration method using channel control structures that are maintained in system memory by the processor. While simple transfer modes are supported, it is also possible to build up sophisticated "task" lists in memory that allow the  $\mu DMA$  controller to perform arbitrary-sized transfers to and from arbitrary locations as part of a single transfer request. The  $\mu DMA$  controller also supports the use of ping-pong buffering to accommodate constant streaming of data to or from a peripheral.

Each channel also has a configurable arbitration size. The arbitration size is the number of items that are transferred in a burst before the  $\mu DMA$  controller rearbitrates for channel priority. Using the arbitration size, it is possible to control exactly how many items are transferred to or from a peripheral each time it makes a  $\mu DMA$  service request.

# 7.2.1 Channel Assignments

μDMA channels 0-31 are assigned to peripherals according to the following table. The **DMA Channel Assignment (DMACHASGN)** register (see page 396) can be used to specify the primary or secondary assignment. If the primary function is not available on this microcontroller, the secondary function becomes the primary function. If the secondary function is not available, the primary function is the only option.

**Note:** Channels noted in the table as "Available for software" may be assigned to peripherals in the future. However, they are currently available for software use. Channel 30 is dedicated for software use.

The USB endpoints mapped to  $\mu$ DMA channels 0-3 can be changed with the **USBDMASEL** register (see page 1120).

Because of the way the  $\mu$ DMA controller interacts with peripherals, the  $\mu$ DMA channel for the peripheral must be enabled in order for the  $\mu$ DMA controller to be able to read and write the peripheral registers, even if a different  $\mu$ DMA channel is used to perform the  $\mu$ DMA transfer. To minimize confusion and chance of software errors, it is best practice to use a peripheral's  $\mu$ DMA channel for performing all  $\mu$ DMA transfers for that peripheral, even if it is processor-triggered and using AUTO mode, which could be considered a software transfer. Note that if the software channel is used, interrupts occur on the dedicated  $\mu$ DMA interrupt vector. If the peripheral channel is used, then the interrupt occurs on the interrupt vector for the peripheral.

Table 7-1. µDMA Channel Assignments

μDMA Channel	Primary Assignment	Secondary Assignment
0	USB Endpoint 1 Receive	UART2 Receive
1	USB Endpoint 1 Transmit	UART2 Transmit
2	USB Endpoint 2 Receive	General-Purpose Timer 3A
3	USB Endpoint 2 Transmit	General-Purpose Timer 3B
4	USB Endpoint 3 Receive	General-Purpose Timer 2A
5	USB Endpoint 3 Transmit	General-Purpose Timer 2B
6	Ethernet Receive	General-Purpose Timer 2A
7	Ethernet Transmit	General-Purpose Timer 2B
8	UART0 Receive	UART1 Receive
9	UART0 Transmit	UART1 Transmit
10	SSI0 Receive	SSI1 Receive
11	SSI0 Transmit	SSI1 Transmit
12	Available for software	UART2 Receive
13	Available for software	UART2 Transmit
14	ADC0 Sample Sequencer 0	General-Purpose Timer 2A
15	ADC0 Sample Sequencer 1	General-Purpose Timer 2B
16	ADC0 Sample Sequencer 2	Available for software
17	ADC0 Sample Sequencer 3	Available for software

µDMA Channel **Primary Assignment Secondary Assignment** General-Purpose Timer 0A General-Purpose Timer 1A 18 19 General-Purpose Timer 0B General-Purpose Timer 1B General-Purpose Timer 1A EPI0 NBRFIFO 20 **EPI0 WFIFO** 21 General-Purpose Timer 1B 22 **UART1** Receive Available for software 23 UART1 Transmit Available for software SSI1 Receive 24 ADC1 Sample Sequencer 0 25 SSI1 Transmit ADC1 Sample Sequencer 1 26 Available for software ADC1 Sample Sequencer 2 27 Available for software ADC1 Sample Sequencer 3 I2S0 Receive 28 Available for software I<sup>2</sup>S0 Transmit 29 Available for software

Table 7-1. µDMA Channel Assignments (continued)

Dedicated for software use

Reserved

## 7.2.2 Priority

30

31

The µDMA controller assigns priority to each channel based on the channel number and the priority level bit for the channel. Channel number 0 has the highest priority and as the channel number increases, the priority of a channel decreases. Each channel has a priority level bit to provide two levels of priority: default priority and high priority. If the priority level bit is set, then that channel has higher priority than all other channels at default priority. If multiple channels are set for high priority, then the channel number is used to determine relative priority among all the high priority channels.

The priority bit for a channel can be set using the **DMA Channel Priority Set (DMAPRIOSET)** register and cleared with the **DMA Channel Priority Clear (DMAPRIOCLR)** register.

### 7.2.3 Arbitration Size

When a  $\mu$ DMA channel requests a transfer, the  $\mu$ DMA controller arbitrates among all the channels making a request and services the  $\mu$ DMA channel with the highest priority. Once a transfer begins, it continues for a selectable number of transfers before rearbitrating among the requesting channels again. The arbitration size can be configured for each channel, ranging from 1 to 1024 item transfers. After the  $\mu$ DMA controller transfers the number of items specified by the arbitration size, it then checks among all the channels making a request and services the channel with the highest priority.

If a lower priority  $\mu$ DMA channel uses a large arbitration size, the latency for higher priority channels is increased because the  $\mu$ DMA controller completes the lower priority burst before checking for higher priority requests. Therefore, lower priority channels should not use a large arbitration size for best response on high priority channels.

The arbitration size can also be thought of as a burst size. It is the maximum number of items that are transferred at any one time in a burst. Here, the term arbitration refers to determination of  $\mu DMA$  channel priority, not arbitration for the bus. When the  $\mu DMA$  controller arbitrates for the bus, the processor always takes priority. Furthermore, the  $\mu DMA$  controller is held off whenever the processor must perform a bus transaction on the same bus, even in the middle of a burst transfer.

## 7.2.4 Request Types

The µDMA controller responds to two types of requests from a peripheral: single or burst. Each peripheral may support either or both types of requests. A single request means that the peripheral is ready to transfer one item, while a burst request means that the peripheral is ready to transfer multiple items.

The  $\mu$ DMA controller responds differently depending on whether the peripheral is making a single request or a burst request. If both are asserted, and the  $\mu$ DMA channel has been set up for a burst transfer, then the burst request takes precedence. See Table 7-2 on page 350, which shows how each peripheral supports the two request types.

**Table 7-2. Request Type Support** 

Peripheral	Single Request Signal	Burst Request Signal
ADC	None	Sequencer IE bit
EPI WFIFO	None	WFIFO Level (configurable)
EPI NBRFIFO	None	NBRFIFO Level (configurable)
Ethernet TX	TX FIFO empty	None
Ethernet RX	RX packet received	None
General-Purpose Timer	None	Trigger event
I <sup>2</sup> S TX	None	FIFO service request
I <sup>2</sup> S RX	None	FIFO service request
SSI TX	TX FIFO Not Full	TX FIFO Level (fixed at 4)
SSI RX	RX FIFO Not Empty	RX FIFO Level (fixed at 4)
UART TX	TX FIFO Not Full	TX FIFO Level (configurable)
UART RX	RX FIFO Not Empty	RX FIFO Level (configurable)
USB TX	None	FIFO TXRDY
USB RX	None	FIFO RXRDY

### 7.2.4.1 Single Request

When a single request is detected, and not a burst request, the  $\mu$ DMA controller transfers one item and then stops to wait for another request.

### 7.2.4.2 Burst Request

When a burst request is detected, the  $\mu$ DMA controller transfers the number of items that is the lesser of the arbitration size or the number of items remaining in the transfer. Therefore, the arbitration size should be the same as the number of data items that the peripheral can accommodate when making a burst request. For example, the UART generates a burst request based on the FIFO trigger level. In this case, the arbitration size should be set to the amount of data that the FIFO can transfer when the trigger level is reached. A burst transfer runs to completion once it is started, and cannot be interrupted, even by a higher priority channel. Burst transfers complete in a shorter time than the same number of non-burst transfers.

It may be desirable to use only burst transfers and not allow single transfers. For example, perhaps the nature of the data is such that it only makes sense when transferred together as a single unit rather than one piece at a time. The single request can be disabled by using the **DMA Channel Useburst Set (DMAUSEBURSTSET)** register. By setting the bit for a channel in this register, the µDMA controller only responds to burst requests for that channel.

### 7.2.5 Channel Configuration

The  $\mu$ DMA controller uses an area of system memory to store a set of channel control structures in a table. The control table may have one or two entries for each  $\mu$ DMA channel. Each entry in the table structure contains source and destination pointers, transfer size, and transfer mode. The control table can be located anywhere in system memory, but it must be contiguous and aligned on a 1024-byte boundary.

Table 7-3 on page 351 shows the layout in memory of the channel control table. Each channel may have one or two control structures in the control table: a primary control structure and an optional alternate control structure. The table is organized so that all of the primary entries are in the first half of the table, and all the alternate structures are in the second half of the table. The primary entry is used for simple transfer modes where transfers can be reconfigured and restarted after each transfer is complete. In this case, the alternate control structures are not used and therefore only the first half of the table must be allocated in memory; the second half of the control table is not necessary, and that memory can be used for something else. If a more complex transfer mode is used such as ping-pong or scatter-gather, then the alternate control structure is also used and memory space should be allocated for the entire table.

Any unused memory in the control table may be used by the application. This includes the control structures for any channels that are unused by the application as well as the unused control word for each channel.

Offset	Channel
0x0	0, Primary
0x10	1, Primary
0x1F0	31, Primary
0x200	0, Alternate
0x210	1, Alternate
0x3F0	31, Alternate

**Table 7-3. Control Structure Memory Map** 

Table 7-4 shows an individual control structure entry in the control table. Each entry is aligned on a 16-byte boundary. The entry contains four long words: the source end pointer, the destination end pointer, the control word, and an unused entry. The end pointers point to the ending address of the transfer and are inclusive. If the source or destination is non-incrementing (as for a peripheral register), then the pointer should point to the transfer address.

**Table 7-4. Channel Control Structure** 

Offset	Description
0x000	Source End Pointer
0x004	Destination End Pointer
0x008	Control Word
0x00C	Unused

The control word contains the following fields:

Source and destination data sizes

- Source and destination address increment size
- Number of transfers before bus arbitration
- Total number of items to transfer
- Useburst flag
- Transfer mode

The control word and each field are described in detail in " $\mu$ DMA Channel Control Structure" on page 370. The  $\mu$ DMA controller updates the transfer size and transfer mode fields as the transfer is performed. At the end of a transfer, the transfer size indicates 0, and the transfer mode indicates "stopped." Because the control word is modified by the  $\mu$ DMA controller, it must be reconfigured before each new transfer. The source and destination end pointers are not modified, so they can be left unchanged if the source or destination addresses remain the same.

Prior to starting a transfer, a µDMA channel must be enabled by setting the appropriate bit in the **DMA Channel Enable Set (DMAENASET)** register. A channel can be disabled by setting the channel bit in the **DMA Channel Enable Clear (DMAENACLR)** register. At the end of a complete µDMA transfer, the controller automatically disables the channel.

### 7.2.6 Transfer Modes

The  $\mu$ DMA controller supports several transfer modes. Two of the modes support simple one-time transfers. Several complex modes support a continuous flow of data.

### 7.2.6.1 Stop Mode

While Stop is not actually a transfer mode, it is a valid value for the mode field of the control word. When the mode field has this value, the  $\mu DMA$  controller does not perform any transfers and disables the channel if it is enabled. At the end of a transfer, the  $\mu DMA$  controller updates the control word to set the mode to Stop.

### 7.2.6.2 Basic Mode

In Basic mode, the  $\mu$ DMA controller performs transfers as long as there are more items to transfer, and a transfer request is present. This mode is used with peripherals that assert a  $\mu$ DMA request signal whenever the peripheral is ready for a data transfer. Basic mode should not be used in any situation where the request is momentary even though the entire transfer should be completed. For example, a software-initiated transfer creates a momentary request, and in Basic mode, only the number of transfers specified by the ARBSIZE field in the **DMA Channel Control Word (DMACHCTL)** register is transferred on a software request, even if there is more data to transfer.

When all of the items have been transferred using Basic mode, the µDMA controller sets the mode for that channel to Stop.

#### 7.2.6.3 Auto Mode

Auto mode is similar to Basic mode, except that once a transfer request is received, the transfer runs to completion, even if the  $\mu$ DMA request is removed. This mode is suitable for software-triggered transfers. Generally, Auto mode is not used with a peripheral.

When all the items have been transferred using Auto mode, the  $\mu DMA$  controller sets the mode for that channel to Stop.

### **7.2.6.4** Ping-Pong

Ping-Pong mode is used to support a continuous data flow to or from a peripheral. To use Ping-Pong mode, both the primary and alternate data structures must be implemented. Both structures are set up by the processor for data transfer between memory and a peripheral. The transfer is started using the primary control structure. When the transfer using the primary control structure is complete, the  $\mu$ DMA controller reads the alternate control structure for that channel to continue the transfer. Each time this happens, an interrupt is generated, and the processor can reload the control structure for the just-completed transfer. Data flow can continue indefinitely this way, using the primary and alternate control structures to switch back and forth between buffers as the data flows to or from the peripheral.

Refer to Figure 7-2 on page 354 for an example showing operation in Ping-Pong mode.

μDMA Controller Cortex-M3 Processor SOURCE transfers using BUFFER A **Primary Structure** BUFFER A DEST CONTROL Unused ransfer continues using alternate Peripheral/µDMA Interrupt SOURCE transfers using BUFFER B BUFFER B Alternate Structure DEST CONTROL Unused Process data in BUFFER A Reload primary structure transfer continues using primary Peripheral/µDMA Interrupt SOURCE transfers using BUFFER A Primary Structure BUFFER A DEST CONTROL Process data in BUFFER B Unused Reload alternate structure transfer continues using alternate PeripherallyDMA Interrupt SOURCE transfers using BUFFER B Alternate Structure DEST BUFFER B CONTROL Process data in BUFFER B Unused Reload alternate structure

Figure 7-2. Example of Ping-Pong μDMA Transaction

## 7.2.6.5 Memory Scatter-Gather

Memory Scatter-Gather mode is a complex mode used when data must be transferred to or from varied locations in memory instead of a set of contiguous locations in a memory buffer. For example, a gather  $\mu DMA$  operation could be used to selectively read the payload of several stored packets of a communication protocol and store them together in sequence in a memory buffer.

In Memory Scatter-Gather mode, the primary control structure is used to program the alternate control structure from a table in memory. The table is set up by the processor software and contains a list of control structures, each containing the source and destination end pointers, and the control word for a specific transfer. The mode of each control word must be set to Scatter-Gather mode. Each entry in the table is copied in turn to the alternate structure where it is then executed. The  $\mu$ DMA controller alternates between using the primary control structure to copy the next transfer instruction from the list and then executing the new transfer instruction. The end of the list is marked by programming the control word for the last entry to use Auto transfer mode. Once the last transfer is performed using Auto mode, the  $\mu$ DMA controller stops. A completion interrupt is generated only after the last transfer. It is possible to loop the list by having the last entry copy the primary control structure to point back to the beginning of the list (or to a new list). It is also possible to trigger a set of other channels to perform a transfer, either directly, by programming a write to the software trigger for another channel, or indirectly, by causing a peripheral action that results in a  $\mu$ DMA request.

By programming the  $\mu$ DMA controller using this method, a set of arbitrary transfers can be performed based on a single  $\mu$ DMA request.

Refer to Figure 7-3 on page 356 and Figure 7-4 on page 357, which show an example of operation in Memory Scatter-Gather mode. This example shows a *gather* operation, where data in three separate buffers in memory is copied together into one buffer. Figure 7-3 on page 356 shows how the application sets up a  $\mu$ DMA task list in memory that is used by the controller to perform three sets of copy operations from different locations in memory. The primary control structure for the channel that is used for the operation is configured to copy from the task list to the alternate control structure.

Figure 7-4 on page 357 shows the sequence as the  $\mu DMA$  controller performs the three sets of copy operations. First, using the primary control structure, the  $\mu DMA$  controller loads the alternate control structure with task A. It then performs the copy operation specified by task A, copying the data from the source buffer A to the destination buffer. Next, the  $\mu DMA$  controller again uses the primary control structure to load task B into the alternate control structure, and then performs the B operation with the alternate control structure. The process is repeated for task C.





Figure 7-3. Memory Scatter-Gather, Setup and Configuration

### NOTES:

- 1. Application has a need to copy data items from three separate locations in memory into one combined buffer.
- 2. Application sets up μDMA "task list" in memory, which contains the pointers and control configuration for three μDMA copy "tasks."
- 3. Application sets up the channel primary control structure to copy each task configuration, one at a time, to the alternate control structure, where it is executed by the μDMA controller.
- 4. The SRC and DST pointers in the task list must point to the last location in the corresponding buffer.


Figure 7-4. Memory Scatter-Gather, µDMA Copy Sequence



Using the channel's primary control structure, the  $\mu DMA$  controller copies task A configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer A to the destination buffer.


\_\_\_\_\_\_



Using the channel's primary control structure, the  $\mu DMA$  controller copies task B configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer B to the destination buffer.

\_\_\_\_\_\_



Using the channel's primary control structure, the  $\mu DMA$  controller copies task C configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer C to the destination buffer.

### 7.2.6.6 Peripheral Scatter-Gather

Peripheral Scatter-Gather mode is very similar to Memory Scatter-Gather, except that the transfers are controlled by a peripheral making a  $\mu$ DMA request. Upon detecting a request from the peripheral, the  $\mu$ DMA controller uses the primary control structure to copy one entry from the list to the alternate control structure and then performs the transfer. At the end of this transfer, the next transfer is started only if the peripheral again asserts a  $\mu$ DMA request. The  $\mu$ DMA controller continues to perform transfers from the list only when the peripheral is making a request, until the last transfer is complete. A completion interrupt is generated only after the last transfer.

By using this method, the  $\mu$ DMA controller can transfer data to or from a peripheral from a set of arbitrary locations whenever the peripheral is ready to transfer data.

Refer to Figure 7-5 on page 359 and Figure 7-6 on page 360, which show an example of operation in Peripheral Scatter-Gather mode. This example shows a gather operation, where data from three separate buffers in memory is copied to a single peripheral data register. Figure 7-5 on page 359 shows how the application sets up a  $\mu$ DMA task list in memory that is used by the controller to perform three sets of copy operations from different locations in memory. The primary control structure for the channel that is used for the operation is configured to copy from the task list to the alternate control structure.

Figure 7-6 on page 360 shows the sequence as the  $\mu$ DMA controller performs the three sets of copy operations. First, using the primary control structure, the  $\mu$ DMA controller loads the alternate control structure with task A. It then performs the copy operation specified by task A, copying the data from the source buffer A to the peripheral data register. Next, the  $\mu$ DMA controller again uses the primary control structure to load task B into the alternate control structure, and then performs the B operation with the alternate control structure. The process is repeated for task C.





Figure 7-5. Peripheral Scatter-Gather, Setup and Configuration

### NOTES:

- 1. Application has a need to copy data items from three separate locations in memory into a peripheral data register.
- Application sets up μDMA "task list" in memory, which contains the pointers and control configuration for three μDMA copy "tasks."
- 3. Application sets up the channel primary control structure to copy each task configuration, one at a time, to the alternate control structure, where it is executed by the μDMA controller.

Figure 7-6. Peripheral Scatter-Gather, µDMA Copy Sequence



Using the channel's primary control structure, the  $\mu DMA$  controller copies task A configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer A to the peripheral data register.


\_\_\_\_\_



Using the channel's primary control structure, the  $\mu DMA$  controller copies task B configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer B to the peripheral data register.

\_\_\_\_\_



Using the channel's primary control structure, the  $\mu DMA$  controller copies task C configuration to the channel's alternate control structure.

Then, using the channel's alternate control structure, the  $\mu DMA$  controller copies data from the source buffer C to the peripheral data register.

#### 7.2.7 Transfer Size and Increment

The µDMA controller supports transfer data sizes of 8, 16, or 32 bits. The source and destination data size must be the same for any given transfer. The source and destination address can be auto-incremented by bytes, half-words, or words, or can be set to no increment. The source and destination address increment values can be set independently, and it is not necessary for the address increment to match the data size as long as the increment is the same or larger than the data size. For example, it is possible to perform a transfer using 8-bit data size, but using an address increment of full words (4 bytes). The data to be transferred must be aligned in memory according to the data size (8, 16, or 32 bits).

Table 7-5 shows the configuration to read from a peripheral that supplies 8-bit data.

Table 7-5. µDMA Read Example: 8-Bit Peripheral

Field	Configuration
Source data size	8 bits
Destination data size	8 bits
Source address increment	No increment
Destination address increment	Byte
Source end pointer	Peripheral read FIFO register
Destination end pointer	End of the data buffer in memory

## 7.2.8 Peripheral Interface

Each peripheral that supports  $\mu$ DMA has a single request and/or burst request signal that is asserted when the peripheral is ready to transfer data (see Table 7-2 on page 350). The request signal can be disabled or enabled using the **DMA Channel Request Mask Set (DMAREQMASKSET)** and **DMA Channel Request Mask Clear (DMAREQMASKCLR)** registers. The  $\mu$ DMA request signal is disabled, or masked, when the channel request mask bit is set. When the request is not masked, the  $\mu$ DMA channel is configured correctly and enabled, and the peripheral asserts the request signal, the  $\mu$ DMA controller begins the transfer.

**Note:** When using  $\mu$ DMA to transfer data to and from a peripheral, the peripheral must disable all interrupts to the NVIC.

When a  $\mu$ DMA transfer is complete, the  $\mu$ DMA controller generates an interrupt, see "Interrupts and Errors" on page 362 for more information.

For more information on how a specific peripheral interacts with the  $\mu$ DMA controller, refer to the DMA Operation section in the chapter that discusses that peripheral.

## 7.2.9 Software Request

One  $\mu$ DMA channel is dedicated to software-initiated transfers. This channel also has a dedicated interrupt to signal completion of a  $\mu$ DMA transfer. A transfer is initiated by software by first configuring and enabling the transfer, and then issuing a software request using the **DMA Channel Software Request (DMASWREQ)** register. For software-based transfers, the Auto transfer mode should be used.

It is possible to initiate a transfer on any channel using the **DMASWREQ** register. If a request is initiated by software using a peripheral µDMA channel, then the completion interrupt occurs on the interrupt vector for the peripheral instead of the software interrupt vector. Any channel may be used for software requests as long as the corresponding peripheral is not using µDMA for data transfer.

## 7.2.10 Interrupts and Errors

When a  $\mu$ DMA transfer is complete, the  $\mu$ DMA controller generates a completion interrupt on the interrupt vector of the peripheral. Therefore, if  $\mu$ DMA is used to transfer data for a peripheral and interrupts are used, then the interrupt handler for that peripheral must be designed to handle the  $\mu$ DMA transfer completion interrupt. If the transfer uses the software  $\mu$ DMA channel, then the completion interrupt occurs on the dedicated software  $\mu$ DMA interrupt vector (see Table 7-6 on page 362).

When  $\mu DMA$  is enabled for a peripheral, the  $\mu DMA$  controller stops the normal transfer interrupts for a peripheral from reaching the interrupt controller (the interrupts are still reported in the peripheral's interrupt registers). Thus, when a large amount of data is transferred using  $\mu DMA$ , instead of receiving multiple interrupts from the peripheral as data flows, the interrupt controller receives only one interrupt when the transfer is complete. Unmasked peripheral error interrupts continue to be sent to the interrupt controller.

When a  $\mu DMA$  channel generates a completion interrupt, the CHIS bit corresponding to the peripheral channel is set in the **DMA Channel Interrupt Status (DMACHIS)** register (see page 397). This register can be used by the peripheral interrupt handler code to determine if the interrupt was caused by the  $\mu DMA$  channel or an error event reported by the peripheral's interrupt registers. The completion interrupt request from the  $\mu DMA$  controller is automatically cleared when the interrupt handler is activated.

If the  $\mu$ DMA controller encounters a bus or memory protection error as it attempts to perform a data transfer, it disables the  $\mu$ DMA channel that caused the error and generates an interrupt on the  $\mu$ DMA error interrupt vector. The processor can read the **DMA Bus Error Clear (DMAERRCLR)** register to determine if an error is pending. The ERRCLR bit is set if an error occurred. The error can be cleared by writing a 1 to the ERRCLR bit.

Table 7-6 shows the dedicated interrupt assignments for the μDMA controller.

Table 7-6. µDMA Interrupt Assignments

Interrupt	Assignment
46	μDMA Software Channel Transfer
47	μDMA Error

# 7.3 Initialization and Configuration

#### 7.3.1 Module Initialization

Before the  $\mu$ DMA controller can be used, it must be enabled in the System Control block and in the peripheral. The location of the channel control structure must also be programmed.

The following steps should be performed one time during system initialization:

- 1. The μDMA peripheral must be enabled in the System Control block. To do this, set the UDMA bit of the System Control RCGC2 register (see page 284).
- 2. Enable the μDMA controller by setting the MASTEREN bit of the **DMA Configuration (DMACFG)** register.
- Program the location of the channel control table by writing the base address of the table to the DMA Channel Control Base Pointer (DMACTLBASE) register. The base address must be aligned on a 1024-byte boundary.

## 7.3.2 Configuring a Memory-to-Memory Transfer

μDMA channel 30 is dedicated for software-initiated transfers. However, any channel can be used for software-initiated, memory-to-memory transfer if the associated peripheral is not being used.

### 7.3.2.1 Configure the Channel Attributes

First, configure the channel attributes:

- 1. Program bit 30 of the **DMA Channel Priority Set (DMAPRIOSET)** or **DMA Channel Priority Clear (DMAPRIOCLR)** registers to set the channel to High priority or Default priority.
- 2. Set bit 30 of the **DMA Channel Primary Alternate Clear (DMAALTCLR)** register to select the primary channel control structure for this transfer.
- 3. Set bit 30 of the **DMA Channel Useburst Clear (DMAUSEBURSTCLR)** register to allow the µDMA controller to respond to single and burst requests.
- **4.** Set bit 30 of the **DMA Channel Request Mask Clear (DMAREQMASKCLR)** register to allow the μDMA controller to recognize requests for this channel.

### 7.3.2.2 Configure the Channel Control Structure

Now the channel control structure must be configured.

This example transfers 256 words from one memory buffer to another. Channel 30 is used for a software transfer, and the control structure for channel 30 is at offset 0x1E0 of the channel control table. The channel control structure for channel 30 is located at the offsets shown in Table 7-7.

Table 7-7. Channel Control Structure Offsets for Channel 30

Offset	Description
Control Table Base + 0x1E0	Channel 30 Source End Pointer
Control Table Base + 0x1E4	Channel 30 Destination End Pointer
Control Table Base + 0x1E8	Channel 30 Control Word

#### Configure the Source and Destination

The source and destination end pointers must be set to the last address for the transfer (inclusive).

- 1. Program the source end pointer at offset 0x1E0 to the address of the source buffer + 0x3FC.
- Program the destination end pointer at offset 0x1E4 to the address of the destination buffer + 0x3FC.

The control word at offset 0x1E8 must be programmed according to Table 7-8.

**Table 7-8. Channel Control Word Configuration for Memory Transfer Example** 

Field in DMACHCTL	Bits	Value	Description
DSTINC	31:30	2	32-bit destination address increment
DSTSIZE	29:28	2	32-bit destination data size
SRCINC	27:26	2	32-bit source address increment
SRCSIZE	25:24	2	32-bit source data size
reserved	23:18	0	Reserved

Table 7-8. Channel Control Word Configuration for Memory Transfer Example (continued)

Field in DMACHCTL	Bits	Value	Description
ARBSIZE	17:14	3	Arbitrates after 8 transfers
XFERSIZE	13:4	255	Transfer 256 items
NXTUSEBURST	3	0	N/A for this transfer type
XFERMODE	2:0	2	Use Auto-request transfer mode

#### 7.3.2.3 Start the Transfer

Now the channel is configured and is ready to start.

- 1. Enable the channel by setting bit 30 of the **DMA Channel Enable Set (DMAENASET)** register.
- 2. Issue a transfer request by setting bit 30 of the **DMA Channel Software Request (DMASWREQ)** register.

The µDMA transfer begins. If the interrupt is enabled, then the processor is notified by interrupt when the transfer is complete. If needed, the status can be checked by reading bit 30 of the **DMAENASET** register. This bit is automatically cleared when the transfer is complete. The status can also be checked by reading the XFERMODE field of the channel control word at offset 0x1E8. This field is automatically cleared at the end of the transfer.

## 7.3.3 Configuring a Peripheral for Simple Transmit

This example configures the  $\mu$ DMA controller to transmit a buffer of data to a peripheral. The peripheral has a transmit FIFO with a trigger level of 4. The example peripheral uses  $\mu$ DMA channel 7.

#### 7.3.3.1 Configure the Channel Attributes

First, configure the channel attributes:

- 1. Configure bit 7 of the DMA Channel Priority Set (DMAPRIOSET) or DMA Channel Priority Clear (DMAPRIOCLR) registers to set the channel to High priority or Default priority.
- 2. Set bit 7 of the **DMA Channel Primary Alternate Clear (DMAALTCLR)** register to select the primary channel control structure for this transfer.
- 3. Set bit 7 of the **DMA Channel Useburst Clear (DMAUSEBURSTCLR)** register to allow the µDMA controller to respond to single and burst requests.
- **4.** Set bit 7 of the **DMA Channel Request Mask Clear (DMAREQMASKCLR)** register to allow the μDMA controller to recognize requests for this channel.

#### 7.3.3.2 Configure the Channel Control Structure

This example transfers 64 bytes from a memory buffer to the peripheral's transmit FIFO register using µDMA channel 7. The control structure for channel 7 is at offset 0x070 of the channel control table. The channel control structure for channel 7 is located at the offsets shown in Table 7-9.

Table 7-9. Channel Control Structure Offsets for Channel 7

Offset	Description
Control Table Base + 0x070	Channel 7 Source End Pointer

Table 7-9. Channel Control Structure Offsets for Channel 7 (continued)

Offset	Description	
Control Table Base + 0x074	Channel 7 Destination End Pointer	
Control Table Base + 0x078	Channel 7 Control Word	

#### Configure the Source and Destination

The source and destination end pointers must be set to the last address for the transfer (inclusive). Because the peripheral pointer does not change, it simply points to the peripheral's data register.

- 1. Program the source end pointer at offset 0x070 to the address of the source buffer + 0x3F.
- **2.** Program the destination end pointer at offset 0x074 to the address of the peripheral's transmit FIFO register.

The control word at offset 0x078 must be programmed according to Table 7-10.

Table 7-10. Channel Control Word Configuration for Peripheral Transmit Example

Field in DMACHCTL	Bits	Value	Description
DSTINC	31:30	3	Destination address does not increment
DSTSIZE	29:28	0	8-bit destination data size
SRCINC	27:26	0	8-bit source address increment
SRCSIZE	25:24	0	8-bit source data size
reserved	23:18	0	Reserved
ARBSIZE	17:14	2	Arbitrates after 4 transfers
XFERSIZE	13:4	63	Transfer 64 items
NXTUSEBURST	3	0	N/A for this transfer type
XFERMODE	2:0	1	Use Basic transfer mode

Note: In this example, it is not important if the peripheral makes a single request or a burst request. Because the peripheral has a FIFO that triggers at a level of 4, the arbitration size is set to 4. If the peripheral does make a burst request, then 4 bytes are transferred, which is what the FIFO can accommodate. If the peripheral makes a single request (if there is any space in the FIFO), then one byte is transferred at a time. If it is important to the application that transfers only be made in bursts, then the Channel Useburst SET[7] bit should be set in the DMA Channel Useburst Set (DMAUSEBURSTSET) register.

### 7.3.3.3 Start the Transfer

Now the channel is configured and is ready to start.

1. Enable the channel by setting bit 7 of the DMA Channel Enable Set (DMAENASET) register.

The  $\mu DMA$  controller is now configured for transfer on channel 7. The controller makes transfers to the peripheral whenever the peripheral asserts a  $\mu DMA$  request. The transfers continue until the entire buffer of 64 bytes has been transferred. When that happens, the  $\mu DMA$  controller disables the channel and sets the XFERMODE field of the channel control word to 0 (Stopped). The status of the transfer can be checked by reading bit 7 of the **DMA Channel Enable Set (DMAENASET)** register. This bit is automatically cleared when the transfer is complete. The status can also be checked by reading the XFERMODE field of the channel control word at offset 0x078. This field is automatically cleared at the end of the transfer.

If peripheral interrupts are enabled, then the peripheral interrupt handler receives an interrupt when the entire transfer is complete.

## 7.3.4 Configuring a Peripheral for Ping-Pong Receive

This example configures the  $\mu$ DMA controller to continuously receive 8-bit data from a peripheral into a pair of 64-byte buffers. The peripheral has a receive FIFO with a trigger level of 8. The example peripheral uses  $\mu$ DMA channel 8.

#### 7.3.4.1 Configure the Channel Attributes

First, configure the channel attributes:

- Configure bit 8 of the DMA Channel Priority Set (DMAPRIOSET) or DMA Channel Priority Clear (DMAPRIOCLR) registers to set the channel to High priority or Default priority.
- 2. Set bit 8 of the **DMA Channel Primary Alternate Clear (DMAALTCLR)** register to select the primary channel control structure for this transfer.
- 3. Set bit 8 of the **DMA Channel Useburst Clear (DMAUSEBURSTCLR)** register to allow the μDMA controller to respond to single and burst requests.
- **4.** Set bit 8 of the **DMA Channel Request Mask Clear (DMAREQMASKCLR)** register to allow the μDMA controller to recognize requests for this channel.

### 7.3.4.2 Configure the Channel Control Structure

This example transfers bytes from the peripheral's receive FIFO register into two memory buffers of 64 bytes each. As data is received, when one buffer is full, the  $\mu$ DMA controller switches to use the other.

To use Ping-Pong buffering, both primary and alternate channel control structures must be used. The primary control structure for channel 8 is at offset 0x080 of the channel control table, and the alternate channel control structure is at offset 0x280. The channel control structures for channel 8 are located at the offsets shown in Table 7-11.

Table 7-11. Primary and Alternate Channel Control Structure Offsets for Channel 8

Offset	Description
Control Table Base + 0x080	Channel 8 Primary Source End Pointer
Control Table Base + 0x084	Channel 8 Primary Destination End Pointer
Control Table Base + 0x088	Channel 8 Primary Control Word
Control Table Base + 0x280	Channel 8 Alternate Source End Pointer
Control Table Base + 0x284	Channel 8 Alternate Destination End Pointer
Control Table Base + 0x288	Channel 8 Alternate Control Word

#### Configure the Source and Destination

The source and destination end pointers must be set to the last address for the transfer (inclusive). Because the peripheral pointer does not change, it simply points to the peripheral's data register. Both the primary and alternate sets of pointers must be configured.

 Program the primary source end pointer at offset 0x080 to the address of the peripheral's receive buffer.

- 2. Program the primary destination end pointer at offset 0x084 to the address of ping-pong buffer A + 0x3F.
- 3. Program the alternate source end pointer at offset 0x280 to the address of the peripheral's receive buffer.
- Program the alternate destination end pointer at offset 0x284 to the address of ping-pong buffer B + 0x3F.

The primary control word at offset 0x088 and the alternate control word at offset 0x288 are initially programmed the same way.

- 1. Program the primary channel control word at offset 0x088 according to Table 7-12.
- 2. Program the alternate channel control word at offset 0x288 according to Table 7-12.

Table 7-12. Channel Control Word Configuration for Peripheral Ping-Pong Receive Example

Field in DMACHCTL	Bits	Value	Description
DSTINC	31:30	0	8-bit destination address increment
DSTSIZE	29:28	0	8-bit destination data size
SRCINC	27:26	3	Source address does not increment
SRCSIZE	25:24	0	8-bit source data size
reserved	23:18	0	Reserved
ARBSIZE	17:14	3	Arbitrates after 8 transfers
XFERSIZE	13:4	63	Transfer 64 items
NXTUSEBURST	3	0	N/A for this transfer type
XFERMODE	2:0	3	Use Ping-Pong transfer mode

Note: In this example, it is not important if the peripheral makes a single request or a burst request. Because the peripheral has a FIFO that triggers at a level of 8, the arbitration size is set to 8. If the peripheral does make a burst request, then 8 bytes are transferred, which is what the FIFO can accommodate. If the peripheral makes a single request (if there is any data in the FIFO), then one byte is transferred at a time. If it is important to the application that transfers only be made in bursts, then the Channel Useburst SET[8] bit should be set in the DMA Channel Useburst Set (DMAUSEBURSTSET) register.

#### 7.3.4.3 Configure the Peripheral Interrupt

An interrupt handler should be configured when using  $\mu$ DMA Ping-Pong mode, it is best to use an interrupt handler. However, the Ping-Pong mode can be configured without interrupts by polling. The interrupt handler is triggered after each buffer is complete.

1. Configure and enable an interrupt handler for the peripheral.

## 7.3.4.4 Enable the µDMA Channel

Now the channel is configured and is ready to start.

1. Enable the channel by setting bit 8 of the DMA Channel Enable Set (DMAENASET) register.

#### 7.3.4.5 Process Interrupts

The  $\mu$ DMA controller is now configured and enabled for transfer on channel 8. When the peripheral asserts the  $\mu$ DMA request signal, the  $\mu$ DMA controller makes transfers into buffer A using the primary channel control structure. When the primary transfer to buffer A is complete, it switches to the alternate channel control structure and makes transfers into buffer B. At the same time, the primary channel control word mode field is configured to indicate Stopped, and an interrupt is

When an interrupt is triggered, the interrupt handler must determine which buffer is complete and process the data or set a flag that the data must be processed by non-interrupt buffer processing code. Then the next buffer transfer must be set up.

In the interrupt handler:

- 1. Read the primary channel control word at offset 0x088 and check the XFERMODE field. If the field is 0, this means buffer A is complete. If buffer A is complete, then:
  - **a.** Process the newly received data in buffer A or signal the buffer processing code that buffer A has data available.
  - **b.** Reprogram the primary channel control word at offset 0x88 according to Table 7-12 on page 367.
- 2. Read the alternate channel control word at offset 0x288 and check the XFERMODE field. If the field is 0, this means buffer B is complete. If buffer B is complete, then:
  - a. Process the newly received data in buffer B or signal the buffer processing code that buffer B has data available.
  - **b.** Reprogram the alternate channel control word at offset 0x288 according to Table 7-12 on page 367.

## 7.3.5 Configuring Channel Assignments

Channel assignments for each  $\mu DMA$  channel can be changed using the **DMACHASGN** register. Each bit represents a  $\mu DMA$  channel. If the bit is set, then the secondary function is used for the channel.

Refer to Table 7-1 on page 348 for channel assignments.

For example, to use SSI1 Receive on channel 8 instead of UART0, set bit 8 of the **DMACHASGN** register.

# 7.4 Register Map

Table 7-13 on page 369 lists the  $\mu$ DMA channel control structures and registers. The channel control structure shows the layout of one entry in the channel control table. The channel control table is located in system memory, and the location is determined by the application, that is, the base address is n/a (not applicable). In the table below, the offset for the channel control structures is the offset from the entry in the channel control table. See "Channel Configuration" on page 351 and Table 7-3 on page 351 for a description of how the entries in the channel control table are located in memory. The  $\mu$ DMA register addresses are given as a hexadecimal increment, relative to the  $\mu$ DMA base address of 0x400F.F000. Note that the  $\mu$ DMA module clock must be enabled before the registers can be programmed (see page 284). There must be a delay of 3 system clocks after the  $\mu$ DMA module clock is enabled before any  $\mu$ DMA module registers are accessed.

Table 7-13. µDMA Register Map

Offset	Name	Туре	Reset	Description	See page
µDMA Ch	annel Control Structure	(Offset fro	m Channel Control	Table Base)	
0x000	DMASRCENDP R/W - DMA Channel Source Address End Pointer		371		
0x004	DMADSTENDP	R/W	-	DMA Channel Destination Address End Pointer	372
800x0	DMACHCTL	R/W	-	DMA Channel Control Word	373
µDMA Re	gisters (Offset from µDN	IA Base A	ddress)		
0x000	DMASTAT	RO	0x001F.0000	DMA Status	378
0x004	DMACFG	WO	-	DMA Configuration	380
0x008	DMACTLBASE	R/W	0x0000.0000	DMA Channel Control Base Pointer	381
0x00C	DMAALTBASE	RO	0x0000.0200	DMA Alternate Channel Control Base Pointer	382
0x010	DMAWAITSTAT	RO	0xFFFF.FFC0	DMA Channel Wait-on-Request Status	383
0x014	DMASWREQ	WO	-	DMA Channel Software Request	384
0x018	DMAUSEBURSTSET	R/W	0x0000.0000	DMA Channel Useburst Set	385
0x01C	DMAUSEBURSTCLR	WO	-	DMA Channel Useburst Clear	386
0x020	DMAREQMASKSET	R/W	0x0000.0000	DMA Channel Request Mask Set	387
0x024	DMAREQMASKCLR	WO	-	DMA Channel Request Mask Clear	388
0x028	DMAENASET	R/W	0x0000.0000	DMA Channel Enable Set	389
0x02C	DMAENACLR	WO	-	DMA Channel Enable Clear	390
0x030	DMAALTSET	R/W	0x0000.0000	DMA Channel Primary Alternate Set	391
0x034	DMAALTCLR	WO	-	DMA Channel Primary Alternate Clear	392
0x038	DMAPRIOSET	R/W	0x0000.0000	DMA Channel Priority Set	393
0x03C	DMAPRIOCLR	WO	-	DMA Channel Priority Clear	394
0x04C	DMAERRCLR	R/W	0x0000.0000	DMA Bus Error Clear	395
0x500	DMACHASGN	R/W	0x0000.0000	DMA Channel Assignment	396
0x504	DMACHIS	R/W1C	0x0000.0000	DMA Channel Interrupt Status	397
0xFD0	DMAPeriphID4	RO	0x0000.0004	DMA Peripheral Identification 4	402
0xFE0	DMAPeriphID0	RO	0x0000.0030	DMA Peripheral Identification 0	398
0xFE4	DMAPeriphID1	RO	0x0000.00B2	DMA Peripheral Identification 1	399
0xFE8	DMAPeriphID2	RO	0x0000.000B	DMA Peripheral Identification 2	400
0xFEC	DMAPeriphID3	RO	0x0000.0000	DMA Peripheral Identification 3	401
0xFF0	DMAPCellID0	RO	0x0000.000D	DMA PrimeCell Identification 0	403
0xFF4	DMAPCellID1	RO	0x0000.00F0	DMA PrimeCell Identification 1	404
0xFF8	DMAPCellID2	RO	0x0000.0005	DMA PrimeCell Identification 2	405

## Table 7-13. µDMA Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0xFFC	DMAPCellID3	RO	0x0000.00B1	DMA PrimeCell Identification 3	406

# 7.5 µDMA Channel Control Structure

The  $\mu$ DMA Channel Control Structure holds the transfer settings for a  $\mu$ DMA channel. Each channel has two control structures, which are located in a table in system memory. Refer to "Channel Configuration" on page 351 for an explanation of the Channel Control Table and the Channel Control Structure.

The channel control structure is one entry in the channel control table. Each channel has a primary and alternate structure. The primary control structures are located at offsets 0x0, 0x10, 0x20 and so on. The alternate control structures are located at offsets 0x200, 0x210, 0x220, and so on.

# Register 1: DMA Channel Source Address End Pointer (DMASRCENDP), offset 0x000


**DMA Channel Source Address End Pointer (DMASRCENDP)** is part of the Channel Control Structure and is used to specify the source address for a µDMA transfer.

The  $\mu$ DMA controller can transfer data to and from the on-chip SRAM. However, because the Flash memory and ROM are located on a separate internal bus, it is not possible to transfer data from the Flash memory or ROM with the  $\mu$ DMA controller.

**Note:** The offset specified is from the base address of the control structure in system memory, not the µDMA module base address.

DMA Channel Source Address End Pointer (DMASRCENDP)

Base n/a Offset 0x000 Type R/W, reset -



This field points to the last address of the µDMA transfer source (inclusive). If the source address is not incrementing (the SRCINC field in the **DMACHCTL** register is 0x3), then this field points at the source location itself (such as a peripheral data register).


# Register 2: DMA Channel Destination Address End Pointer (DMADSTENDP), offset 0x004

**DMA Channel Destination Address End Pointer (DMADSTENDP)** is part of the Channel Control Structure and is used to specify the destination address for a µDMA transfer.

**Note:** The offset specified is from the base address of the control structure in system memory, not the  $\mu$ DMA module base address.

DMA Channel Destination Address End Pointer (DMADSTENDP)

Base n/a Offset 0x004 Type R/W, reset -



This field points to the last address of the  $\mu DMA$  transfer destination (inclusive). If the destination address is not incrementing (the DSTINC field in the **DMACHCTL** register is 0x3), then this field points at the destination location itself (such as a peripheral data register).


# Register 3: DMA Channel Control Word (DMACHCTL), offset 0x008

**DMA Channel Control Word (DMACHCTL)** is part of the Channel Control Structure and is used to specify parameters of a  $\mu$ DMA transfer.

**Note:** The offset specified is from the base address of the control structure in system memory, not the  $\mu$ DMA module base address.

DMA Channel Control Word (DMACHCTL)

Base n/a Offset 0x008 Type R/W, reset -



Bit/Field Name Type Reset Description

31:30 DSTINC R/W - Destination Address Increment

This field configures the destination address increment.

The address increment value must be equal or greater than the value of the destination size ( ${\tt DSTSIZE}$ ).

Value Description

0x0 Byte

Increment by 8-bit locations

0x1 Half-word

Increment by 16-bit locations

0x2 Word

Increment by 32-bit locations

0x3 No increment

Address remains set to the value of the Destination Address End Pointer (DMADSTENDP) for the channel

Bit/Field	Name	Туре	Reset	Description
29:28	DSTSIZE	R/W	-	Destination Data Size  This field configures the destination item data size.  Note: DSTSIZE must be the same as SRCSIZE.
				Value Description
				0x0 Byte
				8-bit data size
				0x1 Half-word
				16-bit data size
				0x2 Word
				32-bit data size
				0x3 Reserved
27:26	SRCINC	R/W	_	Source Address Increment
				This field configures the source address increment.
				The address increment value must be equal or greater than the value of the source size (SRCSIZE).
				Value Description
				0x0 Byte
				Increment by 8-bit locations
				0x1 Half-word
				Increment by 16-bit locations
				0x2 Word
				Increment by 32-bit locations
				0x3 No increment
				Address remains set to the value of the Source Address End Pointer (DMASRCENDP) for the channel
25:24	SRCSIZE	R/W	-	Source Data Size
				This field configures the source item data size.
				Note: DSTSIZE must be the same as SRCSIZE.
				Value Description
				0x0 Byte
				8-bit data size.
				0x1 Half-word
				16-bit data size.
				0x2 Word
				32-bit data size.
				0x3 Reserved
23:18	reserved	R/W	-	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
17:14	ARBSIZE	R/W	-	Arbitration Size This field configures the number of transfers that can occur before the $\mu$ DMA controller re-arbitrates. The possible arbitration rate configurations represent powers of 2 and are shown below.
				Value Description
				0x0 1 Transfer
				Arbitrates after each µDMA transfer
				0x1 2 Transfers
				0x2 4 Transfers
				0x3 8 Transfers
				0x4 16 Transfers
				0x5 32 Transfers
				0x6 64 Transfers
				0x7 128 Transfers
				0x8 256 Transfers
				0x9 512 Transfers
				0xA-0xF 1024 Transfers
				In this configuration, no arbitration occurs during the $\mu DMA$ transfer because the maximum transfer size is 1024.
13:4	XFERSIZE	R/W	-	Transfer Size (minus 1)
				This field configures the total number of items to transfer. The value of this field is 1 less than the number to transfer (value 0 means transfer 1 item). The maximum value for this 10-bit field is 1023 which represents a transfer size of 1024 items.
				The transfer size is the number of items, not the number of bytes. If the data size is 32 bits, then this value is the number of 32-bit words to transfer.
				The $\mu$ DMA controller updates this field immediately prior to entering the arbitration process, so it contains the number of outstanding items that is necessary to complete the $\mu$ DMA cycle.
3	NXTUSEBURST	R/W	_	Next Useburst
-	2 2 2 2			This field controls whether the Useburst SET[n] bit is automatically set for the last transfer of a peripheral scatter-gather operation. Normally, for the last transfer, if the number of remaining items to transfer is less than the arbitration size, the $\mu$ DMA controller uses single transfers to complete the transaction. If this bit is set, then the controller uses a burst transfer to complete the last transfer.

Bit/Field	Name	Туре	Reset	Description
2:0	XFERMODE	R/W	-	μDMA Transfer Mode
				This field configures the operating mode of the $\mu DMA$ cycle. Refer to "Transfer Modes" on page 352 for a detailed explanation of transfer modes.
				Because this register is in system RAM, it has no reset value. Therefore, this field should be initialized to 0 before the channel is enabled.
				Value Description
				0x0 Stop
				0x1 Basic
				0x2 Auto-Request
				0x3 Ping-Pong
				0x4 Memory Scatter-Gather
				0x5 Alternate Memory Scatter-Gather
				0x6 Peripheral Scatter-Gather
				0x7 Alternate Peripheral Scatter-Gather

#### XFERMODE Bit Field Values.

#### Stop

Channel is stopped or configuration data is invalid. No more transfers can occur.

#### Basic

For each trigger (whether from a peripheral or a software request), the µDMA controller performs the number of transfers specified by the ARBSIZE field.

## Auto-Request

The initial request (software- or peripheral-initiated) is sufficient to complete the entire transfer of XFERSIZE items without any further requests.

#### Ping-Pong

This mode uses both the primary and alternate control structures for this channel. When the number of transfers specified by the XFERSIZE field have completed for the current control structure (primary or alternate), the  $\mu$ DMA controller switches to the other one. These switches continue until one of the control structures is not set to ping-pong mode. At that point, the  $\mu$ DMA controller stops. An interrupt is generated on completion of the transfers configured by each control structure. See "Ping-Pong" on page 353.

### Memory Scatter-Gather

When using this mode, the primary control structure for the channel is configured to allow a list of operations (tasks) to be performed. The source address pointer specifies the start of a table of tasks to be copied to the alternate control structure for this channel. The XFERMODE field for the alternate control structure should be configured to 0x5 (Alternate memory scatter-gather) to perform the task. When the task completes, the µDMA switches back to the primary channel control structure, which then copies the next task to the alternate control structure. This process continues until the table of tasks is empty. The last task must have an XFERMODE value other than 0x5. Note that for continuous operation, the last task can update the primary channel control structure back to the start of the list or to another list. See "Memory Scatter-Gather" on page 354.

### Alternate Memory Scatter-Gather

This value must be used in the alternate channel control data structure when the  $\mu$ DMA controller operates in Memory Scatter-Gather mode.

#### Peripheral Scatter-Gather

This value must be used in the primary channel control data structure when the  $\mu$ DMA controller operates in Peripheral Scatter-Gather mode. In this mode, the  $\mu$ DMA controller operates exactly the same as in Memory Scatter-Gather mode, except that instead of performing the number of transfers specified by the XFERSIZE field in the alternate control structure at one time, the  $\mu$ DMA controller only performs the number of transfers specified by the ARBSIZE field per trigger; see Basic mode for details. See "Peripheral Scatter-Gather" on page 358.

#### Alternate Peripheral Scatter-Gather

This value must be used in the alternate channel control data structure when the  $\mu$ DMA controller operates in Peripheral Scatter-Gather mode.

# 7.6 µDMA Register Descriptions

The register addresses given are relative to the µDMA base address of 0x400F.F000.

# Register 4: DMA Status (DMASTAT), offset 0x000

The DMA Status (DMASTAT) register returns the status of the µDMA controller. You cannot read this register when the µDMA controller is in the reset state.

#### DMA Status (DMASTAT)

3:1


378

reserved

RO

0x0

Base 0x400F.F000 Offset 0x000 Type RO, reset 0x001F.0000



set	0	0	0	0	0	0	0	0 0	)	0	0	0	0	0	0	0
Е	Bit/Field		Nam	e	Ту	ре	Reset	Descript	ion							
	31:21		reserv	ed .	R	0	0x000	Software compatible preserve	oility w	ith futu	re produ	icts, the	value of	a reserv	•	
	20:16		DMACH	IANS	R	0	0x1F	Available This field µDMA co	d conta ontrolle	ains a v er is co	/alue eq	ual to the I to use,				
	15:8		reserv	ed .	R	0	0x00	Software compatible preserve	oility w	ith futu	re produ	icts, the	value of	a reserv		
	7:4		STAT	Ē	R	0	0x0	Control S This field can be o	show	s the c	current s		the conti	ol state	machine	. Status
								Value	Desc	cription						
								0x0	ldle							
								0x1	Read	ding ch	annel co	ontroller	data.			
								0x2	Read	ding so	urce en	d pointer				
								0x3	Read	ding de	estinatio	n end po	inter.			
								0x4	Read	ding so	ource da	ta.				
								0x5	Writi	ng des	tination	data.				
								0x6	Waiti	ing for	µDMA r	equest to	o clear.			
								0x7	Writi	ng cha	nnel cor	ntroller d	ata.			
								8x0	Stall	ed						
								0x9	Done	е						
								0xA-0xF	Unde	efined						

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

October 06, 2012

preserved across a read-modify-write operation.


Bit/Field	Name	Туре	Reset	Description
0	MASTEN	RO	0	Master Enable Status
				Value Description
				0 The μDMA controller is disabled.
				1 The μDMA controller is enabled.

# Register 5: DMA Configuration (DMACFG), offset 0x004

The **DMACFG** register controls the configuration of the µDMA controller.

## DMA Configuration (DMACFG)

Base 0x400F.F000 Offset 0x004 Type WO, reset -



Bit/Field	Name	Type	Reset	Description
31:1	reserved	WO	-	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	MASTEN	WO	_	Controller Master Enable

Value Description

0 Disables the μDMA controller.

Enables μDMA controller.

## Register 6: DMA Channel Control Base Pointer (DMACTLBASE), offset 0x008


The **DMACTLBASE** register must be configured so that the base pointer points to a location in system memory.

The amount of system memory that must be assigned to the  $\mu DMA$  controller depends on the number of  $\mu DMA$  channels used and whether the alternate channel control data structure is used. See "Channel Configuration" on page 351 for details about the Channel Control Table. The base address must be aligned on a 1024-byte boundary. This register cannot be read when the  $\mu DMA$  controller is in the reset state.

#### DMA Channel Control Base Pointer (DMACTLBASE)

Base 0x400F.F000

Offset 0x008
Type R/W, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:10	ADDR	R/W	0x0000.00	Channel Control Base Address  This field contains the pointer to the base address of the channel control table. The base address must be 1024-byte aligned.
9:0	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 7: DMA Alternate Channel Control Base Pointer (DMAALTBASE), offset 0x00C

The **DMAALTBASE** register returns the base address of the alternate channel control data. This register removes the necessity for application software to calculate the base address of the alternate channel control structures. This register cannot be read when the  $\mu DMA$  controller is in the reset state.

DMA Alternate Channel Control Base Pointer (DMAALTBASE)

Base 0x400F.F000 Offset 0x00C Type RO, reset 0x0000.0200



31:0 ADDR RO 0x0000.0200 Alternate Channel Address Pointer


This field provides the base address of the alternate channel control structures.

## Register 8: DMA Channel Wait-on-Request Status (DMAWAITSTAT), offset 0x010

This read-only register indicates that the µDMA channel is waiting on a request. A peripheral can hold off the µDMA from performing a single request until the peripheral is ready for a burst request to enhance the µDMA performance. The use of this feature is dependent on the design of the peripheral and is not controllable by software in any way. This register cannot be read when the µDMA controller is in the reset state.

DMA Channel Wait-on-Request Status (DMAWAITSTAT)

Base 0x400F.F000 Offset 0x010
Type RO, reset 0xFFFF.FFC0



31:0 WAITREQ[n] RO 0xFFFF.FFC0 Channel [n] Wait Status

> These bits provide the channel wait-on-request status. Bit 0 corresponds to channel 0.

Value Description


- 1 The corresponding channel is waiting on a request.
- 0 The corresponding channel is not waiting on a request.

# Register 9: DMA Channel Software Request (DMASWREQ), offset 0x014

Each bit of the **DMASWREQ** register represents the corresponding  $\mu$ DMA channel. Setting a bit generates a request for the specified  $\mu$ DMA channel.

DMA Channel Software Request (DMASWREQ)

Base 0x400F.F000 Offset 0x014 Type WO, reset -



31:0 SWREQ[n] WO - Channel [n] Software Request

These bits generate software requests. Bit 0 corresponds to channel 0.

Value Description

- 1 Generate a software request for the corresponding channel.
- 0 No request generated.

These bits are automatically cleared when the software request has been completed.

## Register 10: DMA Channel Useburst Set (DMAUSEBURSTSET), offset 0x018

Each bit of the **DMAUSEBURSTSET** register represents the corresponding  $\mu$ DMA channel. Setting a bit disables the channel's single request input from generating requests, configuring the channel to only accept burst requests. Reading the register returns the status of USEBURST.


If the amount of data to transfer is a multiple of the arbitration (burst) size, the corresponding SET[n] bit is cleared after completing the final transfer. If there are fewer items remaining to transfer than the arbitration (burst) size, the  $\mu DMA$  controller automatically clears the corresponding SET[n] bit, allowing the remaining items to transfer using single requests. In order to resume transfers using burst requests, the corresponding bit must be set again. A bit should not be set if the corresponding peripheral does not support the burst request model.

Refer to "Request Types" on page 350 for more details about request types.

#### DMA Channel Useburst Set (DMAUSEBURSTSET)

Base 0x400F.F000

Offset 0x018 Type R/W, reset 0x0000.0000



#### Value Description

- 0 μDMA channel [n] responds to single or burst requests.
- 1 µDMA channel [n] responds only to burst requests.

Bit 0 corresponds to channel 0. This bit is automatically cleared as described above. A bit can also be manually cleared by setting the corresponding  ${\tt CLR[n]}$  bit in the **DMAUSEBURSTCLR** register.

## Register 11: DMA Channel Useburst Clear (DMAUSEBURSTCLR), offset 0x01C

Each bit of the **DMAUSEBURSTCLR** register represents the corresponding  $\mu$ DMA channel. Setting a bit clears the corresponding SET[n] bit in the **DMAUSEBURSTSET** register.


DMA Channel Useburst Clear (DMAUSEBURSTCLR)

CLR[n]

WO

Base 0x400F.F000 Offset 0x01C Type WO, reset -

31:0



Value Description

Channel [n] Useburst Clear

0 No effect.

1 Setting a bit clears the corresponding SET[n] bit in the **DMAUSEBURSTSET** register meaning that μDMA channel [n] responds to single and burst requests.


# Register 12: DMA Channel Request Mask Set (DMAREQMASKSET), offset 0x020

Each bit of the **DMAREQMASKSET** register represents the corresponding  $\mu$ DMA channel. Setting a bit disables  $\mu$ DMA requests for the channel. Reading the register returns the request mask status. When a  $\mu$ DMA channel's request is masked, that means the peripheral can no longer request  $\mu$ DMA transfers. The channel can then be used for software-initiated transfers.

DMA Channel Request Mask Set (DMAREQMASKSET)

Base 0x400F.F000 Offset 0x020

Type R/W, reset 0x0000.0000



Value Description

- The peripheral associated with channel [n] is enabled to request  $\mu DMA$  transfers.
- The peripheral associated with channel [n] is not able to request  $\mu$ DMA transfers. Channel [n] may be used for software-initiated transfers.


Bit 0 corresponds to channel 0. A bit can only be cleared by setting the corresponding CLR[n] bit in the **DMAREQMASKCLR** register.

# Register 13: DMA Channel Request Mask Clear (DMAREQMASKCLR), offset 0x024

Each bit of the **DMAREQMASKCLR** register represents the corresponding  $\mu$ DMA channel. Setting a bit clears the corresponding SET[n] bit in the **DMAREQMASKSET** register.

DMA Channel Request Mask Clear (DMAREQMASKCLR)

Base 0x400F.F000 Offset 0x024 Type WO, reset -



Value Description

- 0 No effect.
- Setting a bit clears the corresponding SET[n] bit in the DMAREQMASKSET register meaning that the peripheral associated with channel [n] is enabled to request μDMA transfers.


## Register 14: DMA Channel Enable Set (DMAENASET), offset 0x028

Each bit of the **DMAENASET** register represents the corresponding  $\mu$ DMA channel. Setting a bit enables the corresponding  $\mu$ DMA channel. Reading the register returns the enable status of the channels. If a channel is enabled but the request mask is set (**DMAREQMASKSET**), then the channel can be used for software-initiated transfers.

DMA Channel Enable Set (DMAENASET)

Base 0x400F.F000

Offset 0x028 Type R/W, reset 0x0000.0000



Value Description

0 μDMA Channel [n] is disabled.

1 μDMA Channel [n] is enabled.

Bit 0 corresponds to channel 0. A bit can only be cleared by setting the corresponding CLR[n] bit in the **DMAENACLR** register.

# Register 15: DMA Channel Enable Clear (DMAENACLR), offset 0x02C

Each bit of the **DMAENACLR** register represents the corresponding  $\mu$ DMA channel. Setting a bit clears the corresponding SET[n] bit in the **DMAENASET** register.


DMA Channel Enable Clear (DMAENACLR)

CLR[n]

WO

Base 0x400F.F000 Offset 0x02C Type WO, reset -

31:0



Value Description

Clear Channel [n] Enable Clear

0 No effect.

Setting a bit clears the corresponding SET[n] bit in the DMAENASET register meaning that channel [n] is disabled for μDMA transfers.

 $\begin{tabular}{ll} \textbf{Note:} & The controller disables a channel when it completes the $\mu$DMA cycle. \end{tabular}$ 


# Register 16: DMA Channel Primary Alternate Set (DMAALTSET), offset 0x030

Each bit of the **DMAALTSET** register represents the corresponding  $\mu$ DMA channel. Setting a bit configures the  $\mu$ DMA channel to use the alternate control data structure. Reading the register returns the status of which control data structure is in use for the corresponding  $\mu$ DMA channel.

DMA Channel Primary Alternate Set (DMAALTSET)

Base 0x400F.F000 Offset 0x030

Type R/W, reset 0x0000.0000



Value Description

- 0 μDMA channel [n] is using the primary control structure.
- 1 μDMA channel [n] is using the alternate control structure.

Bit 0 corresponds to channel 0. A bit can only be cleared by setting the corresponding CLR[n] bit in the **DMAALTCLR** register.

Note:


For Ping-Pong and Scatter-Gather cycle types, the µDMA controller automatically sets these bits to select the alternate channel control data structure.

# Register 17: DMA Channel Primary Alternate Clear (DMAALTCLR), offset 0x034

Each bit of the **DMAALTCLR** register represents the corresponding µDMA channel. Setting a bit clears the corresponding SET[n] bit in the **DMAALTSET** register.

DMA Channel Primary Alternate Clear (DMAALTCLR)

Base 0x400F.F000 Offset 0x034 Type WO, reset -



Value Description

- 0 No effect.
- Setting a bit clears the corresponding SET[n] bit in the DMAALTSET register meaning that channel [n] is using the primary control structure.

Note: For Ping-Pong and Scatter-Gather cycle types, the μDMA controller automatically sets these bits to select the alternate channel control data structure.

# Register 18: DMA Channel Priority Set (DMAPRIOSET), offset 0x038

Each bit of the **DMAPRIOSET** register represents the corresponding  $\mu$ DMA channel. Setting a bit configures the  $\mu$ DMA channel to have a high priority level. Reading the register returns the status of the channel priority mask.

DMA Channel Priority Set (DMAPRIOSET)


SET[n]

R/W

Base 0x400F.F000

31:0

Offset 0x038
Type R/W, reset 0x0000.0000



Value Description

0x0000.0000 Channel [n] Priority Set

0 μDMA channel [n] is using the default priority level.

1 μDMA channel [n] is using a high priority level.

Bit 0 corresponds to channel 0. A bit can only be cleared by setting the corresponding  $\mathtt{CLR[n]}$  bit in the **DMAPRIOCLR** register.

## Register 19: DMA Channel Priority Clear (DMAPRIOCLR), offset 0x03C

Each bit of the **DMAPRIOCLR** register represents the corresponding  $\mu$ DMA channel. Setting a bit clears the corresponding SET[n] bit in the **DMAPRIOSET** register.


DMA Channel Priority Clear (DMAPRIOCLR)

CLR[n]

WO

Base 0x400F.F000 Offset 0x03C Type WO, reset -

31:0



Channel [n] Priority Clear

Value Description

0 No effect.

Setting a bit clears the corresponding SET[n] bit in the DMAPRIOSET register meaning that channel [n] is using the default priority level.


# Register 20: DMA Bus Error Clear (DMAERRCLR), offset 0x04C

The **DMAERRCLR** register is used to read and clear the  $\mu$ DMA bus error status. The error status is set if the  $\mu$ DMA controller encountered a bus error while performing a transfer. If a bus error occurs on a channel, that channel is automatically disabled by the  $\mu$ DMA controller. The other channels are unaffected.

DMA Bus Error Clear (DMAERRCLR)

Base 0x400F.F000

Offset 0x04C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ERRCLR	R/W1C	0	μDMA Bus Error Status

Value Description

0 No bus error is pending.

A bus error is pending.

This bit is cleared by writing a 1 to it.

# Register 21: DMA Channel Assignment (DMACHASGN), offset 0x500

Each bit of the DMACHASGN register represents the corresponding µDMA channel. Setting a bit selects the secondary channel assignment as specified in Table 7-1 on page 348.


DMA Channel Assignment (DMACHASGN)

CHASGN[n]

R/W

Base 0x400F.F000 Offset 0x500 Type R/W, reset 0x0000.0000

31:0



Value Description

Channel [n] Assignment Select

0 Use the primary channel assignment.

Use the secondary channel assignment.


# Register 22: DMA Channel Interrupt Status (DMACHIS), offset 0x504

Each bit of the **DMACHIS** register represents the corresponding  $\mu$ DMA channel. A bit is set when that  $\mu$ DMA channel causes a completion interrupt. The bits are cleared by a writing a 1.

DMA Channel Interrupt Status (DMACHIS)

Base 0x400F.F000

Offset 0x504 Type R/W1C, reset 0x0000.0000



Value Description

- 1 The corresponding µDMA channel caused an interrupt.
- 0 The corresponding μDMA channel has not caused an interrupt.


This bit is cleared by writing a 1 to it.

# Register 23: DMA Peripheral Identification 0 (DMAPeriphID0), offset 0xFE0

The **DMAPeriphIDn** registers are hard-coded, and the fields within the registers determine the reset values.

## DMA Peripheral Identification 0 (DMAPeriphID0)

Base 0x400F.F000 Offset 0xFE0 Type RO, reset 0x0000.0030




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID0	RO	0x30	μDMA Peripheral ID Register [7:0] Can be used by software to identify the presence of this peripheral.

# Register 24: DMA Peripheral Identification 1 (DMAPeriphID1), offset 0xFE4

The **DMAPeriphIDn** registers are hard-coded, and the fields within the registers determine the reset values.

DMA Peripheral Identification 1 (DMAPeriphID1)

Base 0x400F.F000 Offset 0xFE4 Type RO, reset 0x0000.00B2




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID1	RO	0xB2	μDMA Peripheral ID Register [15:8]
				Can be used by software to identify the presence of this peripheral.

# Register 25: DMA Peripheral Identification 2 (DMAPeriphID2), offset 0xFE8

The **DMAPeriphIDn** registers are hard-coded, and the fields within the registers determine the reset values.

## DMA Peripheral Identification 2 (DMAPeriphID2)

Base 0x400F.F000 Offset 0xFE8 Type RO, reset 0x0000.000B



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID2	RO	0x0B	μDMA Peripheral ID Register [23:16]


Can be used by software to identify the presence of this peripheral.

# Register 26: DMA Peripheral Identification 3 (DMAPeriphID3), offset 0xFEC

The **DMAPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

DMA Peripheral Identification 3 (DMAPeriphID3)

Base 0x400F.F000 Offset 0xFEC Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID3	RO	0x00	μDMA Peripheral ID Register [31:24]
				Can be used by software to identify the presence of this peripheral.

# Register 27: DMA Peripheral Identification 4 (DMAPeriphID4), offset 0xFD0

The **DMAPeriphIDn** registers are hard-coded, and the fields within the registers determine the reset values.

## DMA Peripheral Identification 4 (DMAPeriphID4)

Base 0x400F.F000 Offset 0xFD0 Type RO, reset 0x0000.0004



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID4	RO	0x04	μDMA Peripheral ID Register


Can be used by software to identify the presence of this peripheral.

# Register 28: DMA PrimeCell Identification 0 (DMAPCellID0), offset 0xFF0

The **DMAPCellIDn** registers are hard-coded, and the fields within the registers determine the reset values.

DMA PrimeCell Identification 0 (DMAPCellID0)

Base 0x400F.F000 Offset 0xFF0 Type RO, reset 0x0000.000D



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID0	RO	0x0D	μDMA PrimeCell ID Register [7:0]


Provides software a standard cross-peripheral identification system.

# Register 29: DMA PrimeCell Identification 1 (DMAPCellID1), offset 0xFF4

The **DMAPCellIDn** registers are hard-coded, and the fields within the registers determine the reset values.

DMA PrimeCell Identification 1 (DMAPCellID1)

Base 0x400F.F000 Offset 0xFF4 Type RO, reset 0x0000.00F0




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID1	RO	0xF0	μDMA PrimeCell ID Register [15:8]
				Provides software a standard cross-peripheral identification system.

# Register 30: DMA PrimeCell Identification 2 (DMAPCellID2), offset 0xFF8

The **DMAPCellIDn** registers are hard-coded, and the fields within the registers determine the reset values.

DMA PrimeCell Identification 2 (DMAPCelIID2)

Base 0x400F.F000 Offset 0xFF8 Type RO, reset 0x0000.0005



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID2	RO	0x05	μDMA PrimeCell ID Register [23:16]

Provides software a standard cross-peripheral identification system.

# Register 31: DMA PrimeCell Identification 3 (DMAPCellID3), offset 0xFFC

The **DMAPCellIDn** registers are hard-coded, and the fields within the registers determine the reset values.

DMA PrimeCell Identification 3 (DMAPCellID3)

Base 0x400F.F000 Offset 0xFFC Type RO, reset 0x0000.00B1



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID3	RO	0xB1	μDMA PrimeCell ID Register [31:24]

Provides software a standard cross-peripheral identification system.

# 8 General-Purpose Input/Outputs (GPIOs)

The GPIO module is composed of nine physical GPIO blocks, each corresponding to an individual GPIO port (Port A, Port B, Port C, Port D, Port E, Port F, Port G, Port H, Port J). The GPIO module supports up to 65 programmable input/output pins, depending on the peripherals being used.

The GPIO module has the following features:

- Up to 65 GPIOs, depending on configuration
- Highly flexible pin muxing allows use as GPIO or one of several peripheral functions
- 5-V-tolerant in input configuration
- Two means of port access: either Advanced High-Performance Bus (AHB) with better back-to-back access performance, or the legacy Advanced Peripheral Bus (APB) for backwards-compatibility with existing code
- Fast toggle capable of a change every clock cycle for ports on AHB, every two clock cycles for ports on APB
- Programmable control for GPIO interrupts
  - Interrupt generation masking
  - Edge-triggered on rising, falling, or both
  - Level-sensitive on High or Low values
- Bit masking in both read and write operations through address lines
- Can be used to initiate an ADC sample sequence
- Pins configured as digital inputs are Schmitt-triggered
- Programmable control for GPIO pad configuration
  - Weak pull-up or pull-down resistors
  - 2-mA, 4-mA, and 8-mA pad drive for digital communication; up to four pads can sink 18-mA for high-current applications
  - Slew rate control for the 8-mA drive
  - Open drain enables
  - Digital input enables

# 8.1 Signal Description

GPIO signals have alternate hardware functions. The following table lists the GPIO pins and their analog and digital alternate functions. The AINx and VREFA analog signals are not 5-V tolerant and go through an isolation circuit before reaching their circuitry. These signals are configured by clearing the corresponding DEN bit in the GPIO Digital Enable (GPIODEN) register and setting the corresponding AMSEL bit in the GPIO Analog Mode Select (GPIOAMSEL) register. Other analog

signals are 5-V tolerant and are connected directly to their circuitry ( $CO_-$ ,  $CO_+$ ,  $CI_-$ ,  $CI_+$ ,  $CI_-$ 

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.

Table 8-1. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

Table 8-2. GPIO Pins and Alternate Functions (100LQFP)

10	Digital Function (GPIOPCTL PMCx Bit Field Encoding) <sup>a</sup>								ng) <sup>a</sup>				
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PA0	26	-	U0Rx	-	-	-	-	-	-	I2C1SCL	U1Rx	-	-
PA1	27	-	U0Tx	-	-	-	-	-	-	I2C1SDA	UlTx	-	-
PA2	28	-	SSI0Clk	-	-	PWM4	-	-	-	-	I2S0RXSD	-	-
PA3	29	-	SSI0Fss	-	-	PWM5	-	-	-	-	I2SORXMCIK	-	-
PA4	30	-	SSI0Rx	-	-	РWМ6	CAN0Rx	-	-	-	I2SOTXSCK	-	-
PA5	31	-	SSIOTx	-	-	PWM7	CAN0Tx	-	-	-	I2SOTXWS	-	-
PA6	34	-	I2C1SCL	CCP1	-	PWM0	PWM4	CAN0Rx	-	USB0EPEN	U1CTS	-	-
PA7	35	-	I2C1SDA	CCP4	-	PWM1	PWM5	CAN0Tx	CCP3	USB0PFLT	U1DCD	-	-
PB0	66	USB0ID	CCP0	PWM2	-	-	U1Rx	-	-	-	-	-	-
PB1	67	USB0VBUS	CCP2	PWM3	-	CCP1	U1Tx	-	-	-	-	-	-
PB2	72	-	I2C0SCL	IDX0	-	CCP3	CCP0	-	-	USB0EPEN	-	-	-
PB3	65	-	I2C0SDA	Fault0	-	Fault3	-	-	-	USB0PFLT	-	-	-
PB4	92	AIN10 CO-	-	-	-	U2Rx	CAN0Rx	IDX0	U1Rx	EPIOS23	-	-	-
PB5	91	AIN11 C1-	C0o	CCP5	CCP6	CCP0	CAN0Tx	CCP2	UlTx	EPI0S22	-	-	-
PB6	90	VREFA C0+	CCP1	CCP7	C0o	Fault1	IDX0	CCP5	-	-	I2S0TXSCK	-	-
PB7	89	-	-	-	-	NMI	-	-	-	-	-	-	-
PC0	80	-	-	-	TCK SWCLK	-	-	-	-	-	-	-	-

Table 8-2. GPIO Pins and Alternate Functions (100LQFP) (continued)

10	D:	Analog			Digi	tal Functi	on (GPIO	PCTL PM	Cx Bit Fiel	d Encodi	ng) <sup>a</sup>		
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PC1	79	-	-	-	TMS SWDIO	-	-	-	-	-	-	-	-
PC2	78	-	-	-	TDI	-	-	-	-	-	-	-	-
PC3	77	-	-	-	TDO SWO	-	-	-	-	-	-	-	-
PC4	25	-	CCP5	PhA0	-	РWМ6	CCP2	CCP4	-	EPI0S2	CCP1	-	-
PC5	24	C1+	CCP1	C1o	C0o	Fault2	CCP3	USB0EPEN	-	EPI0S3	-	-	-
PC6	23	C2+	CCP3	PhB0	C20	РИМ7	U1Rx	CCP0	USB0PFLT	EPI0S4	-	-	-
PC7	22	C2-	CCP4	PhB0	-	CCP0	UlTx	USB0PFLT	Clo	EPI0S5	-	-	-
PD0	10	AIN15	PWM0	CAN0Rx	IDX0	U2Rx	U1Rx	CCP6	-	I2SORXSCK	Ulcts	-	-
PD1	11	AIN14	PWM1	CAN0Tx	PhA0	U2Tx	UlTx	CCP7	-	I2SORXWS	U1DCD	CCP2	PhB1
PD2	12	AIN13	U1Rx	CCP6	PWM2	CCP5	-	-	-	EPI0S20	-	-	-
PD3	13	AIN12	U1Tx	CCP7	PWM3	CCP0	-	-	-	EPI0S21	-	-	-
PD4	97	AIN7	CCP0	CCP3	-	-	-	-	-	I2S0RXSD	U1RI	EPIOS19	-
PD5	98	AIN6	CCP2	CCP4	-	-	-	-	-	I2SORXMOLK	U2Rx	EPIOS28	-
PD6	99	AIN5	Fault0	-	-	-	-	-	-	I2SOTXSCK	U2Tx	EPIOS29	-
PD7	100	AIN4	IDX0	C0o	CCP1	-	-	-	-	I2SOTXWS	U1DTR	EPIOS30	-
PE0	74	-	PWM4	SSI1Clk	CCP3	-	-	-	-	EPIOS8	USB0PFLT	-	-
PE1	75	-	PWM5	SSI1Fss	Fault0	CCP2	CCP6	-	-	EPIOS9	-	-	-
PE2	95	AIN9	CCP4	SSI1Rx	PhB1	PhA0	CCP2	-	-	EPI0S24	-	-	-
PE3	96	AIN8	CCP1	SSI1Tx	PhA1	PhB0	CCP7	-	-	EPI0S25	-	-	-
PE4	6	AIN3	CCP3	-	-	Fault0	U2Tx	CCP2	-	-	I2SOTXWS	-	-
PE5	5	AIN2	CCP5	-	-	-	-	-	-	-	I2SOTXSD	-	-
PE6	2	AIN1	PWM4	C1o	-	-	-	-	-	-	U1CTS	-	-
PE7	1	AIN0	PWM5	C20	-	-	-	-	-	-	U1DCD	-	-
PF0	47	-	CAN1Rx	PhB0	PWM0	-	-	-	-	I2SOTXSD	U1DSR	-	-
PF1	61	-	CAN1Tx	IDX1	PWM1	-	-	-	-	12S01XM1K	Ulrts	CCP3	-
PF2	60	-	LED1	PWM4	-	PWM2	-	-	-	-	SSI1Clk	-	-
PF3	59	-	LED0	PWM5	-	РWМ3	-	-	-	-	SSI1Fss	-	-
PF4	42	-	CCP0	C0o	-	Fault0	-	-	-	EPIOS12	SSI1Rx	-	-
PF5	41	-	CCP2	C1o	-	-	-	-	-	EPIOS15	SSI1Tx	-	-
PG0	19	-	U2Rx	PWM0	I2C1SCL	PWM4	-	-	USB0EPEN	EPIOS13	-	-	-
PG1	18	-	U2Tx	PWM1	I2C1SDA	PWM5	-	-	-	EPIOS14	-	-	-
PG7	36	-	PhB1	-	-	PWM7	-	-	-	CCP5	EPI0S31	-	-
PH0	86	-	CCP6	PWM2	-	-	-	-	-	EPI0S6	PWM4	-	-
PH1	85	-	CCP7	PWM3	-	-	-	-	-	EPI0S7	PWM5	-	-
PH2	84	-	IDX1	C1o	-	Fault3	-	-	-	EPI0S1	-	-	-
РН3	83	-	PhB0	Fault0	-	USB0EPEN	-	-	-	EPI0S0	-	-	-
PH4	76	-	-	-	-	USB0PFLT	-	-	-	EPIOS10	-	-	SSI1Clk
PH5	63	-	-	-	-	-	-	-	-	EPIOS11	-	Fault2	SSI1Fss
РН6	62	-	-	-	-	-	-	-	-	EPI0S26	-	PWM4	SSI1Rx

Table 8-2. GPIO Pins and Alternate Functions (100LQFP) (continued)

10	Pin	Analog			Digi	ital Functi	on (GPIO	PCTL PM	Cx Bit Fie	ld Encodi	ng) <sup>a</sup>		
10	PIII	Function	1	2	3	4	5	6	7	8	9	10	11
PH7	15	-	-	-	-	-	-	-	-	EPI0S27	-	PWM5	SSI1Tx
рј0	14	-	-	-	-	-	-	-	-	EPIOS16	-	PWM0	I2C1SCL
PJ1	87	-	-	-	-	-	-	-	-	EPIOS17	USB0PFLT	PWM1	I2C1SDA
РЈ2	39	-	-	-	-	-	-	-	-	EPIOS18	CCP0	Fault0	-
рј3	50	-	-	-	-	-	-	-	-	EPIOS19	Ulcts	CCP6	-
рј4	52	-	-	-	-	-	-	-	-	EPIOS28	U1DCD	CCP4	-
PJ5	53	-	-	-	-	-	-	-	-	EPIOS29	U1DSR	CCP2	-
РЈ6	54	-	-	-	-	-	-	-	-	EPIOS30	Ulrts	CCP1	-
рј7	55	-	-	-	-	-	-	-	-	-	U1DTR	CCP0	-

a. The digital signals that are shaded gray are the power-on default values for the corresponding GPIO pin.

Table 8-3. GPIO Pins and Alternate Functions (108BGA)

10	Pin	Analog			Digi	ital Functi	ion (GPIO	PCTL PM	Cx Bit Fie	ld Encodi	ng) <sup>a</sup>		
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PA0	L3	-	U0Rx	-	-	-	-	-	-	I2C1SCL	U1Rx	-	-
PA1	МЗ	-	U0Tx	-	-	-	-	-	-	I2C1SDA	U1Tx	-	-
PA2	M4	-	SSI0Clk	-	-	PWM4	-	-	-	-	I2S0RXSD	-	-
PA3	L4	-	SSI0Fss	-	-	PWM5	-	-	-	-	I2SORXMOLK	-	-
PA4	L5	-	SSI0Rx	-	-	PWM6	CAN0Rx	-	-	-	I2SOTXSCK	-	-
PA5	M5	-	SSIOTx	-	-	PWM7	CAN0Tx	-	-	-	I2SOTXWS	-	-
PA6	L6	-	I2C1SCL	CCP1	-	PWM0	PWM4	CAN0Rx	-	USB0EPEN	U1CTS	-	-
PA7	M6	-	I2C1SDA	CCP4	-	PWM1	PWM5	CAN0Tx	CCP3	USB0PFLT	U1DCD	-	-
PB0	E12	USB0ID	CCP0	PWM2	-	-	U1Rx	-	-	-	-	-	-
PB1	D12	USB0VBUS	CCP2	PWM3	-	CCP1	U1Tx	-	-	-	-	-	-
PB2	A11	-	I2C0SCL	IDX0	-	CCP3	CCP0	-	-	USB0EPEN	-	-	-
PB3	E11	-	I2C0SDA	Fault0	-	Fault3	-	-	-	USB0PFLT	-	-	-
PB4	A6	AIN10 C0-	-	-	-	U2Rx	CAN0Rx	IDX0	U1Rx	EPI0S23	-	-	-
PB5	В7	AIN11 C1-	C00	CCP5	CCP6	CCP0	CAN0Tx	CCP2	U1Tx	EPI0S22	-	-	-
PB6	A7	VREFA C0+	CCP1	CCP7	C00	Fault1	IDX0	CCP5	-	-	I2S0IXSCK	-	-
PB7	A8	-	-	-	-	NMI	-	-	-	-	-	-	-
PC0	A9	-	-	-	TCK SWCLK	-	-	-	-	-	-	-	-
PC1	В9	-	-	-	TMS SWDIO	-	-	-	-	-	-	-	-
PC2	В8	-	-	-	TDI	-	-	-	-	-	-	-	-
PC3	A10	-	-	-	TDO SWO	-	-	-	-	-	-	-	-
PC4	L1	-	CCP5	PhA0	-	PWM6	CCP2	CCP4	-	EPI0S2	CCP1	-	-
PC5	M1	C1+	CCP1	C10	C0o	Fault2	CCP3	USB0EPEN	-	EPI0S3	-	-	-

Table 8-3. GPIO Pins and Alternate Functions (108BGA) (continued)

		Analog			Digi	ital Function (GPIOPCTL PMCx Bit Field Encoding) <sup>a</sup>							
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PC6	M2	C2+	CCP3	PhB0	C20	РWM7	U1Rx	CCP0	USB0PFLT	EPI0S4	-	-	-
PC7	L2	C2-	CCP4	PhB0	-	CCP0	UlTx	USB0PFLT	C10	EPI0S5	-	-	-
PD0	G1	AIN15	PWM0	CAN0Rx	IDX0	U2Rx	U1Rx	CCP6	-	I2SORXSCK	U1CTS	-	-
PD1	G2	AIN14	PWM1	CAN0Tx	PhA0	U2Tx	UlTx	CCP7	-	I2SORXWS	U1DCD	CCP2	PhB1
PD2	H2	AIN13	U1Rx	CCP6	PWM2	CCP5	-	-	-	EPI0S20	-	-	-
PD3	H1	AIN12	U1Tx	CCP7	PWM3	CCP0	-	-	-	EPI0S21	-	-	-
PD4	B5	AIN7	CCP0	CCP3	-	-	-	-	-	I2S0RXSD	U1RI	EPIOS19	-
PD5	C6	AIN6	CCP2	CCP4	-	-	-	-	-	I2SORXMOLK	U2Rx	EPIOS28	-
PD6	A3	AIN5	Fault0	-	-	-	-	-	-	I2SOTXSCK	U2Tx	EPI0S29	-
PD7	A2	AIN4	IDX0	C0o	CCP1	-	-	-	-	I2SOTXWS	U1DTR	EPIOS30	-
PE0	B11	-	PWM4	SSI1Clk	CCP3	-	-	-	-	EPIOS8	USB0PFLT	-	-
PE1	A12	-	PWM5	SSI1Fss	Fault0	CCP2	CCP6	-	-	EPIOS9	-	-	-
PE2	A4	AIN9	CCP4	SSI1Rx	PhB1	PhA0	CCP2	-	-	EPI0S24	-	-	-
PE3	B4	AIN8	CCP1	SSI1Tx	PhA1	PhB0	CCP7	-	-	EPI0S25	-	-	-
PE4	B2	AIN3	CCP3	-	-	Fault0	U2Tx	CCP2	-	-	I2SOTXWS	-	-
PE5	В3	AIN2	CCP5	-	-	-	-	-	-	-	I2SOTXSD	-	-
PE6	A1	AIN1	PWM4	C1o	-	-	-	-	-	-	Ulcts	-	-
PE7	B1	AIN0	PWM5	C20	-	-	-	-	-	-	U1DCD	-	-
PF0	M9	-	CAN1Rx	PhB0	PWM0	-	-	-	-	I2S0TXSD	U1DSR	-	-
PF1	H12	-	CAN1Tx	IDX1	PWM1	-	-	-	-	I2SOIXMCLK	Ulrts	CCP3	-
PF2	J11	-	LED1	PWM4	-	PWM2	-	-	-	-	SSI1Clk	-	-
PF3	J12	-	LED0	PWM5	-	PWM3	-	-	-	-	SSI1Fss	-	-
PF4	K4	-	CCP0	C0o	-	Fault0	-	-	-	EPIOS12	SSI1Rx	-	-
PF5	K3	-	CCP2	C10	-	-	-	-	-	EPIOS15	SSI1Tx	-	-
PG0	K1	-	U2Rx	PWM0	I2C1SCL	PWM4	-	-	USB0EPEN	EPIOS13	-	-	-
PG1	K2	-	U2Tx	PWM1	I2C1SDA	PWM5	-	-	-	EPIOS14	-	-	-
PG7	C10	-	PhB1	-	-	PWM7	-	-	-	CCP5	EPI0S31	-	-
PH0	C9	-	CCP6	PWM2	-	-	-	-	-	EPI0S6	PWM4	-	-
PH1	C8	-	CCP7	PWM3	-	-	-	-	-	EPI0S7	PWM5	-	-
PH2	D11	-	IDX1	C1o	-	Fault3	-	-	-	EPI0S1	-	-	-
PH3	D10	-	PhB0	Fault0	-	USB0EPEN	-	-	-	EPI0S0	-	-	-
PH4	B10	-	-	-	-	USB0PFLT	-	-	-	EPIOS10	-	-	SSI1Clk
PH5	F10	-	-	-	-	-	-	-	-	EPIOS11	-	Fault2	SSI1Fss
РН6	G3	-	-	-	-	-	-	-	-	EPI0S26	-	PWM4	SSI1Rx
PH7	H3	-	-	-	-	-	-	-	-	EPI0S27	-	PWM5	SSI1Tx
PJ0	F3	-	-	-	-	-	-	-	-	EPIOS16	-	PWM0	I2C1SCL
PJ1	B6	-	-	-	-	-	-	-	-	EPIOS17	USB0PFLT	PWM1	I2C1SDA
PJ2	K6	-	-	-	-	-	-	-	-	EPIOS18	CCP0	Fault0	-
РЈ3	M10	-	-	-	-	-	-	-	-	EPIOS19	U1CTS	CCP6	-
рј4	K11	-	-	-	-	-	-	-	-	EPI0S28	U1DCD	CCP4	-

Table 8-3. GPIO Pins and Alternate Functions (108BGA) (continued)


10	Pin	Analog			Digi	ital Functi	on (GPIO	PCTL PM	Cx Bit Fie	ld Encodii	ng) <sup>a</sup>		
	F 1111	Function	1	2	3	4	5	6	7	8	9	10	11
PJ5	K12	-	-	-	-	-	-	-	-	EPI0S29	U1DSR	CCP2	-
РЈ6	L10	-	-	-	-	-	-	-	-	EPIOS30	U1RTS	CCP1	-
PJ7	L12	-	-	-	-	-	-	-	-	-	U1DTR	CCP0	-

a. The digital signals that are shaded gray are the power-on default values for the corresponding GPIO pin.

# 8.2 Functional Description

Each GPIO port is a separate hardware instantiation of the same physical block (see Figure 8-1 on page 412 and Figure 8-2 on page 413). The LM3S9D96 microcontroller contains nine ports and thus nine of these physical GPIO blocks. Note that not all pins may be implemented on every block. Some GPIO pins can function as I/O signals for the on-chip peripheral modules. For information on which GPIO pins are used for alternate hardware functions, refer to Table 24-5 on page 1270.

Figure 8-1. Digital I/O Pads






Figure 8-2. Analog/Digital I/O Pads

### 8.2.1 Data Control

The data control registers allow software to configure the operational modes of the GPIOs. The data direction register configures the GPIO as an input or an output while the data register either captures incoming data or drives it out to the pads.

Caution – It is possible to create a software sequence that prevents the debugger from connecting to the Stellaris® microcontroller. If the program code loaded into flash immediately changes the JTAG pins to their GPIO functionality, the debugger may not have enough time to connect and halt the controller before the JTAG pin functionality switches. As a result, the debugger may be locked out of the part. This issue can be avoided with a software routine that restores JTAG functionality based on an external or software trigger.

## 8.2.1.1 Data Direction Operation

The **GPIO Direction (GPIODIR)** register (see page 421) is used to configure each individual pin as an input or output. When the data direction bit is cleared, the GPIO is configured as an input, and the corresponding data register bit captures and stores the value on the GPIO port. When the data direction bit is set, the GPIO is configured as an output, and the corresponding data register bit is driven out on the GPIO port.


## 8.2.1.2 Data Register Operation

To aid in the efficiency of software, the GPIO ports allow for the modification of individual bits in the **GPIO Data (GPIODATA)** register (see page 420) by using bits [9:2] of the address bus as a mask. In this manner, software drivers can modify individual GPIO pins in a single instruction without affecting the state of the other pins. This method is more efficient than the conventional method of performing a read-modify-write operation to set or clear an individual GPIO pin. To implement this feature, the **GPIODATA** register covers 256 locations in the memory map.

During a write, if the address bit associated with that data bit is set, the value of the **GPIODATA** register is altered. If the address bit is cleared, the data bit is left unchanged.


For example, writing a value of 0xEB to the address GPIODATA + 0x098 has the results shown in Figure 8-3, where u indicates that data is unchanged by the write.

Figure 8-3. GPIODATA Write Example



During a read, if the address bit associated with the data bit is set, the value is read. If the address bit associated with the data bit is cleared, the data bit is read as a zero, regardless of its actual value. For example, reading address GPIODATA + 0x0C4 yields as shown in Figure 8-4.

Figure 8-4. GPIODATA Read Example



## 8.2.2 Interrupt Control

The interrupt capabilities of each GPIO port are controlled by a set of seven registers. These registers are used to select the source of the interrupt, its polarity, and the edge properties. When one or more GPIO inputs cause an interrupt, a single interrupt output is sent to the interrupt controller for the entire GPIO port. For edge-triggered interrupts, software must clear the interrupt to enable any further interrupts. For a level-sensitive interrupt, the external source must hold the level constant for the interrupt to be recognized by the controller.

Three registers define the edge or sense that causes interrupts:

■ GPIO Interrupt Sense (GPIOIS) register (see page 422)

- GPIO Interrupt Both Edges (GPIOIBE) register (see page 423)
- GPIO Interrupt Event (GPIOIEV) register (see page 424)

Interrupts are enabled/disabled via the GPIO Interrupt Mask (GPIOIM) register (see page 425).

When an interrupt condition occurs, the state of the interrupt signal can be viewed in two locations: the **GPIO Raw Interrupt Status (GPIORIS)** and **GPIO Masked Interrupt Status (GPIOMIS)** registers (see page 426 and page 427). As the name implies, the **GPIOMIS** register only shows interrupt conditions that are allowed to be passed to the interrupt controller. The **GPIORIS** register indicates that a GPIO pin meets the conditions for an interrupt, but has not necessarily been sent to the interrupt controller.

Interrupts are cleared by writing a 1 to the appropriate bit of the **GPIO Interrupt Clear (GPIOICR)** register (see page 429).

When programming the interrupt control registers (**GPIOIS**, **GPIOIBE**, or **GPIOIEV**), the interrupts should be masked (**GPIOIM** cleared). Writing any value to an interrupt control register can generate a spurious interrupt if the corresponding bits are enabled.

## 8.2.2.1 ADC Trigger Source

In addition to providing GPIO functionality, PB4 can also be used as an external trigger for the ADC. If PB4 is configured as a non-masked interrupt pin (the appropriate bit of GPIOIM is set), an interrupt for Port B is generated, and an external trigger signal is sent to the ADC. If the **ADC Event Multiplexer Select (ADCEMUX)** register is configured to use the external trigger, an ADC conversion is initiated. See page 642.

If no other Port B pins are being used to generate interrupts, the **Interrupt 0-31 Set Enable (EN0)** register can disable the Port B interrupts, and the ADC interrupt can be used to read back the converted data. Otherwise, the Port B interrupt handler must ignore and clear interrupts on PB4 and wait for the ADC interrupt, or the ADC interrupt must be disabled in the **EN0** register and the Port B interrupt handler must poll the ADC registers until the conversion is completed. See page 129 for more information.

## 8.2.3 Mode Control

The GPIO pins can be controlled by either software or hardware. Software control is the default for most signals and corresponds to the GPIO mode, where the **GPIODATA** register is used to read or write the corresponding pins. When hardware control is enabled via the **GPIO Alternate Function Select (GPIOAFSEL)** register (see page 430), the pin state is controlled by its alternate function (that is, the peripheral).

Further pin muxing options are provided through the **GPIO Port Control (GPIOPCTL)** register which selects one of several peripheral functions for each GPIO. For information on the configuration options, refer to Table 24-5 on page 1270.

**Note:** If any pin is to be used as an ADC input, the appropriate bit in the **GPIOAMSEL** register must be set to disable the analog isolation circuit.

### 8.2.4 Commit Control

The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see

page 441) are not committed to storage unless the **GPIO Lock (GPIOLOCK)** register (see page 443) has been unlocked and the appropriate bits of the **GPIO Commit (GPIOCR)** register (see page 444) have been set.

### 8.2.5 Pad Control

The pad control registers allow software to configure the GPIO pads based on the application requirements. The pad control registers include the **GPIODR2R**, **GPIODR4R**, **GPIODR8R**, **GPIODDR**, **GPIOPUR**, **GPIOPDR**, **GPIOPDR**, and **GPIODEN** registers. These registers control drive strength, open-drain configuration, pull-up and pull-down resistors, slew-rate control and digital input enable for each GPIO.

## 8.2.6 Identification

The identification registers configured at reset allow software to detect and identify the module as a GPIO block. The identification registers include the **GPIOPeriphID0-GPIOPeriphID7** registers as well as the **GPIOPCeIIID0-GPIOPCeIIID3** registers.

# 8.3 Initialization and Configuration

The GPIO modules may be accessed via two different memory apertures. The legacy aperture, the Advanced Peripheral Bus (APB), is backwards-compatible with previous Stellaris parts. The other aperture, the Advanced High-Performance Bus (AHB), offers the same register map but provides better back-to-back access performance than the APB bus. These apertures are mutually exclusive. The aperture enabled for a given GPIO port is controlled by the appropriate bit in the **GPIOHBCTL** register (see page 227).

To use the pins in a particular GPIO port, the clock for the port must be enabled by setting the appropriate GPIO Port bit field (GPIOn) in the **RCGC2** register (see page 284).

When the internal POR signal is asserted and until otherwise configured, all GPIO pins are configured to be undriven (tristate): **GPIOAFSEL=**0, **GPIODEN=**0, **GPIOPDR=**0, and **GPIOPUR=**0, except for the pins shown in Table 8-1 on page 408. Table 8-4 on page 416 shows all possible configurations of the GPIO pads and the control register settings required to achieve them. Table 8-5 on page 417 shows how a rising edge interrupt is configured for pin 2 of a GPIO port.

Table 8-4. GPIO Pad Configuration Examples

Configuration	GPIO Reg	gister Bit Va	alue <sup>a</sup>							
Configuration	AFSEL	DIR	ODR	DEN	PUR	PDR	DR2R	DR4R	DR8R	SLR
Digital Input (GPIO)	0	0	0	1	?	?	Х	Х	Х	Х
Digital Output (GPIO)	0	1	0	1	?	?	?	?	?	?
Open Drain Output (GPIO)	0	1	1	1	Х	Х	?	?	?	?
Open Drain Input/Output (I <sup>2</sup> C)	1	Х	1	1	Х	Х	?	?	?	?
Digital Input (Timer CCP)	1	Х	0	1	?	?	Х	Х	Х	X
Digital Input (QEI)	1	Х	0	1	?	?	Х	Х	Х	Х
Digital Output (PWM)	1	Х	0	1	?	?	?	?	?	?
Digital Output (Timer PWM)	1	Х	0	1	?	?	?	?	?	?
Digital Input/Output (SSI)	1	Х	0	1	?	?	?	?	?	?

Table 8-4. GPIO Pad Configuration Examples (continued)

Configuration	GPIO Register Bit Value <sup>a</sup>												
Comiguration	AFSEL	DIR	ODR	DEN	PUR	PDR	DR2R	DR4R	DR8R	SLR			
Digital Input/Output (UART)	1	Х	0	1	?	?	?	?	?	?			
Analog Input (Comparator)	0	0	0	0	0	0	Х	Х	Х	Х			
Digital Output (Comparator)	1	Х	0	1	?	?	?	?	?	?			

a. X=Ignored (don't care bit)

**Table 8-5. GPIO Interrupt Configuration Example** 

Register	Desired Interrupt	Pin 2 Bit \	/alue <sup>a</sup>						
Register	Event Trigger	7	6	5	4	3	2	1	0
GPIOIS	0=edge 1=level	Х	Х	Х	Х	Х	0	Х	Х
GPIOIBE	0=single edge 1=both edges	Х	Х	Х	х	Х	0	х	Х
GPIOIEV	0=Low level, or falling edge 1=High level, or rising edge		Х	Х	Х	Х	1	Х	х
GPIOIM	0=masked 1=not masked	0	0	0	0	0	1	0	0

a. X=Ignored (don't care bit)

# 8.4 Register Map

Table 8-7 on page 418 lists the GPIO registers. Each GPIO port can be accessed through one of two bus apertures. The legacy aperture, the Advanced Peripheral Bus (APB), is backwards-compatible with previous Stellaris parts. The other aperture, the Advanced High-Performance Bus (AHB), offers the same register map but provides better back-to-back access performance than the APB bus.

**Important:** The GPIO registers in this chapter are duplicated in each GPIO block; however, depending on the block, all eight bits may not be connected to a GPIO pad. In those cases, writing to unconnected bits has no effect, and reading unconnected bits returns no meaningful data.

The offset listed is a hexadecimal increment to the register's address, relative to that GPIO port's base address:

- GPIO Port A (APB): 0x4000.4000
- GPIO Port A (AHB): 0x4005.8000
- GPIO Port B (APB): 0x4000.5000
- GPIO Port B (AHB): 0x4005.9000
- GPIO Port C (APB): 0x4000.6000
- GPIO Port C (AHB): 0x4005.A000
- GPIO Port D (APB): 0x4000.7000
- GPIO Port D (AHB): 0x4005.B000

<sup>?=</sup>Can be either 0 or 1, depending on the configuration

- GPIO Port E (APB): 0x4002.4000
- GPIO Port E (AHB): 0x4005.C000
- GPIO Port F (APB): 0x4002.5000
- GPIO Port F (AHB): 0x4005.D000
- GPIO Port G (APB): 0x4002.6000
- GPIO Port G (AHB): 0x4005.E000
- GPIO Port H (APB): 0x4002.7000
- GPIO Port H (AHB): 0x4005.F000
- GPIO Port J (APB): 0x4003.D000
- GPIO Port J (AHB): 0x4006.0000

Note that each GPIO module clock must be enabled before the registers can be programmed (see page 284). There must be a delay of 3 system clocks after the GPIO module clock is enabled before any GPIO module registers are accessed.

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.

Table 8-6. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

The default register type for the **GPIOCR** register is RO for all GPIO pins with the exception of the NMI pin and the four JTAG/SWD pins (PB7 and PC[3:0]). These five pins are the only GPIOs that are protected by the **GPIOCR** register. Because of this, the register type for GPIO Port B7 and GPIO Port C[3:0] is R/W.

The default reset value for the **GPIOCR** register is 0x0000.00FF for all GPIO pins, with the exception of the NMI pin and the four JTAG/SWD pins (PB7 and PC[3:0]). To ensure that the JTAG port is not accidentally programmed as GPIO pins, the PC[3:0] pins default to non-committable. Similarly, to ensure that the NMI pin is not accidentally programmed as a GPIO pin, the PB7 pin defaults to non-committable. Because of this, the default reset value of **GPIOCR** for GPIO Port B is 0x0000.007F while the default reset value of **GPIOCR** for Port C is 0x0000.00F0.

Table 8-7. GPIO Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	GPIODATA	R/W	0x0000.0000	GPIO Data	420
0x400	GPIODIR	R/W	0x0000.0000	GPIO Direction	421
0x404	GPIOIS	R/W	0x0000.0000	GPIO Interrupt Sense	422
0x408	GPIOIBE	R/W	0x0000.0000	GPIO Interrupt Both Edges	423
0x40C	GPIOIEV	R/W	0x0000.0000	GPIO Interrupt Event	424

Table 8-7. GPIO Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x410	GPIOIM	R/W	0x0000.0000	GPIO Interrupt Mask	425
0x414	GPIORIS	RO	0x0000.0000	GPIO Raw Interrupt Status	426
0x418	GPIOMIS	RO	0x0000.0000	GPIO Masked Interrupt Status	427
0x41C	GPIOICR	W1C	0x0000.0000	GPIO Interrupt Clear	429
0x420	GPIOAFSEL	R/W	-	GPIO Alternate Function Select	430
0x500	GPIODR2R	R/W	0x0000.00FF	GPIO 2-mA Drive Select	432
0x504	GPIODR4R	R/W	0x0000.0000	GPIO 4-mA Drive Select	433
0x508	GPIODR8R	R/W	0x0000.0000	GPIO 8-mA Drive Select	434
0x50C	GPIOODR	R/W	0x0000.0000	GPIO Open Drain Select	435
0x510	GPIOPUR	R/W	-	GPIO Pull-Up Select	436
0x514	GPIOPDR	R/W	0x0000.0000	GPIO Pull-Down Select	438
0x518	GPIOSLR	R/W	0x0000.0000	GPIO Slew Rate Control Select	440
0x51C	GPIODEN	R/W	-	GPIO Digital Enable	441
0x520	GPIOLOCK	R/W	0x0000.0001	GPIO Lock	443
0x524	GPIOCR	-	-	GPIO Commit	444
0x528	GPIOAMSEL	R/W	0x0000.0000	GPIO Analog Mode Select	446
0x52C	GPIOPCTL	R/W	-	GPIO Port Control	448
0xFD0	GPIOPeriphID4	RO	0x0000.0000	GPIO Peripheral Identification 4	450
0xFD4	GPIOPeriphID5	RO	0x0000.0000	GPIO Peripheral Identification 5	451
0xFD8	GPIOPeriphID6	RO	0x0000.0000	GPIO Peripheral Identification 6	452
0xFDC	GPIOPeriphID7	RO	0x0000.0000	GPIO Peripheral Identification 7	453
0xFE0	GPIOPeriphID0	RO	0x0000.0061	GPIO Peripheral Identification 0	454
0xFE4	GPIOPeriphID1	RO	0x0000.0000	GPIO Peripheral Identification 1	455
0xFE8	GPIOPeriphID2	RO	0x0000.0018	GPIO Peripheral Identification 2	456
0xFEC	GPIOPeriphID3	RO	0x0000.0001	GPIO Peripheral Identification 3	457
0xFF0	GPIOPCellID0	RO	0x0000.000D	GPIO PrimeCell Identification 0	458
0xFF4	GPIOPCellID1	RO	0x0000.00F0	GPIO PrimeCell Identification 1	459
0xFF8	GPIOPCellID2	RO	0x0000.0005	GPIO PrimeCell Identification 2	460
0xFFC	GPIOPCellID3	RO	0x0000.00B1	GPIO PrimeCell Identification 3	461
	1			The state of the s	

# 8.5 Register Descriptions

The remainder of this section lists and describes the GPIO registers, in numerical order by address offset.

# Register 1: GPIO Data (GPIODATA), offset 0x000

The **GPIODATA** register is the data register. In software control mode, values written in the **GPIODATA** register are transferred onto the GPIO port pins if the respective pins have been configured as outputs through the GPIO Direction (GPIODIR) register (see page 421).

In order to write to GPIODATA, the corresponding bits in the mask, resulting from the address bus bits [9:2], must be set. Otherwise, the bit values remain unchanged by the write.


Similarly, the values read from this register are determined for each bit by the mask bit derived from the address used to access the data register, bits [9:2]. Bits that are set in the address mask cause the corresponding bits in GPIODATA to be read, and bits that are clear in the address mask cause the corresponding bits in **GPIODATA** to be read as 0, regardless of their value.

A read from GPIODATA returns the last bit value written if the respective pins are configured as outputs, or it returns the value on the corresponding input pin when these are configured as inputs. All bits are cleared by a reset.

### GPIO Data (GPIODATA)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x000 Type R/W, reset 0x0000.0000

31 30 29



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DATA	R/W	0x00	GPIO Data


This register is virtually mapped to 256 locations in the address space. To facilitate the reading and writing of data to these registers by independent drivers, the data read from and written to the registers are masked by the eight address lines [9:2]. Reads from this register return its current state. Writes to this register only affect bits that are not masked by ADDR[9:2] and are configured as outputs. See "Data Register Operation" on page 414 for examples of reads and writes.

## Register 2: GPIO Direction (GPIODIR), offset 0x400

The **GPIODIR** register is the data direction register. Setting a bit in the **GPIODIR** register configures the corresponding pin to be an output, while clearing a bit configures the corresponding pin to be an input. All bits are cleared by a reset, meaning all GPIO pins are inputs by default.

## GPIO Direction (GPIODIR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x400 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DIR	R/W	0x00	GPIO Data Direction

- 0 Corresponding pin is an input.
- 1 Corresponding pins is an output.


# Register 3: GPIO Interrupt Sense (GPIOIS), offset 0x404

The **GPIOIS** register is the interrupt sense register. Setting a bit in the **GPIOIS** register configures the corresponding pin to detect levels, while clearing a bit configures the corresponding pin to detect edges. All bits are cleared by a reset.

## GPIO Interrupt Sense (GPIOIS)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x404 Type R/W, reset 0x0000.0000





Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	IS	R/W	0x00	GPIO Interrupt Sense


- 0 The edge on the corresponding pin is detected (edge-sensitive).
- 1 The level on the corresponding pin is detected (level-sensitive).

# Register 4: GPIO Interrupt Both Edges (GPIOIBE), offset 0x408

The **GPIOIBE** register allows both edges to cause interrupts. When the corresponding bit in the **GPIO Interrupt Sense (GPIOIS)** register (see page 422) is set to detect edges, setting a bit in the **GPIOIBE** register configures the corresponding pin to detect both rising and falling edges, regardless of the corresponding bit in the **GPIO Interrupt Event (GPIOIEV)** register (see page 424). Clearing a bit configures the pin to be controlled by the **GPIOIEV** register. All bits are cleared by a reset.

#### GPIO Interrupt Both Edges (GPIOIBE)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x408 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	IBE	R/W	0x00	GPIO Interrupt Both Edges

- Interrupt generation is controlled by the GPIO Interrupt Event (GPIOIEV) register (see page 424).
- 1 Both edges on the corresponding pin trigger an interrupt.


# Register 5: GPIO Interrupt Event (GPIOIEV), offset 0x40C

The **GPIOIEV** register is the interrupt event register. Setting a bit in the **GPIOIEV** register configures the corresponding pin to detect rising edges or high levels, depending on the corresponding bit value in the **GPIO Interrupt Sense (GPIOIS)** register (see page 422). Clearing a bit configures the pin to detect falling edges or low levels, depending on the corresponding bit value in the **GPIOIS** register. All bits are cleared by a reset.

#### GPIO Interrupt Event (GPIOIEV)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000

Offset 0x40C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	IEV	R/W	0x00	GPIO Interrupt Event

- 0 A falling edge or a Low level on the corresponding pin triggers an interrupt.
- A rising edge or a High level on the corresponding pin triggers an interrupt.

## Register 6: GPIO Interrupt Mask (GPIOIM), offset 0x410

The **GPIOIM** register is the interrupt mask register. Setting a bit in the **GPIOIM** register allows interrupts that are generated by the corresponding pin to be sent to the interrupt controller on the combined interrupt signal. Clearing a bit prevents an interrupt on the corresponding pin from being sent to the interrupt controller. All bits are cleared by a reset.

### GPIO Interrupt Mask (GPIOIM)


GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x410 Type R/W, reset 0x0000.0000

Rit/Field

Name

Type

Reset



Ditt icia	Name	Турс	reset	Description
31:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	IME	R/W	0x00	GPIO Interrupt Mask Enable

Description


- 0 The interrupt from the corresponding pin is masked.
- The interrupt from the corresponding pin is sent to the interrupt controller.

# Register 7: GPIO Raw Interrupt Status (GPIORIS), offset 0x414

The **GPIORIS** register is the raw interrupt status register. A bit in this register is set when an interrupt condition occurs on the corresponding GPIO pin. If the corresponding bit in the **GPIO Interrupt Mask (GPIOIM)** register (see page 425) is set, the interrupt is sent to the interrupt controller. Bits read as zero indicate that corresponding input pins have not initiated an interrupt. A bit in this register can be cleared by writing a 1 to the corresponding bit in the **GPIO Interrupt Clear (GPIOICR)** register.

## GPIO Raw Interrupt Status (GPIORIS)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x414



Bivrieid	name	туре	Reset	Description
31:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	RIS	RO	0x00	GPIO Interrupt Raw Status

#### Value Description

- 1 An interrupt condition has occurred on the corresponding pin.
- O An interrupt condition has not occurred on the corresponding pin.

A bit is cleared by writing a 1 to the corresponding bit in the **GPIOICR** register.

## Register 8: GPIO Masked Interrupt Status (GPIOMIS), offset 0x418

The **GPIOMIS** register is the masked interrupt status register. If a bit is set in this register, the corresponding interrupt has triggered an interrupt to the interrupt controller. If a bit is clear, either no interrupt has been generated, or the interrupt is masked.

In addition to providing GPIO functionality, PB4 can also be used as an external trigger for the ADC. If PB4 is configured as a non-masked interrupt pin (the appropriate bit of GPIOIM is set), an interrupt for Port B is generated, and an external trigger signal is sent to the ADC. If the **ADC Event Multiplexer Select (ADCEMUX)** register is configured to use the external trigger, an ADC conversion is initiated. See page 642.


If no other Port B pins are being used to generate interrupts, the **Interrupt 0-31 Set Enable (EN0)** register can disable the Port B interrupts, and the ADC interrupt can be used to read back the converted data. Otherwise, the Port B interrupt handler must ignore and clear interrupts on PB4 and wait for the ADC interrupt, or the ADC interrupt must be disabled in the **EN0** register and the Port B interrupt handler must poll the ADC registers until the conversion is completed. See page 129 for more information.

**GPIOMIS** is the state of the interrupt after masking.

#### GPIO Masked Interrupt Status (GPIOMIS)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002,7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x418

Type RO, reset 0x0000.0000



31:8 reserved RO 0 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
7:0	MIS	RO	0x00	GPIO Masked Interrupt Status
				Value Description
				An interrupt condition on the corresponding pin has triggered an interrupt to the interrupt controller.
				O An interrupt condition on the corresponding pin is masked or has not occurred.
				A bit is cleared by writing a 1 to the corresponding bit in the <b>GPIOICR</b> register.


# Register 9: GPIO Interrupt Clear (GPIOICR), offset 0x41C

The **GPIOICR** register is the interrupt clear register. Writing a 1 to a bit in this register clears the corresponding interrupt bit in the **GPIORIS** and **GPIOMIS** registers. Writing a 0 has no effect.

### GPIO Interrupt Clear (GPIOICR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x41C

Type W1C, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	IC	W1C	0x00	GPIO Interrupt Clear

- 1 The corresponding interrupt is cleared.
- 0 The corresponding interrupt is unaffected.

# Register 10: GPIO Alternate Function Select (GPIOAFSEL), offset 0x420

The **GPIOAFSEL** register is the mode control select register. If a bit is clear, the pin is used as a GPIO and is controlled by the GPIO registers. Setting a bit in this register configures the corresponding GPIO line to be controlled by an associated peripheral. Several possible peripheral functions are multiplexed on each GPIO. The **GPIO Port Control (GPIOPCTL)** register is used to select one of the possible functions. Table 24-5 on page 1270 details which functions are muxed on each GPIO pin. The reset value for this register is 0x0000.0000 for GPIO ports that are not listed in the table below.

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.

Table 8-8. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1


Caution – It is possible to create a software sequence that prevents the debugger from connecting to the Stellaris microcontroller. If the program code loaded into flash immediately changes the JTAG pins to their GPIO functionality, the debugger may not have enough time to connect and halt the controller before the JTAG pin functionality switches. As a result, the debugger may be locked out of the part. This issue can be avoided with a software routine that restores JTAG functionality based on an external or software trigger.

The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see page 441) are not committed to storage unless the GPIO Lock (GPIOLOCK) register (see page 443) has been unlocked and the appropriate bits of the GPIO Commit (GPIOCR) register (see page 444) have been set.

When using the I<sup>2</sup>C module, in addition to setting the **GPIOAFSEL** register bits for the I<sup>2</sup>C clock and data pins, the data pins should be set to open drain using the **GPIO Open Drain Select** (**GPIOODR**) register (see examples in "Initialization and Configuration" on page 416).

### GPIO Alternate Function Select (GPIOAFSEL)

GPIO Port A (APB) base: 0x4000.4000
GPIO Port A (AHB) base: 0x4005.8000
GPIO Port B (APB) base: 0x4005.8000
GPIO Port B (APB) base: 0x4005.9000
GPIO Port B (AHB) base: 0x4005.9000
GPIO Port C (APB) base: 0x4006.6000
GPIO Port C (AHB) base: 0x4000.6000
GPIO Port D (AHB) base: 0x4000.7000
GPIO Port D (AHB) base: 0x4000.7000
GPIO Port D (AHB) base: 0x4005.8000
GPIO Port E (APB) base: 0x4002.4000
GPIO Port E (AHB) base: 0x4002.5000
GPIO Port F (AHB) base: 0x4005.0000
GPIO Port F (AHB) base: 0x4005.0000
GPIO Port G (AHB) base: 0x4005.0000
GPIO Port G (AHB) base: 0x4005.0000
GPIO Port G (AHB) base: 0x4002.7000
GPIO Port H (AHB) base: 0x4002.7000
GPIO Port H (AHB) base: 0x4005.7000
GPIO Port J (AHB) base: 0x4005.0000
GPIO Port J (AHB) base: 0x4005.0000
GPIO Port J (AHB) base: 0x4005.0000
GPIO Port J (AHB) base: 0x4006.0000
GPIO Port J (AHB) base: 0x4006.0000
Offset 0x420
Type R/W, reset -



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	AFSEL	R/W	-	GPIO Alternate Function Select

#### Value Description

- The associated pin functions as a GPIO and is controlled by the GPIO registers.
- The associated pin functions as a peripheral signal and is controlled by the alternate hardware function.

The reset value for this register is 0x0000.0000 for GPIO ports that are not listed in Table 8-1 on page 408.

## Register 11: GPIO 2-mA Drive Select (GPIODR2R), offset 0x500


The **GPIODR2R** register is the 2-mA drive control register. Each GPIO signal in the port can be individually configured without affecting the other pads. When setting the DRV2 bit for a GPIO signal, the corresponding DRV4 bit in the **GPIODR4R** register and DRV8 bit in the **GPIODR8R** register are automatically cleared by hardware. By default, all GPIO pins have 2-mA drive.

## GPIO 2-mA Drive Select (GPIODR2R)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x500 Type R/W, reset 0x0000.00FF

Namo

Dit/Eiold



Divrieiu	ivallie	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DRV2	R/W	0xFF	Output Pad 2-mA Drive Enable

Description

Docot

#### Value Description

- 1 The corresponding GPIO pin has 2-mA drive.
- The drive for the corresponding GPIO pin is controlled by the GPIODR4R or GPIODR8R register.

Setting a bit in either the **GPIODR4** register or the **GPIODR8** register clears the corresponding 2-mA enable bit. The change is effective on the second clock cycle after the write if accessing GPIO via the APB memory aperture. If using AHB access, the change is effective on the next clock cycle.

# Register 12: GPIO 4-mA Drive Select (GPIODR4R), offset 0x504


The **GPIODR4R** register is the 4-mA drive control register. Each GPIO signal in the port can be individually configured without affecting the other pads. When setting the DRV4 bit for a GPIO signal, the corresponding DRV2 bit in the **GPIODR2R** register and DRV8 bit in the **GPIODR8R** register are automatically cleared by hardware.

### GPIO 4-mA Drive Select (GPIODR4R)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x504 Type R/W, reset 0x0000.0000

Namo

Dit/Eiold



Divi leiu	Name	Type	Neset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DRV4	R/W	0x00	Output Pad 4-mA Drive Enable

Description

Docot

#### Value Description

- 1 The corresponding GPIO pin has 4-mA drive.
- The drive for the corresponding GPIO pin is controlled by the GPIODR2R or GPIODR8R register.

Setting a bit in either the **GPIODR2** register or the **GPIODR8** register clears the corresponding 4-mA enable bit. The change is effective on the second clock cycle after the write if accessing GPIO via the APB memory aperture. If using AHB access, the change is effective on the next clock cycle.


### Register 13: GPIO 8-mA Drive Select (GPIODR8R), offset 0x508

The **GPIODR8R** register is the 8-mA drive control register. Each GPIO signal in the port can be individually configured without affecting the other pads. When setting the DRV8 bit for a GPIO signal, the corresponding DRV2 bit in the **GPIODR2R** register and DRV4 bit in the **GPIODR4R** register are automatically cleared by hardware. The 8-mA setting is also used for high-current operation.

**Note:** There is no configuration difference between 8-mA and high-current operation. The additional current capacity results from a shift in the V<sub>OH</sub>/V<sub>OL</sub> levels. See "Recommended Operating Conditions" on page 1317 for further information.

### GPIO 8-mA Drive Select (GPIODR8R)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port F (APR) base: 0x4002 4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x508



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DRV8	R/W	0x00	Output Pad 8-mA Drive Enable

#### Value Description

- 1 The corresponding GPIO pin has 8-mA drive.
- The drive for the corresponding GPIO pin is controlled by the GPIODR2R or GPIODR4R register.

Setting a bit in either the **GPIODR2** register or the **GPIODR4** register clears the corresponding 8-mA enable bit. The change is effective on the second clock cycle after the write if accessing GPIO via the APB memory aperture. If using AHB access, the change is effective on the next clock cycle.


# Register 14: GPIO Open Drain Select (GPIOODR), offset 0x50C


The **GPIOODR** register is the open drain control register. Setting a bit in this register enables the open-drain configuration of the corresponding GPIO pad. When open-drain mode is enabled, the corresponding bit should also be set in the **GPIO Digital Enable (GPIODEN)** register (see page 441). Corresponding bits in the drive strength and slew rate control registers (**GPIODR2R**, **GPIODR4R**, **GPIODR8R**, and **GPIOSLR**) can be set to achieve the desired rise and fall times. The GPIO acts as an input if the corresponding bit in the **GPIODIR** register is cleared. If open drain is selected while the GPIO is configured as an input, the GPIO will remain an input and the open-drain selection has no effect until the GPIO is changed to an output.

When using the I<sup>2</sup>C module, in addition to configuring the pin to open drain, the **GPIO Alternate Function Select (GPIOAFSEL)** register bits for the I<sup>2</sup>C clock and data pins should be set (see examples in "Initialization and Configuration" on page 416).

### GPIO Open Drain Select (GPIOODR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x50C





Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	ODE	R/W	0x00	Output Pad Open Drain Enable

### Value Description

- 1 The corresponding pin is configured as open drain.
- 0 The corresponding pin is not configured as open drain.

### Register 15: GPIO Pull-Up Select (GPIOPUR), offset 0x510

The **GPIOPUR** register is the pull-up control register. When a bit is set, a weak pull-up resistor on the corresponding GPIO signal is enabled. Setting a bit in **GPIOPUR** automatically clears the corresponding bit in the **GPIO Pull-Down Select (GPIOPDR)** register (see page 438). Write access to this register is protected with the **GPIOCR** register. Bits in **GPIOCR** that are cleared prevent writes to the equivalent bit in this register.

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.


Table 8-9. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

Note: The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see page 441) are not committed to storage unless the GPIO Lock (GPIOLOCK) register (see page 443) has been unlocked and the appropriate bits of the GPIO Commit (GPIOCR) register (see page 444) have been set.

#### GPIO Pull-Up Select (GPIOPUR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x510



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PUE	R/W	-	Pad Weak Pull-Up Enable
				Value Description  The corresponding pin's weak pull-up resistor is disabled.
				1 The corresponding pin's weak pull-up resistor is enabled.

Setting a bit in the **GPIOPDR** register clears the corresponding bit in the **GPIOPUR** register. The change is effective on the second clock cycle after the write if accessing GPIO via the APB memory aperture. If using AHB access, the change is effective on the next clock cycle.

The reset value for this register is 0x0000.0000 for GPIO ports that are not listed in Table 8-1 on page 408.

### Register 16: GPIO Pull-Down Select (GPIOPDR), offset 0x514

The **GPIOPDR** register is the pull-down control register. When a bit is set, a weak pull-down resistor on the corresponding GPIO signal is enabled. Setting a bit in **GPIOPDR** automatically clears the corresponding bit in the **GPIO Pull-Up Select (GPIOPUR)** register (see page 436).

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.


Table 8-10. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

Note: The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see page 441) are not committed to storage unless the GPIO Lock (GPIOLOCK) register (see page 443) has been unlocked and the appropriate bits of the GPIO Commit (GPIOCR) register (see page 444) have been set.

#### GPIO Pull-Down Select (GPIOPDR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x514 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PDE	R/W	0x00	Pad Weak Pull-Down Enable
				Value Description  O The corresponding pin's weak pull-down resistor is disabled

- The corresponding pin's weak pull-down resistor is disabled.
- 1 The corresponding pin's weak pull-down resistor is enabled.


Setting a bit in the GPIOPUR register clears the corresponding bit in the **GPIOPDR** register. The change is effective on the second clock cycle after the write if accessing GPIO via the APB memory aperture. If using AHB access, the change is effective on the next clock cycle.

# Register 17: GPIO Slew Rate Control Select (GPIOSLR), offset 0x518

The **GPIOSLR** register is the slew rate control register. Slew rate control is only available when using the 8-mA drive strength option via the **GPIO 8-mA Drive Select (GPIODR8R)** register (see page 434).

### GPIO Slew Rate Control Select (GPIOSLR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x518 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	SRL	R/W	0x00	Slew Rate Limit Enable (8-mA drive only)

### Value Description

- Slew rate control is enabled for the corresponding pin.
- O Slew rate control is disabled for the corresponding pin.

### Register 18: GPIO Digital Enable (GPIODEN), offset 0x51C

**Note:** Pins configured as digital inputs are Schmitt-triggered.

The **GPIODEN** register is the digital enable register. By default, all GPIO signals except those listed below are configured out of reset to be undriven (tristate). Their digital function is disabled; they do not drive a logic value on the pin and they do not allow the pin voltage into the GPIO receiver. To use the pin as a digital input or output (either GPIO or alternate function), the corresponding GPIODEN bit must be set.

Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.


Table 8-11. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

Note: The GPIO commit control registers provide a layer of protection against accidental programming of critical hardware peripherals. Protection is provided for the NMI pin (PB7) and the four JTAG/SWD pins (PC[3:0]). Writes to protected bits of the GPIO Alternate Function Select (GPIOAFSEL) register (see page 430), GPIO Pull Up Select (GPIOPUR) register (see page 436), GPIO Pull-Down Select (GPIOPDR) register (see page 438), and GPIO Digital Enable (GPIODEN) register (see page 441) are not committed to storage unless the GPIO Lock (GPIOLOCK) register (see page 443) has been unlocked and the appropriate bits of the GPIO Commit (GPIOCR) register (see page 444) have been set.

### GPIO Digital Enable (GPIODEN)

GPIO Port A (APB) base: 0x4000.4000
GPIO Port A (AHB) base: 0x4005.8000
GPIO Port B (APB) base: 0x4005.8000
GPIO Port B (APB) base: 0x4005.9000
GPIO Port C (APB) base: 0x4000.6000
GPIO Port C (AHB) base: 0x4005.A000
GPIO Port D (APB) base: 0x4005.A000
GPIO Port D (APB) base: 0x4005.B000
GPIO Port D (APB) base: 0x4005.B000
GPIO Port E (APB) base: 0x4002.4000
GPIO Port E (AHB) base: 0x4002.5000
GPIO Port F (APB) base: 0x4005.D000
GPIO Port F (APB) base: 0x4005.D000
GPIO Port G (APB) base: 0x4005.E000
GPIO Port G (AHB) base: 0x4002.7000
GPIO Port H (APB) base: 0x4005.F000
GPIO Port J (APB) base: 0x4005.F000
GPIO Port J (APB) base: 0x4005.D000
GPIO Port J (APB) base: 0x4005.D000
GPIO Port J (APB) base: 0x4005.D000
GPIO Port J (APB) base: 0x4003.D000
GPIO Port J (AHB) base: 0x4006.0000
Offset 0x51C
Type R/W, reset -



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DEN	R/W	-	Digital Enable

#### Value Description

- 0 The digital functions for the corresponding pin are disabled.
- The digital functions for the corresponding pin are enabled.


  The reset value for this register is 0x0000.0000 for GPIO ports that are not listed in Table 8-1 on page 408.

### Register 19: GPIO Lock (GPIOLOCK), offset 0x520

The **GPIOLOCK** register enables write access to the **GPIOCR** register (see page 444). Writing 0x4C4F.434B to the **GPIOLOCK** register unlocks the **GPIOCR** register. Writing any other value to the **GPIOLOCK** register re-enables the locked state. Reading the **GPIOLOCK** register returns the lock status rather than the 32-bit value that was previously written. Therefore, when write accesses are disabled, or locked, reading the **GPIOLOCK** register returns 0x0000.0001. When write accesses are enabled, or unlocked, reading the **GPIOLOCK** register returns 0x0000.0000.

#### GPIO Lock (GPIOLOCK)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x520 Type R/W, reset 0x0000.0001



Bit/Field	Name	Type	Reset	Description
31:0	LOCK	R/W (	0x0000 0001	GPIO Lock

A write of the value 0x4C4F.434B unlocks the **GPIO Commit (GPIOCR)** register for write access.A write of any other value or a write to the **GPIOCR** register reapplies the lock, preventing any register updates.

A read of this register returns the following values:

Value Description

0x1 The **GPIOCR** register is locked and may not be modified.

0x0 The **GPIOCR** register is unlocked and may be modified.

### Register 20: GPIO Commit (GPIOCR), offset 0x524

The GPIOCR register is the commit register. The value of the GPIOCR register determines which bits of the GPIOAFSEL, GPIOPUR, GPIOPDR, and GPIODEN registers are committed when a write to these registers is performed. If a bit in the **GPIOCR** register is cleared, the data being written to the corresponding bit in the GPIOAFSEL, GPIOPUR, GPIOPDR, or GPIODEN registers cannot be committed and retains its previous value. If a bit in the **GPIOCR** register is set, the data being written to the corresponding bit of the GPIOAFSEL, GPIOPUR, GPIOPDR, or GPIODEN registers is committed to the register and reflects the new value.


The contents of the GPIOCR register can only be modified if the status in the GPIOLOCK register is unlocked. Writes to the GPIOCR register are ignored if the status in the GPIOLOCK register is locked.

**Important:** This register is designed to prevent accidental programming of the registers that control connectivity to the NMI and JTAG/SWD debug hardware. By initializing the bits of the GPIOCR register to 0 for PB7 and PC[3:0], the NMI and JTAG/SWD debug port can only be converted to GPIOs through a deliberate set of writes to the **GPIOLOCK**, **GPIOCR**, and the corresponding registers.

> Because this protection is currently only implemented on the NMI and JTAG/SWD pins on PB7 and PC[3:0], all of the other bits in the GPIOCR registers cannot be written with 0x0. These bits are hardwired to 0x1, ensuring that it is always possible to commit new values to the GPIOAFSEL, GPIOPUR, GPIOPDR, or GPIODEN register bits of these other pins.

### GPIO Commit (GPIOCR)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x524 Type -, reset



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CR	-	-	GPIO Commit

#### Value Description

- 1 The corresponding GPIOAFSEL, GPIOPUR, GPIOPDR, or GPIODEN bits can be written.
- The corresponding GPIOAFSEL, GPIOPUR, GPIOPDR, or GPIODEN bits cannot be written.

#### Note:

The default register type for the **GPIOCR** register is RO for all GPIO pins with the exception of the NMI pin and the four JTAG/SWD pins (PB7 and PC[3:0]). These five pins are the only GPIOs that are protected by the **GPIOCR** register. Because of this, the register type for GPIO Port B7 and GPIO Port C[3:0] is R/W.

The default reset value for the **GPIOCR** register is 0x0000.00FF for all GPIO pins, with the exception of the NMI pin and the four JTAG/SWD pins (PB7 and PC[3:0]). To ensure that the JTAG port is not accidentally programmed as GPIO pins, the PC[3:0] pins default to non-committable. Similarly, to ensure that the NMI pin is not accidentally programmed as a GPIO pin, the PB7 pin defaults to non-committable. Because of this, the default reset value of **GPIOCR** for GPIO Port B is 0x0000.007F while the default reset value of **GPIOCR** for Port C is 0x0000.00FO.

### Register 21: GPIO Analog Mode Select (GPIOAMSEL), offset 0x528

**Important:** This register is only valid for ports D and E; the corresponding base addresses for the remaining ports are not valid.

If any pin is to be used as an ADC input, the appropriate bit in **GPIOAMSEL** must be set to disable the analog isolation circuit.


The **GPIOAMSEL** register controls isolation circuits to the analog side of a unified I/O pad. Because the GPIOs may be driven by a 5-V source and affect analog operation, analog circuitry requires isolation from the pins when they are not used in their analog function.

Each bit of this register controls the isolation circuitry for the corresponding GPIO signal. For information on which GPIO pins can be used for ADC functions, refer to Table 24-5 on page 1270.

#### GPIO Analog Mode Select (GPIOAMSEL)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000

Offset 0x528 Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset Description

31:8 reserved RO 0x0000.00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Type	Reset	Description
7:0	GPIOAMSEL	R/W	0x00	GPIO Analog Mode Select

#### Value Description

- 1 The analog function of the pin is enabled, the isolation is disabled, and the pin is capable of analog functions.
- The analog function of the pin is disabled, the isolation is enabled, and the pin is capable of digital functions as specified by the other GPIO configuration registers.

**Note:** This register and bits are only valid for GPIO signals that share analog function through a unified I/O pad.

The reset state of this register is 0 for all signals.

### Register 22: GPIO Port Control (GPIOPCTL), offset 0x52C

The **GPIOPCTL** register is used in conjunction with the **GPIOAFSEL** register and selects the specific peripheral signal for each GPIO pin when using the alternate function mode. Most bits in the **GPIOAFSEL** register are cleared on reset, therefore most GPIO pins are configured as GPIOs by default. When a bit is set in the **GPIOAFSEL** register, the corresponding GPIO signal is controlled by an associated peripheral. The **GPIOPCTL** register selects one out of a set of peripheral functions for each GPIO, providing additional flexibility in signal definition. For information on the defined encodings for the bit fields in this register, refer to Table 24-5 on page 1270. The reset value for this register is 0x0000.0000 for GPIO ports that are not listed in the table below.

**Note:** If the same signal is assigned to two different GPIO port pins, the signal is assigned to the port with the lowest letter and the assignment to the higher letter port is ignored.


Important: All GPIO pins are configured as GPIOs and tri-stated by default (GPIOAFSEL=0, GPIODEN=0, GPIOPDR=0, GPIOPUR=0, and GPIOPCTL=0, with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.

Table 8-12. GPIO Pins With Non-Zero Reset Values

GPIO Pins	Default State	GPIOAFSEL	GPIODEN	GPIOPDR	GPIOPUR	GPIOPCTL
PA[1:0]	UART0	0	0	0	0	0x1
PA[5:2]	SSI0	0	0	0	0	0x2
PB[3:2]	I <sup>2</sup> C0	0	0	0	0	0x3
PC[3:0]	JTAG/SWD	1	1	0	1	0x1

### GPIO Port Control (GPIOPCTL)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0x52C




Bit/Field	Name	Туре	Reset	Description
31:28	PMC7	R/W	-	Port Mux Control 7 This field controls the configuration for GPIO pin 7.
27:24	PMC6	R/W	-	Port Mux Control 6 This field controls the configuration for GPIO pin 6.
23:20	PMC5	R/W	-	Port Mux Control 5  This field controls the configuration for GPIO pin 5.
19:16	PMC4	R/W	-	Port Mux Control 4  This field controls the configuration for GPIO pin 4.
15:12	PMC3	R/W	-	Port Mux Control 3  This field controls the configuration for GPIO pin 3.
11:8	PMC2	R/W	-	Port Mux Control 2 This field controls the configuration for GPIO pin 2.
7:4	PMC1	R/W	-	Port Mux Control 1  This field controls the configuration for GPIO pin 1.
3:0	PMC0	R/W	-	Port Mux Control 0  This field controls the configuration for GPIO pin 0.

# Register 23: GPIO Peripheral Identification 4 (GPIOPeriphID4), offset 0xFD0

The **GPIOPeriphID4**, **GPIOPeriphID5**, **GPIOPeriphID6**, and **GPIOPeriphID7** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 4 (GPIOPeriphID4)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFD0 Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID4	RO	0x00	GPIO Peripheral ID Register [7:0]

# Register 24: GPIO Peripheral Identification 5 (GPIOPeriphID5), offset 0xFD4

The **GPIOPeriphID4**, **GPIOPeriphID5**, **GPIOPeriphID6**, and **GPIOPeriphID7** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 5 (GPIOPeriphID5)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFD4 Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID5	RO	0x00	GPIO Peripheral ID Register [15:8]

# Register 25: GPIO Peripheral Identification 6 (GPIOPeriphID6), offset 0xFD8

The **GPIOPeriphID4**, **GPIOPeriphID5**, **GPIOPeriphID6**, and **GPIOPeriphID7** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 6 (GPIOPeriphID6)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFD8 Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID6	RO	0x00	GPIO Peripheral ID Register [23:16]

# Register 26: GPIO Peripheral Identification 7 (GPIOPeriphID7), offset 0xFDC

The **GPIOPeriphID4**, **GPIOPeriphID5**, **GPIOPeriphID6**, and **GPIOPeriphID7** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 7 (GPIOPeriphID7)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFDC Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID7	RO	0x00	GPIO Peripheral ID Register [31:24]

# Register 27: GPIO Peripheral Identification 0 (GPIOPeriphID0), offset 0xFE0


The **GPIOPeriphID0**, **GPIOPeriphID1**, **GPIOPeriphID2**, and **GPIOPeriphID3** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 0 (GPIOPeriphID0)

Name

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFE0 Type RO, reset 0x0000.0061

Bit/Field



31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID0	RO	0x61	GPIO Peripheral ID Register [7:0]
				Can be used by software to identify the presence of this peripheral.

Description

Reset

Type

# Register 28: GPIO Peripheral Identification 1 (GPIOPeriphID1), offset 0xFE4

The **GPIOPeriphID0**, **GPIOPeriphID1**, **GPIOPeriphID2**, and **GPIOPeriphID3** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.


### GPIO Peripheral Identification 1 (GPIOPeriphID1)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFE4 Type RO, reset 0x0000.0000

Name

Type

Bit/Field



		. 7   -		
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID1	RO	0x00	GPIO Peripheral ID Register [15:8]  Can be used by software to identify the presence of this peripheral.

Description

Reset

# Register 29: GPIO Peripheral Identification 2 (GPIOPeriphID2), offset 0xFE8


The **GPIOPeriphID0**, **GPIOPeriphID1**, **GPIOPeriphID2**, and **GPIOPeriphID3** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 2 (GPIOPeriphID2)

Name

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFE8 Type RO, reset 0x0000.0018

Bit/Field



31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID2	RO	0x18	GPIO Peripheral ID Register [23:16]
				Can be used by software to identify the presence of this peripheral.

Description

Reset

Type

# Register 30: GPIO Peripheral Identification 3 (GPIOPeriphID3), offset 0xFEC


The **GPIOPeriphID0**, **GPIOPeriphID1**, **GPIOPeriphID2**, and **GPIOPeriphID3** registers can conceptually be treated as one 32-bit register; each register contains eight bits of the 32-bit register, used by software to identify the peripheral.

### GPIO Peripheral Identification 3 (GPIOPeriphID3)

Name

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFEC Type RO, reset 0x0000.0001

Bit/Field



31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID3	RO	0x01	GPIO Peripheral ID Register [31:24]
				Can be used by software to identify the presence of this peripheral.

Description

Reset

Type

# Register 31: GPIO PrimeCell Identification 0 (GPIOPCellID0), offset 0xFF0


The **GPIOPCeIIID1**, **GPIOPCeIIID1**, and **GPIOPCeIIID3** registers are four 8-bit wide registers, that can conceptually be treated as one 32-bit register. The register is used as a standard cross-peripheral identification system.

### GPIO PrimeCell Identification 0 (GPIOPCellID0)

Name

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFF0 Type RO, reset 0x0000.000D

Dit/Fiold



Bivrieid	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID0	RO	0x0D	GPIO PrimeCell ID Register [7:0]
				Provides software a standard cross-peripheral identification system.

Description


Dooot

# Register 32: GPIO PrimeCell Identification 1 (GPIOPCellID1), offset 0xFF4

The **GPIOPCeIIID1**, **GPIOPCeIIID1**, and **GPIOPCeIIID3** registers are four 8-bit wide registers, that can conceptually be treated as one 32-bit register. The register is used as a standard cross-peripheral identification system.

### GPIO PrimeCell Identification 1 (GPIOPCellID1)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFF4 Type RO, reset 0x0000.00F0




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID1	RO	0xF0	GPIO PrimeCell ID Register [15:8] Provides software a standard cross-peripheral identification system.

# Register 33: GPIO PrimeCell Identification 2 (GPIOPCellID2), offset 0xFF8

The **GPIOPCeIIID1**, **GPIOPCeIIID1**, and **GPIOPCeIIID3** registers are four 8-bit wide registers, that can conceptually be treated as one 32-bit register. The register is used as a standard cross-peripheral identification system.

### GPIO PrimeCell Identification 2 (GPIOPCellID2)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFF8 Type RO, reset 0x0000.0005




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID2	RO	0x05	GPIO PrimeCell ID Register [23:16] Provides software a standard cross-peripheral identification system.

# Register 34: GPIO PrimeCell Identification 3 (GPIOPCelIID3), offset 0xFFC

The **GPIOPCeIIID1**, **GPIOPCeIIID1**, and **GPIOPCeIIID3** registers are four 8-bit wide registers, that can conceptually be treated as one 32-bit register. The register is used as a standard cross-peripheral identification system.

### GPIO PrimeCell Identification 3 (GPIOPCellID3)

GPIO Port A (APB) base: 0x4000.4000 GPIO Port A (AHB) base: 0x4005.8000 GPIO Port B (APB) base: 0x4000.5000 GPIO Port B (AHB) base: 0x4005.9000 GPIO Port C (APB) base: 0x4000.6000 GPIO Port C (AHB) base: 0x4005.A000 GPIO Port D (APB) base: 0x4000.7000 GPIO Port D (AHB) base: 0x4005.B000 GPIO Port E (APB) base: 0x4002.4000 GPIO Port E (AHB) base: 0x4005.C000 GPIO Port F (APB) base: 0x4002.5000 GPIO Port F (AHB) base: 0x4005.D000 GPIO Port G (APB) base: 0x4002.6000 GPIO Port G (AHB) base: 0x4005.E000 GPIO Port H (APB) base: 0x4002.7000 GPIO Port H (AHB) base: 0x4005.F000 GPIO Port J (APB) base: 0x4003.D000 GPIO Port J (AHB) base: 0x4006.0000 Offset 0xFFC Type RO, reset 0x0000.00B1



Name	Туре	Reset	Description
reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
CID3	RO	0xB1	GPIO PrimeCell ID Register [31:24] Provides software a standard cross-peripheral identification system.
		reserved RO	reserved RO 0x0000.00

# 9 External Peripheral Interface (EPI)

The External Peripheral Interface is a high-speed parallel bus for external peripherals or memory. It has several modes of operation to interface gluelessly to many types of external devices. The External Peripheral Interface is similar to a standard microprocessor address/data bus, except that it must typically be connected to just one type of external device. Enhanced capabilities include µDMA support, clocking control and support for external FIFO buffers.

The EPI has the following features:

- 8/16/32-bit dedicated parallel bus for external peripherals and memory
- Memory interface supports contiguous memory access independent of data bus width, thus enabling code execution directly from SDRAM, SRAM and Flash memory
- Blocking and non-blocking reads
- Separates processor from timing details through use of an internal write FIFO
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Separate channels for read and write
  - Read channel request asserted by programmable levels on the internal non-blocking read FIFO (NBRFIFO)
  - Write channel request asserted by empty on the internal write FIFO (WFIFO)

The EPI supports three primary functional modes: Synchronous Dynamic Random Access Memory (SDRAM) mode, Traditional Host-Bus mode, and General-Purpose mode. The EPI module also provides custom GPIOs; however, unlike regular GPIOs, the EPI module uses a FIFO in the same way as a communication mechanism and is speed-controlled using clocking.

- Synchronous Dynamic Random Access Memory (SDRAM) mode
  - Supports x16 (single data rate) SDRAM at up to 50 MHz
  - Supports low-cost SDRAMs up to 64 MB (512 megabits)
  - Includes automatic refresh and access to all banks/rows
  - Includes a Sleep/Standby mode to keep contents active with minimal power draw
  - Multiplexed address/data interface for reduced pin count
- Host-Bus mode
  - Traditional x8 and x16 MCU bus interface capabilities
  - Similar device compatibility options as PIC, ATmega, 8051, and others
  - Access to SRAM, NOR Flash memory, and other devices, with up to 1 MB of addressing in unmultiplexed mode and 256 MB in multiplexed mode (512 MB in Host-Bus 16 mode with no byte selects)

- Support of both muxed and de-muxed address and data
- Access to a range of devices supporting the non-address FIFO x8 and x16 interface variant, with support for external FIFO (XFIFO) EMPTY and FULL signals
- Speed controlled, with read and write data wait-state counters
- Chip select modes include ALE, CSn, Dual CSn and ALE with dual CSn
- Manual chip-enable (or use extra address pins)
- General-Purpose mode
  - Wide parallel interfaces for fast communications with CPLDs and FPGAs
  - Data widths up to 32 bits
  - Data rates up to 150 MB/second
  - Optional "address" sizes from 4 bits to 20 bits
  - Optional clock output, read/write strobes, framing (with counter-based size), and clock-enable input
- General parallel GPIO
  - 1 to 32 bits, FIFOed with speed control
  - Useful for custom peripherals or for digital data acquisition and actuator controls

# 9.1 EPI Block Diagram

Figure 9-1 on page 464 provides a block diagram of a Stellaris<sup>®</sup> EPI module.




Figure 9-1. EPI Block Diagram

# 9.2 Signal Description

The following table lists the external signals of the EPI controller and describes the function of each. The EPI controller signals are alternate functions for GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the GPIO pin placement for the EPI signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the EPI controller function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the EPI signals to the specified GPIO port pins. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 9-1. External Peripheral Interface Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPI0S0	83	PH3 (8)	I/O	TTL	EPI module 0 signal 0.
EPI0S1	84	PH2 (8)	I/O	TTL	EPI module 0 signal 1.
EPI0S2	25	PC4 (8)	I/O	TTL	EPI module 0 signal 2.
EPIOS3	24	PC5 (8)	I/O	TTL	EPI module 0 signal 3.
EPI0S4	23	PC6 (8)	I/O	TTL	EPI module 0 signal 4.
EPIOS5	22	PC7 (8)	I/O	TTL	EPI module 0 signal 5.
EPI0S6	86	PH0 (8)	I/O	TTL	EPI module 0 signal 6.
EPIOS7	85	PH1 (8)	I/O	TTL	EPI module 0 signal 7.
EPIOS8	74	PE0 (8)	I/O	TTL	EPI module 0 signal 8.
EPIOS9	75	PE1 (8)	I/O	TTL	EPI module 0 signal 9.
EPI0S10	76	PH4 (8)	I/O	TTL	EPI module 0 signal 10.

Table 9-1. External Peripheral Interface Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPIOS11	63	PH5 (8)	I/O	TTL	EPI module 0 signal 11.
EPI0S12	42	PF4 (8)	I/O	TTL	EPI module 0 signal 12.
EPIOS13	19	PG0 (8)	I/O	TTL	EPI module 0 signal 13.
EPI0S14	18	PG1 (8)	I/O	TTL	EPI module 0 signal 14.
EPI0S15	41	PF5 (8)	I/O	TTL	EPI module 0 signal 15.
EPI0S16	14	PJ0 (8)	I/O	TTL	EPI module 0 signal 16.
EPI0S17	87	PJ1 (8)	I/O	TTL	EPI module 0 signal 17.
EPI0S18	39	PJ2 (8)	I/O	TTL	EPI module 0 signal 18.
EPIOS19	50 97	PJ3 (8) PD4 (10)	I/O	TTL	EPI module 0 signal 19.
EPI0S20	12	PD2 (8)	I/O	TTL	EPI module 0 signal 20.
EPI0S21	13	PD3 (8)	I/O	TTL	EPI module 0 signal 21.
EPI0S22	91	PB5 (8)	I/O	TTL	EPI module 0 signal 22.
EPI0S23	92	PB4 (8)	I/O	TTL	EPI module 0 signal 23.
EPI0S24	95	PE2 (8)	I/O	TTL	EPI module 0 signal 24.
EPI0S25	96	PE3 (8)	I/O	TTL	EPI module 0 signal 25.
EPI0S26	62	PH6 (8)	I/O	TTL	EPI module 0 signal 26.
EPI0S27	15	PH7 (8)	I/O	TTL	EPI module 0 signal 27.
EPIOS28	52 98	PJ4 (8) PD5 (10)	I/O	TTL	EPI module 0 signal 28.
EPIOS29	53 99	PJ5 (8) PD6 (10)	I/O	TTL	EPI module 0 signal 29.
EPIOS30	54 100	PJ6 (8) PD7 (10)	I/O	TTL	EPI module 0 signal 30.
EPIOS31	36	PG7 (9)	I/O	TTL	EPI module 0 signal 31.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 9-2. External Peripheral Interface Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPI0S0	D10	PH3 (8)	I/O	TTL	EPI module 0 signal 0.
EPIOS1	D11	PH2 (8)	I/O	TTL	EPI module 0 signal 1.
EPI0S2	L1	PC4 (8)	I/O	TTL	EPI module 0 signal 2.
EPIOS3	M1	PC5 (8)	I/O	TTL	EPI module 0 signal 3.
EPI0S4	M2	PC6 (8)	I/O	TTL	EPI module 0 signal 4.
EPIOS5	L2	PC7 (8)	I/O	TTL	EPI module 0 signal 5.
EPIOS6	C9	PH0 (8)	I/O	TTL	EPI module 0 signal 6.
EPIOS7	C8	PH1 (8)	I/O	TTL	EPI module 0 signal 7.
EPIOS8	B11	PE0 (8)	I/O	TTL	EPI module 0 signal 8.
EPIOS9	A12	PE1 (8)	I/O	TTL	EPI module 0 signal 9.
EPIOS10	B10	PH4 (8)	I/O	TTL	EPI module 0 signal 10.
EPIOS11	F10	PH5 (8)	I/O	TTL	EPI module 0 signal 11.

Table 9-2. External Peri	pheral Interface Signals	(108BGA)	(continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPIOS12	K4	PF4 (8)	I/O	TTL	EPI module 0 signal 12.
EPIOS13	K1	PG0 (8)	I/O	TTL	EPI module 0 signal 13.
EPIOS14	K2	PG1 (8)	I/O	TTL	EPI module 0 signal 14.
EPIOS15	K3	PF5 (8)	I/O	TTL	EPI module 0 signal 15.
EPIOS16	F3	PJ0 (8)	I/O	TTL	EPI module 0 signal 16.
EPIOS17	В6	PJ1 (8)	I/O	TTL	EPI module 0 signal 17.
EPIOS18	K6	PJ2 (8)	I/O	TTL	EPI module 0 signal 18.
EPIOS19	M10 B5	PJ3 (8) PD4 (10)	I/O	TTL	EPI module 0 signal 19.
EPIOS20	H2	PD2 (8)	I/O	TTL	EPI module 0 signal 20.
EPI0S21	H1	PD3 (8)	I/O	TTL	EPI module 0 signal 21.
EPI0S22	B7	PB5 (8)	I/O	TTL	EPI module 0 signal 22.
EPIOS23	A6	PB4 (8)	I/O	TTL	EPI module 0 signal 23.
EPIOS24	A4	PE2 (8)	I/O	TTL	EPI module 0 signal 24.
EPIOS25	B4	PE3 (8)	I/O	TTL	EPI module 0 signal 25.
EPIOS26	G3	PH6 (8)	I/O	TTL	EPI module 0 signal 26.
EPIOS27	H3	PH7 (8)	I/O	TTL	EPI module 0 signal 27.
EPIOS28	K11 C6	PJ4 (8) PD5 (10)	I/O	TTL	EPI module 0 signal 28.
EPIOS29	K12 A3	PJ5 (8) PD6 (10)	I/O	TTL	EPI module 0 signal 29.
EPIOS30	L10 A2	PJ6 (8) PD7 (10)	I/O	TTL	EPI module 0 signal 30.
EPIOS31	C10	PG7 (9)	I/O	TTL	EPI module 0 signal 31.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 9.3 Functional Description

The EPI controller provides a glueless, programmable interface to a variety of common external peripherals such as SDRAM x 16, Host Bus x8 and x16 devices, RAM, NOR Flash memory, CPLDs and FPGAs. In addition, the EPI controller provides custom GPIO that can use a FIFO with speed control by using either the internal write FIFO (WFIFO) or the non-blocking read FIFO (NBRFIFO). The WFIFO can hold 4 words of data that are written to the external interface at the rate controlled by the **EPI Main Baud Rate (EPIBAUD)** register. The NBRFIFO can hold 8 words of data and samples at the rate controlled by the **EPIBAUD** register. The EPI controller provides predictable operation and thus has an advantage over regular GPIO which has more variable timing due to on-chip bus arbitration and delays across bus bridges. Blocking reads stall the CPU until the transaction completes. Non-blocking reads are performed in the background and allow the processor to continue operation. In addition, write data can also be stored in the WFIFO to allow multiple writes with no stalls.

**Note:** Both the WTAV bit field in the **EPIWFIFOCNT** register and the WBUSY bit in the **EPISTAT** register must be polled to determine if there is a current write transaction from the WFIFO. If both of these bits are clear, then a new bus access may begin.

Main read and write operations can be performed in subsets of the range 0x6000.0000 to 0xDFFF.FFFF. A read from an address mapped location uses the offset and size to control the

address and size of the external operation. When performing a multi-value load, the read is done as a burst (when available) to maximize performance. A write to an address mapped location uses the offset and size to control the address and size of the external operation. When performing a multi-value store, the write is done as a burst (when available) to maximize performance.

NAND Flash memory (x8) can be read natively. Automatic programming support is not provided; programming must be done by the user following the manufacturer's protocol. Automatic page ECC is also not supported, but can be performed in software.

### 9.3.1 Non-Blocking Reads

The EPI Controller supports a special kind of read called a non-blocking read, also referred to as a posted read. Where a normal read stalls the processor or µDMA until the data is returned, a non-blocking read is performed in the background.

A non-blocking read is configured by writing the start address into a **EPIRADDRn** register, the size per transaction into a **EPIRSIZEn** register, and then the count of operations into a **EPIRPSTDn** register. After each read is completed, the result is written into the NBRFIFO and the **EPIRADDRn** register is incremented by the size (1, 2, or 4).

If the NBRFIFO is filled, then the reads pause until space is made available. The NBRFIFO can be configured to interrupt the processor or trigger the  $\mu$ DMA based on fullness using the **EPIFIFOLVL** register. By using the trigger/interrupt method, the  $\mu$ DMA (or processor) can keep space available in the NBRFIFO and allow the reads to continue unimpeded.

When performing non-blocking reads, the SDRAM controller issues two additional read transactions after the burst request is terminated. The data for these additional transfers is discarded. This situation is transparent to the user other than the additional EPI bus activity and can safely be ignored.

Two non-blocking read register sets are available to allow sequencing and ping-pong use. When one completes, the other then activates. So, for example, if 20 words are to be read from 0x100 and 10 words from 0x200, the **EPIRPSTD0** register can be set up with the read from 0x100 (with a count of 20), and the **EPIRPSTD1** register can be set up with the read from 0x200 (with a count of 10). When **EPIRPSTD0** finishes (count goes to 0), the **EPIRPSTD1** register then starts its operation. The NBRFIFO has then passed 30 values. When used with the  $\mu$ DMA, it may transfer 30 values (simple sequence), or the primary/alternate model may be used to handle the first 20 in one way and the second 10 in another. It is also possible to reload the **EPIRPSTD0** register when it is finished (and the **EPIRPSTD1** register is active); thereby, keeping the interface constantly busy.

To cancel a non-blocking read, the **EPIRPSTDn** register is cleared. Care must be taken, however if the register set was active to drain away any values read into the NBRFIFO and ensure that any read in progress is allowed to complete.

To ensure that the cancel is complete, the following algorithm is used (using the **EPIRPSTD0** register for example):

```
EPIRPSTD0 = 0;
while ((EPISTAT & 0x11) == 0x10)
; // we are active and busy
// if here, then other one is active or interface no longer busy
cnt = (EPIRADDR0 - original_address) / EPIRSIZE0; // count of values read
cnt -= values_read_so_far;
```

// cnt is now number left in FIFO

while (cnt--)

value = EPIREADFIFO; // drain

The above algorithm can be optimized in code; however, the important point is to wait for the cancel to complete because the external interface could have been in the process of reading a value when the cancel came in, and it must be allowed to complete.

### 9.3.2 DMA Operation

The  $\mu$ DMA can be used to achieve maximum transfer rates on the EPI through the NBRFIFO and the WFIFO. The  $\mu$ DMA has one channel for write and one for read. The write channel copies values to the WFIFO when the WFIFO is at the level specified by the **EPI FIFO Level Selects (EPIFIFOLVL)** register. The non-blocking read channel copies values from the NBRFIFO when the NBRFIFO is at the level specified by the **EPIFIFOLVL** register. For non-blocking reads, the start address, the size per transaction, and the count of elements must be programmed in the  $\mu$ DMA. Note that both non-blocking read register sets can be used, and they fill the NBRFIFO such that one runs to completion, then the next one starts (they do not interleave). Using the NBRFIFO provides the best possible transfer rate.

For blocking reads, the  $\mu$ DMA software channel (or another unused channel) is used for memory-to-memory transfers (or memory to peripheral, where some other peripheral is used). In this situation, the  $\mu$ DMA stalls until the read is complete and is not able to service another channel until the read is done. As a result, the arbitration size should normally be programmed to one access at a time. The  $\mu$ DMA controller can also transfer from and to the NBRFIFO and the WFIFO using the  $\mu$ DMA software channel in memory mode, however, the  $\mu$ DMA is stalled once the NBRFIFO is empty or the WFIFO is full. Note that when the  $\mu$ DMA controller is stalled, the core continues operation. See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for more information on configuring the  $\mu$ DMA.

The size of the FIFOs must be taken into consideration when configuring the  $\mu$ DMA to transfer data to and from the EPI. The arbitration size should be 4 or less when writing to EPI address space and 8 or less when reading from EPI address space.

# 9.4 Initialization and Configuration

To enable and initialize the EPI controller, the following steps are necessary:

- 1. Enable the EPI module using the **RCGC1** register. See page 272.
- **2.** Enable the clock to the appropriate GPIO module via the **RCGC2** register. See page 284. To find out which GPIO port to enable, refer to "Signal Description" on page 464.
- 3. Set the GPIO AFSEL bits for the appropriate pins. See page 430. To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the GPIO current level and/or slew rate as specified for the mode selected. See page 432 and page 440.
- **5.** Configure the PMCn fields in the **GPIOPCTL** register to assign the EPI signals to the appropriate pins. See page 448 and Table 24-5 on page 1270.
- **6.** Select the mode for the EPI block to SDRAM, HB8, HB16, or general parallel use, using the MODE field in the **EPI Configuration (EPICFG)** register. Set the mode-specific details (if needed)

using the appropriate mode configuration **EPI Host Bus Configuration (EPIHBnCFGn)** registers for the desired chip-select configuration. Set the **EPI Main Baud Rate (EPIBAUD)** register if the baud rate must be slower than the system clock rate.

- 7. Configure the address mapping using the **EPI Address Map (EPIADDRMAP)** register. The selected start address and range is dependent on the type of external device and maximum address (as appropriate). For example, for a 512-megabit SDRAM, program the ERADR field to 0x1 for address 0x6000.0000 or 0x2 for address 0x8000.0000; and program the ERSZ field to 0x3 for 256 MB. If using General-Purpose mode and no address at all, program the EPADR field to 0x1 for address 0xA000.0000 or 0x2 for address 0xC000.0000; and program the EPSZ field to 0x0 for 256 bytes.
- **8.** To read or write directly, use the mapped address area (configured with the **EPIADDRMAP** register). Up to 4 or 5 writes can be performed at once without blocking. Each read is blocked until the value is retrieved.
- 9. To perform a non-blocking read, see "Non-Blocking Reads" on page 467.

The following sub-sections describe the initialization and configuration for each of the modes of operation. Care must be taken to initialize everything properly to ensure correct operation. Control of the GPIO states is also important, as changes may cause the external device to interpret pin states as actions or commands (see "Register Descriptions" on page 419). Normally, a pull-up or pull-down is needed on the board to at least control the chip-select or chip-enable as the Stellaris GPIOs come out of reset in tri-state.

## 9.4.1 SDRAM Mode

When activating the SDRAM mode, it is important to consider a few points:

- 1. Generally, it takes over 100 µs from when the mode is activated to when the first operation is allowed. The SDRAM controller begins the SDRAM initialization sequence as soon as the mode is selected and enabled via the EPICFG register. It is important that the GPIOs are properly configured before the SDRAM mode is enabled, as the EPI controller is relying on the GPIO block's ability to drive the pins immediately. As part of the initialization sequence, the LOAD MODE REGISTER command is automatically sent to the SDRAM with a value of 0x27, which sets a CAS latency of 2 and a full page burst length.
- 2. The INITSEQ bit in the EPI Status (EPISTAT) register can be checked to determine when the initialization sequence is complete.
- 3. When using a frequency range and/or refresh value other than the default value, it is important to configure the FREQ and RFSH fields in the EPI SDRAM Configuration (EPISDRAMCFG) register shortly after activating the mode. After the 100-µs startup time, the EPI block must be configured properly to keep the SDRAM contents stable.
- **4.** The SLEEP bit in the **EPISDRAMCFG** register may be configured to put the SDRAM into a low-power self-refreshing state. It is important to note that the SDRAM mode must not be disabled once enabled, or else the SDRAM is no longer clocked and the contents are lost.
- 5. Before entering SLEEP mode, make sure all non-blocking reads and normal reads and writes have completed. If the system is running at 30 to 50 MHz, wait 2 EPI clocks after clearing the SLEEP bit before executing non-blocking reads, or normal reads and writes. If the system is configured to greater than 50 MHz, wait 5 EPI clocks before read and write transactions. For all other configurations, wait 1 EPI clock.

The SIZE field of the **EPISDRAMCFG** register must be configured correctly based on the amount of SDRAM in the system.

The FREQ field must be configured according to the value that represents the range being used. Based on the range selected, the number of external clocks used between certain operations (for example, PRECHARGE or ACTIVATE) is determined. If a higher frequency is given than is used, then the only downside is that the peripheral is slower (uses more cycles for these delays). If a lower frequency is given, incorrect operation occurs.

See "External Peripheral Interface (EPI)" on page 1326 for timing details for the SDRAM mode.

# 9.4.1.1 External Signal Connections

Table 9-3 on page 470 defines how EPI module signals should be connected to SDRAMs. The table applies when using a SDRAM up to 512 megabits. Note that the EPI signals must use 8-mA drive when interfacing to SDRAM, see page 434. Any unused EPI controller signals can be used as GPIOs or another alternate function.

**Table 9-3. EPI SDRAM Signal Connections** 

EPI Signal	SDRAM	/ Signal <sup>a</sup>	
EPI0S0	A0	D0	
EPI0S1	A1	D1	
EPI0S2	A2	D2	
EPI0S3	A3	D3	
EPI0S4	A4	D4	
EPI0S5	A5	D5	
EPI0S6	A6	D6	
EPI0S7	A7	D7	
EPI0S8	A8	D8	
EPI0S9	A9	D9	
EPI0S10	A10	D10	
EPI0S11	A11	D11	
EPI0S12	A12 <sup>b</sup>	D12	
EPI0S13	BA0	D13	
EPI0S14	BA1	D14	
EPI0S15	D15		
EPI0S16	DC	QML	
EPI0S17	DC	QMH	
EPI0S18	C/	ASn	
EPI0S19	R/	ASn	
EPI0S20-EPI0S27	not used		
EPI0S28	WEn		
EPI0S29	CSn		
EPI0S30	C	KE	
EPI0S31	C	LK	

a. If 2 signals are listed, connect the EPI signal to both pins.

b. Only for 256/512 megabit SDRAMs

## 9.4.1.2 Refresh Configuration

The refresh count is based on the external clock speed and the number of rows per bank as well as the refresh period. The RFSH field represents how many external clock cycles remain before an AUTO-REFRESH is required. The normal formula is:

```
RFSH = (t<sub>Refresh us</sub> / number_rows) / ext_clock_period
```

A refresh period is normally 64 ms, or 64000  $\mu$ s. The number of rows is normally 4096 or 8192. The ext\_clock\_period is a value expressed in  $\mu$ sec and is derived by dividing 1000 by the clock speed expressed in MHz. So, 50 MHz is 1000/50=20 ns, or 0.02  $\mu$ s. A typical SDRAM is 4096 rows per bank if the system clock is running at 50 MHz with an **EPIBAUD** register value of 0:

```
RFSH = (64000/4096) / 0.02 = 15.625 µs / 0.02 µs = 781.25
```

The default value in the RFSH field is 750 decimal or 0x2EE to allow for a margin of safety and providing 15 µs per refresh. It is important to note that this number should always be smaller or equal to what is required by the above equation. For example, if running the external clock at 25 MHz (40 ns per clock period), 390 is the highest number that may be used. Note that the external clock may be 25 MHz when the system clock is 25 MHz or when the system clock is 50 MHz and configuring the COUNTO field in the **EPIBAUD** register to 1 (divide by 2).

If a number larger than allowed is used, the SDRAM is not refreshed often enough, and data is lost.

#### 9.4.1.3 Bus Interface Speed

The EPI Controller SDRAM interface can operate up to 50 MHz. The COUNTO field in the **EPIBAUD** register configures the speed of the EPI clock. For system clock (SysClk) speeds up to 50 MHz, the COUNTO field can be 0x0000, and the SDRAM interface can run at the same speed as SysClk. However, if SysClk is running at higher speeds, the bus interface can run only as fast as half speed, and the COUNTO field must be configured to at least 0x0001.

#### 9.4.1.4 Non-Blocking Read Cycle

Figure 9-2 on page 472 shows a non-blocking read cycle of n halfwords; n can be any number greater than or equal to 1. The cycle begins with the Activate command and the row address on the  $\mathtt{EPIOS[15:0]}$  signals. With the programmed CAS latency of 2, the Read command with the column address on the  $\mathtt{EPIOS[15:0]}$  signals follows after 2 clock cycles. Following one more NOP cycle, data is read in on the  $\mathtt{EPIOS[15:0]}$  signals on every rising clock edge. The Burst Terminate command is issued during the cycle when the next-to-last halfword is read in. The DQMH and DQML signals are deasserted after the last halfword of data is received; the CSn signal deasserts on the following clock cycle, signaling the end of the read cycle. At least one clock period of inactivity separates any two SDRAM cycles.




Figure 9-2. SDRAM Non-Blocking Read Cycle

## 9.4.1.5 Normal Read Cycle

Figure 9-3 on page 472 shows a normal read cycle of n halfwords; n can be 1 or 2. The cycle begins with the Activate command and the row address on the EPIOS[15:0] signals. With the programmed CAS latency of 2, the Read command with the column address on the EPIOS[15:0] signals follows after 2 clock cycles. Following one more NOP cycle, data is read in on the EPIOS[15:0] signals on every rising clock edge. The DQMH, DQML, and CSn signals are deasserted after the last halfword of data is received, signaling the end of the cycle. At least one clock period of inactivity separates any two SDRAM cycles.




Figure 9-3. SDRAM Normal Read Cycle

## **9.4.1.6** Write Cycle

Figure 9-4 on page 473 shows a write cycle of n halfwords; n can be any number greater than or equal to 1. The cycle begins with the Activate command and the row address on the EPIOS[15:0] signals. With the programmed CAS latency of 2, the Write command with the column address on the EPIOS[15:0] signals follows after 2 clock cycles. When writing to SDRAMs, the Write command is presented with the first halfword of data. Because the address lines and the data lines are multiplexed, the column address is modified to be (programmed address -1). During the Write command, the DQMH and DQML signals are high, so no data is written to the SDRAM. On the next clock, the DQMH and DQML signals are asserted, and the data associated with the programmed address is written. The Burst Terminate command occurs during the clock cycle following the write of the last halfword of data. The WEn, DQMH, DQML, and CSn signals are deasserted after the last halfword of data is received, signaling the end of the access. At least one clock period of inactivity separates any two SDRAM cycles.




Figure 9-4. SDRAM Write Cycle

#### 9.4.2 Host Bus Mode

Host Bus supports the traditional 8-bit and 16-bit interfaces popularized by the 8051 devices and SRAM devices. This interface is asynchronous and uses strobe pins to control activity. Addressable memory can be doubled using Host Bus-16 mode as it performs half-word accesses. The EPI0S0 is the LSB of the address and is equivalent to the internal Cortex-M3 A1 address. EPI0S0 should be connected to A0 of 16-bit memories.

#### 9.4.2.1 Control Pins

The main three strobes are Address Latch Enable (ALE), Write (WRn), and Read (RDn, sometimes called OEn). Note that the timings are designed for older logic and so are hold-time vs. setup-time specific. The polarity of the read and write strobes can be active High or active Low by clearing or setting the RDHIGH and WRHIGH bits in the **EPI Host-Bus n Configuration 2 (EPIHBnCFG2)** register.

The ALE can be changed to an active-low chip select signal, CSn, through the **EPIHBnCFG2** register. The ALE is best used for Host-Bus muxed mode in which EPI address and data pins are shared. All Host-Bus accesses have an address phase followed by a data phase. The ALE indicates to an

external latch to capture the address then hold it until the data phase. CSn is best used for Host-Bus unmuxed mode in which EPI address and data pins are separate. The CSn indicates when the address and data phases of a read or write access are occurring. Both the ALE and the CSn modes can be enhanced to access external devices using settings in the **EPIHBnCFG2** register. Wait states can be added to the data phase of the access using the WRWS and RDWS bits in the **EPIHBnCFG2** register.

For FIFO mode, the ALE is not used, and two input holds are optionally supported to gate input and output to what the XFIFO can handle.

Host-Bus 8 and Host-Bus 16 modes are very configurable. The user has the ability to connect external devices to the EPI signals, as well as control whether byte select signals are provided in HB16 mode. These capabilities depend on the configuration of the MODE field in the **EPIHBnCFG** register and the CSCFG fieldin the **EPIHBnCFG2** register, and the BSEL bit in the **EPIHB16CFG** register. The CSCFGEXT bit extends the chip select configuration possibilities by providing the most significant bit of the CSCFG field.

If one of the Dual-Chip-Select modes is selected (CSCFG is 0x2 or 0x3 in the **EPIHBnCFG2** register), both chip selects can share the peripheral or the memory space, or one chip select can use the peripheral space and the other can use the memory space. In the **EPIADDRMAP** register, if the EPADR field is not 0x0 and the ERADR field is 0x0, then the address specified by EPADR is used for both chip selects, with CS0n being asserted when the MSB of the address range is 0 and CS1n being asserted when the MSB of the address range is 1. If the ERADR field is not 0x0 and the EPADR field is 0x0, then the address specified by ERADR is used for both chip selects, with the MSB performing the same delineation. If both the EPADR and the ERADR are not 0x0, then CS0n is asserted for either address range defined by EPADR.

If the CSBAUD bit in the **EPIHBnCFG2** register is set in Dual-chip select mode, the 2 chip selects can use different clock frequencies, wait states and strobe polarity. If the CSBAUD bit is clear, both chip selects use the clock frequency, wait states, and strobe polarity defined for CSOn.

When BSEL=1 in the **EPIHB16CFG** register, byte select signals are provided, so byte-sized data can be read and written at any address, however these signals reduce the available address width by 2 pins. The byte select signals are active Low. BSEL0n corresponds to the LSB of the halfword, and BSEL1n corresponds to the MSB of the halfword.

When BSEL=0, byte reads and writes at odd addresses only act on the even byte, and byte writes at even addresses write invalid values into the odd byte. As a result, accesses should be made as half-words (16-bits) or words (32-bits). In C/C++, programmers should use only short int and long int for accesses. Also, because data accesses in HB16 mode with no byte selects are on 2-byte boundaries, the available address space is doubled. For example, 28 bits of address accesses 512 MB in this mode. Table 9-4 on page 474 shows the capabilities of the HB8 and HB16 modes as well as the available address bits with the possible combinations of these bits.

Although the EPI0S31 signal can be configured for the EPI clock signal in Host-Bus mode, it is not required and should be configured as a GPIO to reduce EMI in the system.

Table 9-4. Capabilities of Host Bus 8 and Host Bus 16 Modes

Host Bus Type	MODE	CSCFG	Max # of External Devices	BSEL	Byte Access	Available Address	Addressable Memory
HB8	0x0	0x0, 0x1	1	N/A	Always	28 bits	256 MB
HB8	0x0	0x2	2	N/A	Always	27 bits	128 MB
HB8	0x0	0x3	2	N/A	Always	26 bits	64 MB

Table 9-4. Capabilities of Host Bus 8 and Host Bus 16 Modes (continued)

Host Bus Type	MODE	CSCFG	Max # of External Devices	BSEL	Byte Access	Available Address	Addressable Memory
HB8	0x1	0x0, 0x1	1	N/A	Always	20 bits	1 MB
HB8	0x1	0x2	2	N/A	Always	19 bits	512 kB
HB8	0x1	0x3	2	N/A	Always	18 bits	256 kB
HB8	0x3	0x1	1	N/A	Always	none	-
HB8	0x3	0x3	2	N/A	Always	none	-
HB16	0x0	0x0, 0x1	1	0	No	28 bits <sup>a</sup>	512 MB
HB16	0x0	0x0, 0x1	1	1	Yes	26 bits <sup>b</sup>	128 MB
HB16	0x0	0x2	2	0	No	27 bits <sup>a</sup>	256 MB
HB16	0x0	0x2	2	1	Yes	25 bits <sup>b</sup>	64 MB
HB16	0x0	0x3	2	0	No	26 bites <sup>a</sup>	128 MB
HB16	0x0	0x3	2	1	Yes	24 bits <sup>b</sup>	32 MB
HB16	0x1	0x0, 0x1	1	0	No	12 bits <sup>a</sup>	8 kB
HB16	0x1	0x0, 0x1	1	1	Yes	10 bits <sup>b</sup>	2 kB
HB16	0x1	0x2	2	0	No	11 bits <sup>a</sup>	4 kB
HB16	0x1	0x2	2	1	Yes	9 bits <sup>b</sup>	1 kB
HB16	0x1	0x3	2	0	No	10 bits <sup>a</sup>	2 kB
HB16	0x1	0x3	2	1	Yes	8 bits <sup>b</sup>	512 B
HB16	0x3	0x1	1	0	No	none	-
HB16	0x3	0x1	1	1	Yes	none	-
HB16	0x3	0x3	2	0	No	none	-
HB16	0x3	0x3	2	1	Yes	none	-

a. If byte selects are not used, data accesses are on 2-byte boundaries. As a result, the available address space is doubled.

Table 9-5 on page 475 shows how the EPI[31:0] signals function while in Host-Bus 8 mode. Notice that the signal configuration changes based on the address/data mode selected by the MODE field in the **EPIHB8CFG2** register and on the chip select configuration selected by the CSCFG field in the same register.

Although the EPI0S31 signal can be configured for the EPI clock signal in Host-Bus mode, it is not required and should be configured as a GPIO to reduce EMI in the system. Any unused EPI controller signals can be used as GPIOs or another alternate function.

Table 9-5. EPI Host-Bus 8 Signal Connections

EPI Signal	CSCFG	HB8 Signal (MODE = ADMUX)	HB8 Signal (MODE =ADNOMUX (Cont. Read))	HB8 Signal (MODE =XFIFO)
EPI0S0	X <sup>a</sup>	AD0	D0	D0
EPI0S1	Х	AD1	D1	D1
EPI0S2	Х	AD2	D2	D2
EPI0S3	Х	AD3	D3	D3
EPI0S4	Х	AD4	D4	D4
EPI0S5	Х	AD5	D5	D5

b. Two EPI signals are used for byte selects, reducing the available address space by two bits.

Table 9-5. EPI Host-Bus 8 Signal Connections (continued)

EPI Signal	CSCFG	HB8 Signal (MODE =ADMUX)	HB8 Signal (MODE =ADNOMUX (Cont. Read))	HB8 Signal (MODE =XFIFO)
EPI0S6	X	AD6	D6	D6
EPI0S7	X	AD7	D7	D7
EPI0S8	X	A8	A0	-
EPI0S9	X	A9	A1	-
EPI0S10	X	A10	A2	-
EPI0S11	X	A11	A3	-
EPI0S12	X	A12	A4	-
EPI0S13	X	A13	A5	-
EPI0S14	X	A14	A6	-
EPI0S15	X	A15	A7	-
EPI0S16	X	A16	A8	-
EPI0S17	X	A17	A9	-
EPI0S18	X	A18	A10	-
EPI0S19	X	A19	A11	-
EPI0S20	X	A20	A12	-
EPI0S21	X	A21	A13	-
EPI0S22	X	A22	A14	-
EPI0S23	X	A23	A15	-
EPI0S24	X	A24	A16	-
	0x0			
EPI0S25	0x1	A25 <sup>b</sup>	A17	
LF10323	0x2	723	All	CS1n
	0x3	_		-
	0x0			
EPI0S26	0x1	A26	A18	FEMPTY
LF10320	0x2			I LIVIF I I
	0x3	CS0n	CS0n	
	0x0	- A27	A19	
EPI0S27	0x1	721	Ala	- FFULL
LI 10021	0x2	- CS1n	CS1n	] ""
	0x3	03111	03111	
EPI0S28	X	RDn/OEn	RDn/OEn	RDn
EPI0S29	Х	WRn	WRn	WRn
	0x0	ALE	ALE	-
EPI0S30	0x1	CSn	CSn	CSn
LI 10000	0x2	CS0n	CS0n	CS0n
	0x3	ALE	ALE	-
EPI0S31	X	Clock <sup>c</sup>	Clock <sup>c</sup>	Clock <sup>c</sup>

a. "X" indicates the state of this field is a don't care.

b. When an entry straddles several row, the signal configuration is the same for all rows.

c. The clock signal is not required for this mode and has unspecified timing relationships to other signals.

Table 9-6 on page 477 shows how the EPI[31:0] signals function while in Host-Bus 16 mode. Notice that the signal configuration changes based on the address/data mode selected by the MODE field in the **EPIHB16CFG2** register, on the chip select configuration selected by the CSCFG field in the same register, and on whether byte selects are used as configured by the BSEL bit in the **EPIHB16CFG** register.

Although the EPI0S31 signal can be configured for the EPI clock signal in Host-Bus mode, it is not required and should be configured as a GPIO to reduce EMI in the system. Any unused EPI controller signals can be used as GPIOs or another alternate function.

Table 9-6. EPI Host-Bus 16 Signal Connections

EPI Signal	CSCFG	BSEL	HB16 Signal (MODE = ADMUX)	HB16 Signal (MODE =ADNOMUX (Cont. Read))	HB16 Signal (MODE =XFIFO)
EPI0S0	X <sup>a</sup>	Х	AD0 <sup>b</sup>	D0	D0
EPI0S1	Х	Х	AD1	D1	D1
EPI0S2	Х	Х	AD2	D2	D2
EPI0S3	Х	Х	AD3	D3	D3
EPI0S4	Х	Х	AD4	D4	D4
EPI0S5	Х	Х	AD5	D5	D5
EPI0S6	Х	Х	AD6	D6	D6
EPI0S7	Х	Х	AD7	D7	D7
EPI0S8	Х	Х	AD8	D8	D8
EPI0S9	Х	Х	AD9	D9	D9
EPI0S10	Х	Х	AD10	D10	D10
EPI0S11	Х	Х	AD11	D11	D11
EPI0S12	Х	Х	AD12	D12	D12
EPI0S13	Х	Х	AD13	D13	D13
EPI0S14	Х	Х	AD14	D14	D14
EPI0S15	Х	Х	AD15	D15	D15
EPI0S16	Х	Х	A16	A0 <sup>b</sup>	-
EPI0S17	Х	Х	A17	A1	-
EPI0S18	Х	Х	A18	A2	-
EPI0S19	Х	Х	A19	A3	-
EPI0S20	Х	Х	A20	A4	-
EPI0S21	Х	Х	A21	A5	-
EPI0S22	Х	Х	A22	A6	-
EPI0S23	Xc	0	A23	A7	
L1 10023	^	1	723		_

Table 9-6. EPI Host-Bus 16 Signal Connections (continued)

EPI Signal	CSCFG	BSEL	HB16 Signal (MODE =ADMUX)	HB16 Signal (MODE =ADNOMUX (Cont. Read))	HB16 Signal (MODE =XFIFO)
	0x0	0			
	0.00	1			
	0x1	0			
EPI0S24	0.11	1	A24	A8	_
LF10324	0x2	0			-
	UAZ	1			
	0x3	0			
	0.3	1	BSEL0n	BSEL0n	]
	0x0	×	A25	A9	
	0x1		AZS	A9	-
EPI0S25	0x2	0	A25	A9	- CS1n
LF10323	0.2	1	BSEL0n	BSEL0n	- 63111
	0x3	0	A25	A9	
	0.00	1	BSEL1n	BSEL1n	
	0x0	0	A26	A10	
	0.00	1	BSEL0n	BSEL0n	]
	0x1	0	A26	A10	]
EPI0S26		1	BSEL0n	BSEL0n	FEMPTY
	0x2	0	A26	A10	]
		1	BSEL1n	BSEL1n	
	0x3	Х	CS0n	CS0n	]
	0.40	0	A27	A11	
	0x0	1	BSEL1n	BSEL1n	]
EPI0S27	0x1	0	A27	A11	FFULL
EP10321	UXI	1	BSEL1n	BSEL1n	FFOLL
	0x2	Х	CS1n	CS1n	]
	0x3	Х	CSIII	Com	
EPI0S28	Х	Х	RDn/OEn	RDn/OEn	RDn
EPI0S29	Х	Х	WRn	WRn	WRn
	0x0	Х	ALE	ALE	-
EPI0S30	0x1	Х	CSn	CSn	CSn
LFIUSSU	0x2	Х	CS0n	CS0n	CS0n
	0x3	Х	ALE	ALE	-
EPI0S31	Х	Х	Clock <sup>d</sup>	Clock <sup>d</sup>	Clock <sup>d</sup>

a. "X" indicates the state of this field is a don't care.

b. In this mode, half-word accesses are used. A0 is the LSB of the address and is equivalent to the internal Cortex-M3 A1 address. This pin should be connected to A0 of 16-bit memories.


c. When an entry straddles several row, the signal configuration is the same for all rows.

d. The clock signal is not required for this mode and has unspecified timing relationships to other signals.

## 9.4.2.2 SRAM support

Figure 9-5 on page 479 shows how to connect the EPI signals to a 16-bit SRAM and a 16-bit Flash memory with muxed address and memory using byte selects and dual chip selects with ALE. This schematic is just an example of how to connect the signals; timing and loading have not been analyzed. In addition, not all bypass capacitors are shown.

Figure 9-5. Example Schematic for Muxed Host-Bus 16 Mode



# 9.4.2.3 Speed of Transactions

The COUNTO field in the **EPIBAUD** register must be configured to set the main transaction rate based on what the slave device can support (including wiring considerations). The main control

transitions are normally ½ the baud rate (COUNTO = 1) because the EPI block forces data vs. control to change on alternating clocks. When using dual chip selects, each chip select can access the bus using differing baud rates by setting the CSBAUD bit in the EPIHBnCFG2 register. In this case, the COUNTO field controls the CSOn transactions, and the COUNTO field controls the CSOn transactions.

Additionally, the Host-Bus mode provides read and write wait states for the data portion to support different classes of device. These wait states stretch the data period (hold the rising edge of data strobe) and may be used in all four sub-modes. The wait states are set using the WRWS and RDWS bits in the **EPI Host-Bus n Configuration (EPIHBnCFG)** register.

#### 9.4.2.4 Sub-Modes of Host Bus 8/16

The EPI controller supports four variants of the Host-Bus model using 8 or 16 bits of data in all four cases. The four sub-modes are selected using the MODE bits in the **EPIHBnCFG** register, and are:

- 1. Address and data are muxed. This scheme is used by many 8051 devices, some Microchip PIC parts, and some ATmega parts. When used for standard SRAMs, a latch must be used between the microcontroller and the SRAM. This sub-mode is provided for compatibility with existing devices that support data transfers without a latch (that is, CPLDs). In general, the de-muxed sub-mode should normally be used. The ALE configuration should be used in this mode, as all Host-Bus accesses have an address phase followed by a data phase. The ALE indicates to an external latch to capture the address then hold until the data phase. The ALE configuration is controlled by configuring the CSCFG field to be 0x0 in the EPIHBnCFG2 register. The ALE can be enhanced to access two external devices with two separate CSn signals. By configuring the CSCFG field to be 0x3 in the EPIHBnCFG2 register, EPI0S30 functions as ALE, EPI0S27 functions as CS1n, and EPI0S26 functions as CS0n. The CSn is best used for Host-Bus unmuxed mode, in which EPI address and data pins are separate. The CSn indicates when the address and data phases of a read or write access are occurring.
- 2. Address and data are separate with 8 or 16 bits of data and up to 20 bits of address (1 MB). This scheme is used by more modern 8051 devices, as well as some PIC and ATmega parts. This mode is generally used with real SRAMs, many EEPROMs, and many NOR Flash memory devices. Note that there is no hardware command write support for Flash memory devices; this mode should only be used for Flash memory devices programmed at manufacturing time. If a Flash memory device must be written and does not support a direct programming model, the command mechanism must be performed in software. The CSn configuration should be used in this mode. The CSn signal indicates when the address and data phases of a read or write access is occurring. The CSn configuration is controlled by configuring the CSCFG field to be 0x1 in the EPIHBnCFG2 register.
- 3. Continuous read mode where address and data are separate. This sub-mode is used for real SRAMs which can be read more quickly by only changing the address (and not using RDn/OEn strobing). In this sub-mode, reads are performed by keeping the read mode selected (output enable is asserted) and then changing the address pins. The data pins are changed by the SRAM after the address pins change. For example, to read data from address 0x100 and then 0x101, the EPI controller asserts the output-enable signal and then configures the address pins to 0x100; the EPI controller then captures what is on the data pins and increments A0 to 1 (so the address is now 0x101); the EPI controller then captures what is on the data pins. Note that this mode consumes higher power because the SRAM must continuously drive the data pins. This mode is not practical in HB16 mode for normal SRAMs because there are generally not enough address bits available. Writes are not permitted in this mode.
- **4.** FIFO mode uses 8 or 16 bits of data, removes ALE and address pins and optionally adds external XFIFO FULL/EMPTY flag inputs. This scheme is used by many devices, such as radios,

communication devices (including USB2 devices), and some FPGA configurations (FIFO through block RAM). This sub-mode provides the data side of the normal Host-Bus interface, but is paced by the FIFO control signals. It is important to consider that the XFIFO FULL/EMPTY control signals may stall the interface and could have an impact on blocking read latency from the processor or  $\mu DMA$ .

The WORD bit in the **EPIHBnCFG2** register can be set to use memory more efficiently. By default, the EPI controller uses data bits [7:0] for Host-Bus 8 accesses or bits [15:0] for Host-Bus 16 accesses. When the WORD bit is set, the EPI controller can automatically route bytes of data onto the correct byte lanes such that bytes or words of data can be transferred on the correct byte or half-word bits on the entire bus. For example, the most significant byte of data will be transferred on bits [31:28] in host-bus 8 mode and the most significant word of data will be transferred on bits [31:16] of Host-Bus 16 mode. In addition, for the three modes above (1, 2, 4) that the Host-Bus 16 mode supports, byte select signals can be optionally implemented by setting the BSEL bit in the **EPIHB16CFG** register.

**Note:** Byte accesses should not be attempted if the BSEL bit has not been enabled in Host-Bus 16 Mode.

See "External Peripheral Interface (EPI)" on page 1326 for timing details for the Host-Bus mode.

#### 9.4.2.5 Bus Operation

Bus operation is the same in Host-Bus 8 and Host-Bus 16 modes and is asynchronous. Timing diagrams show both ALE and CSn operation, but only one signal or the other is used in all modes except for ALE with dual chip selects mode (CSCFG field is 0x3 in the **EPIHBnCFG2** register). Address and data on write cycles are held after the CSn signal is deasserted. The optional HB16 byte select signals have the same timing as the address signals. If wait states are required in the bus access, they can be inserted during the data phase of the access using the WRWS and RDWS bits in the **EPIHBnCFG2** register. Each wait state adds 2 EPI clock cycles to the duration of the WRn or RDn strobe. During idle cycles, the address and muxed address data signals maintain the state of the last cycle.

Figure 9-6 on page 481 shows a basic Host-Bus read cycle. Figure 9-7 on page 482 shows a basic Host-Bus write cycle. Both of these figures show address and data signals in the non-multiplexed mode (MODE field ix 0x1 in the **EPIHBnCFG** register).




Figure 9-6. Host-Bus Read Cycle, MODE = 0x1, WRHIGH = 0, RDHIGH = 0





Figure 9-7. Host-Bus Write Cycle, MODE = 0x1, WRHIGH = 0, RDHIGH = 0

Figure 9-8 on page 482 shows a write cycle with the address and data signals multiplexed (MODE field is 0x0 in the **EPIHBnCFG** register). A read cycle would look similar, with the RDn strobe being asserted along with CSn and data being latched on the rising edge of RDn.

Figure 9-8. Host-Bus Write Cycle with Multiplexed Address and Data, MODE = 0x0, WRHIGH = 0, RDHIGH = 0



<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.

When using ALE with dual CSn configuration (CSCFG field is 0x3 in the **EPIHBnCFG2** register), the appropriate CSn signal is asserted at the same time as ALE, as shown in Figure 9-9 on page 483.

<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.





Figure 9-9. Host-Bus Write Cycle with Multiplexed Address and Data and ALE with Dual CSn

Figure 9-10 on page 483 shows continuous read mode accesses. In this mode, reads are performed by keeping the read mode selected (output enable is asserted) and then changing the address pins. The data pins are changed by the SRAM after the address pins change.


Figure 9-10. Continuous Read Mode Accesses




FIFO mode accesses are the same as normal read and write accesses, except that the ALE signal and address pins are not present. Two input signals can be used to indicate when the XFIFO is full or empty to gate transactions and avoid overruns and underruns. The FFULL and FEMPTY signals are synchronized and must be recognized as asserted by the microcontroller for 2 system clocks before they affect transaction status. The MAXWAIT field in the **EPIHBnCFG** register defines the maximum number of EPI clocks to wait while the FEMPTY or FFULL signal is holding off a transaction. Figure 9-11 on page 484 shows how the FEMPTY signal should respond to a write and read from the XFIFO. Figure 9-12 on page 484 shows how the FEMPTY and FFULL signals should respond to 2 writes and 1 read from an external FIFO that contains two entries.

<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.

Figure 9-11. Write Followed by Read to External FIFO



#### Figure 9-12. Two-Entry FIFO



# 9.4.3 General-Purpose Mode

The **General-Purpose Mode Configuration (EPIGPCFG)** register is used to configure the control, data, and address pins, if used. Any unused EPI controller signals can be used as GPIOs or another alternate function. The general-purpose configuration can be used for custom interfaces with FPGAs, CPLDs, and digital data acquisition and actuator control.

**Important:** The RD2CYC bit in the **EPIGPCFG** register must be set at all times in General-Purpose mode to ensure proper operation.

General-Purpose mode is designed for three general types of use:

- Extremely high-speed clocked interfaces to FPGAs and CPLDs. Three sizes of data and optional address are supported. Framing and clock-enable functions permit more optimized interfaces.
- General parallel GPIO. From 1 to 32 pins may be written or read, with the speed precisely controlled by the **EPIBAUD** register baud rate (when used with the WFIFO and/or the NBRFIFO) or by the rate of accesses from software or µDMA. Examples of this type of use include:
  - Reading 20 sensors at fixed time periods by configuring 20 pins to be inputs, configuring the COUNTO field in the EPIBAUD register to some divider, and then using non-blocking reads.

- Implementing a very wide ganged PWM/PCM with fixed frequency for driving actuators, LEDs, etc.
- Implementing SDIO 4-bit mode where commands are driven or captured on 6 pins with fixed timing, fed by the μDMA.
- General custom interfaces of any speed.

The configuration allows for choice of an output clock (free-running or gated), a framing signal (with frame size), a ready input (to stretch transactions), a read and write strobe, an address (of varying sizes), and data (of varying sizes). Additionally, provisions are made for separating data and address phases.

The interface has the following optional features:

- Use of the EPI clock output is controlled by the CLKPIN bit in the **EPIGPCFG** register. Unclocked uses include general-purpose I/O and asynchronous interfaces (optionally using RD and WR strobes). Clocked interfaces allow for higher speeds and are much easier to connect to FPGAs and CPLDs (which usually include input clocks).
- EPI clock, if used, may be free running or gated depending on the CLKGATE bit in the **EPIGPCFG** register. A free-running EPI clock requires another method for determining when data is live, such as the frame pin or RD/WR strobes. A gated clock approach uses a setup-time model in which the EPI clock controls when transactions are starting and stopping. The gated clock is held high until a new transaction is started and goes high at the end of the cycle where RD/WR/FRAME and address (and data if write) are emitted.
- Use of the ready input (iRDY) from the external device is controlled by the RDYEN bit in the **EPIGPCFG** register. The iRDY signal uses EPI0S27 and may only be used with a free-running clock. iRDY gates transactions, no matter what state they are in. When iRDY is deasserted, the transaction is held off from completing.
- Use of the frame output (FRAME) is controlled by the FRMPIN bit in the **EPIGPCFG** register. The frame pin may be used whether the clock is output or not, and whether the clock is free running or not. It may also be used along with the iRDY signal. The frame may be a pulse (one clock) or may be 50/50 split across the frame size (controlled by the FRM50 bit in the **EPIGPCFG** register). The frame count (the size of the frame as specified by the FRMCNT field in the **EPIGPCFG** register) may be between 1 and 15 clocks for pulsed and between 2 and 30 clocks for 50/50. The frame pin counts transactions and not clocks; a transaction is any clock where the RD or WR strobe is high (if used). So, if the FRMCNT bit is set, then the frame pin pulses every other transaction; if 2-cycle reads and writes are used, it pulses every other address phase. FRM50 must be used with this in mind as it may hold state for many clocks waiting for the next transaction.
- Use of the RD and WR outputs is controlled by the RW bit in the **EPIGPCFG** register. For interfaces where the direction is known (in advance, related to frame size, or other means), these strobes are not needed. For most other interfaces, RD and WR are used so the external peripheral knows what transaction is taking place, and if any transaction is taking place.
- Separation of address/request and data phases may be used on writes using the WR2CYC bit in the EPIGPCFG register. This configuration allows the external peripheral extra time to act. Address and data phases must be separated on reads, and the RD2CYC bit in the EPIGPCFG register must be set. When configured to use an address as specified by the ASIZE field in the EPIGPCFG register, the address is emitted on the with the RD strobe (first cycle) and data is

expected to be returned on the next cycle (when RD is not asserted). If no address is used, then RD is asserted on the first cycle and data is captured on the second cycle (when RD is not asserted), allowing more setup time for data.

For writes, the output may be in one or two cycles. In the two-cycle case, the address (if any) is emitted on the first cycle with the WR strobe and the data is emitted on the second cycle (with WR not asserted). Although split address and write data phases are not normally needed for logic reasons, it may be useful to make read and write timings match. If 2-cycle reads or writes are used, the RW bit is automatically set.

- Address may be emitted (controlled by the ASIZE field in the **EPIGPCFG** register). The address may be up to 4 bits (16 possible values), up to 12 bits (4096 possible values), or up to 20 bits (1 M possible values). Size of address limits size of data, for example, 4 bits of address support up to 24 bits data. 4-bit address uses EPIOS[27:24]; 12-bit address uses EPIOS[27:16]; 20-bit address uses EPIOS[27:8]. The address signals may be used by the external peripheral as an address, code (command), or for other unrelated uses (such as a chip enable). If the chosen address/data combination does not use all of the EPI signals, the unused pins can be used as GPIOs or for other functions. For example, when using a 4-bit address with an 8-bit data, the pins assigned to EPISO[23:8] can be assigned to other functions.
- Data may be 8 bits, 16 bits, 24 bits, or 32 bits (controlled by the DSIZE field in the **EPIGPCFG** register). 32-bit data cannot be used with address or EPI clock or any other signal. 24-bit data can only be used with 4-bit address or no address. 32-bit data requires that either the WR2CYC bit or the RD2CYC bit in the **EPIGPCFG** register is set.
- Memory can be used more efficiently by using the Word Access Mode. By default, the EPI controller uses data bits [7:0] when the DSIZE field in the EPIGPCFG register is 0x0; data bits [15:0] when the DSIZE field is 0x1; data bits [23:0] when the DSIZE field is 0x2; and data bits [31:0] when the DSIZE field is 0x3. When the WORD bit in the EPIGPCFG2 register is set, the EPI controller automatically routes bytes of data onto the correct byte lanes such that data can be stored in bits [31:8] for DSIZE=0x0 and bits [31:16] for DSIZE=0x1.
- When using the EPI controller as a GPIO interface, writes are FIFOed (up to 4 can be held at any time), and up to 32 pins are changed using the EPIBAUD clock rate specified by COUNTO. As a result, output pin control can be very precisely controlled as a function of time. By contrast, when writing to normal GPIOs, writes can only occur 8-bits at a time and take up to two clock cycles to complete. In addition, the write itself may be further delayed by the bus due to μDMA or draining of a previous write. With both GPIO and the EPI controller, reads may be performed directly, in which case the current pin states are read back. With the EPI controller, the non-blocking interface may also be used to perform reads based on a fixed time rule via the EPIBAUD clock rate.

Table 9-7 on page 486 shows how the EPIOS[31:0] signals function while in General-Purpose mode. Notice that the address connections vary depending on the data-width restrictions of the external peripheral.

Table 9-7. EPI General Purpose Signal Connections

EPI Signal	General-Purpose Signal (D8, A20)	General- Purpose Signal (D16, A12)	General- Purpose Signal (D24, A4)	General- Purpose Signal (D32)
EPI0S0	D0	D0	D0	D0
EPI0S1	D1	D1	D1	D1
EPI0S2	D2	D2	D2	D2

Table 9-7. EPI General Purpose Signal Connections (continued)

EPI Signal	General-Purpose Signal (D8, A20)	General- Purpose Signal (D16, A12)	General- Purpose Signal (D24, A4)	General- Purpose Signal (D32)
EPI0S3	D3	D3	D3	D3
EPI0S4	D4	D4	D4	D4
EPI0S5	D5	D5	D5	D5
EPI0S6	D6	D6	D6	D6
EPI0S7	D7	D7	D7	D7
EPI0S8	A0	D8	D8	D8
EPI0S9	A1	D9	D9	D9
EPI0S10	A2	D10	D10	D10
EPI0S11	A3	D11	D11	D11
EPI0S12	A4	D12	D12	D12
EPI0S13	A5	D13	D13	D13
EPI0S14	A6	D14	D14	D14
EPI0S15	A7	D15	D15	D15
EPI0S16	A8	A0 <sup>a</sup>	D16	D16
EPI0S17	A9	A1	D17	D17
EPI0S18	A10	A2	D18	D18
EPI0S19	A11	A3	D19	D19
EPI0S20	A12	A4	D20	D20
EPI0S21	A13	A5	D21	D21
EPI0S22	A14	A6	D22	D22
EPI0S23	A15	A7	D23	D23
EPI0S24	A16	A8	A0 <sup>b</sup>	D24
EPI0S25	A17	A9	A1	D25
EPI0S26	A18	A10	A2	D26
EPI0S27	A19/iRDY <sup>c</sup>	A11/iRDY <sup>c</sup>	A3/iRDY <sup>c</sup>	D27
EPI0S28	WR	WR	WR	D28
EPI0S29	EPI0S29 RD		RD	D29
EPI0S30	Frame	Frame	Frame	D30
EPI0S31	Clock	Clock	Clock	D31

a. In this mode, half-word accesses are used. AO is the LSB of the address and is equivalent to the system A1 address.

# 9.4.3.1 Bus Operation

A basic access is 1 EPI clock for write cycles and 2 EPI clocks for read cycles. An additional EPI clock can be inserted into a write cycle by setting the WR2CYC bit in the **EPIGPCFG** register. Note that the RD2CYC bit must always be set in the **EPIGPCFG** register.

b. In this mode, word accesses are used. AO is the LSB of the address and is equivalent to the system A2 address.

c. This signal is iRDY if the  ${\tt RDYEN}$  bit in the EPIGPCFG register is set.

Figure 9-13. Single-Cycle Write Access, FRM50=0, FRMCNT=0, WRCYC=0





Figure 9-14. Two-Cycle Read, Write Accesses, FRM50=0, FRMCNT=0, RDCYC=1, WRCYC=1







Figure 9-15. Read Accesses, FRM50=0, FRMCNT=0, RDCYC=1

# FRAME Signal Operation


The operation of the FRAME signal is controlled by the FRMCNT and FRM50 bits. When FRM50 is clear, the FRAME signal is high whenever the WR or RD strobe is high. When FRMCNT is clear, the FRAME signal is simply the logical OR of the WR and RD strobes so the FRAME signal is high during every read or write access, see Figure 9-16 on page 489.

Figure 9-16. FRAME Signal Operation, FRM50=0 and FRMCNT=0




If the FRMCNT field is 0x1, then the FRAME signal pulses high during every other read or write access, see Figure 9-17 on page 489.

Figure 9-17. FRAME Signal Operation, FRM50=0 and FRMCNT=1




If the FRMCNT field is 0x2 and FRM50 is clear, then the FRAME signal pulses high during every third access, and so on for every value of FRMCNT, see Figure 9-18 on page 490.

Figure 9-18. FRAME Signal Operation, FRM50=0 and FRMCNT=2




When FRM50 is set, the FRAME signal transitions on the rising edge of either the WR or RD strobes. When FRMCNT=0, the FRAME signal transitions on the rising edge of WR or RD for every access, see Figure 9-19 on page 490.

Figure 9-19. FRAME Signal Operation, FRM50=1 and FRMCNT=0




When FRMCNT=1, the FRAME signal transitions on the rising edge of the WR or RD strobes for every other access, see Figure 9-20 on page 490.

Figure 9-20. FRAME Signal Operation, FRM50=1 and FRMCNT=1



When FRMCNT=2, the FRAME signal transitions the rising edge of the WR or RD strobes for every third access, and so on for every value of FRMCNT, see Figure 9-21 on page 490.

Figure 9-21. FRAME Signal Operation, FRM50=1 and FRMCNT=2



#### iRDY Signal Operation

The ready input (iRDY) signal can be used to lengthen bus cycles and is enabled by the RDYEN bit in the **EPIGPCFG** register. iRDY is input on EPI0S27 and may only be used with a free-running clock (CLKGATE is clear). If iRDY is deasserted, further transactions are held off until the iRDY signal is asserted again. iRDY is sampled on the falling edge of the EPI clock and gates transactions, no matter what state they are in.

A two-cycle access has two phases in the bus cycle. The first clock is the address phase, and the second clock is the data phase. If iRDY is sampled Low at the start of the address phase, as shown in Figure 26-19 on page 1331, then the address phase is extended (FRAME, RD, and Address are all asserted) until after iRDY has been sampled High again. Data is sampled on the subsequent rising edge.

If iRDY is sampled Low at the start of the data phase, as shown in Figure 9-22 on page 491, the FRAME, RD, Address, and Data signals behave as they would during a normal transaction in T1. The data phase (T2) is extended with only Address being asserted until iRDY is recognized as asserted again. Data is latched on the subsequent rising edge.




Figure 9-22. iRDY Signal Operation, FRM50=0, FRMCNT=0, and RD2CYC=1

#### **EPI Clock Operation**

If the CLKGATE bit in the **EPIGPCFG** register is clear, the EPI clock always toggles when General-purpose mode is enabled. If CLKGATE is set, the clock is output only when a transaction is occurring, otherwise the clock is held high. If the WR2CYC bit is clear, the EPI clock begins toggling 1 cycle before the WR strobe goes high. If the WR2CYC bit is set, the EPI clock begins toggling when the WR strobe goes high. The clock stops toggling after the first rising edge after the WR strobe is deasserted. The RD strobe operates in the same manner as the WR strobe when the WR2CYC bit is set, as the RD2CYC bit must always be set. See Figure 9-23 on page 492 and Figure 9-24 on page 492.

Figure 9-23. EPI Clock Operation, CLKGATE=1, WR2CYC=0





Figure 9-24. EPI Clock Operation, CLKGATE=1, WR2CYC=1



# 9.5 Register Map

Table 9-8 on page 492 lists the EPI registers. The offset listed is a hexadecimal increment to the register's address, relative to the base address of 0x400D.0000. Note that the EPI controller clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the EPI module clock is enabled before any EPI module registers are accessed.

**Note:** A back-to-back write followed by a read of the same register reads the value that written by the first write access, not the value from the second write access. (This situation only occurs when the processor core attempts this action, the µDMA does not do this.). To read back what was just written, another instruction must be generated between the write and read. Read-write does not have this issue, so use of read-write for clear of error interrupt cause is not affected.

Table 9-8. External Peripheral Interface (EPI) Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	EPICFG	R/W	0x0000.0000	EPI Configuration	494
0x004	EPIBAUD	R/W	0x0000.0000	EPI Main Baud Rate	495
0x010	EPISDRAMCFG	R/W	0x82EE.0000	EPI SDRAM Configuration	497
0x010	EPIHB8CFG	R/W	0x0000.FF00	EPI Host-Bus 8 Configuration	499
0x010	EPIHB16CFG	R/W	0x0000.FF00	EPI Host-Bus 16 Configuration	502
0x010	EPIGPCFG	R/W	0x0000.0000	EPI General-Purpose Configuration	506
0x014	EPIHB8CFG2	R/W	0x0000.0000	EPI Host-Bus 8 Configuration 2	511

Table 9-8. External Peripheral Interface (EPI) Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x014	EPIHB16CFG2	R/W	0x0000.0000	EPI Host-Bus 16 Configuration 2	514
0x014	EPIGPCFG2	R/W	0x0000.0000	EPI General-Purpose Configuration 2	517
0x01C	EPIADDRMAP	R/W	0x0000.0000	EPI Address Map	518
0x020	EPIRSIZE0	R/W	0x0000.0003	EPI Read Size 0	520
0x024	EPIRADDR0	R/W	0x0000.0000	EPI Read Address 0	521
0x028	EPIRPSTD0	R/W	0x0000.0000	EPI Non-Blocking Read Data 0	522
0x030	EPIRSIZE1	R/W	0x0000.0003	EPI Read Size 1	520
0x034	EPIRADDR1	R/W	0x0000.0000	EPI Read Address 1	521
0x038	EPIRPSTD1	R/W	0x0000.0000	EPI Non-Blocking Read Data 1	522
0x060	EPISTAT	RO	0x0000.0000	EPI Status	524
0x06C	EPIRFIFOCNT	RO	-	EPI Read FIFO Count	526
0x070	EPIREADFIFO	RO	-	EPI Read FIFO	527
0x074	EPIREADFIFO1	RO	-	EPI Read FIFO Alias 1	527
0x078	EPIREADFIFO2	RO	-	EPI Read FIFO Alias 2	527
0x07C	EPIREADFIFO3	RO	-	EPI Read FIFO Alias 3	527
0x080	EPIREADFIFO4	RO	-	EPI Read FIFO Alias 4	527
0x084	EPIREADFIFO5	RO	-	EPI Read FIFO Alias 5	527
0x088	EPIREADFIFO6	RO	-	EPI Read FIFO Alias 6	527
0x08C	EPIREADFIFO7	RO	-	EPI Read FIFO Alias 7	527
0x200	EPIFIFOLVL	R/W	0x0000.0033	EPI FIFO Level Selects	528
0x204	EPIWFIFOCNT	RO	0x0000.0004	EPI Write FIFO Count	530
0x210	EPIIM	R/W	0x0000.0000	EPI Interrupt Mask	531
0x214	EPIRIS	RO	0x0000.0004	EPI Raw Interrupt Status	532
0x218	EPIMIS	RO	0x0000.0000	EPI Masked Interrupt Status	534
0x21C	EPIEISC	R/W1C	0x0000.0000	EPI Error and Interrupt Status and Clear	535

# 9.6 Register Descriptions

This section lists and describes the EPI registers, in numerical order by address offset.

# Register 1: EPI Configuration (EPICFG), offset 0x000

Important: The MODE field determines which configuration register is accessed for offsets 0x010 and 0x014. Any write to the **EPICFG** register resets the register contents at offsets 0x010 and 0x014.


The configuration register is used to enable the block, select a mode, and select the basic pin use (based on the mode). Note that attempting to program an undefined MODE field clears the BLKEN bit and disables the EPI controller.

#### EPI Configuration (EPICFG)

Base 0x400D.0000

Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:5	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	BLKEN	R/W	0	Block Enable
				Value Description
				0 The EPI controller is disabled.
				1 The EPI controller is enabled.
3:0	MODE	R/W	0x0	Mode Select
				Value Description
				0x0 General Purpose
				General-Purpose mode. Control, address, and data pins are configured using the <b>EPIGPCFG</b> and <b>EPIGPCFG2</b> registers.
				0x1 SDRAM
				Supports SDR SDRAM. Control, address, and data pins are configured using the <b>EPISDRAMCFG</b> register.
				0x2 8-Bit Host-Bus (HB8)

16-Bit Host-Bus (HB16)

EPIHB16CFG2 registers.

Host-bus 8-bit interface (also known as the MCU interface). Control, address, and data pins are configured using the

Host-bus 16-bit interface (standard SRAM). Control, address, and data pins are configured using the EPIHB16CFG and

EPIHB8CFG and EPIHB8CFG2 registers.

0x3

# Register 2: EPI Main Baud Rate (EPIBAUD), offset 0x004

The system clock is used internally to the EPI Controller. The baud rate counter can be used to divide the system clock down to control the speed on the external interface. If the mode selected emits an external EPI clock, this register defines the EPI clock emitted. If the mode selected does not use an EPI clock, this register controls the speed of changes on the external interface. Care must be taken to program this register properly so that the speed of the external bus corresponds to the speed of the external peripheral and puts acceptable current load on the pins. COUNTO is the bit field used in all modes except in HB8 and HB16 modes with dual chip selects when different baud rates are selected, see page 511 and page 514. If different baud rates are used, COUNTO is associated with the address range specified by CSOn and COUNT1 is associated with the address range specified by CS1.

The COUNTn field is not a straight divider or count. The EPI Clock on EPI0S31 is related to the COUNTn field and the system clock as follows:

If COUNTn = 0,

EPIClockFreq = SystemClockFreq

#### otherwise:

$$EPIClockFreq = \frac{SystemClockFreq}{\left(\left\lfloor \frac{COUNTn}{2} \right\rfloor + 1\right) \times 2}$$


where the symbol around COUNTn/2 is the floor operator, meaning the largest integer less than or equal to COUNTn/2.

So, for example, a COUNTn of 0x0001 results in a clock rate of  $\frac{1}{2}$ (system clock); a COUNTn of 0x0002 or 0x0003 results in a clock rate of  $\frac{1}{4}$ (system clock).

#### EPI Main Baud Rate (EPIBAUD)

Base 0x400D.0000 Offset 0x004

Type R/W, reset 0x0000.0000



This bit field is only valid with multiple chip selects which are enabled when the CSCFG field is 0x2 or 0x3 and the CSBAUD bit is set in the EPIHBnCFG2 register.

This bit field contains a counter used to divide the system clock by the count

A count of 0 means the system clock is used as is.

Bit/Field	Name	Туре	Reset	Description
15:0	COUNT0	R/W	0x0000	Baud Rate Counter 0  This bit field contains a counter used to divide the system clock by the count.  A count of 0 means the system clock is used as is.

# Register 3: EPI SDRAM Configuration (EPISDRAMCFG), offset 0x010

Important: The MODE field in the EPICFG register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access EPISDRAMCFG, the MODE field must be 0x1.

The SDRAM Configuration register is used to specify several parameters for the SDRAM controller. Note that this register is reset when the MODE field in the EPICFG register is changed. If another mode is selected and the SDRAM mode is selected again, the values must be reinitialized.

The SDRAM interface is designed to interface to x16 SDR SDRAMs of 64 MHz or higher, with the address and data pins overlapped (wire ORed on the board). See Table 9-3 on page 470 for pin assignments.

#### EPI SDRAM Configuration (EPISDRAMCFG)

Name

Base 0x400D.0000 Offset 0x010

Bit/Field

Type R/W, reset 0x82EE.0000

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	FR	EQ		reserved							RFSH		ı			
Type	R/W	R/W	RO	RO	RO	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	0	0	0	0	0	1	0	1	1	1	0	1	1	1	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
			rese	rved			SLEEP				reserved				SI	ZE
Type	RO	RO	RO	RO	RO	RO	R/W	RO	RO	RO	RO	RO	RO	RO	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Description

Bit/Field	Name	Type	Reset	Description
31:30	FREQ	R/W	0x2	EPI Frequency Range

This field configures the frequency range used for delay references by internal counters. This EPI frequency is the system frequency with the divider programmed by the COUNTO bit in the EPIBAUDn register bit. This field affects the power up, precharge, and auto refresh delays. This field does not affect the refresh counting, which is configured separately using the RFSH field (and is based on system clock rate and number of rows per bank). The ranges are:

Value Description

0x0 0 - 15 MHz

0x1 15 - 30 MHz

30 - 50 MHz 0x2

50 - 100 MHz 0x3

29:27 RO Software should not rely on the value of a reserved bit. To provide reserved 0x0 compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

26:16 **RFSH** R/W 0x2EE Refresh Counter

> This field contains the refresh counter in system clocks. The reset value of 0x2EE provides a refresh period of 64 ms when using a 50 MHz clock.

Bit/Field	Name	Туре	Reset	Description
15:10	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	SLEEP	R/W	0	Sleep Mode  Value Description
				0 No effect.
				1 The SDRAM is put into low power state, but is self-refreshed.
8:2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1:0	SIZE	R/W	0x0	Size of SDRAM
				The value of this field affects address pins and behavior.
				Value Description
				0x0 64 megabits (8MB)
				0x1 128 megabits (16MB)
				0x2 256 megabits (32MB)
				0x3 512 megabits (64MB)

# Register 4: EPI Host-Bus 8 Configuration (EPIHB8CFG), offset 0x010

**Important:** The MODE field in the **EPICFG** register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access **EPIHB8CFG**, the MODE field must be 0x2.

The Host Bus 8 Configuration register is activated when the HB8 mode is selected. The HB8 mode supports muxed address/data (overlay of lower 8 address and all 8 data pins), separate address/data, and address-less FIFO mode. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the HB8 mode is selected again, the values must be reinitialized.

This mode is intended to support SRAMs, Flash memory (read), FIFOs, CPLDs/FPGAs, and devices with an MCU/HostBus slave or 8-bit FIFO interface support.

Refer to Table 9-5 on page 475 for information on signal configuration controlled by this register and the **EPIHB8CFG2** register.


If less address pins are required, the corresponding AFSEL bit (page 430) should not be enabled so the EPI controller does not drive those pins, and they are available as standard GPIOs.

EPI Host-Bus 8 Mode can be configured to use one chip select with and without the use of ALE. If an alternative to chip selects are required, a chip enable can be handled in one of three ways:

- Manually control via GPIOs.
- 2. Associate one or more upper address pins to CE. Because CE is normally CEn, lower addresses are not used. For example, if pins EPI0S27 and EPI0S26 are used for Device 1 and 0 respectively, then address 0x6800.0000 accesses Device 0 (Device 1 has its CEn high), and 0x6400.0000 accesses Device 1 (Device 0 has its CEn high). The pull-up behavior on the corresponding GPIOs must be properly configured to ensure that the pins are disabled when the interface is not in use.
- With certain SRAMs, the ALE can be used as CEn because the address remains stable after the ALE strobe. The subsequent WRn or RDn signals write or read when ALE is low thus providing CEn functionality.

#### EPI Host-Bus 8 Configuration (EPIHB8CFG)

Base 0x400D.0000 Offset 0x010 Type R/W, reset 0x0000.FF00



Bit/Field Name Type Reset Description

31:24 reserved RO 0x00 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
23	XFFEN	R/W	0	External FIFO FULL Enable
				Value Description
				0 No effect.
				An external FIFO full signal can be used to control write cycles. If this bit is set and the FFULL full signal is high, XFIFO writes are stalled.
22	XFEEN	R/W	0	External FIFO EMPTY Enable
				Value Description
				0 No effect.
				An external FIFO empty signal can be used to control read cycles. If this bit is set and the FEMPTY signal is high, XFIFO reads are stalled.
21	WRHIGH	R/W	0	WRITE Strobe Polarity
				Value Description
				0 The WRITE strobe for CS0n is WRn (active Low).
				1 The WRITE strobe for CS0n is WR (active High).
20	RDHIGH	R/W	0	READ Strobe Polarity
				Value Description
				0 The READ strobe for CS0n is RDn (active Low).
				1 The READ strobe for CS0n is RD (active High).
19:16	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:8	MAXWAIT	R/W	0xFF	Maximum Wait
				This field defines the maximum number of external clocks to wait while an external FIFO ready signal is holding off a transaction (FFULL and FEMPTY).
				When the MAXWAIT value is reached the ERRRIS interrupt status bit is set in the <b>EPIRIS</b> register. When this field is clear, the transaction can be held off forever without a system interrupt.
				Note: When the MODE field is configured to be 0x2 and the BLKEN bit is set in the EPICFG register, enabling HB8 mode, this field defaults to 0xFF.

Bit/Field	Name	Туре	Reset	Description
7:6	WRWS	R/W	0x0	Write Wait States
				This field adds wait states to the data phase of CS0n (the address phase is not affected). The effect is to delay the rising edge of WRn (or the falling edge of WR). Each wait state adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active WRn is 2 EPI clocks.
				0x1 Active WRn is 4 EPI clocks.
				0x2 Active WRn is 6 EPI clocks.
				0x3 Active WRn is 8 EPI clocks.
				This field is used in conjunction with the <b>EPIBAUD</b> register.
5:4	RDWS	R/W	0x0	Read Wait States
				This field adds wait states to the data phase of CS0n (the address phase is not affected).
				The effect is to delay the rising edge of RDn/Oen (or the falling edge of RD). Each wait state adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active RDn is 2 EPI clocks.
				0x1 Active RDn is 4 EPI clocks.
				0x2 Active RDn is 6 EPI clocks.
				0x3 Active RDn is 8 EPI clocks.
				This field is used in conjunction with the <b>EPIBAUD</b> register
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1:0	MODE	R/W	0x0	Host Bus Sub-Mode
				This field determines which of four Host Bus 8 sub-modes to use. Sub-mode use is determined by the connected external peripheral. See Table 9-5 on page 475 for information on how this bit field affects the operation of the EPI signals.
				Value Description
				0x0 ADMUX – AD[7:0]
				Data and Address are muxed.
				0x1 ADNONMUX – D[7:0]
				Data and address are separate.
				0x2 Continuous Read - D[7:0]
				This mode is the same as ADNONMUX, but uses address switch for multiple reads instead of OEn strobing.
				0x3 XFIFO – D[7:0]
				This mode adds XFIFO controls with sense of XFIFO full and XFIFO empty. This mode uses no address or ALE.

# Register 5: EPI Host-Bus 16 Configuration (EPIHB16CFG), offset 0x010

**Important:** The MODE field in the **EPICFG** register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access **EPIHB16CFG**, the MODE field must be 0x3.

The Host Bus 16 sub-configuration register is activated when the HB16 mode is selected. The HB16 mode supports muxed address/data (overlay of lower 16 address and all 16 data pins), separated address/data, and address-less FIFO mode. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the HB16 mode is selected again, the values must be reinitialized.

This mode is intended to support SRAMs, Flash memory (read), FIFOs, and CPLDs/FPGAs, and devices with an MCU/HostBus slave or 16-bit FIFO interface support.

Refer to Table 9-6 on page 477 for information on signal configuration controlled by this register and the **EPIHB16CFG2** register.


If less address pins are required, the corresponding AFSEL bit (page 430) should not be enabled so the EPI controller does not drive those pins, and they are available as standard GPIOs.

EPI Host-Bus 16 Mode can be configured to use one to four chip selects with and without the use of ALE. If an alternative to chip selects are required, a chip enable can be handled in one of three ways:

- 1. Manually control via GPIOs.
- 2. Associate one or more upper address pins to CE. Because CE is normally CEn, lower addresses are not used. For example, if pins EPI0S27 and EPI0S26 are used for Device 1 and 0 respectively, then address 0x6800.0000 accesses Device 0 (Device 1 has its CEn high), and 0x6400.0000 accesses Device 1 (Device 0 has its CEn high). The pull-up behavior on the corresponding GPIOs must be properly configured to ensure that the pins are disabled when the interface is not in use.
- 3. With certain SRAMs, the ALE can be used as CEn because the address remains stable after the ALE strobe. The subsequent WRn or RDn signals write or read when ALE is low thus providing CEn functionality.

EPI Host-Bus 16 Configuration (EPIHB16CFG)

Base 0x400D.0000 Offset 0x010 Type R/W, reset 0x0000.FF00



Bit/Field	Name	Туре	Reset	Description
31:24	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23	XFFEN	R/W	0	External FIFO FULL Enable
				Value Description
				0 No effect.
				An external FIFO full signal can be used to control write cycles. If this bit is set and the FFULL signal is high, XFIFO writes are stalled.
22	XFEEN	R/W	0	External FIFO EMPTY Enable
				Value Description
				An external FIFO empty signal can be used to control read cycles. If this bit is set and the FEMPTY signal is high, XFIFO reads are stalled.
				0 No effect.
21	WRHIGH	R/W	0	WRITE Strobe Polarity
				Value Description
				0 The WRITE strobe for CS0n is WRn (active Low).
				1 The WRITE strobe for CS0n is WR (active High).
20	RDHIGH	R/W	0	READ Strobe Polarity
				Value Description
				0 The READ strobe for CS0n is RDn (active Low).
				1 The READ strobe is RD (active High).
19:16	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:8	MAXWAIT	R/W	0xFF	Maximum Wait
				This field defines the maximum number of external clocks to wait while an external FIFO ready signal is holding off a transaction (FFULL and FEMPTY).
				When this field is clear, the transaction can be held off forever without a system interrupt.
				<b>Note:</b> When the MODE field is configured to be 0x3 and the <b>BLKEN</b> bit is set in the <b>EPICFG</b> register, enabling HB16 mode, this field defaults to 0xFF.

Bit/Field	Name	Туре	Reset	Description
7:6	WRWS	R/W	0x0	Write Wait States  This field adds wait states to the data phase of CS0n (the address phase is not affected). The effect is to delay the rising edge of WRn (or the falling edge of WR). Each wait state adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active WRn is 2 EPI clocks.
				0x1 Active WRn is 4 EPI clocks.
				0x2 Active WRn is 6 EPI clocks.  0x3 Active WRn is 8 EPI clocks.
				UX3 ACTIVE WRITTS O EFT CIUCKS.
				This field is used in conjunction with the <b>EPIBAUD</b> register.
5:4	RDWS	R/W	0x0	Read Wait States
				This field adds wait states to the data phase of CS0n (the address phase is not affected).
				The effect is to delay the rising edge of RDn/Oen (or the falling edge of RD). Each wait state adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active RDn is 2 EPI clocks.
				0x1 Active RDn is 4 EPI clocks.
				0x2 Active RDn is 6 EPI clocks.
				0x3 Active RDn is 8 EPI clocks.
				This field is used in conjunction with the <b>EPIBAUD</b> register
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	BSEL	R/W	0	Byte Select Configuration
				This bit enables byte select operation.
				Value Description
				0 No Byte Selects
				Data is read and written as 16 bits.
				1 Enable Byte Selects
				Two EPI signals function as byte select signals to allow 8-bit transfers. See Table 9-6 on page 477 for details on which EPI signals are used.

Bit/Field	Name	Туре	Reset	Description
1:0	MODE	R/W	0x0	Host Bus Sub-Mode  This field determines which of three Host Bus 16 sub-modes to use.  Sub-mode use is determined by the connected external peripheral. See Table 9-6 on page 477 for information on how this bit field affects the operation of the EPI signals.
				Value Description
				0x0 ADMUX – AD[15:0]
				Data and Address are muxed.
				0x1 ADNONMUX – D[15:0]
				Data and address are separate. This mode is not practical in HB16 mode for normal peripherals because there are generally not enough address bits available.
				0x2 Continuous Read - D[15:0]
				This mode is the same as ADNONMUX, but uses address switch for multiple reads instead of OEn strobing. This mode is not practical in HB16 mode for normal SRAMs because there are generally not enough address bits available.
				0x3 XFIFO – D[15:0]
				This mode adds XFIFO controls with sense of XFIFO full and XFIFO empty. This mode uses no address or ALE.

## Register 6: EPI General-Purpose Configuration (EPIGPCFG), offset 0x010

Important: The MODE field in the EPICFG register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access **EPIGPCFG**, the MODE field must be 0x0.

The RD2CYC bit must be set at all times in General-Purpose mode to ensure proper operation.

The General-Purpose configuration register is used to configure the control, data, and address pins. This mode can be used for custom interfaces with FPGAs, CPLDs, and for digital data acquisition and actuator control. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the General-purpose mode is selected again, the register the values must be reinitialized.

This mode is designed for 3 general types of use:


- Extremely high-speed clocked interfaces to FPGAs and CPLDs, with 3 sizes of data and optional address. Framing and clock-enable permit more optimized interfaces.
- General parallel GPIO. From 1 to 32 pins may be written or read, with the speed precisely controlled by the baud rate in the EPIBAUD register (when used with the NBRFIFO and/or the WFIFO) or by rate of accesses from software or μDMA.
- General custom interfaces of any speed.

The configuration allows for choice of an output clock (free running or gated), a framing signal (with frame size), a ready input (to stretch transactions), read and write strobes, address of varying sizes, and data of varying sizes. Additionally, provisions are made for splitting address and data phases on the external interface.

#### EPI General-Purpose Configuration (EPIGPCFG)

Base 0x400D.0000 Offset 0x010

Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset Description

31 CLKPIN R/W 0 Clock Pin

Value Description

0 No clock output.

1 EPI0S31 functions as the EPI clock output.

The EPI clock is generated from the COUNTO field in the **EPIBAUD** register (as is the system clock which is divided down from it).

Bit/Field	Name	Туре	Reset	Description
30	CLKGATE	R/W	0	Clock Gated
				Value Description
				0 The EPI clock is free running.
				The EPI clock is output only when there is data to write or read (current transaction); otherwise the EPI clock is held low.
				Note that EPI0S27 is an iRDY signal if RDYEN is set. CLKGATE is ignored if CLKPIN is 0 or if the COUNTO field in the <b>EPIBAUD</b> register is cleared.
29	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28	RDYEN	R/W	0	Ready Enable
				Value Description
				The external peripheral does not drive an iRDY signal and is assumed to be ready always.
				1 The external peripheral drives an iRDY signal into pin EPI0S27.
				The ready enable signal may only be used with a free-running EPI clock (CLKGATE=0).
				The external iRDY signal is sampled on the falling edge of the EPI clock. Setup and hold times must be met to ensure registration on the next falling EPI clock edge.
				This bit is ignored if CLKPIN is 0 or CLKGATE is 1.
27	FRMPIN	R/W	0	Framing Pin
				Value Description
				0 No framing signal is output.
				1 A framing signal is output on EPI0S30.
				Framing has no impact on data itself, but forms a context for the external peripheral. When used with a free-running EPI clock, the FRAME signal forms the valid signal. When used with a gated EPI clock, it is usually used to form a frame size.
26	FRM50	R/W	0	50/50 Frame
				Value Description
				The FRAME signal is output as a single pulse, and then held low for the count.
				1 The FRAME signal is output as 50/50 duty cycle using count (see FRMCNT).
				This bit is ignored if FRMPIN is 0.

October 06, 2012 507

Bit/Field	Name	Туре	Reset	Description
25:22	FRMCNT	R/W	0x0	Frame Count
				This field specifies the size of the frame in EPI clocks. The frame counter is used to determine the frame size. The count is FRMCNT+1. So, a FRMCNT of 0 forms a pure transaction valid signal (held high during transactions, low otherwise).
				A FRMCNT of 0 with FRM50 set inverts the FRAME signal on each transaction. A FRMCNT of 1 means the FRAME signal is inverted every other transaction; a value of 15 means every sixteenth transaction.
				If FRM50 is set, the frame is held high for FRMCNT+1 transactions, then held low for that many transactions, and so on.
				If FRM50 is clear, the frame is pulsed high for one EPI clock and then low for FRMCNT EPI clocks.
				This field is ignored if FRMPIN is 0.
21	RW	R/W	0	Read and Write
				Value Description
				0 RD and WR strobes are not output.
				1 RD and WR strobes are asserted on EPI0S29 and EPI0S28. RD is asserted high on the rising edge of the EPI clock when a read is being performed. WR is asserted high on the rising edge of the EPI clock when a write is being performed
				This bit is forced to 1 when RD2CYC and/or WR2CYC is 1.
20	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	WR2CYC	R/W	0	2-Cycle Writes
				Value Description
				0 Data is output on the same EPI clock cycle as the address.
				Writes are two EPI clock cycles long, with address on one EPI clock cycle (with the WR strobe asserted) and data written on the following EPI clock cycle (with WR strobe de-asserted). The next address (if any) is in the cycle following.
				When this bit is set, then the RW bit is forced to be set.
18	RD2CYC	R/W	0	2-Cycle Reads
				Value Description
				Data is captured on the EPI clock cycle with READ strobe asserted.
				1 Reads are two EPI clock cycles, with address on one EPI clock cycle (with the RD strobe asserted) and data captured on the following EPI clock cycle (with the RD strobe de-asserted). The next address (if any) is in the cycle following.
				When this bit is set, then the RW bit is forced to be set.
				Caution – This bit must be set at all times in General-Purpose mode to ensure proper operation.

Bit/Field	Name	Туре	Reset	Description
17:16	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:8	MAXWAIT	R/W	0x00	Maximum Wait
				This field defines the maximum number of EPI clocks to wait while the iRDY signal (see RDYEN) is holding off a transaction. If this field is 0, the transaction is held forever. If the maximum wait of 255 clocks (MAXWAIT=0xFF) is exceeded, an error interrupt occurs and the transaction is aborted/ignored.
				<b>Note:</b> When the MODE field is configured to be 0x0 and the <b>BLKEN</b> bit is set in the <b>EPICFG</b> register, enabling General-Purpose mode, this field defaults to 0xFF.
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:4	ASIZE	R/W	0x0	Address Bus Size
				This field defines the size of the address bus. The address can be up to 4-bits wide with a 24-bit data bus, up to 12-bits wide with a 16-bit data bus, and up to 20-bits wide with an 8-bit data bus. If the full address bus is not used, use the least significant address bits. Any unused address bits can be used as GPIOs by clearing the AFSEL bit for the corresponding GPIOs. Also, if RDYEN is 1, then the address sizes are 1 smaller (3, 11, 19).
				The values are:
				Value Description
				0x0 No address
				0x1 Up to 4 bits wide.
				0x2 Up to 12 bits wide. This size cannot be used with 24-bit data.
				0x3 Up to 20 bits wide. This size cannot be used with data sizes other than 8.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Type	Reset	Description		
1:0	DSIZE	R/W	0x0	Size of Data Bus  This field defines the size of the data bus (starting at EPIOSO). Subs of these numbers can be created by clearing the AFSEL bit for the corresponding GPIOs. Note that size 32 may not be used with clock frame, address, or other control.  The values are:		
				Value Description  0x0 8 Bits Wide (EPI0S0 to EPI0S7)  0x1 16 Bits Wide (EPI0S0 to EPI0S15)  0x2 24 Bits Wide (EPI0S0 to EPI0S23)		
				Ox3 32 Bits Wide (EPIOSO to EPIOS31)  This size may not be used with an EPI clock. This value is normally used for acquisition input and actuator control as well as other general-purpose uses that require 32 bits per direction.		

## Register 7: EPI Host-Bus 8 Configuration 2 (EPIHB8CFG2), offset 0x014

**Important:** The MODE field in the **EPICFG** register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access EPIHB8CFG2, the MODE field must be 0x2.

This register is used to configure operation while in Host-Bus 8 mode. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the Host-Bus 8 mode is selected again, the values must be reinitialized.


#### EPI Host-Bus 8 Configuration 2 (EPIHB8CFG2)

Name

Base 0x400D.0000 Offset 0x014

Bit/Field

Type R/W, reset 0x0000.0000



31	WORD	R/W	0	Word Access Mode
				By default, the EPI controller uses data bits [7:0] for Host-Bus 8 accesses. When using Word Access mode, the EPI controller can automatically route bytes of data onto the correct byte lanes such that

Description

Reset

data can be stored in bits [31:8]. When  $\mathtt{WORD}$  is set, short and long variables can be used in C programs.

Value Description

0 Word Access mode is disabled.

1 Word Access mode is enabled.

30:27 reserved RO 0x0 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

26 CSBAUD R/W 0 Chip Select Baud Rate

Type

Value Description

0 Same Baud Rate

Both CS0n and CS1n use the baud rate for the external bus that is defined by the  ${\tt COUNT0}$  field in the <code>EPIBAUD</code> register.

1 Different Baud Rates

CS0n uses the baud rate for the external bus that is defined by the COUNTO field in the **EPIBAUD** register. CS1n uses the baud rate defined by the COUNT1 field in the **EPIBAUD** register.

Bit/Field	Name	Type	Reset	Description			
25:24	CSCFG	R/W	0x0	Chip Select Configuration This field controls the chip select options, including an ALE format, a single chip select, two chip selects, and an ALE combined with two chip selects.			
				Value Description			
				0x0 ALE Configuration			
				EPI0S30 is used as an address latch (ALE). The ALE signal is generally used when the address and data are muxed (HB8MODE field in the <b>EPIHB8CFG</b> register is 0x0). The ALE signal is used by an external latch to hold the address through the bus cycle.			
				0x1 CSn Configuration			
				EPI0S30 is used as a Chip Select (CSn). When using this mode, the address and data are generally not muxed (HB8MODE field in the <b>EPIHB8CFG</b> register is 0x1). However, if address and data muxing is needed, the WR signal (EPI0S29) and the RD signal (EPI0S28) can be used to latch the address when CSn is low.			
				0x2 Dual CSn Configuration			
				EPI0S30 is used as CS0n and EPI0S27 is used as CS1n. Whether CS0n or CS1n is asserted is determined by two methods. If only external RAM or external PER is enabled in the address map, the most significant address bit for a respective external address map controls CS0n or CS1n. If both external RAM and external PER is enabled, CS0n is mapped to PER and CS1n is mapped to RAM. This configuration can be used for a RAM bank split between 2 devices as well as when using both an external RAM and an external peripheral.			
				0x3 ALE with Dual CSn Configuration			
				EPI0S30 is used as address latch (ALE), EPI0S27 is used as CS1n, and EPI0S26 is used as CS0n. Whether CS0n or CS1n is asserted is determined by the most significant address bit for a respective external address map.			
23:22	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.			
21	WRHIGH	R/W	0	CS1n WRITE Strobe Polarity			
				This field is used if the CSBAUD bit in the <b>EPIHBnCFG2</b> register is enabled.			
				Value Description			
				0 The WRITE strobe for CS1n accesses is WRn (active Low).			
				1 The WRITE strobe for CS1n accesses is WR (active High).			

Bit/Field	Name	Туре	Reset	Description
20	RDHIGH	R/W	0	CS1n READ Strobe Polarity  This field is used if the CSBAUD bit in the <b>EPIHBnCFG2</b> register is enabled.
				Value Description
				0 The READ strobe for CS1n accesses is RDn (active Low).
				1 The READ strobe for CS1n accesses is RD (active High).
19:8	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:6	WRWS	R/W	0x0	CS1n Write Wait States
				This field adds wait states to the data phase of CS1n accesses (the address phase is not affected).
				The effect is to delay the rising edge of WRn (or the falling edge of WR). Each wait state encoding adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active WRn is 2 EPI clocks.
				0x1 Active WRn is 4 EPI clocks
				0x2 Active WRn is 6 EPI clocks
				0x3 Active WRn is 8 EPI clocks
5:4	RDWS	R/W	0x0	CS1n Read Wait States
				This field adds wait states to the data phase of CS1n accesses (the address phase is not affected).
				The effect is to delay the rising edge of RDn/Oen (or the falling edge of RD). Each wait state encoding adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active RDn is 2 EPI clocks
				0x1 Active RDn is 4 EPI clocks
				0x2 Active RDn is 6 EPI clocks
				0x3 Active RDn is 8 EPI clocks
3:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 8: EPI Host-Bus 16 Configuration 2 (EPIHB16CFG2), offset 0x014

**Important:** The MODE field in the **EPICFG** register determines which configuration register is accessed for offsets 0x010 and 0x014.

To access **EPIHB16CFG2**, the MODE field must be 0x3.

This register is used to configure operation while in Host-Bus 16 mode. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the Host-Bus 16 mode is selected again, the values must be reinitialized.

#### EPI Host-Bus 16 Configuration 2 (EPIHB16CFG2)

Base 0x400D.0000 Offset 0x014

Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	WORD		rese	rved		CSBAUD	CS	CFG	rese	rved	WRHIGH	RDHIGH		rese	rved	
Туре	R/W	RO	RO	RO	RO	R/W	R/W	R/W	RO	RO	R/W	R/W	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved						WR	WS			rese	rved				
Туре	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
31	WORD	R/W	0	Word Access Mode

By default, the EPI controller uses data bits [15:0] for Host-Bus 16 accesses. When using Word Access mode, the EPI controller can automatically route bytes of data onto the correct byte lanes such that data can be stored in bits [31:16]. When WORD is set, long variables can be used in C programs.

#### Value Description

- 0 Word Access mode is disabled.
- 1 Word Access mode is enabled.

30:27	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide
				compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
				preserved dorose a read modify write operation.

#### 26 CSBAUD R/W 0 Chip Select Baud Rate

#### Value Description

0 Same Baud Rate

All CSn use the baud rate for the external bus that is defined by the  ${\tt COUNTO}$  field in the <code>EPIBAUD</code> register.

Different Baud Rates

CS0n uses the baud rate for the external bus that is defined by the COUNTO field in the **EPIBAUD** register. CS1n uses the baud rate defined by the COUNT1 field in the **EPIBAUD** register.

Bit/Field	Name	Туре	Reset	Description
25:24	CSCFG	R/W	0x0	Chip Select Configuration This field controls the chip select options, including an ALE format, a single chip select, two chip selects, and an ALE combined with two chip selects.
				Value Description
				0x0 ALE Configuration
				EPI0S30 is used as an address latch (ALE). When using this mode, the address and data should be muxed (HB16MODE field in the <b>EPIHB16CFG</b> register should be configured to 0x0). If needed, the address can be latched by external logic.
				0x1 CSn Configuration
				EPI0S30 is used as a Chip Select (CSn). When using this mode, the address and data should not be muxed (MODE field in the <b>EPIHB16CFG</b> register should be configured to 0x1). In this mode, the WR signal (EPI0S29) and the RD signal (EPI0S28) are used to latch the address when CSn is low.
				0x2 Dual CSn Configuration
				EPI0S30 is used as CS0n and EPI0S27 is used as CS1n. Whether CS0n or CS1n is asserted is determined by the most significant address bit for a respective external address map. This configuration can be used for a RAM bank split between 2 devices as well as when using both an external RAM and an external peripheral.
				0x3 ALE with Dual CSn Configuration
				EPI0S30 is used as address latch (ALE), EPI0S27 is used as CS1n, and EPI0S26 is used as CS0n. Whether CS0n or CS1n is asserted is determined by the most significant address bit for a respective external address map.
23:22	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
21	WRHIGH	R/W	0	CS1n WRITE Strobe Polarity
				This field is used if CSBAUD bit of the EPIHBnCFG2 register is enabled.
				Value Description
				0 The WRITE strobe for CS1n accesses is WRn (active Low).
				1 The WRITE strobe for CS1n accesses is WR (active High).
20	RDHIGH	R/W	0	CS1n READ Strobe Polarity This field is used if CSBAUD bit of the EPIHBnCFG2 register is enabled.
				Value Description
				0 The READ strobe for CS1n accesses is RDn (active Low).
				1 The READ strobe for CS1n accesses is RD (active High).
19:8	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
7:6	WRWS	R/W	0x0	CS1n Write Wait States
				This field adds wait states to the data phase of CS1n accesses (the address phase is not affected).
				The effect is to delay the rising edge of WRn (or the falling edge of WR). Each wait state encoding adds 2 EPI clock cycles to the access time.
				Value Description
				0x0 Active WRn is 2 EPI clocks
				0x1 Active WRn is 4 EPI clocks.
				0x2 Active WRn is 6 EPI clocks
				0x3 Active WRn is 8 EPI clocks
5:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 9: EPI General-Purpose Configuration 2 (EPIGPCFG2), offset 0x014

Important: The MODE field in the EPICFG register determines which configuration register is accessed for offsets 0x010 and 0x014.


To access **EPIGPCFG2**, the MODE field must be 0x0.

This register is used to configure operation while in General-Purpose mode. Note that this register is reset when the MODE field in the **EPICFG** register is changed. If another mode is selected and the General-Purpose mode is selected again, the values must be reinitialized.

## EPI General-Purpose Configuration 2 (EPIGPCFG2)

Base 0x400D.0000 Offset 0x014

Type R/W, reset 0x0000.0000



DIVI ICIU	INAITIE	туре	Neset	Description
31	WORD	R/W	0	Word Access Mode

By default, the EPI controller uses data bits [7:0] when the DSIZE field in the **EPIGPCFG** register is 0x0; data bits [15:0] when the DSIZE field is 0x1; data bits [23:0] when the DSIZE field is 0x2; and data bits [31:0] when the DSIZE field is 0x3.

When using Word Access mode, the EPI controller can automatically route bytes of data onto the correct byte lanes such that data can be stored in bits [31:8] for DSIZE=0x0 and bits [31:16] for DSIZE=0x1. For DSIZE=0x2 or 0x3, this bit must be clear.

#### Value Description

- 0 Word Access mode is disabled.
- Word Access mode is enabled.

30:0 reserved RO 0x000.0000 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 10: EPI Address Map (EPIADDRMAP), offset 0x01C

This register enables address mapping. The EPI controller can directly address memory and peripherals. In addition, the EPI controller supports address mapping to allow indirect accesses in the External RAM and External Peripheral areas.


If the external device is a peripheral, including a FIFO or a directly addressable device, the EPSZ and EPADR bit fields should be configured for the address space. If the external device is SDRAM, SRAM, or NOR Flash memory, the ERADR and ERSZ bit fields should be configured for the address space.

If one of the dual chip select modes is selected (CSCFG is 0x2 or 0x3 in the **EPIHBnCFG2** register), both chip selects can share the peripheral or the memory space, or one chip select can use the peripheral space and the other can use the memory space. In the **EPIADDRMAP** register, if the EPADR field is not 0x0 and the ERADR field is 0x0, then the address specified by EPADR is used for both chip selects, with CS0n being asserted when the MSB of the address range is 0 and CS1n being asserted when the MSB of the address range is 1. If the ERADR field is not 0x0 and the EPADR field is 0x0, then the address specified by ERADR is used for both chip selects, with the MSB performing the same delineation. If both the EPADR and the ERADR are not 0x0, then CS0n is asserted for either address range defined by EPADR and CS1n is asserted for either address range defined by ERADR.

#### EPI Address Map (EPIADDRMAP)

Base 0x400D.0000 Offset 0x01C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:6	EPSZ	R/W	0x0	External Peripheral Size

This field selects the size of the external peripheral. If the size of the external peripheral is larger, a bus fault occurs. If the size of the external peripheral is smaller, it wraps (upper address bits unused).

**Note:** When not using byte selects in Host-Bus 16, data is accessed on 2-byte boundaries. As a result, the available address space is double the amount shown below.

Value Description

0x0 256 bytes; lower address range: 0x00 to 0xFF

0x1 64 KB; lower address range: 0x0000 to 0xFFFF

0x2 16 MB; lower address range: 0x000.0000 to 0xFF.FFFF

0x3 512 MB; lower address range: 0x000.0000 to 0x1FFF.FFFF

Bit/Field	Name	Туре	Reset	Description
5:4	EPADR	R/W	0x0	External Peripheral Address  This field selects address mapping for the external peripheral area.
				Value Description  0x0 Not mapped  0x1 At 0xA000.0000  0x2 At 0xC000.0000
				0x3 reserved
3:2	ERSZ	R/W	0x0	External RAM Size  This field selects the size of mapped RAM. If the size of the external memory is larger, a bus fault occurs. If the size of the external memory is smaller, it wraps (upper address bits unused):
				Value Description  0x0 256 bytes; lower address range: 0x00 to 0xFF  0x1 64 KB; lower address range: 0x0000 to 0xFFFF  0x2 16 MB; lower address range: 0x00.0000 to 0xFF.FFFF  0x3 512 MB; lower address range: 0x000.0000 to 0x1FFF.FFFF
1:0	ERADR	R/W	0x0	External RAM Address Selects address mapping for external RAM area:  Value Description  0x0 Not mapped  0x1 At 0x6000.0000  0x2 At 0x8000.0000  0x3 reserved

## Register 11: EPI Read Size 0 (EPIRSIZE0), offset 0x020 Register 12: EPI Read Size 1 (EPIRSIZE1), offset 0x030

This register selects the size of transactions when performing non-blocking reads with the **EPIRPSTDn** registers. This size affects how the external address is incremented.

The SIZE field must match the external data width as configured in the EPIHBnCFG or EPIGPCFG register if the WORD bit is clear in the EPIHBnCFG2 or EPIGPCFG2 register. If the WORD bit is set, the SIZE field must be greater than or equal to the external data width.


SDRAM mode uses a 16-bit data interface. If SIZE is 0x1, data is returned on the least significant bits (D[7:0]), and the remaining bits D[31:8] are all zeros, therefore the data on bits D[15:8] is lost. If SIZE is 0x2, data is returned on the least significant bits (D[15:0]), and the remaining bits D[31:16] are all zeros.

Note that changing this register while a read is active has an unpredictable effect.

#### EPI Read Size 0 (EPIRSIZE0)

Base 0x400D.0000 Offset 0x020

Type R/W, reset 0x0000.0003



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1:0	SIZE	R/W	0x3	Current Size

Value Description

0x0 reserved

0x1 Byte (8 bits)

0x2 Half-word (16 bits)

0x3 Word (32 bits)

# Register 13: EPI Read Address 0 (EPIRADDR0), offset 0x024 Register 14: EPI Read Address 1 (EPIRADDR1), offset 0x034


This register holds the current address value. When performing non-blocking reads via the **EPIRPSTDn** registers, this register's value forms the address (when used by the mode). That is, when an **EPIRPSTDn** register is written with a non-0 value, this register is used as the first address. After each read, it is incremented by the size specified by the corresponding **EPIRSIZEn** register. Thus at the end of a read, this register contains the next address for the next read. For example, if the last read was 0x20, and the size is word, then the register contains 0x24. When a non-blocking read is cancelled, this register contains the next address that would have been read had it not been cancelled. For example, if reading by bytes and 0x103 had been read but not 0x104, this register contains 0x104. In this manner, the system can determine the number of values in the NBRFIFO to drain.

Note that changing this register while a read is active has an unpredictable effect due to race condition.

#### EPI Read Address 0 (EPIRADDR0)

Base 0x400D.0000

Offset 0x024 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:29	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
28:0	ADDR	R/W	0x000.0000	Current Address Next address to read.

## Register 15: EPI Non-Blocking Read Data 0 (EPIRPSTD0), offset 0x028 Register 16: EPI Non-Blocking Read Data 1 (EPIRPSTD1), offset 0x038

This register sets up a non-blocking read via the external interface. A non-blocking read is started by writing to this register with the count (other than 0). Clearing this register terminates an active non-blocking read as well as cancelling any that are pending. This register should always be cleared before writing a value other than 0; failure to do so can cause improper operation. Note that both NBR channels can be enabled at the same time, but NBR channel 0 has the highest priority and channel 1 does not start until channel 0 is finished.

The first address is based on the corresponding **EPIRADDRn** register. The address register is incremented by the size specified by the **EPIRSIZEn** register after each read. If the size is less than a word, only the least significant bits of data are filled into the NBRFIFO; the most significant bits are cleared.

Note that all three registers may be written using one STM instruction, such as with a structure copy in C/C++.

The data may be read from the **EPIREADFIFO** register after the read cycle is completed. The interrupt mechanism is normally used to trigger the FIFO reads via ISR or µDMA.

If the countdown has not reached 0 and the NBRFIFO is full, the external interface waits until a NBRFIFO entry becomes available to continue.

Note: if a blocking read or write is performed through the address mapped area (at 0x6000.0000 through 0xDFFF.FFFF), any current non-blocking read is paused (at the next safe boundary), and the blocking request is inserted. After completion of any blocking reads or writes, the non-blocking reads continue from where they were paused.


The other way to read data is via the address mapped locations (see the **EPIADDRMAP** register), but this method is blocking (core or µDMA waits until result is returned).

To cancel a non-blocking read, clear this register. To make sure that all values read are drained from the NBRFIFO, the **EPISTAT** register must be consulted to be certain that bits NBRBUSY and ACTIVE are cleared. One of these registers should not be cleared until either the other **EPIRPSTDn** register becomes active or the external interface is not busy. At that point, the corresponding **EPIRADDRn** register indicates how many values were read.

#### EPI Non-Blocking Read Data 0 (EPIRPSTD0)

Base 0x400D.0000 Offset 0x028

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
12:0	POSTCNT	R/W	0x000	Post Count  A write of a non-zero value starts a read operation for that count. Note that it is the software's responsibility to handle address wrap-around. Reading this register provides the current count.  A write of 0 cancels a non-blocking read (whether active now or pending). Prior to writing a non-zero value, this register must first be cleared.

## Register 17: EPI Status (EPISTAT), offset 0x060

This register indicates which non-blocking read register is currently active; it also indicates whether the external interface is busy performing a write or non-blocking read (it cannot be performing a blocking read, as the bus would be blocked and as a result, this register could not be accessed).


This register is useful to determining which non-blocking read register is active when both are loaded with values and when implementing sequencing or sharing.

This register is also useful when canceling non-blocking reads, as it shows how many values were read by the canceled side.

#### EPI Status (EPISTAT)

Base 0x400D.0000 Offset 0x060

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:10	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	CELOW	RO	0	Clock Enable Low  This bit provides information on the clock status when in general-purpose mode and the RDYEN bit is set.  Value Description
				The external device is not gating the clock.
8	XFFULL	RO	0	External FIFO Full  This bit provides information on the XFIFO when in the FIFO sub-mode

#### Value Description

- 0 The external device is not gating the clock.
- The XFIFO is signaling as full (the FIFO full signal is high). Attempts to write in this case are stalled until the XFIFO full signal goes low or the counter times out as specified by the MAXWAIT field.

of the Host Bus n mode with the XFFEN bit set in the **EPIHBnCFG** register. The EPI0S26 signal reflects the status of this bit.


Bit/Field	Name	Туре	Reset	Description
7	XFEMPTY	RO	0	External FIFO Empty
				This bit provides information on the XFIFO when in the FIFO sub-mode of the Host Bus n mode with the XFEEN bit set in the <b>EPIHBNCFG</b> register. The EPI0S27 signal reflects the status of this bit.
				Value Description
				0 The external device is not gating the clock.
				1 The XFIFO is signaling as empty (the FIFO empty signal is high).
				Attempts to read in this case are stalled until the XFIFO empty signal goes low or the counter times out as specified by the MAXWAIT field.
6	INITSEQ	RO	0	Initialization Sequence
				Value Description
				The SDRAM interface is not in the wakeup period.
				1 The SDRAM interface is running through the wakeup period (greater than $100 \mu s$ ).
				If an attempt is made to read or write the SDRAM during this period, the access is held off until the wakeup period is complete.
5	WBUSY	RO	0	Write Busy
				Value Description
				O The external interface is not performing a write.
				1 The external interface is performing a write.
4	NBRBUSY	RO	0	Non-Blocking Read Busy
				Value Description
				O The external interface is not performing a non-blocking read.
				1 The external interface is performing a non-blocking read, or if the non-blocking read is paused due to a write.
3:1	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ACTIVE	RO	0	Register Active
				Value Description
				0 If NBRBUSY is set, the <b>EPIRPSTD0</b> register is active.
				If the NBRBUSY bit is clear, then neither <b>EPIRPSTDx</b> register is active.
				1 The <b>EPIRPSTD1</b> register is active.

## Register 18: EPI Read FIFO Count (EPIRFIFOCNT), offset 0x06C

This register returns the number of values in the NBRFIFO (the data in the NBRFIFO can be read via the **EPIREADFIFO** register). A race is possible, but that only means that more values may come in after this register has been read.

## EPI Read FIFO Count (EPIRFIFOCNT)

Base 0x400D.0000 Offset 0x06C Type RO, reset -



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	COUNT	RO	_	FIFO Count

Number of filled entries in the NBRFIFO.

Register 19: EPI Read FIFO (EPIREADFIFO), offset 0x070

Register 20: EPI Read FIFO Alias 1 (EPIREADFIFO1), offset 0x074

Register 21: EPI Read FIFO Alias 2 (EPIREADFIFO2), offset 0x078

Register 22: EPI Read FIFO Alias 3 (EPIREADFIFO3), offset 0x07C

Register 23: EPI Read FIFO Alias 4 (EPIREADFIFO4), offset 0x080

Register 24: EPI Read FIFO Alias 5 (EPIREADFIFO5), offset 0x084

Register 25: EPI Read FIFO Alias 6 (EPIREADFIFO6), offset 0x088


Register 26: EPI Read FIFO Alias 7 (EPIREADFIFO7), offset 0x08C

**Important:** This register is read-sensitive. See the register description for details.

This register returns the contents of the NBRFIFO or 0 if the NBRFIFO is empty. Each read returns the data that is at the top of the NBRFIFO, and then empties that value from the NBRFIFO. The alias registers can be used with the LDMIA instruction for more efficient operation (for up to 8 registers). See Cortex™-M3/M4 Instruction Set Technical User's Manual for more information on the LDMIA instruction.

#### EPI Read FIFO (EPIREADFIFO)

Base 0x400D.0000 Offset 0x070 Type RO, reset -



31:0 DATA RO Reads Data

> This field contains the data that is at the top of the NBRFIFO. After being read, the NBRFIFO entry is removed.

## Register 27: EPI FIFO Level Selects (EPIFIFOLVL), offset 0x200

This register allows selection of the FIFO levels which trigger an interrupt to the interrupt controller or, more efficiently, a DMA request to the  $\mu$ DMA. The NBRFIFO select triggers on fullness such that it triggers on match or above (more full). The WFIFO triggers on emptiness such that it triggers on match or below (less entries).

It should be noted that the FIFO triggers are not identical to other such FIFOs in Stellaris peripherals. In particular, empty and full triggers are provided to avoid wait states when using blocking operations.

The settings in this register are only meaningful if the µDMA is active or the interrupt is enabled.

Additionally, this register allows protection against writes stalling and notification of performing blocking reads which stall for extra time due to preceding writes. The two functions behave in a non-orthogonal way because read and write are not orthogonal.


The write error bit configures the system such that an attempted write to an already full WFIFO abandons the write and signals an error interrupt to prevent accidental latencies due to stalling writes.

The read error bit configures the system such that after a read has been stalled due to any preceding writes in the WFIFO, the error interrupt is generated. Note that the excess stall is not prevented, but an interrupt is generated after the fact to notify that it has happened.

#### EPI FIFO Level Selects (EPIFIFOLVL)

Base 0x400D.0000 Offset 0x200

Type R/W, reset 0x0000.0033



Bit/Field	Name	Type	Reset	Description
31:18	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
17	WFERR	R/W	0	Write Full Error

#### Value Description

- The Write Full error interrupt is disabled. Writes are stalled when the WFIFO is full until a space becomes available but an error is not generated. Note that the Cortex-M3 write buffer may hide that stall if no other memory transactions are attempted during that time.
- 1 This bit enables the Write Full error interrupt (WTFULL in the **EPIEISC** register) to be generated when a write is attempted and the WFIFO is full. The write stalls until a WFIFO entry becomes available.

Bit/Field	Name	Туре	Reset	Description
16	RSERR	R/W	0	Read Stall Error
				Value Description
				The Read Stalled error interrupt is disabled. Reads behave as normal and are stalled until any preceding writes have completed and the read has returned a result.
				This bit enables the Read Stalled error interrupt (RSTALL in the <b>EPIEISC</b> register) to be generated when a read is attempted and the WFIFO is not empty. The read is still stalled during the time the WFIFO drains, but this error notifies the application that this excess delay has occurred.
				Note that the configuration of this bit has no effect on non-blocking reads.
15:7	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:4	WRFIFO	R/W	0x3	Write FIFO
				This field configures the trigger point for the WFIFO.
				Value Description
				0x0 Trigger when there are any spaces available in the WFIFO.
				0x1 reserved
				0x2 Trigger when there are up to 3 spaces available in the WFIFO.
				0x3 Trigger when there are up to 2 spaces available in the WFIFO.
				0x4 Trigger when there is 1 space available in the WFIFO.
				0x5-0x7 reserved
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2:0	RDFIFO	R/W	0x3	Read FIFO
				This field configures the trigger point for the NBRFIFO.
				Value Description
				0x0 reserved
				0x1 Trigger when there are 1 or more entries in the NBRFIFO.
				0x2 Trigger when there are 2 or more entries in the NBRFIFO.
				0x3 Trigger when there are 4 or more entries in the NBRFIFO.
				0x4 Trigger when there are 6 or more entries in the NBRFIFO.
				0x5 Trigger when there are 7 or more entries in the NBRFIFO.
				0x6 Trigger when there are 8 entries in the NBRFIFO.
				0x7 reserved

## Register 28: EPI Write FIFO Count (EPIWFIFOCNT), offset 0x204

This register contains the number of slots currently available in the WFIFO. This register may be used for polled writes to avoid stalling and for blocking reads to avoid excess stalling (due to undrained writes). An example use for writes may be:


```
for (idx = 0; idx < cnt; idx++) {
while (EPIWFIFOCNT == 0);
*ext_ram = *mydata++;
}</pre>
```

The above code ensures that writes to the address mapped location do not occur unless the WFIFO has room. Although polling makes the code wait (spinning in the loop), it does not prevent interrupts being serviced due to bus stalling.

#### EPI Write FIFO Count (EPIWFIFOCNT)

Base 0x400D.0000 Offset 0x204

Type RO, reset 0x0000.0004



Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2:0	WTAV	RO	0x4	Available Write Transactions

The number of write transactions available in the WFIFO.

When clear, a write is stalled waiting for a slot to become free (from a preceding write completing).

## Register 29: EPI Interrupt Mask (EPIIM), offset 0x210

This register is the interrupt mask set or clear register. For each interrupt source (read, write, and error), a mask value of 1 allows the interrupt source to trigger an interrupt to the interrupt controller; a mask value of 0 prevents the interrupt source from triggering an interrupt.

Note that interrupt masking has no effect on  $\mu DMA$ , which operates off the raw source of the read and write interrupts.


#### EPI Interrupt Mask (EPIIM)

Base 0x400D.0000

Offset 0x210

1

Type R/W, reset 0x0000.0000



RDIM R/W 0 Read FIFO Full Interrupt Mask

#### Value Description

0 RDRIS in the EPIRIS register is masked and does not cause an interrupt.

interrupt to the interrupt controller.

- 1 RDRIS in the EPIRIS register is not masked and can trigger an interrupt to the interrupt controller.
- 0 ERRIM R/W 0 Error Interrupt Mask

#### Value Description

- 0 ERRIS in the EPIRIS register is masked and does not cause an interrupt.
- 1 ERRIS in the EPIRIS register is not masked and can trigger an interrupt to the interrupt controller.

## Register 30: EPI Raw Interrupt Status (EPIRIS), offset 0x214

This register is the raw interrupt status register. On a read, it gives the current state of each interrupt source. A write has no effect.

Note that raw status for read and write is set or cleared based on FIFO fullness as controlled by **EPIFIFOLVL**.

Raw status for error is held until the error is cleared by writing to the **EPIEISC** register.


#### EPI Raw Interrupt Status (EPIRIS)

Base 0x400D.0000 Offset 0x214

2

**WRRIS** 

Type RO, reset 0x0000.0004



Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

RO

#### Value Description

Write Raw Interrupt Status

- The number of available entries in the WFIFO is above the range specified by the WRFIFO field in the EPIFIFOLVL register.
- The number of available entries in the WFIFO is within the trigger range specified by the WRFIFO field in the EPIFIFOLVL register.

This bit is cleared when the level in the WFIFO is above the trigger point programmed by the  ${\tt WRFIFO}$  field.

1 RDRIS RO 0 Read Raw Interrupt Status

#### Value Description

- The number of valid entries in the NBRFIFO is below the trigger range specified by the RDFIFO field in the EPIFIFOLVL register.
- 1 The number of valid entries in the NBRFIFO is in the trigger range specified by the RDFIFO field in the EPIFIFOLVL register.

This bit is cleared when the level in the NBRFIFO is below the trigger point programmed by the RDFIFO field.

Bit/Field	Name	Туре	Reset	Description
0	ERRRIS	RO	0	Error Raw Interrupt Status  The error interrupt occurs in the following situations:
				■ WFIFO Full. For a full WFIFO to generate an erro

- WFIFO Full. For a full WFIFO to generate an error interrupt, the WFERR bit in the EPIFIFOLVL register must be set.
- Read Stalled. For a stalled read to generate an error interrupt, the RSERR bit in the EPIFIFOLVL register must be set.
- Timeout. If the MAXWAIT field in the **EPIGPCFG** register is configured to a value other than 0, a timeout error occurs when iRDY or XFIFO not-ready signals hold a transaction for more than the count in the MAXWAIT field.

Value Description

- 0 An error has not occurred.
- 1 A WFIFO Full, a Read Stalled, or a Timeout error has occurred.

To determine which error occurred, read the status of the **EPI Error Interrupt Status and Clear (EPIEISC)** register. This bit is cleared by writing a 1 to the bit in the **EPIEISC** register that caused the interrupt.

## Register 31: EPI Masked Interrupt Status (EPIMIS), offset 0x218

This register is the masked interrupt status register. On read, it gives the current state of each interrupt source (read, write, and error) after being masked via the **EPIIM** register. A write has no effect.

The values returned are the ANDing of the **EPIIM** and **EPIRIS** registers. If a bit is set in this register, the interrupt is sent to the interrupt controller.

#### EPI Masked Interrupt Status (EPIMIS)


**WRMIS** 

Base 0x400D.0000

2

Offset 0x218

Type RO, reset 0x0000.0000



#### Value Description

Write Masked Interrupt Status

- The number of available entries in the WFIFO is above the range specified by the trigger level or the interrupt is masked.
- The number of available entries in the WFIFO is within the range specified by the trigger level (the WRFIFO field in the **EPIFIFOLVL** register) and the WRIM bit in the **EPIIM** register is set, triggering an interrupt to the interrupt controller.

1 RD	MIS RO	0 C	Read Masked	Interrupt Status
------	--------	-----	-------------	------------------

RO

0

#### Value Description

- The number of valid entries in the NBRFIFO is below the range specified by the trigger level or the interrupt is masked.
- The number of valid entries in the NBRFIFO is within the range specified by the trigger level (the RDFIFO field in the **EPIFIFOLVL** register) and the RDIM bit in the **EPIIM** register is set, triggering an interrupt to the interrupt controller.

### 0 ERRMIS RO 0 Error Masked Interrupt Status

#### Value Description

- 0 An error has not occurred or the interrupt is masked.
- A WFIFO Full, a Read Stalled, or a Timeout error has occurred and the ERIM bit in the **EPIIM** register is set, triggering an interrupt to the interrupt controller.


## Register 32: EPI Error and Interrupt Status and Clear (EPIEISC), offset 0x21C

This register is used to clear a pending error interrupt. Clearing any defined bit in the **EPIEISC** has no effect; setting a bit clears the error source and the raw error returns to 0. When any of these bits are read as set it indicates that the ERRRIS bit in the **EPIRIS** register is set and an EPI controller error is sent to the interrupt controller if the ERIM bit in the **EPIIM** register is set. If any of bits [2:0] are written as 1, the register bit being written to, as well as the ERRIS bit in the **EPIRIS** register and the ERIM bit in the **EPIIM** register are cleared. Note that writing to this register and reading back immediately (pipelined by the processor) returns the old register contents. One cycle is needed between write and read.

EPI Error and Interrupt Status and Clear (EPIEISC)

Base 0x400D.0000 Offset 0x21C

Type R/W1C, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	WTFULL	R/W1C	0	Write FIFO Full Error
				Value Description
				O The WFERR bit is not enabled or no writes are stalled.
				1 The WFERR bit is enabled and a write is stalled due to the WFIFO being full.
				Writing a 1 to this bit clears it, as well as as the ERRRIS and ERIM bits.
1	RSTALL	R/W1C	0	Read Stalled Error

#### Value Description

- O The RSERR bit is not enabled or no pending reads are stalled.
- 1 The RSERR bit is enabled and a pending read is stalled due to writes in the WFIFO.

Writing a 1 to this bit clears it, as well as as the  ${\tt ERRRIS}$  and  ${\tt ERIM}$  bits.

Bit/Field	Name	Туре	Reset	Description
0	TOUT	R/W1C	0	Timeout Error  This bit is the timeout error source. The timeout error occurs when the iRDY or XFIFO not-ready signals hold a transaction for more than the count in the MAXWAIT field (when not 0).
				Value Description
				0 No timeout error has occurred.
				1 A timeout error has occurred.
				Writing a 1 to this bit clears it, as well as as the ERRRIS and ERIM bits.

## 10 General-Purpose Timers

Programmable timers can be used to count or time external events that drive the Timer input pins. The Stellaris<sup>®</sup> General-Purpose Timer Module (GPTM) contains four GPTM blocks. Each GPTM block provides two 16-bit timers/counters (referred to as Timer A and Timer B) that can be configured to operate independently as timers or event counters, or concatenated to operate as one 32-bit timer or one 32-bit Real-Time Clock (RTC). Timers can also be used to trigger µDMA transfers.

In addition, timers can be used to trigger analog-to-digital conversions (ADC). The ADC trigger signals from all of the general-purpose timers are ORed together before reaching the ADC module, so only one timer should be used to trigger ADC events.

The GPT Module is one timing resource available on the Stellaris microcontrollers. Other timer resources include the System Timer (SysTick) (see 114) and the PWM timer in the PWM module (see "PWM Timer" on page 1141).

The General-Purpose Timer Module (GPTM) contains four GPTM blocks with the following functional options:

- Operating modes:
  - 16- or 32-bit programmable one-shot timer
  - 16- or 32-bit programmable periodic timer
  - 16-bit general-purpose timer with an 8-bit prescaler
  - 32-bit Real-Time Clock (RTC) when using an external 32.768-KHz clock as the input
  - 16-bit input-edge count- or time-capture modes
  - 16-bit PWM mode with software-programmable output inversion of the PWM signal
- Count up or down
- Eight Capture Compare PWM pins (CCP)
- Daisy chaining of timer modules to allow a single timer to initiate multiple timing events
- ADC event trigger
- User-enabled stalling when the microcontroller asserts CPU Halt flag during debug (excluding RTC mode)
- Ability to determine the elapsed time between the assertion of the timer interrupt and entry into the interrupt service routine.
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Dedicated channel for each timer
  - Burst request generated on timer interrupt

## 10.1 Block Diagram

In the block diagram, the specific Capture Compare PWM (CCP) pins available depend on the Stellaris device. See Table 10-1 on page 538 for the available CCP pins and their timer assignments.

Figure 10-1. GPTM Module Block Diagram




Table 10-1. Available CCP Pins

Timer	16-Bit Up/Down Counter	Even CCP Pin	Odd CCP Pin
Timer 0	TimerA	CCP0	-
	TimerB	-	CCP1
Timer 1	TimerA	CCP2	-
	TimerB	-	CCP3
Timer 2	TimerA	CCP4	-
	TimerB	-	CCP5
Timer 3	TimerA	CCP6	-
	TimerB	-	CCP7

## 10.2 Signal Description

The following table lists the external signals of the GP Timer module and describes the function of each. The GP Timer signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for these GP Timer signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the GP Timer function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port** 

**Control (GPIOPCTL)** register (page 448) to assign the GP Timer signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 10-2. General-Purpose Timers Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP0	13 22 23 39 42 55 66 72 91	PD3 (4) PC7 (4) PC6 (6) PJ2 (9) PF4 (1) PJ7 (10) PB0 (1) PB2 (5) PB5 (4) PD4 (1)	I/O	TTL	Capture/Compare/PWM 0.
CCP1	24 25 34 54 67 90 96 100	PC5 (1) PC4 (9) PA6 (2) PJ6 (10) PB1 (4) PB6 (1) PE3 (1) PD7 (3)	I/O	TTL	Capture/Compare/PWM 1.
CCP2	6 11 25 41 53 67 75 91 95	PE4 (6) PD1 (10) PC4 (5) PF5 (1) PJ5 (10) PB1 (1) PE1 (4) PB5 (6) PE2 (5) PD5 (1)	I/O	TTL	Capture/Compare/PWM 2.
CCP3	6 23 24 35 61 72 74 97	PE4 (1) PC6 (1) PC5 (5) PA7 (7) PF1 (10) PB2 (4) PE0 (3) PD4 (2)	I/O	TTL	Capture/Compare/PWM 3.
CCP4	22 25 35 52 95 98	PC7 (1) PC4 (6) PA7 (2) PJ4 (10) PE2 (1) PD5 (2)	I/O	TTL	Capture/Compare/PWM 4.
CCP5	5 12 25 36 90 91	PE5 (1) PD2 (4) PC4 (1) PG7 (8) PB6 (6) PB5 (2)	I/O	TTL	Capture/Compare/PWM 5.

Table 10-2. General-Purpose Timers Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP6	10 12 50 75 86 91	PD0 (6) PD2 (2) PJ3 (10) PE1 (5) PH0 (1) PB5 (3)	I/O	TTL	Capture/Compare/PWM 6.
CCP7	11 13 85 90 96	PD1 (6) PD3 (2) PH1 (1) PB6 (2) PE3 (5)	I/O	TTL	Capture/Compare/PWM 7.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 10-3. General-Purpose Timers Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP0	H1 L2 M2 K6 K4 L12 E12 A11 B7 B5	PD3 (4) PC7 (4) PC6 (6) PJ2 (9) PF4 (1) PJ7 (10) PB0 (1) PB2 (5) PB5 (4) PD4 (1)	I/O	TTL	Capture/Compare/PWM 0.
CCP1	M1 L1 L6 L10 D12 A7 B4 A2	PC5 (1) PC4 (9) PA6 (2) PJ6 (10) PB1 (4) PB6 (1) PE3 (1) PD7 (3)	I/O	TTL	Capture/Compare/PWM 1.
CCP2	B2 G2 L1 K3 K12 D12 A12 B7 A4 C6	PE4 (6) PD1 (10) PC4 (5) PF5 (1) PJ5 (10) PB1 (1) PE1 (4) PB5 (6) PE2 (5) PD5 (1)	I/O	TTL	Capture/Compare/PWM 2.
CCP3	B2 M2 M1 M6 H12 A11 B11 B5	PE4 (1) PC6 (1) PC5 (5) PA7 (7) PF1 (10) PB2 (4) PE0 (3) PD4 (2)	I/O	TTL	Capture/Compare/PWM 3.

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP4	L2 L1 M6 K11 A4 C6	PC7 (1) PC4 (6) PA7 (2) PJ4 (10) PE2 (1) PD5 (2)	I/O	TTL	Capture/Compare/PWM 4.
CCP5	B3 H2 L1 C10 A7 B7	PE5 (1) PD2 (4) PC4 (1) PG7 (8) PB6 (6) PB5 (2)	I/O	TTL	Capture/Compare/PWM 5.
CCP6	G1 H2 M10 A12 C9 B7	PD0 (6) PD2 (2) PJ3 (10) PE1 (5) PH0 (1) PB5 (3)	I/O	TTL	Capture/Compare/PWM 6.
CCP7	G2	PD1 (6)	I/O	TTL	Capture/Compare/PWM 7.

Table 10-3. General-Purpose Timers Signals (108BGA) (continued)

PD3 (2)

PH1 (1)

PB6 (2)

PE3 (5)

H1

C8

Α7

B4

# 10.3 Functional Description

The main components of each GPTM block are two free-running up/down counters (referred to as Timer A and Timer B), two match registers, two prescaler match registers, two shadow registers, and two load/initialization registers and their associated control functions. The exact functionality of each GPTM is controlled by software and configured through the register interface. Timer A and Timer B can be used individually, in which case they have a 16-bit counting range. In addition, Timer A and Timer B can be concatenated to provide a 32-bit counting range. Note that the prescaler can only be used when the timers are used individually.

The available modes for each GPTM block are shown in Table 10-4 on page 541. Note that when counting down in one-shot or periodic modes, the prescaler acts as a true prescaler and contains the least-significant bits of the count. When counting up in one-shot or periodic modes, the prescaler acts as a timer extension and holds the most-significant bits of the count. In input edge count mode, the prescaler always acts as a timer extension, regardless of the count direction.

Table 10-4. General-Purpose Timer Capabilities

Mode	Timer Use	Count Direction	Counter Size	Prescaler Size <sup>a</sup>
On a short	Individual	Up or Down	16-bit	8-bit
One-shot	Concatenated	Up or Down	32-bit	-
D : "	Individual	Up or Down	16-bit	8-bit
Periodic	Concatenated	Up or Down	32-bit	-
RTC	Concatenated	Up	32-bit	-
Edge Count	Individual	Down	16-bit	8-bit
Edge Time	Individual	Down	16-bit	-

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 10-4. General-Purpose Timer Capabilities (continued)

Mode	Timer Use	Count Direction	Counter Size	Prescaler Size <sup>a</sup>
PWM	Individual	Down	16-bit	-

a. The prescaler is only available when the timers are used individually

Software configures the GPTM using the **GPTM Configuration (GPTMCFG)** register (see page 554), the **GPTM Timer A Mode (GPTMTAMR)** register (see page 555), and the **GPTM Timer B Mode (GPTMTBMR)** register (see page 557). When in one of the concatentated modes, Timer A and Timer B can only operate in one mode. However, when configured in an individual mode, Timer A and Timer B can be independently configured in any combination of the individual modes.

### 10.3.1 GPTM Reset Conditions

After reset has been applied to the GPTM module, the module is in an inactive state, and all control registers are cleared and in their default states. Counters Timer A and Timer B are initialized to all 1s, along with their corresponding load registers: the GPTM Timer A Interval Load (GPTMTAILR) register (see page 572) and the GPTM Timer B Interval Load (GPTMTBILR) register (see page 573) and shadow registers: the GPTM Timer A Value (GPTMTAV) register (see page 582) and the GPTM Timer B Value (GPTMTBV) register (see page 583). The prescale counters are initialized to 0x00: the GPTM Timer A Prescale (GPTMTAPR) register (see page 576) and the GPTM Timer B Prescale (GPTMTBPR) register (see page 577).

### 10.3.2 Timer Modes

This section describes the operation of the various timer modes. When using Timer A and Timer B in concatenated mode, only the Timer A control and status bits must be used; there is no need to use Timer B control and status bits. The GPTM is placed into individual/split mode by writing a value of 0x4 to the **GPTM Configuration (GPTMCFG)** register (see page 554). In the following sections, the variable "n" is used in bit field and register names to imply either a Timer A function or a Timer B function. Throughout this section, the timeout event in down-count mode is 0x0 and in up-count mode is the value in the **GPTM Timer n Interval Load (GPTMTnILR)** and the optional **GPTM Timer n Prescale (GPTMTnPR)** registers.

#### 10.3.2.1 One-Shot/Periodic Timer Mode

The selection of one-shot or periodic mode is determined by the value written to the TnMR field of the **GPTM Timer n Mode (GPTMTnMR)** register (see page 555). The timer is configured to count up or down using the TnCDIR bit in the **GPTMTnMR** register.

When software sets the  $\mathtt{TnEN}$  bit in the **GPTM Control (GPTMCTL)** register (see page 559), the timer begins counting up from 0x0 or down from its preloaded value. Alternatively, if the  $\mathtt{TnWOT}$  bit is set in the **GPTMTnMR** register, once the  $\mathtt{TnEN}$  bit is set, the timer waits for a trigger to begin counting (see the section called "Wait-for-Trigger Mode" on page 544). Table 10-5 on page 542 shows the values that are loaded into the timer registers when the timer is enabled.

Table 10-5. Counter Values When the Timer is Enabled in Periodic or One-Shot Modes

Register	Count Down Mode	Count Up Mode
TnR	GPTMTnILR	0x0
TnV	GPTMTnlLR	0x0

When the timer is counting down and it reaches the timeout event (0x0), the timer reloads its start value from the **GPTMTnILR** and the **GPTMTnPR** registers on the next cycle. When the timer is counting up and it reaches the timeout event (the value in the **GPTMTnILR** and the optional

**GPTMTnPR** registers), the timer reloads with 0x0. If configured to be a one-shot timer, the timer stops counting and clears the TnEN bit in the **GPTMCTL** register. If configured as a periodic timer, the timer starts counting again on the next cycle.

In periodic, snap-shot mode (TnMR field is 0x2 and the TnSNAPS bit is set in the **GPTMTnMR** register), the value of the timer at the time-out event is loaded into the **GPTMTnR** register. The free-running counter value is shown in the **GPTMTnV** register. In this manner, software can determine the time elapsed from the interrupt assertion to the ISR entry by examining the snapshot values and the current value of the free-running timer. Snapshot mode is not available when the timer is configured in one-shot mode.

In addition to reloading the count value, the GPTM generates interrupts and triggers when it reaches the time-out event. The GPTM sets the Thtoris bit in the GPTM Raw Interrupt Status (GPTMRIS) register (see page 564), and holds it until it is cleared by writing the GPTM Interrupt Clear (GPTMICR) register (see page 570). If the time-out interrupt is enabled in the GPTM Interrupt Mask (GPTMIMR) register (see page 562), the GPTM also sets the Thtomis bit in the GPTM Masked Interrupt Status (GPTMMIS) register (see page 567). By setting the Thmie bit in the GPTMThmR register, an interrupt condition can also be generated when the Timer value equals the value loaded into the GPTM Timer n Match (GPTMThMATCHR) and GPTM Timer n Prescale Match (GPTMThPMR) registers. This interrupt has the same status, masking, and clearing functions as the time-out interrupt, but uses the match interrupt bits instead (for example, the raw interrupt status is monitored via Thmris bit in the GPTM Raw Interrupt Status (GPTMRIS) register). Note that the interrupt status bits are not updated by the hardware unless the Thmie bit in the GPTMThMR register is set, which is different than the behavior for the time-out interrupt. The ADC trigger is enabled by setting the Thote bit in GPTMCTL. The μDMA trigger is enabled by configuring and enabling the appropriate μDMA channel. See "Channel Configuration" on page 351.

If software updates the **GPTMTnILR** register while the counter is counting down, the counter loads the new value on the next clock cycle and continues counting from the new value. If software updates the **GPTMTnILR** register while the counter is counting up, the timeout event is changed on the next cycle to the new value. If software updates the **GPTM Timer n Value (GPTMTnV)** register while the counter is counting up or down, the counter loads the new value on the next clock cycle and continues counting from the new value..

If the  ${\tt TnSTALL}$  bit in the **GPTMCTL** register is set, the timer freezes counting while the processor is halted by the debugger. The timer resumes counting when the processor resumes execution.

The following table shows a variety of configurations for a 16-bit free-running timer while using the prescaler. All values assume an 80-MHz clock with Tc=12.5 ns (clock period). The prescaler can only be used when a 16/32-bit timer is configured in 16-bit mode.


Prescale (8-bit value)	# of Timer Clocks (Tc) <sup>a</sup>	Max Time	Units
00000000	1	0.8192	ms
0000001	2	1.6384	ms
0000010	3	2.4576	ms
11111101	254	208.0768	ms
11111110	255	208.896	ms
11111111	256	209.7152	ms

a. Tc is the clock period.

#### Wait-for-Trigger Mode

The Wait-for-Trigger mode allows daisy chaining of the timer modules such that once configured, a single timer can initiate mulitple timing events using the Timer triggers. Wait-for-Trigger mode is enabled by setting the Timeot bit in the **GPTMTnMR** register. When the Timeot bit is set, Timer N+1 does not begin counting until the timer in the previous position in the daisy chain (Timer N) reaches its time-out event. The daisy chain is configured such that GPTM1 always follows GPTM0, GPTM2 follows GPTM1, and so on. If Timer A is in 32-bit mode (controlled by the GPTMCFG bit in the **GPTMCFG** register), it triggers Timer A in the next module. If Timer A is in 16-bit mode, it triggers Timer B in the same module, and Timer B triggers Timer A in the next module. Care must be taken that the TAWOT bit is never set in GPTM0. Figure 10-2 on page 544 shows how the GPTMCFG bit affects the daisy chain. This function is valid for both one-shot and periodic modes.

Figure 10-2. Timer Daisy Chain



### 10.3.2.2 Real-Time Clock Timer Mode

In Real-Time Clock (RTC) mode, the concatenated versions of the Timer A and Timer B registers are configured as an up-counter. When RTC mode is selected for the first time after reset, the counter is loaded with a value of 0x1. All subsequent load values must be written to the **GPTM Timer A Interval Load (GPTMTAILR)** register (see page 572). Table 10-7 on page 544 shows the values that are loaded into the timer registers when the timer is enabled.

Table 10-7. Counter Values When the Timer is Enabled in RTC Mode

Register	Count Down Mode	Count Up Mode
TnR	Not available	0x1
TnV	Not available	0x1

The input clock on a CCP input is required to be 32.768 KHz in RTC mode. The clock signal is then divided down to a 1-Hz rate and is passed along to the input of the counter.

When software writes the TAEN bit in the **GPTMCTL** register, the counter starts counting up from its preloaded value of 0x1. When the current count value matches the preloaded value in the **GPTMTAMATCHR** register, the GPTM asserts the RTCRIS bit in **GPTMRIS** and continues counting until either a hardware reset, or it is disabled by software (clearing the TAEN bit). When the timer value reaches the terminal count, the timer rolls over and continues counting up from 0x0. If the RTC interrupt is enabled in **GPTMIMR**, the GPTM also sets the RTCMIS bit in **GPTMMIS** and generates a controller interrupt. The status flags are cleared by writing the RTCCINT bit in **GPTMICR**.

In this mode, the **GPTMTnR** and **GPTMTnV** registers always have the same value.

In addition to generating interrupts, a μDMA trigger can be generated. The μDMA trigger is enabled by configuring and enabling the appropriate μDMA channel. See "Channel Configuration" on page 351.

If the TASTALL bit in the **GPTMCTL** register is set, the timer does not freeze when the processor is halted by the debugger if the RTCEN bit is set in **GPTMCTL**.

### 10.3.2.3 Input Edge-Count Mode

**Note:** For rising-edge detection, the input signal must be High for at least two system clock periods following the rising edge. Similarly, for falling-edge detection, the input signal must be Low for at least two system clock periods following the falling edge. Based on this criteria, the maximum input frequency for edge detection is 1/4 of the system frequency.

In Edge-Count mode, the timer is configured as a 24-bit down-counter including the optional prescaler with the upper count value stored in the **GPTM Timer n Prescale (GPTMTnPR)** register and the lower bits in the **GPTMTnR** register. In this mode, the timer is capable of capturing three types of events: rising edge, falling edge, or both. To place the timer in Edge-Count mode, the <code>TnCMR</code> bit of the **GPTMTnMR** register must be cleared. The type of edge that the timer counts is determined by the <code>TnEVENT</code> fields of the **GPTMCTL** register. During initialization, the **GPTMTnMATCHR** and **GPTMTnPMR** registers are configured so that the difference between the value in the **GPTMTnILR** and **GPTMTnPR** registers and the **GPTMTnMATCHR** and **GPTMTnPMR** registers equals the number of edge events that must be counted. Table 10-8 on page 545 shows the values that are loaded into the timer registers when the timer is enabled.

Table 10-8. Counter Values When the Timer is Enabled in Input Edge-Count Mode

Register	Count Down Mode	Count Up Mode
TnR	GPTMTnlLR	Not available
TnV	GPTMTnlLR	Not available

When software writes the TnEN bit in the GPTM Control (GPTMCTL) register, the timer is enabled for event capture. Each input event on the CCP pin decrements the counter by 1 until the event count matches GPTMTnMATCHR and GPTMTnPMR. When the counts match, the GPTM asserts the CnMRIS bit in the GPTM Raw Interrupt Status (GPTMRIS) register, and holds it until it is cleared by writing the GPTM Interrupt Clear (GPTMICR) register. If the capture mode match interrupt is enabled in the GPTM Interrupt Mask (GPTMIMR) register, the GPTM also sets the CnMMIS bit in the GPTM Masked Interrupt Status (GPTMMIS) register. In this mode, the GPTMTnR register holds the count of the input events while the GPTMTnV register holds the free-running timer value.

In addition to generating interrupts, an ADC and/or a  $\mu$ DMA trigger can be generated. The ADC trigger is enabled by setting the ThOTE bit in **GPTMCTL**. The  $\mu$ DMA trigger is enabled by configuring and enabling the appropriate  $\mu$ DMA channel. See "Channel Configuration" on page 351.

After the match value is reached, the counter is then reloaded using the value in **GPTMTnlLR** and **GPTMTnPR** registers, and stopped because the GPTM automatically clears the  $\mathtt{TnEN}$  bit in the **GPTMCTL** register. Once the event count has been reached, all further events are ignored until  $\mathtt{TnEN}$  is re-enabled by software.

Figure 10-3 on page 546 shows how Input Edge-Count mode works. In this case, the timer start value is set to **GPTMTnILR** =0x000A and the match value is set to **GPTMTnMATCHR** =0x0006 so that four edge events are counted. The counter is configured to detect both edges of the input signal.

Note that the last two edges are not counted because the timer automatically clears the TnEN bit after the current count matches the value in the **GPTMTnMATCHR** register.




Figure 10-3. Input Edge-Count Mode Example

### 10.3.2.4 Input Edge-Time Mode

**Note:** For rising-edge detection, the input signal must be High for at least two system clock periods following the rising edge. Similarly, for falling edge detection, the input signal must be Low for at least two system clock periods following the falling edge. Based on this criteria, the maximum input frequency for edge detection is 1/4 of the system frequency.

The prescaler is not available in 16-Bit Input Edge-Time mode.

In Edge-Time mode, the timer is configured as a 16-bit down-counter. In this mode, the timer is initialized to the value loaded in the **GPTMTnILR**register. The timer is capable of capturing three types of events: rising edge, falling edge, or both. The timer is placed into Edge-Time mode by setting the  ${\tt TnCMR}$  bit in the **GPTMTnMR** register, and the type of event that the timer captures is determined by the  ${\tt TnEVENT}$  fields of the **GPTMCTL** register. Table 10-9 on page 546 shows the values that are loaded into the timer registers when the timer is enabled.

Table 10-9. Counter Values When the Timer is Enabled in Input Event-Count Mode

Register	Count Down Mode	Count Up Mode
TnR	GPTMTnlLR	Not available
TnV	GPTMTnlLR	Not available

When software writes the Tnen bit in the GPTMCTL register, the timer is enabled for event capture. When the selected input event is detected, the current timer counter value is captured in the GPTMTnR register and is available to be read by the microcontroller. The GPTM then asserts the Cneris bit in the GPTM Raw Interrupt Status (GPTMRIS) register, and holds it until it is cleared by writing the GPTM Interrupt Clear (GPTMICR) register. If the capture mode event interrupt is enabled in the GPTM Interrupt Mask (GPTMIMR) register, the GPTM also sets the Cnemis bit in the GPTM Masked Interrupt Status (GPTMMIS) register. In this mode, the GPTMTnR register holds the time at which the selected input event occurred while the GPTMTnV register holds the free-running timer value. These registers can be read to determine the time that elapsed between the interrupt assertion and the entry into the ISR.


In addition to generating interrupts, an ADC and/or a µDMA trigger can be generated. The ADC trigger is enabled by setting the TnOTE bit in **GPTMCTL**. The µDMA trigger is enabled by configuring and enabling the appropriate µDMA channel. See "Channel Configuration" on page 351.

After an event has been captured, the timer does not stop counting. It continues to count until the  $\mathtt{TnEN}$  bit is cleared. When the timer reaches the timeout value, it is reloaded with the value from the **GPTMTnILR** register.

Figure 10-4 on page 547 shows how input edge timing mode works. In the diagram, it is assumed that the start value of the timer is the default value of 0xFFFF, and the timer is configured to capture rising edge events.

Each time a rising edge event is detected, the current count value is loaded into the **GPTMTnR** register, and is held there until another rising edge is detected (at which point the new count value is loaded into the **GPTMTnR** register).

Figure 10-4. 16-Bit Input Edge-Time Mode Example



### 10.3.2.5 PWM Mode

**Note:** The prescaler is not available in 16-Bit PWM mode.

The GPTM supports a simple PWM generation mode. In PWM mode, the timer is configured as a 16-bit down-counter with a start value (and thus period) defined by the **GPTMTnILR** register. In this mode, the PWM frequency and period are synchronous events and therefore guaranteed to be glitch free. PWM mode is enabled with the **GPTMTnMR** register by setting the TnAMS bit to 0x1, the TnCMR bit to 0x0, and the TnMR field to 0x1 or 0x2. Table 10-10 on page 547 shows the values that are loaded into the timer registers when the timer is enabled.

Table 10-10. Counter Values When the Timer is Enabled in PWM Mode

Register	Count Down Mode	Count Up Mode
GPTMTnR	GPTMTnlLR	Not available
GPTMTnV	GPTMTnILR	Not available

When software writes the TnEN bit in the **GPTMCTL** register, the counter begins counting down until it reaches the 0x0 state. On the next counter cycle in periodic mode, the counter reloads its start value from the **GPTMTnILR** register and continues counting until disabled by software clearing the TnEN bit in the **GPTMCTL** register. No interrupts or status bits are asserted in PWM mode.

In this mode, the **GPTMTnR** and **GPTMTnV** registers always have the same value.

The output PWM signal asserts when the counter is at the value of the **GPTMTnILR** register (its start state), and is deasserted when the counter value equals the value in the **GPTMTnMATCHR** register. Software has the capability of inverting the output PWM signal by setting the TnPWML bit in the **GPTMCTL** register.

Figure 10-5 on page 548 shows how to generate an output PWM with a 1-ms period and a 66% duty cycle assuming a 50-MHz input clock and **TnPWML** =0 (duty cycle would be 33% for the **TnPWML** =1 configuration). For this example, the start value is **GPTMTnILR**=0xC350 and the match value is **GPTMTnMATCHR**=0x411A.




Figure 10-5. 16-Bit PWM Mode Example

### 10.3.3 DMA Operation

The timers each have a dedicated  $\mu DMA$  channel and can provide a request signal to the  $\mu DMA$  controller. The request is a burst type and occurs whenever a timer raw interrupt condition occurs. The arbitration size of the  $\mu DMA$  transfer should be set to the amount of data that should be transferred whenever a timer event occurs.

For example, to transfer 256 items, 8 items at a time every 10 ms, configure a timer to generate a periodic timeout at 10 ms. Configure the  $\mu$ DMA transfer for a total of 256 items, with a burst size of 8 items. Each time the timer times out, the  $\mu$ DMA controller transfers 8 items, until all 256 items have been transferred.

No other special steps are needed to enable Timers for μDMA operation. Refer to "Micro Direct Memory Access (μDMA)" on page 346 for more details about programming the μDMA controller.

### 10.3.4 Accessing Concatenated Register Values

The GPTM is placed into concatenated mode by writing a 0x0 or a 0x1 to the GPTMCFG bit field in the **GPTM Configuration (GPTMCFG)** register. In both configurations, certain registers are concatenated to form pseudo 32-bit registers. These registers include:

- GPTM Timer A Interval Load (GPTMTAILR) register [15:0], see page 572
- GPTM Timer B Interval Load (GPTMTBILR) register [15:0], see page 573
- GPTM Timer A (GPTMTAR) register [15:0], see page 580
- GPTM Timer B (GPTMTBR) register [15:0], see page 581
- GPTM Timer A Value (GPTMTAV) register [15:0], see page 582
- GPTM Timer B Value (GPTMTBV) register [15:0], see page 583
- GPTM Timer A Match (GPTMTAMATCHR) register [15:0], see page 574
- GPTM Timer B Match (GPTMTBMATCHR) register [15:0], see page 575

In the 32-bit modes, the GPTM translates a 32-bit write access to **GPTMTAILR** into a write access to both **GPTMTAILR** and **GPTMTBILR**. The resulting word ordering for such a write operation is:

```
GPTMTBILR[15:0]:GPTMTAILR[15:0]
```

Likewise, a 32-bit read access to **GPTMTAR** returns the value:

```
GPTMTBR[15:0]:GPTMTAR[15:0]
```

A 32-bit read access to **GPTMTAV** returns the value:

```
GPTMTBV[15:0]:GPTMTAV[15:0]
```

# 10.4 Initialization and Configuration

To use a GPTM, the appropriate TIMERn bit must be set in the **RCGC1** register (see page 272). If using any CCP pins, the clock to the appropriate GPIO module must be enabled via the **RCGC1** register (see page 272). To find out which GPIO port to enable, refer to Table 24-4 on page 1261. Configure the PMCn fields in the **GPIOPCTL** register to assign the CCP signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).

This section shows module initialization and configuration examples for each of the supported timer modes.

### 10.4.1 One-Shot/Periodic Timer Mode

The GPTM is configured for One-Shot and Periodic modes by the following sequence:

- 1. Ensure the timer is disabled (the TnEN bit in the **GPTMCTL** register is cleared) before making any changes.
- 2. Write the GPTM Configuration Register (GPTMCFG) with a value of 0x0000.0000.

- 3. Configure the TnMR field in the GPTM Timer n Mode Register (GPTMTnMR):
  - a. Write a value of 0x1 for One-Shot mode.
  - **b.** Write a value of 0x2 for Periodic mode.
- **4.** Optionally configure the TnSNAPS, TnWOT, TnMTE, and TnCDIR bits in the **GPTMTnMR** register to select whether to capture the value of the free-running timer at time-out, use an external trigger to start counting, configure an additional trigger or interrupt, and count up or down.
- 5. Load the start value into the GPTM Timer n Interval Load Register (GPTMTnILR).
- 6. If interrupts are required, set the appropriate bits in the **GPTM Interrupt Mask Register** (**GPTMIMR**).
- 7. Set the TnEN bit in the **GPTMCTL** register to enable the timer and start counting.
- 8. Poll the **GPTMRIS** register or wait for the interrupt to be generated (if enabled). In both cases, the status flags are cleared by writing a 1 to the appropriate bit of the **GPTM Interrupt Clear Register (GPTMICR)**.

If the TnMIE bit in the **GPTMTnMR** register is set, the RTCRIS bit in the **GPTMRIS** register is set, and the timer continues counting. In One-Shot mode, the timer stops counting after the time-out event. To re-enable the timer, repeat the sequence. A timer configured in Periodic mode reloads the timer and continues counting after the time-out event.

### 10.4.2 Real-Time Clock (RTC) Mode

To use the RTC mode, the timer must have a 32.768-KHz input signal on an even CCP input. To enable the RTC feature, follow these steps:

- 1. Ensure the timer is disabled (the TAEN bit is cleared) before making any changes.
- 2. Write the GPTM Configuration Register (GPTMCFG) with a value of 0x0000.0001.
- 3. Write the match value to the GPTM Timer n Match Register (GPTMTnMATCHR).
- 4. Set/clear the RTCEN bit in the GPTM Control Register (GPTMCTL) as needed.
- If interrupts are required, set the RTCIM bit in the GPTM Interrupt Mask Register (GPTMIMR).
- 6. Set the TAEN bit in the **GPTMCTL** register to enable the timer and start counting.

When the timer count equals the value in the **GPTMTnMATCHR** register, the GPTM asserts the RTCRIS bit in the **GPTMRIS** register and continues counting until Timer A is disabled or a hardware reset. The interrupt is cleared by writing the RTCCINT bit in the **GPTMICR** register.

### 10.4.3 Input Edge-Count Mode

A timer is configured to Input Edge-Count mode by the following sequence:

- 1. Ensure the timer is disabled (the TnEN bit is cleared) before making any changes.
- 2. Write the **GPTM Configuration (GPTMCFG)** register with a value of 0x0000.0004.

- 3. In the GPTM Timer Mode (GPTMTnMR) register, write the TnCMR field to 0x0 and the TnMR field to 0x3.
- **4.** Configure the type of event(s) that the timer captures by writing the Tnevent field of the **GPTM** Control (GPTMCTL) register.
- 5. If a prescaler is to be used, write the prescale value to the GPTM Timer n Prescale Register (GPTMTnPR).
- 6. Load the timer start value into the GPTM Timer n Interval Load (GPTMTnILR) register.
- 7. Load the event count into the GPTM Timer n Match (GPTMTnMATCHR) register.
- 8. If interrupts are required, set the CnMIM bit in the GPTM Interrupt Mask (GPTMIMR) register.
- 9. Set the Then bit in the GPTMCTL register to enable the timer and begin waiting for edge events.
- 10. Poll the CnMRIS bit in the GPTMRIS register or wait for the interrupt to be generated (if enabled). In both cases, the status flags are cleared by writing a 1 to the CnMCINT bit of the GPTM Interrupt Clear (GPTMICR) register.

When counting down in Input Edge-Count Mode, the timer stops after the programmed number of edge events has been detected. To re-enable the timer, ensure that the TnEN bit is cleared and repeat #4 on page 551 through #9 on page 551.

### 10.4.4 Input Edge Timing Mode

A timer is configured to Input Edge Timing mode by the following sequence:

- 1. Ensure the timer is disabled (the TnEN bit is cleared) before making any changes.
- 2. Write the **GPTM Configuration (GPTMCFG)** register with a value of 0x0000.0004.
- 3. In the GPTM Timer Mode (GPTMTnMR) register, write the TnCMR field to 0x1 and the TnMR field to 0x3.
- 4. Configure the type of event that the timer captures by writing the Tnevent field of the GPTM Control (GPTMCTL) register.
- 5. Load the timer start value into the GPTM Timer n Interval Load (GPTMTnILR) register.
- 6. If interrupts are required, set the CnEIM bit in the GPTM Interrupt Mask (GPTMIMR) register.
- 7. Set the Then bit in the **GPTM Control (GPTMCTL)** register to enable the timer and start counting.
- 8. Poll the Cners bit in the GPTMRIS register or wait for the interrupt to be generated (if enabled). In both cases, the status flags are cleared by writing a 1 to the Cnecint bit of the GPTM Interrupt Clear (GPTMICR) register. The time at which the event happened can be obtained by reading the GPTM Timer n (GPTMTnR) register.

In Input Edge Timing mode, the timer continues running after an edge event has been detected, but the timer interval can be changed at any time by writing the **GPTMTnILR** register. The change takes effect at the next cycle after the write.

### 10.4.5 **PWM Mode**

A timer is configured to PWM mode using the following sequence:

- 1. Ensure the timer is disabled (the TnEN bit is cleared) before making any changes.
- 2. Write the **GPTM Configuration (GPTMCFG)** register with a value of 0x0000.0004.
- 3. In the **GPTM Timer Mode (GPTMTnMR)** register, set the TnAMS bit to 0x1, the TnCMR bit to 0x0, and the TnMR field to 0x2.
- **4.** Configure the output state of the PWM signal (whether or not it is inverted) in the TnPWML field of the **GPTM Control (GPTMCTL)** register.
- 5. Load the timer start value into the GPTM Timer n Interval Load (GPTMTnILR) register.
- 6. Load the GPTM Timer n Match (GPTMTnMATCHR) register with the match value.
- 7. Set the TnEN bit in the **GPTM Control (GPTMCTL)** register to enable the timer and begin generation of the output PWM signal.

In PWM Timing mode, the timer continues running after the PWM signal has been generated. The PWM period can be adjusted at any time by writing the **GPTMTnILR** register, and the change takes effect at the next cycle after the write.

# 10.5 Register Map

Table 10-11 on page 552 lists the GPTM registers. The offset listed is a hexadecimal increment to the register's address, relative to that timer's base address:

Timer 0: 0x4003.0000
Timer 1: 0x4003.1000
Timer 2: 0x4003.2000
Timer 3: 0x4003.3000

Note that the GP Timer module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the Timer module clock is enabled before any Timer module registers are accessed.

Table 10-11. Timers Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	GPTMCFG	R/W	0x0000.0000	GPTM Configuration	554
0x004	GPTMTAMR	R/W	0x0000.0000	GPTM Timer A Mode	555
0x008	GPTMTBMR	R/W	0x0000.0000	GPTM Timer B Mode	557
0x00C	GPTMCTL	R/W	0x0000.0000	GPTM Control	559
0x018	GPTMIMR	R/W	0x0000.0000	GPTM Interrupt Mask	562
0x01C	GPTMRIS	RO	0x0000.0000	GPTM Raw Interrupt Status	564
0x020	GPTMMIS	RO	0x0000.0000	GPTM Masked Interrupt Status	567
0x024	GPTMICR	W1C	0x0000.0000	GPTM Interrupt Clear	570

Table 10-11. Timers Register Map (continued)

Offset	Name	Type	Reset	Description	See page
0x028	GPTMTAILR	R/W	0xFFFF.FFFF	GPTM Timer A Interval Load	572
0x02C	GPTMTBILR	R/W	0x0000.FFFF	GPTM Timer B Interval Load	573
0x030	GPTMTAMATCHR	R/W	0xFFFF.FFFF	GPTM Timer A Match	574
0x034	GPTMTBMATCHR	R/W	0x0000.FFFF	GPTM Timer B Match	575
0x038	GPTMTAPR	R/W	0x0000.0000	GPTM Timer A Prescale	576
0x03C	GPTMTBPR	R/W	0x0000.0000	GPTM Timer B Prescale	577
0x040	GPTMTAPMR	R/W	0x0000.0000	GPTM TimerA Prescale Match	578
0x044	GPTMTBPMR	R/W	0x0000.0000	GPTM TimerB Prescale Match	579
0x048	GPTMTAR	RO	0xFFFF.FFFF	GPTM Timer A	580
0x04C	GPTMTBR	RO	0x0000.FFFF	GPTM Timer B	581
0x050	GPTMTAV	RW	0xFFFF.FFFF	GPTM Timer A Value	582
0x054	GPTMTBV	RW	0x0000.FFFF	GPTM Timer B Value	583

# 10.6 Register Descriptions

The remainder of this section lists and describes the GPTM registers, in numerical order by address offset.

# Register 1: GPTM Configuration (GPTMCFG), offset 0x000

This register configures the global operation of the GPTM module. The value written to this register determines whether the GPTM is in 32- or 16-bit mode.


**Important:** Bits in this register should only be changed when the TAEN and TBEN bits in the **GPTMCTL** register are cleared.

#### GPTM Configuration (GPTMCFG)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2:0	GPTMCFG	R/W	0x0	GPTM Configuration

The GPTMCFG values are defined as follows:

Value Description
0x0 32-bit timer configuration.

0x1 32-bit real-time clock (RTC) counter configuration.

0x2-0x3 Reserved

0x4 16-bit timer configuration.

The function is controlled by bits 1:0 of **GPTMTAMR** and

GPTMTBMR.

0x5-0x7 Reserved

### Register 2: GPTM Timer A Mode (GPTMTAMR), offset 0x004

This register configures the GPTM based on the configuration selected in the **GPTMCFG** register. When in PWM mode, set the TAAMS bit, clear the TACMR bit, and configure the TAMR field to 0x1 or 0x2.

This register controls the modes for Timer A when it is used individually. When Timer A and Timer B are concatenated, this register controls the modes for both Timer A and Timer B, and the contents of **GPTMTBMR** are ignored.

**Important:** Bits in this register should only be changed when the TAEN bit in the **GPTMCTL** register is cleared.

#### GPTM Timer A Mode (GPTMTAMR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x004


Divici - La

6

**TAWOT** 

R/W

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	TASNAPS	R/W	0	GPTM Timer A Snap-Shot Mode
				Value Description
				0 Snap-shot mode is disabled.
				If Timer A is configured in the periodic mode, the actual free-running value of Timer A is loaded at the time-out event into the <b>GPTM Timer A</b> ( <b>GPTMTAR</b> ) register. If the timer prescaler is used, the prescaler snapshot is loaded into the <b>GPTM Timer A</b> ( <b>GPTMTAPR</b> ).

Value Description

**GPTM Timer A Wait-on-Trigger** 

- 0 Timer A begins counting as soon as it is enabled.
- If Timer A is enabled (TAEN is set in the GPTMCTL register), Timer A does not begin counting until it receives a trigger from the timer in the previous position in the daisy chain, see Figure 10-2 on page 544. This function is valid for both one-shot and periodic modes.

This bit must be clear for GP Timer Module 0, Timer A.

Bit/Field	Name	Туре	Reset	Description
5	TAMIE	R/W	0	GPTM Timer A Match Interrupt Enable
				Value Description
				0 The match interrupt is disabled.
				An interrupt is generated when the match value in the <b>GPTMTAMATCHR</b> register is reached in the one-shot and periodic modes.
4	TACDIR	R/W	0	GPTM Timer A Count Direction
				Value Description
				0 The timer counts down.
				When in one-shot or periodic mode, the timer counts up. When counting up, the timer starts from a value of 0x0.
				When in PWM or RTC mode, the status of this bit is ignored. PWM mode always counts down and RTC mode always counts up.
3	TAAMS	R/W	0	GPTM Timer A Alternate Mode Select
				The TAAMS values are defined as follows:
				Value Description
				0 Capture mode is enabled.
				1 PWM mode is enabled.
				<b>Note:</b> To enable PWM mode, you must also clear the TACMR bit and configure the TAMR field to 0x1 or 0x2.
2	TACMR	R/W	0	GPTM Timer A Capture Mode
				The TACMR values are defined as follows:
				Value Description
				0 Edge-Count mode
				1 Edge-Time mode
1:0	TAMR	R/W	0x0	GPTM Timer A Mode
				The TAMR values are defined as follows:
				Value Description
				0x0 Reserved
				0x1 One-Shot Timer mode
				0x2 Periodic Timer mode
				0x3 Capture mode
				The Timer mode is based on the timer configuration defined by bits 2:0 in the <b>GPTMCFG</b> register.

# Register 3: GPTM Timer B Mode (GPTMTBMR), offset 0x008

This register configures the GPTM based on the configuration selected in the **GPTMCFG** register. When in PWM mode, set the TBAMS bit, clear the TBCMR bit, and configure the TBMR field to 0x1 or 0x2.

This register controls the modes for Timer B when it is used individually. When Timer A and Timer B are concatenated, this register is ignored and **GPTMTBMR** controls the modes for both Timer A and Timer B.

**Important:** Bits in this register should only be changed when the TBEN bit in the **GPTMCTL** register is cleared.

#### GPTM Timer B Mode (GPTMTBMR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000


Offset 0x008

6

**TBWOT** 

R/W

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	TBSNAPS	R/W	0	GPTM Timer B Snap-Shot Mode
				Value Description
				0 Snap-shot mode is disabled.
				If Timer B is configured in the periodic mode, the actual free-running value of Timer B is loaded at the time-out event into the <b>GPTM Timer B (GPTMTBR)</b> register. If the timer prescaler is used, the prescaler snapshot is loaded into the <b>GPTM Timer B (GPTMTBPR)</b> .

#### Value Description

**GPTM Timer B Wait-on-Trigger** 

- 0 Timer B begins counting as soon as it is enabled.
- 1 If Timer B is enabled (TBEN is set in the **GPTMCTL** register), Timer B does not begin counting until it receives an it receives a trigger from the timer in the previous position in the daisy chain, see Figure 10-2 on page 544. This function is valid for both one-shot and periodic modes.

Bit/Field	Name	Туре	Reset	Description
5	TBMIE	R/W	0	GPTM Timer B Match Interrupt Enable
				Value Description
				0 The match interrupt is disabled.
				An interrupt is generated when the match value in the GPTMTBMATCHR register is reached in the one-shot and periodic modes.
4	TBCDIR	R/W	0	GPTM Timer B Count Direction
				Value Description
				0 The timer counts down.
				When in one-shot or periodic mode, the timer counts up. When counting up, the timer starts from a value of 0x0.
				When in PWM or RTC mode, the status of this bit is ignored. PWM mode always counts down and RTC mode always counts up.
3	TBAMS	R/W	0	GPTM Timer B Alternate Mode Select
				The TBAMS values are defined as follows:
				Value Description
				0 Capture mode is enabled.
				PWM mode is enabled.
				Note: To enable PWM mode, you must also clear the TBCMR bit and configure the TBMR field to 0x1 or 0x2.
2	TBCMR	R/W	0	GPTM Timer B Capture Mode
				The TBCMR values are defined as follows:
				Value Description
				0 Edge-Count mode
				1 Edge-Time mode
				, and the second
1:0	TBMR	R/W	0x0	GPTM Timer B Mode
				The TBMR values are defined as follows:
				Value Description
				0x0 Reserved
				0x1 One-Shot Timer mode
				0x2 Periodic Timer mode
				0x3 Capture mode
				The timer mode is based on the timer configuration defined by bits 2:0 in the <b>GPTMCFG</b> register.

### Register 4: GPTM Control (GPTMCTL), offset 0x00C

This register is used alongside the **GPTMCFG** and **GMTMTnMR** registers to fine-tune the timer configuration, and to enable other features such as timer stall and the output trigger. The output trigger can be used to initiate transfers on the ADC module.


**Important:** Bits in this register should only be changed when the TnEN bit for the respective timer is cleared.

### GPTM Control (GPTMCTL)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x00C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:15	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14	TBPWML	R/W	0	GPTM Timer B PWM Output Level
				The TBPWML values are defined as follows:
				Value Description
				0 Output is unaffected.
				1 Output is inverted.
13	ТВОТЕ	R/W	0	GPTM Timer B Output Trigger Enable The TBOTE values are defined as follows:
				Value Description
				0 The output Timer B ADC trigger is disabled.
				1 The output Timer B ADC trigger is enabled.
				In addition, the ADC must be enabled and the timer selected as a trigger source with the $\mathtt{EMn}$ bit in the <b>ADCEMUX</b> register (see page 642).
12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
11:10	TBEVENT	R/W	0x0	GPTM Timer B Event Mode The TBEVENT values are defined as follows:
				Value Description  0x0 Positive edge  0x1 Negative edge  0x2 Reserved  0x3 Both edges
9	TBSTALL	R/W	0	GPTM Timer B Stall Enable The TBSTALL values are defined as follows:
				<ul> <li>Value Description</li> <li>Timer B continues counting while the processor is halted by the debugger.</li> <li>Timer B freezes counting while the processor is halted by the debugger.</li> <li>If the processor is executing normally, the TBSTALL bit is ignored.</li> </ul>
8	TBEN	R/W	0	GPTM Timer B Enable The TBEN values are defined as follows:  Value Description 0 Timer B is disabled.
				Timer B is enabled and begins counting or the capture logic is enabled based on the GPTMCFG register.
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	TAPWML	R/W	0	GPTM Timer A PWM Output Level The TAPWML values are defined as follows:  Value Description 0 Output is unaffected.
F	TAOTE	DAM	0	1 Output is inverted.
5	TAOTE	R/W	0	GPTM Timer A Output Trigger Enable The TAOTE values are defined as follows:  Value Description 0 The output Timer A ADC trigger is disabled. 1 The output Timer A ADC trigger is enabled.  In addition, the ADC must be enabled and the timer selected as a trigger source with the EMn bit in the ADCEMUX register (see page 642).

Bit/Field	Name	Туре	Reset	Description
4	RTCEN	R/W	0	GPTM RTC Stall Enable The RTCEN values are defined as follows:
				Value Description
				0 RTC counting freezes while the processor is halted by the debugger.
				1 RTC counting continues while the processor is halted by the debugger.
				If the RTCEN bit is set, it prevents the timer from stalling in all operating modes, even if ${\tt TnSTALL}$ is set.
3:2	TAEVENT	R/W	0x0	GPTM Timer A Event Mode
				The TAEVENT values are defined as follows:
				Value Description
				0x0 Positive edge
				0x1 Negative edge
				0x2 Reserved
				0x3 Both edges
1	TASTALL	R/W	0	GPTM Timer A Stall Enable
				The TASTALL values are defined as follows:
				Value Description
				Timer A continues counting while the processor is halted by the debugger.
				1 Timer A freezes counting while the processor is halted by the debugger.
				If the processor is executing normally, the ${\tt TASTALL}$ bit is ignored.
0	TAEN	R/W	0	GPTM Timer A Enable
				The TAEN values are defined as follows:
				Value Description
				0 Timer A is disabled.
				1 Timer A is enabled and begins counting or the capture logic is enabled based on the GPTMCFG register.

# Register 5: GPTM Interrupt Mask (GPTMIMR), offset 0x018


This register allows software to enable/disable GPTM controller-level interrupts. Setting a bit enables the corresponding interrupt, while clearing a bit disables it.

### GPTM Interrupt Mask (GPTMIMR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x018

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	TBMIM	R/W	0	GPTM Timer B Match Interrupt Mask
				The TBMIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
10	CBEIM	R/W	0	GPTM Timer B Capture Mode Event Interrupt Mask
				The CBEIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
9	СВМІМ	R/W	0	GPTM Timer B Capture Mode Match Interrupt Mask
				The CBMIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.

Bit/Field	Name	Туре	Reset	Description
8	ТВТОІМ	R/W	0	GPTM Timer B Time-Out Interrupt Mask
				The TBTOIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
7:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	TAMIM	R/W	0	GPTM Timer A Match Interrupt Mask
				The TAMIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
3	RTCIM	R/W	0	GPTM RTC Interrupt Mask
				The RTCIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
2	CAEIM	R/W	0	GPTM Timer A Capture Mode Event Interrupt Mask
				The CAEIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
1	CAMIM	R/W	0	GPTM Timer A Capture Mode Match Interrupt Mask
				The CAMIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.
0	TATOIM	R/W	0	GPTM Timer A Time-Out Interrupt Mask
				The TATOIM values are defined as follows:
				Value Description
				0 Interrupt is disabled.
				1 Interrupt is enabled.

# Register 6: GPTM Raw Interrupt Status (GPTMRIS), offset 0x01C


This register shows the state of the GPTM's internal interrupt signal. These bits are set whether or not the interrupt is masked in the GPTMIMR register. Each bit can be cleared by writing a 1 to its corresponding bit in GPTMICR.

### GPTM Raw Interrupt Status (GPTMRIS)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x01C

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	TBMRIS	RO	0	GPTM Timer B Match Raw Interrupt

#### Value Description

- The TBMIE bit is set in the **GPTMTBMR** register, and the match values in the GPTMTBMATCHR and (optionally) GPTMTBPMR registers have been reached when configured in one-shot or periodic mode.
- The match value has not been reached.

This bit is cleared by writing a 1 to the TBMCINT bit in the GPTMICR register.

**CBERIS** RO GPTM Timer B Capture Mode Event Raw Interrupt 10 0

#### Value Description

- A capture mode event has occurred for Timer B. This interrupt asserts when the subtimer is configured in Input Edge-Time mode.
- The capture mode event for Timer B has not occurred. 0

This bit is cleared by writing a 1 to the  ${\tt CBECINT}$  bit in the  ${\tt GPTMICR}$ register.

Bit/Field	Name	Туре	Reset	Description
9	CBMRIS	RO	0	GPTM Timer B Capture Mode Match Raw Interrupt
				Value Description
				The capture mode match has occurred for Timer B. This interrupt asserts when the values in the <b>GPTMTBR</b> and <b>GPTMTBPR</b> match the values in the <b>GPTMTBMATCHR</b> and <b>GPTMTBPMR</b> when configured in Input Edge-Time mode.
				0 The capture mode match for Timer B has not occurred.
				This bit is cleared by writing a 1 to the CBMCINT bit in the <b>GPTMICR</b> register.
8	TBTORIS	RO	0	GPTM Timer B Time-Out Raw Interrupt
				Value Description
				Timer B has timed out. This interrupt is asserted when a one-shot or periodic mode timer reaches it's count limit (0 or the value loaded into GPTMTBILR, depending on the count direction).
				0 Timer B has not timed out.
				This bit is cleared by writing a 1 to the TBTOCINT bit in the <b>GPTMICR</b> register.
7:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	TAMRIS	RO	0	GPTM Timer A Match Raw Interrupt
				Value Description
				The TAMIE bit is set in the <b>GPTMTAMR</b> register, and the match value in the <b>GPTMTAMATCHR</b> and (optionally) <b>GPTMTAPMR</b> registers have been reached when configured in one-shot or periodic mode.
				0 The match value has not been reached.
				This bit is cleared by writing a 1 to the TAMCINT bit in the <b>GPTMICR</b> register.
3	RTCRIS	RO	0	GPTM RTC Raw Interrupt
				Value Description
				1 The RTC event has occurred.
				0 The RTC event has not occurred.
				This bit is cleared by writing a 1 to the RTCCINT bit in the <b>GPTMICR</b> register.

Bit/Field	Name	Туре	Reset	Description
2	CAERIS	RO	0	GPTM Timer A Capture Mode Event Raw Interrupt
				Value Description  1 A capture mode event has occurred for Timer A. This interrupt asserts when the subtimer is configured in Input Edge-Time mode.
				O The capture mode event for Timer A has not occurred.
				This bit is cleared by writing a 1 to the CAECINT bit in the <b>GPTMICR</b> register.
1	CAMRIS	RO	0	GPTM Timer A Capture Mode Match Raw Interrupt
				Value Description
				A capture mode match has occurred for Timer A. This interrupt asserts when the values in the <b>GPTMTAR</b> and <b>GPTMTAPR</b> match the values in the <b>GPTMTAMATCHR</b> and <b>GPTMTAPMR</b> when configured in Input Edge-Time mode.
				0 The capture mode match for Timer A has not occurred.
				This bit is cleared by writing a 1 to the CAMCINT bit in the <b>GPTMICR</b> register.
0	TATORIS	RO	0	GPTM Timer A Time-Out Raw Interrupt
				Value Description
				Timer A has timed out. This interrupt is asserted when a one-shot or periodic mode timer reaches it's count limit (0 or the value loaded into GPTMTAILR, depending on the count direction).
				0 Timer A has not timed out.
				This bit is cleared by writing a 1 to the ${\tt TATOCINT}$ bit in the ${\tt GPTMICR}$ register.

# Register 7: GPTM Masked Interrupt Status (GPTMMIS), offset 0x020


This register show the state of the GPTM's controller-level interrupt. If an interrupt is unmasked in **GPTMIMR**, and there is an event that causes the interrupt to be asserted, the corresponding bit is set in this register. All bits are cleared by writing a 1 to the corresponding bit in **GPTMICR**.

### **GPTM Masked Interrupt Status (GPTMMIS)**

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x020

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	TBMMIS	RO	0	GPTM Timer B Match Masked Interrupt
				Value Description
				<ol> <li>An unmasked Timer B Mode Match interrupt has occurred.</li> </ol>
				0 A Timer B Mode Match interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the ${\tt TBMCINT}$ bit in the $\mbox{\bf GPTMICR}$ register.
10	CBEMIS	RO	0	GPTM Timer B Capture Mode Event Masked Interrupt

Value Description

- 1 An unmasked Capture B event interrupt has occurred.
- 0 A Capture B event interrupt has not occurred or is masked.

This bit is cleared by writing a 1 to the  ${\tt CBECINT}$  bit in the  $\mbox{\bf GPTMICR}$  register.

Bit/Field	Name	Туре	Reset	Description
9	CBMMIS	RO	0	GPTM Timer B Capture Mode Match Masked Interrupt
				Value Description
				<ol> <li>An unmasked Capture B Match interrupt has occurred.</li> </ol>
				O A Capture B Mode Match interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the CBMCINT bit in the <b>GPTMICR</b> register.
8	TBTOMIS	RO	0	GPTM Timer B Time-Out Masked Interrupt
				Value Description
				<ol> <li>An unmasked Timer B Time-Out interrupt has occurred.</li> </ol>
				0 A Timer B Time-Out interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the ${\tt TBTOCINT}$ bit in the ${\tt GPTMICR}$ register.
7:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	TAMMIS	RO	0	GPTM Timer A Match Masked Interrupt
				Value Description
				<ol> <li>An unmasked Timer A Mode Match interrupt has occurred.</li> </ol>
				0 A Timer A Mode Match interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the TAMCINT bit in the <b>GPTMICR</b> register.
3	RTCMIS	RO	0	GPTM RTC Masked Interrupt
				Value Description
				<ol> <li>An unmasked RTC event interrupt has occurred.</li> </ol>
				O An RTC event interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the RTCCINT bit in the <b>GPTMICR</b> register.
2	CAEMIS	RO	0	GPTM Timer A Capture Mode Event Masked Interrupt
				Value Description
				<ol> <li>An unmasked Capture A event interrupt has occurred.</li> </ol>
				0 A Capture A event interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the CAECINT bit in the <b>GPTMICR</b> register.

Bit/Field	Name	Туре	Reset	Description
1	CAMMIS	RO	0	GPTM Timer A Capture Mode Match Masked Interrupt
				Value Description
				<ol> <li>An unmasked Capture A Match interrupt has occurred.</li> </ol>
				0 A Capture A Mode Match interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the CAMCINT bit in the <b>GPTMICR</b> register.
0	TATOMIS	RO	0	GPTM Timer A Time-Out Masked Interrupt
				Value Description
				<ol> <li>An unmasked Timer A Time-Out interrupt has occurred.</li> </ol>
				0 A Timer A Time-Out interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the TATOCINT bit in the <b>GPTMICR</b> register.

# Register 8: GPTM Interrupt Clear (GPTMICR), offset 0x024


This register is used to clear the status bits in the **GPTMRIS** and **GPTMMIS** registers. Writing a 1 to a bit clears the corresponding bit in the **GPTMRIS** and **GPTMMIS** registers.

### GPTM Interrupt Clear (GPTMICR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x024

Type W1C, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	TBMCINT	W1C	0	GPTM Timer B Match Interrupt Clear Writing a 1 to this bit clears the TBMRIS bit in the <b>GPTMRIS</b> register
				and the TBMMIS bit in the <b>GPTMMIS</b> register.
10	CBECINT	W1C	0	GPTM Timer B Capture Mode Event Interrupt Clear
				Writing a 1 to this bit clears the CBERIS bit in the <b>GPTMRIS</b> register and the CBEMIS bit in the <b>GPTMMIS</b> register.
9	CBMCINT	W1C	0	GPTM Timer B Capture Mode Match Interrupt Clear
				Writing a 1 to this bit clears the CBMRIS bit in the <b>GPTMRIS</b> register and the CBMMIS bit in the <b>GPTMMIS</b> register.
8	TBTOCINT	W1C	0	GPTM Timer B Time-Out Interrupt Clear
				Writing a 1 to this bit clears the TBTORIS bit in the GPTMRIS register and the TBTOMIS bit in the GPTMMIS register.
7:5	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	TAMCINT	W1C	0	GPTM Timer A Match Interrupt Clear
				Writing a 1 to this bit clears the TAMRIS bit in the <b>GPTMRIS</b> register and the TAMMIS bit in the <b>GPTMMIS</b> register.
3	RTCCINT	W1C	0	GPTM RTC Interrupt Clear
				Writing a 1 to this bit clears the RTCRIS bit in the <b>GPTMRIS</b> register and the RTCMIS bit in the <b>GPTMMIS</b> register.
2	CAECINT	W1C	0	GPTM Timer A Capture Mode Event Interrupt Clear
				Writing a 1 to this bit clears the CAERIS bit in the <b>GPTMRIS</b> register and the CAEMIS bit in the <b>GPTMMIS</b> register.

Bit/Field	Name	Туре	Reset	Description
1	CAMCINT	W1C	0	GPTM Timer A Capture Mode Match Interrupt Clear Writing a 1 to this bit clears the CAMRIS bit in the GPTMRIS register and the CAMMIS bit in the GPTMMIS register.
0	TATOCINT	W1C	0	GPTM Timer A Time-Out Raw Interrupt Writing a 1 to this bit clears the TATORIS bit in the GPTMRIS register and the TATOMIS bit in the GPTMMIS register.

# Register 9: GPTM Timer A Interval Load (GPTMTAILR), offset 0x028


When the timer is counting down, this register is used to load the starting count value into the timer. When the timer is counting up, this register sets the upper bound for the timeout event.

When a GPTM is configured to one of the 32-bit modes, **GPTMTAILR** appears as a 32-bit register (the upper 16-bits correspond to the contents of the **GPTM Timer B Interval Load (GPTMTBILR)** register). In a 16-bit mode, the upper 16 bits of this register read as 0s and have no effect on the state of **GPTMTBILR**.

#### GPTM Timer A Interval Load (GPTMTAILR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000 Offset 0x028

Type R/W, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 TAILR R/W 0xFFF.FFFF GPTM Timer A Interval Load Register

Writing this field loads the counter for Timer A. A read returns the current value of **GPTMTAILR**.

# Register 10: GPTM Timer B Interval Load (GPTMTBILR), offset 0x02C


When the timer is counting down, this register is used to load the starting count value into the timer. When the timer is counting up, this register sets the upper bound for the timeout event.

When a GPTM is configured to one of the 32-bit modes, the contents of bits 15:0 in this register are loaded into the upper 16 bits of the **GPTMTAILR** register. Reads from this register return the current value of Timer B and writes are ignored. In a 16-bit mode, bits 15:0 are used for the load value. Bits 31:16 are reserved in both cases.

#### GPTM Timer B Interval Load (GPTMTBILR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000 Offset 0x02C

Type R/W, reset 0x0000.FFFF



Bit/Field Name Type Reset Description

31:0 TBILR R/W 0x0000.FFFF GPTM Timer B Interval Load Register

Writing this field loads the counter for Timer B. A read returns the current value of **GPTMTBILR**.

When a GPTM is in 32-bit mode, writes are ignored, and reads return the current value of **GPTMTBILR**.

### Register 11: GPTM Timer A Match (GPTMTAMATCHR), offset 0x030

This register is loaded with a match value. Interrupts can be generated when the timer value is equal to the value in this register in one-shot or periodic mode.

In Edge-Count mode, this register along with **GPTMTAILR**, determines how many edge events are counted. The total number of edge events counted is equal to the value in **GPTMTAILR** minus this value.

In PWM mode, this value along with **GPTMTAILR**, determines the duty cycle of the output PWM signal.


When a GPTM is configured to one of the 32-bit modes, **GPTMTAMATCHR** appears as a 32-bit register (the upper 16-bits correspond to the contents of the **GPTM Timer B Match** (**GPTMTBMATCHR**) register). In a 16-bit mode, the upper 16 bits of this register read as 0s and have no effect on the state of **GPTMTBMATCHR**.

### GPTM Timer A Match (GPTMTAMATCHR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x030

Type R/W, reset 0xFFFF.FFF



This value is compared to the  $\ensuremath{\mathbf{GPTMTAR}}$  register to determine match events.

### Register 12: GPTM Timer B Match (GPTMTBMATCHR), offset 0x034

This register is loaded with a match value. Interrupts can be generated when the timer value is equal to the value in this register in one-shot or periodic mode.

In Edge-Count mode, this register along with **GPTMTBILR**, determines how many edge events are counted. The total number of edge events counted is equal to the value in **GPTMTBILR** minus this value.

In PWM mode, this value along with **GPTMTBILR**, determines the duty cycle of the output PWM signal.


When a GPTM is configured to one of the 32-bit modes, the contents of bits 15:0 in this register are loaded into the upper 16 bits of the **GPTMTAMATCHR** register. Reads from this register return the current match value of Timer B and writes are ignored. In a 16-bit mode, bits 15:0 are used for the match value. Bits 31:16 are reserved in both cases.

### GPTM Timer B Match (GPTMTBMATCHR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x034

Type R/W, reset 0x0000.FFFF



This value is compared to the  $\ensuremath{\mathbf{GPTMTBR}}$  register to determine match events.

# Register 13: GPTM Timer A Prescale (GPTMTAPR), offset 0x038


This register allows software to extend the range of the 16-bit timers in periodic and one-shot modes. In Edge-Count mode, this register is the MSB of the 24-bit count value.

### GPTM Timer A Prescale (GPTMTAPR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x038

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	TAPSR	R/W	0x00	GPTM Timer A Prescale

The register loads this value on a write. A read returns the current value of the register.

Refer to Table 10-6 on page 543 for more details and an example.

## Register 14: GPTM Timer B Prescale (GPTMTBPR), offset 0x03C


This register allows software to extend the range of the 16-bit timers in periodic and one-shot modes. In Edge-Count mode, this register is the MSB of the 24-bit count value.

#### GPTM Timer B Prescale (GPTMTBPR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x03C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	TBPSR	R/W	0x00	GPTM Timer B Prescale

The register loads this value on a write. A read returns the current value of this register.

Refer to Table 10-6 on page 543 for more details and an example.

## Register 15: GPTM TimerA Prescale Match (GPTMTAPMR), offset 0x040


This register effectively extends the range of **GPTMTAMATCHR** to 24 bits when operating in 16-bit one-shot or periodic mode.

#### GPTM TimerA Prescale Match (GPTMTAPMR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x040

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	TAPSMR	R/W	0x00	GPTM TimerA Prescale Match

This value is used alongside **GPTMTAMATCHR** to detect timer match events while using a prescaler.

## Register 16: GPTM TimerB Prescale Match (GPTMTBPMR), offset 0x044


This register effectively extends the range of GPTMTBMATCHR to 24 bits when operating in 16-bit one-shot or periodic mode.

#### GPTM TimerB Prescale Match (GPTMTBPMR)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x044

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	TBPSMR	R/W	0x00	GPTM TimerB Prescale Match

This value is used alongside **GPTMTBMATCHR** to detect timer match events while using a prescaler.

### Register 17: GPTM Timer A (GPTMTAR), offset 0x048

This register shows the current value of the Timer A counter in all cases except for Input Edge Count and Time modes. In the Input Edge Count mode, this register contains the number of edges that have occurred. In the Input Edge Time mode, this register contains the time at which the last edge event took place. Also in Input Edge-Count mode, bits 23:16 contain the upper 8 bits of the count.


When a GPTM is configured to one of the 32-bit modes, **GPTMTAR** appears as a 32-bit register (the upper 16-bits correspond to the contents of the **GPTM Timer B (GPTMTBR)** register). In the16-bit Input Edge Count, Input Edge Time, and PWM modes, bits 15:0 contain the value of the counter and bits 23:16 contain the value of the prescaler, which is the upper 8 bits of the count. Bits 31:24 always read as 0. To read the value of the prescaler in 16-bit One-Shot and Periodic modes, read bits [23:16] in the **GPTMTAV** register.

#### **GPTM Timer A (GPTMTAR)**

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x048

Type RO, reset 0xFFFF.FFF



A read returns the current value of the **GPTM Timer A Count Register**, in all cases except for Input Edge Count and Time modes. In the Input Edge Count mode, this register contains the number of edges that have occurred. In the Input Edge Time mode, this register contains the time at which the last edge event took place.

### Register 18: GPTM Timer B (GPTMTBR), offset 0x04C

This register shows the current value of the Timer B counter in all cases except for Input Edge Count and Time modes. In the Input Edge Count mode, this register contains the number of edges that have occurred. In the Input Edge Time mode, this register contains the time at which the last edge event took place. Also in Input Edge-Count mode, bits 23:16 contain the upper 8 bits of the count.


When a GPTM is configured to one of the 32-bit modes, the contents of bits 15:0 in this register are loaded into the upper 16 bits of the **GPTMTAR** register. Reads from this register return the current value of Timer B. In a 16-bit mode, bits 15:0 contain the value of the counter and bits 23:16 contain the value of the prescaler in Input Edge Count, Input Edge Time, and PWM modes, which is the upper 8 bits of the count. Bits 31:24 always read as 0. To read the value of the prescaler in 16-bit One-Shot and Periodic modes, read bits [23:16] in the **GPTMTBV** register.

#### **GPTM Timer B (GPTMTBR)**

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x04C

Type RO, reset 0x0000.FFFF



A read returns the current value of the **GPTM Timer B Count Register**, in all cases except for Input Edge Count and Time modes. In the Input Edge Count mode, this register contains the number of edges that have occurred. In the Input Edge Time mode, this register contains the time at which the last edge event took place.

### Register 19: GPTM Timer A Value (GPTMTAV), offset 0x050

When read, this register shows the current, free-running value of Timer A in all modes. Software can use this value to determine the time elapsed between an interrupt and the ISR entry when using the snapshot feature with the periodic operating mode. When written, the value written into this register is loaded into the **GPTMTAR** register on the next clock cycle. In Input Edge-Count mode, bits 23:16 contain the upper 8 bits of the count.


When a GPTM is configured to one of the 32-bit modes, **GPTMTAV** appears as a 32-bit register (the upper 16-bits correspond to the contents of the **GPTM Timer B Value (GPTMTBV)** register). In a 16-bit mode, bits 15:0 contain the value of the counter and bits 23:16 contain the current, free-running value of the prescaler, which is the upper 8 bits of the count in Input Edge Count, Input Edge Time, PWM and one-shot or periodic up count modes. In one-shot or periodic down count modes, the prescaler stored in 23:16 is a true prescaler, meaning bits 23:16 count down before decrementing the value in bits 15:0. The prescaler in bits 31:24 always reads as 0.

#### GPTM Timer A Value (GPTMTAV)

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000

Offset 0x050

Type RW, reset 0xFFFF.FFF



A read returns the current, free-running value of Timer A in all modes. When written, the value written into this register is loaded into the **GPTMTAR** register on the next clock cycle.

Note:

In 16-bit mode, only the lower 16-bits of the **GPTMTAV** register can be written with a new value. Writes to the prescaler bits have no effect.

## Register 20: GPTM Timer B Value (GPTMTBV), offset 0x054

When read, this register shows the current, free-running value of Timer B in all modes. Software can use this value to determine the time elapsed between an interrupt and the ISR entry. When written, the value written into this register is loaded into the **GPTMTBR** register on the next clock cycle. In Input Edge-Count mode, bits 23:16 contain the upper 8 bits of the count.

When a GPTM is configured to one of the 32-bit modes, the contents of bits 15:0 in this register are loaded into the upper 16 bits of the **GPTMTAV** register. Reads from this register return the current free-running value of Timer B. In a 16-bit mode, bits 15:0 contain the value of the counter and bits 23:16 contain the current, free-running value of the prescaler, which is the upper 8 bits of the count in Input Edge Count, Input Edge Time, PWM and one-shot or periodic up count modes. In one-shot or periodic down count modes, the prescaler stored in 23:16 is a true prescaler, meaning bits 23:16 count down before decrementing the value in bits 15:0. The prescaler in bits 31:24 always reads as 0.

#### **GPTM Timer B Value (GPTMTBV)**


**TBV** 

RW

Timer 0 base: 0x4003.0000 Timer 1 base: 0x4003.1000 Timer 2 base: 0x4003.2000 Timer 3 base: 0x4003.3000 Offset 0x054

Type RW, reset 0x0000.FFFF

31:0



0x0000.FFFF GPTM Timer B Value

A read returns the current, free-running value of Timer A in all modes. When written, the value written into this register is loaded into the **GPTMTAR** register on the next clock cycle.

Note: In 16-bit mode, only the lower 16-bits of the **GPTMTBV** register can be written with a new value. Writes to the

prescaler bits have no effect.

## 11 Watchdog Timers

A watchdog timer can generate an interrupt or a reset when a time-out value is reached. The watchdog timer is used to regain control when a system has failed due to a software error or due to the failure of an external device to respond in the expected way. The LM3S9D96 microcontroller has two Watchdog Timer Modules, one module is clocked by the system clock (Watchdog Timer 0) and the other is clocked by the PIOSC (Watchdog Timer 1). The two modules are identical except that WDT1 is in a different clock domain, and therefore requires synchronizers. As a result, WDT1 has a bit defined in the **Watchdog Timer Control (WDTCTL)** register to indicate when a write to a WDT1 register is complete. Software can use this bit to ensure that the previous access has completed before starting the next access.


The Stellaris<sup>®</sup> LM3S9D96 controller has two Watchdog Timer modules with the following features:

- 32-bit down counter with a programmable load register
- Separate watchdog clock with an enable
- Programmable interrupt generation logic with interrupt masking
- Lock register protection from runaway software
- Reset generation logic with an enable/disable
- User-enabled stalling when the microcontroller asserts the CPU Halt flag during debug

The Watchdog Timer can be configured to generate an interrupt to the controller on its first time-out, and to generate a reset signal on its second time-out. Once the Watchdog Timer has been configured, the lock register can be written to prevent the timer configuration from being inadvertently altered.

## 11.1 Block Diagram

Figure 11-1. WDT Module Block Diagram



## 11.2 Functional Description

The Watchdog Timer module generates the first time-out signal when the 32-bit counter reaches the zero state after being enabled; enabling the counter also enables the watchdog timer interrupt. After the first time-out event, the 32-bit counter is re-loaded with the value of the **Watchdog Timer Load (WDTLOAD)** register, and the timer resumes counting down from that value. Once the Watchdog Timer has been configured, the **Watchdog Timer Lock (WDTLOCK)** register is written, which prevents the timer configuration from being inadvertently altered by software.

If the timer counts down to its zero state again before the first time-out interrupt is cleared, and the reset signal has been enabled by setting the RESEN bit in the **WDTCTL** register, the Watchdog timer asserts its reset signal to the system. If the interrupt is cleared before the 32-bit counter reaches its second time-out, the 32-bit counter is loaded with the value in the **WDTLOAD** register, and counting resumes from that value.

If **WDTLOAD** is written with a new value while the Watchdog Timer counter is counting, then the counter is loaded with the new value and continues counting.

Writing to **WDTLOAD** does not clear an active interrupt. An interrupt must be specifically cleared by writing to the **Watchdog Interrupt Clear (WDTICR)** register.

The Watchdog module interrupt and reset generation can be enabled or disabled as required. When the interrupt is re-enabled, the 32-bit counter is preloaded with the load register value and not its last state.

#### 11.2.1 Register Access Timing

Because the Watchdog Timer 1 module has an independent clocking domain, its registers must be written with a timing gap between accesses. Software must guarantee that this delay is inserted between back-to-back writes to WDT1 registers or between a write followed by a read to the registers. The timing for back-to-back reads from the WDT1 module has no restrictions. The WRC bit in the **Watchdog Control (WDTCTL)** register for WDT1 indicates that the required timing gap has elapsed. This bit is cleared on a write operation and set once the write completes, indicating to software that another write or read may be started safely. Software should poll **WDTCTL** for WRC=1 prior to accessing another register. Note that WDT0 does not have this restriction as it runs off the system clock.

## 11.3 Initialization and Configuration

To use the WDT, its peripheral clock must be enabled by setting the WDT bit in the **RCGC0n** register, see page 264.

The Watchdog Timer is configured using the following sequence:

- 1. Load the WDTLOAD register with the desired timer load value.
- 2. If WDT1, wait for the WRC bit in the WDTCTL register to be set.
- If the Watchdog is configured to trigger system resets, set the RESEN bit in the WDTCTL register.
- 4. If WDT1, wait for the WRC bit in the WDTCTL register to be set.
- 5. Set the INTEN bit in the WDTCTL register to enable the Watchdog and lock the control register.

If software requires that all of the watchdog registers are locked, the Watchdog Timer module can be fully locked by writing any value to the **WDTLOCK** register. To unlock the Watchdog Timer, write a value of 0x1ACC.E551.

To service the watchdog, periodically reload the count value into the **WDTLOAD** register to restart the count. The interrupt can be enabled using the INTEN bit in the **WDTCTL** register to allow the processor to attempt corrective action if the watchdog is not serviced often enough. The RESEN bit in the **WDTCTL** can be set so that the system resets if the failure is not recoverable using the ISR.

## 11.4 Register Map

Table 11-1 on page 587 lists the Watchdog registers. The offset listed is a hexadecimal increment to the register's address, relative to the Watchdog Timer base address:

WDT0: 0x4000.0000
WDT1: 0x4000.1000

Note that the Watchdog Timer module clock must be enabled before the registers can be programmed (see page 264).

Table 11-1. Watchdog Timers Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	WDTLOAD	R/W	0xFFFF.FFFF	Watchdog Load	588
0x004	WDTVALUE	RO	0xFFFF.FFFF	Watchdog Value	589
0x008	WDTCTL	R/W	0x0000.0000 (WDT0) 0x8000.0000 (WDT1)	Watchdog Control	590
0x00C	WDTICR	WO	-	Watchdog Interrupt Clear	592
0x010	WDTRIS	RO	0x0000.0000	Watchdog Raw Interrupt Status	593
0x014	WDTMIS	RO	0x0000.0000	Watchdog Masked Interrupt Status	594
0x418	WDTTEST	R/W	0x0000.0000	Watchdog Test	595
0xC00	WDTLOCK	R/W	0x0000.0000	Watchdog Lock	596
0xFD0	WDTPeriphID4	RO	0x0000.0000	Watchdog Peripheral Identification 4	597
0xFD4	WDTPeriphID5	RO	0x0000.0000	Watchdog Peripheral Identification 5	598
0xFD8	WDTPeriphID6	RO	0x0000.0000	Watchdog Peripheral Identification 6	599
0xFDC	WDTPeriphID7	RO	0x0000.0000	Watchdog Peripheral Identification 7	600
0xFE0	WDTPeriphID0	RO	0x0000.0005	Watchdog Peripheral Identification 0	601
0xFE4	WDTPeriphID1	RO	0x0000.0018	Watchdog Peripheral Identification 1	602
0xFE8	WDTPeriphID2	RO	0x0000.0018	Watchdog Peripheral Identification 2	603
0xFEC	WDTPeriphID3	RO	0x0000.0001	Watchdog Peripheral Identification 3	604
0xFF0	WDTPCellID0	RO	0x0000.000D	Watchdog PrimeCell Identification 0	605
0xFF4	WDTPCellID1	RO	0x0000.00F0	Watchdog PrimeCell Identification 1	606
0xFF8	WDTPCellID2	RO	0x0000.0006	Watchdog PrimeCell Identification 2	607
0xFFC	WDTPCellID3	RO	0x0000.00B1	Watchdog PrimeCell Identification 3	608

## 11.5 Register Descriptions

The remainder of this section lists and describes the WDT registers, in numerical order by address offset.

## Register 1: Watchdog Load (WDTLOAD), offset 0x000

This register is the 32-bit interval value used by the 32-bit counter. When this register is written, the value is immediately loaded and the counter restarts counting down from the new value. If the **WDTLOAD** register is loaded with 0x0000.0000, an interrupt is immediately generated.

#### Watchdog Load (WDTLOAD)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000


Offset 0x000

31:0

**WDTLOAD** 

R/W

Type R/W, reset 0xFFFF.FFF



0xFFFF.FFFF Watchdog Load Value


### Register 2: Watchdog Value (WDTVALUE), offset 0x004

This register contains the current count value of the timer.

Watchdog Value (WDTVALUE)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0x004

Type RO, reset 0xFFFF.FFFF



Bit/Field Name Type Reset Description

31:0 WDTVALUE RO 0xFFF.FFFF Watchdog Value

Current value of the 32-bit down counter.

### Register 3: Watchdog Control (WDTCTL), offset 0x008

This register is the watchdog control register. The watchdog timer can be configured to generate a reset signal (on second time-out) or an interrupt on time-out.

When the watchdog interrupt has been enabled by setting the INTEN bit, all subsequent writes to the INTEN bit are ignored. The only mechanism that can re-enable writes to this bit is a hardware reset.

Important: Because the Watchdog Timer 1 module has an independent clocking domain, its registers must be written with a timing gap between accesses. Software must guarantee that this delay is inserted between back-to-back writes to WDT1 registers or between a write followed by a read to the registers. The timing for back-to-back reads from the WDT1 module has no restrictions. The WRC bit in the Watchdog Control (WDTCTL) register for WDT1 indicates that the required timing gap has elapsed. This bit is cleared on a write operation and set once the write completes, indicating to software that another write or read may be started safely. Software should poll WDTCTL for WRC=1 prior to accessing another register. Note that WDT0 does not have this restriction as it runs off the system clock and therefore does not have a WRC bit.

#### Watchdog Control (WDTCTL)


WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000

Offset 0x008

Rit/Field

Type R/W, reset 0x0000.0000 (WDT0) and 0x8000.0000 (WDT1)

Name



2.00.0		.,,,,		2 000p.1.0
31	WRC	RO	1	Write Complete
				T

Reset

Type

The WRC values are defined as follows:

Value Description

Description

- 0 A write access to one of the WDT1 registers is in progress.
- A write access is not in progress, and WDT1 registers can be 1 read or written.

This bit is reserved for WDT0 and has a reset value of 0. Note:

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

30:2 reserved RO 0x000 000

Bit/Field	Name	Туре	Reset	Description
1	RESEN	R/W	0	Watchdog Reset Enable
				The RESEN values are defined as follows:
				Value Description
				0 Disabled.
				1 Enable the Watchdog module reset output.
0	INTEN	R/W	0	Watchdog Interrupt Enable
				The INTEN values are defined as follows:
				Value Description
				0 Interrupt event disabled (once this bit is set, it can only be cleared by a hardware reset).
				1 Interrupt event enabled. Once enabled, all writes are ignored.


## Register 4: Watchdog Interrupt Clear (WDTICR), offset 0x00C

This register is the interrupt clear register. A write of any value to this register clears the Watchdog interrupt and reloads the 32-bit counter from the **WDTLOAD** register. Value for a read or reset is indeterminate.

#### Watchdog Interrupt Clear (WDTICR)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0x00C

Type WO, reset -



Bit/Field Name Type Reset Description

31:0 WDTINTCLR WO - Watchdog Interrupt Clear


### Register 5: Watchdog Raw Interrupt Status (WDTRIS), offset 0x010

This register is the raw interrupt status register. Watchdog interrupt events can be monitored via this register if the controller interrupt is masked.

Watchdog Raw Interrupt Status (WDTRIS)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0x010

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	WDTRIS	RO	0	Watchdog Raw Interrupt Status

Value Description

- A watchdog time-out event has occurred.
- 0 The watchdog has not timed out.


#### Register 6: Watchdog Masked Interrupt Status (WDTMIS), offset 0x014

This register is the masked interrupt status register. The value of this register is the logical AND of the raw interrupt bit and the Watchdog interrupt enable bit.

#### Watchdog Masked Interrupt Status (WDTMIS)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0x014

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	WDTMIS	RO	0	Watchdog Masked Interrupt Status

#### Value Description

- A watchdog time-out event has been signalled to the interrupt controller.
- 0 The watchdog has not timed out or the watchdog timer interrupt is masked.

### Register 7: Watchdog Test (WDTTEST), offset 0x418

This register provides user-enabled stalling when the microcontroller asserts the CPU halt flag during debug.

#### Watchdog Test (WDTTEST)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0x418 Type R/W, reset 0x0000.0000

Bit/Field

7:0

Name


reserved

Type

RO

Reset

0x00



31:9	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	STALL	R/W	0	Watchdog Stall Enable
				Value Description
				1 If the microcontroller is stopped with a debugger, the watchdog timer stops counting. Once the microcontroller is restarted, the watchdog timer resumes counting.
				O The watchdog timer continues counting if the microcontroller is stopped with a debugger.

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

Description

### Register 8: Watchdog Lock (WDTLOCK), offset 0xC00


Writing 0x1ACC.E551 to the **WDTLOCK** register enables write access to all other registers. Writing any other value to the **WDTLOCK** register re-enables the locked state for register writes to all the other registers. Reading the **WDTLOCK** register returns the lock status rather than the 32-bit value written. Therefore, when write accesses are disabled, reading the **WDTLOCK** register returns 0x0000.0001 (when locked; otherwise, the returned value is 0x0000.0000 (unlocked)).

#### Watchdog Lock (WDTLOCK)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000

Offset 0xC00

Type R/W, reset 0x0000.0000



A write of the value 0x1ACC.E551 unlocks the watchdog registers for write access. A write of any other value reapplies the lock, preventing any register updates.

A read of this register returns the following values:

Value Description
0x0000.0001 Locked
0x0000.0000 Unlocked


### Register 9: Watchdog Peripheral Identification 4 (WDTPeriphID4), offset 0xFD0

The WDTPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 4 (WDTPeriphID4)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFD0

Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID4	RO	0x00	WDT Peripheral ID Register [7:0]

# Register 10: Watchdog Peripheral Identification 5 (WDTPeriphID5), offset 0xFD4

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 5 (WDTPeriphID5)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFD4 Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID5	RO	0x00	WDT Peripheral ID Register [15:8]

## Register 11: Watchdog Peripheral Identification 6 (WDTPeriphID6), offset 0xFD8

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 6 (WDTPeriphID6)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFD8 Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID6	RO	0x00	WDT Peripheral ID Register [23:16]

# Register 12: Watchdog Peripheral Identification 7 (WDTPeriphID7), offset 0xFDC

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 7 (WDTPeriphID7)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFDC Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID7	RO	0x00	WDT Peripheral ID Register [31:24]

## Register 13: Watchdog Peripheral Identification 0 (WDTPeriphID0), offset 0xFE0

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 0 (WDTPeriphID0)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFE0 Type RO, reset 0x0000.0005




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID0	RO	0x05	Watchdog Peripheral ID Register [7:0]

# Register 14: Watchdog Peripheral Identification 1 (WDTPeriphID1), offset 0xFE4

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 1 (WDTPeriphID1)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFE4 Type RO, reset 0x0000.0018




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID1	RO	0x18	Watchdog Peripheral ID Register [15:8]

## Register 15: Watchdog Peripheral Identification 2 (WDTPeriphID2), offset 0xFE8

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 2 (WDTPeriphID2)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFE8 Type RO, reset 0x0000.0018




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID2	RO	0x18	Watchdog Peripheral ID Register [23:16]

# Register 16: Watchdog Peripheral Identification 3 (WDTPeriphID3), offset 0xFEC

The **WDTPeriphIDn** registers are hard-coded and the fields within the register determine the reset value.

Watchdog Peripheral Identification 3 (WDTPeriphID3)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFEC Type RO, reset 0x0000.0001



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID3	RO	0x01	Watchdog Peripheral ID Register [31:24]


## Register 17: Watchdog PrimeCell Identification 0 (WDTPCellID0), offset 0xFF0

The WDTPCellIDn registers are hard-coded and the fields within the register determine the reset value.

Watchdog PrimeCell Identification 0 (WDTPCellID0)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFF0

Type RO, reset 0x0000.000D



Bit/Field	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID0	RO	0x0D	Watchdog PrimeCell ID Register [7:0]


## Register 18: Watchdog PrimeCell Identification 1 (WDTPCellID1), offset 0xFF4

The WDTPCellIDn registers are hard-coded and the fields within the register determine the reset value.

Watchdog PrimeCell Identification 1 (WDTPCellID1)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFF4

Type RO, reset 0x0000.00F0



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID1	RO	0xF0	Watchdog PrimeCell ID Register [15:8]


## Register 19: Watchdog PrimeCell Identification 2 (WDTPCellID2), offset 0xFF8

The WDTPCellIDn registers are hard-coded and the fields within the register determine the reset value.

Watchdog PrimeCell Identification 2 (WDTPCellID2)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFF8

Type RO, reset 0x0000.0006



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID2	RO	0x06	Watchdog PrimeCell ID Register [23:16]


## Register 20: Watchdog PrimeCell Identification 3 (WDTPCellID3), offset 0xFFC

The WDTPCellIDn registers are hard-coded and the fields within the register determine the reset value.

Watchdog PrimeCell Identification 3 (WDTPCellID3)

WDT0 base: 0x4000.0000 WDT1 base: 0x4000.1000 Offset 0xFFC

Type RO, reset 0x0000.00B1



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID3	RO	0xB1	Watchdog PrimeCell ID Register [31:24]

## 12 Analog-to-Digital Converter (ADC)

An analog-to-digital converter (ADC) is a peripheral that converts a continuous analog voltage to a discrete digital number. Two identical converter modules are included, which share 16 input channels.

The Stellaris<sup>®</sup> ADC module features 12-bit conversion resolution and supports 16 input channels, plus an internal temperature sensor. Each ADC module contains four programmable sequencers allowing the sampling of multiple analog input sources without controller intervention. Each sample sequencer provides flexible programming with fully configurable input source, trigger events, interrupt generation, and sequencer priority. A digital comparator function is included which allows the conversion value to be diverted to a digital comparator module. Each ADC module provides eight digital comparators. Each digital comparator evaluates the ADC conversion value against its two user-defined values to determine the operational range of the signal. The trigger source for ADC0 and ADC1 may be independent or the two ADC modules may operate from the same trigger source and operate on the same or different inputs. A phase shifter can delay the start of sampling by a specified phase angle. When using both ADC modules, it is possible to configure the converters to start the conversions coincidentally or within a relative phase from each other, see "Sample Phase Control" on page 615.

The Stellaris LM3S9D96 microcontroller provides two ADC modules with each having the following features:

- 16 shared analog input channels
- 12-bit precision ADC with an accurate 10-bit data compatibility mode
- Single-ended and differential-input configurations
- On-chip internal temperature sensor
- Maximum sample rate of one million samples/second
- Optional phase shift in sample time programmable from 22.5° to 337.5°
- Four programmable sample conversion sequencers from one to eight entries long, with corresponding conversion result FIFOs
- Flexible trigger control
  - Controller (software)
  - Timers
  - Analog Comparators
  - PWM
  - GPIO
- Hardware averaging of up to 64 samples
- Digital comparison unit providing eight digital comparators
- Converter uses an internal 3-V reference or an external reference

- Power and ground for the analog circuitry is separate from the digital power and ground
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Dedicated channel for each sample sequencer
  - ADC module uses burst requests for DMA

## 12.1 Block Diagram

The Stellaris microcontroller contains two identical Analog-to-Digital Converter modules. These two modules, ADC0 and ADC1, share the same 16 analog input channels. Each ADC module operates independently and can therefore execute different sample sequences, sample any of the analog input channels at any time, and generate different interrupts and triggers. Figure 12-1 on page 610 shows how the two modules are connected to analog inputs and the system bus.

Figure 12-1. Implementation of Two ADC Blocks




Figure 12-2 on page 611 provides details on the internal configuration of the ADC controls and data registers.




Figure 12-2. ADC Module Block Diagram

## 12.2 Signal Description

The following table lists the external signals of the ADC module and describes the function of each. The ADC signals are analog functions for some GPIO signals. The column in the table below titled "Pin Mux/Pin Assignment" lists the GPIO pin placement for the ADC signals. The AINx and VREFA analog signals are not 5-V tolerant and go through an isolation circuit before reaching their circuitry. These signals are configured by clearing the corresponding DEN bit in the GPIO Digital Enable (GPIODEN) register and setting the corresponding AMSEL bit in the GPIO Analog Mode Select (GPIOAMSEL) register. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 12-1. ADC Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN0	1	PE7	I	Analog	Analog-to-digital converter input 0.
AIN1	2	PE6	I	Analog	Analog-to-digital converter input 1.
AIN2	5	PE5	I	Analog	Analog-to-digital converter input 2.
AIN3	6	PE4	I	Analog	Analog-to-digital converter input 3.
AIN4	100	PD7	I	Analog	Analog-to-digital converter input 4.
AIN5	99	PD6	I	Analog	Analog-to-digital converter input 5.
AIN6	98	PD5	I	Analog	Analog-to-digital converter input 6.
AIN7	97	PD4	I	Analog	Analog-to-digital converter input 7.
AIN8	96	PE3	I	Analog	Analog-to-digital converter input 8.
AIN9	95	PE2	I	Analog	Analog-to-digital converter input 9.

Table 12-1. ADC Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN10	92	PB4	1	Analog	Analog-to-digital converter input 10.
AIN11	91	PB5	1	Analog	Analog-to-digital converter input 11.
AIN12	13	PD3	I	Analog	Analog-to-digital converter input 12.
AIN13	12	PD2	1	Analog	Analog-to-digital converter input 13.
AIN14	11	PD1	Ţ	Analog	Analog-to-digital converter input 14.
AIN15	10	PD0	1	Analog	Analog-to-digital converter input 15.
VREFA	90	PB6	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 12-2. ADC Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN0	B1	PE7	I	Analog	Analog-to-digital converter input 0.
AIN1	A1	PE6	I	Analog	Analog-to-digital converter input 1.
AIN2	В3	PE5	I	Analog	Analog-to-digital converter input 2.
AIN3	B2	PE4	I	Analog	Analog-to-digital converter input 3.
AIN4	A2	PD7	I	Analog	Analog-to-digital converter input 4.
AIN5	A3	PD6	I	Analog	Analog-to-digital converter input 5.
AIN6	C6	PD5	I	Analog	Analog-to-digital converter input 6.
AIN7	B5	PD4	I	Analog	Analog-to-digital converter input 7.
AIN8	B4	PE3	I	Analog	Analog-to-digital converter input 8.
AIN9	A4	PE2	I	Analog	Analog-to-digital converter input 9.
AIN10	A6	PB4	I	Analog	Analog-to-digital converter input 10.
AIN11	B7	PB5	I	Analog	Analog-to-digital converter input 11.
AIN12	H1	PD3	I	Analog	Analog-to-digital converter input 12.
AIN13	H2	PD2	I	Analog	Analog-to-digital converter input 13.
AIN14	G2	PD1	I	Analog	Analog-to-digital converter input 14.
AIN15	G1	PD0	I	Analog	Analog-to-digital converter input 15.
VREFA	A7	PB6	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 12.3 Functional Description

The Stellaris ADC collects sample data by using a programmable sequence-based approach instead of the traditional single or double-sampling approaches found on many ADC modules. Each *sample sequence* is a fully programmed series of consecutive (back-to-back) samples, allowing the ADC to collect data from multiple input sources without having to be re-configured or serviced by the processor. The programming of each sample in the sample sequence includes parameters such as the input source and mode (differential versus single-ended input), interrupt generation on sample completion, and the indicator for the last sample in the sequence. In addition, the  $\mu$ DMA can be used to more efficiently move data from the sample sequencers without CPU intervention.

### 12.3.1 Sample Sequencers

The sampling control and data capture is handled by the sample sequencers. All of the sequencers are identical in implementation except for the number of samples that can be captured and the depth of the FIFO. Table 12-3 on page 613 shows the maximum number of samples that each sequencer can capture and its corresponding FIFO depth. Each sample that is captured is stored in the FIFO. In this implementation, each FIFO entry is a 32-bit word, with the lower 12 bits containing the conversion result.

 Sequencer
 Number of Samples
 Depth of FIFO

 SS3
 1
 1

 SS2
 4
 4

 SS1
 4
 4

 SS0
 8
 8

Table 12-3. Samples and FIFO Depth of Sequencers

For a given sample sequence, each sample is defined by bit fields in the ADC Sample Sequence Input Multiplexer Select (ADCSSMUXn) and ADC Sample Sequence Control (ADCSSCTLn) registers, where "n" corresponds to the sequence number. The ADCSSMUXn fields select the input pin, while the ADCSSCTLn fields contain the sample control bits corresponding to parameters such as temperature sensor selection, interrupt enable, end of sequence, and differential input mode. Sample sequencers are enabled by setting the respective ASENn bit in the ADC Active Sample Sequencer (ADCACTSS) register and should be configured before being enabled. Sampling is then initiated by setting the SSn bit in the ADC Processor Sample Sequence Initiate (ADCPSSI) register. In addition, sample sequences may be initiated on multiple ADC modules simultaneously using the GSYNC and SYNCWAIT bits in the ADCPSSI register during the configuration of each ADC module. For more information on using these bits, refer to page 652.

When configuring a sample sequence, multiple uses of the same input pin within the same sequence are allowed. In the **ADCSSCTLn** register, the <code>IEn</code> bits can be set for any combination of samples, allowing interrupts to be generated after every sample in the sequence if necessary. Also, the <code>END</code> bit can be set at any point within a sample sequence. For example, if Sequencer 0 is used, the <code>END</code> bit can be set in the nibble associated with the fifth sample, allowing Sequencer 0 to complete execution of the sample sequence after the fifth sample.

After a sample sequence completes execution, the result data can be retrieved from the **ADC Sample Sequence Result FIFO (ADCSSFIFOn)** registers. The FIFOs are simple circular buffers that read a single address to "pop" result data. For software debug purposes, the positions of the FIFO head and tail pointers are visible in the **ADC Sample Sequence FIFO Status (ADCSSFSTATn)** registers along with FULL and EMPTY status flags. If a write is attempted when the FIFO is full, the write does not occur and an overflow condition is indicated. Overflow and underflow conditions are monitored using the **ADCOSTAT** and **ADCUSTAT** registers.

### 12.3.2 Module Control

Outside of the sample sequencers, the remainder of the control logic is responsible for tasks such as:

- Interrupt generation
- DMA operation
- Sequence prioritization
- Trigger configuration
- Comparator configuration
- External voltage reference
- Sample phase control

Most of the ADC control logic runs at the ADC clock rate of 16 MHz. The internal ADC divider is configured for 16-MHz operation automatically by hardware when the system XTAL is selected with the PLL.

#### **12.3.2.1** Interrupts

The register configurations of the sample sequencers and digital comparators dictate which events generate raw interrupts, but do not have control over whether the interrupt is actually sent to the interrupt controller. The ADC module's interrupt signals are controlled by the state of the MASK bits in the ADC Interrupt Mask (ADCIM) register. Interrupt status can be viewed at two locations: the ADC Raw Interrupt Status (ADCRIS) register, which shows the raw status of the various interrupt signals; and the ADC Interrupt Status and Clear (ADCISC) register, which shows active interrupts that are enabled by the ADCIM register. Sequencer interrupts are cleared by writing a 1 to the corresponding IN bit in ADCISC. Digital comparator interrupts are cleared by writing a 1 to the ADC Digital Comparator Interrupt Status and Clear (ADCDCISC) register.

### 12.3.2.2 DMA Operation

DMA may be used to increase efficiency by allowing each sample sequencer to operate independently and transfer data without processor intervention or reconfiguration. The ADC module provides a request signal from each sample sequencer to the associated dedicated channel of the  $\mu$ DMA controller. The ADC does not support single transfer requests. A burst transfer request is asserted when the interrupt bit for the sample sequence is set (IE bit in the **ADCSSCTLn** register is set).

The arbitration size of the  $\mu$ DMA transfer must be a power of 2, and the associated IE bits in the **ADDSSCTLn** register must be set. For example, if the  $\mu$ DMA channel of SS0 has an arbitration size of four, the IE3 bit (4th sample) and the IE7 bit (8th sample) must be set. Thus the  $\mu$ DMA request occurs every time 4 samples have been acquired. No other special steps are needed to enable the ADC module for  $\mu$ DMA operation.

Refer to the "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for more details about programming the  $\mu$ DMA controller.

#### 12.3.2.3 Prioritization

When sampling events (triggers) happen concurrently, they are prioritized for processing by the values in the **ADC Sample Sequencer Priority (ADCSSPRI)** register. Valid priority values are in the range of 0-3, with 0 being the highest priority and 3 being the lowest. Multiple active sample

sequencer units with the same priority do not provide consistent results, so software must ensure that all active sample sequencer units have a unique priority value.

#### 12.3.2.4 Sampling Events


Sample triggering for each sample sequencer is defined in the **ADC Event Multiplexer Select** (**ADCEMUX**) register. Trigger sources include processor (default), analog comparators, an external signal on GPIO PB4, a GP Timer, a PWM generator, and continuous sampling. The processor triggers sampling by setting the SSx bits in the **ADC Processor Sample Sequence Initiate** (**ADCPSSI**) register.

Care must be taken when using the continuous sampling trigger. If a sequencer's priority is too high, it is possible to starve other lower priority sequencers. Generally, a sample sequencer using continuous sampling should be set to the lowest priority. Continuous sampling can be used with a digital comparator to cause an interrupt when a particular voltage is seen on an input.

#### 12.3.2.5 Sample Phase Control


The trigger source for ADC0 and ADC1 may be independent or the two ADC modules may operate from the same trigger source and operate on the same or different inputs. If the converters are running at the same sample rate, they may be configured to start the conversions coincidentally or with one of 15 different discrete phases relative to each other. The sample time can be delayed from the standard sampling time in 22.5° increments up to 337.5° using the **ADC Sample Phase Control (ADCSPC)** register. Figure 12-3 on page 615 shows an example of various phase relationships at a 1 Msps rate.

#### Figure 12-3. ADC Sample Phases



This feature can be used to double the sampling rate of an input. Both ADC module 0 and ADC module 1 can be programmed to sample the same input. ADC module 0 could sample at the standard position (the PHASE field in the ADCSPC register is 0x0). ADC module 1 can be configured to sample at 180 (PHASE = 0x8). The two modules can be be synchronized using the GSYNC and SYNCWAIT bits in the ADC Processor Sample Sequence Initiate (ADCPSSI) register. Software could then combine the results from the two modules to create a sample rate of two million samples/second at 16 MHz as shown in Figure 12-4 on page 616.


Figure 12-4. Doubling the ADC Sample Rate



Using the **ADCSPC** register, ADC0 and ADC1 may provide a number of interesting applications:

- Coincident sampling of different signals. The sample sequence steps run coincidently in both converters.
  - ADC Module 0, ADCSPC = 0x0, sampling AIN0
  - ADC Module 1, ADCSPC = 0x0, sampling AIN1
- Skewed sampling of the same signal. The sample sequence steps are 1/2 of an ADC clock (500 µs for a 1Ms/s ADC) out of phase with each other. This configuration doubles the conversion bandwidth of a single input when software combines the results as shown in Figure 12-5 on page 616.
  - ADC Module 0, ADCSPC = 0x0, sampling AIN0
  - ADC Module 1, ADCSPC = 0x8, sampling AIN0

Figure 12-5. Skewed Sampling



# 12.3.3 Hardware Sample Averaging Circuit


Higher precision results can be generated using the hardware averaging circuit, however, the improved results are at the cost of throughput. Up to 64 samples can be accumulated and averaged to form a single data entry in the sequencer FIFO. Throughput is decreased proportionally to the

number of samples in the averaging calculation. For example, if the averaging circuit is configured to average 16 samples, the throughput is decreased by a factor of 16.

By default the averaging circuit is off, and all data from the converter passes through to the sequencer FIFO. The averaging hardware is controlled by the **ADC Sample Averaging Control (ADCSAC)** register (see page 654). A single averaging circuit has been implemented, thus all input channels receive the same amount of averaging whether they are single-ended or differential.

Figure 12-6 shows an example in which the **ADCSAC** register is set to 0x2 for 4x hardware oversampling and the IE1 bit is set for the sample sequence, resulting in an interrupt after the second averaged value is stored in the FIFO.

Figure 12-6. Sample Averaging Example



# 12.3.4 Analog-to-Digital Converter

The Analog-to-Digital Converter (ADC) module uses a Successive Approximation Register (SAR) architecture to deliver a 12-bit, low-power, high-precision conversion value. The ADC defaults to a 10-bit conversion result, providing backwards compatibility with previous generations of Stellaris microcontrollers. To enable 12-bit resolution, set the RES bit in the **ADC Control (ADCCTL)** register. The successive-approximation algorithm uses a current mode D/A converter to achieve lower settling time, resulting in higher conversion speeds for the A/D converter. In addition, built-in sample-and-hold circuitry with offset-calibration circuitry improves conversion accuracy. The ADC must be run from the PLL or a 16-MHz clock source. Figure 12-7 shows the ADC input equivalency diagram; for parameter values, see "Analog-to-Digital Converter (ADC)" on page 1332.




Figure 12-7. ADC Input Equivalency Diagram

The ADC operates from both the 3.3-V analog and 1.2-V digital power supplies. The ADC clock can be configured to reduce power consumption when ADC conversions are not required (see "System Control" on page 205). The analog inputs are connected to the ADC through specially balanced input paths to minimize the distortion and cross-talk on the inputs. Detailed information on the ADC power supplies and analog inputs can be found in "Analog-to-Digital Converter (ADC)" on page 1332.

### 12.3.4.1 Internal Voltage Reference

The band-gap circuitry generates an internal 3.0 V reference that can be used by the ADC to produce a conversion value from the selected analog input. The range of this conversion value is from 0x000 to 0xFFF in 12-bit mode, or 0x3FF in 10-bit mode. In single-ended-input mode, the 0x000 value corresponds to an analog input voltage of 0.0 V; the 0xFFF in 12-bit mode, or 0x3FF in 10-bit mode value corresponds to an analog input voltage of 3.0 V. This configuration results in a resolution of approximately 0.7 mV in 12-bit mode and 2.9 mV per ADC code in 10-bit mode. While the analog input pads can handle voltages beyond this range, the ADC conversions saturate in under-voltage and over-voltage cases. Figure 12-8 on page 619 shows the ADC conversion function of the analog inputs.




Figure 12-8. Internal Voltage Conversion Result

### 12.3.4.2 External Voltage Reference

The ADC can use an external voltage reference to produce the conversion value from the selected analog input by configuring the VREF field in the **ADC Control (ADCCTL)** register. The VREF field specifies whether to use the internal, an external reference in the 3.0 V range, or an external reference in the 1.0 V range. While the range of the conversion value remains the same (0x000 to 0xFFF or 0x3FF), the analog voltage associated with the 0xFFF or 0x3FF value corresponds to the value of the voltage when using the 3.0-V setting and three times the voltage when using the 1.0-V setting, resulting in a smaller voltage resolution per ADC code. Ground is always used as the reference level for the minimum conversion value. Analog input voltages above the external voltage reference saturate to 0xFFF or 0x3FF while those below 0.0 V continue to saturate at 0x000. The  $V_{REFA}$  specification defines the useful range for the external voltage reference, see Table 26-23 on page 1333. Care must be taken to supply a reference voltage of acceptable quality.

Figure 12-9 on page 620 shows the ADC conversion function of the analog inputs when using anthe 3.0-V setting on the external voltage reference. Figure 12-10 on page 620 shows the ADC conversion function when using the 1.0-V setting on the external voltage reference.

The external voltage reference can be more accurate than the internal reference by using a high-precision source or trimming the source.





Figure 12-9. External Voltage Conversion Result with 3.0-V Setting

Figure 12-10. External Voltage Conversion Result with 1.0-V Setting



### 12.3.5 Differential Sampling

In addition to traditional single-ended sampling, the ADC module supports differential sampling of two analog input channels. To enable differential sampling, software must set the Dn bit in the **ADCSSCTL0n** register in a step's configuration nibble.

When a sequence step is configured for differential sampling, the input pair to sample must be configured in the **ADCSSMUXn** register. Differential pair 0 samples analog inputs 0 and 1; differential pair 1 samples analog inputs 2 and 3; and so on (see Table 12-4 on page 621). The ADC does not support other differential pairings such as analog input 0 with analog input 3.

**Table 12-4. Differential Sampling Pairs** 

Differential Pair	Analog Inputs
0	0 and 1
1	2 and 3
2	4 and 5
3	6 and 7
4	8 and 9
5	10 and 11
6	12 and 13
7	14 and 15

The voltage sampled in differential mode is the difference between the odd and even channels:  $\Delta V$  (differential voltage) =  $V_{IN}$  (even channel) –  $V_{IN}$  ODD (odd channel), therefore:

- If  $\Delta V = 0$ , then the conversion result = 0x1FF for 10-bit and 0x7FF for 12-bit
- If  $\Delta$ V > 0, then the conversion result > 0x1FF (range is 0x1FF–0x3FF) for 10-bit and > 0x7FF (range is 0x7FF 0xFFF) for 12-bit
- If  $\Delta$ V < 0, then the conversion result < 0x1FF (range is 0–0x1FF) for 10-bit and < 0x7FF (range is 0 0x7FF) for 12-bit

The differential pairs assign polarities to the analog inputs: the even-numbered input is always positive, and the odd-numbered input is always negative. In order for a valid conversion result to appear, the negative input must be in the range of  $\pm$  1.5 V of the positive input. If an analog input is greater than 3 V or less than 0 V (the valid range for analog inputs), the input voltage is clipped, meaning it appears as either 3 V or 0 V , respectively, to the ADC.

Figure 12-11 on page 622 shows an example of the negative input centered at 1.5 V. In this configuration, the differential range spans from -1.5 V to 1.5 V. Figure 12-12 on page 622 shows an example where the negative input is centered at 0.75 V, meaning inputs on the positive input saturate past a differential voltage of -0.75 V because the input voltage is less than 0 V. Figure 12-13 on page 623 shows an example of the negative input centered at 2.25 V, where inputs on the positive channel saturate past a differential voltage of 0.75 V since the input voltage would be greater than 3 V.







Figure 12-12. Differential Sampling Range,  $V_{IN\_ODD}$  = 0.75 V






Figure 12-13. Differential Sampling Range,  $V_{IN\_ODD}$  = 2.25 V

### 12.3.6 Internal Temperature Sensor

The temperature sensor's primary purpose is to notify the system that the internal temperature is too high or low for reliable operation.

The temperature sensor does not have a separate enable, because it also contains the bandgap reference and must always be enabled. The reference is supplied to other analog modules; not just the ADC.

The internal temperature sensor provides an analog temperature reading as well as a reference voltage. This reference voltage, *SENSO*, is given by the following equation:

$$SENSO = 2.7 - ((T + 55) / 75)$$

This relation is shown in Figure 12-14 on page 624.




Figure 12-14. Internal Temperature Sensor Characteristic

The temperature sensor reading can be sampled in a sample sequence by setting the  ${\tt TSn}$  bit in the **ADCSSCTLn** register. The temperature reading from the temperature sensor can also be given as a function of the ADC value. The following formula calculates temperature (in  ${}^{\circ}$ C) based on the ADC reading:

Temperature =  $147.5 - ((225 \times ADC) / 4095)$ 

### 12.3.7 Digital Comparator Unit

An ADC is commonly used to sample an external signal and to monitor its value to ensure that it remains in a given range. To automate this monitoring procedure and reduce the amount of processor overhead that is required, each module provides eight digital comparators. Conversions from the ADC that are sent to the digital comparators are compared against the user programmable limits in the **ADC Digital Comparator Range (ADCDCCMPn)** registers. If the observed signal moves out of the acceptable range, a processor interrupt can be generated and/or a trigger can be sent to the PWM module. The digital comparators four operational modes (Once, Always, Hysteresis Once, Hysteresis Always) can be applied to three separate regions (low band, mid band, high band) as defined by the user.

#### 12.3.7.1 Output Functions

ADC conversions can either be stored in the ADC Sample Sequence FIFOs or compared using the digital comparator resources as defined by the SnDCOP bits in the **ADC Sample Sequence n Operation (ADCSSOPn)** register. These selected ADC conversions are used by their respective digital comparator to monitor the external signal. Each comparator has two possible output functions: processor interrupts and triggers.

Each function has its own state machine to track the monitored signal. Even though the interrupt and trigger functions can be enabled individually or both at the same time, the same conversion data is used by each function to determine if the right conditions have been met to assert the associated output.

#### Interrupts

The digital comparator interrupt function is enabled by setting the CIE bit in the **ADC Digital Comparator Control (ADCDCCTLn)** register. This bit enables the interrupt function state machine to start monitoring the incoming ADC conversions. When the appropriate set of conditions is met, and the DCONSSX bit is set in the **ADCIM** register, an interrupt is sent to the interrupt controller.

#### **Triggers**

The digital comparator trigger function is enabled by setting the CTE bit in the **ADCDCCTLn** register. This bit enables the trigger function state machine to start monitoring the incoming ADC conversions. When the appropriate set of conditions is met, the corresponding digital comparator trigger to the PWM module is asserted

#### 12.3.7.2 Operational Modes

Four operational modes are provided to support a broad range of applications and multiple possible signaling requirements: Always, Once, Hysteresis Always, and Hysteresis Once. The operational mode is selected using the CIM or CTM field in the **ADCDCCTLn** register.

#### Always Mode

In the Always operational mode, the associated interrupt or trigger is asserted whenever the ADC conversion value meets its comparison criteria. The result is a string of assertions on the interrupt or trigger while the conversions are within the appropriate range.

#### Once Mode

In the Once operational mode, the associated interrupt or trigger is asserted whenever the ADC conversion value meets its comparison criteria, and the previous ADC conversion value did not. The result is a single assertion of the interrupt or trigger when the conversions are within the appropriate range.

#### Hysteresis-Always Mode

The Hysteresis-Always operational mode can only be used in conjunction with the low-band or high-band regions because the mid-band region must be crossed and the opposite region entered to clear the hysteresis condition. In the Hysteresis-Always mode, the associated interrupt or trigger is asserted in the following cases: 1) the ADC conversion value meets its comparison criteria or 2) a previous ADC conversion value has met the comparison criteria, and the hysteresis condition has not been cleared by entering the opposite region. The result is a string of assertions on the interrupt or trigger that continue until the opposite region is entered.

#### Hysteresis-Once Mode

The Hysteresis-Once operational mode can only be used in conjunction with the low-band or high-band regions because the mid-band region must be crossed and the opposite region entered to clear the hysteresis condition. In the Hysteresis-Once mode, the associated interrupt or trigger is asserted only when the ADC conversion value meets its comparison criteria, the hysteresis condition is clear, and the previous ADC conversion did not meet the comparison criteria. The result is a single assertion on the interrupt or trigger.


#### 12.3.7.3 Function Ranges

The two comparison values, COMPO and COMP1, in the ADC Digital Comparator Range (ADCDCCMPn) register effectively break the conversion area into three distinct regions. These regions are referred to as the low-band (less than or equal to COMPO), mid-band (greater than COMPO but less than or equal to COMP1), and high-band (greater than COMP1) regions. COMPO and COMP1 may be programmed to the same value, effectively creating two regions, but COMP1 must always be greater than or equal to the value of COMPO. A COMP1 value that is less than COMPO generates unpredictable results.

#### Low-Band Operation

To operate in the low-band region, either the CIC field or the CTC field in the **ADCDCCTLn** register must be programmed to 0x0. This setting causes interrupts or triggers to be generated in the low-band region as defined by the programmed operational mode. An example of the state of the interrupt/trigger signal in the low-band region for each of the operational modes is shown in Figure 12-15 on page 626. Note that a "0" in a column following the operational mode name (Always, Once, Hysteresis Always, and Hysteresis Once) indicates that the interrupt or trigger signal is de-asserted and a "1" indicates that the signal is asserted.

Figure 12-15. Low-Band Operation (CIC=0x0 and/or CTC=0x0)



#### **Mid-Band Operation**

To operate in the mid-band region, either the CIC field or the CTC field in the **ADCDCCTLn** register must be programmed to 0x1. This setting causes interrupts or triggers to be generated in the mid-band region according the operation mode. Only the Always and Once operational modes are available in the mid-band region. An example of the state of the interrupt/trigger signal in the mid-band region for each of the allowed operational modes is shown in Figure 12-16 on page 627. Note that a "0" in

a column following the operational mode name (Always or Once) indicates that the interrupt or trigger signal is de-asserted and a "1" indicates that the signal is asserted.




Figure 12-16. Mid-Band Operation (CIC=0x1 and/or CTC=0x1)

#### **High-Band Operation**

Hysteresis Always -Hysteresis Once -

To operate in the high-band region, either the CIC field or the CTC field in the **ADCDCCTLn** register must be programmed to 0x3. This setting causes interrupts or triggers to be generated in the high-band region according the operation mode. An example of the state of the interrupt/trigger signal in the high-band region for each of the allowed operational modes is shown in Figure 12-17 on page 628. Note that a "0" in a column following the operational mode name (Always, Once, Hysteresis Always, and Hysteresis Once) indicates that the interrupt or trigger signal is de-asserted and a "1" indicates that the signal is asserted.




Figure 12-17. High-Band Operation (CIC=0x3 and/or CTC=0x3)

# 12.4 Initialization and Configuration

In order for the ADC module to be used, the PLL must be enabled and programmed to a supported crystal frequency in the **RCC** register (see page 221). Using unsupported frequencies can cause faulty operation in the ADC module.

### 12.4.1 Module Initialization

Initialization of the ADC module is a simple process with very few steps: enabling the clock to the ADC, disabling the analog isolation circuit associated with all inputs that are to be used, and reconfiguring the sample sequencer priorities (if needed).

The initialization sequence for the ADC is as follows:

- 1. Enable the ADC clock by using the **RCGC0** register (see page 264).
- **2.** Enable the clock to the appropriate GPIO modules via the **RCGC2** register (see page 284). To find out which GPIO ports to enable, refer to "Signal Description" on page 611.
- 3. Set the GPIO AFSEL bits for the ADC input pins (see page 430). To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the AINx and VREFA signals to be analog inputs by clearing the corresponding DEN bit in the **GPIO Digital Enable (GPIODEN)** register (see page 441).
- **5.** Disable the analog isolation circuit for all ADC input pins that are to be used by writing a 1 to the appropriate bits of the **GPIOAMSEL** register (see page 446) in the associated GPIO block.

**6.** If required by the application, reconfigure the sample sequencer priorities in the **ADCSSPRI** register. The default configuration has Sample Sequencer 0 with the highest priority and Sample Sequencer 3 as the lowest priority.

### 12.4.2 Sample Sequencer Configuration

Configuration of the sample sequencers is slightly more complex than the module initialization because each sample sequencer is completely programmable.

The configuration for each sample sequencer should be as follows:

- Ensure that the sample sequencer is disabled by clearing the corresponding ASENn bit in the ADCACTSS register. Programming of the sample sequencers is allowed without having them enabled. Disabling the sequencer during programming prevents erroneous execution if a trigger event were to occur during the configuration process.
- 2. Configure the trigger event for the sample sequencer in the ADCEMUX register.
- **3.** For each sample in the sample sequence, configure the corresponding input source in the **ADCSSMUXn** register.
- **4.** For each sample in the sample sequence, configure the sample control bits in the corresponding nibble in the **ADCSSCTLn** register. When programming the last nibble, ensure that the END bit is set. Failure to set the END bit causes unpredictable behavior.
- 5. If interrupts are to be used, set the corresponding MASK bit in the ADCIM register.
- **6.** Enable the sample sequencer logic by setting the corresponding ASENn bit in the **ADCACTSS** register.

# 12.5 Register Map

Table 12-5 on page 629 lists the ADC registers. The offset listed is a hexadecimal increment to the register's address, relative to that ADC module's base address of:

ADC0: 0x4003.8000ADC1: 0x4003.9000

Note that the ADC module clock must be enabled before the registers can be programmed (see page 264). There must be a delay of 3 system clocks after the ADC module clock is enabled before any ADC module registers are accessed.

Table 12-5. ADC Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	ADCACTSS	R/W	0x0000.0000	ADC Active Sample Sequencer	632
0x004	ADCRIS	RO	0x0000.0000	ADC Raw Interrupt Status	633
0x008	ADCIM	R/W	0x0000.0000	ADC Interrupt Mask	635
0x00C	ADCISC	R/W1C	0x0000.0000	ADC Interrupt Status and Clear	637
0x010	ADCOSTAT	R/W1C	0x0000.0000	ADC Overflow Status	640
0x014	ADCEMUX	R/W	0x0000.0000	ADC Event Multiplexer Select	642

Table 12-5. ADC Register Map (continued)

Offset	Name Type Reset		Reset	Description	See page
0x018	ADCUSTAT	R/W1C	0x0000.0000	ADC Underflow Status	647
0x020	ADCSSPRI	R/W	0x0000.3210	ADC Sample Sequencer Priority	648
0x024	ADCSPC	R/W	0x0000.0000	ADC Sample Phase Control	650
0x028	ADCPSSI	R/W	-	ADC Processor Sample Sequence Initiate	652
0x030	ADCSAC	R/W	0x0000.0000	ADC Sample Averaging Control	654
0x034	ADCDCISC	R/W1C	0x0000.0000	ADC Digital Comparator Interrupt Status and Clear	655
0x038	ADCCTL	R/W	0x0000.0000	ADC Control	657
0x040	ADCSSMUX0	R/W	0x0000.0000	ADC Sample Sequence Input Multiplexer Select 0	658
0x044	ADCSSCTL0	R/W	0x0000.0000	ADC Sample Sequence Control 0	660
0x048	ADCSSFIFO0	RO	-	ADC Sample Sequence Result FIFO 0	663
0x04C	ADCSSFSTAT0	RO	0x0000.0100	ADC Sample Sequence FIFO 0 Status	664
0x050	ADCSSOP0	R/W	0x0000.0000	ADC Sample Sequence 0 Operation	666
0x054	ADCSSDC0	R/W	0x0000.0000	ADC Sample Sequence 0 Digital Comparator Select	668
0x060	ADCSSMUX1	R/W	0x0000.0000	ADC Sample Sequence Input Multiplexer Select 1	670
0x064	ADCSSCTL1	R/W	0x0000.0000	ADC Sample Sequence Control 1	671
0x068	ADCSSFIFO1	RO	-	ADC Sample Sequence Result FIFO 1	663
0x06C	ADCSSFSTAT1	RO	0x0000.0100	ADC Sample Sequence FIFO 1 Status	664
0x070	ADCSSOP1	R/W	0x0000.0000	ADC Sample Sequence 1 Operation	673
0x074	ADCSSDC1	R/W	0x0000.0000	ADC Sample Sequence 1 Digital Comparator Select	674
0x080	ADCSSMUX2	R/W	0x0000.0000	ADC Sample Sequence Input Multiplexer Select 2	670
0x084	ADCSSCTL2	R/W	0x0000.0000	ADC Sample Sequence Control 2	671
0x088	ADCSSFIFO2	RO	-	ADC Sample Sequence Result FIFO 2	663
0x08C	ADCSSFSTAT2	RO	0x0000.0100	ADC Sample Sequence FIFO 2 Status	664
0x090	ADCSSOP2	R/W	0x0000.0000	ADC Sample Sequence 2 Operation	673
0x094	ADCSSDC2	R/W	0x0000.0000	ADC Sample Sequence 2 Digital Comparator Select	674
0x0A0	ADCSSMUX3	R/W	0x0000.0000	ADC Sample Sequence Input Multiplexer Select 3	676
0x0A4	ADCSSCTL3	R/W	0x0000.0002	ADC Sample Sequence Control 3	677
0x0A8	ADCSSFIFO3	RO	-	ADC Sample Sequence Result FIFO 3	663
0x0AC	ADCSSFSTAT3	RO	0x0000.0100	ADC Sample Sequence FIFO 3 Status	664
0x0B0	ADCSSOP3	R/W	0x0000.0000	ADC Sample Sequence 3 Operation	678
0x0B4	ADCSSDC3	R/W	0x0000.0000	ADC Sample Sequence 3 Digital Comparator Select	679
0xD00	ADCDCRIC	R/W	0x0000.0000	ADC Digital Comparator Reset Initial Conditions	680

Table 12-5. ADC Register Map (continued)

Offset	Name	Type	Reset	Description	See page
0xE00	ADCDCCTL0	R/W	0x0000.0000	ADC Digital Comparator Control 0	685
0xE04	ADCDCCTL1	R/W	0x0000.0000	ADC Digital Comparator Control 1	685
0xE08	ADCDCCTL2	R/W	0x0000.0000	ADC Digital Comparator Control 2	685
0xE0C	ADCDCCTL3	R/W	0x0000.0000	ADC Digital Comparator Control 3	685
0xE10	ADCDCCTL4	R/W	0x0000.0000	ADC Digital Comparator Control 4	685
0xE14	ADCDCCTL5	R/W	0x0000.0000	ADC Digital Comparator Control 5	685
0xE18	ADCDCCTL6	R/W	0x0000.0000	ADC Digital Comparator Control 6	685
0xE1C	ADCDCCTL7	R/W	0x0000.0000	ADC Digital Comparator Control 7	685
0xE40	ADCDCCMP0	R/W	0x0000.0000	ADC Digital Comparator Range 0	688
0xE44	ADCDCCMP1	R/W	0x0000.0000	ADC Digital Comparator Range 1	688
0xE48	ADCDCCMP2	R/W	0x0000.0000	ADC Digital Comparator Range 2	688
0xE4C	ADCDCCMP3	R/W	0x0000.0000	ADC Digital Comparator Range 3	688
0xE50	ADCDCCMP4	R/W	0x0000.0000	ADC Digital Comparator Range 4	688
0xE54	ADCDCCMP5	R/W	0x0000.0000	ADC Digital Comparator Range 5	688
0xE58	ADCDCCMP6	R/W	0x0000.0000	ADC Digital Comparator Range 6	688
0xE5C	ADCDCCMP7	R/W	0x0000.0000	ADC Digital Comparator Range 7	688

# 12.6 Register Descriptions

The remainder of this section lists and describes the ADC registers, in numerical order by address offset.


# Register 1: ADC Active Sample Sequencer (ADCACTSS), offset 0x000

This register controls the activation of the sample sequencers. Each sample sequencer can be enabled or disabled independently.

ADC Active Sample Sequencer (ADCACTSS)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	ASEN3	R/W	0	ADC SS3 Enable
				Value Description
				1 Sample Sequencer 3 is enabled.
				0 Sample Sequencer 3 is disabled.
2	ASEN2	R/W	0	ADC SS2 Enable
				Value Description
				1 Sample Sequencer 2 is enabled.
				0 Sample Sequencer 2 is disabled.
1	ASEN1	R/W	0	ADC SS1 Enable
				Value Description
				1 Sample Sequencer 1 is enabled.
				0 Sample Sequencer 1 is disabled.
0	ASEN0	R/W	0	ADC SS0 Enable
				Value Description
				1 Sample Sequencer 0 is enabled.
				0 Sample Sequencer 0 is disabled.

### Register 2: ADC Raw Interrupt Status (ADCRIS), offset 0x004

This register shows the status of the raw interrupt signal of each sample sequencer. These bits may be polled by software to look for interrupt conditions without sending the interrupts to the interrupt controller.

#### ADC Raw Interrupt Status (ADCRIS)

Name

Type


Reset

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x004

Bit/Field

Type RO, reset 0x0000.0000



Description

31:17	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
16	INRDC	RO	0	Digital Comparator Raw Interrupt Status
				Value Description
				1 At least one bit in the <b>ADCDCISC</b> register is set, meaning that a digital comparator interrupt has occurred.
				0 All bits in the <b>ADCDCISC</b> register are clear.
15:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INR3	RO	0	SS3 Raw Interrupt Status
				Value Description
				A sample has completed conversion and the respective ADCSSCTL3 IEn bit is set, enabling a raw interrupt.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the IN3 bit in the <b>ADCISC</b> register.
2	INR2	RO	0	SS2 Raw Interrupt Status
				Value Description

- A sample has completed conversion and the respective ADCSSCTL2 IEn bit is set, enabling a raw interrupt.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the IN2 bit in the ADCISC register.

Bit/Field	Name	Туре	Reset	Description
1	INR1	RO	0	SS1 Raw Interrupt Status
				Value Description
				A sample has completed conversion and the respective ADCSSCTL1 IEn bit is set, enabling a raw interrupt.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the IN1 bit in the ADCISC register.
0	INR0	RO	0	SS0 Raw Interrupt Status
				Value Description
				A sample has completed conversion and the respective ADCSSCTL0 IEn bit is set, enabling a raw interrupt.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the TNO bit in the ADCISC register


### Register 3: ADC Interrupt Mask (ADCIM), offset 0x008

This register controls whether the sample sequencer and digital comparator raw interrupt signals are sent to the interrupt controller. Each raw interrupt signal can be masked independently. Only a single <code>DCONSSn</code> bit should be set at any given time. Setting more than one of these bits results in the <code>INRDC</code> bit from the **ADCRIS** register being masked, and no interrupt is generated on any of the sample sequencer interrupt lines.

#### ADC Interrupt Mask (ADCIM)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:20	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	DCONSS3	R/W	0	Digital Comparator Interrupt on SS3
				Value Description
				The raw interrupt signal from the digital comparators (INRDC bit in the <b>ADCRIS</b> register) is sent to the interrupt controller on the SS3 interrupt line.
				O The status of the digital comparators does not affect the SS3 interrupt status.
18	DCONSS2	R/W	0	Digital Comparator Interrupt on SS2
				Value Description
				The raw interrupt signal from the digital comparators (INRDC bit in the <b>ADCRIS</b> register) is sent to the interrupt controller on the SS2 interrupt line.
				O The status of the digital comparators does not affect the SS2 interrupt status.
17	DCONSS1	R/W	0	Digital Comparator Interrupt on SS1
				Value Description

### Value Description

- The raw interrupt signal from the digital comparators (INRDC bit in the ADCRIS register) is sent to the interrupt controller on the SS1 interrupt line.
- The status of the digital comparators does not affect the SS1 interrupt status.

Bit/Field	Name	Туре	Reset	Description
16	DCONSS0	R/W	0	Digital Comparator Interrupt on SS0
				Value Description
				The raw interrupt signal from the digital comparators (INRDC bit in the <b>ADCRIS</b> register) is sent to the interrupt controller on the SS0 interrupt line.
				O The status of the digital comparators does not affect the SS0 interrupt status.
15:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	MASK3	R/W	0	SS3 Interrupt Mask
				Value Description
				1 The raw interrupt signal from Sample Sequencer 3 ( <b>ADCRIS</b> register INR3 bit) is sent to the interrupt controller.
				0 The status of Sample Sequencer 3 does not affect the SS3 interrupt status.
2	MASK2	R/W	0	SS2 Interrupt Mask
				Value Description
				1 The raw interrupt signal from Sample Sequencer 2 ( <b>ADCRIS</b> register INR2 bit) is sent to the interrupt controller.
				0 The status of Sample Sequencer 2 does not affect the SS2 interrupt status.
1	MASK1	R/W	0	SS1 Interrupt Mask
				Value Description
				1 The raw interrupt signal from Sample Sequencer 1 (ADCRIS register INR1 bit) is sent to the interrupt controller.
				O The status of Sample Sequencer 1 does not affect the SS1 interrupt status.
0	MASK0	R/W	0	SS0 Interrupt Mask
				Value Description
				1 The raw interrupt signal from Sample Sequencer 0 (ADCRIS register INR0 bit) is sent to the interrupt controller.
				The status of Sample Sequencer 0 does not affect the SS0 interrupt status.

## Register 4: ADC Interrupt Status and Clear (ADCISC), offset 0x00C

This register provides the mechanism for clearing sample sequencer interrupt conditions and shows the status of interrupts generated by the sample sequencers and the digital comparators which have been sent to the interrupt controller. When read, each bit field is the logical AND of the respective INR and MASK bits. Sample sequencer interrupts are cleared by writing a 1 to the corresponding bit position. Digital comparator interrupts are cleared by writing a 1 to the appropriate bits in the ADCDCISC register. If software is polling the ADCRIS instead of generating interrupts, the sample sequence INRn bits are still cleared via the ADCISC register, even if the INn bit is not set.

ADC Interrupt Status and Clear (ADCISC)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x00C

Type R/W1C, reset 0x0000.0000

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1	1	1	rese	rved		<b>'</b>			1	DCINSS3	DCINSS2	DCINSS1	DCINSS0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		'	ı	!	! !	rese	rved					•	IN3	IN2	IN1	IN0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W1C	R/W1C	R/W1C	R/W1C
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
E	Bit/Field		Nan	ne	Ту	pe	Reset	Des	cription							

31:20	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	DCINSS3	RO	0	Digital Comparator Interrupt Status on SS3

# Digital Comparator Interrupt Status on SS3

### Value Description

- Both the INRDC bit in the ADCRIS register and the  ${\tt DCONSS3}$ bit in the ADCIM register are set, providing a level-based interrupt to the interrupt controller.
- No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1 to it. Clearing this bit also clears the INRDC bit in the ADCRIS register.

DCINSS2 RO Digital Comparator Interrupt Status on SS2 18 0

#### Value Description

- Both the INRDC bit in the ADCRIS register and the DCONSS2 bit in the ADCIM register are set, providing a level-based interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1 to it. Clearing this bit also clears the INRDC bit in the ADCRIS register.

Bit/Field	Name	Туре	Reset	Description
17	DCINSS1	RO	0	Digital Comparator Interrupt Status on SS1
				Value Description
				Both the INRDC bit in the <b>ADCRIS</b> register and the DCONSS1 bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1 to it. Clearing this bit also clears the INRDC bit in the <b>ADCRIS</b> register.
16	DCINSS0	RO	0	Digital Comparator Interrupt Status on SS0
				Value Description
				Both the INRDC bit in the <b>ADCRIS</b> register and the DCONSS0 bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1 to it. Clearing this bit also clears the INRDC bit in the <b>ADCRIS</b> register.
15:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	IN3	R/W1C	0	SS3 Interrupt Status and Clear
				Value Description
				Both the INR3 bit in the <b>ADCRIS</b> register and the MASK3 bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt INR3}$ bit in the <b>ADCRIS</b> register.
2	IN2	R/W1C	0	SS2 Interrupt Status and Clear
				Value Description
				1 Both the INR2 bit in the <b>ADCRIS</b> register and the MASK2 bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt INR2}$ bit in the $\textbf{ADCRIS}$ register.

Bit/Field	Name	Туре	Reset	Description
1	IN1	R/W1C	0	SS1 Interrupt Status and Clear
				Value Description
				Both the INR1 bit in the <b>ADCRIS</b> register and the MASK1 bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt INR1}$ bit in the <b>ADCRIS</b> register.
0	IN0	R/W1C	0	SS0 Interrupt Status and Clear
				Value Description
				1 Both the INRO bit in the <b>ADCRIS</b> register and the MASKO bit in the <b>ADCIM</b> register are set, providing a level-based interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt INR0}$ bit in the <b>ADCRIS</b> register.

# Register 5: ADC Overflow Status (ADCOSTAT), offset 0x010


This register indicates overflow conditions in the sample sequencer FIFOs. Once the overflow condition has been handled by software, the condition can be cleared by writing a 1 to the corresponding bit position.

#### ADC Overflow Status (ADCOSTAT)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x010

Type R/W1C, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description	
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.	
3	OV3	R/W1C	0	SS3 FIFO Overflow	
				Value Description	
				1 The FIFO for Sample Sequencer 3 has hit an overflow condition, meaning that the FIFO is full and a write was requested. When an overflow is detected, the most recent write is dropped.	
				0 The FIFO has not overflowed.	
				This bit is cleared by writing a 1.	
2	OV2	R/W1C	0	SS2 FIFO Overflow	
				Value Description	
				1 The FIFO for Sample Sequencer 2 has hit an overflow condition, meaning that the FIFO is full and a write was requested. When an overflow is detected, the most recent write is dropped.	
				0 The FIFO has not overflowed.	
				This bit is cleared by writing a 1.	
1	OV1	R/W1C	0	SS1 FIFO Overflow	
				Value Description	
				1 The FIFO for Sample Sequencer 1 has hit an overflow condition, meaning that the FIFO is full and a write was requested. When	

This bit is cleared by writing a 1.

The FIFO has not overflowed.

an overflow is detected, the most recent write is dropped.

0

Bit/Field	Name	Туре	Reset	Description	
0	OV0	R/W1C	0	SS0 FIFO Overflow	
				Value Description  The FIFO for Sample Sequencer 0 has hit an overflow condition,	
				meaning that the FIFO is full and a write was requested. When an overflow is detected, the most recent write is dropped.	
				0 The FIFO has not overflowed.	
				This bit is cleared by writing a 1.	

# Register 6: ADC Event Multiplexer Select (ADCEMUX), offset 0x014

The **ADCEMUX** selects the event (trigger) that initiates sampling for each sample sequencer. Each sample sequencer can be configured with a unique trigger source.

ADC Event Multiplexer Select (ADCEMUX)


reserved

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x014

31:16

Type R/W, reset 0x0000.0000



RO

0x0000

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description	on
15:12	EM3	R/W	0x0	This field	ger Select selects the trigger source for Sample Sequencer 3. configurations for this field are:
				Value	Event
				0x0	Processor (default)
				SAC .	The trigger is initiated by setting the SSn bit in the <b>ADCPSSI</b> register.
				0x1	Analog Comparator 0
					This trigger is configured by the <b>Analog Comparator Control 0 (ACCTL0)</b> register (page 1134).
				0x2	Analog Comparator 1
					This trigger is configured by the <b>Analog Comparator Control 1 (ACCTL1)</b> register (page 1134).
				0x3	Analog Comparator 2
					This trigger is configured by the <b>Analog Comparator Control 2 (ACCTL2)</b> register (page 1134).
				0x4	External (GPIO PB4)
					This trigger is connected to the GPIO interrupt for PB4 (see "ADC Trigger Source" on page 415).
					Note: PB4 can be used to trigger the ADC. However, the PB4/AIN10 pin cannot be used as both a GPIO and an analog input.
				0x5	Timer
					In addition, the trigger must be enabled with the ${\tt TnOTE}$ bit in the <b>GPTMCTL</b> register (page 559).
				0x6	PWM0
					The PWM generator 0 trigger can be configured with the <b>PWM0 Interrupt and Trigger Enable (PWM0INTEN)</b> register (page 1181).
				0x7	PWM1
					The PWM generator 1 trigger can be configured with the <b>PWM1INTEN</b> register (page 1181).
				0x8	PWM2
					The PWM generator 2 trigger can be configured with the <b>PWM2INTEN</b> register (page 1181).
				0x9	PWM3
					The PWM generator 3 trigger can be configured with the <b>PWM3INTEN</b> register (page 1181).
				0xA-0xE	reserved
				0xF	Always (continuously sample)

Bit/Field	Name	Туре	Reset	Description	on			
11:8	EM2	R/W	0x0	SS2 Trigger Select				
					selects the trigger source for Sample Sequencer 2. configurations for this field are:			
				The valid	configurations for this field are.			
				Value	Event			
				0x0	Processor (default)			
					The trigger is initiated by setting the ${\tt SSn}$ bit in the ${\tt ADCPSSI}$ register.			
				0x1	Analog Comparator 0			
					This trigger is configured by the <b>Analog Comparator Control 0 (ACCTL0)</b> register (page 1134).			
				0x2	Analog Comparator 1			
					This trigger is configured by the <b>Analog Comparator Control 1 (ACCTL1)</b> register (page 1134).			
				0x3	Analog Comparator 2			
					This trigger is configured by the <b>Analog Comparator Control 2 (ACCTL2)</b> register (page 1134).			
				0x4	External (GPIO PB4)			
					This trigger is connected to the GPIO interrupt for $\mathtt{PB4}$ (see "ADC Trigger Source" on page 415).			
					Note: PB4 can be used to trigger the ADC. However, the PB4/AIN10 pin cannot be used as both a GPIO and an analog input.			
				0x5	Timer			
					In addition, the trigger must be enabled with the ThOTE bit in the <b>GPTMCTL</b> register (page 559).			
				0x6	PWM0			
					The PWM generator 0 trigger can be configured with the <b>PWM0 Interrupt and Trigger Enable (PWM0INTEN)</b> register (page 1181).			
				0x7	PWM1			
					The PWM generator 1 trigger can be configured with the <b>PWM1INTEN</b> register (page 1181).			
				0x8	PWM2			
					The PWM generator 2 trigger can be configured with the <b>PWM2INTEN</b> register (page 1181).			
				0x9	PWM3			
					The PWM generator 3 trigger can be configured with the <b>PWM3INTEN</b> register (page 1181).			
				0xA-0xE	reserved			
				0xF	Always (continuously sample)			

Bit/Field	Name	Туре	Reset	Description	on
7:4	EM1	R/W	0x0	This field	ger Select selects the trigger source for Sample Sequencer 1. configurations for this field are:
				Value	Event
				0x0	Processor (default)
					The trigger is initiated by setting the SSn bit in the ADCPSSI register.
				0x1	Analog Comparator 0
					This trigger is configured by the <b>Analog Comparator Control 0 (ACCTL0)</b> register (page 1134).
				0x2	Analog Comparator 1
					This trigger is configured by the <b>Analog Comparator Control 1 (ACCTL1)</b> register (page 1134).
				0x3	Analog Comparator 2
					This trigger is configured by the <b>Analog Comparator Control 2 (ACCTL2)</b> register (page 1134).
				0x4	External (GPIO PB4)
					This trigger is connected to the GPIO interrupt for PB4 (see "ADC Trigger Source" on page 415).
					Note: PB4 can be used to trigger the ADC. However, the PB4/AIN10 pin cannot be used as both a GPIO and an analog input.
				0x5	Timer
					In addition, the trigger must be enabled with the ${\tt TnOTE}$ bit in the <b>GPTMCTL</b> register (page 559).
				0x6	PWM0
					The PWM generator 0 trigger can be configured with the <b>PWM0 Interrupt and Trigger Enable (PWM0INTEN)</b> register (page 1181).
				0x7	PWM1
					The PWM generator 1 trigger can be configured with the <b>PWM1INTEN</b> register (page 1181).
				8x0	PWM2
					The PWM generator 2 trigger can be configured with the <b>PWM2INTEN</b> register (page 1181).
				0x9	PWM3
					The PWM generator 3 trigger can be configured with the <b>PWM3INTEN</b> register (page 1181).
				0xA-0xE	reserved
				0xF	Always (continuously sample)

Bit/Field	Name	Туре	Reset	Description	on	
3:0	EM0	R/W	0x0	SS0 Trigg	er Select	
						e trigger source for Sample Sequencer 0
				The valid	configurat	tions for this field are:
				Value	Event	
				0x0	Processo	or (default)
					The trigge register.	er is initiated by setting the SSn bit in the ADCPSSI
				0x1	Analog C	comparator 0
						er is configured by the <b>Analog Comparator Control L0)</b> register (page 1134).
				0x2	Analog C	omparator 1
						er is configured by the <b>Analog Comparator Control L1)</b> register (page 1134).
				0x3	Analog C	comparator 2
						er is configured by the <b>Analog Comparator Control L2)</b> register (page 1134).
				0x4	External	(GPIO PB4)
						er is connected to the GPIO interrupt for PB4 (see gger Source" on page 415).
					Note:	${\tt PB4}$ can be used to trigger the ADC. However, the ${\tt PB4/AIN10}$ pin cannot be used as both a GPIO and an analog input.
				0x5	Timer	
						n, the trigger must be enabled with the TnOTE bit PTMCTL register (page 559).
				0x6	PWM0	
						All generator 0 trigger can be configured with the <b>terrupt and Trigger Enable (PWM0INTEN)</b> register 81).
				0x7	PWM1	
						If generator 1 trigger can be configured with the <b>TEN</b> register (page 1181).
				0x8	PWM2	
						A generator 2 trigger can be configured with the <b>TEN</b> register (page 1181).
				0x9	PWM3	
						If generator 3 trigger can be configured with the <b>TEN</b> register (page 1181).
				0xA-0xE	reserved	
				0xF	Always (d	continuously sample)


### Register 7: ADC Underflow Status (ADCUSTAT), offset 0x018

This register indicates underflow conditions in the sample sequencer FIFOs. The corresponding underflow condition is cleared by writing a 1 to the relevant bit position.

ADC Underflow Status (ADCUSTAT)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x018

Type R/W1C, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	UV3	R/W1C	0	SS3 FIFO Underflow
				The valid configurations for this field are shown below. This bit is cleared by writing a 1.
				Value Description
				1 The FIFO for the Sample Sequencer has hit an underflow condition, meaning that the FIFO is empty and a read was requested. The problematic read does not move the FIFO pointers, and 0s are returned.
				0 The FIFO has not underflowed.
2	UV2	R/W1C	0	SS2 FIFO Underflow
				The valid configurations are the same as those for the ${\tt UV3}$ field. This bit is cleared by writing a 1.
1	UV1	R/W1C	0	SS1 FIFO Underflow
				The valid configurations are the same as those for the ${\tt UV3}$ field. This bit is cleared by writing a 1.
0	UV0	R/W1C	0	SS0 FIFO Underflow
				The valid configurations are the same as those for the ${\tt UV3}$ field. This bit is cleared by writing a 1.

### Register 8: ADC Sample Sequencer Priority (ADCSSPRI), offset 0x020


This register sets the priority for each of the sample sequencers. Out of reset, Sequencer 0 has the highest priority, and Sequencer 3 has the lowest priority. When reconfiguring sequence priorities, each sequence must have a unique priority for the ADC to operate properly.

#### ADC Sample Sequencer Priority (ADCSSPRI)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x020

Type R/W, reset 0x0000.3210



Bit/Field	Name	Туре	Reset	Description
31:14	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13:12	SS3	R/W	0x3	SS3 Priority  This field contains a binary-encoded value that specifies the priority encoding of Sample Sequencer 3. A priority encoding of 0x0 is highest and 0x3 is lowest. The priorities assigned to the sequencers must be uniquely mapped. The ADC may not operate properly if two or more fields are equal.
11:10	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9:8	SS2	R/W	0x2	SS2 Priority  This field contains a binary-encoded value that specifies the priority encoding of Sample Sequencer 2. A priority encoding of 0x0 is highest and 0x3 is lowest. The priorities assigned to the sequencers must be uniquely mapped. The ADC may not operate properly if two or more fields are equal.
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:4	SS1	R/W	0x1	SS1 Priority  This field contains a binary-encoded value that specifies the priority encoding of Sample Sequencer 1. A priority encoding of 0x0 is highest and 0x3 is lowest. The priorities assigned to the sequencers must be uniquely mapped. The ADC may not operate properly if two or more fields are equal.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
1:0	SS0	R/W	0x0	SS0 Priority  This field contains a binary-encoded value that specifies the priority encoding of Sample Sequencer 0. A priority encoding of 0x0 is highest and 0x3 is lowest. The priorities assigned to the sequencers must be uniquely mapped. The ADC may not operate properly if two or more fields are equal.


### Register 9: ADC Sample Phase Control (ADCSPC), offset 0x024

This register allows the ADC module to sample at one of 16 different discrete phases from 0.0° through 337.5°. For example, the sample rate could be effectively doubled by sampling a signal using one ADC module configured with the standard sample time and the second ADC module configured with a 180.0° phase lag.

Note: Care should be taken when the PHASE field is non-zero, as the resulting delay in sampling the AINx input may result in undesirable system consequences. The time from ADC trigger to sample is increased and could make the response time longer than anticipated. The added latency could have ramifications in the system design. Designers should carefully consider the impact of this delay.

#### ADC Sample Phase Control (ADCSPC)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x024 Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset [
31:4 reserved RO 0x0000.000 \$

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
3:0	PHASE	R/W	0x0	Phase Difference This field selects the sample phase difference from the standard sample time.
				Value Description
				0x0 ADC sample lags by 0.0°
				0x1 ADC sample lags by 22.5°
				0x2 ADC sample lags by 45.0°
				0x3 ADC sample lags by 67.5°
				0x4 ADC sample lags by 90.0°
				0x5 ADC sample lags by 112.5°
				0x6 ADC sample lags by 135.0°
				0x7 ADC sample lags by 157.5°
				0x8 ADC sample lags by 180.0°
				0x9 ADC sample lags by 202.5°
				0xA ADC sample lags by 225.0°
				0xB ADC sample lags by 247.5°
				0xC ADC sample lags by 270.0°
				0xD ADC sample lags by 292.5°
				0xE ADC sample lags by 315.0°
				0xF ADC sample lags by 337.5°

### Register 10: ADC Processor Sample Sequence Initiate (ADCPSSI), offset 0x028

This register provides a mechanism for application software to initiate sampling in the sample sequencers. Sample sequences can be initiated individually or in any combination. When multiple sequences are triggered simultaneously, the priority encodings in **ADCSSPRI** dictate execution order.

This register also provides a means to configure and then initiate concurrent sampling on all ADC modules. To do this, the first ADC module should be configured. The **ADCPSSI** register for that module should then be written. The appropriate SS bits should be set along with the SYNCWAIT bit. Additional ADC modules should then be configured following the same procedure. Once the final ADC module is configured, its **ADCPSSI** register should be written with the appropriate SS bits set along with the GSYNC bit. All of the ADC modules then begin concurrent sampling according to their configuration.

#### ADC Processor Sample Sequence Initiate (ADCPSSI)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x028 Type R/W, reset -

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	GSYNC		reserved		SYNCWAIT			1			reserved					ı
Type	R/W	RO	RO	RO	R/W	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
			1		·	rese	rved	1	1		1	1	SS3	SS2	SS1	SS0
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	WO	WO	WO	WO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	-	-	-	-

Bit/Field	Name	Туре	Reset	Description
31	GSYNC	R/W	0	Global Synchronize
				Value Description
				This bit initiates sampling in multiple ADC modules at the same time. Any ADC module that has been initialized by setting an SSn bit and the SYNCWAIT bit starts sampling once this bit is written.
				O This bit is cleared once sampling has been initiated.
30:28	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
27	SYNCWAIT	R/W	0	Synchronize Wait
				Value Description
				This bit allows the sample sequences to be initiated, but delays sampling until the GSYNC bit is set.
				O Sampling begins when a sample sequence has been initiated.
26:4	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
3	SS3	WO	-	SS3 Initiate
				Value Description
				Begin sampling on Sample Sequencer 3, if the sequencer is enabled in the ADCACTSS register.
				0 No effect.
				Only a write by software is valid; a read of this register returns no meaningful data.
2	SS2	WO	-	SS2 Initiate
				Value Description
				Begin sampling on Sample Sequencer 2, if the sequencer is enabled in the ADCACTSS register.
				0 No effect.
				Only a write by software is valid; a read of this register returns no meaningful data.
1	SS1	WO	-	SS1 Initiate
				Value Description
				Begin sampling on Sample Sequencer 1, if the sequencer is enabled in the ADCACTSS register.
				0 No effect.
				Only a write by software is valid; a read of this register returns no meaningful data.
0	SS0	WO	-	SS0 Initiate
				Value Description
				Begin sampling on Sample Sequencer 0, if the sequencer is enabled in the ADCACTSS register.
				0 No effect.
				Only a write by software is valid; a read of this register returns no meaningful data.


### Register 11: ADC Sample Averaging Control (ADCSAC), offset 0x030

This register controls the amount of hardware averaging applied to conversion results. The final conversion result stored in the FIFO is averaged from 2 AVG consecutive ADC samples at the specified ADC speed. If AVG is 0, the sample is passed directly through without any averaging. If AVG=6, then 64 consecutive ADC samples are averaged to generate one result in the sequencer FIFO. An AVG=7 provides unpredictable results.

#### ADC Sample Averaging Control (ADCSAC)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x030

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2.0	AVG	R/M	0x0	Hardware Averaging Control

Specifies the amount of hardware averaging that will be applied to ADC samples. The AVG field can be any value between 0 and 6. Entering a value of 7 creates unpredictable results.

Value Description 0x0 No hardware oversampling 0x1 2x hardware oversampling 0x2 4x hardware oversampling 0x3 8x hardware oversampling 0x4 16x hardware oversampling 0x5 32x hardware oversampling 0x6 64x hardware oversampling 0x7 reserved

# Register 12: ADC Digital Comparator Interrupt Status and Clear (ADCDCISC), offset 0x034


This register provides status and acknowledgement of digital comparator interrupts. One bit is provided for each comparator.

ADC Digital Comparator Interrupt Status and Clear (ADCDCISC)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x034

Type R/W1C, reset 0x0000.0000



Value Description

Digital Comparator 5 has generated an interrupt.

0 No interrupt.

This bit is cleared by writing a 1.

Bit/Field	Name	Туре	Reset	Description
4	DCINT4	R/W1C	0	Digital Comparator 4 Interrupt Status and Clear
				Value Description  1 Digital Comparator 4 has generated an interrupt.  0 No interrupt.
				This bit is cleared by writing a 1.
3	DCINT3	R/W1C	0	Digital Comparator 3 Interrupt Status and Clear
				Value Description  1 Digital Comparator 3 has generated an interrupt.  0 No interrupt.
				This bit is cleared by writing a 1.
2	DCINT2	R/W1C	0	Digital Comparator 2 Interrupt Status and Clear
				Value Description  1 Digital Comparator 2 has generated an interrupt.  0 No interrupt.
				This bit is cleared by writing a 1.
1	DCINT1	R/W1C	0	Digital Comparator 1 Interrupt Status and Clear
				Value Description  1 Digital Comparator 1 has generated an interrupt.  0 No interrupt.
				This bit is cleared by writing a 1.
0	DCINT0	R/W1C	0	Digital Comparator 0 Interrupt Status and Clear
				Value Description  1 Digital Comparator 0 has generated an interrupt.  0 No interrupt.
				This bit is cleared by writing a 1.


#### Register 13: ADC Control (ADCCTL), offset 0x038

This register configures various ADC module attributes, including the ADC resolution and the voltage reference. The resolution of the ADC defaults to 10-bit for backwards compatibility with other members of the Stellaris family, but can be configured to 12-bit resolution. The voltage reference for the conversion can be the internal 3.0-V reference, an external voltage reference in the range of 2.4 V to 3.06 V, or an external voltage reference in the range of 0.8 V to 1.02 V.

#### ADC Control (ADCCTL)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x038

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:5	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	RES	R/W	0	Sample Resolution
				Value Description  1 The ADC returns 12-bit data to the FIFOs.  0 The ADC returns 10-bit data to the FIFOs.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1:0	VREF	R/W	0x0	Voltage Reference Select

Value Description

0x0 Internal Reference

The internal reference as the voltage reference. The conversion range is from 0 V to 3.0 V.

0x1 3.0 V External Reference

A 3.0 V external <code>VREFA</code> input is the voltage reference. The ADC conversion range is 0.0 V to the voltage of the <code>VREFA</code> input.

0x2 Reserved

0x3 1.0 V External Reference

A 1.0 V external  ${\tt VREFA}$  input is the voltage reference. The ADC conversion range is 0.0 V to three times the voltage of the  ${\tt VREFA}$  input.

# Register 14: ADC Sample Sequence Input Multiplexer Select 0 (ADCSSMUX0), offset 0x040

This register defines the analog input configuration for each sample in a sequence executed with Sample Sequencer 0. This register is 32 bits wide and contains information for eight possible samples.

ADC Sample Sequence Input Multiplexer Select 0 (ADCSSMUX0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x040

Offset 0x040 Type R/W, reset 0x0000.0000

. , po	,																
	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	
	'	MU	JX7	•		. м	UX6	•	MUX5					MUX4			
Туре	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	
Reset																	
	15	14	13 I	12 T	11 T	10 1	9	8	7	6	5 1	4 T	3	2	1 1	0	
			JX3				UX2		MUX1 MUX0								
Type Reset	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	
E	Bit/Field Name			ne	Ту	ре	Reset	Des	cription								
	31:28		MUX	<b>X</b> 7	R	/W	0x0	8th	Sample	Input Se	elect						
											ū	the eight			•		
												t specifie ital conve			• .		
											-	ample, a					
								is A	IN1.								
	27:24		MUX	<b>X</b> 6	R	/W	0x0	7th	Sample	Input Se	elect						
								The	MUX6 fi	eld is us	ed during	g the sev	enth sar	mple of a	sequen	ce	
								executed with the sample sequencer. It specifies which of the analog inputs is sampled for the analog-to-digital conversion.									
								inpu	its is sar	пріеа то	r the ana	ilog-to-ai	gitai con	version.			
	23:20		MUX	<b>X</b> 5	R	/W	0x0	6th Sample Input Select									
								The MUX5 field is used during the sixth sample of a sequence executed with the sample sequencer. It specifies which of the applied inputs is									
								with the sample sequencer. It specifies which of the analog inputs is sampled for the analog-to-digital conversion.									
	19:16		MUX	<b>Υ</b> Δ	R	/W	0x0		Sample			5					
	13.10		IVIO	<b>\</b> 4	IV	, v v	0.00		•	•		g the fifth	n sample	of a sec	wence e	xecuted	
												t specifie					
								san	pled for	the anal	log-to-di	gital conv	version.				
	15:12		MUX	<b>X</b> 3	R	/W	0x0	4th	Sample	Input Se	elect						
								The	MUX3 fie	eld is use	ed during	the fourt	th sample	e of a sec	quence e	xecuted	
												t specifie		of the ar	nalog inp	uts is	
								અવા	ibien ioi	uic aila	iog-to-di	gital conv	v = 1 3 1 U 1 1.				
	11:8		MUX	X2	R	/W	0x0	3rd	Sample	Input Se	elect						
												g the third	•		•		
												t specifie gital con		or trie at	iaioy iiip	rulo 15	
									-		•	-					

Bit/Field	Name	Туре	Reset	Description
7:4	MUX1	R/W	0x0	2nd Sample Input Select The MUX1 field is used during the second sample of a sequence executed with the sample sequencer. It specifies which of the analog inputs is sampled for the analog-to-digital conversion.
3:0	MUX0	R/W	0x0	1st Sample Input Select The MUX0 field is used during the first sample of a sequence executed with the sample sequencer. It specifies which of the analog inputs is sampled for the analog-to-digital conversion.

#### Register 15: ADC Sample Sequence Control 0 (ADCSSCTL0), offset 0x044

This register contains the configuration information for each sample for a sequence executed with a sample sequencer. When configuring a sample sequence, the END bit must be set for the final sample, whether it be after the first sample, eighth sample, or any sample in between. This register is 32 bits wide and contains information for eight possible samples.

#### ADC Sample Sequence Control 0 (ADCSSCTL0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x044

Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	TS7	IE7	END7	D7	TS6	IE6	END6	D6	TS5	IE5	END5	D5	TS4	IE4	END4	D4
Type Reset	R/W 0															
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	TS3	IE3	END3	D3	TS2	IE2	END2	D2	TS1	IE1	END1	D1	TS0	IE0	END0	D0
Туре	R/W															
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31	TS7	R/W	0	8th Sample Temp Sensor Select
				Value Description
				1 The temperature sensor is read during the eighth sample of the sample sequence.
				The input pin specified by the ADCSSMUXn register is read during the eighth sample of the sample sequence.
30	IE7	R/W	0	8th Sample Interrupt Enable
				Value Description
				The raw interrupt signal (INR0 bit) is asserted at the end of the eighth sample's conversion. If the MASK0 bit in the <b>ADCIM</b> register is set, the interrupt is promoted to the interrupt controller.
				0 The raw interrupt is not asserted to the interrupt controller.
				It is legal to have multiple samples within a sequence generate interrupts.
29	END7	R/W	0	8th Sample is End of Sequence
				Value Description

- The eighth sample is the last sample of the sequence.
- 0 Another sample in the sequence is the final sample.

It is possible to end the sequence on any sample position. Software must set an  $\mathtt{ENDn}$  bit somewhere within the sequence. Samples defined after the sample containing a set  $\mathtt{ENDn}$  bit are not requested for conversion even though the fields may be non-zero.

Bit/Field	Name	Туре	Reset	Description
28	D7	R/W	0	8th Sample Diff Input Select
				Value Description
				The analog input is differentially sampled. The corresponding <b>ADCSSMUXn</b> nibble must be set to the pair number "i", where the paired inputs are "2i and 2i+1".
				The analog inputs are not differentially sampled.
				Because the temperature sensor does not have a differential option, this bit must not be set when the ${\tt TS7}$ bit is set.
27	TS6	R/W	0	7th Sample Temp Sensor Select
				Same definition as TS7 but used during the seventh sample.
26	IE6	R/W	0	7th Sample Interrupt Enable
				Same definition as IE7 but used during the seventh sample.
25	END6	R/W	0	7th Sample is End of Sequence
				Same definition as END7 but used during the seventh sample.
24	D6	R/W	0	7th Sample Diff Input Select
				Same definition as D7 but used during the seventh sample.
23	TS5	R/W	0	6th Sample Temp Sensor Select
				Same definition as TS7 but used during the sixth sample.
22	IE5	R/W	0	6th Sample Interrupt Enable
				Same definition as $\mathtt{IE7}$ but used during the sixth sample.
21	END5	R/W	0	6th Sample is End of Sequence
				Same definition as END7 but used during the sixth sample.
20	D5	R/W	0	6th Sample Diff Input Select
				Same definition as ${\tt D7}$ but used during the sixth sample.
19	TS4	R/W	0	5th Sample Temp Sensor Select
				Same definition as TS7 but used during the fifth sample.
18	IE4	R/W	0	5th Sample Interrupt Enable
				Same definition as IE7 but used during the fifth sample.
17	END4	R/W	0	5th Sample is End of Sequence
				Same definition as END7 but used during the fifth sample.
16	D4	R/W	0	5th Sample Diff Input Select
				Same definition as $\mathtt{D}7$ but used during the fifth sample.
15	TS3	R/W	0	4th Sample Temp Sensor Select
				Same definition as ${\tt TS7}$ but used during the fourth sample.
14	IE3	R/W	0	4th Sample Interrupt Enable
				Same definition as ${\tt IE7}$ but used during the fourth sample.

Bit/Field	Name	Туре	Reset	Description
13	END3	R/W	0	4th Sample is End of Sequence Same definition as END7 but used during the fourth sample.
12	D3	R/W	0	4th Sample Diff Input Select Same definition as D7 but used during the fourth sample.
11	TS2	R/W	0	3rd Sample Temp Sensor Select Same definition as TS7 but used during the third sample.
10	IE2	R/W	0	3rd Sample Interrupt Enable Same definition as IE7 but used during the third sample.
9	END2	R/W	0	3rd Sample is End of Sequence Same definition as END7 but used during the third sample.
8	D2	R/W	0	3rd Sample Diff Input Select Same definition as D7 but used during the third sample.
7	TS1	R/W	0	2nd Sample Temp Sensor Select Same definition as TS7 but used during the second sample.
6	IE1	R/W	0	2nd Sample Interrupt Enable Same definition as IE7 but used during the second sample.
5	END1	R/W	0	2nd Sample is End of Sequence Same definition as END7 but used during the second sample.
4	D1	R/W	0	2nd Sample Diff Input Select Same definition as D7 but used during the second sample.
3	TS0	R/W	0	1st Sample Temp Sensor Select Same definition as TS7 but used during the first sample.
2	IE0	R/W	0	1st Sample Interrupt Enable Same definition as IE7 but used during the first sample.
1	END0	R/W	0	1st Sample is End of Sequence Same definition as END7 but used during the first sample.
0	D0	R/W	0	1st Sample Diff Input Select Same definition as D7 but used during the first sample.


Register 16: ADC Sample Sequence Result FIFO 0 (ADCSSFIFO0), offset 0x048 Register 17: ADC Sample Sequence Result FIFO 1 (ADCSSFIFO1), offset 0x068 Register 18: ADC Sample Sequence Result FIFO 2 (ADCSSFIFO2), offset 0x088 Register 19: ADC Sample Sequence Result FIFO 3 (ADCSSFIFO3), offset 0x0A8

**Important:** This register is read-sensitive. See the register description for details.

This register contains the conversion results for samples collected with the sample sequencer (the ADCSSFIFO0 register is used for Sample Sequencer 0, ADCSSFIFO1 for Sequencer 1, ADCSSFIFO2 for Sequencer 2, and ADCSSFIFO3 for Sequencer 3). Reads of this register return conversion result data in the order sample 0, sample 1, and so on, until the FIFO is empty. If the FIFO is not properly handled by software, overflow and underflow conditions are registered in the ADCOSTAT and ADCUSTAT registers.

#### ADC Sample Sequence Result FIFO n (ADCSSFIFOn)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x048 Type RO, reset -



Bit/Field	Name	Type	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11:0	DATA	RO	-	Conversion Result Data

Register 20: ADC Sample Sequence FIFO 0 Status (ADCSSFSTAT0), offset 0x04C

Register 21: ADC Sample Sequence FIFO 1 Status (ADCSSFSTAT1), offset 0x06C

Register 22: ADC Sample Sequence FIFO 2 Status (ADCSSFSTAT2), offset 0x08C

# Register 23: ADC Sample Sequence FIFO 3 Status (ADCSSFSTAT3), offset 0x0AC

This register provides a window into the sample sequencer, providing full/empty status information as well as the positions of the head and tail pointers. The reset value of 0x100 indicates an empty FIFO with the head and tail pointers both pointing to index 0. The **ADCSSFSTAT0** register provides status on FIFO0, which has 8 entries; **ADCSSFSTAT1** on FIFO1, which has 4 entries;

**ADCSSFSTAT2** on FIFO2, which has 4 entries; and **ADCSSFSTAT3** on FIFO3 which has a single entry.

#### ADC Sample Sequence FIFO 0 Status (ADCSSFSTAT0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x04C Type RO, reset 0x0000.0100

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		'		•		' '		rese	rved	'				'	'	•
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		reserved		FULL		reserved		EMPTY		HP	TR	ı		TP	TR	
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	1	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:13	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	FULL	RO	0	Value Description  1 The FIFO is currently full.  0 The FIFO is not currently full.
11:9	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	EMPTY	RO	1	FIFO Empty  Value Description  1 The FIFO is currently empty.

0

The FIFO is not currently empty.

Bit/Field	Name	Туре	Reset	Description
7:4	HPTR	RO	0x0	FIFO Head Pointer This field contains the current "head" pointer index for the FIFO, that is, the next entry to be written.
				Valid values are 0x0-0x7 for FIFO0; 0x0-0x3 for FIFO1 and FIFO2; and 0x0 for FIFO3.
3:0	TPTR	RO	0x0	FIFO Tail Pointer  This field contains the current "tail" pointer index for the FIFO, that is, the next entry to be read.
				Valid values are 0x0-0x7 for FIFO0; 0x0-0x3 for FIFO1 and FIFO2; and 0x0 for FIFO3.

### Register 24: ADC Sample Sequence 0 Operation (ADCSSOP0), offset 0x050

This register determines whether the sample from the given conversion on Sample Sequence 0 is saved in the Sample Sequence FIFO0 or sent to the digital comparator unit.

ADC Sample Sequence 0 Operation (ADCSSOP0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x050

Type R/W, reset 0x0000.0000

.,,,,,	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		reserved		S7DCOP		reserved		S6DCOP		reserved		S5DCOP		reserved		S4DCOP
Type Reset	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		reserved		S3DCOP		reserved		S2DCOP		reserved		S1DCOP		reserved		SODCOP
Type Reset	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	R/W 0
В	sit/Field		Nan	ne	Ту	ре	Reset	Des	cription							
	31:29		reser	ved	R	0	0x0	com	patibility		re prod	ucts, the	value o	served bit. f a reserve on.		
	28		S7DC	OP	R/	W	0	Sam	ple 7 D	igital Com	parato	r Operatio	n			
								Valu	ue Desc	cription						
								1	by th		EL bit ir	n the ADC		comparato  register,		
								0	The	eighth sa	mple is	saved in	Sample	e Sequenc	e FIFC	00.
	27:25		reser	ved	R	0	0x0	com	patibility		re prod	ucts, the	value o	served bit. f a reserve on.		
	24		S6DC	OP	R/	W	0	Sam	ple 6 D	igital Com	parato	r Operatio	n			
								Sam	ne defini	tion as S7	DCOP I	out used o	during t	he sevent	h samp	ole.
	23:21		reser	ved	R	0	0x0	com	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.							
	20		S5DC	OP	R/	W	0			igital Com				he sixth sa	ample	
	19:17		reser	ved	R	0	0x0	Soft	ware sh patibility	ould not r	ely on t re prod	the value of ucts, the v	of a res	served bit. f a reserve	To pro	
	16		S4DC	OP	R/	W	0			igital Com						
								Sam	ie defini	tion as S7	DCOP I	out used o	auring t	he fifth sa	mple.	
	15:13		reser	ved	R	0	0x0	com	patibility		re prod	ucts, the	value o	served bit. f a reserve on.		

Bit/Field	Name	Туре	Reset	Description
12	S3DCOP	R/W	0	Sample 3 Digital Comparator Operation  Same definition as S7DCOP but used during the fourth sample.
11:9	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	S2DCOP	R/W	0	Sample 2 Digital Comparator Operation
				Same definition as S7DCOP but used during the third sample.
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	S1DCOP	R/W	0	Sample 1 Digital Comparator Operation
				Same definition as ${\tt S7DCOP}$ but used during the second sample.
3:1	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	SODCOP	R/W	0	Sample 0 Digital Comparator Operation
				Same definition as S7DCOP but used during the first sample.


# Register 25: ADC Sample Sequence 0 Digital Comparator Select (ADCSSDC0), offset 0x054

This register determines which digital comparator receives the sample from the given conversion on Sample Sequence 0, if the corresponding SnDCOP bit in the **ADCSSOP0** register is set.

ADC Sample Sequence 0 Digital Comparator Select (ADCSSDC0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x054

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:28	S7DCSEL	R/W	0x0	Sample 7 Digital Comparator Select

When the S7DCOP bit in the **ADCSSOP0** register is set, this field indicates which digital comparator unit (and its associated set of control registers) receives the eighth sample from Sample Sequencer 0.

Note: Values not listed are reserved.

Value	Description
0x0	Digital Comparator Unit 0 (ADCDCCMP0 and ADCDCCTL0)
0x1	Digital Comparator Unit 1 (ADCDCCMP1 and ADCDCCTL1)
0x2	Digital Comparator Unit 2 (ADCDCCMP2 and ADCDCCTL2)
0x3	Digital Comparator Unit 3 (ADCDCCMP3 and ADCDCCTL3)
0x4	Digital Comparator Unit 4 (ADCDCCMP4 and ADCDCCTL4)
0x5	Digital Comparator Unit 5 (ADCDCCMP5 and ADCDCCTL5)
0x6	Digital Comparator Unit 6 (ADCDCCMP6 and ADCDCCTL6)
0x7	Digital Comparator Unit 7 (ADCDCCMP7 and ADCDCCTL7)

27:24	S6DCSEL	R/W	0x0	Sample 6 Digital Comparator Select
				This field has the same encodings as ${\tt S7DCSEL}$ but is used during the seventh sample.
23:20	S5DCSEL	R/W	0x0	Sample 5 Digital Comparator Select
				This field has the same encodings as ${\tt S7DCSEL}$ but is used during the sixth sample.
19:16	S4DCSEL	R/W	0x0	Sample 4 Digital Comparator Select
				This field has the same encodings as ${\tt S7DCSEL}$ but is used during the fifth sample.
15:12	S3DCSEL	R/W	0x0	Sample 3 Digital Comparator Select
				This field has the same encodings as ${\tt S7DCSEL}$ but is used during the fourth sample.

Bit/Field	Name	Туре	Reset	Description
11:8	S2DCSEL	R/W	0x0	Sample 2 Digital Comparator Select This field has the same encodings as S7DCSEL but is used during the third sample.
7:4	S1DCSEL	R/W	0x0	Sample 1 Digital Comparator Select  This field has the same encodings as S7DCSEL but is used during the second sample.
3:0	SODCSEL	R/W	0x0	Sample 0 Digital Comparator Select This field has the same encodings as S7DCSEL but is used during the first sample.

# Register 26: ADC Sample Sequence Input Multiplexer Select 1 (ADCSSMUX1), offset 0x060


# Register 27: ADC Sample Sequence Input Multiplexer Select 2 (ADCSSMUX2), offset 0x080

This register defines the analog input configuration for each sample in a sequence executed with Sample Sequencer 1 or 2. These registers are 16 bits wide and contain information for four possible samples. See the **ADCSSMUX0** register on page 658 for detailed bit descriptions. The **ADCSSMUX1** register affects Sample Sequencer 1 and the **ADCSSMUX2** register affects Sample Sequencer 2.

ADC Sample Sequence Input Multiplexer Select 1 (ADCSSMUX1)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x060

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:12	MUX3	R/W	0x0	4th Sample Input Select
11:8	MUX2	R/W	0x0	3rd Sample Input Select
7:4	MUX1	R/W	0x0	2nd Sample Input Select
3:0	MUX0	R/W	0x0	1st Sample Input Select

# Register 28: ADC Sample Sequence Control 1 (ADCSSCTL1), offset 0x064 Register 29: ADC Sample Sequence Control 2 (ADCSSCTL2), offset 0x084

These registers contain the configuration information for each sample for a sequence executed with Sample Sequencer 1 or 2. When configuring a sample sequence, the END bit must be set for the final sample, whether it be after the first sample, fourth sample, or any sample in between. These registers are 16-bits wide and contain information for four possible samples. See the **ADCSSCTL0** register on page 660 for detailed bit descriptions. The **ADCSSCTL1** register configures Sample Sequencer 1 and the **ADCSSCTL2** register configures Sample Sequencer 2.

#### ADC Sample Sequence Control 1 (ADCSSCTL1)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x064 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	!		1		! !	!	•	rese	rved		•			!	!	!
Туре	RO															
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	TS3	IE3	END3	D3	TS2	IE2	END2	D2	TS1	IE1	END1	D1	TS0	IE0	END0	D0
Type Reset	R/W 0															

Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15	TS3	R/W	0	4th Sample Temp Sensor Select Same definition as TS7 but used during the fourth sample.
14	IE3	R/W	0	4th Sample Interrupt Enable Same definition as IE7 but used during the fourth sample.
13	END3	R/W	0	4th Sample is End of Sequence Same definition as END7 but used during the fourth sample.
12	D3	R/W	0	4th Sample Diff Input Select Same definition as D7 but used during the fourth sample.
11	TS2	R/W	0	3rd Sample Temp Sensor Select Same definition as TS7 but used during the third sample.
10	IE2	R/W	0	3rd Sample Interrupt Enable Same definition as IE7 but used during the third sample.
9	END2	R/W	0	3rd Sample is End of Sequence Same definition as END7 but used during the third sample.
8	D2	R/W	0	3rd Sample Diff Input Select Same definition as D7 but used during the third sample.

Bit/Field	Name	Туре	Reset	Description
7	TS1	R/W	0	2nd Sample Temp Sensor Select Same definition as TS7 but used during the second sample.
6	IE1	R/W	0	2nd Sample Interrupt Enable Same definition as IE7 but used during the second sample.
5	END1	R/W	0	2nd Sample is End of Sequence Same definition as END7 but used during the second sample.
4	D1	R/W	0	2nd Sample Diff Input Select Same definition as D7 but used during the second sample.
3	TS0	R/W	0	1st Sample Temp Sensor Select Same definition as TS7 but used during the first sample.
2	IE0	R/W	0	1st Sample Interrupt Enable Same definition as IE7 but used during the first sample.
1	END0	R/W	0	1st Sample is End of Sequence Same definition as END7 but used during the first sample.
0	D0	R/W	0	1st Sample Diff Input Select Same definition as D7 but used during the first sample.

### Register 30: ADC Sample Sequence 1 Operation (ADCSSOP1), offset 0x070 Register 31: ADC Sample Sequence 2 Operation (ADCSSOP2), offset 0x090

This register determines whether the sample from the given conversion on Sample Sequence n is saved in the Sample Sequence n FIFO or sent to the digital comparator unit. The ADCSSOP1 register controls Sample Sequencer 1 and the ADCSSOP2 register controls Sample Sequencer 2.

ADC Sample Sequence 1 Operation (ADCSSOP1)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x070 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
ſ		1 1		' '		, ,		rese	rved			1		, ,		1
l l																
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		reserved		S3DCOP		reserved		S2DCOP		reserved		S1DCOP		reserved		SODCOP
Type "	RO	RO	RO	R/W	RO	RO	RO	R/W	RO	RO	RO	R/W	RO	RO	RO	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:13	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	S3DCOP	R/W	0	Sample 3 Digital Comparator Operation
				Value Description
				The fourth sample is sent to the digital comparator unit specified by the S3DCSEL bit in the <b>ADCSSDC0n</b> register, and the value is not written to the FIFO.
				0 The fourth sample is saved in Sample Sequence FIFOn.
11:9	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	S2DCOP	R/W	0	Sample 2 Digital Comparator Operation
				Same definition as S3DCOP but used during the third sample.
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	S1DCOP	R/W	0	Sample 1 Digital Comparator Operation
				Same definition as S3DCOP but used during the second sample.
3:1	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	SODCOP	R/W	0	Sample 0 Digital Comparator Operation
				Same definition as S3DCOP but used during the first sample.

### Register 32: ADC Sample Sequence 1 Digital Comparator Select (ADCSSDC1), offset 0x074

# Register 33: ADC Sample Sequence 2 Digital Comparator Select (ADCSSDC2), offset 0x094

These registers determine which digital comparator receives the sample from the given conversion on Sample Sequence n if the corresponding SnDCOP bit in the ADCSSOPn register is set. The ADCSSDC1 register controls the selection for Sample Sequencer 1 and the ADCSSDC2 register controls the selection for Sample Sequencer 2.

ADC Sample Sequence 1 Digital Comparator Select (ADCSSDC1)

N I = ---

S2DCSEL

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x074

D:4/E:414

11:8

Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		S3D0	CSEL	ı	'	S2D0	CSEL	ı	'	S1D0	SEL			SODO	CSEL	'
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:12	S3DCSEL	R/W	0x0	Sample 3 Digital Comparator Select

D = = ==i=+i==

When the S3DCOP bit in the **ADCSSOPn** register is set, this field indicates which digital comparator unit (and its associated set of control registers) receives the eighth sample from Sample Sequencer n.

Note: Values not listed are reserved.

Value Description Digital Comparator Unit 0 (ADCDCCMP0 and ADCCCTL0) 0x0 Digital Comparator Unit 1 (ADCDCCMP1 and ADCCCTL1) 0x1 0x2Digital Comparator Unit 2 (ADCDCCMP2 and ADCCCTL2) 0x3 Digital Comparator Unit 3 (ADCDCCMP3 and ADCCCTL3) Digital Comparator Unit 4 (ADCDCCMP4 and ADCCCTL4) 0x4 0x5 Digital Comparator Unit 5 (ADCDCCMP5 and ADCCCTL5) Digital Comparator Unit 6 (ADCDCCMP6 and ADCCCTL6) 0x6 Digital Comparator Unit 7 (ADCDCCMP7 and ADCCCTL7)

R/W 0x0 Sample 2 Digital Comparator Select

This field has the same encodings as  ${\tt S3DCSEL}$  but is used during the third sample.

Bit/Field	Name	Туре	Reset	Description
7:4	S1DCSEL	R/W	0x0	Sample 1 Digital Comparator Select  This field has the same encodings as S3DCSEL but is used during the second sample.
3:0	SODCSEL	R/W	0x0	Sample 0 Digital Comparator Select  This field has the same encodings as S3DCSEL but is used during the first sample.


# Register 34: ADC Sample Sequence Input Multiplexer Select 3 (ADCSSMUX3), offset 0x0A0

This register defines the analog input configuration for the sample executed with Sample Sequencer 3. This register is 4 bits wide and contains information for one possible sample. See the **ADCSSMUX0** register on page 658 for detailed bit descriptions.

ADC Sample Sequence Input Multiplexer Select 3 (ADCSSMUX3)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x040

Offset 0x0A0 Type R/W, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	MUX0	R/W	0	1st Sample Input Select

### Register 35: ADC Sample Sequence Control 3 (ADCSSCTL3), offset 0x0A4

This register contains the configuration information for a sample executed with Sample Sequencer 3. The ENDO bit is always set as this sequencer can execute only one sample. This register is 4 bits wide and contains information for one possible sample. See the **ADCSSCTLO** register on page 660 for detailed bit descriptions.

ADC Sample Sequence Control 3 (ADCSSCTL3)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x0A4 Type R/W, reset 0x0000.0002



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	TS0	R/W	0	1st Sample Temp Sensor Select
				Same definition as TS7 but used during the first sample.
2	IE0	R/W	0	1st Sample Interrupt Enable
				Same definition as IE7 but used during the first sample.
1	END0	R/W	1	1st Sample is End of Sequence
				Same definition as $\mathtt{END7}$ but used during the first sample.
				Because this sequencer has only one entry, this bit must be set.
0	D0	R/W	0	1st Sample Diff Input Select
				Same definition as D7 but used during the first sample.

### Register 36: ADC Sample Sequence 3 Operation (ADCSSOP3), offset 0x0B0


This register determines whether the sample from the given conversion on Sample Sequence 3 is saved in the Sample Sequence 3 FIFO or sent to the digital comparator unit.

ADC Sample Sequence 3 Operation (ADCSSOP3)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000

Offset 0x0B0

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	SODCOP	R/W	0	Sample 0 Digital Comparator Operation

#### Value Description

- The sample is sent to the digital comparator unit specified by the SODCSEL bit in the ADCSSDC03 register, and the value is not written to the FIFO.
- 0 The sample is saved in Sample Sequence FIFO3.


# Register 37: ADC Sample Sequence 3 Digital Comparator Select (ADCSSDC3), offset 0x0B4

This register determines which digital comparator receives the sample from the given conversion on Sample Sequence 3 if the corresponding SnDCOP bit in the **ADCSSOP3** register is set.

ADC Sample Sequence 3 Digital Comparator Select (ADCSSDC3)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0x0B4

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	SODCSEL	R/W	0x0	Sample 0 Digital Comparator Select

When the SODCOP bit in the **ADCSSOP3** register is set, this field indicates which digital comparator unit (and its associated set of control registers) receives the sample from Sample Sequencer 3.

Note: Values not listed are reserved.

Value	Description
0x0	Digital Comparator Unit 0 (ADCDCCMP0 and ADCCCTL0)
0x1	Digital Comparator Unit 1 (ADCDCCMP1 and ADCCCTL1)
0x2	Digital Comparator Unit 2 (ADCDCCMP2 and ADCCCTL2)
0x3	Digital Comparator Unit 3 (ADCDCCMP3 and ADCCCTL3)
0x4	Digital Comparator Unit 4 (ADCDCCMP4 and ADCCCTL4)
0x5	Digital Comparator Unit 5 (ADCDCCMP5 and ADCCCTL5)
0x6	Digital Comparator Unit 6 (ADCDCCMP6 and ADCCCTL6)
0x7	Digital Comparator Unit 7 (ADCDCCMP7 and ADCCCTL7)

# Register 38: ADC Digital Comparator Reset Initial Conditions (ADCDCRIC), offset 0xD00

This register provides the ability to reset any of the digital comparator interrupt or trigger functions back to their initial conditions. Resetting these functions ensures that the data that is being used by the interrupt and trigger functions in the digital comparator unit is not stale.


ADC Digital Comparator Reset Initial Conditions (ADCDCRIC)

DCTRIG7

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0xD00

23

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:24	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

0

Value Description

Digital Comparator Trigger 7

 Resets the Digital Comparator 7 trigger unit to its initial conditions.

0 No effect.

When the trigger has been cleared, this bit is automatically cleared.

Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used. After setting this bit, software should wait until the bit clears before continuing.

22 DCTRIG6 R/W 0 Digital Comparator Trigger 6

R/W

Value Description

 Resets the Digital Comparator 6 trigger unit to its initial conditions.

0 No effect.

When the trigger has been cleared, this bit is automatically cleared.

Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.

Bit/Field	Name	Туре	Reset	Description
21	DCTRIG5	R/W	0	Digital Comparator Trigger 5
				Value Description
				<ol> <li>Resets the Digital Comparator 5 trigger unit to its initial conditions.</li> </ol>
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared. Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
20	DCTRIG4	R/W	0	Digital Comparator Trigger 4
				Value Description
				<ol> <li>Resets the Digital Comparator 4 trigger unit to its initial conditions.</li> </ol>
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
19	DCTRIG3	R/W	0	Digital Comparator Trigger 3
				Value Description
				1 Resets the Digital Comparator 3 trigger unit to its initial conditions.
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
18	DCTRIG2	R/W	0	Digital Comparator Trigger 2
				Value Description
				1 Resets the Digital Comparator 2 trigger unit to its initial conditions.
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.

Bit/Field	Name	Туре	Reset	Description
17	DCTRIG1	R/W	0	Digital Comparator Trigger 1
				Value Description
				1 Resets the Digital Comparator 1 trigger unit to its initial conditions.
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
16	DCTRIG0	R/W	0	Digital Comparator Trigger 0
				Value Description
				<ol> <li>Resets the Digital Comparator 0 trigger unit to its initial conditions.</li> </ol>
				0 No effect.
				When the trigger has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the trigger, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
15:8	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	DCINT7	R/W	0	Digital Comparator Interrupt 7
				Value Description
				1 Resets the Digital Comparator 7 interrupt unit to its initial conditions.
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
6	DCINT6	R/W	0	Digital Comparator Interrupt 6
				Value Description
				<ol> <li>Resets the Digital Comparator 6 interrupt unit to its initial conditions.</li> </ol>
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.

Bit/Field	Name	Type	Reset	Description
5	DCINT5	R/W	0	Digital Comparator Interrupt 5
				Value Description
				<ol> <li>Resets the Digital Comparator 5 interrupt unit to its initial conditions.</li> </ol>
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared. Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting
				a new sequence so that stale data is not used.
4	DCINT4	R/W	0	Digital Comparator Interrupt 4
				Value Description
				<ol> <li>Resets the Digital Comparator 4 interrupt unit to its initial conditions.</li> </ol>
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
3	DCINT3	R/W	0	Digital Comparator Interrupt 3
				Value Description
				1 Resets the Digital Comparator 3 interrupt unit to its initial conditions.
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
2	DCINT2	R/W	0	Digital Comparator Interrupt 2
				Value Description
				<ol> <li>Resets the Digital Comparator 2 interrupt unit to its initial conditions.</li> </ol>
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.
				Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.

Bit/Field	Name	Туре	Reset	Description
1	DCINT1	R/W	0	Digital Comparator Interrupt 1
				Value Description
				1 Resets the Digital Comparator 1 interrupt unit to its initial conditions.
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared. Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.
0	DCINT0	R/W	0	Digital Comparator Interrupt 0
				Value Description
				1 Resets the Digital Comparator 0 interrupt unit to its initial conditions.
				0 No effect.
				When the interrupt has been cleared, this bit is automatically cleared.


When the interrupt has been cleared, this bit is automatically cleared. Because the digital comparators use the current and previous ADC conversion values to determine when to assert the interrupt, it is important to reset the digital comparator to initial conditions when starting a new sequence so that stale data is not used.

Register 39: ADC Digital Comparator Control 0 (ADCDCCTL0), offset 0xE00 Register 40: ADC Digital Comparator Control 1 (ADCDCCTL1), offset 0xE04 Register 41: ADC Digital Comparator Control 2 (ADCDCCTL2), offset 0xE08 Register 42: ADC Digital Comparator Control 3 (ADCDCCTL3), offset 0xE0C Register 43: ADC Digital Comparator Control 4 (ADCDCCTL4), offset 0xE10 Register 44: ADC Digital Comparator Control 5 (ADCDCCTL5), offset 0xE14 Register 45: ADC Digital Comparator Control 6 (ADCDCCTL6), offset 0xE18 Register 46: ADC Digital Comparator Control 7 (ADCDCCTL7), offset 0xE1C

This register provides the comparison encodings that generate an interrupt and/or PWM trigger. See "Interrupt/ADC-Trigger Selector" on page 1144 for more information on using the ADC digital comparators to trigger a PWM generator.

### ADC Digital Comparator Control 0 (ADCDCCTL0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0xE00



Bit/Field	Name	Type	Reset	Description
31:13	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12	CTE	R/W	0	Comparison Trigger Enable

### Value Description

- 1 Enables the trigger function state machine. The ADC conversion data is used to determine if a trigger should be generated according to the programming of the CTC and CTM fields.
- O Disables the trigger function state machine. ADC conversion data is ignored by the trigger function.

Bit/Field	Name	Туре	Reset	Description
11:10	стс	R/W	0x0	Comparison Trigger Condition  This field specifies the operational region in which a trigger is generated when the ADC conversion data is compared against the values of COMPO and COMP1. The COMPO and COMP1 fields are defined in the ADCDCCMPx registers.
				Value Description  0x0 Low Band ADC Data < COMP0 ≤ COMP1  0x1 Mid Band COMP0 ≤ ADC Data < COMP1  0x2 reserved  0x3 High Band COMP0 ≤ COMP1 ≤ ADC Data
9:8	СТМ	RW	0x0	Comparison Trigger Mode This field specifies the mode by which the trigger comparison is made.  Value Description  0x0 Always  This mode generates a trigger every time the ADC conversion data falls within the selected operational region.  0x1 Once  This mode generates a trigger the first time that the ADC conversion data enters the selected operational region.  0x2 Hysteresis Always  This mode generates a trigger when the ADC conversion data falls within the selected operational region and continues to generate the trigger until the hysteresis condition is cleared by entering the opposite operational region.  Note that the hysteresis modes are only defined for CTC encodings of 0x0 and 0x3.  0x3 Hysteresis Once  This mode generates a trigger the first time that the ADC conversion data falls within the selected operational region. No additional triggers are generated until the hysteresis condition is cleared by entering the opposite operational region.  Note that the hysteresis modes are only defined for CTC encodings of 0x0 and 0x3.
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
4	CIE	R/W	0	Comparison Interrupt Enable
				Value Description
				Enables the comparison interrupt. The ADC conversion data is used to determine if an interrupt should be generated according to the programming of the CIC and CIM fields.
				0 Disables the comparison interrupt. ADC conversion data has no effect on interrupt generation.
3:2	CIC	R/W	0x0	Comparison Interrupt Condition
				This field specifies the operational region in which an interrupt is generated when the ADC conversion data is compared against the values of COMPO and COMP1. The COMPO and COMP1 fields are defined in the ADCDCCMPx registers.
				Value Description
				0x0 Low Band
				ADC Data < COMP0 ≤ COMP1
				0x1 Mid Band  COMP0 ≤ ADC Data < COMP1
				0x2 reserved
				0x3 High Band
				COMP0 < COMP1 ≤ ADC Data
1:0	CIM	R/W	0x0	Comparison Interrupt Mode
				This field specifies the mode by which the interrupt comparison is made.
				Value Description
				0x0 Always
				This mode generates an interrupt every time the ADC conversion data falls within the selected operational region.
				0x1 Once
				This mode generates an interrupt the first time that the ADC conversion data enters the selected operational region.
				0x2 Hysteresis Always
				This mode generates an interrupt when the ADC conversion data falls within the selected operational region and continues to generate the interrupt until the hysteresis condition is cleared by entering the opposite operational region.
				Note that the hysteresis modes are only defined for $\mathtt{CTC}$ encodings of $\mathtt{0x0}$ and $\mathtt{0x3}$ .
				0x3 Hysteresis Once
				This mode generates an interrupt the first time that the ADC conversion data falls within the selected operational region. No additional interrupts are generated until the hysteresis condition is cleared by entering the opposite operational region.
				Note that the hysteresis modes are only defined for $\mathtt{CTC}$ encodings of 0x0 and 0x3.

Register 47: ADC Digital Comparator Range 0 (ADCDCCMP0), offset 0xE40 Register 48: ADC Digital Comparator Range 1 (ADCDCCMP1), offset 0xE44 Register 49: ADC Digital Comparator Range 2 (ADCDCCMP2), offset 0xE48 Register 50: ADC Digital Comparator Range 3 (ADCDCCMP3), offset 0xE4C Register 51: ADC Digital Comparator Range 4 (ADCDCCMP4), offset 0xE50 Register 52: ADC Digital Comparator Range 5 (ADCDCCMP5), offset 0xE54 Register 53: ADC Digital Comparator Range 6 (ADCDCCMP6), offset 0xE58 Register 54: ADC Digital Comparator Range 7 (ADCDCCMP7), offset 0xE5C


This register defines the comparison values that are used to determine if the ADC conversion data falls in the appropriate operating region.

**Note:** The value in the COMP1 field must be greater than or equal to the value in the COMP0 field or unexpected results can occur.

If the RES bit in the **ADCCTL** register is clear, selecting 10-bit resolution, use only bits [25:16] in the COMP1 field and bits [9:0] in the COMP0 field; otherwise unexpected results can occur.

#### ADC Digital Comparator Range 0 (ADCDCCMP0)

ADC0 base: 0x4003.8000 ADC1 base: 0x4003.9000 Offset 0xE40 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:28	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
27:16	COMP1	R/W	0x000	Compare 1
				The value in this field is compared against the ADC conversion data. The result of the comparison is used to determine if the data lies within the high-band region.
				Note that the value of ${\tt COMP1}$ must be greater than or equal to the value of ${\tt COMP0}.$
15:12	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
11:0	COMP0	R/W	0x000	Compare 0  The value in this field is compared against the ADC conversion data.  The result of the comparison is used to determine if the data lies within the low-band region.

# 13 Universal Asynchronous Receivers/Transmitters (UARTs)


The Stellaris<sup>®</sup> LM3S9D96 controller includes three Universal Asynchronous Receiver/Transmitter (UART) with the following features:

- Programmable baud-rate generator allowing speeds up to 5 Mbps for regular speed (divide by 16) and 10 Mbps for high speed (divide by 8)
- Separate 16x8 transmit (TX) and receive (RX) FIFOs to reduce CPU interrupt service loading
- Programmable FIFO length, including 1-byte deep operation providing conventional double-buffered interface
- FIFO trigger levels of 1/8, 1/4, 1/2, 3/4, and 7/8
- Standard asynchronous communication bits for start, stop, and parity
- Line-break generation and detection
- Fully programmable serial interface characteristics
  - 5, 6, 7, or 8 data bits
  - Even, odd, stick, or no-parity bit generation/detection
  - 1 or 2 stop bit generation
- IrDA serial-IR (SIR) encoder/decoder providing
  - Programmable use of IrDA Serial Infrared (SIR) or UART input/output
  - Support of IrDA SIR encoder/decoder functions for data rates up to 115.2 Kbps half-duplex
  - Support of normal 3/16 and low-power (1.41-2.23 μs) bit durations
  - Programmable internal clock generator enabling division of reference clock by 1 to 256 for low-power mode bit duration
- Support for communication with ISO 7816 smart cards
- Full modem handshake support (on UART1)
- LIN protocol support
- Standard FIFO-level and End-of-Transmission interrupts
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Receive single request asserted when data is in the FIFO; burst request asserted at programmed FIFO level

 Transmit single request asserted when there is space in the FIFO; burst request asserted at programmed FIFO level

### 13.1 Block Diagram

Figure 13-1. UART Module Block Diagram



### 13.2 Signal Description

The following table lists the external signals of the UART module and describes the function of each. The UART signals are alternate functions for some GPIO signals and default to be GPIO signals at reset, with the exception of the UORX and UOTX pins which default to the UART function. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for these UART signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the UART function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the UART signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOS)" on page 407.

Table 13-1. UART Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
UORx	26	PA0 (1)	ı	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
UOTx	27	PA1 (1)	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.
U1CTS	2 10 34 50	PE6 (9) PD0 (9) PA6 (9) PJ3 (9)	I	TTL	UART module 1 Clear To Send modem flow control input signal.
U1DCD	1 11 35 52	PE7 (9) PD1 (9) PA7 (9) PJ4 (9)	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
U1DSR	47 53	PF0 (9) PJ5 (9)	I	TTL	UART module 1 Data Set Ready modem output control line.
U1DTR	55 100	PJ7 (9) PD7 (9)	0	TTL	UART module 1 Data Terminal Ready modem status input signal.
UlRI	97	PD4 (9)	I	TTL	UART module 1 Ring Indicator modem status input signal.
U1RTS	54 61	PJ6 (9) PF1 (9)	0	TTL	UART module 1 Request to Send modem flow control output line.
UlRx	10 12 23 26 66 92	PD0 (5) PD2 (1) PC6 (5) PA0 (9) PB0 (5) PB4 (7)	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
UlTx	11 13 22 27 67 91	PD1 (5) PD3 (1) PC7 (5) PA1 (9) PB1 (5) PB5 (7)	O	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
U2Rx	10 19 92 98	PD0 (4) PG0 (1) PB4 (4) PD5 (9)	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
U2Tx	6 11 18 99	PE4 (5) PD1 (4) PG1 (1) PD6 (9)	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### Table 13-2. UART Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
UORx	L3	PA0 (1)	I		UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
UOTx	М3	PA1 (1)	0		UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.

Table 13-2. UART Signals (108BGA) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
U1CTS	A1 G1 L6 M10	PE6 (9) PD0 (9) PA6 (9) PJ3 (9)	I	TTL	UART module 1 Clear To Send modem flow control input signal.
U1DCD	B1 G2 M6 K11	PE7 (9) PD1 (9) PA7 (9) PJ4 (9)	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
U1DSR	M9 K12	PF0 (9) PJ5 (9)	I	TTL	UART module 1 Data Set Ready modem output control line.
U1DTR	L12 A2	PJ7 (9) PD7 (9)	0	TTL	UART module 1 Data Terminal Ready modem status input signal.
UlRI	B5	PD4 (9)	I	TTL	UART module 1 Ring Indicator modem status input signal.
U1RTS	L10 H12	PJ6 (9) PF1 (9)	0	TTL	UART module 1 Request to Send modem flow control output line.
U1Rx	G1 H2 M2 L3 E12 A6	PD0 (5) PD2 (1) PC6 (5) PA0 (9) PB0 (5) PB4 (7)	ı	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
UlTx	G2 H1 L2 M3 D12 B7	PD1 (5) PD3 (1) PC7 (5) PA1 (9) PB1 (5) PB5 (7)	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
U2Rx	G1 K1 A6 C6	PD0 (4) PG0 (1) PB4 (4) PD5 (9)	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
U2Tx	B2 G2 K2 A3	PE4 (5) PD1 (4) PG1 (1) PD6 (9)	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### 13.3 Functional Description

Each Stellaris UART performs the functions of parallel-to-serial and serial-to-parallel conversions. It is similar in functionality to a 16C550 UART, but is not register compatible.

The UART is configured for transmit and/or receive via the TXE and RXE bits of the **UART Control** (**UARTCTL**) register (see page 718). Transmit and receive are both enabled out of reset. Before any control registers are programmed, the UART must be disabled by clearing the UARTEN bit in **UARTCTL**. If the UART is disabled during a TX or RX operation, the current transaction is completed prior to the UART stopping.

The UART module also includes a serial IR (SIR) encoder/decoder block that can be connected to an infrared transceiver to implement an IrDA SIR physical layer. The SIR function is programmed using the **UARTCTL** register.

### 13.3.1 Transmit/Receive Logic

The transmit logic performs parallel-to-serial conversion on the data read from the transmit FIFO. The control logic outputs the serial bit stream beginning with a start bit and followed by the data bits (LSB first), parity bit, and the stop bits according to the programmed configuration in the control registers. See Figure 13-2 on page 694 for details.

The receive logic performs serial-to-parallel conversion on the received bit stream after a valid start pulse has been detected. Overrun, parity, frame error checking, and line-break detection are also performed, and their status accompanies the data that is written to the receive FIFO.

Figure 13-2. UART Character Frame



### 13.3.2 Baud-Rate Generation

The baud-rate divisor is a 22-bit number consisting of a 16-bit integer and a 6-bit fractional part. The number formed by these two values is used by the baud-rate generator to determine the bit period. Having a fractional baud-rate divisor allows the UART to generate all the standard baud rates.

The 16-bit integer is loaded through the **UART Integer Baud-Rate Divisor (UARTIBRD)** register (see page 714) and the 6-bit fractional part is loaded with the **UART Fractional Baud-Rate Divisor (UARTFBRD)** register (see page 715). The baud-rate divisor (BRD) has the following relationship to the system clock (where *BRDI* is the integer part of the *BRD* and *BRDF* is the fractional part, separated by a decimal place.)

```
BRD = BRDI + BRDF = UARTSysClk / (ClkDiv * Baud Rate)
```

where <code>UARTSysClk</code> is the system clock connected to the UART, and <code>ClkDiv</code> is either 16 (if <code>HSE</code> in <code>UARTCTL</code> is clear) or 8 (if <code>HSE</code> is set).

The 6-bit fractional number (that is to be loaded into the DIVFRAC bit field in the **UARTFBRD** register) can be calculated by taking the fractional part of the baud-rate divisor, multiplying it by 64, and adding 0.5 to account for rounding errors:

```
UARTFBRD[DIVFRAC] = integer(BRDF * 64 + 0.5)
```

The UART generates an internal baud-rate reference clock at 8x or 16x the baud-rate (referred to as Baud8 and Baud16, depending on the setting of the HSE bit (bit 5) in **UARTCTL**). This reference clock is divided by 8 or 16 to generate the transmit clock, and is used for error detection during receive operations. Note that the state of the HSE bit has no effect on clock generation in ISO 7816 smart card mode (when the SMART bit in the **UARTCTL** register is set).

Along with the **UART Line Control**, **High Byte (UARTLCRH)** register (see page 716), the **UARTIBRD** and **UARTFBRD** registers form an internal 30-bit register. This internal register is only updated when a write operation to **UARTLCRH** is performed, so any changes to the baud-rate divisor must be followed by a write to the **UARTLCRH** register for the changes to take effect.

To update the baud-rate registers, there are four possible sequences:

■ UARTIBRD write, UARTFBRD write, and UARTLCRH write

- UARTFBRD write, UARTIBRD write, and UARTLCRH write
- UARTIBRD write and UARTLCRH write
- UARTFBRD write and UARTLCRH write

### 13.3.3 Data Transmission

Data received or transmitted is stored in two 16-byte FIFOs, though the receive FIFO has an extra four bits per character for status information. For transmission, data is written into the transmit FIFO. If the UART is enabled, it causes a data frame to start transmitting with the parameters indicated in the **UARTLCRH** register. Data continues to be transmitted until there is no data left in the transmit FIFO. The BUSY bit in the **UART Flag (UARTFR)** register (see page 710) is asserted as soon as data is written to the transmit FIFO (that is, if the FIFO is non-empty) and remains asserted while data is being transmitted. The BUSY bit is negated only when the transmit FIFO is empty, and the last character has been transmitted from the shift register, including the stop bits. The UART can indicate that it is busy even though the UART may no longer be enabled.

When the receiver is idle (the UnRx signal is continuously 1), and the data input goes Low (a start bit has been received), the receive counter begins running and data is sampled on the eighth cycle of Baud16 or fourth cycle of Baud8 depending on the setting of the HSE bit (bit 5) in **UARTCTL** (described in "Transmit/Receive Logic" on page 694).

The start bit is valid and recognized if the Unrx signal is still low on the eighth cycle of Baud16 (HSE clear) or the fourth cycle of Baud 8 (HSE set), otherwise it is ignored. After a valid start bit is detected, successive data bits are sampled on every 16th cycle of Baud16 or 8th cycle of Baud8 (that is, one bit period later) according to the programmed length of the data characters and value of the HSE bit in UARTCTL. The parity bit is then checked if parity mode is enabled. Data length and parity are defined in the UARTLCRH register.

Lastly, a valid stop bit is confirmed if the UnRx signal is High, otherwise a framing error has occurred. When a full word is received, the data is stored in the receive FIFO along with any error bits associated with that word.

### 13.3.4 **Serial IR (SIR)**


The UART peripheral includes an IrDA serial-IR (SIR) encoder/decoder block. The IrDA SIR block provides functionality that converts between an asynchronous UART data stream and a half-duplex serial SIR interface. No analog processing is performed on-chip. The role of the SIR block is to provide a digital encoded output and decoded input to the UART. When enabled, the SIR block uses the UnTx and UnRx pins for the SIR protocol. These signals should be connected to an infrared transceiver to implement an IrDA SIR physical layer link. The SIR block can receive and transmit, but it is only half-duplex so it cannot do both at the same time. Transmission must be stopped before data can be received. The IrDA SIR physical layer specifies a minimum 10-ms delay between transmission and reception. The SIR block has two modes of operation:

- In normal IrDA mode, a zero logic level is transmitted as a high pulse of 3/16th duration of the selected baud rate bit period on the output pin, while logic one levels are transmitted as a static LOW signal. These levels control the driver of an infrared transmitter, sending a pulse of light for each zero. On the reception side, the incoming light pulses energize the photo transistor base of the receiver, pulling its output LOW and driving the UART input pin LOW.
- In low-power IrDA mode, the width of the transmitted infrared pulse is set to three times the period of the internally generated IrLPBaud16 signal (1.63 μs, assuming a nominal 1.8432 MHz

frequency) by changing the appropriate bit in the **UARTCR** register. See page 713 for more information on IrDA low-power pulse-duration configuration.

Figure 13-3 on page 696 shows the UART transmit and receive signals, with and without IrDA modulation.

Figure 13-3. IrDA Data Modulation



In both normal and low-power IrDA modes:

- During transmission, the UART data bit is used as the base for encoding
- During reception, the decoded bits are transferred to the UART receive logic

The IrDA SIR physical layer specifies a half-duplex communication link, with a minimum 10-ms delay between transmission and reception. This delay must be generated by software because it is not automatically supported by the UART. The delay is required because the infrared receiver electronics might become biased or even saturated from the optical power coupled from the adjacent transmitter LED. This delay is known as latency or receiver setup time.

### 13.3.5 ISO 7816 Support

The UART offers basic support to allow communication with an ISO 7816 smartcard. When bit 3 (SMART) of the **UARTCTL** register is set, the UnTx signal is used as a bit clock, and the UnRx signal is used as the half-duplex communication line connected to the smartcard. A GPIO signal can be used to generate the reset signal to the smartcard. The remaining smartcard signals should be provided by the system design. The maximum clock rate in this mode is system clock / 16.

When using ISO 7816 mode, the **UARTLCRH** register must be set to transmit 8-bit words (WLEN bits 6:5 configured to 0x3) with EVEN parity (PEN set and EPS set). In this mode, the UART automatically uses 2 stop bits, and the STP2 bit of the **UARTLCRH** register is ignored.

If a parity error is detected during transmission, UnRx is pulled Low during the second stop bit. In this case, the UART aborts the transmission, flushes the transmit FIFO and discards any data it contains, and raises a parity error interrupt, allowing software to detect the problem and initiate retransmission of the affected data. Note that the UART does not support automatic retransmission in this case.

### 13.3.6 Modem Handshake Support

This section describes how to configure and use the modem flow control and status signals for UART1 when connected as a DTE (data terminal equipment) or as a DCE (data communications equipment). In general, a modem is a DCE and a computing device that connects to a modem is the DTE.

### 13.3.6.1 **Signaling**

The status signals provided by UART1 differ based on whether the UART is used as a DTE or DCE. When used as a DTE, the modem flow control and status signals are defined as:

- UICTS is Clear To Send
- ŪIDSR is Data Set Ready
- ŪIDCD is Data Carrier Detect
- UIRI is Ring Indicator
- ŪIRTS is Request To Send
- U1DTR is Data Terminal Ready

When used as a DCE, the the modem flow control and status signals are defined as:

- Ū1CTS is Request To Send
- UIDSR is Data Terminal Ready
- ŪIRTS is Clear To Send
- UIDTR is Data Set Ready

Note that the support for DCE functions Data Carrier Detect and Ring Indicator are not provided. If these signals are required, their function can be emulated by using a general-purpose I/O signal and providing software support.

#### **13.3.6.2** Flow Control

Flow control can be accomplished by either hardware or software. The following sections describe the different methods.

### Hardware Flow Control (RTS/CTS)

Hardware flow control between two devices is accomplished by connecting the  $\overline{\mathtt{UIRTS}}$  output to the Clear-To-Send input on the receiving device, and connecting the Request-To-Send output on the receiving device to the  $\overline{\mathtt{UICTS}}$  input.

The  $\overline{\mathtt{U1CTS}}$  input controls the transmitter. The transmitter may only transmit data when the  $\overline{\mathtt{U1CTS}}$  input is asserted. The  $\overline{\mathtt{U1RTS}}$  output signal indicates the state of the receive FIFO.  $\overline{\mathtt{U1CTS}}$  remains asserted until the preprogrammed watermark level is reached, indicating that the Receive FIFO has no space to store additional characters.

The **UARTCTL** register bits 15 (CTSEN) and 14 (RTSEN) specify the flow control mode as shown in Table 13-3 on page 698.

**Table 13-3. Flow Control Mode** 

CTSEN	RTSEN	Description
1	1	RTS and CTS flow control enabled
1	0	Only CTS flow control enabled
0	1	Only RTS flow control enabled
0	0	Both RTS and CTS flow control disabled

Note that when RTSEN is 1, software cannot modify the  $\overline{\mathtt{UIRTS}}$  output value through the **UARTCTL** register Request to Send (RTS) bit, and the status of the RTS bit should be ignored.


### Software Flow Control (Modem Status Interrupts)

Software flow control between two devices is accomplished by using interrupts to indicate the status of the UART. Interrupts may be generated for the  $\overline{\mathtt{UIDSR}}$ ,  $\overline{\mathtt{UIDCD}}$ ,  $\overline{\mathtt{UICTS}}$ , and  $\overline{\mathtt{UIRI}}$  signals using bits 3:0 of the **UARTIM** register, respectively. The raw and masked interrupt status may be checked using the **UARTRIS** and **UARTMIS** register. These interrupts may be cleared using the **UARTICR** register.

### 13.3.7 LIN Support

The UART module offers hardware support for the LIN protocol as either a master or a slave. The LIN mode is enabled by setting the LIN bit in the **UARTCTL** register. A LIN message is identified by the use of a Sync Break at the beginning of the message. The Sync Break is a transmission of a series of 0s. The Sync Break is followed by the Sync data field (0x55). Figure 13-4 on page 698 illustrates the structure of a LIN message.

Figure 13-4. LIN Message



The UART should be configured as followed to operate in LIN mode:

- 1. Configure the UART for 1 start bit, 8 data bits, no parity, and 1 stop bit. Enable the Transmit FIFO.
- 2. Set the LIN bit in the **UARTCTL** register.

When preparing to send a LIN message, the TXFIFO should contain the Sync data (0x55) at FIFO location 0 and the Identifier data at location 1, followed by the data to be transmitted, and with the checksum in the final FIFO entry.

### 13.3.7.1 LIN Master


The UART is enabled to be the LIN master by setting the MASTER bit in the **UARTLCTL** register. The length of the Sync Break is programmable using the BLEN field in the **UARTLCTL** register and can be 13-16 bits (baud clock cycles).

### 13.3.7.2 LIN Slave

The LIN UART slave is required to adjust its baud rate to that of the LIN master. In slave mode, the LIN UART recognizes the Sync Break, which must be at least 13 bits in duration. A timer is provided to capture timing data on the 1st and 5th falling edges of the Sync field so that the baud rate can be adjusted to match the master.

After detecting a Sync Break, the UART waits for the synchronization field. The first falling edge generates an interrupt using the LMEIRIS bit in the **UARTRIS** register, and the timer value is captured and stored in the **UARTLSS** register (T1). On the fifth falling edge, a second interrupt is generated using the LME5RIS bit in the **UARTRIS** register, and the timer value is captured again (T2). The actual baud rate can be calculated using (T2-T1)/8, and the local baud rate should be adjusted as needed. Figure 13-5 on page 699 illustrates the synchronization field.

Figure 13-5. LIN Synchronization Field



### 13.3.8 FIFO Operation

The UART has two 16x8 FIFOs; one for transmit and one for receive. Both FIFOs are accessed via the **UART Data (UARTDR)** register (see page 705). Read operations of the **UARTDR** register return a 12-bit value consisting of 8 data bits and 4 error flags while write operations place 8-bit data in the transmit FIFO.

Out of reset, both FIFOs are disabled and act as 1-byte-deep holding registers. The FIFOs are enabled by setting the FEN bit in **UARTLCRH** (page 716).

FIFO status can be monitored via the **UART Flag (UARTFR)** register (see page 710) and the **UART Receive Status (UARTRSR)** register. Hardware monitors empty, full and overrun conditions. The **UARTFR** register contains empty and full flags (TXFE, TXFF, RXFE, and RXFF bits), and the **UARTRSR** register shows overrun status via the OE bit. If the FIFOs are disabled, the empty and full flags are set according to the status of the 1-byte-deep holding registers.

The trigger points at which the FIFOs generate interrupts is controlled via the **UART Interrupt FIFO Level Select (UARTIFLS)** register (see page 722). Both FIFOs can be individually configured to trigger interrupts at different levels. Available configurations include ½, ¼, ½, ¾, and ¾. For example,

if the ¼ option is selected for the receive FIFO, the UART generates a receive interrupt after 4 data bytes are received. Out of reset, both FIFOs are configured to trigger an interrupt at the ½ mark.

### 13.3.9 Interrupts

The UART can generate interrupts when the following conditions are observed:

- Overrun Error
- Break Error
- Parity Error
- Framing Error
- Receive Timeout
- Transmit (when condition defined in the TXIFLSEL bit in the **UARTIFLS** register is met, or if the EOT bit in **UARTCTL** is set, when the last bit of all transmitted data leaves the serializer)
- Receive (when condition defined in the RXIFLSEL bit in the **UARTIFLS** register is met)

All of the interrupt events are ORed together before being sent to the interrupt controller, so the UART can only generate a single interrupt request to the controller at any given time. Software can service multiple interrupt events in a single interrupt service routine by reading the **UART Masked Interrupt Status (UARTMIS)** register (see page 732).

The interrupt events that can trigger a controller-level interrupt are defined in the **UART Interrupt Mask (UARTIM)** register (see page 724) by setting the corresponding IM bits. If interrupts are not used, the raw interrupt status is always visible via the **UART Raw Interrupt Status (UARTRIS)** register (see page 728).

Interrupts are always cleared (for both the **UARTMIS** and **UARTRIS** registers) by writing a 1 to the corresponding bit in the **UART Interrupt Clear (UARTICR)** register (see page 736).

The receive timeout interrupt is asserted when the receive FIFO is not empty, and no further data is received over a 32-bit period. The receive timeout interrupt is cleared either when the FIFO becomes empty through reading all the data (or by reading the holding register), or when a 1 is written to the corresponding bit in the **UARTICR** register.

The receive interrupt changes state when one of the following events occurs:

- If the FIFOs are enabled and the receive FIFO reaches the programmed trigger level, the RXRIS bit is set. The receive interrupt is cleared by reading data from the receive FIFO until it becomes less than the trigger level, or by clearing the interrupt by writing a 1 to the RXIC bit.
- If the FIFOs are disabled (have a depth of one location) and data is received thereby filling the location, the RXRIS bit is set. The receive interrupt is cleared by performing a single read of the receive FIFO, or by clearing the interrupt by writing a 1 to the RXIC bit.

The transmit interrupt changes state when one of the following events occurs:

■ If the FIFOs are enabled and the transmit FIFO reaches the programmed trigger level, the TXRIS bit is set. The transmit interrupt is cleared by writing data to the transmit FIFO until it becomes greater than the trigger level, or by clearing the interrupt by writing a 1 to the TXIC bit.

■ If the FIFOs are disabled (have a depth of one location) and there is no data present in the transmitters single location, the TXRIS bit is set. It is cleared by performing a single write to the transmit FIFO, or by clearing the interrupt by writing a 1 to the TXIC bit.

### 13.3.10 Loopback Operation

The UART can be placed into an internal loopback mode for diagnostic or debug work by setting the LBE bit in the **UARTCTL** register (see page 718). In loopback mode, data transmitted on the  $\mathtt{UnTx}$  output is received on the  $\mathtt{UnRx}$  input. Note that the LBE bit should be set before the UART is enabled.

### 13.3.11 DMA Operation

The UART provides an interface to the  $\mu$ DMA controller with separate channels for transmit and receive. The DMA operation of the UART is enabled through the **UART DMA Control** (**UARTDMACTL**) register. When DMA operation is enabled, the UART asserts a DMA request on the receive or transmit channel when the associated FIFO can transfer data. For the receive channel, a single transfer request is asserted whenever any data is in the receive FIFO. A burst transfer request is asserted whenever the amount of data in the receive FIFO is at or above the FIFO trigger level configured in the **UARTIFLS** register. For the transmit channel, a single transfer request is asserted whenever there is at least one empty location in the transmit FIFO. The burst request is asserted whenever the transmit FIFO contains fewer characters than the FIFO trigger level. The single and burst DMA transfer requests are handled automatically by the  $\mu$ DMA controller depending on how the DMA channel is configured.

To enable DMA operation for the receive channel, set the RXDMAE bit of the **DMA Control** (**UARTDMACTL**) register. To enable DMA operation for the transmit channel, set the TXDMAE bit of the **UARTDMACTL** register. The UART can also be configured to stop using DMA for the receive channel if a receive error occurs. If the DMAERR bit of the **UARTDMACR** register is set and a receive error occurs, the DMA receive requests are automatically disabled. This error condition can be cleared by clearing the appropriate UART error interrupt.

If DMA is enabled, then the  $\mu$ DMA controller triggers an interrupt when a transfer is complete. The interrupt occurs on the UART interrupt vector. Therefore, if interrupts are used for UART operation and DMA is enabled, the UART interrupt handler must be designed to handle the  $\mu$ DMA completion interrupt.

See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for more details about programming the  $\mu$ DMA controller.

### 13.4 Initialization and Configuration

To enable and initialize the UART, the following steps are necessary:

- 1. The peripheral clock must be enabled by setting the UARTO, UART1, or UART2 bits in the RCGC1 register (see page 272).
- 2. The clock to the appropriate GPIO module must be enabled via the RCGC2 register in the System Control module (see page 284).
- 3. Set the GPIO AFSEL bits for the appropriate pins (see page 430). To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the GPIO current level and/or slew rate as specified for the mode selected (see page 432 and page 440).

**5.** Configure the PMCn fields in the **GPIOPCTL** register to assign the UART signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).

To use the UART, the peripheral clock must be enabled by setting the appropriate bit in the **RCGC1** register (page 272). In addition, the clock to the appropriate GPIO module must be enabled via the **RCGC2** register (page 284) in the System Control module. To find out which GPIO port to enable, refer to Table 24-5 on page 1270.

This section discusses the steps that are required to use a UART module. For this example, the UART clock is assumed to be 20 MHz, and the desired UART configuration is:

- 115200 baud rate
- Data length of 8 bits
- One stop bit
- No parity
- FIFOs disabled
- No interrupts

The first thing to consider when programming the UART is the baud-rate divisor (BRD), because the **UARTIBRD** and **UARTFBRD** registers must be written before the **UARTLCRH** register. Using the equation described in "Baud-Rate Generation" on page 694, the BRD can be calculated:

```
BRD = 20,000,000 / (16 * 115,200) = 10.8507
```

which means that the DIVINT field of the **UARTIBRD** register (see page 714) should be set to 10 decimal or 0xA. The value to be loaded into the **UARTFBRD** register (see page 715) is calculated by the equation:

```
UARTFBRD[DIVFRAC] = integer(0.8507 * 64 + 0.5) = 54
```

With the BRD values in hand, the UART configuration is written to the module in the following order:

- 1. Disable the UART by clearing the UARTEN bit in the **UARTCTL** register.
- 2. Write the integer portion of the BRD to the **UARTIBRD** register.
- 3. Write the fractional portion of the BRD to the **UARTFBRD** register.
- **4.** Write the desired serial parameters to the **UARTLCRH** register (in this case, a value of 0x0000.0060).
- **5.** Optionally, configure the μDMA channel (see "Micro Direct Memory Access (μDMA)" on page 346) and enable the DMA option(s) in the **UARTDMACTL** register.
- **6.** Enable the UART by setting the UARTEN bit in the **UARTCTL** register.

### 13.5 Register Map

Table 13-4 on page 703 lists the UART registers. The offset listed is a hexadecimal increment to the register's address, relative to that UART's base address:

■ UART0: 0x4000.C000

UART1: 0x4000.D000UART2: 0x4000.E000

Note that the UART module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the UART module clock is enabled before any UART module registers are accessed.

**Note:** The UART must be disabled (see the UARTEN bit in the **UARTCTL** register on page 718) before any of the control registers are reprogrammed. When the UART is disabled during a TX or RX operation, the current transaction is completed prior to the UART stopping.

Table 13-4. UART Register Map

Offset	Name	Type	Reset	Description	See page
0x000	UARTDR	R/W	0x0000.0000	UART Data	705
0x004	UARTRSR/UARTECR	R/W	0x0000.0000	UART Receive Status/Error Clear	707
0x018	UARTFR	RO	0x0000.0090	UART Flag	710
0x020	UARTILPR	R/W	0x0000.0000	UART IrDA Low-Power Register	713
0x024	UARTIBRD	R/W	0x0000.0000	UART Integer Baud-Rate Divisor	714
0x028	UARTFBRD	R/W	0x0000.0000	UART Fractional Baud-Rate Divisor	715
0x02C	UARTLCRH	R/W	0x0000.0000	UART Line Control	716
0x030	UARTCTL	R/W	0x0000.0300	UART Control	718
0x034	UARTIFLS	R/W	0x0000.0012	UART Interrupt FIFO Level Select	722
0x038	UARTIM	R/W	0x0000.0000	UART Interrupt Mask	724
0x03C	UARTRIS	RO	0x0000.0000	UART Raw Interrupt Status	728
0x040	UARTMIS	RO	0x0000.0000	UART Masked Interrupt Status	732
0x044	UARTICR	W1C	0x0000.0000	UART Interrupt Clear	736
0x048	UARTDMACTL	R/W	0x0000.0000	UART DMA Control	738
0x090	UARTLCTL	R/W	0x0000.0000	UART LIN Control	739
0x094	UARTLSS	RO	0x0000.0000	UART LIN Snap Shot	740
0x098	UARTLTIM	RO	0x0000.0000	UART LIN Timer	741
0xFD0	UARTPeriphID4	RO	0x0000.0000	UART Peripheral Identification 4	742
0xFD4	UARTPeriphID5	RO	0x0000.0000	UART Peripheral Identification 5	743
0xFD8	UARTPeriphID6	RO	0x0000.0000	UART Peripheral Identification 6	744
0xFDC	UARTPeriphID7	RO	0x0000.0000	UART Peripheral Identification 7	745
0xFE0	UARTPeriphID0	RO	0x0000.0060	UART Peripheral Identification 0	746
0xFE4	UARTPeriphID1	RO	0x0000.0000	UART Peripheral Identification 1	747
0xFE8	UARTPeriphID2	RO	0x0000.0018	UART Peripheral Identification 2	748
0xFEC	UARTPeriphID3	RO	0x0000.0001	UART Peripheral Identification 3	749

### Table 13-4. UART Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0xFF0	UARTPCellID0	RO	0x0000.000D	UART PrimeCell Identification 0	750
0xFF4	UARTPCellID1	RO	0x0000.00F0	UART PrimeCell Identification 1	751
0xFF8	UARTPCellID2	RO	0x0000.0005	UART PrimeCell Identification 2	752
0xFFC	UARTPCellID3	RO	0x0000.00B1	UART PrimeCell Identification 3	753

### 13.6 Register Descriptions

The remainder of this section lists and describes the UART registers, in numerical order by address offset.

### Register 1: UART Data (UARTDR), offset 0x000

**Important:** This register is read-sensitive. See the register description for details.

This register is the data register (the interface to the FIFOs).

For transmitted data, if the FIFO is enabled, data written to this location is pushed onto the transmit FIFO. If the FIFO is disabled, data is stored in the transmitter holding register (the bottom word of the transmit FIFO). A write to this register initiates a transmission from the UART.


For received data, if the FIFO is enabled, the data byte and the 4-bit status (break, frame, parity, and overrun) is pushed onto the 12-bit wide receive FIFO. If the FIFO is disabled, the data byte and status are stored in the receiving holding register (the bottom word of the receive FIFO). The received data can be retrieved by reading this register.

#### UART Data (UARTDR)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	OE	RO	0	UART Overrun Error
				Value Description
				New data was received when the FIFO was full, resulting in data loss.
				0 No data has been lost due to a FIFO overrun.
10	BE	RO	0	UART Break Error

#### Value Description

- A break condition has been detected, indicating that the receive data input was held Low for longer than a full-word transmission time (defined as start, data, parity, and stop bits).
- 0 No break condition has occurred

In FIFO mode, this error is associated with the character at the top of the FIFO. When a break occurs, only one 0 character is loaded into the FIFO. The next character is only enabled after the received data input goes to a 1 (marking state), and the next valid start bit is received.

Bit/Field	Name	Туре	Reset	Description
9	PE	RO	0	UART Parity Error
				Value Description
				The parity of the received data character does not match the parity defined by bits 2 and 7 of the UARTLCRH register.
				0 No parity error has occurred
				In FIFO mode, this error is associated with the character at the top of the FIFO.
8	FE	RO	0	UART Framing Error
				Value Description
				1 The received character does not have a valid stop bit (a valid stop bit is 1).
				0 No framing error has occurred
7.0	DATA	DAM	000	Data Tanana Madaa Basai aad
7:0	DATA	R/W	0x00	Data Transmitted or Received
				Data that is to be transmitted via the UART is written to this field.
				When read, this field contains the data that was received by the UART.

## Register 2: UART Receive Status/Error Clear (UARTRSR/UARTECR), offset 0x004

The **UARTRSR/UARTECR** register is the receive status register/error clear register.

In addition to the **UARTDR** register, receive status can also be read from the **UARTRSR** register. If the status is read from this register, then the status information corresponds to the entry read from **UARTDR** prior to reading **UARTRSR**. The status information for overrun is set immediately when an overrun condition occurs.


The **UARTRSR** register cannot be written.

A write of any value to the **UARTECR** register clears the framing, parity, break, and overrun errors. All the bits are cleared on reset.

### **Read-Only Status Register**

UART Receive Status/Error Clear (UARTRSR/UARTECR)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x004



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	OE	RO	0	UART Overrun Error

Value Description

- New data was received when the FIFO was full, resulting in data loss.
- 0 No data has been lost due to a FIFO overrun.

This bit is cleared by a write to **UARTECR**.

The FIFO contents remain valid because no further data is written when the FIFO is full, only the contents of the shift register are overwritten. The CPU must read the data in order to empty the FIFO.

Bit/Field	Name	Туре	Reset	Description
2	BE	RO	0	UART Break Error
				Value Description
				A break condition has been detected, indicating that the receive data input was held Low for longer than a full-word transmission time (defined as start, data, parity, and stop bits).
				0 No break condition has occurred
				This bit is cleared to 0 by a write to <b>UARTECR</b> .
				In FIFO mode, this error is associated with the character at the top of the FIFO. When a break occurs, only one 0 character is loaded into the FIFO. The next character is only enabled after the receive data input goes to a 1 (marking state) and the next valid start bit is received.
1	PE	RO	0	UART Parity Error
				Value Description
				The parity of the received data character does not match the parity defined by bits 2 and 7 of the <b>UARTLCRH</b> register.
				0 No parity error has occurred
				This bit is cleared to 0 by a write to <b>UARTECR</b> .
0	FE	RO	0	UART Framing Error
				Value Description
				1 The received character does not have a valid stop bit (a valid stop bit is 1).
				0 No framing error has occurred


This bit is cleared to 0 by a write to **UARTECR**.

In FIFO mode, this error is associated with the character at the top of the FIFO.

### Write-Only Error Clear Register

UART Receive Status/Error Clear (UARTRSR/UARTECR)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x004 Type WO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	WO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DATA	WO	0x00	Error Clear  A write to this register of any data clears the framing, parity, break, and overrun flags.

### Register 3: UART Flag (UARTFR), offset 0x018


The **UARTFR** register is the flag register. After reset, the TXFF, RXFF, and BUSY bits are 0, and TXFE and RXFE bits are 1. The RI, DCD, DSR and CTS bits indicate the modem flow control and status. Note that the modem bits are only implemented on UART1 and are reserved on UART0 and UART2.

### **UART Flag (UARTFR)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x018

Type RO, reset 0x0000.0090



Bit/Field	Name	Туре	Reset	Description
31:9	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8	RI	RO	0	Ring Indicator
				Value Description
				1 The ulri signal is asserted.
				0 The ulri signal is not asserted.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
7	TXFE	RO	1	UART Transmit FIFO Empty
				The meaning of this bit depends on the state of the ${\tt FEN}$ bit in the

#### Value Description

**UARTLCRH** register.

- 1 If the FIFO is disabled (FEN is 0), the transmit holding register is empty.
  - If the FIFO is enabled (FEN is 1), the transmit FIFO is empty.
- 0 The transmitter has data to transmit.

Bit/Field	Name	Туре	Reset	Description
6	RXFF	RO	0	UART Receive FIFO Full  The meaning of this bit depends on the state of the FEN bit in the UARTLCRH register.
				Value Description
				1 If the FIFO is disabled (FEN is 0), the receive holding register is full.
				If the FIFO is enabled ( $FEN$ is 1), the receive FIFO is full.
				0 The receiver can receive data.
5	TXFF	RO	0	UART Transmit FIFO Full
				The meaning of this bit depends on the state of the FEN bit in the <b>UARTLCRH</b> register.
				Value Description
				If the FIFO is disabled (FEN is 0), the transmit holding register is full.
				If the FIFO is enabled (FEN is 1), the transmit FIFO is full.
				0 The transmitter is not full.
4	RXFE	RO	1	UART Receive FIFO Empty
				The meaning of this bit depends on the state of the ${\tt FEN}$ bit in the ${\tt UARTLCRH}$ register.
				Value Description
				1 If the FIFO is disabled (FEN is 0), the receive holding register is empty.
				If the FIFO is enabled (FEN is 1), the receive FIFO is empty.
				0 The receiver is not empty.
3	BUSY	RO	0	UART Busy
				Value Description
				The UART is busy transmitting data. This bit remains set until the complete byte, including all stop bits, has been sent from the shift register.
				0 The UART is not busy.
				•
				This bit is set as soon as the transmit FIFO becomes non-empty (regardless of whether UART is enabled).
2	DCD	RO	0	Data Carrier Detect
				Value Description
				1 The U1DCD signal is asserted.
				0 The U1DCD signal is not asserted.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.

Bit/Field	Name	Туре	Reset	Description
1	DSR	RO	0	Data Set Ready
				Value Description
				1 The ulder signal is asserted.
				0 The Ulder signal is not asserted.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
0	CTS	RO	0	Clear To Send
				Value Description
				1 The ulcts signal is asserted.
				0 The U1CTS signal is not asserted.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.

### Register 4: UART IrDA Low-Power Register (UARTILPR), offset 0x020

The **UARTILPR** register stores the 8-bit low-power counter divisor value used to derive the low-power SIR pulse width clock by dividing down the system clock (SysClk). All the bits are cleared when reset.

The internal IrlPBaud16 clock is generated by dividing down SysClk according to the low-power divisor value written to **UARTILPR**. The duration of SIR pulses generated when low-power mode is enabled is three times the period of the IrlPBaud16 clock. The low-power divisor value is calculated as follows:

 $ILPDVSR = SysClk / F_{IrLPBaud16}$ 

where  $F_{IrlPBaud16}$  is nominally 1.8432 MHz.


The divisor must be programmed such that 1.42 MHz <  $F_{\tt IrlPBaud16}$  < 2.12 MHz, resulting in a low-power pulse duration of 1.41–2.11  $\mu s$  (three times the period of  $\tt IrlPBaud16$ ). The minimum frequency of  $\tt IrlPBaud16$  ensures that pulses less than one period of  $\tt IrlPBaud16$  are rejected, but pulses greater than 1.4  $\mu s$  are accepted as valid pulses.

**Note:** Zero is an illegal value. Programming a zero value results in no IrlPBaud16 pulses being generated.

### UART IrDA Low-Power Register (UARTILPR)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x020

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	ILPDVSR	R/W	0x00	IrDA Low-Power Divisor
				This field contains the 8-bit low-power divisor value.

### Register 5: UART Integer Baud-Rate Divisor (UARTIBRD), offset 0x024

The **UARTIBRD** register is the integer part of the baud-rate divisor value. All the bits are cleared on reset. The minimum possible divide ratio is 1 (when **UARTIBRD**=0), in which case the **UARTFBRD** register is ignored. When changing the **UARTIBRD** register, the new value does not take effect until transmission/reception of the current character is complete. Any changes to the baud-rate divisor must be followed by a write to the **UARTLCRH** register. See "Baud-Rate Generation" on page 694 for configuration details.

### UART Integer Baud-Rate Divisor (UARTIBRD)


DIVINT

R/W

0x0000

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

15:0



Integer Baud-Rate Divisor

### Register 6: UART Fractional Baud-Rate Divisor (UARTFBRD), offset 0x028


The **UARTFBRD** register is the fractional part of the baud-rate divisor value. All the bits are cleared on reset. When changing the **UARTFBRD** register, the new value does not take effect until transmission/reception of the current character is complete. Any changes to the baud-rate divisor must be followed by a write to the **UARTLCRH** register. See "Baud-Rate Generation" on page 694 for configuration details.

### UART Fractional Baud-Rate Divisor (UARTFBRD)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x028

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:0	DIVFRAC	R/W	0x0	Fractional Baud-Rate Divisor

### Register 7: UART Line Control (UARTLCRH), offset 0x02C


The **UARTLCRH** register is the line control register. Serial parameters such as data length, parity, and stop bit selection are implemented in this register.

When updating the baud-rate divisor (**UARTIBRD** and/or **UARTIFRD**), the **UARTLCRH** register must also be written. The write strobe for the baud-rate divisor registers is tied to the **UARTLCRH** register.

### **UART Line Control (UARTLCRH)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x02C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	SPS	R/W	0	UART Stick Parity Select
				When bits 1, 2, and 7 of <b>UARTLCRH</b> are set, the parity bit is transmitted and checked as a 0. When bits 1 and 7 are set and 2 is cleared, the parity bit is transmitted and checked as a 1.
				When this bit is cleared, stick parity is disabled.
6:5	WLEN	R/W	0x0	UART Word Length
				The bits indicate the number of data bits transmitted or received in a frame as follows:
				Value Description
				0x0 5 bits (default)
				0x1 6 bits
				0x2 7 bits
				0x3 8 bits
4	FEN	R/W	0	UART Enable FIFOs
				Value Description

### Value Description

- 1 The transmit and receive FIFO buffers are enabled (FIFO mode).
- The FIFOs are disabled (Character mode). The FIFOs become
   1-byte-deep holding registers.

Bit/Field	Name	Туре	Reset	Description
3	STP2	R/W	0	UART Two Stop Bits Select
				Value Description  Two stop bits are transmitted at the end of a frame. The receive
				logic does not check for two stop bits being received.
				When in 7816 smartcard mode (the SMART bit is set in the <b>UARTCTL</b> register), the number of stop bits is forced to 2.
				One stop bit is transmitted at the end of a frame.
2	EPS	R/W	0	UART Even Parity Select
				Value Description
				Even parity generation and checking is performed during transmission and reception, which checks for an even number of 1s in data and parity bits.
				Odd parity is performed, which checks for an odd number of 1s.
				This bit has no effect when parity is disabled by the $\mathtt{PEN}$ bit.
1	PEN	R/W	0	UART Parity Enable
				Value Description
				1 Parity checking and generation is enabled.
				O Parity is disabled and no parity bit is added to the data frame.
0	BRK	R/W	0	UART Send Break
				Value Description
				1 A Low level is continually output on the UnIx signal, after completing transmission of the current character. For the proper execution of the break command, software must set this bit for
				at least two frames (character periods).

### Register 8: UART Control (UARTCTL), offset 0x030

The **UARTCTL** register is the control register. All the bits are cleared on reset except for the Transmit Enable (TXE) and Receive Enable (RXE) bits, which are set.

To enable the UART module, the UARTEN bit must be set. If software requires a configuration change in the module, the UARTEN bit must be cleared before the configuration changes are written. If the UART is disabled during a transmit or receive operation, the current transaction is completed prior to the UART stopping.

Note that bits [15:14,11:10] are only implemented on UART1. These bits are reserved on UART0 and UART2.

**Note:** The **UARTCTL** register should not be changed while the UART is enabled or else the results are unpredictable. The following sequence is recommended for making changes to the **UARTCTL** register.

- 1. Disable the UART.
- 2. Wait for the end of transmission or reception of the current character.
- 3. Flush the transmit FIFO by clearing bit 4 (FEN) in the line control register (UARTLCRH).

compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.


- 4. Reprogram the control register.
- Enable the UART.

### UART Control (UARTCTL)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x030

Type R/W, reset 0x0000.0300



Bit/Field	Name	Туре	Reset	Description
15	CTSEN	R/W	0	Enable Clear To Send
				Value Description
				1 CTS hardware flow control is enabled. Data is only transmitted when the ulcts signal is asserted.
				0 CTS hardware flow control is disabled.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
14	RTSEN	R/W	0	Enable Request to Send
				Value Description
				1 RTS hardware flow control is enabled. Data is only requested (by asserting ulrts) when the receive FIFO has available entries.
				0 RTS hardware flow control is disabled.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
13:12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11	RTS	R/W	0	Request to Send
				When RTSEN is clear, the status of this bit is reflected on the U1RTS signal. If RTSEN is set, this bit is ignored on a write and should be ignored on read.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
10	DTR	R/W	0	Data Terminal Ready
				This bit sets the state of the Uldtr output.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
9	RXE	R/W	1	UART Receive Enable
				Value Description
				1 The receive section of the UART is enabled.
				0 The receive section of the UART is disabled.
				If the UART is disabled in the middle of a receive, it completes the current character before stopping.
				Note: To enable reception, the UARTEN bit must also be set.

October 06, 2012 719

Bit/Field	Name	Type	Reset	Description
8	TXE	R/W	1	UART Transmit Enable
				Value Description
				1 The transmit section of the UART is enabled.
				0 The transmit section of the UART is disabled.
				If the UART is disabled in the middle of a transmission, it completes the current character before stopping.
				<b>Note:</b> To enable transmission, the UARTEN bit must also be set.
7	LBE	R/W	0	UART Loop Back Enable
				Value Description
				1 The UnTx path is fed through the UnRx path.
				0 Normal operation.
6	LIN	R/W	0	LIN Mode Enable
				Value Description
				The UART operates in LIN mode.
				0 Normal operation.
5	HSE	R/W	0	High-Speed Enable
				Value Description
				The UART is clocked using the system clock divided by 16.
				1 The UART is clocked using the system clock divided by 8.
				<b>Note:</b> System clock used is also dependent on the baud-rate divisor configuration (see page 714) and page 715).
				The state of this bit has no effect on clock generation in ISO 7816 smart card mode (the SMART bit is set).
4	EOT	R/W	0	End of Transmission
				This bit determines the behavior of the ${\tt TXRIS}$ bit in the $\textbf{UARTRIS}$ register.
				Value Description
				1 The TXRIS bit is set only after all transmitted data, including stop bits, have cleared the serializer.
				0 The TXRIS bit is set when the transmit FIFO condition specified

in **UARTIFLS** is met.

Bit/Field	Name	Туре	Reset	Description
3	SMART	R/W	0	ISO 7816 Smart Card Support
				Value Description  1 The UART operates in Smart Card mode.  0 Normal operation.  The application must ensure that it sets 8-bit word length (WLEN set to 0x3) and even parity (PEN set to 1, EPS set to 1, SPS set to 0) in UARTLCRH when using ISO 7816 mode.  In this mode, the value of the STP2 bit in UARTLCRH is ignored and the number of stop bits is forced to 2. Note that the UART does not support automatic retransmission on parity errors. If a parity error is detected on transmission, all further transmit operations are aborted and software must handle retransmission of the affected byte or
2	SIRLP	R/W	0	message.  UART SIR Low-Power Mode This bit selects the IrDA encoding mode.  Value Description  1 The UART operates in SIR Low-Power mode. Low-level bits are transmitted with a pulse width which is 3 times the period of the IrLPBaud16 input signal, regardless of the selected bit rate.  0 Low-level bits are transmitted as an active High pulse with a width of 3/16th of the bit period.
				Setting this bit uses less power, but might reduce transmission distances. See page 713 for more information.
1	SIREN	R/W	0	UART SIR Enable  Value Description  1 The IrDA SIR block is enabled, and the UART will transmit and
				receive data using SIR protocol.  Normal operation.
0	UARTEN	R/W	0	UART Enable  Value Description  1 The UART is enabled.
				0 The UART is disabled.

If the UART is disabled in the middle of transmission or reception, it completes the current character before stopping.

### Register 9: UART Interrupt FIFO Level Select (UARTIFLS), offset 0x034

The **UARTIFLS** register is the interrupt FIFO level select register. You can use this register to define the FIFO level at which the TXRIS and RXRIS bits in the **UARTRIS** register are triggered.


The interrupts are generated based on a transition through a level rather than being based on the level. That is, the interrupts are generated when the fill level progresses through the trigger level. For example, if the receive trigger level is set to the half-way mark, the interrupt is triggered as the module is receiving the 9th character.

Out of reset, the TXIFLSEL and RXIFLSEL bits are configured so that the FIFOs trigger an interrupt at the half-way mark.

#### UART Interrupt FIFO Level Select (UARTIFLS)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x034

Type R/W, reset 0x0000.0012



Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:3	RXIFLSEL	R/W	0x2	UART Receive Interrupt FIFO Level Select

The trigger points for the receive interrupt are as follows:

Value	Description
0x0	RX FIFO ≥ 1/8 full
0x1	RX FIFO ≥ ¼ full
0x2	RX FIFO ≥ ½ full (default)
0x3	RX FIFO ≥ ¾ full
0x4	RX FIFO ≥ 7/8 full
0x5-0x7	Reserved

Bit/Field	Name	Type	Reset	Description
2:0	TXIFLSEL	R/W	0x2	UART Transmit Interrupt FIFO Level Select The trigger points for the transmit interrupt are as follows:
				Value Description
				0x0 TX FIFO ≤ % empty
				0x1 TX FIFO ≤ ¾ empty
				0x2 TX FIFO ≤ ½ empty (default)
				0x3 TX FIFO ≤ ¼ empty
				0x4 TX FIFO ≤ 1/8 empty
				0x5-0x7 Reserved
				Note: If the EOT bit in UARTCTL is set (see page 718), the transmi interrupt is generated once the FIFO is completely empty and all data including stop bits have left the transmit serializer. In this case, the setting of TXIFLSEL is ignored.

### Register 10: UART Interrupt Mask (UARTIM), offset 0x038

The **UARTIM** register is the interrupt mask set/clear register.


On a read, this register gives the current value of the mask on the relevant interrupt. Setting a bit allows the corresponding raw interrupt signal to be routed to the interrupt controller. Clearing a bit prevents the raw interrupt signal from being sent to the interrupt controller.

Note that bits [3:0] are only implemented on UART1. These bits are reserved on UART0 and UART2.

#### **UART Interrupt Mask (UARTIM)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x038 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15	LME5IM	R/W	0	LIN Mode Edge 5 Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the LME5RIS bit in the <b>UARTRIS</b> register is set.
				The LMESRIS interrupt is suppressed and not sent to the interrupt controller.
14	LME1IM	R/W	0	LIN Mode Edge 1 Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the LME1RIS bit in the <b>UARTRIS</b> register is set.
				O The LMEIRIS interrupt is suppressed and not sent to the interrupt controller.
13	LMSBIM	R/W	0	LIN Mode Sync Break Interrupt Mask

1

0

Value Description

An interrupt is sent to the interrupt controller when the LMSBRIS

The LMSBRIS interrupt is suppressed and not sent to the

bit in the **UARTRIS** register is set.

interrupt controller.

Bit/Field	Name	Туре	Reset	Description
12:11	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10	OEIM	R/W	0	UART Overrun Error Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the OERIS bit in the <b>UARTRIS</b> register is set.
				O The OERIS interrupt is suppressed and not sent to the interrupt controller.
9	BEIM	R/W	0	UART Break Error Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the BERIS bit in the <b>UARTRIS</b> register is set.
				O The BERIS interrupt is suppressed and not sent to the interrupt controller.
8	PEIM	R/W	0	UART Parity Error Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the PERIS bit in the <b>UARTRIS</b> register is set.
				O The PERIS interrupt is suppressed and not sent to the interrupt controller.
7	FEIM	R/W	0	UART Framing Error Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the FERIS bit in the <b>UARTRIS</b> register is set.
				O The FERIS interrupt is suppressed and not sent to the interrupt controller.
6	RTIM	R/W	0	UART Receive Time-Out Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the RTRIS bit in the <b>UARTRIS</b> register is set.
				O The RTRIS interrupt is suppressed and not sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
5	TXIM	R/W	0	UART Transmit Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the TXRIS bit in the <b>UARTRIS</b> register is set.
				O The TXRIS interrupt is suppressed and not sent to the interrupt controller.
4	RXIM	R/W	0	UART Receive Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the RXRIS bit in the <b>UARTRIS</b> register is set.
				O The RXRIS interrupt is suppressed and not sent to the interrupt controller.
3	DSRIM	R/W	0	UART Data Set Ready Modem Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the DSRRIS bit in the <b>UARTRIS</b> register is set.
				O The DSRRIS interrupt is suppressed and not sent to the interrupt controller.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
2	DCDIM	R/W	0	UART Data Carrier Detect Modem Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the DCDRIS bit in the <b>UARTRIS</b> register is set.
				O The DCDRIS interrupt is suppressed and not sent to the interrupt controller.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
1	CTSIM	R/W	0	UART Clear to Send Modem Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the CTSRIS bit in the <b>UARTRIS</b> register is set.
				O The CTSRIS interrupt is suppressed and not sent to the interrupt controller.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.

Bit/Field	Name	Туре	Reset	Description
0	RIIM	R/W	0	UART Ring Indicator Modem Interrupt Mask
				Value Description
				An interrupt is sent to the interrupt controller when the RIRIS bit in the <b>UARTRIS</b> register is set.
				O The RIRIS interrupt is suppressed and not sent to the interrupt controller.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.

### Register 11: UART Raw Interrupt Status (UARTRIS), offset 0x03C

The **UARTRIS** register is the raw interrupt status register. On a read, this register gives the current raw status value of the corresponding interrupt. A write has no effect.


Note that bits [3:0] are only implemented on UART1. These bits are reserved on UART0 and UART2.

#### **UART Raw Interrupt Status (UARTRIS)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x03C

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
12:11	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10	OERIS	RO	0	UART Overrun Error Raw Interrupt Status
				Value Description  1 An overrun error has occurred.  0 No interrupt
				This bit is cleared by writing a 1 to the OEIC bit in the <b>UARTICR</b> register.
9	BERIS	RO	0	UART Break Error Raw Interrupt Status
				Value Description
				<ul><li>1 A break error has occurred.</li><li>0 No interrupt</li></ul>
				This bit is cleared by writing a 1 to the BEIC bit in the <b>UARTICR</b> register.
8	PERIS	RO	0	UART Parity Error Raw Interrupt Status
				Value Description
				1 A parity error has occurred.
				0 No interrupt
				This bit is cleared by writing a 1 to the ${\tt PEIC}$ bit in the $\textbf{UARTICR}$ register.
7	FERIS	RO	0	UART Framing Error Raw Interrupt Status
				Value Description
				1 A framing error has occurred.
				0 No interrupt
				This bit is cleared by writing a 1 to the FEIC bit in the <b>UARTICR</b> register.
6	RTRIS	RO	0	UART Receive Time-Out Raw Interrupt Status
				Value Description
				1 A receive time out has occurred.
				0 No interrupt
				This bit is cleared by writing a 1 to the RTIC bit in the <b>UARTICR</b> register.

Bit/Field	Name	Туре	Reset	Description
5	TXRIS	RO	0	UART Transmit Raw Interrupt Status
				Value Description
				If the EOT bit in the <b>UARTCTL</b> register is clear, the transmit FIFO level has passed through the condition defined in the <b>UARTIFLS</b> register.
				If the ${\tt EOT}$ bit is set, the last bit of all transmitted data and flags has left the serializer.
				0 No interrupt
				This bit is cleared by writing a 1 to the TXIC bit in the <b>UARTICR</b> register or by writing data to the transmit FIFO until it becomes greater than the trigger level, if the FIFO is enabled, or by writing a single byte if the FIFO is disabled.
4	RXRIS	RO	0	UART Receive Raw Interrupt Status
				Value Description
				The receive FIFO level has passed through the condition defined in the <b>UARTIFLS</b> register.
				0 No interrupt
				This bit is cleared by writing a 1 to the RXIC bit in the <b>UARTICR</b> register or by reading data from the receive FIFO until it becomes less than the trigger level, if the FIFO is enabled, or by reading a single byte if the FIFO is disabled.
3	DSRRIS	RO	0	UART Data Set Ready Modem Raw Interrupt Status
				Value Description
				1 Data Set Ready used for software flow control.
				0 No interrupt
				This bit is cleared by writing a 1 to the DSRIC bit in the <b>UARTICR</b> register.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
2	DCDRIS	RO	0	UART Data Carrier Detect Modem Raw Interrupt Status
				Value Description
				1 Data Carrier Detect used for software flow control.
				0 No interrupt
				This bit is cleared by writing a 1 to the DCDIC bit in the <b>UARTICR</b> register.  This bit is implemented only on UART1 and is reserved for UART0 and UART2.

Bit/Field	Name	Туре	Reset	Description
1	CTSRIS	RO	0	UART Clear to Send Modem Raw Interrupt Status
				Value Description
				1 Clear to Send used for software flow control.
				0 No interrupt
				This bit is cleared by writing a 1 to the CTSIC bit in the <b>UARTICR</b> register.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
0	RIRIS	RO	0	UART Ring Indicator Modem Raw Interrupt Status
				Value Description
				1 Ring Indicator used for software flow control.
				0 No interrupt
				This bit is cleared by writing a 1 to the RIIC bit in the <b>UARTICR</b> register.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.

### Register 12: UART Masked Interrupt Status (UARTMIS), offset 0x040

The **UARTMIS** register is the masked interrupt status register. On a read, this register gives the current masked status value of the corresponding interrupt. A write has no effect.


Note that bits [3:0] are only implemented on UART1. These bits are reserved on UART0 and UART2.

#### **UART Masked Interrupt Status (UARTMIS)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x040

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
12:11	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10	OEMIS	RO	0	UART Overrun Error Masked Interrupt Status
				Value Description  An unmasked interrupt was signaled due to an overrun error.  An interrupt has not occurred or is masked.  This bit is cleared by writing a 1 to the OEIC bit in the UARTICR register.
9	BEMIS	RO	0	UART Break Error Masked Interrupt Status
·	220		•	Value Description  An unmasked interrupt was signaled due to a break error.  An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the BEIC bit in the <b>UARTICR</b> register.
8	PEMIS	RO	0	UART Parity Error Masked Interrupt Status
				Value Description  1 An unmasked interrupt was signaled due to a parity error.  O An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the PEIC bit in the <b>UARTICR</b> register.
7	FEMIS	RO	0	UART Framing Error Masked Interrupt Status  Value Description  1 An unmasked interrupt was signaled due to a framing error.  0 An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the FEIC bit in the <b>UARTICR</b> register.
6	RTMIS	RO	0	Value Description  An unmasked interrupt was signaled due to a receive time out.  An interrupt has not occurred or is masked.  This bit is cleared by writing a 1 to the RTIC bit in the UARTICR register.

Bit/Field	Name	Туре	Reset	Description
5	TXMIS	RO	0	UART Transmit Masked Interrupt Status
				Value Description
				An unmasked interrupt was signaled due to passing through the specified transmit FIFO level (if the EOT bit is clear) or due to the transmission of the last data bit (if the EOT bit is set).
				O An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the TXIC bit in the <b>UARTICR</b> register or by writing data to the transmit FIFO until it becomes greater than the trigger level, if the FIFO is enabled, or by writing a single byte if the FIFO is disabled.
4	RXMIS	RO	0	UART Receive Masked Interrupt Status
				Value Description
				An unmasked interrupt was signaled due to passing through the specified receive FIFO level.
				O An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the RXIC bit in the <b>UARTICR</b> register or by reading data from the receive FIFO until it becomes less than the trigger level, if the FIFO is enabled, or by reading a single byte if the FIFO is disabled.
3	DSRMIS	RO	0	UART Data Set Ready Modem Masked Interrupt Status
				Value Description
				1 An unmasked interrupt was signaled due to Data Set Ready.
				O An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the DSRIC bit in the <b>UARTICR</b> register.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
2	DCDMIS	RO	0	UART Data Carrier Detect Modem Masked Interrupt Status
				Value Description
				1 An unmasked interrupt was signaled due to Data Carrier Detect.
				0 An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the DCDIC bit in the <b>UARTICR</b> register.  This bit is implemented only on UART1 and is reserved for UART0 and UART2.

734 October 06, 2012

Bit/Field	Name	Туре	Reset	Description
1	CTSMIS	RO	0	UART Clear to Send Modem Masked Interrupt Status
				Value Description  1 An unmasked interrupt was signaled due to Clear to Send.  0 An interrupt has not occurred or is masked.  This bit is cleared by writing a 1 to the CTSIC bit in the UARTICR register.
				This bit is implemented only on UART1 and is reserved for UART0 and UART2.
0	RIMIS	RO	0	UART Ring Indicator Modem Masked Interrupt Status  Value Description
				An unmasked interrupt was signaled due to Ring Indicator.
				O An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the RIIC bit in the <b>UARTICR</b> register. This bit is implemented only on UART1 and is reserved for UART0 and UART2.

### Register 13: UART Interrupt Clear (UARTICR), offset 0x044

The **UARTICR** register is the interrupt clear register. On a write of 1, the corresponding interrupt (both raw interrupt and masked interrupt, if enabled) is cleared. A write of 0 has no effect.

Note that bits [3:0] are only implemented on UART1. These bits are reserved on UART0 and UART2.


#### **UART Interrupt Clear (UARTICR)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x044

8

Type W1C, reset 0x0000.0000



10 OEIC W1C 0 Overrun Error Interrupt Clear

Writing a 1 to this bit clears the OERIS bit in the **UARTRIS** register and the OEMIS bit in the **UARTMIS** register.

Writing a 1 to this bit clears the LMSBRIS bit in the **UARTRIS** register

and the LMSBMIS bit in the UARTMIS register.

9 BEIC W1C 0 Break Error Interrupt Clear

Writing a 1 to this bit clears the  ${\tt BERIS}$  bit in the <code>UARTRIS</code> register and the  ${\tt BEMIS}$  bit in the <code>UARTMIS</code> register.

PEIC W1C 0 Parity Error Interrupt Clear

Writing a 1 to this bit clears the PERIS bit in the **UARTRIS** register and the PEMIS bit in the **UARTMIS** register.

Bit/Field	Name	Туре	Reset	Description
7	FEIC	W1C	0	Framing Error Interrupt Clear  Writing a 1 to this bit clears the FERIS bit in the UARTRIS register and the FEMIS bit in the UARTMIS register.
6	RTIC	W1C	0	Receive Time-Out Interrupt Clear  Writing a 1 to this bit clears the RTRIS bit in the UARTRIS register and the RTMIS bit in the UARTMIS register.
5	TXIC	W1C	0	Transmit Interrupt Clear  Writing a 1 to this bit clears the TXRIS bit in the UARTRIS register and the TXMIS bit in the UARTMIS register.
4	RXIC	W1C	0	Receive Interrupt Clear  Writing a 1 to this bit clears the RXRIS bit in the UARTRIS register and the RXMIS bit in the UARTMIS register.
3	DSRMIC	W1C	0	UART Data Set Ready Modem Interrupt Clear Writing a 1 to this bit clears the DSRRIS bit in the <b>UARTRIS</b> register and the DSRMIS bit in the <b>UARTMIS</b> register. This bit is implemented only on UART1 and is reserved for UART0 and UART2.
2	DCDMIC	W1C	0	UART Data Carrier Detect Modem Interrupt Clear Writing a 1 to this bit clears the DCDRIS bit in the <b>UARTRIS</b> register and the DCDMIS bit in the <b>UARTMIS</b> register. This bit is implemented only on UART1 and is reserved for UART0 and UART2.
1	CTSMIC	W1C	0	UART Clear to Send Modem Interrupt Clear Writing a 1 to this bit clears the CTSRIS bit in the UARTRIS register and the CTSMIS bit in the UARTMIS register. This bit is implemented only on UART1 and is reserved for UART0 and UART2.
0	RIMIC	W1C	0	UART Ring Indicator Modem Interrupt Clear Writing a 1 to this bit clears the RIRIS bit in the <b>UARTRIS</b> register and the RIMIS bit in the <b>UARTMIS</b> register. This bit is implemented only on UART1 and is reserved for UART0 and UART2.

## Register 14: UART DMA Control (UARTDMACTL), offset 0x048

The **UARTDMACTL** register is the DMA control register.

#### UART DMA Control (UARTDMACTL)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000


Offset 0x048

0

**RXDMAE** 

R/W

Type R/W, reset 0x0000.0000



#### Value Description

Receive DMA Enable

- 1 μDMA for the receive FIFO is enabled.
- 0 μDMA for the receive FIFO is disabled.

### Register 15: UART LIN Control (UARTLCTL), offset 0x090


The **UARTLCTL** register is the configures the operation of the UART when in LIN mode.

#### **UART LIN Control (UARTLCTL)**

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x090

Type R/W, reset 0x0000.0000



Value Description

0x3 Sync break length is 16T bits

0x2 Sync break length is 15T bits Sync break length is 14T bits 0x1

0x0 Sync break length is 13T bits (default)

3:1 RO 0x0 Software should not rely on the value of a reserved bit. To provide reserved compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

0 **MASTER** R/W 0 LIN Master Enable

Value Description

1 The UART operates as a LIN master.


0 The UART operates as a LIN slave.


# Register 16: UART LIN Snap Shot (UARTLSS), offset 0x094

The **UARTLSS** register captures the free-running timer value when either the Sync Edge 1 or the Sync Edge 5 is detected in LIN mode.

#### UART LIN Snap Shot (UARTLSS)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0x094 Type RO, reset 0x0000.0000





Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	TSS	RO	0x0000	Timer Snap Shot

This field contains the value of the free-running timer when either the Sync Edge 5 or the Sync Edge 1 was detected.

20

19

16


### Register 17: UART LIN Timer (UARTLTIM), offset 0x098

The **UARTLTIM** register contains the current timer value for the free-running timer that is used to calculate the baud rate when in LIN slave mode. The value in this register is used along with the value in the UART LIN Snap Shot (UARTLSS) register to adjust the baud rate to match that of the master.

#### UART LIN Timer (UARTLTIM)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000

Offset 0x098 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	TIMER	RO	0x0000	Timer Value


This field contains the value of the free-running timer.

### Register 18: UART Peripheral Identification 4 (UARTPeriphID4), offset 0xFD0

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 4 (UARTPeriphID4)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFD0 Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID4	RO	0x00	UART Peripheral ID Register [7:0]
				Can be used by software to identify the presence of this peripheral.

# Register 19: UART Peripheral Identification 5 (UARTPeriphID5), offset 0xFD4

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 5 (UARTPeriphID5)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFD4 Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID5	RO	0x00	UART Peripheral ID Register [15:8]
				Can be used by software to identify the presence of this peripheral.

### Register 20: UART Peripheral Identification 6 (UARTPeriphID6), offset 0xFD8

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 6 (UARTPeriphID6)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFD8 Type RO, reset 0x0000.0000




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID6	RO	0x00	UART Peripheral ID Register [23:16]
				Can be used by software to identify the presence of this peripheral.

### Register 21: UART Peripheral Identification 7 (UARTPeriphID7), offset 0xFDC

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 7 (UARTPeriphID7)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFDC Type RO, reset 0x0000.0000




Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID7	RO	0x00	UART Peripheral ID Register [31:24]
				Can be used by software to identify the presence of this peripheral.

# Register 22: UART Peripheral Identification 0 (UARTPeriphID0), offset 0xFE0

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 0 (UARTPeriphID0)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFE0 Type RO, reset 0x0000.0060




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID0	RO	0x60	UART Peripheral ID Register [7:0]
				Can be used by software to identify the presence of this peripheral.

### Register 23: UART Peripheral Identification 1 (UARTPeriphID1), offset 0xFE4

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 1 (UARTPeriphID1)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFE4 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID1	RO	0x00	UART Peripheral ID Register [15:8]
				Can be used by software to identify the presence of this peripheral.


# Register 24: UART Peripheral Identification 2 (UARTPeriphID2), offset 0xFE8

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 2 (UARTPeriphID2)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFE8

Offset 0xFE8
Type RO, reset 0x0000.0018




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID2	RO	0x18	UART Peripheral ID Register [23:16]
	22		57.10	Can be used by software to identify the presence of the

# Register 25: UART Peripheral Identification 3 (UARTPeriphID3), offset 0xFEC

The **UARTPeriphIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART Peripheral Identification 3 (UARTPeriphID3)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFEC Type RO, reset 0x0000.0001




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID3	RO	0x01	UART Peripheral ID Register [31:24]  Can be used by software to identify the presence of this peripheral.

# Register 26: UART PrimeCell Identification 0 (UARTPCellID0), offset 0xFF0

The **UARTPCellIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART PrimeCell Identification 0 (UARTPCellID0)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFF0 Type RO, reset 0x0000.000D



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID0	RO	0x0D	UART PrimeCell ID Register [7:0] Provides software a standard cross-peripheral identification system.


# Register 27: UART PrimeCell Identification 1 (UARTPCellID1), offset 0xFF4

The **UARTPCellIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART PrimeCell Identification 1 (UARTPCellID1)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFF4

Type RO, reset 0x0000.00F0




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID1	RO	0xF0	UART PrimeCell ID Register [15:8]
				Provides software a standard cross-peripheral identification system.

# Register 28: UART PrimeCell Identification 2 (UARTPCellID2), offset 0xFF8

The **UARTPCellIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART PrimeCell Identification 2 (UARTPCellID2)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFF8 Type RO, reset 0x0000.0005




Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID2	RO	0x05	UART PrimeCell ID Register [23:16] Provides software a standard cross-peripheral identification system.

# Register 29: UART PrimeCell Identification 3 (UARTPCellID3), offset 0xFFC

The **UARTPCellIDn** registers are hard-coded and the fields within the registers determine the reset values.

UART PrimeCell Identification 3 (UARTPCellID3)

UART0 base: 0x4000.C000 UART1 base: 0x4000.D000 UART2 base: 0x4000.E000 Offset 0xFFC Type RO, reset 0x0000.00B1



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID3	RO	0xB1	UART PrimeCell ID Register [31:24]
				Provides software a standard cross-peripheral identification system.

# 14 Synchronous Serial Interface (SSI)


The Stellaris<sup>®</sup> microcontroller includes two Synchronous Serial Interface (SSI) modules. Each SSI is a master or slave interface for synchronous serial communication with peripheral devices that have either Freescale SPI, MICROWIRE, or Texas Instruments synchronous serial interfaces.

The Stellaris LM3S9D96 controller includes two SSI modules with the following features:

- Programmable interface operation for Freescale SPI, MICROWIRE, or Texas Instruments synchronous serial interfaces
- Master or slave operation
- Programmable clock bit rate and prescaler
- Separate transmit and receive FIFOs, each 16 bits wide and 8 locations deep
- Programmable data frame size from 4 to 16 bits
- Internal loopback test mode for diagnostic/debug testing
- Standard FIFO-based interrupts and End-of-Transmission interrupt
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Receive single request asserted when data is in the FIFO; burst request asserted when FIFO contains 4 entries
  - Transmit single request asserted when there is space in the FIFO; burst request asserted when FIFO contains 4 entries

# 14.1 Block Diagram

Figure 14-1. SSI Module Block Diagram



# 14.2 Signal Description

The following table lists the external signals of the SSI module and describes the function of each. The SSI signals are alternate functions for some GPIO signals and default to be GPIO signals at reset., with the exception of the SSIOClk, SSIOFss, SSIORx, and SSIOTx pins which default to the SSI function. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for the SSI signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the SSI function. The number in

parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control** (**GPIOPCTL**) register (page 448) to assign the SSI signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 14-1. SSI Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SSI0Clk	28	PA2 (1)	I/O	TTL	SSI module 0 clock
SSI0Fss	29	PA3 (1)	I/O	TTL	SSI module 0 frame signal
SSIORx	30	PA4 (1)	I	TTL	SSI module 0 receive
SSIOTx	31	PA5 (1)	0	TTL	SSI module 0 transmit
SSI1Clk	60 74 76	PF2 (9) PE0 (2) PH4 (11)	I/O	TTL	SSI module 1 clock.
SSI1Fss	59 63 75	PF3 (9) PH5 (11) PE1 (2)	I/O	TTL	SSI module 1 frame signal.
SSI1Rx	42 62 95	PF4 (9) PH6 (11) PE2 (2)	I	TTL	SSI module 1 receive.
SSI1Tx	15 41 96	PH7 (11) PF5 (9) PE3 (2)	0	TTL	SSI module 1 transmit.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 14-2. SSI Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SSI0Clk	M4	PA2 (1)	I/O	TTL	SSI module 0 clock
SSI0Fss	L4	PA3 (1)	I/O	TTL	SSI module 0 frame signal
SSIORx	L5	PA4 (1)	1	TTL	SSI module 0 receive
SSIOTx	M5	PA5 (1)	0	TTL	SSI module 0 transmit
SSI1Clk	J11 B11 B10	PF2 (9) PE0 (2) PH4 (11)	I/O	TTL	SSI module 1 clock.
SSI1Fss	J12 F10 A12	PF3 (9) PH5 (11) PE1 (2)	I/O	TTL	SSI module 1 frame signal.
SSI1Rx	K4 G3 A4	PF4 (9) PH6 (11) PE2 (2)	I	TTL	SSI module 1 receive.
SSI1Tx	H3 K3 B4	PH7 (11) PF5 (9) PE3 (2)	0	TTL	SSI module 1 transmit.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 14.3 Functional Description

The SSI performs serial-to-parallel conversion on data received from a peripheral device. The CPU accesses data, control, and status information. The transmit and receive paths are buffered with internal FIFO memories allowing up to eight 16-bit values to be stored independently in both transmit

and receive modes. The SSI also supports the  $\mu$ DMA interface. The transmit and receive FIFOs can be programmed as destination/source addresses in the  $\mu$ DMA module.  $\mu$ DMA operation is enabled by setting the appropriate bit(s) in the **SSIDMACTL** register (see page 783).

#### 14.3.1 Bit Rate Generation

The SSI includes a programmable bit rate clock divider and prescaler to generate the serial output clock. Bit rates are supported to 2 MHz and higher, although maximum bit rate is determined by peripheral devices.

The serial bit rate is derived by dividing down the input clock (SysClk). The clock is first divided by an even prescale value CPSDVSR from 2 to 254, which is programmed in the **SSI Clock Prescale** (**SSICPSR**) register (see page 776). The clock is further divided by a value from 1 to 256, which is 1 + SCR, where SCR is the value programmed in the **SSI Control 0** (**SSICR0**) register (see page 769).

The frequency of the output clock SSIClk is defined by:

```
SSIClk = SysClk / (CPSDVSR * (1 + SCR))
```

**Note:** For master mode, the system clock must be at least two times faster than the SSIClk, with the restriction that SSIClk cannot be faster than 25 MHz. For slave mode, the system clock must be at least 12 times faster than the SSIClk.

See "Synchronous Serial Interface (SSI)" on page 1333 to view SSI timing parameters.

### 14.3.2 FIFO Operation

#### 14.3.2.1 Transmit FIFO

The common transmit FIFO is a 16-bit wide, 8-locations deep, first-in, first-out memory buffer. The CPU writes data to the FIFO by writing the **SSI Data (SSIDR)** register (see page 773), and data is stored in the FIFO until it is read out by the transmission logic.

When configured as a master or a slave, parallel data is written into the transmit FIFO prior to serial conversion and transmission to the attached slave or master, respectively, through the SSITX pin.

In slave mode, the SSI transmits data each time the master initiates a transaction. If the transmit FIFO is empty and the master initiates, the slave transmits the 8th most recent value in the transmit FIFO. If less than 8 values have been written to the transmit FIFO since the SSI module clock was enabled using the SSI bit in the **RGCG1** register, then 0 is transmitted. Care should be taken to ensure that valid data is in the FIFO as needed. The SSI can be configured to generate an interrupt or a  $\mu$ DMA request when the FIFO is empty.

### 14.3.2.2 Receive FIFO

The common receive FIFO is a 16-bit wide, 8-locations deep, first-in, first-out memory buffer. Received data from the serial interface is stored in the buffer until read out by the CPU, which accesses the read FIFO by reading the **SSIDR** register.

When configured as a master or slave, serial data received through the SSIRx pin is registered prior to parallel loading into the attached slave or master receive FIFO, respectively.

### 14.3.3 Interrupts

The SSI can generate interrupts when the following conditions are observed:

- Transmit FIFO service (when the transmit FIFO is half full or less)
- Receive FIFO service (when the receive FIFO is half full or more)

- Receive FIFO time-out
- Receive FIFO overrun
- End of transmission

All of the interrupt events are ORed together before being sent to the interrupt controller, so the SSI generates a single interrupt request to the controller regardless of the number of active interrupts. Each of the four individual maskable interrupts can be masked by clearing the appropriate bit in the **SSI Interrupt Mask (SSIIM)** register (see page 777). Setting the appropriate mask bit enables the interrupt.

The individual outputs, along with a combined interrupt output, allow use of either a global interrupt service routine or modular device drivers to handle interrupts. The transmit and receive dynamic dataflow interrupts have been separated from the status interrupts so that data can be read or written in response to the FIFO trigger levels. The status of the individual interrupt sources can be read from the SSI Raw Interrupt Status (SSIRIS) and SSI Masked Interrupt Status (SSIMIS) registers (see page 778 and page 780, respectively).

The receive FIFO has a time-out period that is 32 periods at the rate of SSIClk (whether or not SSIClk is currently active) and is started when the RX FIFO goes from EMPTY to not-EMPTY. If the RX FIFO is emptied before 32 clocks have passed, the time-out period is reset. As a result, the ISR should clear the Receive FIFO Time-out Interrupt just after reading out the RX FIFO by writing a 1 to the RTIC bit in the SSI Interrupt Clear (SSIICR) register. The interrupt should not be cleared so late that the ISR returns before the interrupt is actually cleared, or the ISR may be re-activated unnecessarily.

The End-of-Transmission (EOT) interrupt indicates that the data has been transmitted completely. This interrupt can be used to indicate when it is safe to turn off the SSI module clock or enter sleep mode. In addition, because transmitted data and received data complete at exactly the same time, the interrupt can also indicate that read data is ready immediately, without waiting for the receive FIFO time-out period to complete.

### 14.3.4 Frame Formats

Each data frame is between 4 and 16 bits long, depending on the size of data programmed, and is transmitted starting with the MSB. There are three basic frame types that can be selected:

- Texas Instruments synchronous serial
- Freescale SPI
- MICROWIRE

For all three formats, the serial clock (SSIClk) is held inactive while the SSI is idle, and SSIClk transitions at the programmed frequency only during active transmission or reception of data. The idle state of SSIClk is utilized to provide a receive timeout indication that occurs when the receive FIFO still contains data after a timeout period.

For Freescale SPI and MICROWIRE frame formats, the serial frame (SSIFss) pin is active Low, and is asserted (pulled down) during the entire transmission of the frame.

For Texas Instruments synchronous serial frame format, the SSIFss pin is pulsed for one serial clock period starting at its rising edge, prior to the transmission of each frame. For this frame format, both the SSI and the off-chip slave device drive their output data on the rising edge of SSIClk and latch data from the other device on the falling edge.

Unlike the full-duplex transmission of the other two frame formats, the MICROWIRE format uses a special master-slave messaging technique which operates at half-duplex. In this mode, when a frame begins, an 8-bit control message is transmitted to the off-chip slave. During this transmit, no incoming data is received by the SSI. After the message has been sent, the off-chip slave decodes it and, after waiting one serial clock after the last bit of the 8-bit control message has been sent, responds with the requested data. The returned data can be 4 to 16 bits in length, making the total frame length anywhere from 13 to 25 bits.

#### 14.3.4.1 Texas Instruments Synchronous Serial Frame Format

Figure 14-2 on page 759 shows the Texas Instruments synchronous serial frame format for a single transmitted frame.





Figure 14-2. TI Synchronous Serial Frame Format (Single Transfer)

In this mode, SSIClk and SSIFSS are forced Low, and the transmit data line SSITx is tristated whenever the SSI is idle. Once the bottom entry of the transmit FIFO contains data, SSIFSS is pulsed High for one SSIClk period. The value to be transmitted is also transferred from the transmit FIFO to the serial shift register of the transmit logic. On the next rising edge of SSIClk, the MSB of the 4 to 16-bit data frame is shifted out on the SSITx pin. Likewise, the MSB of the received data is shifted onto the SSIRx pin by the off-chip serial slave device.

Both the SSI and the off-chip serial slave device then clock each data bit into their serial shifter on each falling edge of SSIClk. The received data is transferred from the serial shifter to the receive FIFO on the first rising edge of SSIClk after the LSB has been latched.

Figure 14-3 on page 759 shows the Texas Instruments synchronous serial frame format when back-to-back frames are transmitted.





#### 14.3.4.2 Freescale SPI Frame Format

The Freescale SPI interface is a four-wire interface where the SSIFss signal behaves as a slave select. The main feature of the Freescale SPI format is that the inactive state and phase of the SSIClk signal are programmable through the SPO and SPH bits in the **SSISCRO** control register.

#### SPO Clock Polarity Bit

When the SPO clock polarity control bit is clear, it produces a steady state Low value on the SSIClk pin. If the SPO bit is set, a steady state High value is placed on the SSIClk pin when data is not being transferred.

#### SPH Phase Control Bit

The SPH phase control bit selects the clock edge that captures data and allows it to change state. The state of this bit has the most impact on the first bit transmitted by either allowing or not allowing a clock transition before the first data capture edge. When the SPH phase control bit is clear, data is captured on the first clock edge transition. If the SPH bit is set, data is captured on the second clock edge transition.

#### 14.3.4.3 Freescale SPI Frame Format with SPO=0 and SPH=0

Single and continuous transmission signal sequences for Freescale SPI format with SPO=0 and SPH=0 are shown in Figure 14-4 on page 760 and Figure 14-5 on page 760.

Figure 14-4. Freescale SPI Format (Single Transfer) with SPO=0 and SPH=0





Figure 14-5. Freescale SPI Format (Continuous Transfer) with SPO=0 and SPH=0



In this configuration, during idle periods:

■ SSIClk is forced Low

- SSIFss is forced High
- The transmit data line SSITx is arbitrarily forced Low
- When the SSI is configured as a master, it enables the SSIClk pad
- When the SSI is configured as a slave, it disables the SSIClk pad

If the SSI is enabled and valid data is in the transmit FIFO, the start of transmission is signified by the SSIFss master signal being driven Low, causing slave data to be enabled onto the SSIRx input line of the master. The master SSITx output pad is enabled.

One half SSIClk period later, valid master data is transferred to the SSITx pin. Once both the master and slave data have been set, the SSIClk master clock pin goes High after one additional half SSIClk period.

The data is now captured on the rising and propagated on the falling edges of the SSIClk signal.


In the case of a single word transmission, after all bits of the data word have been transferred, the SSIFss line is returned to its idle High state one SSIClk period after the last bit has been captured.

However, in the case of continuous back-to-back transmissions, the SSIFss signal must be pulsed High between each data word transfer because the slave select pin freezes the data in its serial peripheral register and does not allow it to be altered if the SPH bit is clear. Therefore, the master device must raise the SSIFss pin of the slave device between each data transfer to enable the serial peripheral data write. On completion of the continuous transfer, the SSIFss pin is returned to its idle state one SSIClk period after the last bit has been captured.

#### 14.3.4.4 Freescale SPI Frame Format with SPO=0 and SPH=1

The transfer signal sequence for Freescale SPI format with SPO=0 and SPH=1 is shown in Figure 14-6 on page 761, which covers both single and continuous transfers.

Figure 14-6. Freescale SPI Frame Format with SPO=0 and SPH=1



In this configuration, during idle periods:

- SSIC1k is forced Low
- SSIFss is forced High
- The transmit data line SSITx is arbitrarily forced Low
- When the SSI is configured as a master, it enables the SSIClk pad

■ When the SSI is configured as a slave, it disables the SSIClk pad

If the SSI is enabled and valid data is in the transmit FIFO, the start of transmission is signified by the SSIFss master signal being driven Low. The master SSITx output is enabled. After an additional one-half SSIC1k period, both master and slave valid data are enabled onto their respective transmission lines. At the same time, the SSIC1k is enabled with a rising edge transition.

Data is then captured on the falling edges and propagated on the rising edges of the SSIC1k signal.

In the case of a single word transfer, after all bits have been transferred, the SSIFss line is returned to its idle High state one SSIClk period after the last bit has been captured.

For continuous back-to-back transfers, the SSIFss pin is held Low between successive data words, and termination is the same as that of the single word transfer.

#### 14.3.4.5 Freescale SPI Frame Format with SPO=1 and SPH=0

Single and continuous transmission signal sequences for Freescale SPI format with SPO=1 and SPH=0 are shown in Figure 14-7 on page 762 and Figure 14-8 on page 762.

Figure 14-7. Freescale SPI Frame Format (Single Transfer) with SPO=1 and SPH=0





Figure 14-8. Freescale SPI Frame Format (Continuous Transfer) with SPO=1 and SPH=0



In this configuration, during idle periods:

- SSIClk is forced High
- SSIFss is forced High
- The transmit data line SSITx is arbitrarily forced Low
- When the SSI is configured as a master, it enables the SSIClk pad
- When the SSI is configured as a slave, it disables the SSIClk pad

If the SSI is enabled and valid data is in the transmit FIFO, the start of transmission is signified by the SSIFss master signal being driven Low, causing slave data to be immediately transferred onto the SSIRx line of the master. The master SSITx output pad is enabled.

One-half period later, valid master data is transferred to the SSITx line. Once both the master and slave data have been set, the SSIClk master clock pin becomes Low after one additional half SSIClk period, meaning that data is captured on the falling edges and propagated on the rising edges of the SSIClk signal.

In the case of a single word transmission, after all bits of the data word are transferred, the SSIFss line is returned to its idle High state one SSIClk period after the last bit has been captured.

However, in the case of continuous back-to-back transmissions, the SSIFss signal must be pulsed High between each data word transfer because the slave select pin freezes the data in its serial peripheral register and does not allow it to be altered if the SPH bit is clear. Therefore, the master device must raise the SSIFss pin of the slave device between each data transfer to enable the serial peripheral data write. On completion of the continuous transfer, the SSIFss pin is returned to its idle state one SSIClk period after the last bit has been captured.

#### 14.3.4.6 Freescale SPI Frame Format with SPO=1 and SPH=1

The transfer signal sequence for Freescale SPI format with SPO=1 and SPH=1 is shown in Figure 14-9 on page 763, which covers both single and continuous transfers.




Figure 14-9. Freescale SPI Frame Format with SPO=1 and SPH=1

In this configuration, during idle periods:

■ SSIC1k is forced High

Note:

- SSIFss is forced High
- The transmit data line SSITx is arbitrarily forced Low

Q is undefined.

- When the SSI is configured as a master, it enables the SSIClk pad
- When the SSI is configured as a slave, it disables the SSIClk pad

If the SSI is enabled and valid data is in the transmit FIFO, the start of transmission is signified by the SSIFss master signal being driven Low. The master SSITx output pad is enabled. After an additional one-half SSIClk period, both master and slave data are enabled onto their respective transmission lines. At the same time, SSIClk is enabled with a falling edge transition. Data is then captured on the rising edges and propagated on the falling edges of the SSIClk signal.

After all bits have been transferred, in the case of a single word transmission, the SSIFss line is returned to its idle high state one SSIClk period after the last bit has been captured.


For continuous back-to-back transmissions, the SSIFss pin remains in its active Low state until the final bit of the last word has been captured and then returns to its idle state as described above.

For continuous back-to-back transfers, the SSIFss pin is held Low between successive data words and termination is the same as that of the single word transfer.

#### 14.3.4.7 MICROWIRE Frame Format

Figure 14-10 on page 764 shows the MICROWIRE frame format for a single frame. Figure 14-11 on page 765 shows the same format when back-to-back frames are transmitted.

Figure 14-10. MICROWIRE Frame Format (Single Frame)



MICROWIRE format is very similar to SPI format, except that transmission is half-duplex instead of full-duplex and uses a master-slave message passing technique. Each serial transmission begins with an 8-bit control word that is transmitted from the SSI to the off-chip slave device. During this transmission, no incoming data is received by the SSI. After the message has been sent, the off-chip slave decodes it and, after waiting one serial clock after the last bit of the 8-bit control message has been sent, responds with the required data. The returned data is 4 to 16 bits in length, making the total frame length anywhere from 13 to 25 bits.

In this configuration, during idle periods:

- SSIC1k is forced Low
- SSIFss is forced High
- The transmit data line SSITx is arbitrarily forced Low

A transmission is triggered by writing a control byte to the transmit FIFO. The falling edge of SSIFss causes the value contained in the bottom entry of the transmit FIFO to be transferred to the serial shift register of the transmit logic and the MSB of the 8-bit control frame to be shifted out onto the SSITx pin. SSIFss remains Low for the duration of the frame transmission. The SSIRx pin remains tristated during this transmission.

The off-chip serial slave device latches each control bit into its serial shifter on each rising edge of <code>SSIClk</code>. After the last bit is latched by the slave device, the control byte is decoded during a one clock wait-state, and the slave responds by transmitting data back to the SSI. Each bit is driven onto the <code>SSIRx</code> line on the falling edge of <code>SSIClk</code>. The SSI in turn latches each bit on the rising edge of <code>SSIClk</code>. At the end of the frame, for single transfers, the <code>SSIFss</code> signal is pulled High one clock period after the last bit has been latched in the receive serial shifter, causing the data to be transferred to the receive FIFO.

**Note:** The off-chip slave device can tristate the receive line either on the falling edge of SSIC1k after the LSB has been latched by the receive shifter or when the SSIFss pin goes High.

For continuous transfers, data transmission begins and ends in the same manner as a single transfer. However, the SSIFSS line is continuously asserted (held Low) and transmission of data occurs back-to-back. The control byte of the next frame follows directly after the LSB of the received data from the current frame. Each of the received values is transferred from the receive shifter on the falling edge of SSIClk, after the LSB of the frame has been latched into the SSI.




Figure 14-11. MICROWIRE Frame Format (Continuous Transfer)

In the MICROWIRE mode, the SSI slave samples the first bit of receive data on the rising edge of SSIClk after SSIFss has gone Low. Masters that drive a free-running SSIClk must ensure that the SSIFss signal has sufficient setup and hold margins with respect to the rising edge of SSIClk.

Figure 14-12 on page 765 illustrates these setup and hold time requirements. With respect to the SSIClk rising edge on which the first bit of receive data is to be sampled by the SSI slave, SSIFss must have a setup of at least two times the period of SSIClk on which the SSI operates. With respect to the SSIClk rising edge previous to this edge, SSIFss must have a hold of at least one SSIClk period.




Figure 14-12. MICROWIRE Frame Format, SSIFss Input Setup and Hold Requirements

### 14.3.5 DMA Operation

The SSI peripheral provides an interface to the  $\mu$ DMA controller with separate channels for transmit and receive. The  $\mu$ DMA operation of the SSI is enabled through the **SSI DMA Control (SSIDMACTL)** register. When  $\mu$ DMA operation is enabled, the SSI asserts a  $\mu$ DMA request on the receive or transmit channel when the associated FIFO can transfer data. For the receive channel, a single transfer request is asserted whenever any data is in the receive FIFO. A burst transfer request is asserted whenever the amount of data in the receive FIFO is 4 or more items. For the transmit channel, a single transfer request is asserted whenever at least one empty location is in the transmit

FIFO. The burst request is asserted whenever the transmit FIFO has 4 or more empty slots. The single and burst  $\mu$ DMA transfer requests are handled automatically by the  $\mu$ DMA controller depending how the  $\mu$ DMA channel is configured. To enable  $\mu$ DMA operation for the receive channel, the RXDMAE bit of the **DMA Control (SSIDMACTL)** register should be set. To enable  $\mu$ DMA operation for the transmit channel, the TXDMAE bit of **SSIDMACTL** should be set. If  $\mu$ DMA is enabled, then the  $\mu$ DMA controller triggers an interrupt when a transfer is complete. The interrupt occurs on the SSI interrupt vector. Therefore, if interrupts are used for SSI operation and  $\mu$ DMA is enabled, the SSI interrupt handler must be designed to handle the  $\mu$ DMA completion interrupt.

See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for more details about programming the  $\mu$ DMA controller.

## 14.4 Initialization and Configuration

To enable and initialize the SSI, the following steps are necessary:

- 1. Enable the SSI module by setting the SSI bit in the RCGC1 register (see page 272).
- **2.** Enable the clock to the appropriate GPIO module via the **RCGC2** register (see page 284). To find out which GPIO port to enable, refer to Table 24-5 on page 1270.
- 3. Set the GPIO AFSEL bits for the appropriate pins (see page 430). To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the PMCn fields in the **GPIOPCTL** register to assign the SSI signals to the appropriate pins. See page 448 and Table 24-5 on page 1270.

For each of the frame formats, the SSI is configured using the following steps:

- 1. Ensure that the SSE bit in the **SSICR1** register is clear before making any configuration changes.
- 2. Select whether the SSI is a master or slave:
  - **a.** For master operations, set the **SSICR1** register to 0x0000.0000.
  - **b.** For slave mode (output enabled), set the **SSICR1** register to 0x0000.0004.
  - c. For slave mode (output disabled), set the **SSICR1** register to 0x0000.000C.
- 3. Configure the clock prescale divisor by writing the **SSICPSR** register.
- **4.** Write the **SSICR0** register with the following configuration:
  - Serial clock rate (SCR)
  - Desired clock phase/polarity, if using Freescale SPI mode (SPH and SPO)
  - The protocol mode: Freescale SPI, TI SSF, MICROWIRE (FRF)
  - The data size (DSS)
- **5.** Optionally, configure the μDMA channel (see "Micro Direct Memory Access (μDMA)" on page 346) and enable the DMA option(s) in the **SSIDMACTL** register.
- **6.** Enable the SSI by setting the SSE bit in the **SSICR1** register.

As an example, assume the SSI must be configured to operate with the following parameters:

- Master operation
- Freescale SPI mode (SPO=1, SPH=1)
- 1 Mbps bit rate
- 8 data bits

Assuming the system clock is 20 MHz, the bit rate calculation would be:

```
SSIClk = SysClk / (CPSDVSR * (1 + SCR))
1x106 = 20x106 / (CPSDVSR * (1 + SCR))
```

In this case, if CPSDVSR=0x2, SCR must be 0x9.

The configuration sequence would be as follows:

- 1. Ensure that the SSE bit in the SSICR1 register is clear.
- 2. Write the **SSICR1** register with a value of 0x0000.0000.
- 3. Write the **SSICPSR** register with a value of 0x0000.0002.
- **4.** Write the **SSICR0** register with a value of 0x0000.09C7.
- 5. The SSI is then enabled by setting the SSE bit in the SSICR1 register.

### 14.5 Register Map

Table 14-3 on page 767 lists the SSI registers. The offset listed is a hexadecimal increment to the register's address, relative to that SSI module's base address:

SSI0: 0x4000.8000SSI1: 0x4000.9000

Note that the SSI module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the SSI module clock is enabled before any SSI module registers are accessed.

**Note:** The SSI must be disabled (see the SSE bit in the **SSICR1** register) before any of the control registers are reprogrammed.

Table 14-3. SSI Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	SSICR0	R/W	0x0000.0000	SSI Control 0	769
0x004	SSICR1	R/W	0x0000.0000	SSI Control 1	771
0x008	SSIDR	R/W	0x0000.0000	SSI Data	773
0x00C	SSISR	RO	0x0000.0003	SSI Status	774
0x010	SSICPSR	R/W	0x0000.0000	SSI Clock Prescale	776

Table 14-3. SSI Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x014	SSIIM	R/W	0x0000.0000	SSI Interrupt Mask	777
0x018	SSIRIS	RO	0x0000.0008	SSI Raw Interrupt Status	778
0x01C	SSIMIS	RO	0x0000.0000	SSI Masked Interrupt Status	780
0x020	SSIICR	W1C	0x0000.0000	SSI Interrupt Clear	782
0x024	SSIDMACTL	R/W	0x0000.0000	SSI DMA Control	783
0xFD0	SSIPeriphID4	RO	0x0000.0000	SSI Peripheral Identification 4	784
0xFD4	SSIPeriphID5	RO	0x0000.0000	SSI Peripheral Identification 5	785
0xFD8	SSIPeriphID6	RO	0x0000.0000	SSI Peripheral Identification 6	786
0xFDC	SSIPeriphID7	RO	0x0000.0000	SSI Peripheral Identification 7	787
0xFE0	SSIPeriphID0	RO	0x0000.0022	SSI Peripheral Identification 0	788
0xFE4	SSIPeriphID1	RO	0x0000.0000	SSI Peripheral Identification 1	789
0xFE8	SSIPeriphID2	RO	0x0000.0018	SSI Peripheral Identification 2	790
0xFEC	SSIPeriphID3	RO	0x0000.0001	SSI Peripheral Identification 3	791
0xFF0	SSIPCelIID0	RO	0x0000.000D	SSI PrimeCell Identification 0	792
0xFF4	SSIPCellID1	RO	0x0000.00F0	SSI PrimeCell Identification 1	793
0xFF8	SSIPCellID2	RO	0x0000.0005	SSI PrimeCell Identification 2	794
0xFFC	SSIPCelIID3	RO	0x0000.00B1	SSI PrimeCell Identification 3	795

# 14.6 Register Descriptions

The remainder of this section lists and describes the SSI registers, in numerical order by address offset.

### Register 1: SSI Control 0 (SSICR0), offset 0x000

The **SSICR0** register contains bit fields that control various functions within the SSI module. Functionality such as protocol mode, clock rate, and data size are configured in this register.

SSI Control 0 (SSICR0)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x000


6

SPO

R/W

0

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:8	SCR	R/W	0x00	SSI Serial Clock Rate
				This bit field is used to generate the transmit and receive bit rate of the SSI. The bit rate is: $ BR=SysClk/(CPSDVSR * (1 + SCR)) $
				where CPSDVSR is an even value from 2-254 programmed in the SSICPSR register, and SCR is a value from 0-255.
7	SPH	R/W	0	SSI Serial Clock Phase
				This bit is only applicable to the Freescale SPI Format.
				The SPH control bit selects the clock edge that captures data and allows it to change state. This bit has the most impact on the first bit transmitted by either allowing or not allowing a clock transition before the first data capture edge.
				Value Description
				0 Data is captured on the first clock edge transition.
				1 Data is captured on the second clock edge transition.

Value Description

SSI Serial Clock Polarity

- 0 A steady state Low value is placed on the SSIC1k pin.
- A steady state High value is placed on the SSIC1k pin when data is not being transferred.

Bit/Field	Name	Туре	Reset	Description
5:4	FRF	R/W	0x0	SSI Frame Format Select
				Value Frame Format  0x0 Freescale SPI Frame Format  0x1 Texas Instruments Synchronous Serial Frame Format  0x2 MICROWIRE Frame Format  0x3 Reserved
3:0	DSS	R/W	0x0	SSI Data Size Select
				Value Data Size  0x0-0x2 Reserved  0x3     4-bit data  0x4     5-bit data  0x5     6-bit data  0x6     7-bit data  0x7     8-bit data  0x8     9-bit data  0x9     10-bit data  0xA     11-bit data  0xB     12-bit data  0xC     13-bit data  0xC     13-bit data  0xE     15-bit data

### Register 2: SSI Control 1 (SSICR1), offset 0x004

The SSICR1 register contains bit fields that control various functions within the SSI module. Master and slave mode functionality is controlled by this register.

SSI Control 1 (SSICR1)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x004

Bit/Field

2

Name

MS


Type

R/W

0

Reset

Type R/W, reset 0x0000.0000



Description

Divi leiu	Name	Турс	Neset	Description
31:5	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	EOT	R/W	0	End of Transmission
				Value Description
				0 The TXRIS interrupt indicates that the transmit FIFO is half full or less.
				1 The End of Transmit interrupt mode for the TXRIS interrupt is enabled.
3	SOD	R/W	0	SSI Slave Mode Output Disable
				This bit is relevant only in the Slave mode (MS=1). In multiple-slave systems, it is possible for the SSI master to broadcast a message to all slaves in the system while ensuring that only one slave drives data onto the serial output line. In such systems, the TXD lines from multiple slaves could be tied together. To operate in such a system, the SOD bit can be configured so that the SSI slave does not drive the SSITx pin.
				Value Description
				0 SSI can drive the SSITx output in Slave mode.
				1 SSI must not drive the SSITx output in Slave mode.

SSI Master/Slave Select

This bit selects Master or Slave mode and can be modified only when the SSI is disabled (SSE=0).

Value Description

- 0 The SSI is configured as a master.
- 1 The SSI is configured as a slave.

Bit/Field	Name	Туре	Reset	Description
1	SSE	R/W	0	SSI Synchronous Serial Port Enable
				Value Description
				0 SSI operation is disabled.
				1 SSI operation is enabled.
				<b>Note:</b> This bit must be cleared before any control registers are reprogrammed.
0	LBM	R/W	0	SSI Loopback Mode
				Value Description
				0 Normal serial port operation enabled.
				Output of the transmit serial shift register is connected internally to the input of the receive serial shift register.

### Register 3: SSI Data (SSIDR), offset 0x008

Important: This register is read-sensitive. See the register description for details.

The **SSIDR** register is 16-bits wide. When the **SSIDR** register is read, the entry in the receive FIFO that is pointed to by the current FIFO read pointer is accessed. When a data value is removed by the SSI receive logic from the incoming data frame, it is placed into the entry in the receive FIFO pointed to by the current FIFO write pointer.

When the **SSIDR** register is written to, the entry in the transmit FIFO that is pointed to by the write pointer is written to. Data values are removed from the transmit FIFO one value at a time by the transmit logic. Each data value is loaded into the transmit serial shifter, then serially shifted out onto the SSITX pin at the programmed bit rate.

When a data size of less than 16 bits is selected, the user must right-justify data written to the transmit FIFO. The transmit logic ignores the unused bits. Received data less than 16 bits is automatically right-justified in the receive buffer.


When the SSI is programmed for MICROWIRE frame format, the default size for transmit data is eight bits (the most significant byte is ignored). The receive data size is controlled by the programmer. The transmit FIFO and the receive FIFO are not cleared even when the SSE bit in the **SSICR1** register is cleared, allowing the software to fill the transmit FIFO before enabling the SSI.

#### SSI Data (SSIDR)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000

Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	DATA	R/W	0x0000	SSI Receive/Transmit Data

A read operation reads the receive FIFO. A write operation writes the transmit FIFO.

Software must right-justify data when the SSI is programmed for a data size that is less than 16 bits. Unused bits at the top are ignored by the transmit logic. The receive logic automatically right-justifies the data.

## Register 4: SSI Status (SSISR), offset 0x00C

The **SSISR** register contains bits that indicate the FIFO fill status and the SSI busy status.

SSI Status (SSISR)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x00C Type RO, reset 0x0000.0003

-	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1			1	reserved		1				BSY	RFF	RNE	TNF	TFE
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1	1

Bit/Field	Name	Type	Reset	Description
31:5	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	BSY	RO	0	SSI Busy Bit
				Value Description
				0 The SSI is idle.
				1 The SSI is currently transmitting and/or receiving a frame, or the transmit FIFO is not empty.
3	RFF	RO	0	SSI Receive FIFO Full
				Value Description
				0 The receive FIFO is not full.
				1 The receive FIFO is full.
2	RNE	RO	0	SSI Receive FIFO Not Empty
				Value Description
				0 The receive FIFO is empty.
				1 The receive FIFO is not empty.
1	TNF	RO	1	SSI Transmit FIFO Not Full
				Value Description
				0 The transmit FIFO is full.

The transmit FIFO is not full.

Bit/Field	Name	Туре	Reset	Description
0	TFE	RO	1	SSI Transmit FIFO Empty
				Value Description
				0 The transmit FIFO is not empty.
				1 The transmit FIFO is empty.

### Register 5: SSI Clock Prescale (SSICPSR), offset 0x010

The **SSICPSR** register specifies the division factor which is used to derive the SSIC1k from the system clock. The clock is further divided by a value from 1 to 256, which is 1 + SCR. SCR is programmed in the **SSICR0** register. The frequency of the SSIC1k is defined by:

$$SSIClk = SysClk / (CPSDVSR * (1 + SCR))$$


The value programmed into this register must be an even number between 2 and 254. The least-significant bit of the programmed number is hard-coded to zero. If an odd number is written to this register, data read back from this register has the least-significant bit as zero.

#### SSI Clock Prescale (SSICPSR)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000

Offset 0x010

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CPSDVSR	R/W	0x00	SSI Clock Prescale Divisor

This value must be an even number from 2 to 254, depending on the frequency of  ${\tt SSIClk}.$  The LSB always returns 0 on reads.

### Register 6: SSI Interrupt Mask (SSIIM), offset 0x014

The **SSIIM** register is the interrupt mask set or clear register. It is a read/write register and all bits are cleared on reset.


On a read, this register gives the current value of the mask on the corresponding interrupt. Setting a bit sets the mask, preventing the interrupt from being signaled to the interrupt controller. Clearing a bit clears the corresponding mask, enabling the interrupt to be sent to the interrupt controller.

#### SSI Interrupt Mask (SSIIM)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000

Offset 0x014

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	TXIM	R/W	0	SSI Transmit FIFO Interrupt Mask
				Value Description
				0 The transmit FIFO interrupt is masked.
				1 The transmit FIFO interrupt is not masked.
2	RXIM	R/W	0	SSI Receive FIFO Interrupt Mask
				Value Description
				0 The receive FIFO interrupt is masked.
				1 The receive FIFO interrupt is not masked.
1	RTIM	R/W	0	SSI Receive Time-Out Interrupt Mask
				Value Description
				The receive FIFO time-out interrupt is masked.
				1 The receive FIFO time-out interrupt is not masked.
0	RORIM	R/W	0	SSI Receive Overrun Interrupt Mask
				Value Description
				The receive FIFO overrun interrupt is masked.
				1 The receive FIFO overrun interrupt is not masked.

### Register 7: SSI Raw Interrupt Status (SSIRIS), offset 0x018

The **SSIRIS** register is the raw interrupt status register. On a read, this register gives the current raw status value of the corresponding interrupt prior to masking. A write has no effect.

SSI Raw Interrupt Status (SSIRIS)

Name

**TXRIS** 

**RTRIS** 

Type

RO

RO


SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000

Offset 0x018

Bit/Field

3

Type RO, reset 0x0000.0008



		,,		'
31:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Description

Value Description

No interrupt.

SSI Transmit FIFO Raw Interrupt Status

1 If the EOT bit in the SSICR1 register is clear, the transmit FIFO is half empty or less.

If the  ${\tt EOT}$  bit is set, the transmit FIFO is empty, and the last bit has been transmitted out of the serializer.

This bit is cleared when the transmit FIFO is more than half full (if the  ${\tt EOT}$  bit is clear) or when it has any data in it (if the  ${\tt EOT}$  bit is set).

2 RXRIS RO 0 SSI Receive FIFO Raw Interrupt Status

Reset

1

Value Description

0 No interrupt.

1 The receive FIFO is half full or more.

This bit is cleared when the receive FIFO is less than half full.

0 SSI Receive Time-Out Raw Interrupt Status

Value Description

0 No interrupt.

1 The receive time-out has occurred.

This bit is cleared when a 1 is written to the RTIC bit in the SSI Interrupt Clear (SSIICR) register.

Bit/Field	Name	Type	Reset	Description
0	RORRIS	RO	0	SSI Receive Overrun Raw Interrupt Status
				Value Description
				0 No interrupt.
				1 The receive FIFO has overflowed
				This bit is cleared when a 1 is written to the RORIC bit in the SSI Interrupt Clear (SSIICR) register.

### Register 8: SSI Masked Interrupt Status (SSIMIS), offset 0x01C

The SSIMIS register is the masked interrupt status register. On a read, this register gives the current masked status value of the corresponding interrupt. A write has no effect.

SSI Masked Interrupt Status (SSIMIS)


**RTMIS** 

RO

0

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x01C

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	TXMIS	RO	0	SSI Transmit FIFO Masked Interrupt Status
				Value Description
				O An interrupt has not occurred or is masked.
				An unmasked interrupt was signaled due to the transmit FIFO being half empty or less (if the EOT bit is clear) or due to the transmission of the last data bit (if the EOT bit is set).
				This bit is cleared when the transmit FIFO is more than half empty (if the ${\tt EOT}$ bit is clear) or when it has any data in it (if the ${\tt EOT}$ bit is set).
2	RXMIS	RO	0	SSI Receive FIFO Masked Interrupt Status
				Value Description
				0 An interrupt has not occurred or is masked.
				An unmasked interrupt was signaled due to the receive FIFO being half full or more.

This bit is cleared when the receive FIFO is less than half full.

SSI Receive Time-Out Masked Interrupt Status

Value Description

- 0 An interrupt has not occurred or is masked.
- 1 An unmasked interrupt was signaled due to the receive time

This bit is cleared when a 1 is written to the RTIC bit in the SSI Interrupt Clear (SSIICR) register.


Bit/Field	Name	Type	Reset	Description
0	RORMIS	RO	0	SSI Receive Overrun Masked Interrupt Status
				Value Description  O An interrupt has not occurred or is masked.  An unmasked interrupt was signaled due to the receive FIFO overflowing.
				This bit is cleared when a 1 is written to the RORIC bit in the SSI Interrupt Clear (SSIICR) register.

## Register 9: SSI Interrupt Clear (SSIICR), offset 0x020

The **SSIICR** register is the interrupt clear register. On a write of 1, the corresponding interrupt is cleared. A write of 0 has no effect.

SSI Interrupt Clear (SSIICR)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x020 Type W1C, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	RTIC	W1C	0	SSI Receive Time-Out Interrupt Clear
				Writing a 1 to this bit clears the RTRIS bit in the <b>SSIRIS</b> register and the RTMIS bit in the <b>SSIMIS</b> register.
0	RORIC	W1C	0	SSI Receive Overrun Interrupt Clear
				Writing a 1 to this bit clears the RORRIS bit in the SSIRIS register and the RORMIS bit in the SSIMIS register.


## Register 10: SSI DMA Control (SSIDMACTL), offset 0x024

The **SSIDMACTL** register is the  $\mu$ DMA control register.

SSI DMA Control (SSIDMACTL)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0x024

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	TXDMAE	R/W	0	Transmit DMA Enable
				Value Description
				0 μDMA for the transmit FIFO is disabled.
				1 μDMA for the transmit FIFO is enabled.
0	RXDMAE	R/W	0	Receive DMA Enable

Value Description

μDMA for the receive FIFO is disabled. 0

μDMA for the receive FIFO is enabled.


## Register 11: SSI Peripheral Identification 4 (SSIPeriphID4), offset 0xFD0

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 4 (SSIPeriphID4)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFD0

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID4	RO	0x00	SSI Peripheral ID Register [7:0]


## Register 12: SSI Peripheral Identification 5 (SSIPeriphID5), offset 0xFD4

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 5 (SSIPeriphID5)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFD4

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID5	RO	0x00	SSI Peripheral ID Register [15:8]
				Can be used by software to identify the presence of this peripheral.


## Register 13: SSI Peripheral Identification 6 (SSIPeriphID6), offset 0xFD8

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 6 (SSIPeriphID6)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFD8

Type RO, reset 0x0000.0000



Bit/Field	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID6	RO	0x00	SSI Peripheral ID Register [23:16]


### Register 14: SSI Peripheral Identification 7 (SSIPeriphID7), offset 0xFDC

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 7 (SSIPeriphID7)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFDC

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID7	RO	0x00	SSI Peripheral ID Register [31:24]


## Register 15: SSI Peripheral Identification 0 (SSIPeriphID0), offset 0xFE0

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 0 (SSIPeriphID0)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFE0

Type RO, reset 0x0000.0022



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID0	RO	0x22	SSI Peripheral ID Register [7:0]


## Register 16: SSI Peripheral Identification 1 (SSIPeriphID1), offset 0xFE4

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 1 (SSIPeriphID1)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFE4

Type RO, reset 0x0000.0000



Bit/Field	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID1	RO	0x00	SSI Peripheral ID Register [15:8]


## Register 17: SSI Peripheral Identification 2 (SSIPeriphID2), offset 0xFE8

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 2 (SSIPeriphID2)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFE8

Type RO, reset 0x0000.0018



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID2	RO	0x18	SSI Peripheral ID Register [23:16]


## Register 18: SSI Peripheral Identification 3 (SSIPeriphID3), offset 0xFEC

The SSIPeriphIDn registers are hard-coded and the fields within the register determine the reset value.

SSI Peripheral Identification 3 (SSIPeriphID3)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFEC

Type RO, reset 0x0000.0001



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	PID3	RO	0x01	SSI Peripheral ID Register [31:24] Can be used by software to identify the presence of this peripheral.


## Register 19: SSI PrimeCell Identification 0 (SSIPCellID0), offset 0xFF0

The SSIPCeIIIDn registers are hard-coded, and the fields within the register determine the reset value.

SSI PrimeCell Identification 0 (SSIPCellID0)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFF0

Type RO, reset 0x0000.000D



Bit/Field	Name	туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID0	RO	0x0D	SSI PrimeCell ID Register [7:0]

Provides software a standard cross-peripheral identification system.


## Register 20: SSI PrimeCell Identification 1 (SSIPCellID1), offset 0xFF4

The SSIPCellIDn registers are hard-coded, and the fields within the register determine the reset value.

SSI PrimeCell Identification 1 (SSIPCelIID1)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFF4

Type RO, reset 0x0000.00F0



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID1	RO	0xF0	SSI PrimeCell ID Register [15:8]

Provides software a standard cross-peripheral identification system.


## Register 21: SSI PrimeCell Identification 2 (SSIPCellID2), offset 0xFF8

The SSIPCeIIIDn registers are hard-coded, and the fields within the register determine the reset value.

SSI PrimeCell Identification 2 (SSIPCelIID2)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFF8

Type RO, reset 0x0000.0005



Bit/Field	Name	Туре	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID2	RO	0x05	SSI PrimeCell ID Register [23:16]

Provides software a standard cross-peripheral identification system.


## Register 22: SSI PrimeCell Identification 3 (SSIPCelIID3), offset 0xFFC

The SSIPCeIIIDn registers are hard-coded, and the fields within the register determine the reset value.

SSI PrimeCell Identification 3 (SSIPCelIID3)

SSI0 base: 0x4000.8000 SSI1 base: 0x4000.9000 Offset 0xFFC

Type RO, reset 0x0000.00B1



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	CID3	RO	0xB1	SSI PrimeCell ID Register [31:24]

Provides software a standard cross-peripheral identification system.

# 15 Inter-Integrated Circuit (I<sup>2</sup>C) Interface


The Inter-Integrated Circuit ( $I^2C$ ) bus provides bi-directional data transfer through a two-wire design (a serial data line SDA and a serial clock line SCL), and interfaces to external  $I^2C$  devices such as serial memory (RAMs and ROMs), networking devices, LCDs, tone generators, and so on. The  $I^2C$  bus may also be used for system testing and diagnostic purposes in product development and manufacture. The LM3S9D96 microcontroller includes two  $I^2C$  modules, providing the ability to interact (both transmit and receive) with other  $I^2C$  devices on the bus.

The Stellaris<sup>®</sup> LM3S9D96 controller includes two I<sup>2</sup>C modules with the following features:

- Devices on the I<sup>2</sup>C bus can be designated as either a master or a slave
  - Supports both transmitting and receiving data as either a master or a slave
  - Supports simultaneous master and slave operation
- Four I<sup>2</sup>C modes
  - Master transmit
  - Master receive
  - Slave transmit
  - Slave receive
- Two transmission speeds: Standard (100 Kbps) and Fast (400 Kbps)
- Master and slave interrupt generation
  - Master generates interrupts when a transmit or receive operation completes (or aborts due to an error)
  - Slave generates interrupts when data has been transferred or requested by a master or when a START or STOP condition is detected
- Master with arbitration and clock synchronization, multimaster support, and 7-bit addressing mode

## 15.1 Block Diagram

Figure 15-1. I<sup>2</sup>C Block Diagram



## 15.2 Signal Description

The following table lists the external signals of the  $I^2C$  interface and describes the function of each. The  $I^2C$  interface signals are alternate functions for some GPIO signals and default to be GPIO signals at reset., with the exception of the I2COSCL and I2CSDA pins which default to the  $I^2C$  function. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for the  $I^2C$  signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the  $I^2C$  function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the  $I^2C$  signal to the specified GPIO port pin. Note that the  $I^2C$  pins should be set to open drain using the **GPIO Open Drain Select (GPIOODR)** register. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 15-1. I2C Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2C0SCL	72	PB2 (1)	I/O	OD	I <sup>2</sup> C module 0 clock.
I2C0SDA	65	PB3 (1)	I/O	OD	I <sup>2</sup> C module 0 data.
I2C1SCL	14 19 26 34	PJ0 (11) PG0 (3) PA0 (8) PA6 (1)	I/O	OD	I <sup>2</sup> C module 1 clock.
I2C1SDA	18 27 35 87	PG1 (3) PA1 (8) PA7 (1) PJ1 (11)	I/O	OD	I <sup>2</sup> C module 1 data.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 15-2. I2C Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2C0SCL	A11	PB2 (1)	I/O	OD	I <sup>2</sup> C module 0 clock.

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2C0SDA	E11	PB3 (1)	I/O	OD	I <sup>2</sup> C module 0 data.
12C1SCL	F3 K1 L3 L6	PJ0 (11) PG0 (3) PA0 (8) PA6 (1)	I/O	OD	I <sup>2</sup> C module 1 clock.
I2C1SDA	K2 M3 M6 B6	PG1 (3) PA1 (8) PA7 (1) PJ1 (11)	I/O	OD	I <sup>2</sup> C module 1 data.


Table 15-2. I2C Signals (108BGA) (continued)

## 15.3 Functional Description

Each I<sup>2</sup>C module is comprised of both master and slave functions. For proper operation, the SDA and SCL pins must be configured as open-drain signals. A typical I<sup>2</sup>C bus configuration is shown in Figure 15-2.

See "Inter-Integrated Circuit (I<sup>2</sup>C) Interface" on page 1335 for I<sup>2</sup>C timing diagrams.

Figure 15-2. I<sup>2</sup>C Bus Configuration



### 15.3.1 I<sup>2</sup>C Bus Functional Overview

The  $I^2C$  bus uses only two signals: SDA and SCL, named <code>I2CSDA</code> and <code>I2CSCL</code> on Stellaris microcontrollers. SDA is the bi-directional serial data line and SCL is the bi-directional serial clock line. The bus is considered idle when both lines are High.


Every transaction on the I<sup>2</sup>C bus is nine bits long, consisting of eight data bits and a single acknowledge bit. The number of bytes per transfer (defined as the time between a valid START and STOP condition, described in "START and STOP Conditions" on page 798) is unrestricted, but each byte has to be followed by an acknowledge bit, and data must be transferred MSB first. When a receiver cannot receive another complete byte, it can hold the clock line SCL Low and force the transmitter into a wait state. The data transfer continues when the receiver releases the clock SCL.

#### 15.3.1.1 START and STOP Conditions

The protocol of the I<sup>2</sup>C bus defines two states to begin and end a transaction: START and STOP. A High-to-Low transition on the SDA line while the SCL is High is defined as a START condition, and a Low-to-High transition on the SDA line while SCL is High is defined as a STOP condition. The bus is considered busy after a START condition and free after a STOP condition. See Figure 15-3.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Figure 15-3. START and STOP Conditions




The STOP bit determines if the cycle stops at the end of the data cycle or continues on to a repeated START condition. To generate a single transmit cycle, the  $I^2C$  Master Slave Address (I2CMSA) register is written with the desired address, the R/S bit is cleared, and the Control register is written with ACK=X (0 or 1), STOP=1, START=1, and RUN=1 to perform the operation and stop. When the operation is completed (or aborted due an error), the interrupt pin becomes active and the data may be read from the  $I^2C$  Master Data (I2CMDR) register. When the  $I^2C$  module operates in Master receiver mode, the ACK bit is normally set causing the  $I^2C$  bus controller to transmit an acknowledge automatically after each byte. This bit must be cleared when the  $I^2C$  bus controller requires no further data to be transmitted from the slave transmitter.

When operating in slave mode, two bits in the I<sup>2</sup>C Slave Raw Interrupt Status (I2CSRIS) register indicate detection of start and stop conditions on the bus; while two bits in the I<sup>2</sup>C Slave Masked Interrupt Status (I2CSMIS) register allow start and stop conditions to be promoted to controller interrupts (when interrupts are enabled).

### 15.3.1.2 Data Format with 7-Bit Address


Data transfers follow the format shown in Figure 15-4. After the START condition, a slave address is transmitted. This address is 7-bits long followed by an eighth bit, which is a data direction bit ( $\mathbb{R}/\mathbb{S}$  bit in the **I2CMSA** register). If the  $\mathbb{R}/\mathbb{S}$  bit is clear, it indicates a transmit operation (send), and if it is set, it indicates a request for data (receive). A data transfer is always terminated by a STOP condition generated by the master, however, a master can initiate communications with another device on the bus by generating a repeated START condition and addressing another slave without first generating a STOP condition. Various combinations of receive/transmit formats are then possible within a single transfer.

Figure 15-4. Complete Data Transfer with a 7-Bit Address



The first seven bits of the first byte make up the slave address (see Figure 15-5). The eighth bit determines the direction of the message. A zero in the R/S position of the first byte means that the master transmits (sends) data to the selected slave, and a one in this position means that the master receives data from the slave.


Figure 15-5. R/S Bit in First Byte



## 15.3.1.3 Data Validity

The data on the SDA line must be stable during the high period of the clock, and the data line can only change when SCL is Low (see Figure 15-6).

Figure 15-6. Data Validity During Bit Transfer on the I<sup>2</sup>C Bus



### 15.3.1.4 Acknowledge

All bus transactions have a required acknowledge clock cycle that is generated by the master. During the acknowledge cycle, the transmitter (which can be the master or slave) releases the SDA line. To acknowledge the transaction, the receiver must pull down SDA during the acknowledge clock cycle. The data transmitted out by the receiver during the acknowledge cycle must comply with the data validity requirements described in "Data Validity" on page 800.

When a slave receiver does not acknowledge the slave address, SDA must be left High by the slave so that the master can generate a STOP condition and abort the current transfer. If the master device is acting as a receiver during a transfer, it is responsible for acknowledging each transfer made by the slave. Because the master controls the number of bytes in the transfer, it signals the end of data to the slave transmitter by not generating an acknowledge on the last data byte. The slave transmitter must then release SDA to allow the master to generate the STOP or a repeated START condition.

### 15.3.1.5 Arbitration

A master may start a transfer only if the bus is idle. It's possible for two or more masters to generate a START condition within minimum hold time of the START condition. In these situations, an arbitration scheme takes place on the SDA line, while SCL is High. During arbitration, the first of the competing master devices to place a '1' (High) on SDA while another master transmits a '0' (Low) switches off its data output stage and retires until the bus is idle again.

Arbitration can take place over several bits. Its first stage is a comparison of address bits, and if both masters are trying to address the same device, arbitration continues on to the comparison of data bits.

### 15.3.2 Available Speed Modes

The  $I^2C$  bus can run in either Standard mode (100 kbps) or Fast mode (400 kbps). The selected mode should match the speed of the other  $I^2C$  devices on the bus.

### 15.3.2.1 Standard and Fast Modes

Standard and Fast modes are selected using a value in the I<sup>2</sup>C Master Timer Period (I2CMTPR) register that results in an SCL frequency of 100 kbps for Standard mode.

The I<sup>2</sup>C clock rate is determined by the parameters *CLK\_PRD*, *TIMER\_PRD*, *SCL\_LP*, and *SCL\_HP* where:

CLK\_PRD is the system clock period

SCL\_LP is the low phase of SCL (fixed at 6)

SCL\_HP is the high phase of SCL (fixed at 4)

TIMER\_PRD is the programmed value in the I2CMTPR register (see page 820).

The I<sup>2</sup>C clock period is calculated as follows:

SCL\_PERIOD = 2 × (1 + TIMER\_PRD) × (SCL\_LP + SCL\_HP) × CLK\_PRD

For example:

 $CLK\_PRD = 50 \text{ ns}$ 

TIMER PRD = 2

SCL\_LP=6

SCL HP=4

yields a SCL frequency of:

1/SCL PERIOD = 333 Khz

Table 15-3 gives examples of the timer periods that should be used to generate SCL frequencies based on various system clock frequencies.

Table 15-3. Examples of I<sup>2</sup>C Master Timer Period versus Speed Mode

System Clock	Timer Period	Standard Mode	Timer Period	Fast Mode
4 MHz	0x01	100 Kbps	-	-
6 MHz	0x02	100 Kbps	-	-
12.5 MHz	0x06	89 Kbps	0x01	312 Kbps
16.7 MHz	0x08	93 Kbps	0x02	278 Kbps
20 MHz	0x09	100 Kbps	0x02	333 Kbps
25 MHz	0x0C	96.2 Kbps	0x03	312 Kbps
33 MHz	0x10	97.1 Kbps	0x04	330 Kbps
40 MHz	0x13	100 Kbps	0x04	400 Kbps
50 MHz	0x18	100 Kbps	0x06	357 Kbps
80 MHz	0x27	100 Kbps	0x09	400 Kbps

### 15.3.3 Interrupts

The I<sup>2</sup>C can generate interrupts when the following conditions are observed:

- Master transaction completed
- Master arbitration lost

- Master transaction error
- Slave transaction received
- Slave transaction requested
- Stop condition on bus detected
- Start condition on bus detected

The I<sup>2</sup>C master and I<sup>2</sup>C slave modules have separate interrupt signals. While both modules can generate interrupts for multiple conditions, only a single interrupt signal is sent to the interrupt controller.

## 15.3.3.1 I<sup>2</sup>C Master Interrupts

The  $I^2C$  master module generates an interrupt when a transaction completes (either transmit or receive), when arbitration is lost, or when an error occurs during a transaction. To enable the  $I^2C$  master interrupt, software must set the IM bit in the  $I^2C$  Master Interrupt Mask (I2CMIMR) register. When an interrupt condition is met, software must check the ERROR and ARBLST bits in the  $I^2C$  Master Control/Status (I2CMCS) register to verify that an error didn't occur during the last transaction and to ensure that arbitration has not been lost. An error condition is asserted if the last transaction wasn't acknowledged by the slave. If an error is not detected and the master has not lost arbitration, the application can proceed with the transfer. The interrupt is cleared by writing a 1 to the IC bit in the  $I^2C$  Master Interrupt Clear (I2CMICR) register.

If the application doesn't require the use of interrupts, the raw interrupt status is always visible via the  $I^2C$  Master Raw Interrupt Status (I2CMRIS) register.

## 15.3.3.2 I<sup>2</sup>C Slave Interrupts

The slave module can generate an interrupt when data has been received or requested. This interrupt is enabled by setting the DATAIM bit in the  $I^2C$  Slave Interrupt Mask (I2CSIMR) register. Software determines whether the module should write (transmit) or read (receive) data from the  $I^2C$  Slave Data (I2CSDR) register, by checking the RREQ and TREQ bits of the  $I^2C$  Slave Control/Status (I2CSCSR) register. If the slave module is in receive mode and the first byte of a transfer is received, the FBR bit is set along with the RREQ bit. The interrupt is cleared by setting the DATAIC bit in the  $I^2C$  Slave Interrupt Clear (I2CSICR) register.

In addition, the slave module can generate an interrupt when a start and stop condition is detected. These interrupts are enabled by setting the STARTIM and STOPIM bits of the I<sup>2</sup>C Slave Interrupt Mask (I2CSIMR) register and cleared by writing a 1 to the STOPIC and STARTIC bits of the I<sup>2</sup>C Slave Interrupt Clear (I2CSICR) register.

If the application doesn't require the use of interrupts, the raw interrupt status is always visible via the  $I^2C$  Slave Raw Interrupt Status (I2CSRIS) register.

### 15.3.4 Loopback Operation

The I<sup>2</sup>C modules can be placed into an internal loopback mode for diagnostic or debug work by setting the LPBK bit in the I<sup>2</sup>C Master Configuration (I2CMCR) register. In loopback mode, the SDA and SCL signals from the master and slave modules are tied together.

## 15.3.5 Command Sequence Flow Charts

This section details the steps required to perform the various  $I^2C$  transfer types in both master and slave mode.

## 15.3.5.1 I<sup>2</sup>C Master Command Sequences

The figures that follow show the command sequences available for the I<sup>2</sup>C master.




Figure 15-7. Master Single TRANSMIT




Figure 15-8. Master Single RECEIVE




Figure 15-9. Master TRANSMIT with Repeated START




Figure 15-10. Master RECEIVE with Repeated START




Figure 15-11. Master RECEIVE with Repeated START after TRANSMIT with Repeated START




Figure 15-12. Master TRANSMIT with Repeated START after RECEIVE with Repeated START

## 15.3.5.2 I<sup>2</sup>C Slave Command Sequences

Figure 15-13 on page 810 presents the command sequence available for the I<sup>2</sup>C slave.




Figure 15-13. Slave Command Sequence

## 15.4 Initialization and Configuration

The following example shows how to configure the  $I^2C$  module to transmit a single byte as a master. This assumes the system clock is 20 MHz.

- **1.** Enable the I<sup>2</sup>C clock by writing a value of 0x0000.1000 to the **RCGC1** register in the System Control module (see page 272).
- 2. Enable the clock to the appropriate GPIO module via the RCGC2 register in the System Control module (see page 284). To find out which GPIO port to enable, refer to Table 24-5 on page 1270.
- 3. In the GPIO module, enable the appropriate pins for their alternate function using the **GPIOAFSEL** register (see page 430). To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Enable the I<sup>2</sup>C pins for open-drain operation. See page 435.
- **5.** Configure the PMCn fields in the **GPIOPCTL** register to assign the I<sup>2</sup>C signals to the appropriate pins. See page 448 and Table 24-5 on page 1270.
- 6. Initialize the I<sup>2</sup>C Master by writing the I2CMCR register with a value of 0x0000.0010.

7. Set the desired SCL clock speed of 100 Kbps by writing the **I2CMTPR** register with the correct value. The value written to the **I2CMTPR** register represents the number of system clock periods in one SCL clock period. The TPR value is determined by the following equation:

```
TPR = (System Clock/(2*(SCL_LP + SCL_HP)*SCL_CLK))-1;
TPR = (20MHz/(2*(6+4)*100000))-1;
TPR = 9
```

Write the **I2CMTPR** register with the value of 0x0000.0009.

- 8. Specify the slave address of the master and that the next operation is a Transmit by writing the I2CMSA register with a value of 0x0000.0076. This sets the slave address to 0x3B.
- **9.** Place data (byte) to be transmitted in the data register by writing the **I2CMDR** register with the desired data.
- **10.** Initiate a single byte transmit of the data from Master to Slave by writing the **I2CMCS** register with a value of 0x0000.0007 (STOP, START, RUN).
- 11. Wait until the transmission completes by polling the I2CMCS register's BUSBSY bit until it has been cleared.
- 12. Check the ERROR bit in the I2CMCS register to confirm the transmit was acknowledged.

## 15.5 Register Map

Table 15-4 on page 811 lists the I<sup>2</sup>C registers. All addresses given are relative to the I<sup>2</sup>C base address:

■ I<sup>2</sup>C 0: 0x4002.0000 ■ I<sup>2</sup>C 1: 0x4002.1000

Note that the I<sup>2</sup>C module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the I<sup>2</sup>C module clock is enabled before any I<sup>2</sup>C module registers are accessed.

The hw\_i2c.h file in the StellarisWare<sup>®</sup> Driver Library uses a base address of 0x800 for the I<sup>2</sup>C slave registers. Be aware when using registers with offsets between 0x800 and 0x818 that StellarisWare uses an offset between 0x000 and 0x018 with the slave base address.

Table 15-4. Inter-Integrated Circuit (I<sup>2</sup>C) Interface Register Map

Offset	Name	Туре	Reset	Description	See page
I <sup>2</sup> C Maste	r				
0x000	I2CMSA	R/W	0x0000.0000	I2C Master Slave Address	813
0x004	I2CMCS	R/W	0x0000.0020	I2C Master Control/Status	814
0x008	I2CMDR	R/W	0x0000.0000	I2C Master Data	819
0x00C	I2CMTPR	R/W	0x0000.0001	I2C Master Timer Period	820
0x010	I2CMIMR	R/W	0x0000.0000	I2C Master Interrupt Mask	821
0x014	I2CMRIS	RO	0x0000.0000	I2C Master Raw Interrupt Status	822

Table 15-4. Inter-Integrated Circuit (I<sup>2</sup>C) Interface Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x018	I2CMMIS	RO	0x0000.0000	I2C Master Masked Interrupt Status	823
0x01C	I2CMICR	WO	0x0000.0000	I2C Master Interrupt Clear	824
0x020	I2CMCR	R/W	0x0000.0000	I2C Master Configuration	825
I <sup>2</sup> C Slave					
0x800	I2CSOAR	R/W	0x0000.0000	I2C Slave Own Address	826
0x804	I2CSCSR	RO	0x0000.0000	I2C Slave Control/Status	827
0x808	I2CSDR	R/W	0x0000.0000	I2C Slave Data	829
0x80C	I2CSIMR	R/W	0x0000.0000	I2C Slave Interrupt Mask	830
0x810	I2CSRIS	RO	0x0000.0000	I2C Slave Raw Interrupt Status	831
0x814	I2CSMIS	RO	0x0000.0000	I2C Slave Masked Interrupt Status	832
0x818	I2CSICR	WO	0x0000.0000	I2C Slave Interrupt Clear	833

# 15.6 Register Descriptions (I<sup>2</sup>C Master)

The remainder of this section lists and describes the I<sup>2</sup>C master registers, in numerical order by address offset.

# Register 1: I<sup>2</sup>C Master Slave Address (I2CMSA), offset 0x000


This register consists of eight bits: seven address bits (A6-A0), and a Receive/Send bit, which determines if the next operation is a Receive (High), or Transmit (Low).

I2C Master Slave Address (I2CMSA)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000

Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description	
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.	
7:1	SA	R/W	0x00	I <sup>2</sup> C Slave Address This field specifies bits A6 through A0 of the slave address.	
0	R/S	R/W	0	Receive/Send The R/S bit specifies if the next operation is a Receive (High) or Transmit	

(Low).

Value Description

0 Transmit

1 Receive

# Register 2: I<sup>2</sup>C Master Control/Status (I2CMCS), offset 0x004

This register accesses status bits when read and control bits when written. When read, the status register indicates the state of the  $I^2C$  bus controller. When written, the control register configures the  $I^2C$  controller operation.

The START bit generates the START or REPEATED START condition. The STOP bit determines if the cycle stops at the end of the data cycle or continues on to a repeated START condition. To generate a single transmit cycle, the  $I^2C$  Master Slave Address (I2CMSA) register is written with the desired address, the R/S bit is cleared, and this register is written with ACK=X (0 or 1), STOP=1, START=1, and RUN=1 to perform the operation and stop. When the operation is completed (or aborted due an error), an interrupt becomes active and the data may be read from the I2CMDR register. When the I2CMDR register. When the I2CMDR module operates in Master receiver mode, the ACK bit is normally set, causing the I2CMDR to transmit an acknowledge automatically after each byte. This bit must be cleared when the I2CMDR requires no further data to be transmitted from the slave transmitter.

### **Read-Only Status Register**

I2C Master Control/Status (I2CMCS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x004 Type RO, reset 0x0000.0020

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1			 			rese	rved •			'		'		
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		ı			reserved				! !	BUSBSY	IDLE	ARBLST	DATACK	ADRACK	ERROR	BUSY
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	1	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
31:7	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	BUSBSY	RO	0	Bus Busy
				Value Description  The I <sup>2</sup> C bus is idle.  The I <sup>2</sup> C bus is busy.
				The bit changes based on the START and STOP conditions.
5	IDLE	RO	1	I <sup>2</sup> C Idle
				Value Description
				The I <sup>2</sup> C controller is not idle.
				1 The I <sup>2</sup> C controller is idle.

Bit/Field	Name	Туре	Reset	Description
4	ARBLST	RO	0	Arbitration Lost
				Value Description
				The I <sup>2</sup> C controller won arbitration.
				1 The I <sup>2</sup> C controller lost arbitration.
3	DATACK	RO	0	Acknowledge Data
				Value Description
				0 The transmitted data was acknowledged
				1 The transmitted data was not acknowledged.
2	ADRACK	RO	0	Acknowledge Address
				Value Description
				0 The transmitted address was acknowledged
				1 The transmitted address was not acknowledged.
1	ERROR	RO	0	Error
				Value Description
				0 No error was detected on the last operation.
				1 An error occurred on the last operation.
				The error can be from the slave address not being acknowledged or the transmit data not being acknowledged.
0	BUSY	RO	0	I <sup>2</sup> C Busy
				Value Description
				0 The controller is idle.
				1 The controller is busy.

### **Write-Only Control Register**

I2C Master Control/Status (I2CMCS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x004 Type WO, reset 0x0000.0020

31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 16 reserved Type RO 15 14 13 12 11 10 8 3 2 0 ACK STOP START RUN reserved reserved reserved WO WO WO RO RO WO RO RO RO RO RO RO RO RO Туре RO RO Reset 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0

When the BUSY bit is set, the other status bits are not valid.

Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	reserved	RO	1	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	ACK	WO	0	Data Acknowledge Enable
				Value Description
				The received data byte is not acknowledged automatically by the master.
				The received data byte is acknowledged automatically by the master. See field decoding in Table 15-5 on page 817.
2	STOP	WO	0	Generate STOP
				Value Description
				0 The controller does not generate the STOP condition.
				The controller generates the STOP condition. See field decoding in Table 15-5 on page 817.
1	START	WO	0	Generate START
				Value Description
				The controller does not generate the START condition.
				1 The controller generates the START or repeated START condition. See field decoding in .
0	RUN	WO	0	I <sup>2</sup> C Master Enable
				Value Description
				0 The master is disabled.
				1 The master is enabled to transmit or receive data. See field

1 The master is enabled to transmit or receive data. See field decoding in Table 15-5 on page 817.

Table 15-5. Write Field Decoding for I2CMCS[3:0] Field

Current	I2CMSA[0]		I2CMC	S[3:0]		Description
State	R/S	ACK	STOP	START	RUN	Description
	0	X <sup>a</sup>	0	1	1	START condition followed by TRANSMIT (master goes to the Master Transmit state).
	0	Х	1	1	1	START condition followed by a TRANSMIT and STOP condition (master remains in Idle state).
1-11-	1	0	0	1	1	START condition followed by RECEIVE operation with negative ACK (master goes to the Master Receive state).
Idle	1	0	1	1	1	START condition followed by RECEIVE and STOP condition (master remains in Idle state).
	1	1	0	1	1	START condition followed by RECEIVE (master goes to the Master Receive state).
	1	1	1	1	1	Illegal
	All other co	mbinations	not listed	are non-op	erations.	NOP
	Х	Х	0	0	1	TRANSMIT operation (master remains in Master Transmit state).
	Х	Х	1	0	0	STOP condition (master goes to Idle state).
	Х	Х	1	0	1	TRANSMIT followed by STOP condition (master goes to Idle state).
	0	Х	0	1	1	Repeated START condition followed by a TRANSMIT (master remains in Master Transmit state).
Master	0	Х	1	1	1	Repeated START condition followed by TRANSMIT and STOP condition (master goes to Idle state).
Transmit	1	0	0	1	1	Repeated START condition followed by a RECEIVE operation with a negative ACK (master goes to Master Receive state).
	1	0	1	1	1	Repeated START condition followed by a TRANSMIT and STOP condition (master goes to Idle state).
	1	1	0	1	1	Repeated START condition followed by RECEIVE (master goes to Master Receive state).
	1	1	1	1	1	Illegal.
	All other co	mbinations	s not listed	are non-op	erations.	NOP.

Table 15-5. Write Field Decoding for I2CMCS[3:0] Field (continued)

Current	I2CMSA[0]		I2CMC	S[3:0]		Description
State	R/S	ACK	STOP	START	RUN	Description
	Х	0	0	0	1	RECEIVE operation with negative ACK (master remains in Master Receive state).
	Х	Х	1	0	0	STOP condition (master goes to Idle state).b
	Х	0	1	0	1	RECEIVE followed by STOP condition (master goes to Idle state).
Master Receive	Х	1	0	0	1	RECEIVE operation (master remains in Master Receive state).
	Х	1	1	0	1	Illegal.
	1	0	0	1	1	Repeated START condition followed by RECEIVE operation with a negative ACK (master remains in Master Receive state).
	1	0	1	1	1	Repeated START condition followed by RECEIVE and STOP condition (master goes to Idle state).
	1	1	0	1	1	Repeated START condition followed by RECEIVE (master remains in Master Receive state).
	0	Х	0	1	1	Repeated START condition followed by TRANSMIT (master goes to Master Transmit state).
	0	Х	1	1	1	Repeated START condition followed by TRANSMIT and STOP condition (master goes to Idle state).
	All other co	mbinations	s not listed	are non-op	erations.	NOP.

a. An X in a table cell indicates the bit can be 0 or 1.

b. In Master Receive mode, a STOP condition should be generated only after a Data Negative Acknowledge executed by the master or an Address Negative Acknowledge executed by the slave.

# Register 3: I<sup>2</sup>C Master Data (I2CMDR), offset 0x008


**Important:** This register is read-sensitive. See the register description for details.

This register contains the data to be transmitted when in the Master Transmit state and the data received when in the Master Receive state.

## I2C Master Data (I2CMDR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DATA	R/W	0x00	Data Transferred
				Data transferred during transaction.


# Register 4: I<sup>2</sup>C Master Timer Period (I2CMTPR), offset 0x00C

This register specifies the period of the SCL clock.

## I2C Master Timer Period (I2CMTPR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x00C

Type R/W, reset 0x0000.0001



Bit/Field	Name	Туре	Reset	Description
31:7	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	TPR	R/W	0x1	SCL Clock Period

This field specifies the period of the SCL clock.

 $SCL\_PRD = 2 \times (1 + TPR) \times (SCL\_LP + SCL\_HP) \times CLK\_PRD$ 

where:

SCL\_PRD is the SCL line period (I<sup>2</sup>C clock).

TPR is the Timer Period register value (range of 1 to 127).

SCL\_LP is the SCL Low period (fixed at 6).

 ${\it SCL\_HP}$  is the SCL High period (fixed at 4).

 $\textit{CLK\_PRD}$  is the system clock period in ns.


# Register 5: I<sup>2</sup>C Master Interrupt Mask (I2CMIMR), offset 0x010

This register controls whether a raw interrupt is promoted to a controller interrupt.

I2C Master Interrupt Mask (I2CMIMR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x010

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	IM	R/W	0	Interrupt Mask

#### Value Description

- 1 The master interrupt is sent to the interrupt controller when the RIS bit in the **I2CMRIS** register is set.
- The RIS interrupt is suppressed and not sent to the interrupt controller.


# Register 6: I<sup>2</sup>C Master Raw Interrupt Status (I2CMRIS), offset 0x014

This register specifies whether an interrupt is pending.

I2C Master Raw Interrupt Status (I2CMRIS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x014

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	RIS	RO	0	Raw Interrupt Status

Value Description

1 A master interrupt is pending.

0 No interrupt.

This bit is cleared by writing a 1 to the IC bit in the I2CMICR register.


# Register 7: I<sup>2</sup>C Master Masked Interrupt Status (I2CMMIS), offset 0x018

This register specifies whether an interrupt was signaled.

I2C Master Masked Interrupt Status (I2CMMIS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x018

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	MIS	RO	0	Masked Interrupt Status

Value Description

- 1 An unmasked master interrupt was signaled and is pending.
- 0 An interrupt has not occurred or is masked.

This bit is cleared by writing a 1 to the  ${\tt IC}$  bit in the  ${\tt I2CMICR}$  register.


# Register 8: I<sup>2</sup>C Master Interrupt Clear (I2CMICR), offset 0x01C

This register clears the raw and masked interrupts.

### I2C Master Interrupt Clear (I2CMICR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x01C

Type WO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	IC	WO	0	Interrupt Clear

Writing a 1 to this bit clears the RIS bit in the I2CMRIS register and the MIS bit in the I2CMMIS register.

A read of this register returns no meaningful data.

# Register 9: I<sup>2</sup>C Master Configuration (I2CMCR), offset 0x020

This register configures the mode (Master or Slave) and sets the interface for test mode loopback.

I2C Master Configuration (I2CMCR)


Name

Type

Reset

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x020

Bit/Field



Description

31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	SFE	R/W	0	I <sup>2</sup> C Slave Function Enable
				Value Description
				1 Slave mode is enabled.
				0 Slave mode is disabled.
4	MFE	R/W	0	I <sup>2</sup> C Master Function Enable
				Value Description
				1 Master mode is enabled.
				0 Master mode is disabled.
3:1	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	LPBK	R/W	0	I <sup>2</sup> C Loopback

# 15.7 Register Descriptions (I<sup>2</sup>C Slave)

The remainder of this section lists and describes the I<sup>2</sup>C slave registers, in numerical order by address offset.

Value Description

Normal operation.

The controller in a test mode loopback configuration.


0

# Register 10: I<sup>2</sup>C Slave Own Address (I2CSOAR), offset 0x800

This register consists of seven address bits that identify the Stellaris I<sup>2</sup>C device on the I<sup>2</sup>C bus.

I2C Slave Own Address (I2CSOAR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x800 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:7	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	OAR	R/W	0x00	I <sup>2</sup> C Slave Own Address

This field specifies bits A6 through A0 of the slave address.

# Register 11: I<sup>2</sup>C Slave Control/Status (I2CSCSR), offset 0x804

This register functions as a control register when written, and a status register when read.

### **Read-Only Status Register**

I2C Slave Control/Status (I2CSCSR)

Name

Type

Reset

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x804

Bit/Field

Type RO, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1		1	1			rese	rved						1	
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		•		1	reserved						FBR	TREQ	RREQ			
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Description

31:3	reserved	RO	0x0000.000	tware should not rely on the value of a reserved bit. To provide npatibility with future products, the value of a reserved bit should be served across a read-modify-write operation.				
2	FBR	RO	0	First Byte Received				
				Value Description				
				The first byte following the slave's own address has been received.				
				0 The first byte has not been received.				
				This bit is only valid when the RREQ bit is set and is automatically cleared when data has been read from the I2CSDR register.				
				<b>Note:</b> This bit is not used for slave transmit operations.				
1	TREQ	RO	0	Transmit Request				
				Value Description				
				The I <sup>2</sup> C controller has been addressed as a slave transmitter and is using clock stretching to delay the master until data has been written to the <b>I2CSDR</b> register.				
				0 No outstanding transmit request.				
0	RREQ	RO	0	Receive Request				
				Value Description				
				The I <sup>2</sup> C controller has outstanding receive data from the I <sup>2</sup> C				

master and is using clock stretching to delay the master until


the data has been read from the I2CSDR register.

No outstanding receive data.

## **Write-Only Control Register**

I2C Slave Control/Status (I2CSCSR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x804 Type WO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	DA	WO	0	Device Active

Value Description

- Disables the I<sup>2</sup>C slave operation. 0
- Enables the I<sup>2</sup>C slave operation. 1

Once this bit has been set, it should not be set again unless it has been cleared by writing a 0 or by a reset, otherwise transfer failures may occur.

### Register 12: I<sup>2</sup>C Slave Data (I2CSDR), offset 0x808

**Important:** This register is read-sensitive. See the register description for details.


This register contains the data to be transmitted when in the Slave Transmit state, and the data received when in the Slave Receive state.

### I2C Slave Data (I2CSDR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000

Offset 0x808

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DATA	R/W	0x00	Data for Transfer

This field contains the data for transfer during a slave receive or transmit operation.

### Register 13: I<sup>2</sup>C Slave Interrupt Mask (I2CSIMR), offset 0x80C

This register controls whether a raw interrupt is promoted to a controller interrupt.

#### I2C Slave Interrupt Mask (I2CSIMR)

DATAIM

R/W

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000

Offset 0x80C

Type R/W, reset 0x0000.0000

					reserved											
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ĺ			1		ı	1	reserved						1	STOPIM	STARTIM	DATAIM
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
					_											
Е	Bit/Field		Nam	ie	Ту	pe	Reset	Des	cription							
	31:3		reserv	/ed	R	0	0	Soft	ware sho	ould not	rely on th	he value	of a res	served bit	t. To prov	ride
								com	patibility	with futu	ıre produ	ucts, the	value of	f a reserv	ed bit sh	ould be
								pres	served a	cross a r	ead-mod	dify-write	operation	on.		
	2		STOF	DIN A	R/	۱۸/	0	Stor	Conditi	on Intorn	unt Maal	را ا				
	2		310	IIVI	TX/	VV	U	Stop	Conditi	on inten	upt iviasi	N.				
								Valı	ue Desc	ription						
								1	The :	STOP co	ndition i	nterrupt	is sent t	o the inte	errupt coi	ntroller
									wher	the STO	PRIS bi	it in the I	2CSRIS	register	is set.	
								0	The	STOPRIS	interru	ot is supp	oressed	and not	sent to th	ne
									inter	upt cont	roller.					
	1		STAR	ΤΙΜ	R/	W	0	Star	t Conditi	on Interr	upt Mas	k				
								Valı	ue Desc	ription						
								1		-	ondition	interrunt	is sent	to the int	errupt co	ntroller
								•						S registe		On O
								0	The	STARTR	s interri	upt is su	opresse	d and no	t sent to	the
										upt cont						
										-						

### Data Interrupt Mask Value Description

- The data received or data requested interrupt is sent to the interrupt controller when the DATARIS bit in the I2CSRIS register is set.
- The  ${\tt DATARIS}$  interrupt is suppressed and not sent to the 0 interrupt controller.

### Register 14: I<sup>2</sup>C Slave Raw Interrupt Status (I2CSRIS), offset 0x810

This register specifies whether an interrupt is pending.

I2C Slave Raw Interrupt Status (I2CSRIS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x810 Type RO, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1	1	1			rese	rved					-		
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0						
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1	1	1			reserved							STOPRIS	STARTRIS	DATARIS
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0						

Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	STOPRIS	RO	0	Stop Condition Raw Interrupt Status  Value Description  1 A STOP condition interrupt is pending.  0 No interrupt.  This bit is cleared by writing a 1 to the STOPIC bit in the I2CSICR register.
1	STARTRIS	RO	0	Start Condition Raw Interrupt Status  Value Description  1 A START condition interrupt is pending.  0 No interrupt.  This bit is cleared by writing a 1 to the STARTIC bit in the I2CSICR
0	DATARIS	RO	0	register.  Data Raw Interrupt Status  Value Description

- A data received or data requested interrupt is pending. 1
- 0 No interrupt.

This bit is cleared by writing a 1 to the DATAIC bit in the I2CSICR register.

# Register 15: I<sup>2</sup>C Slave Masked Interrupt Status (I2CSMIS), offset 0x814

This register specifies whether an interrupt was signaled.

I2C Slave Masked Interrupt Status (I2CSMIS)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x814 Type RO, reset 0x0000.0000

,,	,															
_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1	1		1	1	rese	erved	1	1	1		1	1	•
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0						
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1	ı	ı	1	1	reserved	ı	1	1	ı	1	·	STOPMIS	STARTMIS	DATAMIS
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO						
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	STOPMIS	RO	0	Stop Condition Masked Interrupt Status
				Value Description  1 An unmasked STOP condition interrupt was signaled is pending.  0 An interrupt has not occurred or is masked.  This bit is cleared by writing a 1 to the STOPIC bit in the I2CSICR
	07457140			register.
1	STARTMIS	RO	0	Value Description     An unmasked START condition interrupt was signaled is pending.     An interrupt has not occurred or is masked.
				This bit is cleared by writing a 1 to the STARTIC bit in the <b>I2CSICR</b> register.
0	DATAMIS	RO	0	Data Masked Interrupt Status
				Value Description

- An unmasked data received or data requested interrupt was signaled is pending.
- An interrupt has not occurred or is masked.

This bit is cleared by writing a 1 to the <code>DATAIC</code> bit in the <code>I2CSICR</code> register.


### Register 16: I<sup>2</sup>C Slave Interrupt Clear (I2CSICR), offset 0x818

This register clears the raw interrupt. A read of this register returns no meaningful data.

I2C Slave Interrupt Clear (I2CSICR)

I2C 0 base: 0x4002.0000 I2C 1 base: 0x4002.1000 Offset 0x818

Type WO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	STOPIC	WO	0	Stop Condition Interrupt Clear
				Writing a 1 to this bit clears the STOPRIS bit in the I2CSRIS register and the STOPMIS bit in the I2CSMIS register.
				A read of this register returns no meaningful data.
1	STARTIC	WO	0	Start Condition Interrupt Clear
				Writing a 1 to this bit clears the STOPRIS bit in the I2CSRIS register and the STOPMIS bit in the I2CSMIS register.
				A read of this register returns no meaningful data.
0	DATAIC	WO	0	Data Interrupt Clear
				Writing a 1 to this bit clears the STOPRIS bit in the I2CSRIS register and the STOPMIS bit in the I2CSMIS register.

# 16 Inter-Integrated Circuit Sound (I<sup>2</sup>S) Interface

The I<sup>2</sup>S module is a configurable serial audio core that contains a transmit module and a receive module. The module is configurable for the I<sup>2</sup>S as well as Left-Justified and Right-Justified serial audio formats. Data can be in one of four modes: Stereo, Mono, Compact 16-bit Stereo and Compact 8-Bit Stereo.

The transmit and receive modules each have an 8-entry audio-sample FIFO. An audio sample can consist of a Left and Right Stereo sample, a Mono sample, or a Left and Right Compact Stereo sample. In Compact 16-Bit Stereo, each FIFO entry contains both the 16-bit left and 16-bit right samples, allowing efficient data transfers and requiring less memory space. In Compact 8-bit Stereo, each FIFO entry contains an 8-bit left and an 8-bit right sample, reducing memory requirements further.


Both the transmitter and receiver are capable of being a master or a slave.

The Stellaris<sup>®</sup> I<sup>2</sup>S module has the following features:

- Configurable audio format supporting I<sup>2</sup>S, Left-justification, and Right-justification
- Configurable sample size from 8 to 32 bits
- Mono and Stereo support
- 8-, 16-, and 32-bit FIFO interface for packing memory
- Independent transmit and receive 8-entry FIFOs
- Configurable FIFO-level interrupt and µDMA requests
- Independent transmit and receive MCLK direction control
- Transmit and receive internal MCLK sources
- Independent transmit and receive control for serial clock and word select
- MCLK and SCLK can be independently set to master or slave
- Configurable transmit zero or last sample when FIFO empty
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Burst requests
  - Channel requests asserted when FIFO contains required amount of data

### 16.1 Block Diagram

Figure 16-1. I<sup>2</sup>S Block Diagram



# 16.2 Signal Description

The following table lists the external signals of the  $I^2S$  module and describes the function of each. The  $I^2S$  module signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for the  $I^2S$  signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the  $I^2S$  function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the  $I^2S$  signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 16-1. I2S Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2S0RXMCLK	29 98	PA3 (9) PD5 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
I2S0RXSCK	10	PD0 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
I2S0RXSD	28 97	PA2 (9) PD4 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive data.
I2S0RXWS	11	PD1 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
I2S0TXMCLK	61	PF1 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
I2S0TXSCK	30 90 99	PA4 (9) PB6 (9) PD6 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
I2SOTXSD	5 47	PE5 (9) PF0 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
I2SOTXWS	6 31 100	PE4 (9) PA5 (9) PD7 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 16-2. I2S Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2S0RXMCLK	L4 C6	PA3 (9) PD5 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
I2S0RXSCK	G1	PD0 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
I2S0RXSD	M4 B5	PA2 (9) PD4 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive data.
I2S0RXWS	G2	PD1 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
I2S0TXMCLK	H12	PF1 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
I2S0TXSCK	L5 A7 A3	PA4 (9) PB6 (9) PD6 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
I2S0TXSD	B3 M9	PE5 (9) PF0 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
I2SOTXWS	B2 M5 A2	PE4 (9) PA5 (9) PD7 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 16.3 Functional Description

The Inter-Integrated Circuit Sound ( $I^2S$ ) module contains separate transmit and receive engines. Each engine consists of the following:

- Serial encoder for the transmitter; serial decoder for the receiver
- 8-entry FIFO to store sample data
- Independent configuration of all programmable settings

The basic programming model of the I<sup>2</sup>S block is as follows:

#### Configuration

- Overall I<sup>2</sup>S module configuration in the I<sup>2</sup>S Module Configuration (I2SCFG) register. This
  register is used to select the MCLK source and enable the receiver and transmitter.
- Transmit and receive configuration in the I<sup>2</sup>S Transmit Module Configuration (I2STXCFG) and I<sup>2</sup>S Receive Module Configuration (I2SRXCFG) registers. These registers set the basic parameters for the receiver and transmitter such as data configuration (justification, delay, read mode, sample size, and system data size); SCLK (polarity and source); and word select polarity.
- Transmit and receive FIFO configuration in the I<sup>2</sup>S Transmit FIFO Configuration
  (I2STXFIFOCFG) and I<sup>2</sup>S Receive FIFO Configuration (I2SRXFIFOCFG) registers. These
  registers select the Compact Stereo mode size (16-bit or 8-bit), provide indication of whether
  the next sample is Left or Right, and select mono mode for the receiver.

#### ■ FIFO

- Transmit and receive FIFO data in the I<sup>2</sup>S Transmit FIFO Data (I2STXFIFO) and I<sup>2</sup>S Receive FIFO Data (I2SRXFIFO) registers
- Information on FIFO data levels in the I<sup>2</sup>S Transmit FIFO Level (I2STXLEV) and I<sup>2</sup>S Receive FIFO Level (I2SRXLEV) registers
- Configuration for FIFO service requests based on FIFO levels in the I<sup>2</sup>S Transmit FIFO Limit (I2STXLIMIT) and I<sup>2</sup>S Receive FIFO Limit (I2SRXLIM) registers

### Interrupt Control

- Interrupt masking configuration in the I<sup>2</sup>S Interrupt Mask (I2SIM) register
- Raw and masked interrupt status in the I<sup>2</sup>S Raw Interrupt Status (I2SRIS) and I<sup>2</sup>S Masked Interrupt Status (I2SMIS) registers
- Interrupt clearing through the I<sup>2</sup>S Interrupt Clear (I2SIC) register
- Configuration for FIFO service requests interrupts and transmit/receive error interrupts in the I<sup>2</sup>S Transmit Interrupt Status and Mask (I2STXISM) and I<sup>2</sup>S Receive Interrupt Status and Mask (I2SRXISM) registers

Figure 16-2 on page 838 provides an example of an I<sup>2</sup>S data transfer. Figure 16-3 on page 838 provides an example of an Left-Justified data transfer. Figure 16-4 on page 838 provides an example of an Right-Justified data transfer.

Figure 16-2. I<sup>2</sup>S Data Transfer




Figure 16-3. Left-Justified Data Transfer





Figure 16-4. Right-Justified Data Transfer



### 16.3.1 Transmit

The transmitter consists of a serial encoder, an 8-entry FIFO, and control logic. The transmitter has independent MCLK (I2SOTXMCLK), SCLK (I2SOTXSCK), and Word-Select (I2SOTXWS) signals.

#### 16.3.1.1 Serial Encoder

The serial encoder reads audio samples from the receive FIFO and converts them into an audio stream. By configuring the serial encoder, common audio formats I<sup>2</sup>S, Left-Justified, and Right-Justified are supported. The MSB is transmitted first. The sample size and system data size are configurable with the SSZ and SDSZ bits in the I<sup>2</sup>S Transmit Module Configuration (I2STXCFG) register. The sample size is the number of bits of data being transmitted, and the system data size is the number of I2SOTXSCK transitions between the word select transitions. The system data size must be large enough to accommodate the maximum sample size. In Mono mode, the sample data

is repeated in both the left and right channels. When the FIFO is empty, the user may select either transmission of zeros or of the last sample. The serial encoder is enabled using the TXEN bit in the I<sup>2</sup>S Module Configuration (I2SCFG) register.

#### 16.3.1.2 FIFO Operation

The transmit FIFO stores eight Mono samples or eight Stereo sample-pairs of data and is accessed through the I<sup>2</sup>S Transmit FIFO Data (I2STXFIFO) register. The FIFO interface for the audio data is different based on the Write mode, defined by the I<sup>2</sup>S Transmit FIFO Configuration (I2STXFIFOCFG) Compact Stereo Sample Size bit (CSS) and the I2STXCFG Write Mode field (WM). All data samples are MSB-aligned. Table 16-3 on page 839 defines the interface for each Write mode. Stereo samples are written first left then right. The next sample (right or left) to be written is indicated by the LRS bit in the I2STXFIFOCFG register.

₩M field in I2STXCFG	CSS bit in I2STXFIFOCFG	Write Mode	Sample Width	Samples per FIFO Write	Data Alignment
0x0	don't care	Stereo	8-32 bits	1	MSB
0x1	0	Compact Stereo - 16 bit	8-16 bits	2	MSB Right [31:16], Left [15:0]
0x1	1	Compact Stereo - 8 bit	8 bits	2	Right [15:8], Left[7:0]
0v2	don't care	Mono	8_32 hite	1	MSB

Table 16-3, I<sup>2</sup>S Transmit FIFO Interface

The number of samples in the transmit FIFO can be read using the I<sup>2</sup>S Transmit FIFO Level (I2STXLEV) register. The value ranges from 0 to 16. Stereo and compact stereo sample pairs are counted as two. The mono samples also increment the count by two, therefore, four mono samples will have a count of eight.

#### 16.3.1.3 Clock Control

The transmitter MCLK and SCLK can be independently programmed to be the master or slave. The transmitter is programmed to be the master or slave of the SCLK using the MSL bit in the I2STXCFG register. When the transmitter is the master, the I2SOTXSCK frequency is the specified I2SOTXMCLK divided by four. The I2SOTXSCK may be inverted using the SCP bit in the I2STXCFG register.

The transmitter can also be the master or slave of the MCLK. When the transmitter is the master, the PLL must be active and a fractional clock divider must be programmed. See page 236 for the setup for the master I2SOTXMCLK source. An external transmit I2SOTXMCLK does not require the use of the PLL and is selected using the TXSLV bit in the **I2SCFG** register.

The following tables show combinations of the TXINT and TXFRAC bits in the I<sup>2</sup>S MCLK Configuration (I2SMCLKCFG) register that provide MCLK frequencies within acceptable error limits. In the table, Fs is the sampling frequency in kHz and possible crystal frequencies are shown in MHz across the top row of the table. The words "not supported" in the table mean that it is not possible to obtain the specified sampling frequencies with the specified crystal frequency within the error tolerance of 0.3%. The values in the table are based on the following values:

$$MCLK = Fs \times 256$$
 $PLL = 400 MHz$ 

The Integer value is taken from the result of the following calculation:

ROUND (PLL/MCLK)

The remaining fractional component is converted to binary, and the first four bits are the Fractional value.

Table 16-4. Crystal Frequency (Values from 3.5795 MHz to 5 MHz)

Sampling		Crystal Frequency (MHz)													
Frequency	3.	5795	3.6864			4	4	.096	4.	9152		5			
Fs (kHz)	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional			
8	195	12	194	6	195	5	196	0	194	6	195	5			
11.025	142	1	141	1	141	12	142	4	141	1	141	12			
12	130	8	129	10	130	3	130	11	129	10	130	3			
16	97	14	97	3	97	10	98	0	97	3	97	10			
22.05	71	0	70	8	70	14	71	2	70	8	70	14			
24	65	4	64	13	65	2	65	5	64	13	65	2			
32	48	15	48	10	48	13	49	0	48	10	48	13			
44.1	35	8	35	4	35	7	35	9	35	4	35	7			
48	32	10	32	6	32	9	32	11	32	6	32	9			
64	24	8	24	5	24	7	24	8	24	5	24	7			
88.2	17	12	17	10	17	11	17	12	17	10	17	11			
96	16	5	16	3	16	4	16	5	16	3	16	4			
128	12	4	12	2	12	3	12	4	12	2	12	3			
176.4	8	14	8	13	8	14	8	14	8	13	8	14			
192	Not supported Not supported		upported	8	2	8	3	Not s	upported	8	2				

Table 16-5. Crystal Frequency (Values from 5.12 MHz to 8.192 MHz)

Sampling					C	Crystal Freq	uency (N	ИHz)				
Frequency	ţ	5.12	6		6	5.144	7.	3728		8	8	3.192
Fs (kHz)	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional
8	195	0	195	5	195	0	194	6	195	5	194	11
11.025	141	8	141	12	141	8	141	1	141	12	141	4
12	130	0	130	3	130	0	129	10	130	3	129	12
16	97	8	97	10	97	8	97	3	97	10	97	5
22.05	70	12	70	14	70	12	70	8	70	14	70	10
24	65	0	65	2	65	0	64	13	65	2	64	14
32	48	12	48	13	48	12	48	10	48	13	48	11
44.1	35	6	35	7	35	6	35	4	35	7	35	5
48	32	8	32	9	32	8	32	6	32	9	32	7
64	24	6	24	7	24	6	24	5	24	7	24	5
88.2	17	11	17	11	17	11	17	10	17	11	17	11
96	16	4	16	4	16	4	16	3	16	4	16	4
128	12	3	12	3	12	3	12	2	12	3	12	3
176.4	Not s	upported	8	14	Not s	upported	8	13	8	14	8	13
192	8	2	8	2	8	2	Not s	upported	8	2	8	2

Table 16-6. Crystal Frequency (Values from 10 MHz to 14.3181 MHz)

Sampling					Crystal Frequency (MHz)							
Frequency	1	10		12		12.288		.56	14.3181			
Fs (kHz)	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional	Integer	Fractional		
8	195	5	195	5	196	0	194	3	195	12		
11.025	141	12	141	12	142	4	140	15	142	1		
12	130	3	130	3	130	11	129	8	130	8		
16	97	10	97	10	98	0	97	2	97	14		
22.05	70	14	70	14	71	2	70f	7	71	0		
24	65	2	65	2	65	5	64	12	65	4		
32	48	13	48	13	49	0	48	9	48	15		
44.1	35	7	35	7	35	9	35	4	35	8		
48	32	9	32	9	32	11	32	6	32	10		
64	24	7	24	7	24	8	24	4	24	8		
88.2	17	11	17	11	17	12	17	10	17	12		
96	16	4	16	4	16	5	16	3	16	5		
128	12	3	12	3	12	4	12	2	12	4		
176.4	8	14	8	14	8	14	8	13	8	14		
192	8	2	8	2	8	3	Not su	oported	Not su	pported		

Table 16-7. Crystal Frequency (Values from 16 MHz to 16.384 MHz)

	Crystal Frequency (MHz)									
Sampling Frequency Fs (kHz)	1	6	16.	384						
(1112)	Integer	Fractional	Integer	Fractional						
8	195	5	192	0						
11.025	141	12	139	5						
12	130	3	128	0						
16	97	10	96	0						
22.05	70	14	69	11						
24	65	2	64	0						
32	48	13	48	0						
44.1	35	7	34	13						
48	32	9	32	0						
64	24	7	24	0						
88.2	17	11	17	7						
96	16	4	16	0						
128	12	3	12	0						
176.4	8	14	8	11						
192	8	2	8	0						

### 16.3.1.4 Interrupt Control

A single interrupt is asserted to the CPU whenever any of the transmit or receive sources is asserted. The transmit module has two interrupt sources: the FIFO service request and write error. The interrupts may be masked using the TXSRIM and TXWEIM bits in the  $I^2S$  Interrupt Mask (I2SIM)

register. The status of the interrupt source is indicated by the I<sup>2</sup>S Raw Interrupt Status (I2SRIS) register. The status of enabled interrupts is indicated by the I<sup>2</sup>S Masked Interrupt Status (I2SMIS) register. The FIFO level interrupt has a second level of masking using the FFM bit in the I<sup>2</sup>S Transmit Interrupt Status and Mask (I2STXISM) register.

The FIFO service request interrupt is asserted when the FIFO level (indicated by the LEVEL field in the I<sup>2</sup>S Transmit FIFO Level (I2STXLEV) register) is below the FIFO limit (programmed using the I<sup>2</sup>S Transmit FIFO Limit (I2STXLIMIT) register) and both the TXSRIM and FFM bits are set. If software attempts to write to a full FIFO, a Transmit FIFO Write error occurs (indicated by the TXWERIS bit in the I<sup>2</sup>S Raw Interrupt Status (I2SRIS) register). The TXWERIS bit in the I2SRIS register and the TXWEMIS bit in the I2SMIS register are cleared by setting the TXWEIC bit in the I<sup>2</sup>S Interrupt Clear (I2SIC) register.

### 16.3.1.5 **DMA Support**

The  $\mu$ DMA can be used to more efficiently stream data to and from the I<sup>2</sup>S bus. The I<sup>2</sup>S tranmit and receive modules have separate  $\mu$ DMA channels. The FIFO Interrupt Mask bit (FFM) in the **I2STXISM** register must be set for the request signaling to propagate to the  $\mu$ DMA module. See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for channel configuration.

The I<sup>2</sup>S module uses the  $\mu$ DMA burst request signal, not the single request. Thus each time a  $\mu$ DMA request is made, the  $\mu$ DMA controller transfers the number of items specified as the burst size for the  $\mu$ DMA channel. Therefore, the  $\mu$ DMA channel burst size and the I<sup>2</sup>S FIFO service request limit must be set to the same value (using the LIMIT field in the **I2STXLIMIT** register).

### 16.3.2 Receive

The receiver consists of a serial decoder, an 8-entry FIFO, and control logic. The receiver has independent MCLK (I2SORXMCLK), SCLK (I2SORXSCK), and Word-Select (I2SORXWS) signals.

#### 16.3.2.1 Serial Decoder

The serial decoder accepts incoming audio stream data and places the sample data in the receive FIFO. By configuring the serial decoder, common audio formats I<sup>2</sup>S, Left-Justified, and Right-Justified are supported. The MSB is transmitted first. The sample size and system data size are configurable with the SSZ and SDSZ bits in the I<sup>2</sup>S Receive Module Configuration (I2SRXCFG) register. The sample size is the number of bits of data being received, and the system data size is the number of I2SORXSCK transitions between the word select transitions. The system data size must be large enough to accommodate the maximum sample size. Any bits received after the LSB are 0s. If the FIFO is full, the incoming sample (in Mono) or sample-pairs (Stereo) are dropped until the FIFO has space. The serial decoder is enabled using the RXEN bit in the I2SCFG register.

#### 16.3.2.2 FIFO Operation

The receive FIFO stores eight Mono samples or eight Stereo sample-pairs of data and is accessed through the I<sup>2</sup>S Receive FIFO Data (I2SRXFIFO) register. Table 16-8 on page 843 defines the interface for each Read mode. All data is stored MSB-aligned. The Stereo data is read left sample then right.

In Mono mode, the FIFO interface can be configured to read the right or left channel by setting the FIFO Mono Mode bit (FMM) in the  $I^2S$  Receive FIFO Configuration (I2SRXFIFOCFG) register. This enables reads from a single channel, where the channel selected can be either the right or left as determined by the LRP bit in the I2SRXCFG register.

RM bit in I2RXCFG	CSS bit in I2SRXFIFOCFG	Read Mode	Sample Width	Samples per FIFO Read	Data Alignment
0	don't care	Stereo	8-32 bits	1	MSB
1	0	Compact Stereo - 16 bit	8-16 bits	2	MSB Right [31:15], Left [15:0]
1	1	Compact Stereo - 8 bit	8 bits	2	Right [15:8] Left[7:0]
0	don't care	Mono (FMM bit in the I2SRXFIFOCFG register must be set.)	8-32 bits	1	MSB

Table 16-8. I<sup>2</sup>S Receive FIFO Interface

The number of samples in the receive FIFO can be read using the I<sup>2</sup>S Receive FIFO Level (I2SRXLEV) register. The value ranges from 0 to 16. Stereo and compact stereo sample pairs are counted as two. The mono samples also increment the count by two, therefore four Mono samples will have a count of eight.

#### 16.3.2.3 Clock Control

The receiver MCLK and SCLK can be independently programmed to be the master or slave. The receiver is programmed to be the master or slave of the SCLK using the MSL bit in the I2SRXCFG register. When the receiver is the master, the I2SORXSCK frequency is the specified I2SORXMCLK divided by four. The I2SORXSCK may be inverted using the SCP bit in the I2SRXCFG register.

The receiver can also be the master or slave of the MCLK. When the receiver is the master, the PLL must be active and a fractional clock divider must be programmed. See page 236 for the setup for the master <code>I2SORXMCLK</code> source. An external transmit <code>I2SORXMCLK</code> does not require the use of the PLL and is selected using the <code>RXSLV</code> bit in the <code>I2SCFG</code> register.

Refer to "Clock Control" on page 839 for combinations of the RXINT and RXFRAC bits in the I<sup>2</sup>S MCLK Configuration (I2SMCLKCFG) register that provide MCLK frequencies within acceptable error limits. In the table, Fs is the sampling frequency in kHz and possible crystal frequencies are shown in MHz across the top row of the table. The words "not supported" in the table mean that it is not possible to obtain the specified sampling frequencies with the specified crystal frequency within the error tolerance of 0.3%.

#### 16.3.2.4 Interrupt Control

A single interrupt is asserted to the CPU whenever any of the transmit or receive sources is asserted. The receive module has two interrupt sources: the FIFO service request and read error. The interrupts may be masked using the RXSRIM and RXREIM bits in the I2SIM register. The status of the interrupt source is indicated by the I2SRIS register. The status of enabled interrupts is indicated by the I2SMIS register. The FIFO service request interrupt has a second level of masking using the FFM bit in the I2S Receive Interrupt Status and Mask (I2SRXISM) register. The sources may be masked using the I2SIM register.

The FIFO service request interrupt is asserted when the FIFO level (indicated by the LEVEL field in the I²S Receive FIFO Level (I2SRXLEV) register) is above the FIFO limit (programmed using the I²S Receive FIFO Limit (I2SRXLIMIT) register) and both the RXSRIM and FFM bits are set. An error occurs when reading an empty FIFO or if a stereo sample pair is not read left then right. To clear an interrupt, write a 1 to the appropriate bit in the I2SIC register. If software attempts to read an empty FIFO or if a stereo sample pair is not read left then right, a Receive FIFO Read error occurs (indicated by the RXRERIS bit in the I2SRIS register). The RXRERIS bit in the I2SRIS register and the RXREMIS bit in the I2SMIS register are cleared by setting the RXREIC bit in the I2SIC register.

### 16.3.2.5 DMA Support

The  $\mu$ DMA can be used to more efficiently stream data to and from the I<sup>2</sup>S bus. The I<sup>2</sup>S transmit and receive modules have separate  $\mu$ DMA channels. The FIFO Interrupt Mask bit (FFM) in the **I2SRXISM** register must be set for the request signaling to propagate to the  $\mu$ DMA module. See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for channel configuration.

The I<sup>2</sup>S module uses the  $\mu$ DMA burst request signal, not the single request. Thus each time a  $\mu$ DMA request is made, the  $\mu$ DMA controller transfers the number of items specified as the burst size for the  $\mu$ DMA channel. Therefore, the  $\mu$ DMA channel burst size and the I<sup>2</sup>S FIFO service request limit must be set to the same value (using the LIMIT field in the **I2SRXLIMIT** register).

### 16.4 Initialization and Configuration

The default setup for the I<sup>2</sup>S transmit and receive is to use external MCLK, external SCLK, Stereo, I<sup>2</sup>S audio format, and 32-bit data samples. The following example shows how to configure a system using the internal MCLK, internal SCLK, Compact Stereo, and Left-Justified audio format with 16-bit data samples.

- 1. Enable the I<sup>2</sup>S peripheral clock by writing a value of 0x1000.0000 to the **RCGC1** register in the System Control module (see page 272).
- 2. Enable the clock to the appropriate GPIO module via the RCGC2 register in the System Control module (see page 284). To find out which GPIO port to enable, refer to Table 24-5 on page 1270.
- 3. In the GPIO module, enable the appropriate pins for their alternate function using the **GPIOAFSEL** register (see page 430). To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the PMCn fields in the **GPIOPCTL** register to assign the I<sup>2</sup>S signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).
- **5.** Set up the MCLK sources for a 48-kHz sample rate. The input crystal is assumed to be 6 MHz for this example (internal source).
  - Enable the PLL by clearing the PWRDWN bit in the RCC register in the System Control module (see page 221).
  - Set the MCLK dividers and enable them by writing 0x0208.0208 to the **I2SMCLKCFG** register in the System Control module (see page 236).
  - Enable the MCLK internal sources by writing 0x8208.8208 to the **I2SMCLKCFG** register in the System Control module.

To allow an external MCLK to be used, set bits 4 and 5 of the **I2SCFG** register. Starting up the PLL and enabling the MCLK sources is not required.

- 6. Set up the Serial Bit Clock SCLK source. By default, the SCLK is externally sourced.
  - Receiver: Masters the I2SORXSCK by ORing 0x0040.0000 into the I2SRXCFG register.
  - Transmitter: Masters the I2SOTXSCK by ORing 0x0040.0000 into the I2STXCFG register.
- **7.** Configure the Serial Encoder/Decoder (Left-Justified, Compact Stereo, 16-bit samples, 32-bit system data size).

■ Set the audio format using the Justification (JST), Data Delay (DLY), SCLK polarity (SCP), and Left-Right Polarity (LRP) bits written to the **I2STXCFG** and **I2SRXCFG** registers. The settings are shown in the table below.

**Table 16-9. Audio Formats Configuration** 

Audio Format	I2STXCFG/I2SRXCFG Register Bit								
Addio Format	JST	DLY	SCP	LRP					
I <sup>2</sup> S	0	1	0	1					
Left-Justified	0	0	0	0					
Right-Justified	1	0	0	0					

- Write 0x0140.3DF0 to both the I2STXCFG and I2SRXCFG registers to program the following configurations:
  - Set the sample size to 16 bits using the SSZ field of the I2STXCFG and I2SRXCFG registers.
  - Set the system data size to 32 bits using the SDSZ field of the I2STXCFG and I2SRXCFG registers.
  - Set the Write and Read modes using the WM and RM fields in the I2STXCFG and I2SRXCFG registers, respectively.
- 8. Set up the FIFO limits for triggering interrupts (also used for µDMA)
  - Set up the transmit FIFO to trigger when it has less than four sample pairs by writing a 0x0000.0008 to the I2STXLIMIT register.
  - Set up the receive FIFO to trigger when there are more than four sample pairs by writing a 0x0000.00008 to the **I2SRXLIMIT** register.
- **9.** Enable interrupts.
  - Enable the transmit FIFO interrupt by setting the FFM bit in the **I2STXISM** register (write 0x0000.0001).
  - Set up the receive FIFO interrupts by setting the FFM bit in the **I2SRXISM** register (write 0x0000.0001).
  - Enable the TX FIFO service request, the TX Error, the RX FIFO service request, and the RX Error interrupts to be sent to the CPU by writing a 0x0000.0033 to the I2SSIM register.
- 10. Enable the Serial Encoder and Serial Decoders by writing a 0x0000.0003 to the I2SCFG register.

# 16.5 Register Map

Table 16-10 on page 846 lists the  $I^2S$  registers. The offset listed is a hexadecimal increment to the register's address, relative to the  $I^2S$  interface base address of 0x4005.4000. Note that the  $I^2S$  module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the  $I^2S$  module clock is enabled before any  $I^2S$  module registers are accessed.

Table 16-10. Inter-Integrated Circuit Sound (I<sup>2</sup>S) Interface Register Map

Offset	Name	Type	Reset	Description	See page
0x000	I2STXFIFO	WO	0x0000.0000	I2S Transmit FIFO Data	847
0x004	12STXFIFOCFG	R/W	0x0000.0000	I2S Transmit FIFO Configuration	848
0x008	I2STXCFG	R/W	0x1400.7DF0	I2S Transmit Module Configuration	849
0x00C	I2STXLIMIT	R/W	0x0000.0000	I2S Transmit FIFO Limit	851
0x010	I2STXISM	R/W	0x0000.0000	I2S Transmit Interrupt Status and Mask	852
0x018	I2STXLEV	RO	0x0000.0000	I2S Transmit FIFO Level	853
0x800	I2SRXFIFO	RO	0x0000.0000	I2S Receive FIFO Data	854
0x804	12SRXFIFOCFG	R/W	0x0000.0000	I2S Receive FIFO Configuration	855
0x808	I2SRXCFG	R/W	0x1400.7DF0	I2S Receive Module Configuration	856
0x80C	I2SRXLIMIT	R/W	0x0000.7FFF	I2S Receive FIFO Limit	859
0x810	I2SRXISM	R/W	0x0000.0000	I2S Receive Interrupt Status and Mask	860
0x818	I2SRXLEV	RO	0x0000.0000	I2S Receive FIFO Level	861
0xC00	I2SCFG	R/W	0x0000.0000	I2S Module Configuration	862
0xC10	I2SIM	R/W	0x0000.0000	I2S Interrupt Mask	864
0xC14	I2SRIS	RO	0x0000.0000	I2S Raw Interrupt Status	866
0xC18	I2SMIS	RO	0x0000.0000	I2S Masked Interrupt Status	868
0xC1C	I2SIC	WO	0x0000.0000	I2S Interrupt Clear	870

# 16.6 Register Descriptions

The remainder of this section lists and describes the I<sup>2</sup>S registers, in numerical order by address offset.

### Register 1: I<sup>2</sup>S Transmit FIFO Data (I2STXFIFO), offset 0x000


This register is the 32-bit serial audio transmit data register. In Stereo mode, the data is written left, right, left, right, and so on. The LRS bit in the  $I^2S$  Transmit FIFO Configuration (I2STXFIFOCFG) register can be read to verify the next position expected. In Compact 16-bit mode, bits [31:16] contain the right sample, and bits [15:0] contain the left sample. In Compact 8-bit mode, bits [15:8] contain the right sample, and bits [7:0] contain the left sample. In Mono mode, each 32-bit entry is a single sample.

Note that if the FIFO is full and a write is attempted, a transmit FIFO write error is generated.

#### I2S Transmit FIFO Data (I2STXFIFO)

Base 0x4005.4000 Offset 0x000

Type WO, reset 0x0000.0000




Serial audio sample data to be transmitted.

### Register 2: I<sup>2</sup>S Transmit FIFO Configuration (I2STXFIFOCFG), offset 0x004

This register configures the sample for dual-channel operation. In Stereo mode, the LRS bit toggles between left and right samples as the Transmit FIFO is written. The left sample is written first, followed by the right.

### I2S Transmit FIFO Configuration (I2STXFIFOCFG)

Base 0x4005.4000 Offset 0x004 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	CSS	R/W	0	Compact Stereo Sample Size
				Value Description
				O The transmitter is in Compact 16-bit Stereo Mode with a 16-bit sample size.
				1 The transmitter is in Compact 8-bit Stereo Mode with an 8-bit sample size.
0	LRS	R/W	0	Left-Right Sample Indicator

Value Description

- 0 The left sample is the next position.
- The right sample is the next position.

In Mono mode and Compact stereo mode, this bit toggles as if it were in Stereo mode, but it has no meaning and should be ignored.

# Register 3: I<sup>2</sup>S Transmit Module Configuration (I2STXCFG), offset 0x008

This register controls the configuration of the Transmit module.

I2S Transmit Module Configuration (I2STXCFG)

Base 0x4005.4000 Offset 0x008

Type R/W, reset 0x1400.7DF0

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	rese	rved	JST	DLY	SCP	LRP	W	I /M	FMT	MSL		'	rese	rved	ı	
Type <sup>*</sup>	RO	RO	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO	RO	RO	RO	RO	RO
Reset	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		ı	S	SZ	 	1		ı	SE •	I SZ		ı		rese	erved	
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO	RO	RO	RO
Reset	0	1	1	1	1	1	0	1	1	1	1	1	0	0	0	0

Bit/Field	Name	Туре	Reset	Description		
31:30	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.		
29	JST	R/W	0	Justification of Output Data		
				Value Description		
				0 The data is Left-Justified.		
				1 The data is Right-Justified.		
28	DLY	R/W	1	Data Delay		
				Value Description		
				Data is latched on the next latching edge of I2SOTXSCK as defined by the SCP bit. This bit should be clear in Left-Justified or Right-Justified mode.		
				A one-I2S0TXSCK delay from the edge of I2S0TXWS is inserted before data is latched. This bit should be set in I <sup>2</sup> S mode.		
27	SCP	R/W	0	SCLK Polarity		
				Value Description		
				O Data and the I2SOTXWS signal (when the MSL bit is set) are launched on the falling edge of I2SOTXSCK.		
				Data and the I2SOTXWS signal (when the MSL bit is set) are launched on the rising edge of I2SOTXSCK.		
26	LRP	R/W	1	Left/Right Clock Polarity		

#### Value Description

- 0 I2SOTXWS is high during the transmission of the left channel data.
- 1 I2SOTXWS is high during the transmission of the right channel data.

Bit/Field	Name	Туре	Reset	Description
25:24	WM	R/W	0x0	Write Mode
				This bit field selects the mode in which the transmit data is stored in the FIFO and transmitted.
				Value Description
				0x0 Stereo mode
				0x1 Compact Stereo mode
				Left/Right sample packed. Refer to <b>I2STXFIFOCFG</b> for 8/16-bit sample size selection.
				0x2 Mono mode
				0x3 reserved
23	FMT	R/W	0	FIFO Empty
				Value Description
				O All zeroes are transmitted if the FIFO is empty.
				1 The last sample is transmitted if the FIFO is empty.
22	MSL	R/W	0	SCLK Master/Slave
				Source of serial bit clock (I2S0TXSCK) and Word Select (I2S0TXWS).
				Value Description
				O The transmitter is a slave using the externally driven I2SOTXSCK and I2SOTXWS signals.
				1 The transmitter is a master using the internally generated I2SOTXSCK and I2SOTXWS signals.
21:16	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:10	SSZ	R/W	0x1F	Sample Size
				This field contains the number of bits minus one in the sample.
				<b>Note:</b> This field is only used in Right-Justified mode. Unused bits are not masked.
9:4	SDSZ	R/W	0x1F	System Data Size
				This field contains the number of bits minus one during the high or low phase of the I2SOTXWS signal.
3:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.


### Register 4: I<sup>2</sup>S Transmit FIFO Limit (I2STXLIMIT), offset 0x00C

This register sets the lower FIFO limit at which a FIFO service request is issued.

I2S Transmit FIFO Limit (I2STXLIMIT)

Base 0x4005.4000 Offset 0x00C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:5	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4:0	LIMIT	R/W	0x00	FIFO Limit

This field sets the FIFO level at which a FIFO service request is issued, generating an interrupt or a µDMA transfer request.

The transmit FIFO generates a service request when the number of items in the FIFO is less than the level specified by the LIMIT field. For example, if the LIMIT field is set to 8, then a service request is generated when there are less than 8 samples remaining in the transmit FIFO.

### Register 5: I<sup>2</sup>S Transmit Interrupt Status and Mask (I2STXISM), offset 0x010

This register indicates the transmit interrupt status and interrupt masking control.

I2S Transmit Interrupt Status and Mask (I2STXISM)

Name


Type

Reset

Base 0x4005.4000 Offset 0x010

Bit/Field

Type R/W, reset 0x0000.0000



31:17	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
16	FFI	RO	0	Transmit FIFO Service Request Interrupt
				Value Description  The FIFO level is equal to or above the FIFO limit.  The FIFO level is below the FIFO limit.
15:1	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	FFM	R/W	0	FIFO Interrupt Mask

Description

Value Description

- 0 The FIFO interrupt is masked and not sent to the CPU.
- 1 The FIFO interrupt is enabled to be sent to the interrupt controller.


### Register 6: I<sup>2</sup>S Transmit FIFO Level (I2STXLEV), offset 0x018

The number of samples in the transmit FIFO can be read using the **I2STXLEV** register. The value ranges from 0 to 16. Stereo and Compact Stereo sample-pairs are counted as two. Mono samples also increment the count by two. For example, the LEVEL field is set to eight if there are four Mono samples.

#### I2S Transmit FIFO Level (I2STXLEV)

Base 0x4005.4000 Offset 0x018

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:5	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4:0	LEVEL	RO	0x00	Number of Audio Samples

This field contains the number of samples in the FIFO.

### Register 7: I<sup>2</sup>S Receive FIFO Data (I2SRXFIFO), offset 0x800


**Important:** This register is read-sensitive. See the register description for details.

This register is the 32-bit serial audio receive data register. In Stereo mode, the data is read left, right, left, right, and so on. The LRS bit in the I²S Receive FIFO Configuration (I2SRXFIFOCFG) register can be read to verify the next position expected. In Compact 16-bit mode, bits [31:16] contain the right sample, and bits [15:0] contain the left sample. In Compact 8-bit mode, bits [15:8] contain the right sample, and bits [7:0] contain the left sample. In Mono mode, each 32-bit entry is a single sample. If the FIFO is empty, a read of this register returns a value of 0x0000.0000 and generates a receive FIFO read error.

#### I2S Receive FIFO Data (I2SRXFIFO)

Base 0x4005.4000 Offset 0x800

Type RO, reset 0x0000.0000



Serial audio sample data received.

The read of an empty FIFO returns a value of 0x0.

### Register 8: I<sup>2</sup>S Receive FIFO Configuration (I2SRXFIFOCFG), offset 0x804

This register configures the sample for dual-channel operation. In Stereo mode, the LRS bit toggles between Left and Right as the samples are read from the receive FIFO. In Mono mode, both the left and right samples are stored in the FIFO. The FMM bit can be used to read only the left or right sample as determined by the LRP bit. In Compact Stereo 8- or 16-bit mode, both the left and right samples are read in one access from the FIFO.

#### I2S Receive FIFO Configuration (I2SRXFIFOCFG)

Base 0x4005.4000 Offset 0x804

Type R/W, reset 0x0000.0000

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	l					reserved								FMM	css	LRS
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	FMM	R/W	0	FIFO Mono Mode
				Value Description
				0 The receiver is in Stereo Mode.
				1 The receiver is in Mono mode.
				If the LRP bit in the <b>I2SRXCFG</b> register is clear, data is read while the I2SORXWS signal is low (Right Channel); if the LRP bit is set, data is read while the I2SORXWS signal is high (Left Channel).
1	CSS	R/W	0	Compact Stereo Sample Size
				Value Description
				The receiver is in Compact 16-bit Stereo Mode with a 16-bit sample size.
				1 The receiver is in Compact 8-bit Stereo Mode with a 8-bit sample size.
0	LRS	R/W	0	Left-Right Sample Indicator
				Value Description
				0 The left sample is the next position to be read.

The right sample is the next position to be read.

This bit is only meaningful in Compact Stereo Mode.

# Register 9: I<sup>2</sup>S Receive Module Configuration (I2SRXCFG), offset 0x808

This register controls the configuration of the receive module.

Type

Reset

I2S Receive Module Configuration (I2SRXCFG)

Name

Base 0x4005.4000 Offset 0x808

Bit/Field

Type R/W, reset 0x1400.7DF0

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	rese	rved	JST	DLY	SCP	LRP	reserved	RM	reserved	MSL		1	rese	rved		1
Type	RO	RO	R/W	R/W	R/W	R/W	RO	R/W	RO	R/W	RO	RO	RO	RO	RO	RO
Reset	0	0	0	1	0	1	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		ı	S	SZ	!	•	'	l	SD	SZ		•		rese	rved	1
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO	RO	RO	RO
Reset	0	1	1	1	1	1	0	1	1	1	1	1	0	0	0	0

Description

31:30	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
29	JST	R/W	0	Justification of Input Data
				Value Description
				0 The data is Left-Justified.
				1 The data is Right-Justified.
28	DLY	R/W	1	Data Delay
				Value Description
				Data is latched on the next latching edge of I2SORXSCK as defined by the SCP bit. This bit should be clear in Left-Justified or Right-Justified mode.
				A one-I2SORXSCK delay from the edge of I2SORXWS is inserted before data is latched. This bit should be set in I <sup>2</sup> S mode.
27	SCP	R/W	0	SCLK Polarity

#### Value Description

- Data is latched on the rising edge and the I2SORXWS signal (when the MSL bit is set) is launched on the falling edge of I2SORXSCK.
- Data is latched on the falling edge and the I2SORXWS signal (when the MSL bit is set) is launched on the rising edge of I2SORXSCK.

Bit/Field	Name	Туре	Reset	Description
26	LRP	R/W	1	Left/Right Clock Polarity
				Value Description
				0 In Stereo mode, I2SORXWS is high during the transmission of the left channel data.
				In Mono mode, data is read while the I2SORXWS signal is low (Right Channel).
				1 In Stereo mode, I2SORXWS is high during the transmission of the right channel data.
				In Mono mode, data is read while the I2SORXWS signal is high (Left Channel).
25	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
24	RM	R/W	0	Read Mode
				This bit selects the mode in which the receive data is received and stored in the FIFO.
				Value Description
				0 Stereo/Mono mode
				<b>I2SRXFIFOCFG</b> FMM bit specifies Stereo or Mono FIFO read behavior.
				1 Compact Stereo mode
				Left/Right sample packed. Refer to <b>I2SRXFIFOCFG</b> for 8/16-bit sample size selection.
23	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
22	MSL	R/W	0	SCLK Master/Slave
				Value Description
				The receiver is a slave and uses the externally driven I2SORXSCK and I2SORXWS signals.
				The receiver is a master and uses the internally generated I2SORXSCK and I2SORXWS signals.
21:16	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:10	SSZ	R/W	0x1F	Sample Size This field contains the number of bits minus one in the sample.
9:4	SDSZ	R/W	0x1F	System Data Size
-	- <del></del>			This field contains the number of bits minus one during the high or low phase of the I2SORXWS signal.

Bit/Field	Name	Type	Reset	Description
3:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.


### Register 10: I<sup>2</sup>S Receive FIFO Limit (I2SRXLIMIT), offset 0x80C

This register sets the upper FIFO limit at which a FIFO service request is issued.

I2S Receive FIFO Limit (I2SRXLIMIT)

Base 0x4005.4000 Offset 0x80C

Type R/W, reset 0x0000.7FFF



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:5	reserved	RO	0x7FF	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4:0	LIMIT	R/W	0x1F	FIFO Limit

This field sets the FIFO level at which a FIFO service request is issued, generating an interrupt or a µDMA transfer request.

The receive FIFO generates a service request when the number of items in the FIFO is greater than the level specified by the  ${\tt LIMIT}$  field. For example, if the LIMIT field is set to 4, then a service request is generated when there are more than 4 samples remaining in the transmit FIFO.

### Register 11: I<sup>2</sup>S Receive Interrupt Status and Mask (I2SRXISM), offset 0x810

This register indicates the receive interrupt status and interrupt masking control.

I2S Receive Interrupt Status and Mask (I2SRXISM)

Name


Type

Reset

Base 0x4005.4000 Offset 0x810

Bit/Field

Type R/W, reset 0x0000.0000



Description

31:17	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
16	FFI	RO	0	Receive FIFO Service Request Interrupt  Value Description  The FIFO level is equal to or below the FIFO limit.  The FIFO level is above the FIFO limit.
15:1	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	FFM	R/W	0	FIFO Interrupt Mask

Value Description

- 0 The FIFO interrupt is masked and not sent to the CPU.
- 1 The FIFO interrupt is enabled to be sent to the interrupt controller.


### Register 12: I<sup>2</sup>S Receive FIFO Level (I2SRXLEV), offset 0x818

The number of samples in the receive FIFO can be read using the **I2SRXLEV** register. The value ranges from 0 to 16. Stereo and Compact Stereo sample pairs are counted as two. Mono samples also increment the count by two. For example, the LEVEL field is set to eight if there are four Mono samples.

#### I2S Receive FIFO Level (I2SRXLEV)

Base 0x4005.4000 Offset 0x818

Type RO, reset 0x0000.0000



E	Bit/Field	Name	Туре	Reset	Description
	31:5	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
	4:0	LEVEL	RO	0x00	Number of Audio Samples

This field contains the number of samples in the FIFO.


### Register 13: I<sup>2</sup>S Module Configuration (I2SCFG), offset 0xC00

This register enables the transmit and receive serial engines and sets the source of the  ${\tt I2S0TXMCLK}$  and  ${\tt I2S0RXMCLK}$  signals.

### I2S Module Configuration (I2SCFG)

Base 0x4005.4000

Offset 0xC00 Type R/W, reset 0x0000.0000



Dit/Filala	Mana	T	Desert	December
Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	RXSLV	R/W	0	Use External I2SORXMCLK
				Value Description
				The receiver uses the internally generated MCLK as the I2SORXMCLK signal. See "Clock Control" on page 839 for information on how to program the I2SORXMCLK.
				1 The receiver uses the externally driven I2SORXMCLK signal.
4	TXSLV	R/W	0	Use External I2S0TXMCLK
				Value Description
				The transmitter uses the internally generated MCLK as the I2S0TXMCLK signal. See "Clock Control" on page 839 for information on how to program the I2S0TXMCLK.
				1 The transmitter uses the externally driven I2SOTXMCLK signal.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	RXEN	R/W	0	Serial Receive Engine Enable

#### Value Description

- 0 Disables the serial receive engine.
- 1 Enables the serial receive engine.

Bit/Field	Name	Type	Reset	Description
0	TXEN	R/W	0	Serial Transmit Engine Enable
				Value Description
				0 Disables the serial transmit engine.
				1 Enables the serial transmit engine.


### Register 14: I<sup>2</sup>S Interrupt Mask (I2SIM), offset 0xC10

This register masks the interrupts to the CPU.

I2S Interrupt Mask (I2SIM)

Base 0x4005.4000 Offset 0xC10

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	RXREIM	R/W	0	Receive FIFO Read Error
				Value Description
				The receive FIFO read error interrupt is masked and not sent to the CPU.
				1 The receive FIFO read error is enabled to be sent to the interrupt controller.
4	RXSRIM	R/W	0	Receive FIFO Service Request
				Value Description
				The receive FIFO service request interrupt is masked and not sent to the CPU.
				1 The receive FIFO service request is enabled to be sent to the interrupt controller.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	TXWEIM	R/W	0	Transmit FIFO Write Error
				Value Description

#### Value Description

- The transmit FIFO write error interrupt is masked and not sent to the CPU.
- 1 The transmit FIFO write error is enabled to be sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
0	TXSRIM	R/W	0	Transmit FIFO Service Request
				Value Description
				The transmit FIFO service request interrupt is masked and not sent to the CPU.
				1 The transmit FIFO service request is enabled to be sent to the interrupt controller.


# Register 15: I<sup>2</sup>S Raw Interrupt Status (I2SRIS), offset 0xC14

This register reads the unmasked interrupt status.

I2S Raw Interrupt Status (I2SRIS)

Base 0x4005.4000

Offset 0xC14
Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	RXRERIS	RO	0	Receive FIFO Read Error
				Value Description
				1 A receive FIFO read error interrupt has occurred.
				0 No interrupt
				This bit is cleared by setting the RXREIC bit in the I2SIC register.
4	RXSRRIS	RO	0	Receive FIFO Service Request
				Value Description
				1 A receive FIFO service request interrupt has occurred.
				0 No interrupt
				This bit is cleared when the level in the receive FIFO has risen to a value greater than the value programmed in the LIMIT field in the I2SRXLIMIT register.
3:2	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	TXWERIS	RO	0	Transmit FIFO Write Error
				Value Description
				1 A transmit FIFO write error interrupt has occurred.

0

No interrupt

This bit is cleared by setting the TXWEIC bit in the I2SIC register.

Bit/Field	Name	Туре	Reset	Description
0	TXSRRIS	RO	0	Transmit FIFO Service Request
				Value Description  A transmit FIFO service request interrupt has occurred.  No interrupt  This bit is cleared when the level in the transmit FIFO has fallen to a value less than the value programmed in the LIMIT field in the I2STXLIMIT register.


# Register 16: I<sup>2</sup>S Masked Interrupt Status (I2SMIS), offset 0xC18

This register reads the masked interrupt status. The mask is defined in the **I2SIM** register.

I2S Masked Interrupt Status (I2SMIS)

Base 0x4005.4000

Offset 0xC18
Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	RXREMIS	RO	0	Receive FIFO Read Error
				Value Description
				An unmasked interrupt was signaled due to a receive FIFO read error.
				0 An interrupt has not occurred or is masked.
				This bit is cleared by setting the RXREIC bit in the I2SIC register.
4	RXSRMIS	RO	0	Receive FIFO Service Request
				Value Description
				An unmasked interrupt was signaled due to a receive FIFO service request.
				O An interrupt has not occurred or is masked.
				This bit is cleared when the level in the receive FIFO has risen to a value greater than the value programmed in the ${\tt LIMIT}$ field in the <code>I2SRXLIMIT</code> register.
3:2	reserved	RO	0s0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	TXWEMIS	RO	0	Transmit FIFO Write Error
				Value Description
				An unmasked interrupt was signaled due to a transmit FIFO  write error.

- write error.
- 0 An interrupt has not occurred or is masked.

This bit is cleared by setting the  ${\tt TXWEIC}$  bit in the <code>I2SIC</code> register.


Bit/Field	Name	Туре	Reset	Description
0	TXSRMIS	RO	0	Transmit FIFO Service Request
				Value Description
				An unmasked interrupt was signaled due to a transmit FIFO service request.
				O An interrupt has not occurred or is masked.
				This bit is cleared when the level in the transmit FIFO has fallen to a value less than the value programmed in the ${\tt LIMIT}$ field in the <code>I2STXLIMIT</code> register.

# Register 17: I<sup>2</sup>S Interrupt Clear (I2SIC), offset 0xC1C

Writing a 1 to a bit in this register clears the corresponding interrupt.

I2S Interrupt Clear (I2SIC)

Base 0x4005.4000 Offset 0xC1C Type WO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:6	reserved	WO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	RXREIC	WO	0	Receive FIFO Read Error  Writing a 1 to this bit clears the RXRERIS bit in the I2CRIS register and the RXREMIS bit in the I2CMIS register.
4:2	reserved	WO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	TXWEIC	WO	0	Transmit FIFO Write Error Writing a 1 to this bit clears the TXWERIS bit in the I2CRIS register and the TXWEMIS bit in the I2CMIS register.
0	reserved	WO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# 17 Controller Area Network (CAN) Module


Controller Area Network (CAN) is a multicast, shared serial bus standard for connecting electronic control units (ECUs). CAN was specifically designed to be robust in electromagnetically-noisy environments and can utilize a differential balanced line like RS-485 or a more robust twisted-pair wire. Originally created for automotive purposes, it is also used in many embedded control applications (such as industrial and medical). Bit rates up to 1 Mbps are possible at network lengths less than 40 meters. Decreased bit rates allow longer network distances (for example, 125 Kbps at 500 meters).

The Stellaris<sup>®</sup> LM3S9D96 microcontroller includes two CAN units with the following features:

- CAN protocol version 2.0 part A/B
- Bit rates up to 1 Mbps
- 32 message objects with individual identifier masks
- Maskable interrupt
- Disable Automatic Retransmission mode for Time-Triggered CAN (TTCAN) applications
- Programmable Loopback mode for self-test operation
- Programmable FIFO mode enables storage of multiple message objects
- Gluelessly attaches to an external CAN transceiver through the CANnTX and CANnRX signals

# 17.1 Block Diagram

Figure 17-1. CAN Controller Block Diagram



# 17.2 Signal Description

The following table lists the external signals of the CAN controller and describes the function of each. The CAN controller signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for the CAN signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the CAN controller function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the CAN signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 17-1. Controller Area Network Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CANORX	10 30 34 92	PD0 (2) PA4 (5) PA6 (6) PB4 (5)	_	TTL	CAN module 0 receive.
CANOTX	11 31 35 91	PD1 (2) PA5 (5) PA7 (6) PB5 (5)	0	TTL	CAN module 0 transmit.
CAN1Rx	47	PF0 (1)	1	TTL	CAN module 1 receive.
CAN1Tx	61	PF1 (1)	0	TTL	CAN module 1 transmit.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 17-2. Controller Area Network Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CANORX	G1 L5 L6 A6	PD0 (2) PA4 (5) PA6 (6) PB4 (5)	1	TTL	CAN module 0 receive.
CANOTX	G2 M5 M6 B7	PD1 (2) PA5 (5) PA7 (6) PB5 (5)	0	TTL	CAN module 0 transmit.
CAN1Rx	M9	PF0 (1)	1	TTL	CAN module 1 receive.
CAN1Tx	H12	PF1 (1)	0	TTL	CAN module 1 transmit.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 17.3 Functional Description


The Stellaris CAN controller conforms to the CAN protocol version 2.0 (parts A and B). Message transfers that include data, remote, error, and overload frames with an 11-bit identifier (standard) or a 29-bit identifier (extended) are supported. Transfer rates can be programmed up to 1 Mbps.

The CAN module consists of three major parts:

- CAN protocol controller and message handler
- Message memory
- CAN register interface

A data frame contains data for transmission, whereas a remote frame contains no data and is used to request the transmission of a specific message object. The CAN data/remote frame is constructed as shown in Figure 17-2.

Figure 17-2. CAN Data/Remote Frame



The protocol controller transfers and receives the serial data from the CAN bus and passes the data on to the message handler. The message handler then loads this information into the appropriate message object based on the current filtering and identifiers in the message object memory. The message handler is also responsible for generating interrupts based on events on the CAN bus.

The message object memory is a set of 32 identical memory blocks that hold the current configuration, status, and actual data for each message object. These memory blocks are accessed via either of the CAN message object register interfaces.

The message memory is not directly accessible in the Stellaris memory map, so the Stellaris CAN controller provides an interface to communicate with the message memory via two CAN interface register sets for communicating with the message objects. The message object memory cannot be directly accessed, so these two interfaces must be used to read or write to each message object. The two message object interfaces allow parallel access to the CAN controller message objects when multiple objects may have new information that must be processed. In general, one interface is used for transmit data and one for receive data.

### 17.3.1 Initialization

To use the CAN controller, the peripheral clock must be enabled using the **RCGC0** register (see page 264). In addition, the clock to the appropriate GPIO module must be enabled via the **RCGC2** register (see page 284). To find out which GPIO port to enable, refer to Table 24-4 on page 1261. Set the GPIO AFSEL bits for the appropriate pins (see page 430). Configure the PMCn fields in the **GPIOPCTL** register to assign the CAN signals to the appropriate pins. See page 448 and Table 24-5 on page 1270.

Software initialization is started by setting the INIT bit in the **CAN Control (CANCTL)** register (with software or by a hardware reset) or by going bus-off, which occurs when the transmitter's error counter exceeds a count of 255. While INIT is set, all message transfers to and from the CAN bus are stopped and the CANnTX signal is held High. Entering the initialization state does not change the configuration of the CAN controller, the message objects, or the error counters. However, some configuration registers are only accessible while in the initialization state.

To initialize the CAN controller, set the CAN Bit Timing (CANBIT) register and configure each message object. If a message object is not needed, label it as not valid by clearing the MSGVAL bit in the CAN IFn Arbitration 2 (CANIFnARB2) register. Otherwise, the whole message object must be initialized, as the fields of the message object may not have valid information, causing unexpected results. Both the INIT and CCE bits in the CANCTL register must be set in order to access the CANBIT register and the CAN Baud Rate Prescaler Extension (CANBRPE) register to configure the bit timing. To leave the initialization state, the INIT bit must be cleared. Afterwards, the internal Bit Stream Processor (BSP) synchronizes itself to the data transfer on the CAN bus by waiting for the occurrence of a sequence of 11 consecutive recessive bits (indicating a bus idle condition) before it takes part in bus activities and starts message transfers. Message object initialization does not require the CAN to be in the initialization state and can be done on the fly. However, message objects should all be configured to particular identifiers or set to not valid before message transfer starts. To change the configuration of a message object during normal operation, clear the MSGVAL bit in the CANIFnARB2 register to indicate that the message object is not valid during the change. When the configuration is completed, set the MSGVAL bit again to indicate that the message object is once again valid.

### 17.3.2 Operation

Two sets of CAN Interface Registers (**CANIF1x** and **CANIF2x**) are used to access the message objects in the Message RAM. The CAN controller coordinates transfers to and from the Message RAM to and from the registers. The two sets are independent and identical and can be used to queue transactions. Generally, one interface is used to transmit data and one is used to receive data.

Once the CAN module is initialized and the INIT bit in the **CANCTL** register is cleared, the CAN module synchronizes itself to the CAN bus and starts the message transfer. As each message is received, it goes through the message handler's filtering process, and if it passes through the filter, is stored in the message object specified by the MNUM bit in the **CAN IFn Command Request** (**CANIFnCRQ**) register. The whole message (including all arbitration bits, data-length code, and eight data bytes) is stored in the message object. If the Identifier Mask (the MSK bits in the **CAN IFn Mask 1** and **CAN IFn Mask 2** (**CANIFnMSKn**) registers) is used, the arbitration bits that are masked to "don't care" may be overwritten in the message object.

The CPU may read or write each message at any time via the CAN Interface Registers. The message handler guarantees data consistency in case of concurrent accesses.

The transmission of message objects is under the control of the software that is managing the CAN hardware. Message objects can be used for one-time data transfers or can be permanent message objects used to respond in a more periodic manner. Permanent message objects have all arbitration and control set up, and only the data bytes are updated. At the start of transmission, the appropriate TXRQST bit in the CAN Transmission Request n (CANTXRQn) register and the NEWDAT bit in the CAN New Data n (CANNWDAn) register are set. If several transmit messages are assigned to the same message object (when the number of message objects is not sufficient), the whole message object has to be configured before the transmission of this message is requested.

The transmission of any number of message objects may be requested at the same time; they are transmitted according to their internal priority, which is based on the message identifier (MNUM) for the message object, with 1 being the highest priority and 32 being the lowest priority. Messages may be updated or set to not valid any time, even when their requested transmission is still pending. The old data is discarded when a message is updated before its pending transmission has started. Depending on the configuration of the message object, the transmission of a message may be requested autonomously by the reception of a remote frame with a matching identifier.

Transmission can be automatically started by the reception of a matching remote frame. To enable this mode, set the RMTEN bit in the **CAN IFn Message Control (CANIFnMCTL)** register. A matching received remote frame causes the TXRQST bit to be set, and the message object automatically transfers its data or generates an interrupt indicating a remote frame was requested. A remote frame can be strictly a single message identifier, or it can be a range of values specified in the message object. The CAN mask registers, **CANIFnMSKn**, configure which groups of frames are identified as remote frame requests. The UMASK bit in the **CANIFnMCTL** register enables the MSK bits in the **CANIFnMSKn** register to filter which frames are identified as a remote frame request. The MXTD bit in the **CANIFnMSK2** register should be set if a remote frame request is expected to be triggered by 29-bit extended identifiers.

## 17.3.3 Transmitting Message Objects

If the internal transmit shift register of the CAN module is ready for loading, and if a data transfer is not occurring between the CAN Interface Registers and message RAM, the valid message object with the highest priority that has a pending transmission request is loaded into the transmit shift register by the message handler and the transmission is started. The message object's NEWDAT bit in the CANNWDAn register is cleared. After a successful transmission, and if no new data was written to the message object since the start of the transmission, the TXRQST bit in the CANTXRQn register is cleared. If the CAN controller is configured to interrupt on a successful transmission of a message object, (the TXIE bit in the CAN IFn Message Control (CANIFnMCTL) register is set), the INTPND bit in the CANIFnMCTL register is set after a successful transmission. If the CAN module has lost the arbitration or if an error occurred during the transmission, the message is re-transmitted as soon as the CAN bus is free again. If, meanwhile, the transmission of a message with higher priority has been requested, the messages are transmitted in the order of their priority.

### 17.3.4 Configuring a Transmit Message Object

The following steps illustrate how to configure a transmit message object.

- 1. In the CAN IFn Command Mask (CANIFnCMASK) register:
  - Set the WRNRD bit to specify a write to the **CANIFnCMASK** register; specify whether to transfer the IDMASK, DIR, and MXTD of the message object into the **CAN IFn** registers using the MASK bit
  - Specify whether to transfer the ID, DIR, XTD, and MSGVAL of the message object into the interface registers using the ARB bit
  - Specify whether to transfer the control bits into the interface registers using the CONTROL bit
  - Specify whether to clear the INTPND bit in the CANIFnMCTL register using the CLRINTPND bit
  - Specify whether to clear the NEWDAT bit in the CANNWDAn register using the NEWDAT bit
  - Specify which bits to transfer using the DATAA and DATAB bits
- 2. In the CANIFnMSK1 register, use the MSK[15:0] bits to specify which of the bits in the 29-bit or 11-bit message identifier are used for acceptance filtering. Note that MSK[15:0] in this register are used for bits [15:0] of the 29-bit message identifier and are not used for an 11-bit identifier. A value of 0x00 enables all messages to pass through the acceptance filtering. Also

- note that in order for these bits to be used for acceptance filtering, they must be enabled by setting the UMASK bit in the **CANIFnMCTL** register.
- 3. In the CANIFnMSK2 register, use the MSK[12:0] bits to specify which of the bits in the 29-bit or 11-bit message identifier are used for acceptance filtering. Note that MSK[12:0] are used for bits [28:16] of the 29-bit message identifier; whereas MSK[12:2] are used for bits [10:0] of the 11-bit message identifier. Use the MXTD and MDIR bits to specify whether to use XTD and DIR for acceptance filtering. A value of 0x00 enables all messages to pass through the acceptance filtering. Also note that in order for these bits to be used for acceptance filtering, they must be enabled by setting the UMASK bit in the CANIFnMCTL register.
- 4. For a 29-bit identifier, configure ID[15:0] in the CANIFnARB1 register for bits [15:0] of the message identifier and ID[12:0] in the CANIFnARB2 register for bits [28:16] of the message identifier. Set the XTD bit to indicate an extended identifier; set the DIR bit to indicate transmit; and set the MSGVAL bit to indicate that the message object is valid.
- 5. For an 11-bit identifier, disregard the **CANIFnARB1** register and configure ID[12:2] in the **CANIFnARB2** register for bits [10:0] of the message identifier. Clear the XTD bit to indicate a standard identifier; set the DIR bit to indicate transmit; and set the MSGVAL bit to indicate that the message object is valid.
- **6.** In the **CANIFnMCTL** register:
  - Optionally set the UMASK bit to enable the mask (MSK, MXTD, and MDIR specified in the CANIFnMSK1 and CANIFnMSK2 registers) for acceptance filtering
  - Optionally set the TXIE bit to enable the INTPND bit to be set after a successful transmission
  - Optionally set the RMTEN bit to enable the TXRQST bit to be set on the reception of a matching remote frame allowing automatic transmission
  - Set the EOB bit for a single message object
  - Configure the DLC[3:0] field to specify the size of the data frame. Take care during this configuration not to set the NEWDAT, MSGLST, INTPND or TXRQST bits.
- 7. Load the data to be transmitted into the CAN IFn Data (CANIFnDA1, CANIFnDA2, CANIFnDB1, CANIFnDB2) registers. Byte 0 of the CAN data frame is stored in DATA[7:0] in the CANIFnDA1 register.
- 8. Program the number of the message object to be transmitted in the MNUM field in the CAN IFn Command Request (CANIFnCRQ) register.
- 9. When everything is properly configured, set the TXRQST bit in the CANIFnMCTL register. Once this bit is set, the message object is available to be transmitted, depending on priority and bus availability. Note that setting the RMTEN bit in the CANIFnMCTL register can also start message transmission if a matching remote frame has been received.

## 17.3.5 Updating a Transmit Message Object

The CPU may update the data bytes of a Transmit Message Object any time via the CAN Interface Registers and neither the MSGVAL bit in the CANIFnARB2 register nor the TXRQST bits in the CANIFnMCTL register have to be cleared before the update.

Even if only some of the data bytes are to be updated, all four bytes of the corresponding **CANIFnDAn/CANIFnDBn** register have to be valid before the content of that register is transferred to the message object. Either the CPU must write all four bytes into the **CANIFnDAn/CANIFnDBn** register or the message object is transferred to the **CANIFnDAn/CANIFnDBn** register before the CPU writes the new data bytes.

In order to only update the data in a message object, the WRNRD, DATAA and DATAB bits in the **CANIFnMSKn** register are set, followed by writing the updated data into **CANIFnDA1**, **CANIFnDA2**, **CANIFnDB1**, and **CANIFnDB2** registers, and then the number of the message object is written to the MNUM field in the **CAN IFn Command Request (CANIFnCRQ)** register. To begin transmission of the new data as soon as possible, set the TXROST bit in the **CANIFnMSKn** register.

To prevent the clearing of the TXRQST bit in the **CANIFnMCTL** register at the end of a transmission that may already be in progress while the data is updated, the NEWDAT and TXRQST bits have to be set at the same time in the **CANIFnMCTL** register. When these bits are set at the same time, NEWDAT is cleared as soon as the new transmission has started.

### 17.3.6 Accepting Received Message Objects

When the arbitration and control field (the ID and XTD bits in the **CANIFnARB2** and the RMTEN and DLC[3:0] bits of the **CANIFnMCTL** register) of an incoming message is completely shifted into the CAN controller, the message handling capability of the controller starts scanning the message RAM for a matching valid message object. To scan the message RAM for a matching message object, the controller uses the acceptance filtering programmed through the mask bits in the **CANIFnMSKn** register and enabled using the UMASK bit in the **CANIFnMCTL** register. Each valid message object, starting with object 1, is compared with the incoming message to locate a matching message object in the message RAM. If a match occurs, the scanning is stopped and the message handler proceeds depending on whether it is a data frame or remote frame that was received.

# 17.3.7 Receiving a Data Frame

The message handler stores the message from the CAN controller receive shift register into the matching message object in the message RAM. The data bytes, all arbitration bits, and the DLC bits are all stored into the corresponding message object. In this manner, the data bytes are connected with the identifier even if arbitration masks are used. The NEWDAT bit of the CANIFnMCTL register is set to indicate that new data has been received. The CPU should clear this bit when it reads the message object to indicate to the controller that the message has been received, and the buffer is free to receive more messages. If the CAN controller receives a message and the NEWDAT bit is already set, the MSGLST bit in the CANIFnMCTL register is set to indicate that the previous data was lost. If the system requires an interrupt on successful reception of a frame, the RXIE bit of the CANIFnMCTL register should be set. In this case, the INTPND bit of the same register is set, causing the CANINT register to point to the message object that just received a message. The TXRQST bit of this message object should be cleared to prevent the transmission of a remote frame.

#### 17.3.8 Receiving a Remote Frame

A remote frame contains no data, but instead specifies which object should be transmitted. When a remote frame is received, three different configurations of the matching message object have to be considered:

**Table 17-3. Message Object Configurations** 

Со	nfiguration in CANIFnMCTL	Description
-	CANIFnARB2 register	At the reception of a matching remote frame, the TXRQST bit of this message object is set. The rest of the message object remains unchanged, and the controller automatically transfers the data in
	RMTEN = 1 (set the TXRQST bit of the CANIFnMCTL register at reception of the frame to enable transmission)	the message object as soon as possible.
•	UMASK = 1 or 0	
•	DIR = 1 (direction = transmit); programmed in the CANIFnARB2 register	At the reception of a matching remote frame, the TXRQST bit of this message object remains unchanged, and the remote frame is ignored. This remote frame is disabled, the data is not transferred
•	RMTEN = 0 (do not change the TXRQST bit of the CANIFnMCTL register at reception of the frame)	and nothing indicates that the remote frame ever happened.
•	UMASK = 0 (ignore mask in the <b>CANIFnMSKn</b> register)	
•	DIR = 1 (direction = transmit); programmed in the CANIFnARB2 register	At the reception of a matching remote frame, the TXRQST bit of this message object is cleared. The arbitration and control field (ID + XTD + RMTEN + DLC) from the shift register is stored into the message
•	RMTEN = 0 (do not change the TXRQST bit of the CANIFnMCTL register at reception of the frame)	object in the message RAM, and the NEWDAT bit of this message object is set. The data field of the message object remains
•	UMASK = 1 (use mask (MSK, MXTD, and MDIR in the <b>CANIFnMSKn</b> register) for acceptance filtering)	unchanged; the remote frame is treated similar to a received data frame. This mode is useful for a remote data request from another CAN device for which the Stellaris controller does not have readily available data. The software must fill the data and answer the frame manually.

## 17.3.9 Receive/Transmit Priority

The receive/transmit priority for the message objects is controlled by the message number. Message object 1 has the highest priority, while message object 32 has the lowest priority. If more than one transmission request is pending, the message objects are transmitted in order based on the message object with the lowest message number. This prioritization is separate from that of the message identifier which is enforced by the CAN bus. As a result, if message object 1 and message object 2 both have valid messages to be transmitted, message object 1 is always transmitted first regardless of the message identifier in the message object itself.

### 17.3.10 Configuring a Receive Message Object

The following steps illustrate how to configure a receive message object.

- 1. Program the **CAN IFn Command Mask (CANIFnCMASK)** register as described in the "Configuring a Transmit Message Object" on page 876 section, except that the WRNRD bit is set to specify a write to the message RAM.
- 2. Program the CANIFnMSK1 and CANIFnMSK2 registers as described in the "Configuring a Transmit Message Object" on page 876 section to configure which bits are used for acceptance filtering. Note that in order for these bits to be used for acceptance filtering, they must be enabled by setting the UMASK bit in the CANIFnMCTL register.
- 3. In the CANIFnMSK2 register, use the MSK[12:0] bits to specify which of the bits in the 29-bit or 11-bit message identifier are used for acceptance filtering. Note that MSK[12:0] are used for bits [28:16] of the 29-bit message identifier; whereas MSK[12:2] are used for bits [10:0] of the 11-bit message identifier. Use the MXTD and MDIR bits to specify whether to use XTD and

DIR for acceptance filtering. A value of 0x00 enables all messages to pass through the acceptance filtering. Also note that in order for these bits to be used for acceptance filtering, they must be enabled by setting the UMASK bit in the **CANIFNMCTL** register.

- 4. Program the CANIFnARB1 and CANIFnARB2 registers as described in the "Configuring a Transmit Message Object" on page 876 section to program XTD and ID bits for the message identifier to be received; set the MSGVAL bit to indicate a valid message; and clear the DIR bit to specify receive.
- **5.** In the **CANIFnMCTL** register:
  - Optionally set the UMASK bit to enable the mask (MSK, MXTD, and MDIR specified in the CANIFnMSK1 and CANIFnMSK2 registers) for acceptance filtering
  - Optionally set the RXIE bit to enable the INTPND bit to be set after a successful reception
  - Clear the RMTEN bit to leave the TXRQST bit unchanged
  - Set the EOB bit for a single message object
  - Configure the DLC[3:0] field to specify the size of the data frame

Take care during this configuration not to set the NEWDAT, MSGLST, INTPND or TXRQST bits.

**6.** Program the number of the message object to be received in the MNUM field in the **CAN IFn Command Request (CANIFnCRQ)** register. Reception of the message object begins as soon as a matching frame is available on the CAN bus.

When the message handler stores a data frame in the message object, it stores the received Data Length Code and eight data bytes in the **CANIFnDA1**, **CANIFnDA2**, **CANIFnDB1**, and **CANIFnDB2** register. Byte 0 of the CAN data frame is stored in DATA[7:0] in the **CANIFnDA1** register. If the Data Length Code is less than 8, the remaining bytes of the message object are overwritten by unspecified values.

The CAN mask registers can be used to allow groups of data frames to be received by a message object. The CAN mask registers, **CANIFNMSKn**, configure which groups of frames are received by a message object. The UMASK bit in the **CANIFNMCTL** register enables the MSK bits in the **CANIFNMSKn** register to filter which frames are received. The MXTD bit in the **CANIFNMSK2** register should be set if only 29-bit extended identifiers are expected by this message object.

### 17.3.11 Handling of Received Message Objects

The CPU may read a received message any time via the CAN Interface registers because the data consistency is guaranteed by the message handler state machine.

Typically, the CPU first writes 0x007F to the **CANIFnCMSK** register and then writes the number of the message object to the **CANIFnCRQ** register. That combination transfers the whole received message from the message RAM into the Message Buffer registers (**CANIFnMSKn**, **CANIFnARBn**, and **CANIFnMCTL**). Additionally, the NEWDAT and INTPND bits are cleared in the message RAM, acknowledging that the message has been read and clearing the pending interrupt generated by this message object.

If the message object uses masks for acceptance filtering, the **CANIFnARBn** registers show the full, unmasked ID for the received message.

The NEWDAT bit in the **CANIFnMCTL** register shows whether a new message has been received since the last time this message object was read. The MSGLST bit in the **CANIFnMCTL** register shows whether more than one message has been received since the last time this message object was read. MSGLST is not automatically cleared, and should be cleared by software after reading its status.

Using a remote frame, the CPU may request new data from another CAN node on the CAN bus. Setting the TXRQST bit of a receive object causes the transmission of a remote frame with the receive object's identifier. This remote frame triggers the other CAN node to start the transmission of the matching data frame. If the matching data frame is received before the remote frame could be transmitted, the TXRQST bit is automatically reset. This prevents the possible loss of data when the other device on the CAN bus has already transmitted the data slightly earlier than expected.

### 17.3.11.1 Configuration of a FIFO Buffer

With the exception of the EOB bit in the **CANIFnMCTL** register, the configuration of receive message objects belonging to a FIFO buffer is the same as the configuration of a single receive message object (see "Configuring a Receive Message Object" on page 879). To concatenate two or more message objects into a FIFO buffer, the identifiers and masks (if used) of these message objects have to be programmed to matching values. Due to the implicit priority of the message objects, the message object with the lowest message object number is the first message object in a FIFO buffer. The EOB bit of all message objects of a FIFO buffer except the last one must be cleared. The EOB bit of the last message object of a FIFO buffer is set, indicating it is the last entry in the buffer.

### 17.3.11.2 Reception of Messages with FIFO Buffers

Received messages with identifiers matching to a FIFO buffer are stored starting with the message object with the lowest message number. When a message is stored into a message object of a FIFO buffer, the NEWDAT of the **CANIFNMCTL** register bit of this message object is set. By setting NEWDAT while EOB is clear, the message object is locked and cannot be written to by the message handler until the CPU has cleared the NEWDAT bit. Messages are stored into a FIFO buffer until the last message object of this FIFO buffer is reached. Until all of the preceding message objects have been released by clearing the NEWDAT bit, all further messages for this FIFO buffer are written into the last message object of the FIFO buffer and therefore overwrite previous messages.

#### 17.3.11.3 Reading from a FIFO Buffer

When the CPU transfers the contents of a message object from a FIFO buffer by writing its number to the CANIFnCRQ register, the TXRQST and CLRINTPND bits in the CANIFnCMSK register should be set such that the NEWDAT and INTPEND bits in the CANIFnMCTL register are cleared after the read. The values of these bits in the CANIFnMCTL register always reflect the status of the message object before the bits are cleared. To assure the correct function of a FIFO buffer, the CPU should read out the message objects starting with the message object with the lowest message number. When reading from the FIFO buffer, the user should be aware that a new received message is placed in the message object with the lowest message number for which the NEWDAT bit of the CANIFnMCTL register is clear. As a result, the order of the received messages in the FIFO is not guaranteed. Figure 17-3 on page 882 shows how a set of message objects which are concatenated to a FIFO Buffer can be handled by the CPU.




Figure 17-3. Message Objects in a FIFO Buffer

## 17.3.12 Handling of Interrupts

If several interrupts are pending, the **CAN Interrupt (CANINT)** register points to the pending interrupt with the highest priority, disregarding their chronological order. The status interrupt has the highest

priority. Among the message interrupts, the message object's interrupt with the lowest message number has the highest priority. A message interrupt is cleared by clearing the message object's INTPND bit in the **CANIFNMCTL** register or by reading the **CAN Status (CANSTS)** register. The status Interrupt is cleared by reading the **CANSTS** register.

The interrupt identifier INTID in the **CANINT** register indicates the cause of the interrupt. When no interrupt is pending, the register reads as 0x0000. If the value of the INTID field is different from 0, then an interrupt is pending. If the IE bit is set in the **CANCTL** register, the interrupt line to the interrupt controller is active. The interrupt line remains active until the INTID field is 0, meaning that all interrupt sources have been cleared (the cause of the interrupt is reset), or until IE is cleared, which disables interrupts from the CAN controller.

The INTID field of the **CANINT** register points to the pending message interrupt with the highest interrupt priority. The SIE bit in the **CANCTL** register controls whether a change of the RXOK, TXOK, and LEC bits in the **CANSTS** register can cause an interrupt. The EIE bit in the **CANCTL**register controls whether a change of the BOFF and EWARN bits in the **CANSTS** register can cause an interrupt. The IE bit in the **CANCTL** register controls whether any interrupt from the CAN controller actually generates an interrupt to the interrupt controller. The **CANINT** register is updated even when the IE bit in the **CANCTL** register is clear, but the interrupt is not indicated to the CPU.

A value of 0x8000 in the **CANINT** register indicates that an interrupt is pending because the CAN module has updated, but not necessarily changed, the **CANSTS** register, indicating that either an error or status interrupt has been generated. A write access to the **CANSTS** register can clear the RXOK, TXOK, and LEC bits in that same register; however, the only way to clear the source of a status interrupt is to read the **CANSTS** register.

The source of an interrupt can be determined in two ways during interrupt handling. The first is to read the INTID bit in the **CANINT** register to determine the highest priority interrupt that is pending, and the second is to read the **CAN Message Interrupt Pending (CANMSGnINT)** register to see all of the message objects that have pending interrupts.

An interrupt service routine reading the message that is the source of the interrupt may read the message and clear the message object's INTPND bit at the same time by setting the CLRINTPND bit in the **CANIFTCMSK** register. Once the INTPND bit has been cleared, the **CANINT** register contains the message number for the next message object with a pending interrupt.

#### 17.3.13 Test Mode

A Test Mode is provided which allows various diagnostics to be performed. Test Mode is entered by setting the TEST bit in the **CANCTL** register. Once in Test Mode, the TX[1:0], LBACK, SILENT and BASIC bits in the **CAN Test (CANTST)** register can be used to put the CAN controller into the various diagnostic modes. The RX bit in the **CANTST** register allows monitoring of the CANNRX signal. All **CANTST** register functions are disabled when the TEST bit is cleared.

#### 17.3.13.1 Silent Mode

Silent Mode can be used to analyze the traffic on a CAN bus without affecting it by the transmission of dominant bits (Acknowledge Bits, Error Frames). The CAN Controller is put in Silent Mode setting the SILENT bit in the **CANTST** register. In Silent Mode, the CAN controller is able to receive valid data frames and valid remote frames, but it sends only recessive bits on the CAN bus and cannot start a transmission. If the CAN Controller is required to send a dominant bit (ACK bit, overload flag, or active error flag), the bit is rerouted internally so that the CAN Controller monitors this dominant bit, although the CAN bus remains in recessive state.

#### 17.3.13.2 Loopback Mode

Loopback mode is useful for self-test functions. In Loopback Mode, the CAN Controller internally routes the CANnTX signal on to the CANnRX signal and treats its own transmitted messages as received messages and stores them (if they pass acceptance filtering) into the message buffer. The CAN Controller is put in Loopback Mode by setting the LBACK bit in the **CANTST** register. To be independent from external stimulation, the CAN Controller ignores acknowledge errors (a recessive bit sampled in the acknowledge slot of a data/remote frame) in Loopback Mode. The actual value of the CANNRX signal is disregarded by the CAN Controller. The transmitted messages can be monitored on the CANnTX signal.

#### 17.3.13.3 Loopback Combined with Silent Mode

Loopback Mode and Silent Mode can be combined to allow the CAN Controller to be tested without affecting a running CAN system connected to the CANnTX and CANnRX signals. In this mode, the CANnRX signal is disconnected from the CAN Controller and the CANnTX signal is held recessive. This mode is enabled by setting both the LBACK and SILENT bits in the **CANTST** register.

#### 17.3.13.4 Basic Mode

Basic Mode allows the CAN Controller to be operated without the Message RAM. In Basic Mode, The CANIF1 registers are used as the transmit buffer. The transmission of the contents of the IF1 registers is requested by setting the BUSY bit of the **CANIF1CRQ** register. The CANIF1 registers are locked while the BUSY bit is set. The BUSY bit indicates that a transmission is pending. As soon the CAN bus is idle, the CANIF1 registers are loaded into the shift register of the CAN Controller and transmission is started. When the transmission has completed, the BUSY bit is cleared and the locked CANIF1 registers are released. A pending transmission can be aborted at any time by clearing the BUSY bit in the **CANIF1CRQ** register while the CANIF1 registers are locked. If the CPU has cleared the BUSY bit, a possible retransmission in case of lost arbitration or an error is disabled.

The CANIF2 Registers are used as a receive buffer. After the reception of a message, the contents of the shift register are stored in the CANIF2 registers, without any acceptance filtering. Additionally, the actual contents of the shift register can be monitored during the message transfer. Each time a read message object is initiated by setting the BUSY bit of the **CANIF2CRQ** register, the contents of the shift register are stored into the CANIF2 registers.

In Basic Mode, all message-object-related control and status bits and of the control bits of the **CANIFnCMSK** registers are not evaluated. The message number of the **CANIFnCRQ** registers is also not evaluated. In the **CANIF2MCTL** register, the NEWDAT and MSGLST bits retain their function, the DLC[3:0] field shows the received DLC, the other control bits are cleared.

Basic Mode is enabled by setting the BASIC bit in the CANTST register.

#### 17.3.13.5 Transmit Control

Software can directly override control of the CANnTX signal in four different ways.

- CANnTX is controlled by the CAN Controller
- The sample point is driven on the CANnTX signal to monitor the bit timing
- CANnTX drives a low value
- CANnTX drives a high value

The last two functions, combined with the readable CAN receive pin CANnRX, can be used to check the physical layer of the CAN bus.

The Transmit Control function is enabled by programming the  $\mathtt{TX[1:0]}$  field in the **CANTST** register. The three test functions for the CANnTX signal interfere with all CAN protocol functions.  $\mathtt{TX[1:0]}$  must be cleared when CAN message transfer or Loopback Mode, Silent Mode, or Basic Mode are selected.

### 17.3.14 Bit Timing Configuration Error Considerations

Even if minor errors in the configuration of the CAN bit timing do not result in immediate failure, the performance of a CAN network can be reduced significantly. In many cases, the CAN bit synchronization amends a faulty configuration of the CAN bit timing to such a degree that only occasionally an error frame is generated. In the case of arbitration, however, when two or more CAN nodes simultaneously try to transmit a frame, a misplaced sample point may cause one of the transmitters to become error passive. The analysis of such sporadic errors requires a detailed knowledge of the CAN bit synchronization inside a CAN node and of the CAN nodes' interaction on the CAN bus.

#### 17.3.15 Bit Time and Bit Rate

The CAN system supports bit rates in the range of lower than 1 Kbps up to 1000 Kbps. Each member of the CAN network has its own clock generator. The timing parameter of the bit time can be configured individually for each CAN node, creating a common bit rate even though the CAN nodes' oscillator periods may be different.

Because of small variations in frequency caused by changes in temperature or voltage and by deteriorating components, these oscillators are not absolutely stable. As long as the variations remain inside a specific oscillator's tolerance range, the CAN nodes are able to compensate for the different bit rates by periodically resynchronizing to the bit stream.

According to the CAN specification, the bit time is divided into four segments (see Figure 17-4 on page 886): the Synchronization Segment, the Propagation Time Segment, the Phase Buffer Segment 1, and the Phase Buffer Segment 2. Each segment consists of a specific, programmable number of time quanta (see Table 17-4 on page 886). The length of the time quantum ( $t_q$ ), which is the basic time unit of the bit time, is defined by the CAN controller's input clock ( $f_{\rm SYS}$ ) and the Baud Rate Prescaler (BRP):

$$t_q = BRP / fsys$$

The fsys input clock is the system clock frequency as configured by the **RCC** or **RCC2** registers (see page 221 or page 229).

The Synchronization Segment Sync is that part of the bit time where edges of the CAN bus level are expected to occur; the distance between an edge that occurs outside of Sync and the Sync is called the phase error of that edge.

The Propagation Time Segment Prop is intended to compensate for the physical delay times within the CAN network.

The Phase Buffer Segments Phase1 and Phase2 surround the Sample Point.

The (Re-)Synchronization Jump Width (SJW) defines how far a resynchronization may move the Sample Point inside the limits defined by the Phase Buffer Segments to compensate for edge phase errors.

A given bit rate may be met by different bit-time configurations, but for the proper function of the CAN network, the physical delay times and the oscillator's tolerance range have to be considered.

Figure 17-4. CAN Bit Time




Table 17-4. CAN Protocol Ranges<sup>a</sup>

Parameter	Range	Remark
BRP	[1 64]	Defines the length of the time quantum $t_{\rm q}$ . The <b>CANBRPE</b> register can be used to extend the range to 1024.
Sync	1 t <sub>q</sub>	Fixed length, synchronization of bus input to system clock
Prop	[1 8] t <sub>q</sub>	Compensates for the physical delay times
Phase1	[1 8] t <sub>q</sub>	May be lengthened temporarily by synchronization
Phase2	[1 8] t <sub>q</sub>	May be shortened temporarily by synchronization
SJW	[1 4] t <sub>q</sub>	May not be longer than either Phase Buffer Segment

a. This table describes the minimum programmable ranges required by the CAN protocol.

The bit timing configuration is programmed in two register bytes in the **CANBIT** register. In the **CANBIT** register, the four components TSEG2, TSEG1, SJW, and BRP have to be programmed to a numerical value that is one less than its functional value; so instead of values in the range of [1..n], values in the range of [0..n-1] are programmed. That way, for example, SJW (functional range of [1..4]) is represented by only two bits in the SJW bit field. Table 17-5 shows the relationship between the **CANBIT** register values and the parameters.

**Table 17-5. CANBIT Register Values** 

CANBIT Register Field	Setting
TSEG2	Phase2 - 1
TSEG1	Prop + Phase1 - 1
SJW	SJW - 1
BRP	BRP

Therefore, the length of the bit time is (programmed values):

[TSEG1 + TSEG2 + 3] 
$$\times$$
 t<sub>q</sub> or (functional values):   
 [Sync + Prop + Phase1 + Phase2]  $\times$  t<sub>q</sub>

The data in the **CANBIT** register is the configuration input of the CAN protocol controller. The baud rate prescaler (configured by the BRP field) defines the length of the time quantum, the basic time

unit of the bit time; the bit timing logic (configured by TSEG1, TSEG2, and SJW) defines the number of time quanta in the bit time.

The processing of the bit time, the calculation of the position of the sample point, and occasional synchronizations are controlled by the CAN controller and are evaluated once per time quantum.

The CAN controller translates messages to and from frames. In addition, the controller generates and discards the enclosing fixed format bits, inserts and extracts stuff bits, calculates and checks the CRC code, performs the error management, and decides which type of synchronization is to be used. The bit value is received or transmitted at the sample point. The information processing time (IPT) is the time after the sample point needed to calculate the next bit to be transmitted on the CAN bus. The IPT includes any of the following: retrieving the next data bit, handling a CRC bit, determining if bit stuffing is required, generating an error flag or simply going idle.

The IPT is application-specific but may not be longer than 2  $t_q$ ; the CAN's IPT is 0  $t_q$ . Its length is the lower limit of the programmed length of Phase2. In case of synchronization, Phase2 may be shortened to a value less than IPT, which does not affect bus timing.

## 17.3.16 Calculating the Bit Timing Parameters

Usually, the calculation of the bit timing configuration starts with a required bit rate or bit time. The resulting bit time (1/bit rate) must be an integer multiple of the system clock period.

The bit time may consist of 4 to 25 time quanta. Several combinations may lead to the required bit time, allowing iterations of the following steps.

The first part of the bit time to be defined is Prop. Its length depends on the delay times measured in the system. A maximum bus length as well as a maximum node delay has to be defined for expandable CAN bus systems. The resulting time for Prop is converted into time quanta (rounded up to the nearest integer multiple of  $t_{\alpha}$ ).

Sync is 1  $t_q$  long (fixed), which leaves (bit time - Prop - 1)  $t_q$  for the two Phase Buffer Segments. If the number of remaining  $t_q$  is even, the Phase Buffer Segments have the same length, that is, Phase2 = Phase1, else Phase2 = Phase1 + 1.

The minimum nominal length of Phase2 has to be regarded as well. Phase2 may not be shorter than the CAN controller's Information Processing Time, which is, depending on the actual implementation, in the range of  $[0..2] t_n$ .

The length of the synchronization jump width is set to the least of 4, Phase1 or Phase2.

The oscillator tolerance range necessary for the resulting configuration is calculated by the formula given below:

$$(1 - df) \times fnom \leq fosc \leq (1 + df) \times fnom$$

#### where:

- df = Maximum tolerance of oscillator frequency
- fosc = Actual oscillator frequency
- fnom = Nominal oscillator frequency

Maximum frequency tolerance must take into account the following formulas:

$$df \le \frac{(Phase\_seg1, Phase\_seg2) \min}{2 \times (13 \times tbit - Phase\_Seg2)}$$

$$df \max = 2 \times df \times fnom$$

#### where:

- Phase1 and Phase2 are from Table 17-4 on page 886
- tbit = Bit Time
- dfmax = Maximum difference between two oscillators

If more than one configuration is possible, that configuration allowing the highest oscillator tolerance range should be chosen.

CAN nodes with different system clocks require different configurations to come to the same bit rate. The calculation of the propagation time in the CAN network, based on the nodes with the longest delay times, is done once for the whole network.

The CAN system's oscillator tolerance range is limited by the node with the lowest tolerance range.

The calculation may show that bus length or bit rate have to be decreased or that the oscillator frequencies' stability has to be increased in order to find a protocol-compliant configuration of the CAN bit timing.

### 17.3.16.1 Example for Bit Timing at High Baud Rate

In this example, the frequency of CAN clock is 25 MHz, and the bit rate is 1 Mbps.

```
bit time = 1 \mus = n * t<sub>q</sub> = 5 * t<sub>q</sub>
t_{\alpha} = 200 \text{ ns}
t_q = (Baud rate Prescaler)/CAN Clock
Baud rate Prescaler = t_q * CAN Clock
Baud rate Prescaler = 200E-9 * 25E6 = 5
tSync = 1 * t_q = 200 ns
                                           \\fixed at 1 time quanta
delay of bus driver 50 ns
delay of receiver circuit 30 ns
delay of bus line (40m) 220 ns
tProp 400 ns = 2 * t_{\alpha}
                                           \ is next integer multiple of t_{\alpha}
bit time = tSync + tTSeg1 + tTSeg2 = 5 * t_q
bit time = tSync + tProp + tPhase 1 + tPhase2
tPhase 1 + tPhase2 = bit time - tSync - tProp
tPhase 1 + tPhase 2 = (5 * t_q) - (1 * t_q) - (2 * t_q)
tPhase 1 + tPhase2 = 2 * t_{\alpha}
tPhase1 = 1 * t_{\alpha}
tPhase2 = 1 * t_g
                                           \\tPhase2 = tPhase1
```

In the above example, the bit field values for the **CANBIT** register are:

TSEG2	= TSeg2 -1
	= 1-1
	= 0
TSEG1	= TSeg1 -1
	= 3-1
	= 2
SJW	= SJW -1
	= 1-1
	= 0
BRP	= Baud rate prescaler - 1
	= 5-1
	=4

The final value programmed into the **CANBIT** register = 0x0204.

#### 17.3.16.2 Example for Bit Timing at Low Baud Rate

In this example, the frequency of the CAN clock is 50 MHz, and the bit rate is 100 Kbps.

```
bit time = 10 \mus = n * t<sub>q</sub> = 10 * t<sub>q</sub>
t_q = 1 \mu s
t<sub>q</sub> = (Baud rate Prescaler)/CAN Clock
Baud rate Prescaler = t_q * CAN Clock
Baud rate Prescaler = 1E-6 * 50E6 = 50
tSync = 1 * t_q = 1 \mu s
                                          \\fixed at 1 time quanta
delay of bus driver 200 ns
delay of receiver circuit 80 ns
delay of bus line (40m) 220 ns
tProp 1 \mus = 1 * t<sub>q</sub>
                                          \label{eq:lambda} 1 \mu s is next integer multiple of t_{q}
bit time = tSync + tTSeg1 + tTSeg2 = 10 * t_q
bit time = tSync + tProp + tPhase 1 + tPhase2
tPhase 1 + tPhase2 = bit time - tSync - tProp
tPhase 1 + tPhase 2 = (10 * t_q) - (1 * t_q) - (1 * t_q)
tPhase 1 + tPhase 2 = 8 * t_{q}
tPhase1 = 4 * t_q
tPhase2 = 4 * t_{g}
                                          \\tPhase1 = tPhase2
```

TSEG2	= TSeg2 -1
	= 4-1
	= 3
TSEG1	= TSeg1 -1
	= 5-1
	= 4
SJW	= SJW -1
	= 4-1
	= 3
BRP	= Baud rate prescaler - 1
	= 50-1
	=49

The final value programmed into the **CANBIT** register = 0x34F1.

# 17.4 Register Map

Table 17-6 on page 890 lists the registers. All addresses given are relative to the CAN base address of:

CAN0: 0x4004.0000CAN1: 0x4004.1000

Note that the CAN controller clock must be enabled before the registers can be programmed (see page 264). There must be a delay of 3 system clocks after the CAN module clock is enabled before any CAN module registers are accessed.

Table 17-6. CAN Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	CANCTL	R/W	0x0000.0001	CAN Control	893
0x004	CANSTS	R/W	0x0000.0000	CAN Status	895
0x008	CANERR	RO	0x0000.0000	CAN Error Counter	898
0x00C	CANBIT	R/W	0x0000.2301	CAN Bit Timing	899
0x010	CANINT	RO	0x0000.0000	CAN Interrupt	900
0x014	CANTST	R/W	0x0000.0000	CAN Test	901
0x018	CANBRPE	R/W	0x0000.0000	CAN Baud Rate Prescaler Extension	903
0x020	CANIF1CRQ	R/W	0x0000.0001	CAN IF1 Command Request	904

Table 17-6. CAN Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x024	CANIF1CMSK	R/W	0x0000.0000	CAN IF1 Command Mask	905
0x028	CANIF1MSK1	R/W	0x0000.FFFF	CAN IF1 Mask 1	908
0x02C	CANIF1MSK2	R/W	0x0000.FFFF	CAN IF1 Mask 2	909
0x030	CANIF1ARB1	R/W	0x0000.0000	CAN IF1 Arbitration 1	911
0x034	CANIF1ARB2	R/W	0x0000.0000	CAN IF1 Arbitration 2	912
0x038	CANIF1MCTL	R/W	0x0000.0000	CAN IF1 Message Control	914
0x03C	CANIF1DA1	R/W	0x0000.0000	CAN IF1 Data A1	917
0x040	CANIF1DA2	R/W	0x0000.0000	CAN IF1 Data A2	917
0x044	CANIF1DB1	R/W	0x0000.0000	CAN IF1 Data B1	917
0x048	CANIF1DB2	R/W	0x0000.0000	CAN IF1 Data B2	917
0x080	CANIF2CRQ	R/W	0x0000.0001	CAN IF2 Command Request	904
0x084	CANIF2CMSK	R/W	0x0000.0000	CAN IF2 Command Mask	905
0x088	CANIF2MSK1	R/W	0x0000.FFFF	CAN IF2 Mask 1	908
0x08C	CANIF2MSK2	R/W	0x0000.FFFF	CAN IF2 Mask 2	909
0x090	CANIF2ARB1	R/W	0x0000.0000	CAN IF2 Arbitration 1	911
0x094	CANIF2ARB2	R/W	0x0000.0000	CAN IF2 Arbitration 2	912
0x098	CANIF2MCTL	R/W	0x0000.0000	CAN IF2 Message Control	914
0x09C	CANIF2DA1	R/W	0x0000.0000	CAN IF2 Data A1	917
0x0A0	CANIF2DA2	R/W	0x0000.0000	CAN IF2 Data A2	917
0x0A4	CANIF2DB1	R/W	0x0000.0000	CAN IF2 Data B1	917
0x0A8	CANIF2DB2	R/W	0x0000.0000	CAN IF2 Data B2	917
0x100	CANTXRQ1	RO	0x0000.0000	CAN Transmission Request 1	918
0x104	CANTXRQ2	RO	0x0000.0000	CAN Transmission Request 2	918
0x120	CANNWDA1	RO	0x0000.0000	CAN New Data 1	919
0x124	CANNWDA2	RO	0x0000.0000	CAN New Data 2	919
0x140	CANMSG1INT	RO	0x0000.0000	CAN Message 1 Interrupt Pending	920
0x144	CANMSG2INT	RO	0x0000.0000	CAN Message 2 Interrupt Pending	920
0x160	CANMSG1VAL	RO	0x0000.0000	CAN Message 1 Valid	921
0x164	CANMSG2VAL	RO	0x0000.0000	CAN Message 2 Valid	921
	1			The state of the s	

# 17.5 CAN Register Descriptions

The remainder of this section lists and describes the CAN registers, in numerical order by address offset. There are two sets of Interface Registers that are used to access the Message Objects in

the Message RAM: **CANIF1x** and **CANIF2x**. The function of the two sets are identical and are used to queue transactions.

# Register 1: CAN Control (CANCTL), offset 0x000

This control register initializes the module and enables test mode and interrupts.

The bus-off recovery sequence (see CAN Specification Rev. 2.0) cannot be shortened by setting or clearing INIT. If the device goes bus-off, it sets INIT, stopping all bus activities. Once INIT has been cleared by the CPU, the device then waits for 129 occurrences of Bus Idle (129 \* 11 consecutive High bits) before resuming normal operations. At the end of the bus-off recovery sequence, the Error Management Counters are reset.


During the waiting time after INIT is cleared, each time a sequence of 11 High bits has been monitored, a BITERROR0 code is written to the **CANSTS** register (the LEC field = 0x5), enabling the CPU to readily check whether the CAN bus is stuck Low or continuously disturbed, and to monitor the proceeding of the bus-off recovery sequence.

#### CAN Control (CANCTL)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x000

Type R/W, reset 0x0000.0001



Bit/Field	Name	Туре	Reset	Description	n		
31:8	reserved	RO	0x0000.00	compatibil	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.		
7	TEST	R/W	0	Test Mode	Enable		
				Value	Description		
				0	The CAN controller is operating normally.		
				1	The CAN controller is in test mode.		
6	CCE	R/W	0	Configurat	ion Change Enable		
				Value	Description		
				0	Write accesses to the <b>CANBIT</b> register are not allowed.		
				1	Write accesses to the <b>CANBIT</b> register are allowed if the INIT bit is 1.		
5	DAR	R/W	0	Disable Au	utomatic-Retransmission		
				Value	Description		
				0	Auto-retransmission of disturbed messages is enabled.		
				1	Auto-retransmission is disabled.		

Bit/Field	Name	Туре	Reset	Descripti	ion
4	reserved	RO	0	compatib	e should not rely on the value of a reserved bit. To provide collity with future products, the value of a reserved bit should be across a read-modify-write operation.
3	EIE	R/W	0	Error Inte	errupt Enable
				Value	Description
				0	No error status interrupt is generated.
				1	A change in the BOFF or EWARN bits in the <b>CANSTS</b> register generates an interrupt.
2	SIE	R/W	0	Status In	nterrupt Enable
				Value	Description
				0	No status interrupt is generated.
				1	An interrupt is generated when a message has successfully been transmitted or received, or a CAN bus error has been detected. A change in the TXOK, RXOK or LEC bits in the CANSTS register generates an interrupt.
1	IE	R/W	0	CAN Inte	errupt Enable
				Value	Description
				0	Interrupts disabled.
				1	Interrupts enabled.
0	INIT	R/W	1	Initializat	tion
				Value	Description
				0	Normal operation.
				1	Initialization started.

### Register 2: CAN Status (CANSTS), offset 0x004

**Important:** This register is read-sensitive. See the register description for details.

The status register contains information for interrupt servicing such as Bus-Off, error count threshold, and error types.

The LEC field holds the code that indicates the type of the last error to occur on the CAN bus. This field is cleared when a message has been transferred (reception or transmission) without error. The unused error code 0x7 may be written by the CPU to manually set this field to an invalid error so that it can be checked for a change later.


An error interrupt is generated by the BOFF and EWARN bits, and a status interrupt is generated by the RXOK, TXOK, and LEC bits, if the corresponding enable bits in the **CAN Control (CANCTL)** register are set. A change of the EPASS bit or a write to the RXOK, TXOK, or LEC bits does not generate an interrupt.

Reading the **CAN Status (CANSTS)** register clears the **CAN Interrupt (CANINT)** register, if it is pending.

#### CAN Status (CANSTS)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x004 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description	n
31:8	reserved	RO	0x0000.00	compatibili	should not rely on the value of a reserved bit. To provide ity with future products, the value of a reserved bit should be across a read-modify-write operation.
7	BOFF	RO	0	Bus-Off St	atus
				Value	Description
				0	The CAN controller is not in bus-off state.
				1	The CAN controller is in bus-off state.
6	EWARN	RO	0	Warning S	tatus
				Value	Description
				0	Both error counters are below the error warning limit of 96.
				1	At least one of the error counters has reached the error warning limit of 96.

Bit/Field	Name	Туре	Reset	Description	on
5	EPASS	RO	0	Error Pas	sive
				Value	Description
				0	The CAN module is in the Error Active state, that is, the receive or transmit error count is less than or equal to 127.
				1	The CAN module is in the Error Passive state, that is, the receive or transmit error count is greater than 127.
4	RXOK	R/W	0	Received	a Message Successfully
				Value	Description
				0	Since this bit was last cleared, no message has been successfully received.
				1	Since this bit was last cleared, a message has been successfully received, independent of the result of the acceptance filtering.
				This bit m	ust be cleared by writing a 0 to it.
3	TXOK	R/W	0	Transmitte	ed a Message Successfully
				Value	Description
				0	Since this bit was last cleared, no message has been successfully transmitted.
				1	Since this bit was last cleared, a message has been successfully transmitted error-free and acknowledged by at least one other node.

This bit must be cleared by writing a 0 to it.

Bit/Field	Name	Туре	Reset	Descript	ion
2:0	LEC	R/W	0x0	Last Erro	or Code
				This is th	ne type of the last error to occur on the CAN bus.
				Value	Description
				0x0	No Error
				0x1	Stuff Error
					More than 5 equal bits in a sequence have occurred in a part of a received message where this is not allowed.
				0x2	Format Error
					A fixed format part of the received frame has the wrong format.
				0x3	ACK Error
					The message transmitted was not acknowledged by another node.
				0x4	Bit 1 Error
					When a message is transmitted, the CAN controller monitors the data lines to detect any conflicts. When the arbitration field is transmitted, data conflicts are a part of the arbitration protocol. When other frame fields are transmitted, data conflicts are considered errors.
					A Bit 1 Error indicates that the device wanted to send a High level (logical 1) but the monitored bus value was Low (logical 0).
				0x5	Bit 0 Error
					A Bit 0 Error indicates that the device wanted to send a Low level (logical 0), but the monitored bus value was High (logical 1).
					During bus-off recovery, this status is set each time a sequence of 11 High bits has been monitored. By checking for this status, software can monitor the proceeding of the bus-off recovery sequence without any disturbances to the bus.
				0x6	CRC Error
					The CRC checksum was incorrect in the received message, indicating that the calculated value received did not match the calculated CRC of the data.
				0x7	No Event
					When the LEC bit shows this value, no CAN bus event was detected since this value was written to the LEC field.

# Register 3: CAN Error Counter (CANERR), offset 0x008

This register contains the error counter values, which can be used to analyze the cause of an error.

### CAN Error Counter (CANERR)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x008

Type RO, reset 0x0000.0000

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	î	1				1	rese	rved	1		ı				
RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Ü	Ü	0	0	0	Ü	0	Ü	0	0	0	0	0	0	U	0
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
RP				REC					•		TE	EC			
RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO 0
U	U	U	U	U	U	U	U	U	U	U	U	U	U	U	U
);t/F;ald		Nom		T		Dooot	Doo	orintion							
sil/Field		ivan	ie	ιyμ	Эе	Reset	Des	cription							
31:16		reser	ved	R	)	0x0000									
														ed bit sh	nould be
							pres	erveu a	U1055 a 1	eau-mod	ally-write	operation	л.		
15		RP	•	R	)	0	Rec	eived Er	ror Pass	ive					
							Valu	ne	Descrip	otion					
							0					ter is bel	ow the E	Error Pas	ssive
							1					er has re	ached th	ne Error	Passive
14:8		REG	0	R	)	0x00	Rec	eive Erro	or Count	er					
							This	field co	ntains th	e state o	of the rec	eiver err	or count	er (0 to	127).
7:0		TEC		R	)	0x00	Tran	nsmit Err	or Count	ter					
	RO 0 15 RP RO 0 31:16 15:14:8	RO RO 0 15 14 RP RO 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	RO RO RO O O O O O O O O O O O O O O O	RO RO RO RO O O O O O O O O O O O O O O	RO         RO<	RO         RO<	RO         O	RO	RO	RO	RO	RO	RO R	RO R	RO R

This field contains the state of the transmit error counter (0 to 255).

## Register 4: CAN Bit Timing (CANBIT), offset 0x00C


This register is used to program the bit width and bit quantum. Values are programmed to the system clock frequency. This register is write-enabled by setting the CCE and INIT bits in the **CANCTL** register. See "Bit Time and Bit Rate" on page 885 for more information.

#### CAN Bit Timing (CANBIT)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x00C

Type R/W, reset 0x0000.2301



Bit/Field	Name	Type	Reset	Description
31:15	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
14:12	TSEG2	R/W	0x2	Time Segment after Sample Point
				0x00-0x07: The actual interpretation by the hardware of this value is such that one more than the value programmed here is used.
				So, for example, the reset value of 0x2 means that 3 (2+1) bit time quanta are defined for <code>Phase2</code> (see Figure 17-4 on page 886). The bit time quanta is defined by the <code>BRP</code> field.
11:8	TSEG1	R/W	0x3	Time Segment Before Sample Point
				0x00-0x0F: The actual interpretation by the hardware of this value is such that one more than the value programmed here is used.
				So, for example, the reset value of 0x3 means that 4 (3+1) bit time quanta are defined for <code>Phasel</code> (see Figure 17-4 on page 886). The bit time quanta is defined by the <code>BRP</code> field.
7:6	SJW	R/W	0x0	(Re)Synchronization Jump Width
				0x00-0x03: The actual interpretation by the hardware of this value is such that one more than the value programmed here is used.
				During the start of frame (SOF), if the CAN controller detects a phase error (misalignment), it can adjust the length of ${ t TSEG2}$ or ${ t TSEG1}$ by the value in ${ t SJW}$ . So the reset value of 0 adjusts the length by 1 bit time quanta.
5:0	BRP	R/W	0x1	Baud Rate Prescaler
				The value by which the oscillator frequency is divided for generating the bit time quanta. The bit time is built up from a multiple of this quantum.
				0x00-0x03F: The actual interpretation by the hardware of this value is such that one more than the value programmed here is used.
				${\tt BRP}$ defines the number of CAN clock periods that make up 1 bit time quanta, so the reset value is 2 bit time quanta (1+1).

The **CANBRPE** register can be used to further divide the bit time.

## Register 5: CAN Interrupt (CANINT), offset 0x010

This register indicates the source of the interrupt.

If several interrupts are pending, the **CAN Interrupt (CANINT)** register points to the pending interrupt with the highest priority, disregarding the order in which the interrupts occurred. An interrupt remains pending until the CPU has cleared it. If the <code>INTID</code> field is not 0x0000 (the default) and the <code>IE</code> bit in the **CANCTL** register is set, the interrupt is active. The interrupt line remains active until the <code>INTID</code> field is cleared by reading the **CANSTS** register, or until the <code>IE</code> bit in the **CANCTL** register is cleared.


**Note:** Reading the **CAN Status (CANSTS)** register clears the **CAN Interrupt (CANINT)** register, if it is pending.

#### CAN Interrupt (CANINT)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x010

Type RO, reset 0x0000.0000



Bit/Field	Name	туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	INTID	RO	0x0000	Interrupt Identifier

The number in this field indicates the source of the interrupt.

Value Description

0x0000 No interrupt pending

0x0001-0x0020 Number of the message object that

caused the interrupt

 0x0021-0x7FFF
 Reserved

 0x8000
 Status Interrupt

 0x8001-0xFFFF
 Reserved


# Register 6: CAN Test (CANTST), offset 0x014

This register is used for self-test and external pin access. It is write-enabled by setting the  $\mathtt{TEST}$  bit in the CANCTL register. Different test functions may be combined, however, CAN transfers are affected if the TX bits in this register are not zero.

#### CAN Test (CANTST)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x014

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description	
31:8	reserved	RO	0x0000.00	compatibility	ould not rely on the value of a reserved bit. To provide with future products, the value of a reserved bit should be cross a read-modify-write operation.
7	RX	RO	0	Receive Obs	servation
				Value	Description
				0	The CANnRx pin is low.
				1	The CANnRx pin is high.
6:5	TX	R/W	0x0	Transmit Co	ntrol
				Overrides co	ontrol of the CANnTx pin.

Value

Description

0x0	CAN Module Control
	$\mathtt{CANnTx}$ is controlled by the CAN module; default operation
0x1	Sample Point
	The sample point is driven on the ${\tt CANnTx}$ signal. This mode is useful to monitor bit timing.
0x2	Driven Low
	${\tt CANnTx}$ drives a low value. This mode is useful for checking the physical layer of the CAN bus.
0x3	Driven High
	CANnTx drives a high value. This mode is useful for

checking the physical layer of the CAN bus.

Bit/Field	Name	Туре	Reset	Descriptio	on
4	LBACK	R/W	0	Loopback	Mode
				Value	Description
				0	Loopback mode is disabled.
				1	Loopback mode is enabled. In loopback mode, the data from the transmitter is routed into the receiver. Any data on the receive input is ignored.
3	SILENT	R/W	0	Silent Mod	de
				Value	Description
				0	Silent mode is disabled.
				1	Silent mode is enabled. In silent mode, the CAN controller does not transmit data but instead monitors the bus. This mode is also known as Bus Monitor mode.
2	BASIC	R/W	0	Basic Mod	de
				Value	Description
				0	Basic mode is disabled.
				1	Basic mode is enabled. In basic mode, software should use the CANIF1 registers as the transmit buffer and use the CANIF2 registers as the receive buffer.
1:0	reserved	RO	0x0	compatibi	should not rely on the value of a reserved bit. To provide lity with future products, the value of a reserved bit should be I across a read-modify-write operation.

# Register 7: CAN Baud Rate Prescaler Extension (CANBRPE), offset 0x018


This register is used to further divide the bit time set with the BRP bit in the **CANBIT** register. It is write-enabled by setting the CCE bit in the **CANCTL** register.

### CAN Baud Rate Prescaler Extension (CANBRPE)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x018

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	BRPE	R/W	0x0	Baud Rate Prescaler Extension

0x00-0x0F: Extend the BRP bit in the **CANBIT** register to values up to 1023. The actual interpretation by the hardware is one more than the value programmed by BRPE (MSBs) and BRP (LSBs).

# Register 8: CAN IF1 Command Request (CANIF1CRQ), offset 0x020 Register 9: CAN IF2 Command Request (CANIF2CRQ), offset 0x080

A message transfer is started as soon as there is a write of the message object number to the MNUM field when the TXRQST bit in the **CANIF1MCTL** register is set. With this write operation, the BUSY bit is automatically set to indicate that a transfer between the CAN Interface Registers and the internal message RAM is in progress. After a wait time of 3 to 6 CAN\_CLK periods, the transfer between the interface register and the message RAM completes, which then clears the BUSY bit.

#### CAN IF1 Command Request (CANIF1CRQ)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x020 Type R/W, reset 0x0000.0001

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved I							
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	BUSY			l		reserved					'		MN	UM		'
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	1

Bit/Field	Name	Type	Reset	Description	1
31:16	reserved	RO	0x0000	compatibili	hould not rely on the value of a reserved bit. To provide ty with future products, the value of a reserved bit should be across a read-modify-write operation.
15	BUSY	RO	0	Busy Flag	
				Value	Description
				0	This bit is cleared when read/write action has finished.
				1	This bit is set when a write occurs to the message number in this register.
14:6	reserved	RO	0x00	compatibili	hould not rely on the value of a reserved bit. To provide ty with future products, the value of a reserved bit should be across a read-modify-write operation.
5:0	MNUM	R/W	0x01	Message N	lumber
					e of the 32 message objects in the message RAM for data ne message objects are numbered from 1 to 32.
				Value	Description

Ox00 Reserved

O is not a valid message number; it is interpreted as 0x20, or object 32.

Ox01-0x20 Message Number
Indicates specified message object 1 to 32.

Ox21-0x3F Reserved

Not a valid message number; values are shifted and

it is interpreted as 0x01-0x1F.

# Register 10: CAN IF1 Command Mask (CANIF1CMSK), offset 0x024 Register 11: CAN IF2 Command Mask (CANIF2CMSK), offset 0x084

Reading the Command Mask registers provides status for various functions. Writing to the Command Mask registers specifies the transfer direction and selects which buffer registers are the source or target of the data transfer.

Note that when a read from the message object buffer occurs when the WRNRD bit is clear and the CLRINTPND and/or NEWDAT bits are set, the interrupt pending and/or new data flags in the message object buffer are cleared.

#### CAN IF1 Command Mask (CANIF1CMSK)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x024
Type R/W, reset 0x0000.0000

Type	R/W, rese	et uxuuuc	0.0000														
	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	
			1	•		•		rese	rved	•	1				•		
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	
	_			rese	rved	ı	' '		WRNRD	MASK	ARB	CONTROL	. CLRINTPND	NEWDAT / TXRQST	DATAA	DATAE	
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	
E	Bit/Field 31:8 7		Nan reser			ре О	Reset 0x0000.00	Description  Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.									
	7		WRN	RD	R/	W	0	Write	Write, Not Read								
								Valu	ue D	escriptio	n						
								0	th		тим field	in the CA I in the <b>C</b> A					
								1	m	nessage	object s	in the CA specified I est (CAN	by the мN	∪M field			
								Note	bu	uffer can	be clea	and new red by rea PND and/	ading fror	n the bu	uffer (WRI		
	6		MAS	SK	R	W	0	Acce	ess Mas	k Bits							
								Valu	ue	Desc	ription						
								0		Mask	bits un	changed	-				
								1				MASK + DI		of the	message	e objec	

Bit/Field	Name	Туре	Reset	Descrip	otion
5	ARB	R/W	0	Access	Arbitration Bits
				Value	Description
				0	Arbitration bits unchanged.
				1	Transfer ID + DIR + XTD + MSGVAL of the message object into the Interface registers.
4	CONTROL	R/W	0	Access	Control Bits
				Value	Description
				0	Control bits unchanged.
				1	Transfer control bits from the <b>CANIFnMCTL</b> register into the Interface registers.
3	CLRINTPND	R/W	0	Clear Ir	nterrupt Pending Bit
				The fun	action of this bit depends on the configuration of the $\mathtt{WRNRD}$ bit.
				Value	Description
				0	If wrnrd is clear, the interrupt pending status is transferred from the message buffer into the CANIFnMCTL register.
					If $\mathtt{WRNRD}$ is set, the $\mathtt{INTPND}$ bit in the message object remains unchanged.
				1	If WRNRD is clear, the interrupt pending status is cleared in the message buffer. Note the value of this bit that is transferred to the <b>CANIFnMCTL</b> register always reflects the status of the bits before clearing.
					If $\mathtt{WRNRD}$ is set, the $\mathtt{INTPND}$ bit is cleared in the message object.
2	NEWDAT / TXRQST	R/W	0	NEWD/	AT / TXRQST Bit
				The fun	action of this bit depends on the configuration of the $\mathtt{WRNRD}$ bit.
				Value	Description
				0	If WRNRD is clear, the value of the new data status is transferred

- 0 If WRNRD is clear, the value of the new data status is transferred from the message buffer into the CANIFnMCTL register.
  If WRNRD is set, a transmission is not requested.
- If WRNRD is clear, the new data status is cleared in the message buffer. Note the value of this bit that is transferred to the CANIFNMCTL register always reflects the status of the bits before clearing.

If wrnrd is set, a transmission is requested. Note that when this bit is set, the  ${\tt TXRQST}$  bit in the <code>CANIFnMCTL</code> register is ignored.

Bit/Field	Name	Туре	Reset	Description	1
1	DATAA	R/W	0		ta Byte 0 to 3 on the configuration of the WRNRD bit.
				Value	Description
				0	Data bytes 0-3 are unchanged.
				1	If WRNRD is clear, transfer data bytes 0-3 in <b>CANIFnDA1</b> and <b>CANIFnDA2</b> to the message object.
					If WRNRD is set, transfer data bytes 0-3 in message object to <b>CANIFnDA1</b> and <b>CANIFnDA2</b> .
0	DATAB	R/W	0	Access Da	ta Byte 4 to 7
				The function as follows:	on of this bit depends on the configuration of the WRNRD bit
				Value	Description
				0	Data bytes 4-7 are unchanged.
				1	If WRNRD is clear, transfer data bytes 4-7 in CANIFnDA1 and CANIFnDA2 to the message object.
					If WRNRD is set, transfer data bytes 4-7 in message object to <b>CANIFnDA1</b> and <b>CANIFnDA2</b> .


# Register 12: CAN IF1 Mask 1 (CANIF1MSK1), offset 0x028 Register 13: CAN IF2 Mask 1 (CANIF2MSK1), offset 0x088

The mask information provided in this register accompanies the data (CANIFnDAn), arbitration information (CANIFnARBn), and control information (CANIFnMCTL) to the message object in the message RAM. The mask is used with the ID bit in the CANIFnARBn register for acceptance filtering. Additional mask information is contained in the CANIFnMSK2 register.

### CAN IF1 Mask 1 (CANIF1MSK1)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x028

Type R/W, reset 0x0000.FFFF



Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	MSK	R/W	0xFFFF	Identifier Mask

When using a 29-bit identifier, these bits are used for bits [15:0] of the ID. The MSK field in the CANIFnMSK2 register are used for bits [28:16] of the ID. When using an 11-bit identifier, these bits are ignored.

Value	Description
0	The corresponding identifier field ( ${\tt ID}$ ) in the message object cannot inhibit the match in acceptance filtering.
1	The corresponding identifier field (ID) is used for acceptance filtering.

# Register 14: CAN IF1 Mask 2 (CANIF1MSK2), offset 0x02C Register 15: CAN IF2 Mask 2 (CANIF2MSK2), offset 0x08C

This register holds extended mask information that accompanies the CANIFnMSK1 register.

### CAN IF1 Mask 2 (CANIF1MSK2)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x02C Type R/W, reset 0x0000.FFFF

туре	R/w, res	et uxuuui	J.FFFF														
	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16	
		1				1		rese	erved		'	1		1	1		
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	
	MXTD	MDIR	reserved			1	1 1			MSK	1	1		1	1	1	
Type Reset	R/W 1	R/W 1	RO 1	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	
E	Bit/Field		Nam	ne	Ту	pe	Reset	Des	cription								
	31:16 reserved			R	0	0x0000	com	patibility	should not rely on the value of a reserved bit. To provide ity with future products, the value of a reserved bit should be across a read-modify-write operation.								
	15		MXT	D.	R	W	1	Mas	sk Exten	ded Iden	tifier						
								Val	ue	Descrip	tion						
								0				dentifier be	•				
								1		The ext filtering		dentifier t	oit XTD is	s used fo	or accep	ance	
	14		MDI	R	R	W	1	Mas	sk Messa	age Dired	ction						
								Val	ue	Descrip	otion						
								0			•	lirection be effect for	•			RB2	
								1		The me	•	lirection t	oit dir is	s used fo	or accep	ance	
	13		reserv	/ed	R	.0	1	Soft				the value					

compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.


Bit/Field	Name	Туре	Reset	Description	n
12:0	MSK	R/W	0xFF	ID. The мs	g a 29-bit identifier, these bits are used for bits [28:16] of the sk field in the <b>CANIFnMSK1</b> register are used for bits [15:0] When using an 11-bit identifier, MSK[12:2] are used for bits

# Register 16: CAN IF1 Arbitration 1 (CANIF1ARB1), offset 0x030 Register 17: CAN IF2 Arbitration 1 (CANIF2ARB1), offset 0x090

These registers hold the identifiers for acceptance filtering.

CAN IF1 Arbitration 1 (CANIF1ARB1)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x030 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	ID	R/W	0x0000	Message Identifier

This bit field is used with the ID field in the **CANIFnARB2** register to create the message identifier.

When using a 29-bit identifier, bits 15:0 of the **CANIFnARB1** register are [15:0] of the ID, while bits 12:0 of the **CANIFnARB2** register are [28:16] of the ID.

When using an 11-bit identifier, these bits are not used.

# Register 18: CAN IF1 Arbitration 2 (CANIF1ARB2), offset 0x034 Register 19: CAN IF2 Arbitration 2 (CANIF2ARB2), offset 0x094

These registers hold information for acceptance filtering.

CAN IF1 Arbitration 2 (CANIF1ARB2)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x034 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
	'		1					rese	rved	1						
Type	RO															
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	MSGVAL	XTD	DIR		l			ı	1	I ID						
Type Reset	R/W 0															

Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15	MSGVAL	R/W	0	Message Valid

Value	Description
0	The message object is ignored by the message handler.
1	The message object is configured and ready to be considered by the message handler within the CAN controller.

All unused message objects should have this bit cleared during initialization and before clearing the INIT bit in the CANCTL register. The MSGVAL bit must also be cleared before any of the following bits are modified or if the message object is no longer required: the ID fields in the CANIFnARBn registers, the XTD and DIR bits in the CANIFnARB2 register, or the DLC field in the CANIFNMCTL register.

14	XTD	R/W	0	Extended Identifier

Value	Description
0	An 11-bit Standard Identifier is used for this message object.
1	A 29-bit Extended Identifier is used for this message object.

Bit/Field	Name	Туре	Reset	Description
13	DIR	R/W	0	Message Direction
				Value Description
				Receive. When the TXRQST bit in the <b>CANIFnMCTL</b> register is set, a remote frame with the identifier of this message object is received. On reception of a data frame with matching identifier, that message is stored in this message object.
				Transmit. When the TXRQST bit in the <b>CANIFNMCTL</b> register is set, the respective message object is transmitted as a data frame. On reception of a remote frame with matching identifier, the TXRQST bit of this message object is set (if RMTEN=1).
12:0	ID	R/W	0x000	Message Identifier
				This bit field is used with the ID field in the <b>CANIFnARB2</b> register to create the message identifier.
				When using a 29-bit identifier, ID[15:0] of the <b>CANIFnARB1</b> register are [15:0] of the ID, while these bits, ID[12:0], are [28:16] of the ID.
				When using an 11-bit identifier, $ID[12:2]$ are used for bits [10:0] of the ID. The $ID$ field in the <b>CANIFNARB1</b> register is ignored.

# Register 20: CAN IF1 Message Control (CANIF1MCTL), offset 0x038 Register 21: CAN IF2 Message Control (CANIF2MCTL), offset 0x098

This register holds the control information associated with the message object to be sent to the Message RAM.

# CAN IF1 Message Control (CANIF1MCTL)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x038

Type R/W, reset 0x0000.0000

турс	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	ı				1	rese	rved	1	1	i	i	ì	1	
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	NEWDAT	MSGLST	INTPND	UMASK	TXIE	RXIE	RMTEN	TXRQST	EOB		reserved				ĹC	
Type Reset	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	R/W 0
E	Bit/Field		Nam	ne	Ту	ре	Reset	Des	cription							
	31:16		reserv	ved	R	0	0x0000	Soft	ware sl	nould not	rely on t	he value	of a res	erved bit	t. To prov	vide
									•	-	ture produ read-mod				ed bit sh	ould be
	15		NEW	TAC	R/	W	0	·	/ Data			,	·			
	.0					••	Ü			Dogorinti	0.0					
								Valu 0		Descripti	data has	hoon wr	itton into	the data	nortion	of thio
								U		message	object b was clear	y the me	ssage ha		•	
								1			sage han portion o				en new d	ata into
	14		MSGL	_ST	R/	W	0	Mes	sage L	ost						
								Valu	ue	Descrip	tion					
								0			sage wa by the C		nce the la	ast time t	his bit w	as
								1			ssage ha				-	
										-	for mess ter is clea			n the DII	R bit in th	ne
	13		INTP	ND	R/	W	0	Inter	rupt Pe	ending						
								Valu	ue	Descripti	ion					
								0		This mes	ssage obj	ject is no	ot the sou	irce of a	n interru	pt.
								1		interrupt	ssage obj identifier object if priority.	in the C	ANINT r	egister p	oints to	this

Bit/Field	Name	Туре	Reset	Descript	ion
12	UMASK	R/W	0	Use Acc	eptance Mask
				Value	Description
				0	Mask is ignored.
				1	Use mask (MSK, MXTD, and MDIR bits in the CANIFnMSKn registers) for acceptance filtering.
11	TXIE	R/W	0	Transmit	t Interrupt Enable
				Value	Description
				0	The INTPND bit in the <b>CANIFnMCTL</b> register is unchanged after a successful transmission of a frame.
				1	The INTPND bit in the <b>CANIFNMCTL</b> register is set after a successful transmission of a frame.
10	RXIE	R/W	0	Receive	Interrupt Enable
				Value	Description
				0	The INTPND bit in the <b>CANIFnMCTL</b> register is unchanged after a successful reception of a frame.
				1	The INTPND bit in the <b>CANIFnMCTL</b> register is set after a successful reception of a frame.
9	RMTEN	R/W	0	Remote	Enable
				Value	Description
				0	At the reception of a remote frame, the TXRQST bit in the CANIFnMCTL register is left unchanged.
				1	At the reception of a remote frame, the TXRQST bit in the CANIFnMCTL register is set.
8	TXRQST	R/W	0	Transmit	t Request
				Value	Description
				0	This message object is not waiting for transmission.
				1	The transmission of this message object is requested and is not yet done.
				Note:	If the $\mathtt{WRNRD}$ and $\mathtt{TXRQST}$ bits in the <code>CANIFnCMSK</code> register are set, this bit is ignored.

Bit/Field	Name	Туре	Reset	Description	
7	EOB	R/W	0	End of Buffe	er
				Value	Description
				0	Message object belongs to a FIFO Buffer and is not the last message object of that FIFO Buffer.
				1	Single message object or last message object of a FIFO Buffer.
				to build a FI	sed to concatenate two or more message objects (up to 32) FO buffer. For a single message object (thus not belonging uffer), this bit must be set.
6:4	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.	
3:0	DLC	R/W	0x0	Data Length	n Code
				Value	Description
				0x0-0x8	Specifies the number of bytes in the data frame.
				0x9-0xF	Defaults to a data frame with 8 bytes.
					Id in the <b>CANIFnMCTL</b> register of a message object must he same as in all the corresponding objects with the same

identifier at other nodes. When the message handler stores a data frame,

it writes  ${\tt DLC}$  to the value given by the received message.

Register 22: CAN IF1 Data A1 (CANIF1DA1), offset 0x03C

Register 23: CAN IF1 Data A2 (CANIF1DA2), offset 0x040

Register 24: CAN IF1 Data B1 (CANIF1DB1), offset 0x044

Register 25: CAN IF1 Data B2 (CANIF1DB2), offset 0x048

Register 26: CAN IF2 Data A1 (CANIF2DA1), offset 0x09C

Register 27: CAN IF2 Data A2 (CANIF2DA2), offset 0x0A0

Register 28: CAN IF2 Data B1 (CANIF2DB1), offset 0x0A4

Register 29: CAN IF2 Data B2 (CANIF2DB2), offset 0x0A8


These registers contain the data to be sent or that has been received. In a CAN data frame, data byte 0 is the first byte to be transmitted or received and data byte 7 is the last byte to be transmitted or received. In CAN's serial bit stream, the MSB of each byte is transmitted first.

## CAN IF1 Data A1 (CANIF1DA1)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x03C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	DATA	R/W	0x0000	Data

The **CANIFnDA1** registers contain data bytes 1 and 0; **CANIFnDA2** data bytes 3 and 2; **CANIFnDB1** data bytes 5 and 4; and **CANIFnDB2** data bytes 7 and 6.


# Register 30: CAN Transmission Request 1 (CANTXRQ1), offset 0x100 Register 31: CAN Transmission Request 2 (CANTXRQ2), offset 0x104

The **CANTXRQ1** and **CANTXRQ2** registers hold the TXRQST bits of the 32 message objects. By reading out these bits, the CPU can check which message object has a transmission request pending. The TXRQST bit of a specific message object can be changed by three sources: (1) the CPU via the **CANIFNMCTL** register, (2) the message handler state machine after the reception of a remote frame, or (3) the message handler state machine after a successful transmission.

The **CANTXRQ1** register contains the TXRQST bits of the first 16 message objects in the message RAM; the **CANTXRQ2** register contains the TXRQST bits of the second 16 message objects.

## CAN Transmission Request 1 (CANTXRQ1)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x100 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	TXRQST	RO	0x0000	Transmission Request Bits

Value	Description
0	The corresponding message object is not waiting for transmission.
1	The transmission of the corresponding message object

is requested and is not yet done.


# Register 32: CAN New Data 1 (CANNWDA1), offset 0x120 Register 33: CAN New Data 2 (CANNWDA2), offset 0x124

The **CANNWDA1** and **CANNWDA2** registers hold the NEWDAT bits of the 32 message objects. By reading these bits, the CPU can check which message object has its data portion updated. The NEWDAT bit of a specific message object can be changed by three sources: (1) the CPU via the **CANIFnMCTL** register, (2) the message handler state machine after the reception of a data frame, or (3) the message handler state machine after a successful transmission.

The **CANNWDA1** register contains the NEWDAT bits of the first 16 message objects in the message RAM; the **CANNWDA2** register contains the NEWDAT bits of the second 16 message objects.

#### CAN New Data 1 (CANNWDA1)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x120 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	NEWDAT	RO	0x0000	New Data Bits

Value	Description
0	No new data has been written into the data portion of the corresponding message object by the message handler since the last time this flag was cleared by the CPU.

1 The message handler or the CPU has written new data into the data portion of the corresponding message object.

# Register 34: CAN Message 1 Interrupt Pending (CANMSG1INT), offset 0x140 Register 35: CAN Message 2 Interrupt Pending (CANMSG2INT), offset 0x144

The **CANMSG1INT** and **CANMSG2INT** registers hold the INTPND bits of the 32 message objects. By reading these bits, the CPU can check which message object has an interrupt pending. The INTPND bit of a specific message object can be changed through two sources: (1) the CPU via the **CANIFNMCTL** register, or (2) the message handler state machine after the reception or transmission of a frame.

This field is also encoded in the CANINT register.

The **CANMSG1INT** register contains the INTPND bits of the first 16 message objects in the message RAM; the **CANMSG2INT** register contains the INTPND bits of the second 16 message objects.

### CAN Message 1 Interrupt Pending (CANMSG1INT)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000

Offset 0x140

Type RO, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved I							
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
			ı		i .			INTI	PND I	ı						
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	INTPND	RO	0x0000	Interrupt Pending Bits

1

Value	Description
0	The corresponding message object is not the source of an interrupt.

The corresponding message object is the source of an interrupt.

# Register 36: CAN Message 1 Valid (CANMSG1VAL), offset 0x160 Register 37: CAN Message 2 Valid (CANMSG2VAL), offset 0x164


The **CANMSG1VAL** and **CANMSG2VAL** registers hold the MSGVAL bits of the 32 message objects. By reading these bits, the CPU can check which message object is valid. The message valid bit of a specific message object can be changed with the **CANIFnARB2** register.

The **CANMSG1VAL** register contains the MSGVAL bits of the first 16 message objects in the message RAM; the **CANMSG2VAL** register contains the MSGVAL bits of the second 16 message objects in the message RAM.

#### CAN Message 1 Valid (CANMSG1VAL)

CAN0 base: 0x4004.0000 CAN1 base: 0x4004.1000 Offset 0x160

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	MSGVAL	RO	0x0000	Message Valid Bits

Value	Description
0	The corresponding message object is not configured and is ignored by the message handler.
1	The corresponding message object is configured and should be considered by the message handler.

# 18 Ethernet Controller

The Stellaris<sup>®</sup> Ethernet Controller consists of a fully integrated media access controller (MAC) and network physical (PHY) interface. The Ethernet Controller conforms to *IEEE 802.3* specifications and fully supports 10BASE-T and 100BASE-TX standards.

The Stellaris Ethernet Controller module has the following features:

- Conforms to the IEEE 802.3-2002 specification
  - 10BASE-T/100BASE-TX IEEE-802.3 compliant. Requires only a dual 1:1 isolation transformer interface to the line
  - 10BASE-T/100BASE-TX ENDEC, 100BASE-TX scrambler/descrambler
  - Full-featured auto-negotiation
- Multiple operational modes
  - Full- and half-duplex 100 Mbps
  - Full- and half-duplex 10 Mbps
  - Power-saving and power-down modes
- Highly configurable
  - Programmable MAC address
  - LED activity selection
  - Promiscuous mode support
  - CRC error-rejection control
  - User-configurable interrupts
- Physical media manipulation
  - MDI/MDI-X cross-over support through software assist
  - Register-programmable transmit amplitude
  - Automatic polarity correction and 10BASE-T signal reception
- IEEE 1588 Precision Time Protocol: Provides highly accurate time stamps for individual packets
- Efficient transfers using Micro Direct Memory Access Controller (µDMA)
  - Separate channels for transmit and receive
  - Receive channel request asserted on packet receipt
  - Transmit channel request asserted on empty transmit FIFO

# 18.1 Block Diagram

As shown in Figure 18-1 on page 923, the Ethernet Controller is functionally divided into two layers: the Media Access Controller (MAC) layer and the Network Physical (PHY) layer. These layers correspond to the OSI model layers 2 and 1, respectively. The CPU accesses the Ethernet Controller via the MAC layer. The MAC layer provides transmit and receive processing for Ethernet frames. The MAC layer also provides the interface to the PHY layer via an internal Media Independent Interface (MII). The PHY layer communicates with the Ethernet bus.

Figure 18-1. Ethernet Controller





Figure 18-2 on page 923 shows more detail of the internal structure of the Ethernet Controller and how the register set relates to various functions.

Figure 18-2. Ethernet Controller Block Diagram



# 18.2 Signal Description

The following table lists the external signals of the Ethernet Controller and describes the function of each. The Ethernet LED signals are alternate functions for GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the GPIO pin placement for the LED signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the LED function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the LED0 and LED1 signals to the specified GPIO port pins. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407. The remaining signals (with the word "fixed" in the Pin Mux/Pin Assignment column) have a fixed pin assignment and function.

Table 18-1. Ethernet Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
ERBIAS	33	fixed	0	Analog	12.4-k $\Omega$ resistor (1% precision) used internally for Ethernet PHY.
LED0	59	PF3 (1)	0	TTL	Ethernet LED 0.
LED1	60	PF2 (1)	0	TTL	Ethernet LED 1.
MDIO	58	fixed	I/O	OD	MDIO of the Ethernet PHY.
RXIN	37	fixed	I	Analog	RXIN of the Ethernet PHY.
RXIP	40	fixed	I	Analog	RXIP of the Ethernet PHY.
TXON	46	fixed	0	TTL	TXON of the Ethernet PHY.
TXOP	43	fixed	0	TTL	TXOP of the Ethernet PHY.
XTALNPHY	17	fixed	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
XTALPPHY	16	fixed	1	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 18-2. Ethernet Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
ERBIAS	J3	fixed	0	Analog	12.4-k $\Omega$ resistor (1% precision) used internally for Ethernet PHY.
LED0	J12	PF3 (1)	0	TTL	Ethernet LED 0.
LED1	J11	PF2 (1)	0	TTL	Ethernet LED 1.
MDIO	L9	fixed	I/O	OD	MDIO of the Ethernet PHY.
RXIN	L7	fixed	I	Analog	RXIN of the Ethernet PHY.
RXIP	M7	fixed	I	Analog	RXIP of the Ethernet PHY.
TXON	L8	fixed	0	TTL	TXON of the Ethernet PHY.
TXOP	M8	fixed	0	TTL	TXOP of the Ethernet PHY.
XTALNPHY	J1	fixed	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.

Table 18-2. Ethernet Signals (108BGA) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
XTALPPHY	J2	fixed	1	-	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 18.3 Functional Description

**Note:** A 12.4-k $\Omega$  resistor should be connected between the ERBIAS and ground. The 12.4-k $\Omega$  resistor should have a 1% tolerance and should be located in close proximity to the ERBIAS pin. Power dissipation in the resistor is low, so a chip resistor of any geometry may be used.

The functional description of the Ethernet Controller is discussed in the following sections.

# 18.3.1 MAC Operation

The following sections describe the operation of the MAC layer, including an overview of the Ethernet frame format, the MAC layer FIFOs, Ethernet transmission and reception options, packet timestamps, and LED indicators.

#### 18.3.1.1 Ethernet Frame Format

Ethernet data is carried by Ethernet frames. The basic frame format is shown in Figure 18-3 on page 925.

Figure 18-3. Ethernet Frame

Preamble SFD		Destination Address	Source Address	Length/ Type	Data	FCS
7	1	6	6	2	46 - 1500	4
Bytes	Byte	Bytes	Bytes	Bytes	Bytes	Bytes

The seven fields of the frame are transmitted from left to right. The bits within the frame are transmitted from least to most significant bit.

#### ■ Preamble

The Preamble field is used to synchronize with the received frame's timing. The preamble is 7 octets long.

#### ■ Start Frame Delimiter (SFD)

The SFD field follows the preamble pattern and indicates the start of the frame. Its value is 1010.1011b.

#### Destination Address (DA)

This field specifies destination addresses for which the frame is intended. The LSB (bit 16 of DA oct 1 in the frame, see Table 18-3 on page 927) of the DA determines whether the address is an individual (0), or group/multicast (1) address.

## ■ Source Address (SA)

The source address field identifies the station from which the frame was initiated.

### ■ Length/Type Field

The meaning of this field depends on its numeric value. This field can be interpreted as length or type code. The maximum length of the data field is 1500 octets. If the value of the Length/Type field is less than or equal to 1500 decimal, it indicates the number of MAC client data octets. If the value of this field is greater than or equal to 1536 decimal, then it encodes the type interpretation. The meaning of the Length/Type field when the value is between 1500 and 1536 decimal is unspecified by the IEEE 802.3 standard. However, the Ethernet Controller assumes type interpretation if the value of the Length/Type field is greater than 1500 decimal. The definition of the Type field is specified in the IEEE 802.3 standard. The first of the two octets in this field is most significant.

#### Data

The data field is a sequence of octets that is at least 46 in length, up to 1500 in length. Full data transparency is provided so any values can appear in this field. A minimum frame size of 46 octets is required to meet the IEEE standard. If the frame size is too small, the Ethernet Controller automatically appends extra bits (a pad), thus the pad can have a size of 0 to 46 octets. Data padding can be disabled by clearing the PADEN bit in the **Ethernet MAC Transmit Control** (MACTCTL) register.

For the Ethernet Controller, data sent/received can be larger than 1500 bytes without causing a Frame Too Long error. Instead, a FIFO overrun error is reported using the FOV bit in the **Ethernet MAC Raw Interrupt Status (MACRIS)** register when the frame received is too large to fit into the Ethernet Controller's 2K RAM.

## ■ Frame Check Sequence (FCS)

The frame check sequence carries the cyclic redundancy check (CRC) value. The CRC is computed over the destination address, source address, length/type, and data (including pad) fields using the CRC-32 algorithm. The Ethernet Controller computes the FCS value one nibble at a time. For transmitted frames, this field is automatically inserted by the MAC layer, unless disabled by clearing the CRC bit in the **MACTCTL** register. For received frames, this field is automatically checked. If the FCS does not pass, the frame is not placed in the RX FIFO, unless the FCS check is disabled by clearing the BADCRC bit in the **MACRCTL** register.

### 18.3.1.2 MAC Layer FIFOs

The Ethernet Controller is capable of simultaneous transmission and reception. This feature is enabled by setting the DUPLEX bit in the MACTCTL register.

For Ethernet frame transmission, a 2-KB transmit FIFO is provided that can be used to store a single frame. While the *IEEE 802.3 specification* limits the size of an Ethernet frame's payload section to 1500 Bytes, the Ethernet Controller places no such limit. The full buffer can be used for a payload of up to 2032 bytes (as the first 16 bytes in the FIFO are reserved for destination address, source address and length/type information).

For Ethernet frame reception, a 2-KB receive FIFO is provided that can be used to store multiple frames, up to a maximum of 31 frames. If a frame is received, and there is insufficient space in the RX FIFO, an overflow error is indicated using the FOV bit in the **MACRIS** register.

For details regarding the TX and RX FIFO layout, refer to Table 18-3 on page 927. Please note the following difference between TX and RX FIFO layout. For the TX FIFO, the Data Length field in the first FIFO word refers to the Ethernet frame data payload, as shown in the 5th to nth FIFO positions. For the RX FIFO, the Frame Length field is the total length of the received Ethernet frame, including the Length/Type bytes and the FCS bits.

If FCS generation is disabled by clearing the CRC bit in the **MACTCTL** register, the last word in the TX FIFO must contain the FCS bytes for the frame that has been written to the FIFO.

Also note that if the length of the data payload section is not a multiple of 4, the FCS field is not aligned on a word boundary in the FIFO. However, for the RX FIFO, the beginning of the next frame is always on a word boundary.

Table 18-3. TX & RX FIFO Organization

ength Least ant Byte ength Most Significant		
ength Most Significant		
DA oct 1		
SA oct 2		
nt Byte		
int Byte		
data oct n+1		

a. If the CRC bit in the MACTCTL register is clear, the FCS bytes must be written with the correct CRC. If the CRC bit is set, the Ethernet Controller automatically writes the FCS bytes.

# 18.3.1.3 Ethernet Transmission Options

At the MAC layer, the transmitter can be configured for both full-duplex and half-duplex operation by using the <code>DUPLEX</code> bit in the **MACTCTL** register. Note that in 10BASE-T half-duplex mode, the transmitted data is looped back on the receive path.

The Ethernet Controller automatically generates and inserts the Frame Check Sequence (FCS) at the end of the transmit frame when the CRC bit in the **MACTCTL** register is set. However, for test purposes, this feature can be disabled in order to generate a frame with an invalid CRC by clearing the CRC bit.

The *IEEE 802.3 specification* requires that the Ethernet frame payload section be a minimum of 46 bytes. The Ethernet Controller automatically pads the data section if the payload data section loaded into the FIFO is less than the minimum 46 bytes when the PADEN bit in the **MACTCTL** register is set. This feature can be disabled by clearing the PADEN bit.

The transmitter must be enabled by setting the TXEN bit in the MACTCTL register.

# 18.3.1.4 Ethernet Reception Options

The Ethernet Controller RX FIFO should be cleared during software initialization. The receiver should first be disabled by clearing the RXEN bit in the **Ethernet MAC Receive Control (MACRCTL)** register, then the FIFO can be cleared by setting the RSTFIFO bit in the **MACRCTL** register.

The receiver automatically rejects frames that contain bad CRC values in the FCS field. In this case, a Receive Error interrupt is generated and the receive data is lost. To accept all frames, clear the BADCRC bit in the **MACRCTL** register.

In normal operating mode, the receiver accepts only those frames that have a destination address that matches the address programmed into the **Ethernet MAC Individual Address 0 (MACIA0)** and **Ethernet MAC Individual Address 1 (MACIA1)** registers. However, the Ethernet receiver can also be configured for Promiscuous and Multicast modes by setting the PRMS and AMUL bits in the **MACRCTL** register. It is important to note that when the receiver is enabled, all valid frames with a broadcast address of FF-FF-FF-FF-FF in the Destination Address field are received and stored in the RX FIFO, even if the AMUL bit is not set.

# 18.3.1.5 Packet Timestamps

Some applications require a very precise clock for time stamping samples or triggering events. The IEEE Precision Time Protocol (PTP), or IEEE-1588, provides a mechanism for synchronizing clocks across an Ethernet to sub-microsecond precision. The accuracy of the PTP clock depends greatly upon the accuracy of timestamps of the PTP Ethernet packets. In a software-only PTP solution, there can be jitter in the Ethernet packet timestamps, resulting in a less precise PTP clock on the target. In some Stellaris devices, General-Purpose Timer 3 (GPT3) can be used in conjunction with the **Ethernet MAC Timer Support (MACTS)** register to provide a more accurate timestamp for Ethernet packets.

This feature is enabled by setting the TSEN bit in the **MACTS** register. Note that when this feature is enabled, GPT3 must be dedicated to the Ethernet Controller. GPT3 must be configured to 16-bit edge capture mode, see page 555. Timer A of GPT3 stores the transmit time, and Timer B stores the receive time. One other General-Purpose Timer can be set up as a 16-bit free-running timer to synchronize the receiver and transmitter timers and provide a timestamp with which to compare the timestamps stored in GPT3. The enet\_ptpd example in the StellarisWare software package provides a sample PTP application that illustrates both software-only time stamping as well the use of the GPT3 and **MACTS** register for more accurate timestamps. This example supports version 1 of the IEEE-1588 protocol, but Stellaris microcontrollers support both versions 1 and 2.

#### 18.3.1.6 LED Indicators

The Ethernet Controller supports two LED signals that can be used to indicate various states of operation. These signals are mapped to the  $\mathtt{LED0}$  and  $\mathtt{LED1}$  pins. By default, these pins are configured as GPIO signals ( $\mathtt{PF3}$  and  $\mathtt{PF2}$ ). For the Ethernet Controller to drive these signals, they must be reconfigured to their hardware function. See "General-Purpose Input/Outputs (GPIOs)" on page 407 for additional details. The function of these pins is programmable using the **Ethernet MAC LED Encoding (MACLED)** register. Refer to page 960 for additional details on how to program these LED functions.

# 18.3.2 Internal MII Operation

For the MII management interface to function properly, the MDIO signal must be connected through a 10 k $\Omega$  pull-up resistor to the +3.3 V supply. Failure to connect this pull-up resistor prevents management transactions on this internal MII to function. Note that it is possible for data transmission across the MII to still function since the PHY layer auto-negotiates the link parameters by default.

For the MII management interface to function properly, the internal clock must be divided down from the system clock to a frequency no greater than 2.5 MHz. The **Ethernet MAC Management Divider (MACMDV)** register contains the divider used for scaling down the system clock. See page 954 for more details about the use of this register.

# 18.3.3 PHY Operation

The Physical Layer (PHY) in the Ethernet Controller includes integrated ENDECs, scrambler/descrambler, dual-speed clock recovery, and full-featured auto-negotiation functions. The transmitter includes an on-chip pulse shaper and a low-power line driver. The receiver has an adaptive equalizer and a baseline restoration circuit required for accurate clock and data recovery. The transceiver interfaces to Category-5 unshielded twisted pair (Cat-5 UTP) cabling for 100BASE-TX applications, and Category-3 unshielded twisted pair (Cat-3 UTP) for 10BASE-T applications. The Ethernet Controller is connected to the line media via dual 1:1 isolation transformers. No external filter is required.

#### 18.3.3.1 Clock Selection

The Ethernet Controller can be clocked from an on-chip crystal oscillator which can also be driven by an external oscillator. When using the on-chip crystal oscillator, a 25-MHz crystal should be connected between the XTALPPHY and XTALNPHY pins. Alternatively, an external 25-MHz clock input can be connected to the XTALPPHY pin. In this mode of operation, a crystal is not required and the XTALNPHY pin should be left unconnected. The Ethernet oscillator is powered down when the EPHY0 bit in the Run Mode Clock Gating Control Register 2 (RCGC2) register is clear. After setting the EPHY0 bit, software must wait 3.5 ms before accessing any of the MII Management registers. See "Ethernet Controller" on page 1337 for more information regarding the specifications of the Ethernet Controller.

### 18.3.3.2 Auto-Negotiation

The Ethernet Controller supports the auto-negotiation functions of Clause 28 of the *IEEE 802.3* standard for 10/100 Mbps operation over copper wiring. This function is controlled via register settings. The auto-negotiation function is turned on by default, and the ANEGEN bit in the **Ethernet PHY Management Register 0 - Control (MR0)** is set after reset. Software can disable the auto-negotiation function by clearing the ANEGEN bit. The contents of the **Ethernet PHY Management Register - Auto-Negotiation Advertisement (MR4)** are reflected to the Ethernet Controller's link partner during auto-negotiation via fast-link pulse coding.

Once auto-negotiation is complete, the SPEED bit in the **Ethernet PHY Management Register 31** – **PHY Special Control/Status (MR31)** register reflects the actual speed. The AUTODONE bit in **MR31** is set to indicate that auto-negotiation is complete. Setting the RANEG bit in the **MR0** register also causes auto-negotiation to restart.

## 18.3.3.3 Polarity Correction

The Ethernet Controller is capable of automatic polarity reversal for 10BASE-T and auto-negotiation functions. The xpol bit in the **Ethernet PHY Management Register 27 –Special Control/Status (MR27)** register is set to indicate the polarity has automatically been reversed.

### 18.3.3.4 MDI/MDI-X Configuration

The Ethernet Controller supports the MDI/MDI-X configuration as defined in *IEEE 802.3-2002* specification through software assistance. The MDI/MDI-X configuration eliminates the need for cross-over cables when connecting to another device, such as a hub. Software can implement the MDI/MDI-X configuration using a function outlined by the pseudo code below. This code should be called periodically using one of the available timer resources on the Stellaris microcontroller such as the System Tick Timer or one of the General Purpose timers. The following code refers to the LINK bit in the Ethernet PHY Management Register 1 - Status (MR1), the ENON bit in the Ethernet PHY Management Register 17 - Mode Control/Status (MR17), and the EN bit of the Ethernet PHY MDIX (MDIX) register.

```
//
// Entry Point for MDI/MDI-X configuration.
//
//
// Increment the Link Active and Energy Detect Timers using the elapsed time
// since the last call to this function. If using a periodic timer, the
// elapsed time should be a constant (the programmed period of the timer).
Increment Link Active Timer
Increment Energy Detect Timer
if (No Ethernet Link Active)
    // If energy has been detected on the link, reset the Energy Detect Timer.
    // If it is a "new" energy detect, reset the link detect timer also.
    if (Ethernet Energy Detected)
        Reset Energy Detect Timer
        if (New Energy Detect)
            Reset Link Detect Timer
    }
    //
    // If the Energy or Link Detect timer has expired, toggle the MDI/MDI-X
    // mode. Typically, the Energy Detect Timer would be ~62ms, while the
    // Link Detect Timer would be ~2s
    if((Energy Detect Timer Expired) or
       (Link Detect Timer Expired))
    {
        Reset Energy Detect Timer
        if(Random Event)
        {
```

## 18.3.3.5 Power Management

The PHY has two power-saving modes:

- Power-Down
- Energy Detect Power-Down

Power-down mode is activated by setting the PWRDN bit in the **MR0** register. When the PHY is in power-down mode, it consumes minimum power. When the PWRDN bit is cleared, the PHY powers up and is automatically reset.

The energy detect power-down mode is activated by setting the EDPD bit in the MR17 register. In this mode of operation, when no energy is present on the line, the PHY is powered down, except for the managmenet interface, the SQUELCH circuit and the ENERGYON logic. The ENERGYON logic is used to detect the presence of valid energy from 100BASE-T, 10BASE-T, or auto-negotiation signals. While the PHY is powered down, nothing is transmitted. When link pulses or packets are received, the PHY powers-up. The PHY automatically resets itself into the state it had prior to power down and sets the EONIS bit in the MR29 register. The first and possibly the second packet to activate the ENERGYON mode may be lost.

# 18.3.4 Interrupts

The Ethernet Controller can generate an interrupt for one or more of the following conditions:

- A frame has been received into an empty RX FIFO
- A frame transmission error has occurred
- A frame has been transmitted successfully
- A frame has been received with inadequate room in the RX FIFO (overrun)
- A frame has been received with one or more error conditions (for example, FCS failed)
- An MII management transaction between the MAC and PHY layers has completed
- One or more of the following PHY layer conditions occurs:
  - Auto-Negotiate Complete

- Remote Fault
- Link Partner Acknowledge
- Parallel Detect Fault
- Page Received

Refer to Ethernet PHY Management Register 29 - Interrupt Source Flags (MR29) (see page 978) for additional details regarding PHY interrupts.

# 18.3.5 DMA Operation

The Ethernet peripheral provides request signals to the  $\mu$ DMA controller and has a dedicated channel for transmit and one for receive. The request is a single type for both channels. Burst requests are not supported. The RX channel request is asserted when a packet is received while the TX channel request is asserted when the transmit FIFO becomes empty.

No special configuration is needed to enable the Ethernet peripheral for use with the µDMA controller.

Because the size of a received packet is not known until the header is examined, it is best to set up the initial  $\mu$ DMA transfer to copy the first 4 words including the packet length plus the Ethernet header from the RX FIFO when the RX request occurs. The  $\mu$ DMA causes an interrupt when this transfer is complete. Upon entering the interrupt handler, the packet length in the FIFO and the Ethernet header are in a buffer and can be examined. Once the packet length is known, then another  $\mu$ DMA transfer can be set up to transfer the remaining received packet payload from the FIFO into a buffer. This transfer should be initiated by software. Another interrupt occurs when this transfer is done.

Even though the TX channel generates a TX empty request, the recommended way to handle  $\mu DMA$  transfers for transmitting packets is to set up the transfer from the buffer containing the packet to the transmit FIFO, and then to initiate the transfer with a software request. An interrupt occurs when this transfer is complete. For both channels, the "auto-request" transfer mode should be used. See "Micro Direct Memory Access ( $\mu DMA$ )" on page 346 for more details about programming the  $\mu DMA$  controller.

# 18.4 Initialization and Configuration

The following sections describe the hardware and software configuration required to set up the Ethernet Controller.

# 18.4.1 Hardware Configuration

Figure 18-4 on page 933 shows the proper method for interfacing the Ethernet Controller to a 10/100BASE-T Ethernet jack.




Figure 18-4. Interface to an Ethernet Jack

The following isolation transformers have been tested and are known to successfully interface to the Ethernet PHY layer.

- Isolation Transformers
  - TDK TLA-6T103
  - TDK TLA-6T118
  - Bel-Fuse S558-5999-46
  - Halo TG22-3506ND
  - Halo TG110-S050
  - PCA EPF8023G
  - Pulse PE-68515
  - Valor ST6118
  - YCL 20PMT04
- Isolation transformers with integrated RJ45 connector
  - TDK TLA-6T704
  - Delta RJS-1A08T089A
- Isolation transformers with integrated RJ45 connector, LEDs and termination resistors
  - Pulse J0011D21B/E
  - Pulse J3011G21DNL

# 18.4.2 Software Configuration

To use the Ethernet Controller, it must be enabled by setting the EPHYO and EMACO bits in the RCGC2 register (see page 284). In addition, the clock to the appropriate GPIO module must be enabled via the RCGC2 register in the System Control module. See page 284. To find out which GPIO port to enable, refer to Table 24-4 on page 1261. Configure the PMCn fields in the GPIOPCTL register to assign the Ethernet signals to the appropriate pins. See page 448 and Table 24-5 on page 1270.

The following steps can then be used to configure the Ethernet Controller for basic operation.

- 1. Program the **MACDIV** register to obtain a 2.5 MHz clock (or less) on the internal MII. Assuming a 20-MHz system clock, the **MACDIV** value should be 0x03 or greater.
- 2. Program the MACIA0 and MACIA1 register for address filtering.
- **3.** Program the **MACTCTL** register for Auto CRC generation, padding, and full-duplex operation using a value of 0x16.
- **4.** Program the **MACRCTL** register to flush the receive FIFO and reject frames with bad FCS using a value of 0x18.
- **5.** Enable both the Transmitter and Receive by setting the LSB in both the **MACTCTL** and **MACRCTL** registers.
- 6. To transmit a frame, write the frame into the TX FIFO using the **Ethernet MAC Data (MACDATA)** register. Then set the NEWTX bit in the **Ethernet Mac Transmission Request (MACTR)** register to initiate the transmit process. When the NEWTX bit has been cleared, the TX FIFO is available for the next transmit frame.
- 7. To receive a frame, wait for the NPR field in the Ethernet MAC Number of Packets (MACNP) register to be non-zero. Then begin reading the frame from the RX FIFO by using the MACDATA register. To ensure that the entire packet is received, either use the DriverLib EthernetPacketGet() API or compare the number of bytes received to the Length field from the frame to determine when the packet has been completely read.

# 18.5 Register Map

Table 18-4 on page 934 lists the Ethernet MAC and MII Management registers. The MAC register addresses given are relative to the Ethernet base address of 0x4004.8000. The MII Management registers are accessed using the **MACMCTL** register. Note that the Ethernet controller clocks must be enabled before the registers can be programmed (see page 284). There must be a delay of 3 system clocks after the Ethernet module clock is enabled before any Ethernet module registers are accessed. In addition, the Ethernet oscillator is powered down when the EPHY0 bit in the **Run Mode Clock Gating Control Register 2 (RCGC2)** register is clear. After setting the EPHY0 bit, software must wait 3.5 ms before accessing any of the MII Management registers.

The IEEE 802.3 standard specifies a register set for controlling and gathering status from the PHY layer. The registers are collectively known as the MII Management registers and are detailed in Section 22.2.4 of the IEEE 802.3 specification. Table 18-4 on page 934 also lists these MII Management registers. All addresses given are absolute and are written directly to the REGADR field of the Ethernet MAC Management Control (MACMCTL) register. The format of registers 0 to 15 are defined by the IEEE specification and are common to all PHY layer implementations. The only variance allowed is for features that may or may not be supported by a specific PHY implementation. Registers 16 to 31 are vendor-specific registers, used to support features that are specific to a vendor's PHY implementation.

Table 18-4. Ethernet Register Map

Offset	Name	Туре	Reset	Description	See page		
Ethernet MAC (Ethernet Offset)							
0x000	MACRIS/MACIACK	R/W1C	0x0000.0000	Ethernet MAC Raw Interrupt Status/Acknowledge	937		
0x004	MACIM	R/W	0x0000.007F	Ethernet MAC Interrupt Mask	940		

Table 18-4. Ethernet Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x008	MACRCTL	R/W	0x0000.0008	Ethernet MAC Receive Control	
0x00C	MACTCTL	R/W	0x0000.0000	Ethernet MAC Transmit Control	
0x010	MACDATA	R/W	0x0000.0000	Ethernet MAC Data	946
0x014	MACIA0	R/W	0x0000.0000	Ethernet MAC Individual Address 0	948
0x018	MACIA1	R/W	0x0000.0000	Ethernet MAC Individual Address 1	949
0x01C	MACTHR	R/W	0x0000.003F	Ethernet MAC Threshold	950
0x020	MACMCTL	R/W	0x0000.0000	Ethernet MAC Management Control	952
0x024	MACMDV	R/W	0x0000.0080	Ethernet MAC Management Divider	954
0x02C	MACMTXD	R/W	0x0000.0000	Ethernet MAC Management Transmit Data	955
0x030	MACMRXD	R/W	0x0000.0000	Ethernet MAC Management Receive Data	956
0x034	MACNP	RO	0x0000.0000	Ethernet MAC Number of Packets	957
0x038	MACTR	R/W	0x0000.0000	Ethernet MAC Transmission Request	958
0x03C	MACTS	R/W	0x0000.0000	Ethernet MAC Timer Support	959
0x040	MACLED	R/W	0x0000.0100	Ethernet MAC LED Encoding	960
0x044	MDIX	R/W	0x0000.0000	Ethernet PHY MDIX	962
III Manag	gement (Accessed thro	ugh the MA	CMCTL register)		
-	MR0	R/W	0x1000	Ethernet PHY Management Register 0 – Control	963
-	MR1	RO	0x7809	Ethernet PHY Management Register 1 – Status	965
-	MR2	RO	0x0161	Ethernet PHY Management Register 2 – PHY Identifier 1	967
-	MR3	RO	0xB410	Ethernet PHY Management Register 3 – PHY Identifier 2	968
-	MR4	R/W	0x01E1	Ethernet PHY Management Register 4 – Auto-Negotiation Advertisement	969
-	MR5	RO	0x0001	Ethernet PHY Management Register 5 – Auto-Negotiation Link Partner Base Page Ability	971
-	MR6	RO	0x0000	Ethernet PHY Management Register 6 – Auto-Negotiation Expansion	973
-	MR16	RO	0x0040	Ethernet PHY Management Register 16 – Vendor-Specific	974
-	MR17	R/W	0x0002	Ethernet PHY Management Register 17 – Mode Control/Status	975
-	MR27	RO	-	Ethernet PHY Management Register 27 – Special Control/Status	
-	MR29	RO	0x0000	Ethernet PHY Management Register 29 – Interrupt Status	
_	MR30	R/W	0x0000	Ethernet PHY Management Register 30 – Interrupt Mask	980

# Table 18-4. Ethernet Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
-	MR31	R/W	0x0040	Ethernet PHY Management Register 31 – PHY Special Control/Status	982

# 18.6 Ethernet MAC Register Descriptions

The remainder of this section lists and describes the Ethernet MAC registers, in numerical order by address offset. Also see "MII Management Register Descriptions" on page 962.


### Register 1: Ethernet MAC Raw Interrupt Status/Acknowledge (MACRIS/MACIACK), offset 0x000

The MACRIS/MACIACK register is the interrupt status and acknowledge register. On a read, this register gives the current status value of the corresponding interrupt prior to masking. On a write, setting any bit clears the corresponding interrupt status bit.

Ethernet MAC Raw Interrupt Status/Acknowledge (MACRIS/MACIACK)

Base 0x4004.8000

Offset 0x000 Type R/W1C, reset 0x0000.0000



#### Value Description

- An enabled interrupt in the PHY layer has occurred. MR29 in the PHY must be read to determine the specific PHY event that triggered this interrupt.
- 0 No interrupt.

This bit is cleared by writing a 1 to it.

5 **MDINT** R/W1C 0 MII Transaction Complete

#### Value Description

- A transaction (read or write) on the MII interface has completed successfully.
- 0 No interrupt.

This bit is cleared by writing a 1 to it.

Bit/Field	Name	Туре	Reset	Description
4	RXER	R/W1C	0	Receive Error
				Value Description
				An error was encountered on the receiver. The possible errors that can cause this interrupt bit to be set are:
				<ul> <li>A receive error occurs during the reception of a frame (100 Mbps only).</li> </ul>
				The frame is not an integer number of bytes (dribble bits) due to an alignment error.
				■ The CRC of the frame does not pass the FCS check.
				The length/type field is inconsistent with the frame data size when interpreted as a length field.
				0 No interrupt.
				This bit is cleared by writing a 1 to it.
3	FOV	R/W1C	0	FIFO Overrun
				Value Description
				1 An overrun was encountered on the receive FIFO.
				0 No interrupt.
				This bit is cleared by writing a 1 to it.
2	TXEMP	R/W1C	0	Transmit FIFO Empty
				Value Description
				1 The packet was transmitted and that the TX FIFO is empty.
				0 No interrupt.
				This bit is cleared by writing a 1 to it.
1	TXER	R/W1C	0	Transmit Error
				Value Description
				An error was encountered on the transmitter. The possible errors that can cause this interrupt bit to be set are:
				The data length field stored in the TX FIFO exceeds 2032 decimal (buffer length - 16 bytes of header data). The frame is not sent when this error occurs.
				The retransmission attempts during the backoff process have exceeded the maximum limit of 16 decimal.
				0 No interrupt.
				Writing a 1 to this bit clears it and resets the TX FIFO write pointer.


Bit/Field	Name	Туре	Reset	Description	
0	RXINT	R/W1C	0	Packet Received	
				Value Description	
				1 At least one packet has been received and is stored in the receiver FIFO.	
				0 No interrupt.	
				This bit is cleared by writing a 1 to it.	

## Register 2: Ethernet MAC Interrupt Mask (MACIM), offset 0x004

This register allows software to enable/disable Ethernet MAC interrupts. Clearing a bit disables the interrupt, while setting the bit enables it.

Ethernet MAC Interrupt Mask (MACIM)

Base 0x4004.8000 Offset 0x004 Type R/W, reset 0x0000.007F



Bit/Field	Name	Туре	Reset	Description
31:7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	PHYINTM	R/W	1	Mask PHY Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the PHYINT bit in the MACRIS/MACIACK register is set.
				O The PHYINT interrupt is suppressed and not sent to the interrupt controller.
5	MDINTM	R/W	1	Mask MII Transaction Complete
				Value Description
				An interrupt is sent to the interrupt controller when the MDINT bit in the MACRIS/MACIACK register is set.
				The MDINT interrupt is suppressed and not sent to the interrupt controller.
4	RXERM	R/W	1	Mask Receive Error

#### Value Description

- 1 An interrupt is sent to the interrupt controller when the  $\mathtt{RXER}$  bit in the MACRIS/MACIACK register is set.
- 0 The RXER interrupt is suppressed and not sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
3	FOVM	R/W	1	Mask FIFO Overrun
				Value Description
				An interrupt is sent to the interrupt controller when the FOV bit in the MACRIS/MACIACK register is set.
				O The FOV interrupt is suppressed and not sent to the interrupt controller.
2	TXEMPM	R/W	1	Mask Transmit FIFO Empty
				Value Description
				An interrupt is sent to the interrupt controller when the TXEMP bit in the MACRIS/MACIACK register is set.
				O The TXEMP interrupt is suppressed and not sent to the interrupt controller.
1	TXERM	R/W	1	Mask Transmit Error
				Value Description
				An interrupt is sent to the interrupt controller when the TXER bit in the MACRIS/MACIACK register is set.
				O The TXER interrupt is suppressed and not sent to the interrupt controller.
0	RXINTM	R/W	1	Mask Packet Received
				Value Description
				An interrupt is sent to the interrupt controller when the RXINT bit in the MACRIS/MACIACK register is set.
				O The RXINT interrupt is suppressed and not sent to the interrupt controller.

## Register 3: Ethernet MAC Receive Control (MACRCTL), offset 0x008


This register configures the receiver and controls the types of frames that are received.

It is important to note that when the receiver is enabled, all valid frames with a broadcast address of FF-FF-FF-FF-FF in the Destination Address field are received and stored in the RX FIFO, even if the AMUL bit is not set.

#### Ethernet MAC Receive Control (MACRCTL)

Base 0x4004.8000 Offset 0x008

Type R/W, reset 0x0000.0008



Bit/Field	Name	Туре	Reset	Description
31:5	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	RSTFIFO	R/W	0	Clear Receive FIFO
				Value Description
				1 Clear the receive FIFO. The receive FIFO should be cleared when software initialization is performed.
				0 No effect.
				This bit is automatically cleared when read.
				The receiver should be disabled (RXEN = 0), before a reset is initiated (RSTFIFO = 1). This sequence flushes and resets the RX FIFO.
3	BADCRC	R/W	1	Enable Reject Bad CRC
				Value Description
				1 Enables the rejection of frames with an incorrectly calculated CRC. If a bad CRC is encountered, the RXER bit in the <b>MACRIS</b> register is set and the receiver FIFO is reset.
				O Disables the rejection of frames with an incorrectly calculated CRC.
2	PRMS	R/W	0	Enable Promiscuous Mode
				Value Description
				1 Enables Promiscuous mode, which accepts all valid frames,

0

regardless of the specified Destination Address.

programmed Destination Address.

Disables Promiscuous mode, accepting only frames with the

Bit/Field	Name	Туре	Reset	Description
1	AMUL	R/W	0	Enable Multicast Frames
				Value Description  1 Enables the reception of multicast frames.  0 Disables the reception of multicast frames.
0	RXEN	R/W	0	Enable Receiver  Value Description  1 Enables the Ethernet receiver.  0 Disables the receiver. All frames are ignored.


## Register 4: Ethernet MAC Transmit Control (MACTCTL), offset 0x00C

This register configures the transmitter and controls the frames that are transmitted.

Ethernet MAC Transmit Control (MACTCTL)

Base 0x4004.8000 Offset 0x00C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:5	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	DUPLEX	R/W	0	Enable Duplex Mode
				Value Description
				<ol> <li>Enables Duplex mode, allowing simultaneous transmission and reception.</li> </ol>
				0 Disables Duplex mode.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	CRC	R/W	0	Enable CRC Generation
				Value Description
				1 Enables the automatic generation of the CRC and its placement at the end of the packet.
				The frames placed in the TX FIFO are sent exactly as they are written into the FIFO.
				Note that this bit should generally be set.
1	PADEN	R/W	0	Enable Packet Padding
				Value Description
				1 Enables the automatic padding of packets that do not meet the minimum frame size.
				0 Disables automatic padding.

Note that this bit should generally be set.

Bit/Field	Name	Type	Reset	Description
0	TXEN	R/W	0	Enable Transmitter
				Value Description  1 Enables the transmitter.  0 Disables the transmitter.

#### Register 5: Ethernet MAC Data (MACDATA), offset 0x010

**Important:** This register is read-sensitive. See the register description for details.

This register enables software to access the TX and RX FIFOs.

Reads from this register return the data stored in the RX FIFO from the location indicated by the read pointer. The read pointer is then auto incremented to the next RX FIFO location. Reading from the RX FIFO when a frame has not been received or is in the process of being received returns indeterminate data and does not increment the read pointer.


Writes to this register store the data in the TX FIFO at the location indicated by the write pointer. The write pointer is then auto incremented to the next TX FIFO location. Writing more data into the TX FIFO than indicated in the length field results in the data being lost. Writing less data into the TX FIFO than indicated in the length field results in indeterminate data being appended to the end of the frame to achieve the indicated length. Attempting to write the next frame into the TX FIFO before transmission of the first has completed results in the data being lost.

Bytes may not be randomly accessed in either the RX or TX FIFOs. Data must be read from the RX FIFO sequentially and stored in a buffer for further processing. Once a read has been performed, the data in the FIFO cannot be re-read. Data must be written to the TX FIFO sequentially. If an error is made in placing the frame into the TX FIFO, the write pointer can be reset to the start of the TX FIFO by writing the TXER bit of the **MACIACK** register and then the data re-written.

#### Reads

#### Ethernet MAC Data (MACDATA)

Base 0x4004.8000 Offset 0x010




The RXDATA bits represent the next word of data stored in the RX FIFO.

#### Writes

#### Ethernet MAC Data (MACDATA)

Base 0x4004.8000 Offset 0x010 Type WO, reset 0x0000.0000



Bit/Field	ivame	туре	Reset	Description
31:0	TXDATA	WO	0x0000.0000	Transmit FIFO Data

The  $\ensuremath{\mathtt{TXDATA}}$  bits represent the next word of data to place in the TX FIFO for transmission.


### Register 6: Ethernet MAC Individual Address 0 (MACIA0), offset 0x014

This register enables software to program the first four bytes of the hardware MAC address of the Network Interface Card (NIC). The last two bytes are in MACIA1. The 6-byte Individual Address is compared against the incoming Destination Address fields to determine whether the frame should be received.

Ethernet MAC Individual Address 0 (MACIA0)

Base 0x4004.8000

Offset 0x014 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:24	MACOCT4	R/W	0x00	MAC Address Octet 4  The MACOCT4 bits represent the fourth octet of the MAC address used to uniquely identify the Ethernet Controller.
23:16	MACOCT3	R/W	0x00	MAC Address Octet 3  The MACOCT3 bits represent the third octet of the MAC address used to uniquely identify the Ethernet Controller.
15:8	MACOCT2	R/W	0x00	MAC Address Octet 2  The MACOCT2 bits represent the second octet of the MAC address used to uniquely identify the Ethernet Controller.
7:0	MACOCT1	R/W	0x00	MAC Address Octet 1

The MACOCT1 bits represent the first octet of the MAC address used to

uniquely identify the Ethernet Controller.


## Register 7: Ethernet MAC Individual Address 1 (MACIA1), offset 0x018

This register enables software to program the last two bytes of the hardware MAC address of the Network Interface Card (NIC). The first four bytes are in MACIAO. The 6-byte IAR is compared against the incoming Destination Address fields to determine whether the frame should be received.

Ethernet MAC Individual Address 1 (MACIA1)

Base 0x4004.8000

Offset 0x018
Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:8	MACOCT6	R/W	0x00	MAC Address Octet 6
				The MACOCT6 bits represent the sixth octet of the MAC address used to uniquely identify each Ethernet Controller.
7:0	MACOCT5	R/W	0x00	MAC Address Octet 5
				The MACOCT5 bits represent the fifth octet of the MAC address used to

uniquely identify the Ethernet Controller.

### Register 8: Ethernet MAC Threshold (MACTHR), offset 0x01C

In order to increase the transmission rate, it is possible to program the Ethernet Controller to begin transmission of the next frame prior to the completion of the transmission of the current frame.

Caution – Extreme care must be used when implementing this function. Software must be able to guarantee that the complete frame is able to be stored in the transmission FIFO prior to the completion of the transmission frame.

This register enables software to set the threshold level at which the transmission of the frame begins. If the THRESH bits are set to 0x3F, which is the reset value, the early transmission feature is disabled, and transmission does not start until the NEWTX bit is set in the **MACTR** register.

Writing the THRESH field to any value besides 0x3F enables the early transmission feature. Once the byte count of data in the TX FIFO reaches the value derived from the THRESH bits as shown below, transmission of the frame begins. When the THRESH field is clear, transmission of the frame begins after 4 bytes (a single write) are stored in the TX FIFO. Each increment of the THRESH bit field waits for an additional 32 bytes of data (eight writes) to be stored in the TX FIFO. Therefore, a value of 0x01 causes the transmitter to wait for 36 bytes of data to be written while a value of 0x02 makes the wait equal to 68 bytes of written data. In general, early transmission starts when:

```
Number of Bytes \geq 4 ((THRESH x 8) + 1)
```


Reaching the threshold level has the same effect as setting the NEWTX bit in the **MACTR** register. Transmission of the frame begins, and then the number of bytes indicated by the Data Length field is transmitted. Because underrun checking is not performed, if any event, such as an interrupt, delays the filling of the FIFO, the tail pointer may reach and pass the write pointer in the TX FIFO. In this event, indeterminate values are transmitted rather than the end of the frame. Therefore, sufficient bus bandwidth for writing to the TX FIFO must be guaranteed by the software.

If a frame smaller than the threshold level must be sent, the NEWTX bit in the **MACTR** register must be set with an explicit write, which initiates the transmission of the frame even though the threshold limit has not been reached.

If the threshold level is set too small, it is possible for the transmitter to underrun. If this occurs, the transmit frame is aborted, and a transmit error occurs. Note that in this case, the TXER bit in the MACRIS is not set, meaning that the CPU receives no indication that a transmit error happened.

#### Ethernet MAC Threshold (MACTHR)

Base 0x4004.8000 Offset 0x01C



preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
5:0	THRESH	R/W	0x3F	Threshold Value  The THRESH bits represent the early transmit threshold. Once the amount of data in the TX FIFO exceeds the value represented by the above equation, transmission of the packet begins.

## Register 9: Ethernet MAC Management Control (MACMCTL), offset 0x020

This register enables software to control the transfer of data to and from the MII Management registers in the Ethernet PHY layer. The address, name, type, reset configuration, and functional description of each of these registers can be found in Table 18-4 on page 934 and in "MII Management Register Descriptions" on page 962.


In order to initiate a read transaction from the MII Management registers, the WRITE bit must be cleared during the same cycle that the START bit is set.

In order to initiate a write transaction to the MII Management registers, the WRITE bit must be set during the same cycle that the START bit is set.

#### Ethernet MAC Management Control (MACMCTL)

Base 0x4004.8000

Offset 0x020 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description						
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.						
7:3	REGADR	R/W	0x0	MII Register Address						
				The REGADR bit field represents the MII Management register address for the next MII management interface transaction. Refer to Table 18-4 on page 934 for the PHY register offsets.						
				Note that any address that is not valid in the register map should not be written to, and any data read should be ignored.						
2	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.						
1	WRITE	R/W	0	MII Register Transaction Type						

#### Value Description

- The next operation of the next MII management interface is a write transaction.
- 0 The next operation of the next MII management interface is a read transaction.

Bit/Field	Name	Type	Reset	Description					
0	START	R/W	0	MII Register Transaction Enable					
				Value Description					
				The MII register located at REGADR is read (WRITE=0) or written (WRITE=1).					
				0 No effect.					

## Register 10: Ethernet MAC Management Divider (MACMDV), offset 0x024


This register enables software to set the clock divider for the Management Data Clock (MDC). This clock is used to synchronize read and write transactions between the system and the MII Management registers. The frequency of the MDC clock can be calculated from the following formula:

$$F_{mdc} = \frac{F_{ipclk}}{2 \times (MACMDV + 1)}$$

The clock divider must be written with a value that ensures that the MDC clock does not exceed a frequency of 2.5 MHz.

#### Ethernet MAC Management Divider (MACMDV)

Base 0x4004.8000 Offset 0x024 Type R/W, reset 0x0000.0080



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7:0	DIV	R/W	0x80	Clock Divider

The DIV bits are used to set the clock divider for the MDC clock used to transmit data between the MAC and PHY layers.


### Register 11: Ethernet MAC Management Transmit Data (MACMTXD), offset 0x02C

This register holds the next value to be written to the MII Management registers.

Ethernet MAC Management Transmit Data (MACMTXD)

Base 0x4004.8000

Offset 0x02C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	MDTX	R/W	0x0000	MII Register Transmit Data

The  $\mathtt{MDTX}$  bits represent the data to be written in the next  $\mathbf{MII}$ management transaction.


### Register 12: Ethernet MAC Management Receive Data (MACMRXD), offset 0x030

This register holds the last value read from the MII Management registers.

#### Ethernet MAC Management Receive Data (MACMRXD)

Base 0x4004.8000

Offset 0x030 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	MDRX	R/W	0x0000	MII Register Receive Data

The  ${\tt MDRX}$  bits represent the data that was read in the previous  ${\tt MII}$ management transaction.


## Register 13: Ethernet MAC Number of Packets (MACNP), offset 0x034

This register holds the number of frames that are currently in the RX FIFO. When  $\mathtt{NPR}$  is 0, there are no frames in the RX FIFO, and the RXINT bit is clear. When  $\mathtt{NPR}$  is any other value, at least one frame is in the RX FIFO, and the RXINT bit in the **MACRIS** register is set.

Note: The FCS bytes are not included in the NPR value. As a result, the NPR value could be zero before the FCS bytes are read from the FIFO. In addition, a new packet could be received before the NPR value reaches zero. To ensure that the entire packet is received, either use the DriverLib EthernetPacketGet() API or compare the number of bytes received to the Length field from the frame to determine when the packet has been completely read.

Ethernet MAC Number of Packets (MACNP)

Base 0x4004.8000 Offset 0x034 Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:6	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5:0	NPR	RO	0x00	Number of Packets in Receive FIFO

The NPR bits represent the number of packets stored in the RX FIFO. While the NPR field is greater than 0, the RXINT interrupt in the **MACRIS** register is set.


#### Register 14: Ethernet MAC Transmission Request (MACTR), offset 0x038

This register enables software to initiate the transmission of the frame currently located in the TX FIFO. Once the frame has been transmitted from the TX FIFO or a transmission error has been encountered, the NEWTX bit is automatically cleared.

Ethernet MAC Transmission Request (MACTR)

Base 0x4004.8000

Offset 0x038
Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	NEWTX	R/W	0	New Transmission

Value Description

- Initiates an Ethernet transmission once the packet has been placed in the TX FIFO.
- 0 The transmission has completed.


If early transmission is being used (see the **MACTHR** register), this bit does not need to be set.

## Register 15: Ethernet MAC Timer Support (MACTS), offset 0x03C

This register enables software to enable highly precise timing on the transmission and reception of frames. To enable this function, set the TSEN bit.

Ethernet MAC Timer Support (MACTS)

Base 0x4004.8000 Offset 0x03C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	TSEN	R/W	0	Time Stamp Enable

Value Description

- The TX and RX interrupts are routed to the CCP inputs of General-Purpose Timer 3.
- No effect. 0

## Register 16: Ethernet MAC LED Encoding (MACLED), offset 0x040

This register enables software to select the source that causes the LED1 and LED0 signal to toggle.

#### Ethernet MAC LED Encoding (MACLED)

reserved


RO

0x0

Base 0x4004.8000 Offset 0x040

7:4

Type R/W, reset 0x0000.0100



Bit/Field	Name	Type	Reset	Description
31:12	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11:8	LED1	R/W	0x1	LED1 Source

The LED1 field selects the source that toggles the LED1 signal.

Value Description 0x0 Link OK 0x1 RX or TX Activity (Default LED1)

Note that when RX or TX activity stops, the LED output is

extended by 128 ms.

0x2-0x4 Reserved 100BASE-TX mode 0x5 10BASE-T mode 0x6 0x7 Full-Duplex

0x8 Link OK & Blink=RX or TX Activity

0x9-0xF Reserved

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description					
3:0	LED0	R/W	0x0	LED0 Source The LED0 field selects the source that toggles the LED0 signal.					
				Value Description					
				0x0 Link OK (Default LED0)					
				0x1 RX or TX Activity					
				Note that when RX or TX activity stops, the LED output is extended by 128 ms.					
				0x2-0x4 Reserved					
				0x5 100BASE-TX mode					
				0x6 10BASE-T mode					
				0x7 Full-Duplex					
				0x8 Link OK & Blink=RX or TX Activity					
				0x9-0xF Reserved					


### Register 17: Ethernet PHY MDIX (MDIX), offset 0x044

This register enables the transmit and receive lines to be reversed in order to implement the MDI/MDI-X functionality. Software can implement the MDI/MDI-X configuration by using any available timer resource such as SysTick (see "System Timer (SysTick)" on page 114 for more information) to implement this functionality. Once the Ethernet Controller has been configured and enabled, software should check to see if the LINK bit in the MR1 register has been set within approximately 1 s; if not, set the EN bit of the MDIX register to switch the reverse the transmit and receive lines to the PHY layer. Software should check the LINK bit again after approximately another 1 s and if no link has been established, the EN bit should be cleared. Software must continue to change the termination back and forth by setting and clearing the EN bit every 1 s until a link is established.



Base 0x4004.8000 Offset 0x044

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	EN	R/W	0	MDI/MDI-X Enable

#### Value Description

- 1 The transmit and receive signals are switched such that data is received on the transmit signals TXOP and TXON; data is transmitted on the receive signals RXIP and RXIN
- 0 No effect.

## 18.7 MII Management Register Descriptions

The *IEEE 802.3 standard* specifies a register set for controlling and gathering status from the PHY layer. The registers are collectively known as the MII Management registers. The **Ethernet MAC Management Control (MACMCTL)** register is used to access the MII Management registers, see page 952. All addresses given are absolute. Addresses not listed are reserved; these addresses should not be written to and any data read should be ignored. Also see "Ethernet MAC Register Descriptions" on page 936.

## Register 18: Ethernet PHY Management Register 0 – Control (MR0), address 0x00

This register enables software to configure the operation of the PHY layer. The default settings of these registers are designed to initialize the Ethernet Controller to a normal operational mode without configuration.

Ethernet PHY Management Register 0 – Control (MR0)

Base 0x4004.8000 Address 0x00 Type R/W, reset 0x1000

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	RESET		SPEEDSL	ANEGEN	PWRDN	ISO	RANEG	DUPLEX	COLT				reserved		ı	
Type Reset	R/W 0	R/W 0	R/W 0	R/W 1	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0
E	Bit/Field		Nam	ie	Тур	oe	Reset	Desc	cription							
	15		RESI	ΞT	R/\	W	0	Rese	et Regis	ters						
									Ū							
									ie Desc							
								1					to their d initialized		tate and	the
								0	No e	ffect.						
								Once	e the res	et opera	tion has o	complete	ed, this bit	is auto	matically	cleared
								by h	ardware							
	14		LOOP	BK	R/\	W	0	Loop	back M	ode						
								Valu	ie Desc	ription						
								1					f operation			
										nal input mitter.	ts and re	ceives th	ne data th	at is tra	ansmitted	by the
								0	No e	ffect.						
	13		SPEE	DSL	R/\	W	0	Spe	ed Selec	t						
								Valu	ie Desc	ription						
								1	Enab	les the 1	100 Mbps	s mode o	of operati	on (100	BASE-T	X).
								0	Enab	les the 1	10 Mbps	mode of	operatio	n (10B <i>A</i>	ASE-T).	
					_			_		–						
	12		ANEG	EN	R/\	W	1	Auto	-Negotia	ation Ena	able					
								Valu	ie Desc	ription						
								1			auto-nego	otiation p	orocess.			
								0	No e	ffect.						

Bit/Field	Name	Туре	Reset	Description
11	PWRDN	R/W	0	Power Down
				Value Description
				The PHY layer is configured to be in a low-power consuming state. All data on the data inputs is ignored.
				0 No effect.
10	ISO	R/W	0	Isolate
.0	.00		·	
				Value Description  1 The transmit and receive data paths are isolated and all data
				1 The transmit and receive data paths are isolated and all data being transmitted and received is ignored.
				0 No effect.
9	RANEG	R/W	0	Restart Auto-Negotiation
				Value Description
				Restarts the auto-negotiation process.
				0 No effect.
				Once the restart has initiated, this bit is automatically cleared by hardware.
8	DUPLEX	R/W	0	Set Duplex Mode
				Value Description
				1 Enables the Full-Duplex mode of operation. This bit can be set by software in a manual configuration process or by the auto-negotiation process.
				0 Enables the Half-Duplex mode of operation.
				Note that in 10BASE-T half-duplex mode, the transmitted data is looped back on the receive path.
7	COLT	R/W	0	Collision Test
				Value Description
				1 Enables the Collision Test mode of operation.
				0 No effect.
				The ${\tt COLT}$ bit is set after the initiation of a transmission and is cleared once the transmission is halted.
6:0	reserved	R/W	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
				These bits should always be written as zero.

## Register 19: Ethernet PHY Management Register 1 – Status (MR1), address 0x01

This register enables software to determine the capabilities of the PHY layer and perform its initialization and operation appropriately.

Ethernet PHY Management Register 1 – Status (MR1)

Base 0x4004.8000 Address 0x01 Type RO, reset 0x7809

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	reserved	100X_F	100X_H	10T_F	10T_H		' '	reserved		1	ANEGC	RFAULT	ANEGA	LINK	JAB	EXTD
Type Reset	RO 0	RO 1	RO 1	RO 1	RO 1	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RC 0	RO 1	RO 0	RC 0	RO 1
В	Bit/Field		Nam	ne	Тур	ре	Reset	Descr	ription							
	15		reserv	/ed	R	0	0	comp	atibility	with fut	ure produ	ucts, the	of a rese value of operation	a reserv	•	
	14		100X	_F	R	)	1	100B	ASE-T	X Full-Di	uplex Mo	de				
								Value	e Desc	cription						
								1		Ethernet Duplex n		er is cap	able of s	upportin	g 100B <i>A</i>	ASE-TX
								0			Controll Full-Du		capable de.	of suppo	orting	
	13		100X	_H	R	0	1	100B	ASE-T	X Half-D	uplex Mo	ode				
								Value	e Desc	cription						
								1		Ethernet Duplex r		er is cap	able of s	upportin	g 100BA	ASE-TX
								0			Controll Half-Du		capable de.	of suppo	orting	
	12		10T_	_F	R	)	1	10BA	SE-T F	- ull-Dupl	ex Mode					
								Value	e Desc	cription						
								1		Ethernet Duplex n		er is cap	able of s	upportin	g 10BAS	SE-T
								0		Ethernet Duplex n		er is not o	capable o	of suppo	rting 10E	BASE-T
	11		10T_	_H	R	0	1	10BA	SE-T I	Half-Dup	ex Mode	<b>:</b>				
								Value	e Desc	cription						
								1		Ethernet Duplex r		er is cap	able of s	upportin	g 10BAS	SE-T
								0		Ethernet Duplex r		er is not o	capable (	of suppo	rting 10E	BASE-T


Bit/Field	Name	Туре	Reset	Description			
10:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.			
5	ANEGC	RO	0	Auto-Negotiation Complete			
				Value Description			
				The auto-negotiation process has been completed and that the extended registers defined by the auto-negotiation protocol are valid.			
				The auto-negotiation process is not complete.			
4	RFAULT	RC	0	Remote Fault			
				Value Description			
				1 A remote fault condition has been detected.			
				0 A remote fault condition has not been detected.			
				This bit remains set until it is read, even if the condition no longer exists.			
3	ANEGA	RO	1	Auto-Negotiation			
				Value Description			
				The Ethernet Controller has the ability to perform auto-negotiation.			
				The Ethernet Controller does not have the ability to perform auto-negotiation.			
2	LINK	RO	0	Link Made			
				Value Description			
				1 A valid link has been established by the Ethernet Controller.			
				0 A valid link has not been established by the Ethernet Controller.			
1	JAB	RC	0	Jabber Condition			
				Value Description			
				A jabber condition has been detected by the Ethernet Controller.			
				A jabber condition has not been detected by the Ethernet Controller.			
				This bit remains set until it is read, even if the jabber condition no longer exists.			
0	EXTD	RO	1	Extended Capabilities			
				Value Description			
				1 The Ethernet Controller provides an extended set of capabilities that can be accessed through the extended register set.			
				The Ethernet Controller does not provide extended capabilities.			

## Register 20: Ethernet PHY Management Register 2 – PHY Identifier 1 (MR2), address 0x02

This register, along with **MR3**, provides a 32-bit value indicating the manufacturer, model, and revision information.

Ethernet PHY Management Register 2 – PHY Identifier 1 (MR2)

Base 0x4004.8000 Address 0x02 Type RO, reset 0x0161




This field, along with the  $\mathtt{OUI[5:0]}$  field in **MR3**, makes up the Organizationally Unique Identifier indicating the PHY manufacturer.

## Register 21: Ethernet PHY Management Register 3 – PHY Identifier 2 (MR3), address 0x03

This register, along with **MR2**, provides a 32-bit value indicating the manufacturer, model, and revision information.

Ethernet PHY Management Register 3 – PHY Identifier 2 (MR3)

Base 0x4004.8000 Address 0x03 Type RO, reset 0xB410



Bit/Field	Name	Type	Reset	Description
15:10	OUI[5:0]	RO	0x2D	Organizationally Unique Identifier[5:0]  This field, along with the OUI[21:6] field in MR2, makes up the Organizationally Unique Identifier indicating the PHY manufacturer.
9:4	MN	RO	0x01	Model Number The MN field represents the Model Number of the PHY.
3:0	RN	RO	0x0	Revision Number

The  ${\tt RN}$  field represents the Revision Number of the PHY implementation.

# Register 22: Ethernet PHY Management Register 4 – Auto-Negotiation Advertisement (MR4), address 0x04

This register provides the advertised abilities of the Ethernet Controller used during auto-negotiation. Bits 8:5 represent the Technology Ability Field bits. This field can be overwritten by software to auto-negotiate to an alternate common technology. Writing to this register has no effect until auto-negotiation is re-initiated by setting the RANEG bit in the **MR0** register.

Ethernet PHY Management Register 4 – Auto-Negotiation Advertisement (MR4)

Base 0x4004.8000 Address 0x04 Type R/W, reset 0x01E1

_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	NP	reserved	RF		rese	rved		A3	A2	A1	A0			S		
Type Reset	RO 0	RO 0	R/W 0	RO 0	RO 0	RO 0	RO 0	R/W 1	R/W 1	R/W 1	R/W 1	RO 0	RO 0	RO 0	RO 0	RO 1
В	Bit/Field		Nan	ne	Туј	ре	Reset	Des	cription							
	15		NF	•	R	0	0	Nex	t Page							
								Valu	ue Desc	ription						
								1	provi		Controll detailed					nges to
								0	The I	Ethernet	Controlle	er is not c	capable o	of Next P	age exch	nanges.
	14		reser	ved	R	0	0	com	patibility	with futu	rely on thure produced	icts, the	value of	a reserv		
	13		RF	=	R/	W	0	Rem	note Fau	It						
								Valu	ue Desc	ription						
								1		ates to the	he link pa tered.	artner tha	at a Ren	note Fau	lt conditi	on has
								0	No R	temote F	ault con	dition ha	s been e	encounte	red.	
	12:9		reser	ved	R	0	0x0	com	patibility	with futu	rely on thure produead-mode	ucts, the	value of	a reserv		
	8		A3	3	R/	W	1	Tech	nology	Ability Fi	eld [3]					
								Valu	ue Desc	ription						
								1	signa is no	aling prot t used, tl	Controlletocol. If so his bit ca	oftware n be clea	wants to ared and	ensure auto-ne	that this gotiation	mode

0

The Ethernet Controller does not support the 100Base-TX

full-duplex signaling protocol.


Bit/Field	Name	Туре	Reset	Description				
7	A2	R/W	1	Technology Ability Field [2]				
				Value Description				
				The Ethernet Controller supports the 100Base-TX half-duplex signaling protocol. If software wants to ensure that this mode is not used, this bit can be cleared and auto-negotiation re-initiated with the RANEG bit in the <b>MR0</b> register.				
				0 The Ethernet Controller does not support the 100Base-TX half-duplex signaling protocol.				
6	A1	R/W	1	Technology Ability Field [1]				
				Value Description				
				The Ethernet Controller supports the 10BASE-T full-duplex signaling protocol. If software wants to ensure that this mode is not used, this bit can be cleared and auto-negotiation re-initiated with the RANEG bit in the MR0 register.				
				The Ethernet Controller does not support the 10BASE-T full-duplex signaling protocol.				
5	A0	R/W	1	Technology Ability Field [0]				
				Value Description				
				The Ethernet Controller supports the 10BASE-T half-duplex signaling protocol. If software wants to ensure that this mode is not used, this bit can be cleared and auto-negotiation re-initiated with the RANEG bit in the <b>MR0</b> register.				
				The Ethernet Controller does not support the 10BASE-T half-duplex signaling protocol.				
4:0	S	RO	0x1	Selector Field This field encodes 32 possible messages for communicating between Ethernet Controllers. This field is hard-coded to 0x01, indicating that the Stellaris Ethernet Controller is <i>IEEE 802.3</i> compliant.				

## Register 23: Ethernet PHY Management Register 5 – Auto-Negotiation Link Partner Base Page Ability (MR5), address 0x05

This register provides the advertised abilities of the link partner's Ethernet Controller that are received and stored during auto-negotiation.

Ethernet PHY Management Register 5 - Auto-Negotiation Link Partner Base Page Ability (MR5)

Base 0x4004.8000 Address 0x05 Type RO, reset 0x0001




Bit/Field	Name	Type	Reset	Description				
4:0	S	RO	0x01	Selector Field				
				This field encodes possible messages for communicating between Ethernet Controllers.				
				Value	Description			
				0x00	Reserved			
				0x01	IEEE Std 802.3			
				0x02	IEEE Std 802.9 ISLAN-16T			
				0x03	IEEE Std 802.5			
				0x04	IEEE Std 1394			
				0x05–0x1F	Reserved			

# Register 24: Ethernet PHY Management Register 6 – Auto-Negotiation Expansion (MR6), address 0x06

This register enables software to determine the auto-negotiation and next page capabilities of the Ethernet Controller and the link partner after auto-negotiation.

Ethernet PHY Management Register 6 - Auto-Negotiation Expansion (MR6)

Base 0x4004.8000 Address 0x06 Type RO, reset 0x0000




# Register 25: Ethernet PHY Management Register 16 – Vendor-Specific (MR16), address 0x10

This register contains a silicon revision identifier.

Ethernet PHY Management Register 16 – Vendor-Specific (MR16)

Base 0x4004.8000 Address 0x10 Type RO, reset 0x0040



Bit/Field	Name	Туре	Reset	Description
15:10	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9:6	SR	RO	0x1	Silicon Revision Identifier  This field contains the four-bit identifier for the silicon revision.
5:0	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 26: Ethernet PHY Management Register 17 – Mode Control/Status (MR17), address 0x11

This register provides the means for controlling and observing various PHY layer modes.

Ethernet PHY Management Register 17 – Mode Control/Status (MR17)

Base 0x4004.8000 Address 0x11 Type R/W, reset 0x0002

11

10:9

**LSQE** 

reserved

R/W

RO

l																
Type Reset	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	R/W 0	RO 1	R/W 0
Е	Bit/Field		Nan	ne	Ty	ре	Reset	Des	cription							
	15		reser	ved	R/	W	0	com	patibility	with futu	ure prod	ucts, the	of a resound of operation	a reserv	•	
								lmı	portan	t: This begin		always b	e written	with a 0	to ensur	e proper
	14		FAST	RIP	R/	W	0	10-E	BASE-T	Fast Mod	de Enab	le				
								Val	ue Desc	ription						
								1	Enat	les PHY	T_10 te:	st mode.				
								0	No e	ffect.						
	13		EDF	PD	R/	W	0	Ena	ble Ener	gy Dete	ct Power	Down				
								Val	ue Desc	ription						
								1	Enab	les the E	Energy D	Detect Po	ower Dov	vn mode		
								0	No e	ffect.						
	12		reser	ved	R/	W	0	com	patibility	with fut	ure prodi	ucts, the	of a resolute of operation	a reserv	•	
								lm	portan	t: This b	oit must a	always b	e written	with a 0	to ensur	e proper

operation.

Enables a lower threshold meaning more sensitivity to the signal

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be

preserved across a read-modify-write operation.

Low Squelch Enable
Value Description

levels.
No effect.

0

0


Bit/Field	Name	Type	Reset	Description
8	FASTEST	R/W	0	Auto-Negotiation Test Mode
				Value Description
				1 Enables the Auto-Negotiation Test mode.
				0 No effect.
7:3	reserved	R/W	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
				<b>Important:</b> This bit must always be written with a 0 to ensure proper operation.
2	FGLS	R/W	0	Force Good Link Status
				Value Description
				1 Forces the 100BASE-T link to be active.
				0 No effect.
				<b>Note:</b> This bit should only be set when testing.
1	ENON	RO	1	Energy On
				Value Description
				1 Energy is detected on the line.
				0 Valid energy has not been detected on the line within 256 ms.
				This bit is set by a hardware reset, but is unaffected by a software reset.
0	reserved	R/W	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
				Important: This bit must always be written with a 0 to ensure proper operation.

# Register 27: Ethernet PHY Management Register 27 - Special Control/Status (MR27), address 0x1B

This register shows the status of the 10BASE-T polarity.

Ethernet PHY Management Register 27 - Special Control/Status (MR27)

Base 0x4004.8000 Address 0x1B Type RO, reset -



Value Description

- The 10BASE-T is reversed polarity.
- 0 The 10BASE-T is normal polarity.

RO 3:0 0x0 Software should not rely on the value of a reserved bit. To provide reserved compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 28: Ethernet PHY Management Register 29 – Interrupt Status (MR29), address 0x1D

This register contains information about the source of PHY layer interrupts. Reading this register clears any bits that are set. The PHYINT bit is set in the **MACRIS/MACIACK** register whenever any of the bits in this register are set.

Ethernet PHY Management Register 29 – Interrupt Status (MR29)

Base 0x4004.8000 Address 0x1D Type RO, reset 0x0000

_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	'		'	resei			' '		EONIS	ANCOMPIS	RFLTIS	LDIS	LPACKIS	PDFIS	PRXIS	reserved
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0
В	it/Field		Nam	ne	Тур	ре	Reset	Des	cription							
	15:8		reser	ved	R	0	0x00	com	patibility	ould not / with futo cross a r	ıre produ	icts, the	value of	a reserv	•	vide hould be
	7		EON	IS	R	)	0	ENE	RGYO	N Interrup	ot					
								Valı	ue Des	cription						
								1		nterrupt h e <b>MR17</b> ı		generat	ted due to	o the EN	ON bit be	eing set
								0	No ii	nterrupt.						
								This	bit is cl	eared by	reading	the valu	ie.			
	6		ANCO	MPIS	R	)	0	Auto	o-Negoti	ation Co	mplete Ir	nterrupt				
								Valı	ue Desc	cription						
								1		nterrupt hotiation.	as been	generat	ted due to	o the co	mpletion	of auto
								0		nterrupt.						
								This	bit is cl	eared by	reading	the valu	ıe.			
	5		RFLT	īs	R	)	0	Ren	note Faเ	ılt Interru	pt					
								Valı	ue Desc	cription						
								1		nterrupt h		generat	ted due to	o the de	tection c	of a
								0	No ii	nterrupt.						
								This	bit is cl	eared by	reading	the valu	ie.			
	4		LDI	S	R	)	0	Link	Down I	nterrupt						
								Valu	ue Des	cription						
								1	An ir	nterrupt h ear.	as been	generat	ted becau	use the I	LINK bit	in <b>MR1</b>
								0	No ii	nterrupt.						
								This	bit is cl	eared by	reading	the valu	ie.			


Bit/Field	Name	Туре	Reset	Description
3	LPACKIS	RO	0	Auto-Negotiation LP Acknowledge
				Value Description
				An interrupt has been generated due to the reception of an acknowledge message from the link partner during auto-negotiation.
				0 No interrupt.
				This bit is cleared by reading the value.
2	PDFIS	RO	0	Parallel Detection Fault
				Value Description
				An interrupt has been generated due to the detection of a parallel detection fault during auto negotiation.
				0 No interrupt.
				This bit is cleared by reading the value.
1	PRXIS	RO	0	Auto Negotiation Page Received
				Value Description
				An interrupt has been generated due to the reception of an auto negotiation page from the link partner.
				0 No interrupt.
				This bit is cleared by reading the value.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 29: Ethernet PHY Management Register 30 – Interrupt Mask (MR30), address 0x1E

This register enables interrupts to be generated by the various sources of PHY layer interrupts.

Ethernet PHY Management Register 30 – Interrupt Mask (MR30)

Base 0x4004.8000 Address 0x1E Type R/W, reset 0x0000



controller.


Bit/Field	Name	Туре	Reset	Description
3	LPACKIM	R/W	0	Auto-Negotiation LP Acknowledge Enabled
				Value Description
				An interrupt is sent to the interrupt controller when the LPACKIS bit in the MR29 register is set.
				0 The LPACKIS interrupt is suppressed and not sent to the interrupt controller.
2	PDFIM	R/W	0	Parallel Detection Fault Enabled
				Value Description
				An interrupt is sent to the interrupt controller when the PDFIS bit in the <b>MR29</b> register is set.
				O The PDFIS interrupt is suppressed and not sent to the interrupt controller.
1	PRXIM	R/W	0	Auto Negotiation Page Received Enabled
				Value Description
				An interrupt is sent to the interrupt controller when the PRXIS bit in the <b>MR29</b> register is set.
				O The PRXIS interrupt is suppressed and not sent to the interrupt controller.
0	reserved	R/W	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 30: Ethernet PHY Management Register 31 – PHY Special Control/Status (MR31), address 0x1F

This register provides special control and status for the PHY layer.

Ethernet PHY Management Register 31 – PHY Special Control/Status (MR31)

Base 0x4004.8000 Address 0x1F Type R/W, reset 0x0040



# 19 Universal Serial Bus (USB) Controller


The Stellaris<sup>®</sup> USB controller operates as a full-speed or low-speed function controller during point-to-point communications with USB Host, Device, or OTG functions. The controller complies with the USB 2.0 standard, which includes SUSPEND and RESUME signaling. 32 endpoints including two hard-wired for control transfers (one endpoint for IN and one endpoint for OUT) plus 30 endpoints defined by firmware along with a dynamic sizable FIFO support multiple packet queueing. µDMA access to the FIFO allows minimal interference from system software. Software-controlled connect and disconnect allows flexibility during USB device start-up. The controller complies with OTG standard's session request protocol (SRP) and host negotiation protocol (HNP).

The Stellaris USB module has the following features:

- Complies with USB-IF certification standards
- USB 2.0 full-speed (12 Mbps) and low-speed (1.5 Mbps) operation with integrated PHY
- 4 transfer types: Control, Interrupt, Bulk, and Isochronous
- 32 endpoints
  - 1 dedicated control IN endpoint and 1 dedicated control OUT endpoint
  - 15 configurable IN endpoints and 15 configurable OUT endpoints
- 4 KB dedicated endpoint memory: one endpoint may be defined for double-buffered 1023-byte isochronous packet size
- VBUS droop and valid ID detection and interrupt
- Efficient transfers using Micro Direct Memory Access Controller (μDMA)
  - Separate channels for transmit and receive for up to three IN endpoints and three OUT endpoints
  - Channel requests asserted when FIFO contains required amount of data

# 19.1 Block Diagram

Figure 19-1. USB Module Block Diagram



# 19.2 Signal Description

The following table lists the external signals of the USB controller and describes the function of each. Some USB controller signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for these USB signals. The AFSEL bit in the GPIO Alternate Function Select (GPIOAFSEL) register (page 430) should be set to choose the USB function. The number in parentheses is the encoding that must be programmed into the PMCn field in the GPIO Port Control (GPIOPCTL) register (page 448) to assign the USB signal to the specified GPIO port pin. The USBOVBUS and USBOID signals are configured by clearing the appropriate DEN bit in the GPIO Digital Enable (GPIODEN) register. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407. The remaining signals (with the word "fixed" in the Pin Mux/Pin Assignment column) have a fixed pin assignment and function.

Note: When used in OTG mode, USBOVBUS and USBOID do not require any configuration as they are dedicated pins for the USB controller and directly connect to the USB connector's VBUS and ID signals. If the USB controller is used as either a dedicated Host or Device, the DEVMODOTG and DEVMOD bits in the USB General-Purpose Control and Status (USBGPCS) register can be used to connect the USBOVBUS and USBOID inputs to fixed levels internally, freeing the PBO and PB1 pins for GPIO use. For proper self-powered Device operation, the VBUS value must still be monitored to assure that if the Host removes VBUS, the self-powered Device disables the D+/D- pull-up resistors. This function can be accomplished by connecting a standard GPIO to VBUS.

The termination resistors for the USB PHY have been added internally, and thus there is no need for external resistors. For a device, there is a 1.5 KOhm pull-up on the D+ and for a host there are 15 KOhm pull-downs on both D+ and D-.

Table 19-1. USB Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
USB0DM	70	fixed	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
USB0DP	71	fixed	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
USB0EPEN	19 24 34 72 83	PG0 (7) PC5 (6) PA6 (8) PB2 (8) PH3 (4)	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USB0ID	66	PB0	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).
USB0PFLT	22 23 35 65 74 76 87	PC7 (6) PC6 (7) PA7 (8) PB3 (8) PE0 (9) PH4 (4) PJ1 (9)	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
USB0RBIAS	73	fixed	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
USB0VBUS	67	PB1	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# Table 19-2. USB Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
USB0DM	C11	fixed	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
USB0DP	C12	fixed	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
USB0EPEN	K1 M1 L6 A11 D10	PG0 (7) PC5 (6) PA6 (8) PB2 (8) PH3 (4)	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USBOID	E12	PB0	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).

	Table 19-2.	USB	Signals	(108BGA)	(continued)
--	-------------	-----	---------	----------	-------------

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
USBOPFLT	L2 M2 M6 E11 B11 B10 B6	PC7 (6) PC6 (7) PA7 (8) PB3 (8) PE0 (9) PH4 (4) PJ1 (9)	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
USB0RBIAS	B12	fixed	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
USB0VBUS	D12	PB1	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 19.3 Functional Description

Note: A 9.1-k $\Omega$  resistor should be connected between the USBORBIAS and ground. The 9.1-k $\Omega$  resistor should have a 1% tolerance and should be located in close proximity to the USBORBIAS pin. Power dissipation in the resistor is low, so a chip resistor of any geometry may be used.

The Stellaris USB controller provides full OTG negotiation by supporting both the session request protocol (SRP) and the host negotiation protocol (HNP). The session request protocol allows devices on the B side of a cable to request the A side device turn on VBUS. The host negotiation protocol is used after the initial session request protocol has powered the bus and provides a method to determine which end of the cable will act as the Host controller. When the device is connected to non-OTG peripherals or devices, the controller can detect which cable end was used and provides a register to indicate if the controller should act as the Host or the Device controller. This indication and the mode of operation are handled automatically by the USB controller. This auto-detection allows the system to use a single A/B connector instead of having both A and B connectors in the system and supports full OTG negotiations with other OTG devices.

In addition, the USB controller provides support for connecting to non-OTG peripherals or Host controllers. The USB controller can be configured to act as either a dedicated Host or Device, in which case, the USB0VBUS and USB0ID signals can be used as GPIOs. However, when the USB controller is acting as a self-powered Device, a GPIO input or analog comparator input must be connected to VBUS and configured to generate an interrupt when the VBUS level drops. This interrupt is used to disable the pullup resistor on the USB0DP signal.

**Note:** When the USB module is in operation, MOSC must be the clock source, either with or without using the PLL, and the system clock must be at least 30 MHz.

## 19.3.1 Operation as a Device

This section describes the Stellaris USB controller's actions when it is being used as a USB Device. Before the USB controller's operating mode is changed from Device to Host or Host to Device, software must reset the USB controller by setting the USB0 bit in the **Software Reset Control 2** (SRCR2) register (see page 298). IN endpoints, OUT endpoints, entry into and exit from SUSPEND mode, and recognition of Start of Frame (SOF) are all described.

When in Device mode, IN transactions are controlled by an endpoint's transmit interface and use the transmit endpoint registers for the given endpoint. OUT transactions are handled with an endpoint's receive interface and use the receive endpoint registers for the given endpoint.

When configuring the size of the FIFOs for endpoints, take into account the maximum packet size for an endpoint.

- **Bulk.** Bulk endpoints should be the size of the maximum packet (up to 64 bytes) or twice the maximum packet size if double buffering is used (described further in the following section).
- Interrupt. Interrupt endpoints should be the size of the maximum packet (up to 64 bytes) or twice the maximum packet size if double buffering is used.
- Isochronous. Isochronous endpoints are more flexible and can be up to 1023 bytes.
- **Control.** It is also possible to specify a separate control endpoint for a USB Device. However, in most cases the USB Device should use the dedicated control endpoint on the USB controller's endpoint 0.

## **19.3.1.1** Endpoints

When operating as a Device, the USB controller provides two dedicated control endpoints (IN and OUT) and 30 configurable endpoints (15 IN and 15 OUT) that can be used for communications with a Host controller. The endpoint number and direction associated with an endpoint is directly related to its register designation. For example, when the Host is transmitting to endpoint 1, all configuration and data is in the endpoint 1 transmit register interface.

Endpoint 0 is a dedicated control endpoint used for all control transactions to endpoint 0 during enumeration or when any other control requests are made to endpoint 0. Endpoint 0 uses the first 64 bytes of the USB controller's FIFO RAM as a shared memory for both IN and OUT transactions.

The remaining 30 endpoints can be configured as control, bulk, interrupt, or isochronous endpoints. They should be treated as 15 configurable IN and 15 configurable OUT endpoints. The endpoint pairs are not required to have the same type for their IN and OUT endpoint configuration. For example, the OUT portion of an endpoint pair could be a bulk endpoint, while the IN portion of that endpoint pair could be an interrupt endpoint. The address and size of the FIFOs attached to each endpoint can be modified to fit the application's needs.

#### 19.3.1.2 IN Transactions as a Device

When operating as a USB Device, data for IN transactions is handled through the FIFOs attached to the transmit endpoints. The sizes of the FIFOs for the 15 configurable IN endpoints are determined by the **USB Transmit FIFO Start Address (USBTXFIFOADD)** register. The maximum size of a data packet that may be placed in a transmit endpoint's FIFO for transmission is programmable and is determined by the value written to the **USB Maximum Transmit Data Endpoint n (USBTXMAXPn)** register for that endpoint. The endpoint's FIFO can also be configured to use double-packet or single-packet buffering. When double-packet buffering is enabled, two data packets can be buffered in the FIFO, which also requires that the FIFO is at least two packets in size. When double-packet buffering is disabled, only one packet can be buffered, even if the packet size is less than half the FIFO size.

**Note:** The maximum packet size set for any endpoint must not exceed the FIFO size. The **USBTXMAXPn** register should not be written to while data is in the FIFO as unexpected results may occur.

#### Single-Packet Buffering

If the size of the transmit endpoint's FIFO is less than twice the maximum packet size for this endpoint (as set in the USB Transmit Dynamic FIFO Sizing (USBTXFIFOSZ) register), only one packet can be buffered in the FIFO and single-packet buffering is required. When each packet is completely loaded into the transmit FIFO, the TXRDY bit in the USB Transmit Control and Status Endpoint n Low (USBTXCSRLn) register must be set. If the AUTOSET bit in the USB Transmit Control and Status Endpoint n High (USBTXCSRHn) register is set, the TXRDY bit is automatically set when a maximum-sized packet is loaded into the FIFO. For packet sizes less than the maximum, the TXRDY bit must be set manually. When the TXRDY bit is set, either manually or automatically, the packet is ready to be sent. When the packet has been successfully sent, both TXRDY and FIFONE are cleared, and the appropriate transmit endpoint interrupt signaled. At this point, the next packet can be loaded into the FIFO.

#### **Double-Packet Buffering**

If the size of the transmit endpoint's FIFO is at least twice the maximum packet size for this endpoint, two packets can be buffered in the FIFO and double-packet buffering is allowed. As each packet is loaded into the transmit FIFO, the TXRDY bit in the USBTXCSRLn register must be set. If the AUTOSET bit in the USBTXCSRHn register is set, the TXRDY bit is automatically set when a maximum-sized packet is loaded into the FIFO. For packet sizes less than the maximum, TXRDY must be set manually. When the TXRDY bit is set, either manually or automatically, the packet is ready to be sent. After the first packet is loaded, TXRDY is immediately cleared and an interrupt is generated. A second packet can now be loaded into the transmit FIFO and TXRDY set again (either manually or automatically if the packet is the maximum size). At this point, both packets are ready to be sent. After each packet has been successfully sent, TXRDY is automatically cleared and the appropriate transmit endpoint interrupt signaled to indicate that another packet can now be loaded into the transmit FIFO. The state of the FIFONE bit in the USBTXCSRLn register at this point indicates how many packets may be loaded. If the FIFONE bit is set, then another packet is in the FIFO and only one more packet can be loaded. If the FIFONE bit is clear, then no packets are in the FIFO and two more packets can be loaded.

Note: Double-packet buffering is disabled if an endpoint's corresponding EPn bit is set in the USB Transmit Double Packet Buffer Disable (USBTXDPKTBUFDIS) register. This bit is set by default, so it must be cleared to enable double-packet buffering.

## 19.3.1.3 OUT Transactions as a Device

When in Device mode, OUT transactions are handled through the USB controller receive FIFOs. The sizes of the receive FIFOs for the 15 configurable OUT endpoints are determined by the USB Receive FIFO Start Address (USBRXFIFOADD) register. The maximum amount of data received by an endpoint in any packet is determined by the value written to the USB Maximum Receive Data Endpoint n (USBRXMAXPn) register for that endpoint. When double-packet buffering is enabled, two data packets can be buffered in the FIFO. When double-packet buffering is disabled, only one packet can be buffered even if the packet is less than half the FIFO size.

**Note:** In all cases, the maximum packet size must not exceed the FIFO size.

#### Single-Packet Buffering

If the size of the receive endpoint FIFO is less than twice the maximum packet size for an endpoint, only one data packet can be buffered in the FIFO and single-packet buffering is required. When a packet is received and placed in the receive FIFO, the RXRDY and FULL bits in the **USB Receive Control and Status Endpoint n Low (USBRXCSRLn)** register are set and the appropriate receive endpoint is signaled, indicating that a packet can now be unloaded from the FIFO. After the packet

has been unloaded, the RXRDY bit must be cleared in order to allow further packets to be received. This action also generates the acknowledge signaling to the Host controller. If the AUTOCL bit in the USB Receive Control and Status Endpoint n High (USBRXCSRHn) register is set and a maximum-sized packet is unloaded from the FIFO, the RXRDY and FULL bits are cleared automatically. For packet sizes less than the maximum, RXRDY must be cleared manually.

## **Double-Packet Buffering**

If the size of the receive endpoint FIFO is at least twice the maximum packet size for the endpoint, two data packets can be buffered and double-packet buffering can be used. When the first packet is received and loaded into the receive FIFO, the RXRDY bit in the **USBRXCSRLn** register is set and the appropriate receive endpoint interrupt is signaled to indicate that a packet can now be unloaded from the FIFO.

**Note:** The FULL bit in **USBRXCSRLn** is not set when the first packet is received. It is only set if a second packet is received and loaded into the receive FIFO.

After each packet has been unloaded, the RXRDY bit must be cleared to allow further packets to be received. If the AUTOCL bit in the **USBRXCSRHn** register is set and a maximum-sized packet is unloaded from the FIFO, the RXRDY bit is cleared automatically. For packet sizes less than the maximum, RXRDY must be cleared manually. If the FULL bit is set when RXRDY is cleared, the USB controller first clears the FULL bit, then sets RXRDY again to indicate that there is another packet waiting in the FIFO to be unloaded.

Note: Double-packet buffering is disabled if an endpoint's corresponding EPn bit is set in the USB Receive Double Packet Buffer Disable (USBRXDPKTBUFDIS) register. This bit is set by default, so it must be cleared to enable double-packet buffering.

#### 19.3.1.4 Scheduling

The Device has no control over the scheduling of transactions as scheduling is determined by the Host controller. The Stellaris USB controller can set up a transaction at any time. The USB controller waits for the request from the Host controller and generates an interrupt when the transaction is complete or if it was terminated due to some error. If the Host controller makes a request and the Device controller is not ready, the USB controller sends a busy response (NAK) to all requests until it is ready.

#### 19.3.1.5 Additional Actions

The USB controller responds automatically to certain conditions on the USB bus or actions by the Host controller such as when the USB controller automatically stalls a control transfer or unexpected zero length OUT data packets.

#### Stalled Control Transfer

The USB controller automatically issues a STALL handshake to a control transfer under the following conditions:

- 1. The Host sends more data during an OUT data phase of a control transfer than was specified in the Device request during the SETUP phase. This condition is detected by the USB controller when the Host sends an OUT token (instead of an IN token) after the last OUT packet has been unloaded and the DATAEND bit in the USB Control and Status Endpoint 0 Low (USBCSRL0) register has been set.
- 2. The Host requests more data during an IN data phase of a control transfer than was specified in the Device request during the SETUP phase. This condition is detected by the USB controller

when the Host sends an IN token (instead of an OUT token) after the CPU has cleared TXRDY and set DATAEND in response to the ACK issued by the Host to what should have been the last packet.

- 3. The Host sends more than **USBRXMAXPn** bytes of data with an OUT data token.
- 4. The Host sends more than a zero length data packet for the OUT STATUS phase.

## Zero Length OUT Data Packets

A zero-length OUT data packet is used to indicate the end of a control transfer. In normal operation, such packets should only be received after the entire length of the Device request has been transferred.

However, if the Host sends a zero-length OUT data packet before the entire length of Device request has been transferred, it is signaling the premature end of the transfer. In this case, the USB controller automatically flushes any IN token ready for the data phase from the FIFO and sets the DATAEND bit in the **USBCSRL0** register.

# Setting the Device Address

When a Host is attempting to enumerate the USB Device, it requests that the Device change its address from zero to some other value. The address is changed by writing the value that the Host requested to the **USB Device Functional Address (USBFADDR)** register. However, care should be taken when writing to **USBFADDR** to avoid changing the address before the transaction is complete. This register should only be set after the SET\_ADDRESS command is complete. Like all control transactions, the transaction is only complete after the Device has left the STATUS phase. In the case of a SET\_ADDRESS command, the transaction is completed by responding to the IN request from the Host with a zero-byte packet. Once the Device has responded to the IN request, the **USBFADDR** register should be programmed to the new value as soon as possible to avoid missing any new commands sent to the new address.

**Note:** If the **USBFADDR** register is set to the new value as soon as the Device receives the OUT transaction with the SET\_ADDRESS command in the packet, it changes the address during the control transfer. In this case, the Device does not receive the IN request that allows the USB transaction to exit the STATUS phase of the control transfer because it is sent to the old address. As a result, the Host does not get a response to the IN request, and the Host fails to enumerate the Device.

## 19.3.1.6 Device Mode SUSPEND

When no activity has occurred on the USB bus for 3 ms, the USB controller automatically enters SUSPEND mode. If the SUSPEND interrupt has been enabled in the **USB Interrupt Enable (USBIE)** register, an interrupt is generated at this time. When in SUSPEND mode, the PHY also goes into SUSPEND mode. When RESUME signaling is detected, the USB controller exits SUSPEND mode and takes the PHY out of SUSPEND. If the RESUME interrupt is enabled, an interrupt is generated. The USB controller can also be forced to exit SUSPEND mode by setting the RESUME bit in the **USB Power (USBPOWER)** register. When this bit is set, the USB controller exits SUSPEND mode and drives RESUME signaling onto the bus. The RESUME bit must be cleared after 10 ms (a maximum of 15 ms) to end RESUME signaling.

To meet USB power requirements, the controller can be put into Deep Sleep mode which keeps the controller in a static state.

#### 19.3.1.7 Start-of-Frame

When the USB controller is operating in Device mode, it receives a Start-Of-Frame (SOF) packet from the Host once every millisecond. When the SOF packet is received, the 11-bit frame number contained in the packet is written into the **USB Frame Value (USBFRAME)** register, and an SOF interrupt is also signaled and can be handled by the application. Once the USB controller has started to receive SOF packets, it expects one every millisecond. If no SOF packet is received after 1.00358 ms, the packet is assumed to have been lost, and the **USBFRAME** register is not updated. The USB controller continues and resynchronizes these pulses to the received SOF packets when these packets are successfully received again.

#### 19.3.1.8 USB RESET

When the USB controller is in Device mode and a RESET condition is detected on the USB bus, the USB controller automatically performs the following actions:

- Clears the **USBFADDR** register.
- Clears the USB Endpoint Index (USBEPIDX) register.
- Flushes all endpoint FIFOs.
- Clears all control/status registers.
- Enables all endpoint interrupts.
- Generates a RESET interrupt.

When the application software driving the USB controller receives a RESET interrupt, any open pipes are closed and the USB controller waits for bus enumeration to begin.

#### 19.3.1.9 Connect/Disconnect

The USB controller connection to the USB bus is handled by software. The USB PHY can be switched between normal mode and non-driving mode by setting or clearing the SOFTCONN bit of the USBPOWER register. When the SOFTCONN bit is set, the PHY is placed in its normal mode, and the USBODP/USBODM lines of the USB bus are enabled. At the same time, the USB controller is placed into a state, in which it does not respond to any USB signaling except a USB RESET.

When the SOFTCONN bit is cleared, the PHY is put into non-driving mode, USBODP and USBODM are tristated, and the USB controller appears to other devices on the USB bus as if it has been disconnected. The non-driving mode is the default so the USB controller appears disconnected until the SOFTCONN bit has been set. The application software can then choose when to set the PHY into its normal mode. Systems with a lengthy initialization procedure may use this to ensure that initialization is complete, and the system is ready to perform enumeration before connecting to the USB bus. Once the SOFTCONN bit has been set, the USB controller can be disconnected by clearing this bit.

**Note:** The USB controller does not generate an interrupt when the Device is connected to the Host. However, an interrupt is generated when the Host terminates a session.

## 19.3.2 Operation as a Host

When the Stellaris USB controller is operating in Host mode, it can either be used for point-to-point communications with another USB device or, when attached to a hub, for communication with multiple devices. Before the USB controller's operating mode is changed from Host to Device or

Device to Host, software must reset the USB controller by setting the USB0 bit in the **Software Reset Control 2 (SRCR2)** register (see page 298). Full-speed and low-speed USB devices are supported, both for point-to-point communication and for operation through a hub. The USB controller automatically carries out the necessary transaction translation needed to allow a low-speed or full-speed device to be used with a USB 2.0 hub. Control, bulk, isochronous, and interrupt transactions are supported. This section describes the USB controller's actions when it is being used as a USB Host. Configuration of IN endpoints, OUT endpoints, entry into and exit from SUSPEND mode, and RESET are all described.

When in Host mode, IN transactions are controlled by an endpoint's receive interface. All IN transactions use the receive endpoint registers and all OUT endpoints use the transmit endpoint registers for a given endpoint. As in Device mode, the FIFOs for endpoints should take into account the maximum packet size for an endpoint.

- **Bulk**. Bulk endpoints should be the size of the maximum packet (up to 64 bytes) or twice the maximum packet size if double buffering is used (described further in the following section).
- Interrupt. Interrupt endpoints should be the size of the maximum packet (up to 64 bytes) or twice the maximum packet size if double buffering is used.
- Isochronous. Isochronous endpoints are more flexible and can be up to 1023 bytes.
- **Control.** It is also possible to specify a separate control endpoint to communicate with a Device. However, in most cases the USB controller should use the dedicated control endpoint to communicate with a Device's endpoint 0.

# **19.3.2.1** Endpoints

The endpoint registers are used to control the USB endpoint interfaces which communicate with Device(s) that are connected. The endpoints consist of a dedicated control IN endpoint, a dedicated control OUT endpoint, 15 configurable OUT endpoints, and 15 configurable IN endpoints.

The dedicated control interface can only be used for control transactions to endpoint 0 of Devices. These control transactions are used during enumeration or other control functions that communicate using endpoint 0 of Devices. This control endpoint shares the first 64 bytes of the USB controller's FIFO RAM for IN and OUT transactions. The remaining IN and OUT interfaces can be configured to communicate with control, bulk, interrupt, or isochronous Device endpoints.

These USB interfaces can be used to simultaneously schedule as many as 15 independent OUT and 15 independent IN transactions to any endpoints on any Device. The IN and OUT controls are paired in three sets of registers. However, they can be configured to communicate with different types of endpoints and different endpoints on Devices. For example, the first pair of endpoint controls can be split so that the OUT portion is communicating with a Device's bulk OUT endpoint 1, while the IN portion is communicating with a Device's interrupt IN endpoint 2.

Before accessing any Device, whether for point-to-point communications or for communications via a hub, the relevant **USB Receive Functional Address Endpoint n (USBRXFUNCADDRn)** or **USB Transmit Functional Address Endpoint n (USBTXFUNCADDRn)** registers must be set for each receive or transmit endpoint to record the address of the Device being accessed.

The USB controller also supports connections to Devices through a USB hub by providing a register that specifies the hub address and port of each USB transfer. The FIFO address and size are customizable and can be specified for each USB IN and OUT transfer. Customization includes allowing one FIFO per transaction, sharing a FIFO across transactions, and allowing for double-buffered FIFOs.

#### 19.3.2.2 IN Transactions as a Host

IN transactions are handled in a similar manner to the way in which OUT transactions are handled when the USB controller is in Device mode except that the transaction first must be initiated by setting the REQPKT bit in the USBCSRL0 register, indicating to the transaction scheduler that there is an active transaction on this endpoint. The transaction scheduler then sends an IN token to the target Device. When the packet is received and placed in the receive FIFO, the RXRDY bit in the USBCSRL0 register is set, and the appropriate receive endpoint interrupt is signaled to indicate that a packet can now be unloaded from the FIFO.

When the packet has been unloaded, RXRDY must be cleared. The AUTOCL bit in the USBRXCSRHn register can be used to have RXRDY automatically cleared when a maximum-sized packet has been unloaded from the FIFO. The AUTORQ bit in USBRXCSRHn causes the REQPKT bit to be automatically set when the RXRDY bit is cleared. The AUTOCL and AUTORQ bits can be used with µDMA accesses to perform complete bulk transfers without main processor intervention. When the RXRDY bit is cleared, the controller sends an acknowledge to the Device. When there is a known number of packets to be transferred, the USB Request Packet Count in Block Transfer Endpoint n (USBRQPKTCOUNTn) register associated with the endpoint should be configured to the number of packets to be transferred. The USB controller decrements the value in the USBRQPKTCOUNTn register following each request. When the USBRQPKTCOUNTn value decrements to 0, the AUTORQ bit is cleared to prevent any further transactions being attempted. For cases where the size of the transfer is unknown, USBRQPKTCOUNTn should be cleared. AUTORQ then remains set until cleared by the reception of a short packet (that is, less than the MAXLOAD value in the USBRXMAXPn register) such as may occur at the end of a bulk transfer.

If the Device responds to a bulk or interrupt IN token with a NAK, the USB Host controller keeps retrying the transaction until any NAK Limit that has been set has been reached. If the target Device responds with a STALL, however, the USB Host controller does not retry the transaction but sets the STALLED bit in the **USBCSRL0** register. If the target Device does not respond to the IN token within the required time, or the packet contained a CRC or bit-stuff error, the USB Host controller retries the transaction. If after three attempts the target Device has still not responded, the USB Host controller clears the REQPKT bit and sets the ERROR bit in the **USBCSRL0** register.

## 19.3.2.3 OUT Transactions as a Host

OUT transactions are handled in a similar manner to the way in which IN transactions are handled when the USB controller is in Device mode. The TXRDY bit in the USBTXCSRLn register must be set as each packet is loaded into the transmit FIFO. Again, setting the AUTOSET bit in the USBTXCSRHn register automatically sets TXRDY when a maximum-sized packet has been loaded into the FIFO. Furthermore, AUTOSET can be used with the µDMA controller to perform complete bulk transfers without software intervention.

If the target Device responds to the OUT token with a NAK, the USB Host controller keeps retrying the transaction until the NAK Limit that has been set has been reached. However, if the target Device responds with a STALL, the USB controller does not retry the transaction but interrupts the main processor by setting the STALLED bit in the **USBTXCSRLn** register. If the target Device does not respond to the OUT token within the required time, or the packet contained a CRC or bit-stuff error, the USB Host controller retries the transaction. If after three attempts the target Device has still not responded, the USB controller flushes the FIFO and sets the ERROR bit in the **USBTXCSRLn** register.

## 19.3.2.4 Transaction Scheduling

Scheduling of transactions is handled automatically by the USB Host controller. The Host controller allows configuration of the endpoint communication scheduling based on the type of endpoint transaction. Interrupt transactions can be scheduled to occur in the range of every frame to every

255 frames in 1 frame increments. Bulk endpoints do not allow scheduling parameters, but do allow for a NAK timeout in the event an endpoint on a Device is not responding. Isochronous endpoints can be scheduled from every frame to every 2<sup>16</sup> frames, in powers of 2.

The USB controller maintains a frame counter. If the target Device is a full-speed device, the USB controller automatically sends an SOF packet at the start of each frame and increments the frame counter. If the target Device is a low-speed device, a *K* state is transmitted on the bus to act as a *keep-alive* to stop the low-speed device from going into SUSPEND mode.

After the SOF packet has been transmitted, the USB Host controller cycles through all the configured endpoints looking for active transactions. An active transaction is defined as a receive endpoint for which the REQPKT bit is set or a transmit endpoint for which the TXRDY bit and/or the FIFONE bit is set.

An isochronous or interrupt transaction is started if the transaction is found on the first scheduler cycle of a frame and if the interval counter for that endpoint has counted down to zero. As a result, only one interrupt or isochronous transaction occurs per endpoint every n frames, where n is the interval set via the USB Host Transmit Interval Endpoint n (USBTXINTERVALn) or USB Host Receive Interval Endpoint n (USBRXINTERVALn) register for that endpoint.

An active bulk transaction starts immediately, provided sufficient time is left in the frame to complete the transaction before the next SOF packet is due. If the transaction must be retried (for example, because a NAK was received or the target Device did not respond), then the transaction is not retried until the transaction scheduler has first checked all the other endpoints for active transactions. This process ensures that an endpoint that is sending a lot of NAKs does not block other transactions on the bus. The controller also allows the user to specify a limit to the length of time for NAKs to be received from a target Device before the endpoint times out.

#### 19.3.2.5 USB Hubs

The following setup requirements apply to the USB Host controller only if it is used with a USB hub. When a full- or low-speed Device is connected to the USB controller via a USB 2.0 hub, details of the hub address and the hub port also must be recorded in the corresponding USB Receive Hub Address Endpoint n (USBRXHUBADDRn) and USB Receive Hub Port Endpoint n (USBRXHUBPORTn) or the USB Transmit Hub Address Endpoint n (USBTXHUBADDRn) and USB Transmit Hub Port Endpoint n (USBTXHUBPORTn) registers. In addition, the speed at which the Device operates (full or low) must be recorded in the USB Type Endpoint 0 (USBTYPE0) (endpoint 0), USB Host Configure Transmit Type Endpoint n (USBTXTYPEn), or USB Host Configure Receive Type Endpoint n (USBRXTYPEn) registers for each endpoint that is accessed by the Device.

For hub communications, the settings in these registers record the current allocation of the endpoints to the attached USB Devices. To maximize the number of Devices supported, the USB Host controller allows this allocation to be changed dynamically by simply updating the address and speed information recorded in these registers. Any changes in the allocation of endpoints to Device functions must be made following the completion of any on-going transactions on the endpoints affected.

#### 19.3.2.6 Babble

The USB Host controller does not start a transaction until the bus has been inactive for at least the minimum inter-packet delay. The controller also does not start a transaction unless it can be finished before the end of the frame. If the bus is still active at the end of a frame, then the USB Host controller assumes that the target Device to which it is connected has malfunctioned, and the USB controller suspends all transactions and generates a babble interrupt.

# 19.3.2.7 Host SUSPEND

If the SUSPEND bit in the **USBPOWER** register is set, the USB Host controller completes the current transaction then stops the transaction scheduler and frame counter. No further transactions are started and no SOF packets are generated.

To exit SUSPEND mode, set the RESUME bit and clear the SUSPEND bit. While the RESUME bit is set, the USB Host controller generates RESUME signaling on the bus. After 20 ms, the RESUME bit must be cleared, at which point the frame counter and transaction scheduler start. The Host supports the detection of a remote wake-up.

### 19.3.2.8 USB RESET

If the RESET bit in the **USBPOWER** register is set, the USB Host controller generates USB RESET signaling on the bus. The RESET bit must be set for at least 20 ms to ensure correct resetting of the target Device. After the CPU has cleared the bit, the USB Host controller starts its frame counter and transaction scheduler.

#### 19.3.2.9 Connect/Disconnect

A session is started by setting the SESSION bit in the **USB Device Control (USBDEVCTL)** register, enabling the USB controller to wait for a Device to be connected. When a Device is detected, a connect interrupt is generated. The speed of the Device that has been connected can be determined by reading the **USBDEVCTL** register where the FSDEV bit is set for a full-speed Device, and the LSDEV bit is set for a low-speed Device. The USB controller must generate a RESET to the Device, and then the USB Host controller can begin Device enumeration. If the Device is disconnected while a session is in progress, a disconnect interrupt is generated.

#### 19.3.3 OTG Mode

To conserve power, the USB On-The-Go (OTG) supplement allows VBUS to only be powered up when required and to be turned off when the bus is not in use. VBUS is always supplied by the A device on the bus. The USB OTG controller determines whether it is the A device or the B device by sampling the ID input from the PHY. This signal is pulled Low when an A-type plug is sensed (signifying that the USB OTG controller should act as the A device) but taken High when a B-type plug is sensed (signifying that the USB controller is a B device). Note that when switching between OTG A and OTG B, the USB controller retains all register contents.

## 19.3.3.1 Starting a Session

When the USB OTG controller is ready to start a session, the SESSION bit must be set in the USBDEVCTL register. The USB OTG controller then enables ID pin sensing. The ID input is either taken Low if an A-type connection is detected or High if a B-type connection is detected. The DEV bit in the USBDEVCTL register is also set to indicate whether the USB OTG controller has adopted the role of the A device or the B device. The USB OTG controller also provides an interrupt to indicate that ID pin sensing has completed and the mode value in the USBDEVCTL register is valid. This interrupt is enabled in the USBIDVIM register, and the status is checked in the USBIDVISC register. As soon as the USB controller has detected that it is on the A side of the cable, it must enable VBUS power within 100ms or the USB controller reverts to Device mode.

If the USB OTG controller is the A device, then the USB OTG controller enters Host mode (the A device is always the default Host), turns on VBUS, and waits for VBUS to go above the VBUS Valid threshold, as indicated by the VBUS bit in the **USBDEVCTL** register going to 0x3. The USB OTG controller then waits for a peripheral to be connected. When a peripheral is detected, a Connect interrupt is signaled and either the FSDEV or LSDEV bit in the **USBDEVCTL** register is set, depending whether a full-speed or a low-speed peripheral is detected. The USB controller then issues a RESET

to the connected Device. The SESSION bit in the **USBDEVCTL** register can be cleared to end a session. The USB OTG controller also automatically ends the session if babble is detected or if VBUS drops below session valid.

Note: The USB OTG controller may not remain in Host mode when connected to high-current devices. Some devices draw enough current to momentarily drop VBUS below the VBUS-valid level causing the controller to drop out of Host mode. The only way to get back into Host mode is to allow VBUS to go below the Session End level. In this situation, the device is causing VBUS to drop repeatedly and pull VBUS back low the next time VBUS is enabled.

In addition, the USB OTG controller may not remain in Host mode when a device is told that it can start using it's active configuration. At this point the device starts drawing more current and can also drop VBUS below VBUS valid.

If the USB OTG controller is the B device, then the USB OTG controller requests a session using the session request protocol defined in the USB On-The-Go supplement, that is, it first discharges VBUS. Then when VBUS has gone below the Session End threshold (VBUS bit in the **USBDEVCTL** register goes to 0x0) and the line state has been a single-ended zero for > 2 ms, the USB OTG controller pulses the data line, then pulses VBUS. At the end of the session, the SESSION bit is cleared either by the USB OTG controller or by the application software. The USB OTG controller then causes the PHY to switch out the pull-up resistor on D+, signaling the A device to end the session.

# 19.3.3.2 Detecting Activity

When the other device of the OTG setup wishes to start a session, it either raises VBUS above the Session Valid threshold if it is the A device, or if it is the B device, it pulses the data line then pulses VBUS. Depending on which of these actions happens, the USB controller can determine whether it is the A device or the B device in the current setup and act accordingly. If VBUS is raised above the Session Valid threshold, then the USB controller is the B device. The USB controller sets the SESSION bit in the **USBDEVCTL** register. When RESET signaling is detected on the bus, a RESET interrupt is signaled, which is interpreted as the start of a session.

The USB controller is in Device mode as the B device is the default mode. At the end of the session, the A device turns off the power to VBUS. When VBUS drops below the Session Valid threshold, the USB controller detects this drop and clears the SESSION bit to indicate that the session has ended, causing a disconnect interrupt to be signaled. If data line and VBUS pulsing is detected, then the USB controller is the A device. The controller generates a SESSION REQUEST interrupt to indicate that the B device is requesting a session. The SESSION bit in the USBDEVCTL register must be set to start a session.

## 19.3.3.3 Host Negotiation

When the USB controller is the A device, ID is Low, and the controller automatically enters Host mode when a session starts. When the USB controller is the B device, ID is High, and the controller automatically enters Device mode when a session starts. However, software can request that the USB controller become the Host by setting the Hostreq bit in the USBDEVCTL register. This bit can be set either at the same time as requesting a Session Start by setting the SESSION bit in the USBDEVCTL register or at any time after a session has started. When the USB controller next enters SUSPEND mode and if the Hostreq bit remains set, the controller enters Host mode and begins host negotiation (as specified in the USB On-The-Go supplement) by causing the PHY to disconnect the pull-up resistor on the D+ line, causing the A device to switch to Device mode and connect its own pull-up resistor. When the USB controller detects this, a Connect interrupt is generated and the RESET bit in the USBPOWER register is set to begin resetting the A device. The

USB controller begins this reset sequence automatically to ensure that RESET is started as required within 1 ms of the A device connecting its pull-up resistor. The main processor should wait at least 20 ms, then clear the RESET bit and enumerate the A device.

When the USB OTG controller B device has finished using the bus, the USB controller goes into SUSPEND mode by setting the SUSPEND bit in the **USBPOWER** register. The A device detects this and either terminates the session or reverts to Host mode. If the A device is USB OTG controller, it generates a Disconnect interrupt.

# 19.3.4 DMA Operation

The USB peripheral provides an interface connected to the  $\mu$ DMA controller with separate channels for 3 transmit endpoints and 3 receive endpoints. Software selects which endpoints to service with the  $\mu$ DMA channels using the **USB DMA Select (USBDMASEL)** register. The  $\mu$ DMA operation of the USB is enabled through the **USBTXCSRHn** and **USBRXCSRHn** registers, for the TX and RX channels respectively. When  $\mu$ DMA operation is enabled, the USB asserts a  $\mu$ DMA request on the enabled receive or transmit channel when the associated FIFO can transfer data. When either FIFO can transfer data, the burst request for that channel is asserted. The  $\mu$ DMA channel must be configured to operate in Basic mode, and the size of the  $\mu$ DMA transfer must be restricted to whole multiples of the size of the USB FIFO. Both read and write transfers of the USB FIFOs using  $\mu$ DMA must be configured in this manner. For example, if the USB endpoint is configured with a FIFO size of 64 bytes, the  $\mu$ DMA channel can be used to transfer 64 bytes to or from the endpoint FIFO. If the number of bytes to transfer is less than 64, then a programmed I/O method must be used to copy the data to or from the FIFO.

If the DMAMOD bit in the **USBTXCSRHn/USBRXCSRHn** register is clear, an interrupt is generated after every packet is transferred, but the  $\mu$ DMA continues transferring data. If the DMAMOD bit is set, an interrupt is generated only when the entire  $\mu$ DMA transfer is complete. The interrupt occurs on the USB interrupt vector. Therefore, if interrupts are used for USB operation and the  $\mu$ DMA is enabled, the USB interrupt handler must be designed to handle the  $\mu$ DMA completion interrupt.

Care must be taken when using the  $\mu DMA$  to unload the receive FIFO as data is read from the receive FIFO in 4 byte chunks regardless of value of the MAXLOAD field in the **USBRXCSRHn** register. The RXRDY bit is cleared as follows.

Table 19-3. Remainder (MAXLOAD/4)

Value	Description
0	MAXLOAD = 64 bytes
1	MAXLOAD = 61 bytes
2	MAXLOAD = 62 bytes
3	MAXLOAD = 63 bytes

Table 19-4. Actual Bytes Read

Value	Description
0	MAXLOAD
1	MAXLOAD+3
2	MAXLOAD+2
3	MAXLOAD+1

Table 19-5. Packet Sizes That Clear RXRDY

Value	Description				
0	MAXLOAD, MAXLOAD-1, MAXLOAD-2, MAXLOAD-3				
1	AXLOAD				
2	MAXLOAD, MAXLOAD-1				
3	MAXLOAD, MAXLOAD-1, MAXLOAD-2				

To enable DMA operation for the endpoint receive channel, the DMAEN bit of the **USBRXCSRHn** register should be set. To enable DMA operation for the endpoint transmit channel, the DMAEN bit of the **USBTXCSRHn** register must be set.

See "Micro Direct Memory Access ( $\mu$ DMA)" on page 346 for more details about programming the  $\mu$ DMA controller.

# 19.4 Initialization and Configuration

To use the USB Controller, the peripheral clock must be enabled via the **RCGC2** register (see page 284). In addition, the clock to the appropriate GPIO module must be enabled via the **RCGC2** register in the System Control module (see page 284). To find out which GPIO port to enable, refer to Table 24-4 on page 1261. Configure the PMCn fields in the **GPIOPCTL** register to assign the USB signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).

The initial configuration in all cases requires that the processor enable the USB controller and USB controller's physical layer interface (PHY) before setting any registers. The next step is to enable the USB PLL so that the correct clocking is provided to the PHY. To ensure that voltage is not supplied to the bus incorrectly, the external power control signal, USB0EPEN, should be negated on start up by configuring the USB0EPEN and USB0PFLT pins to be controlled by the USB controller and not exhibit their default GPIO behavior.

When used in OTG mode, USB0VBUS and USB0ID do not require any configuration as they are dedicated pins for the USB controller and directly connect to the USB connector's VBUS and ID signals. If the USB controller is used as either a dedicated Host or Device, the DEVMODOTG and DEVMOD bits in the USB General-Purpose Control and Status (USBGPCS) register can be used to connect the USB0VBUS and USB0ID inputs to fixed levels internally, freeing the PB0 and PB1 pins for GPIO use. For proper self-powered Device operation, the VBUS value must still be monitored to assure that if the Host removes VBUS, the self-powered Device disables the D+/D- pull-up resistors. This function can be accomplished by connecting a standard GPIO to VBUS.

The termination resistors for the USB PHY have been added internally, and thus there is no need for external resistors. For a device, there is a 1.5 KOhm pull-up on the D+ and for a host there are 15 KOhm pull-downs on both D+ and D-.

## 19.4.1 Pin Configuration

When using the Device controller portion of the USB controller in a system that also provides Host functionality, the power to VBUS must be disabled to allow the external Host controller to supply power. Usually, the USB0EPEN signal is used to control the external regulator and should be negated to avoid having two devices driving the USB0VBUS power pin on the USB connector.

When the USB controller is acting as a Host, it is in control of two signals that are attached to an external voltage supply that provides power to VBUS. The Host controller uses the USB0EPEN signal to enable or disable power to the USB0VBUS pin on the USB connector. An input pin, USB0PFLT, provides feedback when there has been a power fault on VBUS. The USB0PFLT signal can be

configured to either automatically negate the USB0EPEN signal to disable power, and/or it can generate an interrupt to the interrupt controller to allow software to handle the power fault condition. The polarity and actions related to both USB0EPEN and USB0PFLT are fully configurable in the USB controller. The controller also provides interrupts on Device insertion and removal to allow the Host controller code to respond to these external events.

# 19.4.2 Endpoint Configuration

To start communication in Host or Device mode, the endpoint registers must first be configured. In Host mode, this configuration establishes a connection between an endpoint register and an endpoint on a Device. In Device mode, an endpoint must be configured before enumerating to the Host controller.

In both cases, the endpoint 0 configuration is limited because it is a fixed-function, fixed-FIFO-size endpoint. In Device and Host modes, the endpoint requires little setup but does require a software-based state machine to progress through the setup, data, and status phases of a standard control transaction. In Device mode, the configuration of the remaining endpoints is done once before enumerating and then only changed if an alternate configuration is selected by the Host controller. In Host mode, the endpoints must be configured to operate as control, bulk, interrupt or isochronous mode. Once the type of endpoint is configured, a FIFO area must be assigned to each endpoint. In the case of bulk, control and interrupt endpoints, each has a maximum of 64 bytes per transaction. Isochronous endpoints can have packets with up to 1023 bytes per packet. In either mode, the maximum packet size for the given endpoint must be set prior to sending or receiving data.

Configuring each endpoint's FIFO involves reserving a portion of the overall USB FIFO RAM to each endpoint. The total FIFO RAM available is 4 Kbytes with the first 64 bytes reserved for endpoint 0. The endpoint's FIFO must be at least as large as the maximum packet size. The FIFO can also be configured as a double-buffered FIFO so that interrupts occur at the end of each packet and allow filling the other half of the FIFO.

If operating as a Device, the USB Device controller's soft connect must be enabled when the Device is ready to start communications, indicating to the Host controller that the Device is ready to start the enumeration process. If operating as a Host controller, the Device soft connect must be disabled and power must be provided to VBUS via the USB0EPEN signal.

# 19.5 Register Map

Table 19-6 on page 999 lists the registers. All addresses given are relative to the USB base address of 0x4005.0000. Note that the USB controller clock must be enabled before the registers can be programmed (see page 284). There must be a delay of 3 system clocks after the USB module clock is enabled before any USB module registers are accessed.

Table 19-6. Universal Serial Bus (USB) Controller Register Map

Offset	Name	Type	Reset	Description	See page
0x000	USBFADDR	R/W	0x00	USB Device Functional Address	1011
0x001	USBPOWER	R/W	0x20	USB Power	1012
0x002	USBTXIS	RO	0x0000	USB Transmit Interrupt Status	1015
0x004	USBRXIS	RO	0x0000	USB Receive Interrupt Status	1017
0x006	USBTXIE	R/W	0xFFFF	USB Transmit Interrupt Enable	1019

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x008	USBRXIE	R/W	0xFFFE	USB Receive Interrupt Enable	1021
0x00A	USBIS	RO	0x00	USB General Interrupt Status	1023
0x00B	USBIE	R/W	0x06	USB Interrupt Enable	1026
0x00C	USBFRAME	RO	0x0000	USB Frame Value	1029
0x00E	USBEPIDX	R/W	0x00	USB Endpoint Index	1030
0x00F	USBTEST	R/W	0x00	USB Test Mode	1031
0x020	USBFIFO0	R/W	0x0000.0000	USB FIFO Endpoint 0	1033
0x024	USBFIFO1	R/W	0x0000.0000	USB FIFO Endpoint 1	1033
0x028	USBFIFO2	R/W	0x0000.0000	USB FIFO Endpoint 2	1033
0x02C	USBFIFO3	R/W	0x0000.0000	USB FIFO Endpoint 3	1033
0x030	USBFIFO4	R/W	0x0000.0000	USB FIFO Endpoint 4	1033
0x034	USBFIFO5	R/W	0x0000.0000	USB FIFO Endpoint 5	1033
0x038	USBFIFO6	R/W	0x0000.0000	USB FIFO Endpoint 6	1033
0x03C	USBFIF07	R/W	0x0000.0000	USB FIFO Endpoint 7	1033
0x040	USBFIFO8	R/W	0x0000.0000	USB FIFO Endpoint 8	1033
0x044	USBFIFO9	R/W	0x0000.0000	USB FIFO Endpoint 9	1033
0x048	USBFIFO10	R/W	0x0000.0000	USB FIFO Endpoint 10	1033
0x04C	USBFIFO11	R/W	0x0000.0000	USB FIFO Endpoint 11	1033
0x050	USBFIFO12	R/W	0x0000.0000	USB FIFO Endpoint 12	1033
0x054	USBFIFO13	R/W	0x0000.0000	USB FIFO Endpoint 13	1033
0x058	USBFIFO14	R/W	0x0000.0000	USB FIFO Endpoint 14	1033
0x05C	USBFIFO15	R/W	0x0000.0000	USB FIFO Endpoint 15	1033
0x060	USBDEVCTL	R/W	0x80	USB Device Control	1035
0x062	USBTXFIFOSZ	R/W	0x00	USB Transmit Dynamic FIFO Sizing	1037
0x063	USBRXFIFOSZ	R/W	0x00	USB Receive Dynamic FIFO Sizing	1037
0x064	USBTXFIFOADD	R/W	0x0000	USB Transmit FIFO Start Address	1038
0x066	USBRXFIFOADD	R/W	0x0000	USB Receive FIFO Start Address	1038
0x07A	USBCONTIM	R/W	0x5C	USB Connect Timing	1039
0x07B	USBVPLEN	R/W	0x3C	USB OTG VBUS Pulse Timing	1040
0x07D	USBFSEOF	R/W	0x77	USB Full-Speed Last Transaction to End of Frame Timing	1041
0x07E	USBLSEOF	R/W	0x72	USB Low-Speed Last Transaction to End of Frame Timing	1042

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x080	USBTXFUNCADDR0	R/W	0x00	USB Transmit Functional Address Endpoint 0	1043
0x082	USBTXHUBADDR0	R/W	0x00	USB Transmit Hub Address Endpoint 0	1045
0x083	USBTXHUBPORT0	R/W	0x00	USB Transmit Hub Port Endpoint 0	1047
0x088	USBTXFUNCADDR1	R/W	0x00	USB Transmit Functional Address Endpoint 1	1043
0x08A	USBTXHUBADDR1	R/W	0x00	USB Transmit Hub Address Endpoint 1	1045
0x08B	USBTXHUBPORT1	R/W	0x00	USB Transmit Hub Port Endpoint 1	1047
0x08C	USBRXFUNCADDR1	R/W	0x00	USB Receive Functional Address Endpoint 1	1049
0x08E	USBRXHUBADDR1	R/W	0x00	USB Receive Hub Address Endpoint 1	1051
0x08F	USBRXHUBPORT1	R/W	0x00	USB Receive Hub Port Endpoint 1	1053
0x090	USBTXFUNCADDR2	R/W	0x00	USB Transmit Functional Address Endpoint 2	1043
0x092	USBTXHUBADDR2	R/W	0x00	USB Transmit Hub Address Endpoint 2	1045
0x093	USBTXHUBPORT2	R/W	0x00	USB Transmit Hub Port Endpoint 2	1047
0x094	USBRXFUNCADDR2	R/W	0x00	USB Receive Functional Address Endpoint 2	1049
0x096	USBRXHUBADDR2	R/W	0x00	USB Receive Hub Address Endpoint 2	1051
0x097	USBRXHUBPORT2	R/W	0x00	USB Receive Hub Port Endpoint 2	1053
0x098	USBTXFUNCADDR3	R/W	0x00	USB Transmit Functional Address Endpoint 3	1043
0x09A	USBTXHUBADDR3	R/W	0x00	USB Transmit Hub Address Endpoint 3	1045
0x09B	USBTXHUBPORT3	R/W	0x00	USB Transmit Hub Port Endpoint 3	1047
0x09C	USBRXFUNCADDR3	R/W	0x00	USB Receive Functional Address Endpoint 3	1049
0x09E	USBRXHUBADDR3	R/W	0x00	USB Receive Hub Address Endpoint 3	1051
0x09F	USBRXHUBPORT3	R/W	0x00	USB Receive Hub Port Endpoint 3	1053
0x0A0	USBTXFUNCADDR4	R/W	0x00	USB Transmit Functional Address Endpoint 4	1043
0x0A2	USBTXHUBADDR4	R/W	0x00	USB Transmit Hub Address Endpoint 4	1045
0x0A3	USBTXHUBPORT4	R/W	0x00	USB Transmit Hub Port Endpoint 4	1047
0x0A4	USBRXFUNCADDR4	R/W	0x00	USB Receive Functional Address Endpoint 4	1049
0x0A6	USBRXHUBADDR4	R/W	0x00	USB Receive Hub Address Endpoint 4	1051
0x0A7	USBRXHUBPORT4	R/W	0x00	USB Receive Hub Port Endpoint 4	1053
0x0A8	USBTXFUNCADDR5	R/W	0x00	USB Transmit Functional Address Endpoint 5	1043
0x0AA	USBTXHUBADDR5	R/W	0x00	USB Transmit Hub Address Endpoint 5	1045
0x0AB	USBTXHUBPORT5	R/W	0x00	USB Transmit Hub Port Endpoint 5	1047
0x0AC	USBRXFUNCADDR5	R/W	0x00	USB Receive Functional Address Endpoint 5	1049
0x0AE	USBRXHUBADDR5	R/W	0x00	USB Receive Hub Address Endpoint 5	1051

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x0AF	USBRXHUBPORT5	R/W	0x00	USB Receive Hub Port Endpoint 5	1053
0x0B0	USBTXFUNCADDR6	R/W	0x00	USB Transmit Functional Address Endpoint 6	1043
0x0B2	USBTXHUBADDR6	R/W	0x00	USB Transmit Hub Address Endpoint 6	1045
0x0B3	USBTXHUBPORT6	R/W	0x00	USB Transmit Hub Port Endpoint 6	1047
0x0B4	USBRXFUNCADDR6	R/W	0x00	USB Receive Functional Address Endpoint 6	1049
0x0B6	USBRXHUBADDR6	R/W	0x00	USB Receive Hub Address Endpoint 6	1051
0x0B7	USBRXHUBPORT6	R/W	0x00	USB Receive Hub Port Endpoint 6	1053
0x0B8	USBTXFUNCADDR7	R/W	0x00	USB Transmit Functional Address Endpoint 7	1043
0x0BA	USBTXHUBADDR7	R/W	0x00	USB Transmit Hub Address Endpoint 7	1045
0x0BB	USBTXHUBPORT7	R/W	0x00	USB Transmit Hub Port Endpoint 7	1047
0x0BC	USBRXFUNCADDR7	R/W	0x00	USB Receive Functional Address Endpoint 7	1049
0x0BE	USBRXHUBADDR7	R/W	0x00	USB Receive Hub Address Endpoint 7	1051
0x0BF	USBRXHUBPORT7	R/W	0x00	USB Receive Hub Port Endpoint 7	1053
0x0C0	USBTXFUNCADDR8	R/W	0x00	USB Transmit Functional Address Endpoint 8	1043
0x0C2	USBTXHUBADDR8	R/W	0x00	USB Transmit Hub Address Endpoint 8	1045
0x0C3	USBTXHUBPORT8	R/W	0x00	USB Transmit Hub Port Endpoint 8	1047
0x0C4	USBRXFUNCADDR8	R/W	0x00	USB Receive Functional Address Endpoint 8	1049
0x0C6	USBRXHUBADDR8	R/W	0x00	USB Receive Hub Address Endpoint 8	1051
0x0C7	USBRXHUBPORT8	R/W	0x00	USB Receive Hub Port Endpoint 8	1053
0x0C8	USBTXFUNCADDR9	R/W	0x00	USB Transmit Functional Address Endpoint 9	1043
0x0CA	USBTXHUBADDR9	R/W	0x00	USB Transmit Hub Address Endpoint 9	1045
0x0CB	USBTXHUBPORT9	R/W	0x00	USB Transmit Hub Port Endpoint 9	1047
0x0CC	USBRXFUNCADDR9	R/W	0x00	USB Receive Functional Address Endpoint 9	1049
0x0CE	USBRXHUBADDR9	R/W	0x00	USB Receive Hub Address Endpoint 9	1051
0x0CF	USBRXHUBPORT9	R/W	0x00	USB Receive Hub Port Endpoint 9	1053
0x0D0	USBTXFUNCADDR10	R/W	0x00	USB Transmit Functional Address Endpoint 10	1043
0x0D2	USBTXHUBADDR10	R/W	0x00	USB Transmit Hub Address Endpoint 10	1045
0x0D3	USBTXHUBPORT10	R/W	0x00	USB Transmit Hub Port Endpoint 10	1047
0x0D4	USBRXFUNCADDR10	R/W	0x00	USB Receive Functional Address Endpoint 10	1049
0x0D6	USBRXHUBADDR10	R/W	0x00	USB Receive Hub Address Endpoint 10	1051
0x0D7	USBRXHUBPORT10	R/W	0x00	USB Receive Hub Port Endpoint 10	1053
0x0D8	USBTXFUNCADDR11	R/W	0x00	USB Transmit Functional Address Endpoint 11	1043

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x0DA	USBTXHUBADDR11	R/W	0x00	USB Transmit Hub Address Endpoint 11	1045
0x0DB	USBTXHUBPORT11	R/W	0x00	USB Transmit Hub Port Endpoint 11	1047
0x0DC	USBRXFUNCADDR11	R/W	0x00	USB Receive Functional Address Endpoint 11	1049
0x0DE	USBRXHUBADDR11	R/W	0x00	USB Receive Hub Address Endpoint 11	1051
0x0DF	USBRXHUBPORT11	R/W	0x00	USB Receive Hub Port Endpoint 11	1053
0x0E0	USBTXFUNCADDR12	R/W	0x00	USB Transmit Functional Address Endpoint 12	1043
0x0E2	USBTXHUBADDR12	R/W	0x00	USB Transmit Hub Address Endpoint 12	1045
0x0E3	USBTXHUBPORT12	R/W	0x00	USB Transmit Hub Port Endpoint 12	1047
0x0E4	USBRXFUNCADDR12	R/W	0x00	USB Receive Functional Address Endpoint 12	1049
0x0E6	USBRXHUBADDR12	R/W	0x00	USB Receive Hub Address Endpoint 12	1051
0x0E7	USBRXHUBPORT12	R/W	0x00	USB Receive Hub Port Endpoint 12	1053
0x0E8	USBTXFUNCADDR13	R/W	0x00	USB Transmit Functional Address Endpoint 13	1043
0x0EA	USBTXHUBADDR13	R/W	0x00	USB Transmit Hub Address Endpoint 13	1045
0x0EB	USBTXHUBPORT13	R/W	0x00	USB Transmit Hub Port Endpoint 13	1047
0x0EC	USBRXFUNCADDR13	R/W	0x00	USB Receive Functional Address Endpoint 13	1049
0x0EE	USBRXHUBADDR13	R/W	0x00	USB Receive Hub Address Endpoint 13	1051
0x0EF	USBRXHUBPORT13	R/W	0x00	USB Receive Hub Port Endpoint 13	1053
0x0F0	USBTXFUNCADDR14	R/W	0x00	USB Transmit Functional Address Endpoint 14	1043
0x0F2	USBTXHUBADDR14	R/W	0x00	USB Transmit Hub Address Endpoint 14	1045
0x0F3	USBTXHUBPORT14	R/W	0x00	USB Transmit Hub Port Endpoint 14	1047
0x0F4	USBRXFUNCADDR14	R/W	0x00	USB Receive Functional Address Endpoint 14	1049
0x0F6	USBRXHUBADDR14	R/W	0x00	USB Receive Hub Address Endpoint 14	1051
0x0F7	USBRXHUBPORT14	R/W	0x00	USB Receive Hub Port Endpoint 14	1053
0x0F8	USBTXFUNCADDR15	R/W	0x00	USB Transmit Functional Address Endpoint 15	1043
0x0FA	USBTXHUBADDR15	R/W	0x00	USB Transmit Hub Address Endpoint 15	1045
0x0FB	USBTXHUBPORT15	R/W	0x00	USB Transmit Hub Port Endpoint 15	1047
0x0FC	USBRXFUNCADDR15	R/W	0x00	USB Receive Functional Address Endpoint 15	1049
0x0FE	USBRXHUBADDR15	R/W	0x00	USB Receive Hub Address Endpoint 15	1051
0x0FF	USBRXHUBPORT15	R/W	0x00	USB Receive Hub Port Endpoint 15	1053
0x102	USBCSRL0	W1C	0x00	USB Control and Status Endpoint 0 Low	1057
0x103	USBCSRH0	W1C	0x00	USB Control and Status Endpoint 0 High	1061
0x108	USBCOUNT0	RO	0x00	USB Receive Byte Count Endpoint 0	1063

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x10A	USBTYPE0	R/W	0x00	USB Type Endpoint 0	1064
0x10B	USBNAKLMT	R/W	0x00	USB NAK Limit	1065
0x110	USBTXMAXP1	R/W	0x0000	USB Maximum Transmit Data Endpoint 1	1055
0x112	USBTXCSRL1	R/W	0x00	USB Transmit Control and Status Endpoint 1 Low	1066
0x113	USBTXCSRH1	R/W	0x00	USB Transmit Control and Status Endpoint 1 High	1071
0x114	USBRXMAXP1	R/W	0x0000	USB Maximum Receive Data Endpoint 1	1075
0x116	USBRXCSRL1	R/W	0x00	USB Receive Control and Status Endpoint 1 Low	1077
0x117	USBRXCSRH1	R/W	0x00	USB Receive Control and Status Endpoint 1 High	1082
0x118	USBRXCOUNT1	RO	0x0000	USB Receive Byte Count Endpoint 1	1087
0x11A	USBTXTYPE1	R/W	0x00	USB Host Transmit Configure Type Endpoint 1	1089
0x11B	USBTXINTERVAL1	R/W	0x00	USB Host Transmit Interval Endpoint 1	1091
0x11C	USBRXTYPE1	R/W	0x00	USB Host Configure Receive Type Endpoint 1	1093
0x11D	USBRXINTERVAL1	R/W	0x00	USB Host Receive Polling Interval Endpoint 1	1095
0x120	USBTXMAXP2	R/W	0x0000	USB Maximum Transmit Data Endpoint 2	1055
0x122	USBTXCSRL2	R/W	0x00	USB Transmit Control and Status Endpoint 2 Low	1066
0x123	USBTXCSRH2	R/W	0x00	USB Transmit Control and Status Endpoint 2 High	1071
0x124	USBRXMAXP2	R/W	0x0000	USB Maximum Receive Data Endpoint 2	1075
0x126	USBRXCSRL2	R/W	0x00	USB Receive Control and Status Endpoint 2 Low	1077
0x127	USBRXCSRH2	R/W	0x00	USB Receive Control and Status Endpoint 2 High	1082
0x128	USBRXCOUNT2	RO	0x0000	USB Receive Byte Count Endpoint 2	1087
0x12A	USBTXTYPE2	R/W	0x00	USB Host Transmit Configure Type Endpoint 2	1089
0x12B	USBTXINTERVAL2	R/W	0x00	USB Host Transmit Interval Endpoint 2	1091
0x12C	USBRXTYPE2	R/W	0x00	USB Host Configure Receive Type Endpoint 2	1093
0x12D	USBRXINTERVAL2	R/W	0x00	USB Host Receive Polling Interval Endpoint 2	1095
0x130	USBTXMAXP3	R/W	0x0000	USB Maximum Transmit Data Endpoint 3	1055
0x132	USBTXCSRL3	R/W	0x00	USB Transmit Control and Status Endpoint 3 Low	1066
0x133	USBTXCSRH3	R/W	0x00	USB Transmit Control and Status Endpoint 3 High	1071
0x134	USBRXMAXP3	R/W	0x0000	USB Maximum Receive Data Endpoint 3	1075
0x136	USBRXCSRL3	R/W	0x00	USB Receive Control and Status Endpoint 3 Low	1077
0x137	USBRXCSRH3	R/W	0x00	USB Receive Control and Status Endpoint 3 High	1082
0x138	USBRXCOUNT3	RO	0x0000	USB Receive Byte Count Endpoint 3	1087
0x13A	USBTXTYPE3	R/W	0x00	USB Host Transmit Configure Type Endpoint 3	1089

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x13B	USBTXINTERVAL3	R/W	0x00	USB Host Transmit Interval Endpoint 3	1091
0x13C	USBRXTYPE3	R/W	0x00	USB Host Configure Receive Type Endpoint 3	1093
0x13D	USBRXINTERVAL3	R/W	0x00	USB Host Receive Polling Interval Endpoint 3	1095
0x140	USBTXMAXP4	R/W	0x0000	USB Maximum Transmit Data Endpoint 4	1055
0x142	USBTXCSRL4	R/W	0x00	USB Transmit Control and Status Endpoint 4 Low	1066
0x143	USBTXCSRH4	R/W	0x00	USB Transmit Control and Status Endpoint 4 High	1071
0x144	USBRXMAXP4	R/W	0x0000	USB Maximum Receive Data Endpoint 4	1075
0x146	USBRXCSRL4	R/W	0x00	USB Receive Control and Status Endpoint 4 Low	1077
0x147	USBRXCSRH4	R/W	0x00	USB Receive Control and Status Endpoint 4 High	1082
0x148	USBRXCOUNT4	RO	0x0000	USB Receive Byte Count Endpoint 4	1087
0x14A	USBTXTYPE4	R/W	0x00	USB Host Transmit Configure Type Endpoint 4	1089
0x14B	USBTXINTERVAL4	R/W	0x00	USB Host Transmit Interval Endpoint 4	1091
0x14C	USBRXTYPE4	R/W	0x00	USB Host Configure Receive Type Endpoint 4	1093
0x14D	USBRXINTERVAL4	R/W	0x00	USB Host Receive Polling Interval Endpoint 4	1095
0x150	USBTXMAXP5	R/W	0x0000	USB Maximum Transmit Data Endpoint 5	1055
0x152	USBTXCSRL5	R/W	0x00	USB Transmit Control and Status Endpoint 5 Low	1066
0x153	USBTXCSRH5	R/W	0x00	USB Transmit Control and Status Endpoint 5 High	1071
0x154	USBRXMAXP5	R/W	0x0000	USB Maximum Receive Data Endpoint 5	1075
0x156	USBRXCSRL5	R/W	0x00	USB Receive Control and Status Endpoint 5 Low	1077
0x157	USBRXCSRH5	R/W	0x00	USB Receive Control and Status Endpoint 5 High	1082
0x158	USBRXCOUNT5	RO	0x0000	USB Receive Byte Count Endpoint 5	1087
0x15A	USBTXTYPE5	R/W	0x00	USB Host Transmit Configure Type Endpoint 5	1089
0x15B	USBTXINTERVAL5	R/W	0x00	USB Host Transmit Interval Endpoint 5	1091
0x15C	USBRXTYPE5	R/W	0x00	USB Host Configure Receive Type Endpoint 5	1093
0x15D	USBRXINTERVAL5	R/W	0x00	USB Host Receive Polling Interval Endpoint 5	1095
0x160	USBTXMAXP6	R/W	0x0000	USB Maximum Transmit Data Endpoint 6	1055
0x162	USBTXCSRL6	R/W	0x00	USB Transmit Control and Status Endpoint 6 Low	1066
0x163	USBTXCSRH6	R/W	0x00	USB Transmit Control and Status Endpoint 6 High	1071
0x164	USBRXMAXP6	R/W	0x0000	USB Maximum Receive Data Endpoint 6	1075
0x166	USBRXCSRL6	R/W	0x00	USB Receive Control and Status Endpoint 6 Low	1077
0x167	USBRXCSRH6	R/W	0x00	USB Receive Control and Status Endpoint 6 High	1082
0x168	USBRXCOUNT6	RO	0x0000	USB Receive Byte Count Endpoint 6	1087

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x16A	USBTXTYPE6	R/W	0x00	USB Host Transmit Configure Type Endpoint 6	1089
0x16B	USBTXINTERVAL6	R/W	0x00	USB Host Transmit Interval Endpoint 6	1091
0x16C	USBRXTYPE6	R/W	0x00	USB Host Configure Receive Type Endpoint 6	1093
0x16D	USBRXINTERVAL6	R/W	0x00	USB Host Receive Polling Interval Endpoint 6	1095
0x170	USBTXMAXP7	R/W	0x0000	USB Maximum Transmit Data Endpoint 7	1055
0x172	USBTXCSRL7	R/W	0x00	USB Transmit Control and Status Endpoint 7 Low	1066
0x173	USBTXCSRH7	R/W	0x00	USB Transmit Control and Status Endpoint 7 High	1071
0x174	USBRXMAXP7	R/W	0x0000	USB Maximum Receive Data Endpoint 7	1075
0x176	USBRXCSRL7	R/W	0x00	USB Receive Control and Status Endpoint 7 Low	1077
0x177	USBRXCSRH7	R/W	0x00	USB Receive Control and Status Endpoint 7 High	1082
0x178	USBRXCOUNT7	RO	0x0000	USB Receive Byte Count Endpoint 7	1087
0x17A	USBTXTYPE7	R/W	0x00	USB Host Transmit Configure Type Endpoint 7	1089
0x17B	USBTXINTERVAL7	R/W	0x00	USB Host Transmit Interval Endpoint 7	1091
0x17C	USBRXTYPE7	R/W	0x00	USB Host Configure Receive Type Endpoint 7	1093
0x17D	USBRXINTERVAL7	R/W	0x00	USB Host Receive Polling Interval Endpoint 7	1095
0x180	USBTXMAXP8	R/W	0x0000	USB Maximum Transmit Data Endpoint 8	1055
0x182	USBTXCSRL8	R/W	0x00	USB Transmit Control and Status Endpoint 8 Low	1066
0x183	USBTXCSRH8	R/W	0x00	USB Transmit Control and Status Endpoint 8 High	1071
0x184	USBRXMAXP8	R/W	0x0000	USB Maximum Receive Data Endpoint 8	1075
0x186	USBRXCSRL8	R/W	0x00	USB Receive Control and Status Endpoint 8 Low	1077
0x187	USBRXCSRH8	R/W	0x00	USB Receive Control and Status Endpoint 8 High	1082
0x188	USBRXCOUNT8	RO	0x0000	USB Receive Byte Count Endpoint 8	1087
0x18A	USBTXTYPE8	R/W	0x00	USB Host Transmit Configure Type Endpoint 8	1089
0x18B	USBTXINTERVAL8	R/W	0x00	USB Host Transmit Interval Endpoint 8	1091
0x18C	USBRXTYPE8	R/W	0x00	USB Host Configure Receive Type Endpoint 8	1093
0x18D	USBRXINTERVAL8	R/W	0x00	USB Host Receive Polling Interval Endpoint 8	1095
0x190	USBTXMAXP9	R/W	0x0000	USB Maximum Transmit Data Endpoint 9	1055
0x192	USBTXCSRL9	R/W	0x00	USB Transmit Control and Status Endpoint 9 Low	1066
0x193	USBTXCSRH9	R/W	0x00	USB Transmit Control and Status Endpoint 9 High	1071
0x194	USBRXMAXP9	R/W	0x0000	USB Maximum Receive Data Endpoint 9	1075
0x196	USBRXCSRL9	R/W	0x00	USB Receive Control and Status Endpoint 9 Low	1077
0x197	USBRXCSRH9	R/W	0x00	USB Receive Control and Status Endpoint 9 High	1082

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x198	USBRXCOUNT9	RO	0x0000	USB Receive Byte Count Endpoint 9	1087
0x19A	USBTXTYPE9	R/W	0x00	USB Host Transmit Configure Type Endpoint 9	1089
0x19B	USBTXINTERVAL9	R/W	0x00	USB Host Transmit Interval Endpoint 9	1091
0x19C	USBRXTYPE9	R/W	0x00	USB Host Configure Receive Type Endpoint 9	1093
0x19D	USBRXINTERVAL9	R/W	0x00	USB Host Receive Polling Interval Endpoint 9	1095
0x1A0	USBTXMAXP10	R/W	0x0000	USB Maximum Transmit Data Endpoint 10	1055
0x1A2	USBTXCSRL10	R/W	0x00	USB Transmit Control and Status Endpoint 10 Low	1066
0x1A3	USBTXCSRH10	R/W	0x00	USB Transmit Control and Status Endpoint 10 High	1071
0x1A4	USBRXMAXP10	R/W	0x0000	USB Maximum Receive Data Endpoint 10	1075
0x1A6	USBRXCSRL10	R/W	0x00	USB Receive Control and Status Endpoint 10 Low	1077
0x1A7	USBRXCSRH10	R/W	0x00	USB Receive Control and Status Endpoint 10 High	1082
0x1A8	USBRXCOUNT10	RO	0x0000	USB Receive Byte Count Endpoint 10	1087
0x1AA	USBTXTYPE10	R/W	0x00	USB Host Transmit Configure Type Endpoint 10	1089
0x1AB	USBTXINTERVAL10	R/W	0x00	USB Host Transmit Interval Endpoint 10	1091
0x1AC	USBRXTYPE10	R/W	0x00	USB Host Configure Receive Type Endpoint 10	1093
0x1AD	USBRXINTERVAL10	R/W	0x00	USB Host Receive Polling Interval Endpoint 10	1095
0x1B0	USBTXMAXP11	R/W	0x0000	USB Maximum Transmit Data Endpoint 11	1055
0x1B2	USBTXCSRL11	R/W	0x00	USB Transmit Control and Status Endpoint 11 Low	1066
0x1B3	USBTXCSRH11	R/W	0x00	USB Transmit Control and Status Endpoint 11 High	1071
0x1B4	USBRXMAXP11	R/W	0x0000	USB Maximum Receive Data Endpoint 11	1075
0x1B6	USBRXCSRL11	R/W	0x00	USB Receive Control and Status Endpoint 11 Low	1077
0x1B7	USBRXCSRH11	R/W	0x00	USB Receive Control and Status Endpoint 11 High	1082
0x1B8	USBRXCOUNT11	RO	0x0000	USB Receive Byte Count Endpoint 11	1087
0x1BA	USBTXTYPE11	R/W	0x00	USB Host Transmit Configure Type Endpoint 11	1089
0x1BB	USBTXINTERVAL11	R/W	0x00	USB Host Transmit Interval Endpoint 11	1091
0x1BC	USBRXTYPE11	R/W	0x00	USB Host Configure Receive Type Endpoint 11	1093
0x1BD	USBRXINTERVAL11	R/W	0x00	USB Host Receive Polling Interval Endpoint 11	1095
0x1C0	USBTXMAXP12	R/W	0x0000	USB Maximum Transmit Data Endpoint 12	1055
0x1C2	USBTXCSRL12	R/W	0x00	USB Transmit Control and Status Endpoint 12 Low	1066
0x1C3	USBTXCSRH12	R/W	0x00	USB Transmit Control and Status Endpoint 12 High	1071
0x1C4	USBRXMAXP12	R/W	0x0000	USB Maximum Receive Data Endpoint 12	1075
0x1C6	USBRXCSRL12	R/W	0x00	USB Receive Control and Status Endpoint 12 Low	1077

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x1C7	USBRXCSRH12	R/W	0x00	USB Receive Control and Status Endpoint 12 High	1082
0x1C8	USBRXCOUNT12	RO	0x0000	USB Receive Byte Count Endpoint 12	1087
0x1CA	USBTXTYPE12	R/W	0x00	USB Host Transmit Configure Type Endpoint 12	1089
0x1CB	USBTXINTERVAL12	R/W	0x00	USB Host Transmit Interval Endpoint 12	1091
0x1CC	USBRXTYPE12	R/W	0x00	USB Host Configure Receive Type Endpoint 12	1093
0x1CD	USBRXINTERVAL12	R/W	0x00	USB Host Receive Polling Interval Endpoint 12	1095
0x1D0	USBTXMAXP13	R/W	0x0000	USB Maximum Transmit Data Endpoint 13	1055
0x1D2	USBTXCSRL13	R/W	0x00	USB Transmit Control and Status Endpoint 13 Low	1066
0x1D3	USBTXCSRH13	R/W	0x00	USB Transmit Control and Status Endpoint 13 High	1071
0x1D4	USBRXMAXP13	R/W	0x0000	USB Maximum Receive Data Endpoint 13	1075
0x1D6	USBRXCSRL13	R/W	0x00	USB Receive Control and Status Endpoint 13 Low	1077
0x1D7	USBRXCSRH13	R/W	0x00	USB Receive Control and Status Endpoint 13 High	1082
0x1D8	USBRXCOUNT13	RO	0x0000	USB Receive Byte Count Endpoint 13	1087
0x1DA	USBTXTYPE13	R/W	0x00	USB Host Transmit Configure Type Endpoint 13	1089
0x1DB	USBTXINTERVAL13	R/W	0x00	USB Host Transmit Interval Endpoint 13	1091
0x1DC	USBRXTYPE13	R/W	0x00	USB Host Configure Receive Type Endpoint 13	1093
0x1DD	USBRXINTERVAL13	R/W	0x00	USB Host Receive Polling Interval Endpoint 13	1095
0x1E0	USBTXMAXP14	R/W	0x0000	USB Maximum Transmit Data Endpoint 14	1055
0x1E2	USBTXCSRL14	R/W	0x00	USB Transmit Control and Status Endpoint 14 Low	1066
0x1E3	USBTXCSRH14	R/W	0x00	USB Transmit Control and Status Endpoint 14 High	1071
0x1E4	USBRXMAXP14	R/W	0x0000	USB Maximum Receive Data Endpoint 14	1075
0x1E6	USBRXCSRL14	R/W	0x00	USB Receive Control and Status Endpoint 14 Low	1077
0x1E7	USBRXCSRH14	R/W	0x00	USB Receive Control and Status Endpoint 14 High	1082
0x1E8	USBRXCOUNT14	RO	0x0000	USB Receive Byte Count Endpoint 14	1087
0x1EA	USBTXTYPE14	R/W	0x00	USB Host Transmit Configure Type Endpoint 14	1089
0x1EB	USBTXINTERVAL14	R/W	0x00	USB Host Transmit Interval Endpoint 14	1091
0x1EC	USBRXTYPE14	R/W	0x00	USB Host Configure Receive Type Endpoint 14	1093
0x1ED	USBRXINTERVAL14	R/W	0x00	USB Host Receive Polling Interval Endpoint 14	1095
0x1F0	USBTXMAXP15	R/W	0x0000	USB Maximum Transmit Data Endpoint 15	1055
0x1F2	USBTXCSRL15	R/W	0x00	USB Transmit Control and Status Endpoint 15 Low	1066
0x1F3	USBTXCSRH15	R/W	0x00	USB Transmit Control and Status Endpoint 15 High	1071
0x1F4	USBRXMAXP15	R/W	0x0000	USB Maximum Receive Data Endpoint 15	1075

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Type	Reset	Description	See page	
0x1F6	USBRXCSRL15	R/W	0x00	USB Receive Control and Status Endpoint 15 Low	1077	
0x1F7	USBRXCSRH15	R/W	0x00	USB Receive Control and Status Endpoint 15 High	1082	
0x1F8	USBRXCOUNT15	RO	0x0000	USB Receive Byte Count Endpoint 15	1087	
0x1FA	USBTXTYPE15	R/W	0x00	USB Host Transmit Configure Type Endpoint 15	1089	
0x1FB	USBTXINTERVAL15	R/W	0x00	USB Host Transmit Interval Endpoint 15	1091	
0x1FC	USBRXTYPE15	R/W	0x00	USB Host Configure Receive Type Endpoint 15	1093	
0x1FD	USBRXINTERVAL15	R/W	0x00	USB Host Receive Polling Interval Endpoint 15	1095	
0x304	USBRQPKTCOUNT1	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 1	1097	
0x308	USBRQPKTCOUNT2	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 2	1097	
0x30C	USBRQPKTCOUNT3	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 3	1097	
0x310	USBRQPKTCOUNT4	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 4	1097	
0x314	USBRQPKTCOUNT5	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 5	1097	
0x318	USBRQPKTCOUNT6	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 6	1097	
0x31C	USBRQPKTCOUNT7	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 7	1097	
0x320	USBRQPKTCOUNT8	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 8	1097	
0x324	USBRQPKTCOUNT9	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 9	1097	
0x328	USBRQPKTCOUNT10	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 10	1097	
0x32C	USBRQPKTCOUNT11	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 11	1097	
0x330	USBRQPKTCOUNT12	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 12	1097	
0x334	USBRQPKTCOUNT13	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 13	1097	
0x338	USBRQPKTCOUNT14	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint 14	1097	
0x33C	USBRQPKTCOUNT15	R/W	0x0000	USB Request Packet Count in Block Transfer Endpoint		
0x340	USBRXDPKTBUFDIS	R/W	0x0000	USB Receive Double Packet Buffer Disable	1099	
0x342	USBTXDPKTBUFDIS	R/W	0x0000	USB Transmit Double Packet Buffer Disable	1101	

Table 19-6. Universal Serial Bus (USB) Controller Register Map (continued)

Offset	Name	Type	Reset	Description	See page
0x400	USBEPC	R/W	0x0000.0000	USB External Power Control	1103
0x404	USBEPCRIS	RO	0x0000.0000	USB External Power Control Raw Interrupt Status	1106
0x408	USBEPCIM	R/W	0x0000.0000	USB External Power Control Interrupt Mask	1107
0x40C	USBEPCISC	R/W	0x0000.0000	USB External Power Control Interrupt Status and Clear	1108
0x410	USBDRRIS	RO	0x0000.0000	USB Device RESUME Raw Interrupt Status	1109
0x414	USBDRIM	R/W	0x0000.0000	USB Device RESUME Interrupt Mask	1110
0x418	USBDRISC	W1C	0x0000.0000	USB Device RESUME Interrupt Status and Clear	1111
0x41C	USBGPCS	R/W	0x0000.0001	USB General-Purpose Control and Status	1112
0x430	USBVDC	R/W	0x0000.0000	USB VBUS Droop Control	1113
0x434	USBVDCRIS	RO	0x0000.0000	USB VBUS Droop Control Raw Interrupt Status	1114
0x438	USBVDCIM	R/W	0x0000.0000	USB VBUS Droop Control Interrupt Mask	1115
0x43C	USBVDCISC	R/W	0x0000.0000	USB VBUS Droop Control Interrupt Status and Clear	1116
0x444	USBIDVRIS	RO	0x0000.0000	USB ID Valid Detect Raw Interrupt Status	1117
0x448	USBIDVIM	R/W	0x0000.0000	USB ID Valid Detect Interrupt Mask	1118
0x44C	USBIDVISC	R/W1C	0x0000.0000	USB ID Valid Detect Interrupt Status and Clear	1119
0x450	USBDMASEL	R/W	0x0033.2211	USB DMA Select	1120

# 19.6 Register Descriptions

The LM3S9D96 USB controller has On-The-Go (OTG) capabilities as specified in the USB0 bit field in the **DC6** register (see page 253).

OTG B /

This icon indicates that the register is used in OTG B or Device mode. Some registers are used for both Host and Device mode and may have different bit definitions depending on the mode.

OTG A / Host This icon indicates that the register is used in OTG A or Host mode. Some registers are used for both Host and Device mode and may have different bit definitions depending on the mode. The USB controller is in OTG B or Device mode upon reset, so the reset values shown for these registers apply to the Device mode definition.

OTG

This icon indicates that the register is used for OTG-specific functions such as ID detection and negotiation. Once OTG negotiation is complete, then the USB controller registers are used according to their Host or Device mode meanings depending on whether the OTG negotiations made the USB controller OTG A (Host) or OTG B (Device).

## Register 1: USB Device Functional Address (USBFADDR), offset 0x000

OTG B /


**USBFADDR** is an 8-bit register that contains the 7-bit address of the Device part of the transaction.

When the USB controller is being used in Device mode (the HOST bit in the **USBDEVCTL** register is clear), this register must be written with the address received through a SET\_ADDRESS command, which is then used for decoding the function address in subsequent token packets.

**Important:** See the section called "Setting the Device Address" on page 990 for special considerations when writing this register.

### USB Device Functional Address (USBFADDR)

Base 0x4005.0000 Offset 0x000 Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	FUNCADDR	R/W	0x00	Function Address

Function Address of Device as received through SET\_ADDRESS.

## Register 2: USB Power (USBPOWER), offset 0x001




**USBPOWER** is an 8-bit register used for controlling SUSPEND and RESUME signaling and some basic operational aspects of the USB controller.

OTG B / **Device** 

### OTG A / Host Mode

**USB Power (USBPOWER)** 

Base 0x4005.0000 Offset 0x001 Type R/W, reset 0x20



Bit/Field	Name	Туре	Reset	Description
7:4	reserved	RO	0x2	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	RESET	R/W	0	RESET Signaling
				Value Description
				1 Enables RESET signaling on the bus.
				0 Ends RESET signaling on the bus.
2	RESUME	R/W	0	RESUME Signaling
				Value Description
				1 Enables RESUME signaling when the Device is in SUSPEND mode.
				0 Ends RESUME signaling on the bus.
				This bit must be cleared by software 20 ms after being set.
1	SUSPEND	R/W1S	0	SUSPEND Mode
				Value Description

Enables SUSPEND mode.

0 No effect.

Bit/Field	Name	Type	Reset	Description
0	PWRDNPHY	R/W	0	Power Down PHY
				Value Description
				1 Powers down the internal USB PHY.
				0 No effect.

### **OTG B / Device Mode**

USB Power (USBPOWER)

Base 0x4005.0000 Offset 0x001 Type R/W, reset 0x20



Bit/Field	Name	Туре	Reset	Description
7	ISOUP	R/W	0	Isochronous Update
				Value Description
				The USB controller waits for an SOF token from the time the TXRDY bit is set in the <b>USBTXCSRLn</b> register before sending the packet. If an IN token is received before an SOF token, then a zero-length data packet is sent.
				0 No effect.
				<b>Note:</b> This bit is only valid for isochronous transfers.
6	SOFTCONN	R/W	0	Soft Connect/Disconnect
				Value Description
				1 The USB D+/D- lines are enabled.
				0 The USB D+/D- lines are tri-stated.
5:4	reserved	RO	0x2	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	RESET	RO	0	RESET Signaling
				Value Description
				1 RESET signaling is present on the bus.
				0 RESET signaling is not present on the bus.

Bit/Field	Name	Туре	Reset	Description
2	RESUME	R/W	0	RESUME Signaling
				Value Description  1 Enables RESUME signaling when the Device is in SUSPEND mode.
				0 Ends RESUME signaling on the bus.
				This bit must be cleared by software 10 ms (a maximum of 15 ms) after being set.
1	SUSPEND	RO	0	SUSPEND Mode
				Value Description
				1 The USB controller is in SUSPEND mode.
				O This bit is cleared when software reads the interrupt register or sets the RESUME bit above.
0	PWRDNPHY	R/W	0	Power Down PHY
				Value Description
				1 Powers down the internal USB PHY.
				0 No effect.

### Register 3: USB Transmit Interrupt Status (USBTXIS), offset 0x002

**Important:** This register is read-sensitive. See the register description for details.

OTG A /

OTG B /

**USBTXIS** is a 16-bit read-only register that indicates which interrupts are currently active for endpoint 0 and the transmit endpoints 1–15. The meaning of the  $\mathtt{EPn}$  bits in this register is based on the mode of the device. The  $\mathtt{EP1}$  through  $\mathtt{EP15}$  bits always indicate that the USB controller is sending data; however, in Host mode, the bits refer to OUT endpoints; while in Device mode, the bits refer to IN endpoints. The  $\mathtt{EP0}$  bit is special in Host and Device modes and indicates that either a control IN or control OUT endpoint has generated an interrupt.

**Note:** Bits relating to endpoints that have not been configured always return 0. Note also that all active interrupts are cleared when this register is read.

USB Transmit Interrupt Status (USBTXIS)

Base 0x4005.0000 Offset 0x002 Type RO, reset 0x0000

_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	EP0	
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	
Pocet	Λ	0	Λ	0	Λ	Λ	Λ	Λ	Λ	Λ	Λ	Λ	0	Λ	Λ	Λ	

Bit/Field	Name	Type	Reset	Description
15	EP15	RO	0	TX Endpoint 15 Interrupt
				Value Description
				0 No interrupt.
				1 The Endpoint 15 transmit interrupt is asserted.
14	EP14	RO	0	TX Endpoint 14 Interrupt
				Same description as EP15.
13	EP13	RO	0	TX Endpoint 13 Interrupt
				Same description as EP15.
12	EP12	RO	0	TX Endpoint 12 Interrupt
				Same description as EP15.
11	EP11	RO	0	TX Endpoint 11 Interrupt
				Same description as EP15.
10	EP10	RO	0	TX Endpoint 10 Interrupt
				Same description as EP15.
9	EP9	RO	0	TX Endpoint 9 Interrupt
				Same description as EP15.
8	EP8	RO	0	TX Endpoint 8 Interrupt
				Same description as EP15.
7	EP7	RO	0	TX Endpoint 7 Interrupt
				Same description as EP15.

Bit/Field	Name	Туре	Reset	Description
6	EP6	RO	0	TX Endpoint 6 Interrupt Same description as EP15.
5	EP5	RO	0	TX Endpoint 5 Interrupt Same description as EP15.
4	EP4	RO	0	TX Endpoint 4 Interrupt Same description as EP15.
3	EP3	RO	0	TX Endpoint 3 Interrupt Same description as EP15.
2	EP2	RO	0	TX Endpoint 2 Interrupt Same description as EP15.
1	EP1	RO	0	TX Endpoint 1 Interrupt Same description as EP15.
0	EP0	RO	0	TX and RX Endpoint 0 Interrupt
				Value Description  No interrupt.  The Endpoint 0 transmit and receive interrupt is asserted.

## Register 4: USB Receive Interrupt Status (USBRXIS), offset 0x004

**Important:** This register is read-sensitive. See the register description for details.

OTG A /

**USBRXIS** is a 16-bit read-only register that indicates which of the interrupts for receive endpoints 1–15 are currently active.

**Note:** Bits relating to endpoints that have not been configured always return 0. Note also that all active interrupts are cleared when this register is read.

OTG B /
Device

USB Receive Interrupt Status (USBRXIS)

Base 0x4005.0000 Offset 0x004 Type RO, reset 0x0000

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0	
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	reserved	
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	
D 4	^	^	^	^	^	•	^	^	•	^	^	^	^	^	^	^	

Bit/Field	Name	Туре	Reset	Description
15	EP15	RO	0	RX Endpoint 15 Interrupt
				Value Description  No interrupt.  The Endpoint 15 receive interrupt is asserted.
14	EP14	RO	0	RX Endpoint 14 Interrupt Same description as EP15.
13	EP13	RO	0	RX Endpoint 13 Interrupt Same description as EP15.
12	EP12	RO	0	RX Endpoint 12 Interrupt Same description as EP15.
11	EP11	RO	0	RX Endpoint 11 Interrupt Same description as EP15.
10	EP10	RO	0	RX Endpoint 10 Interrupt Same description as EP15.
9	EP9	RO	0	RX Endpoint 9 Interrupt Same description as EP15.
8	EP8	RO	0	RX Endpoint 8 Interrupt Same description as EP15.
7	EP7	RO	0	RX Endpoint 7 Interrupt Same description as EP15.
6	EP6	RO	0	RX Endpoint 6 Interrupt Same description as EP15.

Bit/Field	Name	Туре	Reset	Description
5	EP5	RO	0	RX Endpoint 5 Interrupt Same description as EP15.
4	EP4	RO	0	RX Endpoint 4 Interrupt Same description as EP15.
3	EP3	RO	0	RX Endpoint 3 Interrupt Same description as EP15.
2	EP2	RO	0	RX Endpoint 2 Interrupt Same description as EP15.
1	EP1	RO	0	RX Endpoint 1 Interrupt Same description as EP15.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 5: USB Transmit Interrupt Enable (USBTXIE), offset 0x006



**USBTXIE** is a 16-bit register that provides interrupt enable bits for the interrupts in the **USBTXIS** register. When a bit is set, the USB interrupt is asserted to the interrupt controller when the corresponding interrupt bit in the **USBTXIS** register is set. When a bit is cleared, the interrupt in the **USBTXIS** register is still set but the USB interrupt to the interrupt controller is not asserted. On reset, all interrupts are enabled.

OTG B /
Device

USB Transmit Interrupt Enable (USBTXIE)

Base 0x4005.0000 Offset 0x006

Type R/W, reset 0xFFFF

71	,															
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	EP0
Type	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Reset	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

Bit/Field	Name	Туре	Reset	Description
15	EP15	R/W	1	TX Endpoint 15 Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the EP15 bit in the <b>USBTXIS</b> register is set.
				O The EP15 transmit interrupt is suppressed and not sent to the interrupt controller.
14	EP14	R/W	1	TX Endpoint 14 Interrupt Enable
				Same description as EP15.
13	EP13	R/W	1	TX Endpoint 13 Interrupt Enable
				Same description as EP15.
12	EP12	R/W	1	TX Endpoint 12 Interrupt Enable
				Same description as EP15.
11	EP11	R/W	1	TX Endpoint 11 Interrupt Enable
				Same description as EP15.
10	EP10	R/W	1	TX Endpoint 10 Interrupt Enable
				Same description as EP15.
9	EP9	R/W	1	TX Endpoint 9 Interrupt Enable
				Same description as EP15.
8	EP8	R/W	1	TX Endpoint 8 Interrupt Enable
				Same description as EP15.
7	EP7	R/W	1	TX Endpoint 7 Interrupt Enable
				Same description as EP15.
6	EP6	R/W	1	TX Endpoint 6 Interrupt Enable
				Same description as EP15.

Bit/Field	Name	Туре	Reset	Description
5	EP5	R/W	1	TX Endpoint 5 Interrupt Enable Same description as EP15.
4	EP4	R/W	1	TX Endpoint 4 Interrupt Enable Same description as EP15.
3	EP3	R/W	1	TX Endpoint 3 Interrupt Enable Same description as EP15.
2	EP2	R/W	1	TX Endpoint 2 Interrupt Enable Same description as EP15.
1	EP1	R/W	1	TX Endpoint 1 Interrupt Enable Same description as EP15.
0	EP0	R/W	1	TX and RX Endpoint 0 Interrupt Enable

### Value Description

- An interrupt is sent to the interrupt controller when the EPO bit in the **USBTXIS** register is set.
- 0 The  $\mathtt{EP}\,\mathtt{0}$  transmit and receive interrupt is suppressed and not sent to the interrupt controller.

## Register 6: USB Receive Interrupt Enable (USBRXIE), offset 0x008



**USBRXIE** is a 16-bit register that provides interrupt enable bits for the interrupts in the **USBRXIS** register. When a bit is set, the USB interrupt is asserted to the interrupt controller when the corresponding interrupt bit in the USBRXIS register is set. When a bit is cleared, the interrupt in the **USBRXIS** register is still set but the USB interrupt to the interrupt controller is not asserted. On reset, all interrupts are enabled.

OTG B / **Device** 

USB Receive Interrupt Enable (USBRXIE)

Base 0x4005.0000 Offset 0x008

Type	R/W, res	et 0xFFFE														
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	reserved
Type Reset	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	R/W 1	RO 0
Е	Bit/Field		Nam	ne	Ту	pe	Reset	Des	cription							
	15		EP1	5	R/	W	1	RX	Endpoin	t 15 Inte	rupt Ena	able				
								Val	ue Desc	cription						
								1		nterrupt is				troller wh	nen the I	:P15 bit
								0	The	EP15 red	ceive inte			sed and	not sent	to the
									inter	rupt cont	roller.					
	14		EP1	4	R/	W	1	RX	Endpoin	t 14 Intei	rupt Ena	able				
								San	ne descr	iption as	EP15.					
	13		EP1	3	R/	W	1	RX	Endpoin	t 13 Inte	rupt Ena	able				
								San	ne descr	iption as	EP15.					
	12		EP1	2	R/	W	1			t 12 Inte		able				
								San	ne descr	iption as	EP15.					
	11		EP1	11	R/	W	1			t 11 Inter		ıble				
			== .		_					iption as						
	10		EP1	0	R/	W	1			t 10 Intei iption as		able				
	9		EP:	۵	D/	W	1			t 9 Interr		مام				
	9		LI,	9	IV	VV	'			iption as		ЛС				
	8		EP	8	R/	W	1	RX	Endpoin	t 8 Interr	upt Enal	ole				
										iption as						
	7		EP:	7	R/	W	1	RX	Endpoin	t 7 Interr	upt Enat	ole				
								San	ne descr	iption as	EP15.					
	6		EP	6	R/	W	1	RX	Endpoin	t 6 Interr	upt Enat	ole				

Same description as EP15.

Bit/Field	Name	Туре	Reset	Description
5	EP5	R/W	1	RX Endpoint 5 Interrupt Enable Same description as EP15.
4	EP4	R/W	1	RX Endpoint 4 Interrupt Enable Same description as EP15.
3	EP3	R/W	1	RX Endpoint 3 Interrupt Enable Same description as EP15.
2	EP2	R/W	1	RX Endpoint 2 Interrupt Enable Same description as EP15.
1	EP1	R/W	1	RX Endpoint 1 Interrupt Enable Same description as EP15.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 7: USB General Interrupt Status (USBIS), offset 0x00A

**Important:** This register is read-sensitive. See the register description for details.

OTG A /

**USBIS** is an 8-bit read-only register that indicates which USB interrupts are currently active. All active interrupts are cleared when this register is read.



### OTG A / Host Mode

USB General Interrupt Status (USBIS)

Base 0x4005.0000 Offset 0x00A Type RO, reset 0x00

	7	6	5	4	3	2	1	0
	VBUSERR	SESREQ	DISCON	CONN	SOF	BABBLE	RESUME	reserved
Type	RO	RO	RO	RO	RO	RO	RO	RO

Bit/Field	Name	Туре	Reset	Description
7	VBUSERR	RO	0	VBUS Error
				<ul> <li>Value Description</li> <li>1 VBUS has dropped below the VBUS Valid threshold during a session.</li> <li>0 No interrupt.</li> </ul>
6	SESREQ	RO	0	SESSION REQUEST  Value Description  1 SESSION REQUEST signaling has been detected.  0 No interrupt.
5	DISCON	RO	0	Session Disconnect  Value Description  1 A Device disconnect has been detected.  0 No interrupt.
4	CONN	RO	0	Session Connect  Value Description  1 A Device connection has been detected.  0 No interrupt.

Bit/Field	Name	Type	Reset	Description
3	SOF	RO	0	Start of Frame
				Value Description
				1 A new frame has started.
				0 No interrupt.
2	BABBLE	RO	0	Babble Detected
				Value Description
				Babble has been detected. This interrupt is active only after the first SOF has been sent.
				0 No interrupt.
1	RESUME	RO	0	RESUME Signaling Detected
				Value Description
				1 RESUME signaling has been detected on the bus while the USB controller is in SUSPEND mode.
				0 No interrupt.
				This interrupt can only be used if the USB controller's system clock is enabled. If the user disables the clock programming, the <b>USBDRRIS</b> , <b>USBDRIM</b> , and <b>USBDRISC</b> registers should be used.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### OTG B / Device Mode

USB General Interrupt Status (USBIS)

Base 0x4005.0000 Offset 0x00A Type RO, reset 0x00

	7	6	5	4	3	2	1	0
	rese	reserved		reserved	SOF	RESET	RESUME	SUSPEND
Type	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	DISCON	RO	0	Session Disconnect
				Value Description
				1 The device has been disconnected from the host.

0

No interrupt.

Bit/Field	Name	Туре	Reset	Description
4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	SOF	RO	0	Start of Frame  Value Description  1 A new frame has started.  0 No interrupt.
2	RESET	RO	0	RESET Signaling Detected  Value Description  RESET signaling has been detected on the bus.  No interrupt.
1	RESUME	RO	0	PRESUME Signaling Detected  Value Description  RESUME signaling has been detected on the bus while the USB controller is in SUSPEND mode.  No interrupt.  This interrupt can only be used if the USB controller's system clock is enabled. If the user disables the clock programming, the USBDRIS, USBDRIM, and USBDRISC registers should be used.
0	SUSPEND	RO	0	SUSPEND Signaling Detected  Value Description  1 SUSPEND signaling has been detected on the bus.  0 No interrupt.

# Register 8: USB Interrupt Enable (USBIE), offset 0x00B




**USBIE** is an 8-bit register that provides interrupt enable bits for each of the interrupts in **USBIS**. At reset interrupts 1 and 2 are enabled in Device mode.

OTG B / Device

### OTG A / Host Mode

USB Interrupt Enable (USBIE)

Base 0x4005.0000 Offset 0x00B Type R/W, reset 0x06



Bit/Field	Name	Туре	Reset	Description
7	VBUSERR	R/W	0	Enable VBUS Error Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the VBUSERR bit in the <b>USBIS</b> register is set.
				O The VBUSERR interrupt is suppressed and not sent to the interrupt controller.
6	SESREQ	R/W	0	Enable Session Request
				Value Description
				An interrupt is sent to the interrupt controller when the SESREEQ bit in the <b>USBIS</b> register is set.
				O The SESREQ interrupt is suppressed and not sent to the interrupt controller.
5	DISCON	R/W	0	Enable Disconnect Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the DISCON

- An interrupt is sent to the interrupt controller when the DISCON bit in the USBIS register is set.
- The DISCON interrupt is suppressed and not sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
4	CONN	R/W	0	Enable Connect Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the CONN bit in the <b>USBIS</b> register is set.
				O The CONN interrupt is suppressed and not sent to the interrupt controller.
3	SOF	R/W	0	Enable Start-of-Frame Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the SOF bit in the <b>USBIS</b> register is set.
				O The SOF interrupt is suppressed and not sent to the interrupt controller.
2	BABBLE	R/W	1	Enable Babble Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the BABBLE bit in the <b>USBIS</b> register is set.
				O The BABBLE interrupt is suppressed and not sent to the interrupt controller.
1	RESUME	R/W	1	Enable RESUME Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the RESUME bit in the <b>USBIS</b> register is set.
				O The RESUME interrupt is suppressed and not sent to the interrupt controller.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### OTG B / Device Mode

USB Interrupt Enable (USBIE)

Base 0x4005.0000 Offset 0x00B Type R/W, reset 0x06



Bit/Field	Name	Туре	Reset	Description
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	DISCON	R/W	0	Enable Disconnect Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the DISCON bit in the <b>USBIS</b> register is set.
				The DISCON interrupt is suppressed and not sent to the interrupt controller.
4	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	SOF	R/W	0	Enable Start-of-Frame Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the SOF bit in the <b>USBIS</b> register is set.
				O The SOF interrupt is suppressed and not sent to the interrupt controller.
2	RESET	R/W	1	Enable RESET Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the RESET bit in the <b>USBIS</b> register is set.
				O The RESET interrupt is suppressed and not sent to the interrupt controller.
1	RESUME	R/W	1	Enable RESUME Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the RESUME bit in the <b>USBIS</b> register is set.
				The RESUME interrupt is suppressed and not sent to the interrupt controller.
0	SUSPEND	R/W	0	Enable SUSPEND Interrupt
				Value Description
				An interrupt is sent to the interrupt controller when the SUSPEND bit in the <b>USBIS</b> register is set.
				0 The SUSPEND interrupt is suppressed and not sent to the interrupt controller.

# Register 9: USB Frame Value (USBFRAME), offset 0x00C

OTG A /


**USBFRAME** is a 16-bit read-only register that holds the last received frame number.

Host

USB Frame Value (USBFRAME)

Base 0x4005.0000 Offset 0x00C Type RO, reset 0x0000

OTG B / **Device** 



Bit/Field	Name	Туре	Reset	Description
15:11	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10:0	FRAME	RO	0x000	Frame Number

### Register 10: USB Endpoint Index (USBEPIDX), offset 0x00E



Each endpoint's buffer can be accessed by configuring a FIFO size and starting address. The **USBEPIDX** 8-bit register is used with the **USBTXFIFOSZ**, **USBRXFIFOSZ**, **USBTXFIFOADD**, and **USBRXFIFOADD** registers.

# OTG B / Device

USB Endpoint Index (USBEPIDX)

Base 0x4005.0000 Offset 0x00E Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7:4	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	EPIDX	R/W	0x0	Endpoint Index

This bit field configures which endpoint is accessed when reading or writing to one of the USB controller's indexed registers. A value of 0x0 corresponds to Endpoint 0 and a value of 0xF corresponds to Endpoint 15.

### Register 11: USB Test Mode (USBTEST), offset 0x00F



**Device** 

**USBTEST** is an 8-bit register that is primarily used to put the USB controller into one of the four test modes for operation described in the *USB 2.0 Specification*, in response to a SET FEATURE: USBTESTMODE command. This register is not used in normal operation.


OTG B /

**Note:** Only one of these bits should be set at any time.

### OTG A / Host Mode

**USB Test Mode (USBTEST)** 

Base 0x4005.0000 Offset 0x00F Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	FORCEH	R/M	0	Force Host Mode

#### Value Description

- Forces the USB controller to enter Host mode when the SESSION bit is set, regardless of whether the USB controller is connected to any peripheral. The state of the USBODP and USBODM signals is ignored. The USB controller then remains in Host mode until the SESSION bit is cleared, even if a Device is disconnected. If the FORCEH bit remains set, the USB controller re-enters Host mode the next time the SESSION bit is set.
- No effect.

While in this mode, status of the bus connection may be read using the  ${\tt DEV}$  bit of the  ${\tt USBDEVCTL}$  register. The operating speed is determined from the  ${\tt FORCEFS}$  bit.

6	FIFOACC	R/W1S	0	FIFO Access
				Value Description

- Transfers the packet in the endpoint 0 transmit FIFO to the endpoint 0 receive FIFO.
- No effect.

This bit is cleared automatically.

5 FORCEFS R/W 0 Force Full-Speed Mode

### Value Description

- Forces the USB controller into Full-Speed mode upon receiving a USB RESET.
- 0 The USB controller operates at Low Speed.

Bit/Field	Name	Type	Reset	Description
4:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### OTG B / Device Mode

### USB Test Mode (USBTEST)

Base 0x4005.0000 Offset 0x00F Type R/W, reset 0x00

	7	6	5	4	3	2	1	0
	reserved	FIFOACC			resei	rved	1	
Type	RO	R/W1S	RO	RO	RO	RO	RO	RO
Reset	Ω	0	0	0	0	Ω	0	Ω

Bit/Field	Name	Type	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	FIFOACC	R/W1S	0	FIFO Access
				Value Description
				1 Transfers the packet in the endpoint 0 transmit FIFO to the endpoint 0 receive FIFO.
				0 No effect.
				This bit is cleared automatically.
5:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Register 12: USB FIFO Endpoint 0 (USBFIFO0), offset 0x020 Register 13: USB FIFO Endpoint 1 (USBFIFO1), offset 0x024 Register 14: USB FIFO Endpoint 2 (USBFIFO2), offset 0x028 Register 15: USB FIFO Endpoint 3 (USBFIFO3), offset 0x02C Register 16: USB FIFO Endpoint 4 (USBFIFO4), offset 0x030 Register 17: USB FIFO Endpoint 5 (USBFIFO5), offset 0x034 Register 18: USB FIFO Endpoint 6 (USBFIFO6), offset 0x038 Register 19: USB FIFO Endpoint 7 (USBFIFO7), offset 0x03C Register 20: USB FIFO Endpoint 8 (USBFIFO8), offset 0x040 Register 21: USB FIFO Endpoint 9 (USBFIFO9), offset 0x044 Register 22: USB FIFO Endpoint 10 (USBFIFO10), offset 0x048 Register 23: USB FIFO Endpoint 11 (USBFIFO11), offset 0x04C Register 24: USB FIFO Endpoint 12 (USBFIFO12), offset 0x050 Register 25: USB FIFO Endpoint 13 (USBFIFO13), offset 0x054 Register 26: USB FIFO Endpoint 14 (USBFIFO14), offset 0x058 Register 27: USB FIFO Endpoint 15 (USBFIFO15), offset 0x05C

**Important:** This register is read-sensitive. See the register description for details.

OTG A /

These 32-bit registers provide an address for CPU access to the FIFOs for each endpoint. Writing to these addresses loads data into the Transmit FIFO for the corresponding endpoint. Reading from these addresses unloads data from the Receive FIFO for the corresponding endpoint.

OTG B /
Device

Transfers to and from FIFOs may be 8-bit, 16-bit or 32-bit as required, and any combination of accesses is allowed provided the data accessed is contiguous. All transfers associated with one packet must be of the same width so that the data is consistently byte-, halfword- or word-aligned. However, the last transfer may contain fewer bytes than the previous transfers in order to complete an odd-byte or odd-word transfer.

Depending on the size of the FIFO and the expected maximum packet size, the FIFOs support either single-packet or double-packet buffering (see the section called "Single-Packet Buffering" on page 988). Burst writing of multiple packets is not supported as flags must be set after each packet is written.

Following a STALL response or a transmit error on endpoint 1–15, the associated FIFO is completely flushed.

**EPDATA** 


R/W

### USB FIFO Endpoint 0 (USBFIFO0)

Base 0x4005.0000 Offset 0x020

31:0

Type R/W, reset 0x0000.0000



0x0000.0000 Endpoint Data

Writing to this register loads the data into the Transmit FIFO and reading unloads data from the Receive FIFO.

### Register 28: USB Device Control (USBDEVCTL), offset 0x060



**USBDEVCTL** is an 8-bit register used for controlling and monitoring the USB VBUS line. If the PHY is suspended, no PHY clock is received and the VBUS is not sampled. In addition, in Host mode, **USBDEVCTL** provides the status information for the current operating mode (Host or Device) of the USB controller. If the USB controller is in Host mode, this register also indicates if a full- or low-speed Device has been connected.

### USB Device Control (USBDEVCTL)

Base 0x4005.0000 Offset 0x060 Type R/W, reset 0x80

	7	6	5	4	3	2	1	0
	DEV	FSDEV	LSDEV	VB	US	HOST	HOSTREQ	SESSION
Type	RO	RO	RO	RO	RO	RO	R/W	R/W
Reset	1	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
7	DEV	RO	1	Device Mode
				Value Description  The USB controller is operating on the OTG A side of the cable.  The USB controller is operating on the OTG B side of the cable.  Note: This value is only valid while a session is in progress.
6	FSDEV	RO	0	Full-Speed Device Detected
				Value Description  O A full-speed Device has not been detected on the port.  A full-speed Device has been detected on the port.
5	LSDEV	RO	0	Low-Speed Device Detected
				Value Description  O A low-speed Device has not been detected on the port.  A low-speed Device has been detected on the port.
4:3	VBUS	RO	0x0	VBUS Level
				Value Description  0x0 Below SessionEnd     VBUS is detected as under 0.5 V.  0x1 Above SessionEnd, below AValid     VBUS is detected as above 0.5 V and under 1.5 V.  0x2 Above AValid, below VBUSValid     VBUS is detected as above 1.5 V and below 4.75 V.  0x3 Above VBUSValid
				VBUS is detected as above 4.75 V.

Bit/Field	Name	Туре	Reset	Description		
2	HOST	RO	0	Host Mode		
				Value Description  O The USB controller is acting as a Device.  The USB controller is acting as a Host.  Note: This value is only valid while a session is in progress.		
1	HOSTREQ	R/W	0	Host Request  Value Description  0 No effect.  1 Initiates the Host Negotiation when SUSPEND mode is entered.  This bit is cleared when Host Negotiation is completed.		
0	SESSION	R/W	0	Session Start/End  When operating as an OTG A device:  Value Description  0 When cleared by software, this bit ends a session.  1 When set by software, this bit starts a session.  When operating as an OTG B device:		

Value Description

The USB controller has ended a session. When the USB controller is in SUSPEND mode, this bit may be cleared by software to perform a software disconnect.

1 The USB controller has started a session. When set by software, the Session Request Protocol is initiated.

**Note:** Clearing this bit when the USB controller is not suspended results in undefined behavior.

# Register 29: USB Transmit Dynamic FIFO Sizing (USBTXFIFOSZ), offset 0x062 Register 30: USB Receive Dynamic FIFO Sizing (USBRXFIFOSZ), offset 0x063

OTG A /

These 8-bit registers allow the selected TX/RX endpoint FIFOs to be dynamically sized. **USBEPIDX** is used to configure each transmit endpoint's FIFO size.

USB Transmit Dynamic FIFO Sizing (USBTXFIFOSZ)

OTG B /

Base 0x4005.0000 Offset 0x062 Type R/W, reset 0x00

	7	6	5	4	3	2	1	0
	reserved			DPB	SIZE			
Туре	RO	RO	RO	R/W	R/W	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4	DPB	R/W	0	Double Packet Buffer Support
				Value Description  Only single-packet buffering is supported.
				Double-packet buffering is supported.
3:0	SIZE	R/W	0x0	Max Packet Size

Maximum packet size to be allowed.

If  ${\tt DPB}$  = 0, the FIFO also is this size; if  ${\tt DPB}$  = 1, the FIFO is twice this size.


Value	Packet Size (Bytes)
0x0	8
0x1	16
0x2	32
0x3	64
0x4	128
0x5	256
0x6	512
0x7	1024
8x0	2048
0x9-0xF	Reserved

# Register 31: USB Transmit FIFO Start Address (USBTXFIFOADD), offset 0x064 Register 32: USB Receive FIFO Start Address (USBRXFIFOADD), offset 0x066

OTG A / Host **USBTXFIFOADD** and **USBRXFIFOADD** are 16-bit registers that control the start address of the selected transmit and receive endpoint FIFOs.

USB Transmit FIFO Start Address (USBTXFIFOADD)

OTG B / Device Base 0x4005.0000 Offset 0x064 Type R/W, reset 0x0000



Bit/Field	Name	Туре	Reset	Description
15:9	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
8:0	ADDR	R/W	0x00	Transmit/Receive Start Address
				Start address of the endpoint FIFO.

Value	Start Address
0x0	0
0x1	8
0x2	16
0x3	24
0x4	32
0x5	40
0x6	48
0x7	56
8x0	64
0x1FF	4095

## Register 33: USB Connect Timing (USBCONTIM), offset 0x07A

OTG A /

This 8-bit configuration register specifies connection and negotiation delays.

Host

USB Connect Timing (USBCONTIM)

Base 0x4005.0000 Offset 0x07A Type R/W, reset 0x5C

OTG B / Device

	7	6	5	4	3	2	1	0
		WTO	CON		WTID			
Type	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W
Donot	0	4	0	4	4	4	0	0

Bit/Field	Name	Туре	Reset	Description
7:4	WTCON	R/W	0x5	Connect Wait
				This field configures the wait required to allow for the user's connect/disconnect filter, in units of 533.3 ns. The default corresponds to 2.667 $\mu s$ .
3:0	WTID	R/W	0xC	Wait ID  This field configures the delay required from the enable of the ID

This field configures the delay required from the enable of the ID detection to when the ID value is valid, in units of 4.369 ms. The default corresponds to 52.43 ms.


# Register 34: USB OTG VBUS Pulse Timing (USBVPLEN), offset 0x07B

OTG

This 8-bit configuration register specifies the duration of the VBUS pulsing charge.

USB OTG VBUS Pulse Timing (USBVPLEN)

Base 0x4005.0000 Offset 0x07B Type R/W, reset 0x3C



Bit/Field	Name	Type	Reset	Description
7:0	VPLEN	R/W	0x3C	VBUS Pulse Length

This field configures the duration of the VBUS pulsing charge in units of 546.1  $\mu s$  . The default corresponds to 32.77 ms.

# Register 35: USB Full-Speed Last Transaction to End of Frame Timing (USBFSEOF), offset 0x07D


OTG A /

This 8-bit configuration register specifies the minimum time gap allowed between the start of the last transaction and the EOF for full-speed transactions.

USB Full-Speed Last Transaction to End of Frame Timing (USBFSEOF)

OTG B /
Device

Base 0x4005.0000 Offset 0x07D Type R/W, reset 0x77



Bit/Field Name Type Reset Description

7:0 FSEOFG R/W 0x77 Full-Speed End-of-Frame Gap

This field is used during full-speed transactions to configure the gap between the last transaction and the End-of-Frame (EOF), in units of 533.3 ns. The default corresponds to 63.46  $\mu s.$ 

# Register 36: USB Low-Speed Last Transaction to End of Frame Timing (USBLSEOF), offset 0x07E


OTG A /

This 8-bit configuration register specifies the minimum time gap that is to be allowed between the start of the last transaction and the EOF for low-speed transactions.

USB Low-Speed Last Transaction to End of Frame Timing (USBLSEOF)

OTG B /
Device

Base 0x4005.0000 Offset 0x07E Type R/W, reset 0x72



Bit/Field Name Type Reset Description

7:0 LSEOFG R/W 0x72 Low-Speed End-of-Frame Gap

This field is used during low-speed transactions to set the gap between the last transaction and the End-of-Frame (EOF), in units of 1.067  $\mu$ s. The default corresponds to 121.6  $\mu$ s.

Register 37: USB Transmit Functional Address Endpoint 0 (USBTXFUNCADDR0), offset 0x080

Register 38: USB Transmit Functional Address Endpoint 1 (USBTXFUNCADDR1), offset 0x088

Register 39: USB Transmit Functional Address Endpoint 2 (USBTXFUNCADDR2), offset 0x090

Register 40: USB Transmit Functional Address Endpoint 3 (USBTXFUNCADDR3), offset 0x098

Register 41: USB Transmit Functional Address Endpoint 4 (USBTXFUNCADDR4), offset 0x0A0

Register 42: USB Transmit Functional Address Endpoint 5 (USBTXFUNCADDR5), offset 0x0A8

Register 43: USB Transmit Functional Address Endpoint 6 (USBTXFUNCADDR6), offset 0x0B0

Register 44: USB Transmit Functional Address Endpoint 7 (USBTXFUNCADDR7), offset 0x0B8

Register 45: USB Transmit Functional Address Endpoint 8 (USBTXFUNCADDR8), offset 0x0C0

Register 46: USB Transmit Functional Address Endpoint 9 (USBTXFUNCADDR9), offset 0x0C8

Register 47: USB Transmit Functional Address Endpoint 10 (USBTXFUNCADDR10), offset 0x0D0

Register 48: USB Transmit Functional Address Endpoint 11 (USBTXFUNCADDR11), offset 0x0D8

Register 49: USB Transmit Functional Address Endpoint 12 (USBTXFUNCADDR12), offset 0x0E0

Register 50: USB Transmit Functional Address Endpoint 13 (USBTXFUNCADDR13), offset 0x0E8

Register 51: USB Transmit Functional Address Endpoint 14 (USBTXFUNCADDR14), offset 0x0F0


Register 52: USB Transmit Functional Address Endpoint 15 (USBTXFUNCADDR15), offset 0x0F8

OTG A / Host **USBTXFUNCADDRn** is an 8-bit read/write register that records the address of the target function to be accessed through the associated endpoint (EPn). **USBTXFUNCADDRn** must be defined for each transmit endpoint that is used.

Note: USBTXFUNCADDR0 is used for both receive and transmit for endpoint 0.

### USB Transmit Functional Address Endpoint 0 (USBTXFUNCADDR0)

Base 0x4005.0000 Offset 0x080 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	ADDR	R/W	0x00	Device Address Specifies the USB bus address for the target Device.

Register 53: USB Transmit Hub Address Endpoint 0 (USBTXHUBADDR0), offset 0x082

Register 54: USB Transmit Hub Address Endpoint 1 (USBTXHUBADDR1), offset 0x08A

Register 55: USB Transmit Hub Address Endpoint 2 (USBTXHUBADDR2), offset 0x092

Register 56: USB Transmit Hub Address Endpoint 3 (USBTXHUBADDR3), offset 0x09A

Register 57: USB Transmit Hub Address Endpoint 4 (USBTXHUBADDR4), offset 0x0A2

Register 58: USB Transmit Hub Address Endpoint 5 (USBTXHUBADDR5), offset 0x0AA

Register 59: USB Transmit Hub Address Endpoint 6 (USBTXHUBADDR6), offset 0x0B2

Register 60: USB Transmit Hub Address Endpoint 7 (USBTXHUBADDR7), offset 0x0BA

Register 61: USB Transmit Hub Address Endpoint 8 (USBTXHUBADDR8), offset 0x0C2

Register 62: USB Transmit Hub Address Endpoint 9 (USBTXHUBADDR9), offset 0x0CA

Register 63: USB Transmit Hub Address Endpoint 10 (USBTXHUBADDR10), offset 0x0D2

Register 64: USB Transmit Hub Address Endpoint 11 (USBTXHUBADDR11), offset 0x0DA

Register 65: USB Transmit Hub Address Endpoint 12 (USBTXHUBADDR12), offset 0x0E2

Register 66: USB Transmit Hub Address Endpoint 13 (USBTXHUBADDR13), offset 0x0EA

Register 67: USB Transmit Hub Address Endpoint 14 (USBTXHUBADDR14), offset 0x0F2

Register 68: USB Transmit Hub Address Endpoint 15 (USBTXHUBADDR15), offset 0x0FA


OTG A /

**USBTXHUBADDRn** is an 8-bit read/write register that, like **USBTXHUBPORTn**, only must be written when a USB Device is connected to transmit endpoint  $\mathtt{EPn}$  via a USB 2.0 hub. This register records the address of the USB 2.0 hub through which the target associated with the endpoint is accessed.

Note: USBTXHUBADDR0 is used for both receive and transmit for endpoint 0.

# USB Transmit Hub Address Endpoint 0 (USBTXHUBADDR0)

Base 0x4005.0000 Offset 0x082 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	ADDR	R/W	0x00	Hub Address This field specifies the USB bus address for the USB 2.0 hub.

Register 69: USB Transmit Hub Port Endpoint 0 (USBTXHUBPORT0), offset 0x083

Register 70: USB Transmit Hub Port Endpoint 1 (USBTXHUBPORT1), offset 0x08B

Register 71: USB Transmit Hub Port Endpoint 2 (USBTXHUBPORT2), offset 0x093

Register 72: USB Transmit Hub Port Endpoint 3 (USBTXHUBPORT3), offset 0x09B

Register 73: USB Transmit Hub Port Endpoint 4 (USBTXHUBPORT4), offset 0x0A3

Register 74: USB Transmit Hub Port Endpoint 5 (USBTXHUBPORT5), offset 0x0AB

Register 75: USB Transmit Hub Port Endpoint 6 (USBTXHUBPORT6), offset 0x0B3

Register 76: USB Transmit Hub Port Endpoint 7 (USBTXHUBPORT7), offset 0x0BB

Register 77: USB Transmit Hub Port Endpoint 8 (USBTXHUBPORT8), offset 0x0C3

Register 78: USB Transmit Hub Port Endpoint 9 (USBTXHUBPORT9), offset 0x0CB

Register 79: USB Transmit Hub Port Endpoint 10 (USBTXHUBPORT10), offset 0x0D3

Register 80: USB Transmit Hub Port Endpoint 11 (USBTXHUBPORT11), offset 0x0DB

Register 81: USB Transmit Hub Port Endpoint 12 (USBTXHUBPORT12), offset 0x0E3

Register 82: USB Transmit Hub Port Endpoint 13 (USBTXHUBPORT13), offset 0x0EB

Register 83: USB Transmit Hub Port Endpoint 14 (USBTXHUBPORT14), offset 0x0F3


Register 84: USB Transmit Hub Port Endpoint 15 (USBTXHUBPORT15), offset 0x0FB

OTG A / Host **USBTXHUBPORTn** is an 8-bit read/write register that, like **USBTXHUBADDRn**, only must be written when a full- or low-speed Device is connected to transmit endpoint EPn via a USB 2.0 hub. This register records the port of the USB 2.0 hub through which the target associated with the endpoint is accessed.

Note: USBTXHUBPORT0 is used for both receive and transmit for endpoint 0.

# USB Transmit Hub Port Endpoint 0 (USBTXHUBPORT0)

Base 0x4005.0000 Offset 0x083 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	PORT	R/W	0x00	Hub Port This field specifies the USB hub port number.

Register 85: USB Receive Functional Address Endpoint 1 (USBRXFUNCADDR1), offset 0x08C

Register 86: USB Receive Functional Address Endpoint 2 (USBRXFUNCADDR2), offset 0x094

Register 87: USB Receive Functional Address Endpoint 3 (USBRXFUNCADDR3), offset 0x09C

Register 88: USB Receive Functional Address Endpoint 4 (USBRXFUNCADDR4), offset 0x0A4

Register 89: USB Receive Functional Address Endpoint 5 (USBRXFUNCADDR5), offset 0x0AC

Register 90: USB Receive Functional Address Endpoint 6 (USBRXFUNCADDR6), offset 0x0B4

Register 91: USB Receive Functional Address Endpoint 7 (USBRXFUNCADDR7), offset 0x0BC

Register 92: USB Receive Functional Address Endpoint 8 (USBRXFUNCADDR8), offset 0x0C4

Register 93: USB Receive Functional Address Endpoint 9 (USBRXFUNCADDR9), offset 0x0CC

Register 94: USB Receive Functional Address Endpoint 10 (USBRXFUNCADDR10), offset 0x0D4

Register 95: USB Receive Functional Address Endpoint 11 (USBRXFUNCADDR11), offset 0x0DC

Register 96: USB Receive Functional Address Endpoint 12 (USBRXFUNCADDR12), offset 0x0E4

Register 97: USB Receive Functional Address Endpoint 13 (USBRXFUNCADDR13), offset 0x0EC

Register 98: USB Receive Functional Address Endpoint 14 (USBRXFUNCADDR14), offset 0x0F4

Register 99: USB Receive Functional Address Endpoint 15 (USBRXFUNCADDR15), offset 0x0FC


OTG A /

**USBRXFUNCADDRn** is an 8-bit read/write register that records the address of the target function accessed through the associated endpoint (EPn). **USBRXFUNCADDRn** must be defined for each receive endpoint that is used.

**Note: USBTXFUNCADDR0** is used for both receive and transmit for endpoint 0.

# USB Receive Functional Address Endpoint 1 (USBRXFUNCADDR1)

Base 0x4005.0000 Offset 0x08C Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	ADDR	R/W	0x00	Device Address

This field specifies the USB bus address for the target Device.

Register 100: USB Receive Hub Address Endpoint 1 (USBRXHUBADDR1), offset 0x08E

Register 101: USB Receive Hub Address Endpoint 2 (USBRXHUBADDR2), offset 0x096

Register 102: USB Receive Hub Address Endpoint 3 (USBRXHUBADDR3), offset 0x09E

Register 103: USB Receive Hub Address Endpoint 4 (USBRXHUBADDR4), offset 0x0A6

Register 104: USB Receive Hub Address Endpoint 5 (USBRXHUBADDR5), offset 0x0AE

Register 105: USB Receive Hub Address Endpoint 6 (USBRXHUBADDR6), offset 0x0B6

Register 106: USB Receive Hub Address Endpoint 7 (USBRXHUBADDR7), offset 0x0BE

Register 107: USB Receive Hub Address Endpoint 8 (USBRXHUBADDR8), offset 0x0C6

Register 108: USB Receive Hub Address Endpoint 9 (USBRXHUBADDR9), offset 0x0CE

Register 109: USB Receive Hub Address Endpoint 10 (USBRXHUBADDR10), offset 0x0D6

Register 110: USB Receive Hub Address Endpoint 11 (USBRXHUBADDR11), offset 0x0DE

Register 111: USB Receive Hub Address Endpoint 12 (USBRXHUBADDR12), offset 0x0E6

Register 112: USB Receive Hub Address Endpoint 13 (USBRXHUBADDR13), offset 0x0EE

Register 113: USB Receive Hub Address Endpoint 14 (USBRXHUBADDR14), offset 0x0F6


Register 114: USB Receive Hub Address Endpoint 15 (USBRXHUBADDR15), offset 0x0FE

OTG A / Host **USBRXHUBADDRn** is an 8-bit read/write register that, like **USBRXHUBPORTn**, only must be written when a full- or low-speed Device is connected to receive endpoint EPn via a USB 2.0 hub. This register records the address of the USB 2.0 hub through which the target associated with the endpoint is accessed.

Note: USBTXHUBADDR0 is used for both receive and transmit for endpoint 0.

# USB Receive Hub Address Endpoint 1 (USBRXHUBADDR1)

Base 0x4005.0000 Offset 0x08E Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	ADDR	R/W	0x00	Hub Address
				This field specifies the USB bus address for the USB 2.0 hub.

Register 115: USB Receive Hub Port Endpoint 1 (USBRXHUBPORT1), offset 0x08F

Register 116: USB Receive Hub Port Endpoint 2 (USBRXHUBPORT2), offset 0x097

Register 117: USB Receive Hub Port Endpoint 3 (USBRXHUBPORT3), offset 0x09F

Register 118: USB Receive Hub Port Endpoint 4 (USBRXHUBPORT4), offset 0x0A7

Register 119: USB Receive Hub Port Endpoint 5 (USBRXHUBPORT5), offset 0x0AF

Register 120: USB Receive Hub Port Endpoint 6 (USBRXHUBPORT6), offset 0x0B7

Register 121: USB Receive Hub Port Endpoint 7 (USBRXHUBPORT7), offset 0x0BF

Register 122: USB Receive Hub Port Endpoint 8 (USBRXHUBPORT8), offset 0x0C7

Register 123: USB Receive Hub Port Endpoint 9 (USBRXHUBPORT9), offset 0x0CF

Register 124: USB Receive Hub Port Endpoint 10 (USBRXHUBPORT10), offset 0x0D7

Register 125: USB Receive Hub Port Endpoint 11 (USBRXHUBPORT11), offset 0x0DF

Register 126: USB Receive Hub Port Endpoint 12 (USBRXHUBPORT12), offset 0x0E7

Register 127: USB Receive Hub Port Endpoint 13 (USBRXHUBPORT13), offset 0x0EF

Register 128: USB Receive Hub Port Endpoint 14 (USBRXHUBPORT14), offset 0x0F7

Register 129: USB Receive Hub Port Endpoint 15 (USBRXHUBPORT15), offset 0x0FF




**USBRXHUBPORTn** is an 8-bit read/write register that, like **USBRXHUBADDRn**, only must be written when a full- or low-speed Device is connected to receive endpoint EPn via a USB 2.0 hub. This register records the port of the USB 2.0 hub through which the target associated with the endpoint is accessed.

Note: USBTXHUBPORT0 is used for both receive and transmit for endpoint 0.

# USB Receive Hub Port Endpoint 1 (USBRXHUBPORT1)

Base 0x4005.0000 Offset 0x08F Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	PORT	R/W	0x00	Hub Port This field specifies the USB hub port number.

Register 130: USB Maximum Transmit Data Endpoint 1 (USBTXMAXP1), offset 0x110

Register 131: USB Maximum Transmit Data Endpoint 2 (USBTXMAXP2), offset 0x120

Register 132: USB Maximum Transmit Data Endpoint 3 (USBTXMAXP3), offset 0x130

Register 133: USB Maximum Transmit Data Endpoint 4 (USBTXMAXP4), offset 0x140

Register 134: USB Maximum Transmit Data Endpoint 5 (USBTXMAXP5), offset 0x150

Register 135: USB Maximum Transmit Data Endpoint 6 (USBTXMAXP6), offset 0x160

Register 136: USB Maximum Transmit Data Endpoint 7 (USBTXMAXP7), offset 0x170

Register 137: USB Maximum Transmit Data Endpoint 8 (USBTXMAXP8), offset 0x180

Register 138: USB Maximum Transmit Data Endpoint 9 (USBTXMAXP9), offset 0x190

Register 139: USB Maximum Transmit Data Endpoint 10 (USBTXMAXP10), offset 0x1A0

Register 140: USB Maximum Transmit Data Endpoint 11 (USBTXMAXP11), offset 0x1B0

Register 141: USB Maximum Transmit Data Endpoint 12 (USBTXMAXP12), offset 0x1C0

Register 142: USB Maximum Transmit Data Endpoint 13 (USBTXMAXP13), offset 0x1D0

Register 143: USB Maximum Transmit Data Endpoint 14 (USBTXMAXP14), offset 0x1E0

Register 144: USB Maximum Transmit Data Endpoint 15 (USBTXMAXP15), offset 0x1F0

OTG A /

The **USBTXMAXPn** 16-bit register defines the maximum amount of data that can be transferred through the transmit endpoint in a single operation.

OTG B / Device Bits 10:0 define (in bytes) the maximum payload transmitted in a single transaction. The value set can be up to 1024 bytes but is subject to the constraints placed by the *USB Specification* on packet sizes for bulk, interrupt and isochronous transfers in full-speed operation.


The total amount of data represented by the value written to this register must not exceed the FIFO size for the transmit endpoint, and must not exceed half the FIFO size if double-buffering is required.

If this register is changed after packets have been sent from the endpoint, the transmit endpoint FIFO must be completely flushed (using the FLUSH bit in **USBTXCSRLn**) after writing the new value to this register.

**Note: USBTXMAXPn** must be set to an even number of bytes for proper interrupt generation in µDMA Basic Mode.

USB Maximum Transmit Data Endpoint 1 (USBTXMAXP1)

Base 0x4005.0000 Offset 0x110 Type R/W, reset 0x0000



Bit/Field	Name	Type	Reset	Description
15:11	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10:0	MAXLOAD	R/W	0x000	Maximum Payload

This field specifies the maximum payload in bytes per transaction.

# Register 145: USB Control and Status Endpoint 0 Low (USBCSRL0), offset 0x102

OTG A /

**USBCSRL0** is an 8-bit register that provides control and status bits for endpoint 0.

OTG B / Device

## OTG A / Host Mode

USB Control and Status Endpoint 0 Low (USBCSRL0)

Base 0x4005.0000 Offset 0x102 Type W1C, reset 0x00

	7	6	5	4	3	2	1	0	
	NAKTO	STATUS	REQPKT	ERROR	SETUP	STALLED	TXRDY	RXRDY	l
Type	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	
Reset	0	0	0	0	0	0	0	0	

Bit/Field	Name	Туре	Reset	Description
7	NAKTO	R/W	0	NAK Timeout
				Value Description
				0 No timeout.
				Indicates that endpoint 0 is halted following the receipt of NAK responses for longer than the time set by the USBNAKLMT register.
				Software must clear this bit to allow the endpoint to continue.
6	STATUS	R/W	0	STATUS Packet
				Value Description
				0 No transaction.
				1 Initiates a STATUS stage transaction. This bit must be set at the same time as the TXRDY or REQPKT bit is set.
				Setting this bit ensures that the DT bit is set in the <b>USBCSRH0</b> register so that a DATA1 packet is used for the STATUS stage transaction.
				This bit is automatically cleared when the STATUS stage is over.
5	REQPKT	R/W	0	Request Packet
				Value Description
				0 No request.
				1 Requests an IN transaction.
				This bit is cleared when the RXRDY bit is set.


Bit/Field	Name	Туре	Reset	Description
4	ERROR	R/W	0	Error
				Value Description
				0 No error.
				Three attempts have been made to perform a transaction with no response from the peripheral. The EPO bit in the <b>USBTXIS</b> register is also set in this situation.
				Software must clear this bit.
3	SETUP	R/W	0	Setup Packet
				Value Description
				0 Sends an OUT token.
				Sends a SETUP token instead of an OUT token for the transaction. This bit should be set at the same time as the TXRDY bit is set.
				Setting this bit always clears the ${\tt DT}$ bit in the $\textbf{USBCSRH0}$ register to send a DATA0 packet.
2	STALLED	R/W	0	Endpoint Stalled
				Value Description
				0 No handshake has been received.
				1 A STALL handshake has been received.
				Software must clear this bit.
1	TXRDY	R/W	0	Transmit Packet Ready
				Value Description
				0 No transmit packet is ready.
				Software sets this bit after loading a data packet into the TX FIFO. The EP0 bit in the <b>USBTXIS</b> register is also set in this situation.
				If both the ${\tt TXRDY}$ and SETUP bits are set, a setup packet is sent. If just ${\tt TXRDY}$ is set, an OUT packet is sent.
				This bit is cleared automatically when the data packet has been transmitted.
0	RXRDY	R/W	0	Receive Packet Ready
				Value Description
				0 No received packet has been received.
				Indicates that a data packet has been received in the RX FIFO. The EP0 bit in the <b>USBTXIS</b> register is also set in this situation.

Software must clear this bit after the packet has been read from the FIFO to acknowledge that the data has been read from the FIFO.

## OTG B / Device Mode

USB Control and Status Endpoint 0 Low (USBCSRL0)

Base 0x4005.0000 Offset 0x102 Type W1C, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	SETENDC	W1C	0	Setup End Clear
				Writing a 1 to this bit clears the SETEND bit.
6	RXRDYC	W1C	0	RXRDY Clear
				Writing a 1 to this bit clears the RXRDY bit.
5	STALL	R/W	0	Send Stall
				Value Description
				0 No effect.
				1 Terminates the current transaction and transmits the STALL handshake.
				This bit is cleared automatically after the STALL handshake is transmitted.
4	SETEND	RO	0	Setup End
				Value Description
				O A control transaction has not ended or ended after the DATAEND bit was set.
				A control transaction has ended before the DATAEND bit has been set. The EPO bit in the <b>USBTXIS</b> register is also set in this situation.
				This bit is cleared by writing a 1 to the SETENDC bit.
3	DATAEND	R/W	0	Data End
				Value Description
				0 No effect.
				1 Set this bit in the following situations:
				■ When setting TXRDY for the last data packet

This bit is cleared automatically.

When clearing RXRDY after unloading the last data

■ When setting TXRDY for a zero-length data packet

Bit/Field	Name	Туре	Reset	Description
2	STALLED	R/W	0	Endpoint Stalled
				Value Description  O A STALL handshake has not been transmitted.  1 A STALL handshake has been transmitted.  Software must clear this bit.
1	TXRDY	R/W	0	Transmit Packet Ready
				Value Description
				0 No transmit packet is ready.
				Software sets this bit after loading an IN data packet into the TX FIFO. The EPO bit in the <b>USBTXIS</b> register is also set in this situation.
				This bit is cleared automatically when the data packet has been transmitted.
0	RXRDY	RO	0	Receive Packet Ready
				Value Description
				0 No data packet has been received.
				A data packet has been received. The EP0 bit in the <b>USBTXIS</b> register is also set in this situation.

This bit is cleared by writing a 1 to the  ${\tt RXRDYC}$  bit.

# Register 146: USB Control and Status Endpoint 0 High (USBCSRH0), offset 0x103

OTG A /


**USBSR0H** is an 8-bit register that provides control and status bits for endpoint 0.



## OTG A / Host Mode

USB Control and Status Endpoint 0 High (USBCSRH0)

Base 0x4005.0000 Offset 0x103 Type W1C, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7:3	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	DTWE	R/W	0	Data Toggle Write Enable
				<ul> <li>Value Description</li> <li>The DT bit cannot be written.</li> <li>Enables the current state of the endpoint 0 data toggle to be written (see DT bit).</li> </ul>
				This bit is automatically cleared once the new value is written.
1	DT	R/W	0	Data Toggle
				When read, this bit indicates the current state of the endpoint 0 data toggle.

If DTWE is set, this bit may be written with the required setting of the data toggle. If DTWE is Low, this bit cannot be written. Care should be taken when writing to this bit as it should only be changed to RESET USB endpoint 0.

Bit/Field	Name	Type	Reset	Description
0	FLUSH	R/W	0	Flush FIFO

Value Description

- 0 No effect.
- Flushes the next packet to be transmitted/read from the endpoint 0 FIFO. The FIFO pointer is reset and the TXRDY/RXRDY bit is cleared.


This bit is automatically cleared after the flush is performed.

Important: This bit should only be set when TXRDY is clear and RXRDY is set. At other times, it may cause data to be corrupted.

### OTG B / Device Mode

USB Control and Status Endpoint 0 High (USBCSRH0)

Base 0x4005.0000 Offset 0x103 Type W1C, reset 0x00



Bit/Field	Name	Type	Reset	Description
7:1	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	FLUSH	R/W	0	Flush FIFO

Value Description

- 0 No effect.
- Flushes the next packet to be transmitted/read from the endpoint 0 FIFO. The FIFO pointer is reset and the TXRDY/RXRDY bit is cleared.

This bit is automatically cleared after the flush is performed.

**Important:** This bit should only be set when TXRDY is clear and RXRDY is set. At other times, it may cause data to be corrupted.

# Register 147: USB Receive Byte Count Endpoint 0 (USBCOUNT0), offset 0x108




**USBCOUNT0** is an 8-bit read-only register that indicates the number of received data bytes in the endpoint 0 FIFO. The value returned changes as the contents of the FIFO change and is only valid while the RXRDY bit is set.

OTG B /
Device

USB Receive Byte Count Endpoint 0 (USBCOUNT0)

Base 0x4005.0000 Offset 0x108 Type RO, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6:0	COUNT	RO	0x00	FIFO Count

 ${\tt COUNT}$  is a read-only value that indicates the number of received data bytes in the endpoint 0 FIFO.

# Register 148: USB Type Endpoint 0 (USBTYPE0), offset 0x10A




This is an 8-bit register that must be written with the operating speed of the targeted Device being communicated with using endpoint 0.

USB Type Endpoint 0 (USBTYPE0)

Base 0x4005.0000

Offset 0x10A Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description		
7:6	SPEED	R/W	0x0	Operating Speed		
				This field specifies the operating speed of the target Device. If selecthe target is assumed to have the same connection speed as the Loontroller.		
				Value Descrip	otion	
				0x0 - 0x1 Reserve	ed	
				0x2 Full		
				0x3 Low		
5:0	reserved	RO	0x0		ot rely on the value of a reserved bit. To provide uture products, the value of a reserved bit should be	

preserved across a read-modify-write operation.

# Register 149: USB NAK Limit (USBNAKLMT), offset 0x10B




**USBNAKLMT** is an 8-bit register that sets the number of frames after which endpoint 0 should time out on receiving a stream of NAK responses. (Equivalent settings for other endpoints can be made through their **USBTXINTERVALn** and **USBRXINTERVALn** registers.)

The number of frames selected is  $2^{(m-1)}$  (where m is the value set in the register, with valid values of 2–16). If the Host receives NAK responses from the target for more frames than the number represented by the limit set in this register, the endpoint is halted.

**Note:** A value of 0 or 1 disables the NAK timeout function.

### USB NAK Limit (USBNAKLMT)

Base 0x4005.0000 Offset 0x10B Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7:5	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
4:0	NAKLMT	R/W	0x0	EP0 NAK Limit

This field specifies the number of frames after receiving a stream of NAK responses.

Register 150: USB Transmit Control and Status Endpoint 1 Low (USBTXCSRL1), offset 0x112

Register 151: USB Transmit Control and Status Endpoint 2 Low (USBTXCSRL2), offset 0x122

Register 152: USB Transmit Control and Status Endpoint 3 Low (USBTXCSRL3), offset 0x132

Register 153: USB Transmit Control and Status Endpoint 4 Low (USBTXCSRL4), offset 0x142

Register 154: USB Transmit Control and Status Endpoint 5 Low (USBTXCSRL5), offset 0x152

Register 155: USB Transmit Control and Status Endpoint 6 Low (USBTXCSRL6), offset 0x162

Register 156: USB Transmit Control and Status Endpoint 7 Low (USBTXCSRL7), offset 0x172

Register 157: USB Transmit Control and Status Endpoint 8 Low (USBTXCSRL8), offset 0x182

Register 158: USB Transmit Control and Status Endpoint 9 Low (USBTXCSRL9), offset 0x192

Register 159: USB Transmit Control and Status Endpoint 10 Low (USBTXCSRL10), offset 0x1A2

Register 160: USB Transmit Control and Status Endpoint 11 Low (USBTXCSRL11), offset 0x1B2

Register 161: USB Transmit Control and Status Endpoint 12 Low (USBTXCSRL12), offset 0x1C2

Register 162: USB Transmit Control and Status Endpoint 13 Low (USBTXCSRL13), offset 0x1D2

Register 163: USB Transmit Control and Status Endpoint 14 Low (USBTXCSRL14), offset 0x1E2

Register 164: USB Transmit Control and Status Endpoint 15 Low (USBTXCSRL15), offset 0x1F2


OTG A / Host **USBTXCSRLn** is an 8-bit register that provides control and status bits for transfers through the currently selected transmit endpoint.

OTG B /
Device

## OTG A / Host Mode

USB Transmit Control and Status Endpoint 1 Low (USBTXCSRL1)

Base 0x4005.0000 Offset 0x112 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	NAKTO	R/W	0	NAK Timeout
				Value Description
				0 No timeout.
				Bulk endpoints only: Indicates that the transmit endpoint is halted following the receipt of NAK responses for longer than the time set by the NAKLMT field in the <b>USBTXINTERVALn</b> register. Software must clear this bit to allow the endpoint to continue.
6	CLRDT	R/W	0	Clear Data Toggle
				Writing a 1 to this bit clears the DT bit in the <b>USBTXCSRHn</b> register.
5	STALLED	R/W	0	Endpoint Stalled
				Value Description
				0 A STALL handshake has not been received.
				Indicates that a STALL handshake has been received. When this bit is set, any μDMA request that is in progress is stopped, the FIFO is completely flushed, and the TXRDY bit is cleared.
				Software must clear this bit.
4	SETUP	R/W	0	Setup Packet
				Value Description
				No SETLIP token is sent.

0 No SETUP token is sent.

Sends a SETUP token instead of an OUT token for the transaction. This bit should be set at the same time as the TXRDY bit is set.

**Note:** Setting this bit also clears the DT bit in the **USBTXCSRHn** register.


Bit/Field	Name	Туре	Reset	Description		
3	FLUSH	R/W	0	Flush FIFO		
				Value Description  No effect.  Flushes the latest packet from the endpoint transmit FIFO. The FIFO pointer is reset and the TXRDY bit is cleared. The EPn bit in the USBTXIS register is also set in this situation.  This bit may be set simultaneously with the TXRDY bit to abort the packet that is currently being loaded into the FIFO. Note that if the FIFO is double-buffered, FLUSH may have to be set twice to completely clear the FIFO.		
				Important: This bit should only be set when the TXRDY bit is clear. At other times, it may cause data to be corrupted.		
2	ERROR	R/W	0	Error		
				Value Description		
				0 No error.		
				Three attempts have been made to send a packet and no handshake packet has been received. The TXRDY bit is cleared, the EPn bit in the <b>USBTXIS</b> register is set, and the FIFO is completely flushed in this situation.		
				Software must clear this bit.		
				<b>Note:</b> This is valid only when the endpoint is operating in Bulk or Interrupt mode.		
1	FIFONE	R/W	0	FIFO Not Empty		
				Value Description		
				0 The FIFO is empty.		
				1 At least one packet is in the transmit FIFO.		
0	TXRDY	R/W	0	Transmit Packet Ready		
				Value Description		
				0 No transmit packet is ready.		
				1 Software sets this bit after loading a data packet into the TX FIFO.		

This bit is cleared automatically when a data packet has been transmitted. The  $\mathtt{EPn}$  bit in the **USBTXIS** register is also set at this point.  $\mathtt{TXRDY}$  is also automatically cleared prior to loading a second packet into a double-buffered FIFO.

### **OTG B / Device Mode**

USB Transmit Control and Status Endpoint 1 Low (USBTXCSRL1)

Base 0x4005.0000 Offset 0x112 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
6	CLRDT	R/W	0	Clear Data Toggle Writing a 1 to this bit clears the DT bit in the <b>USBTXCSRHn</b> register.
5	STALLED	R/W	0	Endpoint Stalled
				Value Description
				0 A STALL handshake has not been transmitted.
				1 A STALL handshake has been transmitted. The FIFO is flushed and the TXRDY bit is cleared.
				Software must clear this bit.
4	STALL	R/W	0	Send STALL
				Value Description
				0 No effect.
				1 Issues a STALL handshake to an IN token.
				Software clears this bit to terminate the STALL condition.
				<b>Note:</b> This bit has no effect in isochronous transfers.
3	FLUSH	R/W	0	Flush FIFO
				Value Description
				0 No effect.

1 Flushes the latest packet from the endpoint transmit FIFO. The FIFO pointer is reset and the TXRDY bit is cleared. The EPn bit in the **USBTXIS** register is also set in this situation.

This bit may be set simultaneously with the <code>TXRDY</code> bit to abort the packet that is currently being loaded into the FIFO. Note that if the FIFO is double-buffered, <code>FLUSH</code> may have to be set twice to completely clear the FIFO.

**Important:** This bit should only be set when the TXRDY bit is clear. At other times, it may cause data to be corrupted.

Bit/Field	Name	Туре	Reset	Description
2	UNDRN	R/W	0	Underrun
				Value Description  0 No underrun.  1 An IN token has been received when TXRDY is not set.  Software must clear this bit.
1	FIFONE	R/W	0	FIFO Not Empty  Value Description  0 The FIFO is empty.  1 At least one packet is in the transmit FIFO.
0	TXRDY	R/W	0	Transmit Packet Ready  Value Description  0 No transmit packet is ready.  1 Software sets this bit after loading a data packet into the TX FIFO.

This bit is cleared automatically when a data packet has been transmitted. The  $\mathtt{EPn}$  bit in the **USBTXIS** register is also set at this point.  $\mathtt{TXRDY}$  is also automatically cleared prior to loading a second packet into a double-buffered FIFO.

Register 165: USB Transmit Control and Status Endpoint 1 High (USBTXCSRH1), offset 0x113

Register 166: USB Transmit Control and Status Endpoint 2 High (USBTXCSRH2), offset 0x123

Register 167: USB Transmit Control and Status Endpoint 3 High (USBTXCSRH3), offset 0x133

Register 168: USB Transmit Control and Status Endpoint 4 High (USBTXCSRH4), offset 0x143

Register 169: USB Transmit Control and Status Endpoint 5 High (USBTXCSRH5), offset 0x153

Register 170: USB Transmit Control and Status Endpoint 6 High (USBTXCSRH6), offset 0x163

Register 171: USB Transmit Control and Status Endpoint 7 High (USBTXCSRH7), offset 0x173

Register 172: USB Transmit Control and Status Endpoint 8 High (USBTXCSRH8), offset 0x183

Register 173: USB Transmit Control and Status Endpoint 9 High (USBTXCSRH9), offset 0x193

Register 174: USB Transmit Control and Status Endpoint 10 High (USBTXCSRH10), offset 0x1A3

Register 175: USB Transmit Control and Status Endpoint 11 High (USBTXCSRH11), offset 0x1B3

Register 176: USB Transmit Control and Status Endpoint 12 High (USBTXCSRH12), offset 0x1C3

Register 177: USB Transmit Control and Status Endpoint 13 High (USBTXCSRH13), offset 0x1D3

Register 178: USB Transmit Control and Status Endpoint 14 High (USBTXCSRH14), offset 0x1E3

Register 179: USB Transmit Control and Status Endpoint 15 High (USBTXCSRH15), offset 0x1F3


OTG A / Host **USBTXCSRHn** is an 8-bit register that provides additional control for transfers through the currently selected transmit endpoint.

OTG B /
Device

## OTG A / Host Mode

USB Transmit Control and Status Endpoint 1 High (USBTXCSRH1)

Base 0x4005.0000 Offset 0x113 Type R/W, reset 0x00



		_		
Bit/Field	Name	Type	Reset	Description
7	AUTOSET	R/W	0	Auto Set
				Value Description
				The TXRDY bit must be set manually.
				Enables the TXRDY bit to be automatically set when data of the maximum packet size (value in <b>USBTXMAXPn</b> ) is loaded into the transmit FIFO. If a packet of less than the maximum packet size is loaded, then the TXRDY bit must be set manually.
6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	MODE	R/W	0	Mode
				Value Description
				0 Enables the endpoint direction as RX.
				1 Enables the endpoint direction as TX.
				<b>Note:</b> This bit only has an effect when the same endpoint FIFO is used for both transmit and receive transactions.
4	DMAEN	R/W	0	DMA Request Enable
				Value Description
				0 Disables the μDMA request for the transmit endpoint.
				1 Enables the µDMA request for the transmit endpoint.
				Note: 3 TX and 3 /RX endpoints can be connected to the μDMA module. If this bit is set for a particular endpoint, the DMAATX, DMABTX, or DMACTX field in the USB DMA Select (USBDMASEL) register must be programmed correspondingly.
3	FDT	R/W	0	Force Data Toggle
				Value Description
				0 No effect.

endpoints.


Forces the endpoint  $\mathtt{DT}$  bit to switch and the data packet to be cleared from the FIFO, regardless of whether an ACK was received. This bit can be used by interrupt transmit endpoints that are used to communicate rate feedback for isochronous

Bit/Field	Name	Туре	Reset	Description
2	DMAMOD	R/W	0	DMA Request Mode
				Value Description
				0 An interrupt is generated after every μDMA packet transfer.
				1 An interrupt is generated only after the entire $\mu DMA$ transfer is complete.
				<b>Note:</b> This bit must not be cleared either before or in the same cycle as the above DMAEN bit is cleared.
1	DTWE	R/W	0	Data Toggle Write Enable
				Value Description
				0 The DT bit cannot be written.
				Enables the current state of the transmit endpoint data to be written (see DT bit).
				This bit is automatically cleared once the new value is written.
0	DT	R/W	0	Data Toggle
				When read, this bit indicates the current state of the transmit endpoint data toggle.
				If $\mathtt{DTWE}$ is High, this bit may be written with the required setting of the data toggle. If $\mathtt{DTWE}$ is Low, any value written to this bit is ignored. Care

## OTG B / Device Mode

USB Transmit Control and Status Endpoint 1 High (USBTXCSRH1)

Base 0x4005.0000 Offset 0x113 Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	AUTOSET	R/W	0	Auto Set

### Value Description

RESET the transmit endpoint.

- 0 The TXRDY bit must be set manually.
- 1 Enables the TXRDY bit to be automatically set when data of the maximum packet size (value in **USBTXMAXPn**) is loaded into the transmit FIFO. If a packet of less than the maximum packet size is loaded, then the TXRDY bit must be set manually.

should be taken when writing to this bit as it should only be changed to

Bit/Field	Name	Туре	Reset	Description
6	ISO	R/W	0	Isochronous Transfers
				Value Description  0 Enables the transmit endpoint for bulk or interrupt transfers.  1 Enables the transmit endpoint for isochronous transfers.
5	MODE	R/W	0	Mode
				Value Description  0 Enables the endpoint direction as RX.  1 Enables the endpoint direction as TX.  Note: This bit only has an effect where the same endpoint FIFO is
				used for both transmit and receive transactions.
4	DMAEN	R/W	0	DMA Request Enable
				Value Description
				0 Disables the μDMA request for the transmit endpoint.
				1 Enables the μDMA request for the transmit endpoint.
				Note: 3 TX and 3 RX endpoints can be connected to the μDMA module. If this bit is set for a particular endpoint, the DMAATX, DMABTX, or DMACTX field in the USB DMA Select (USBDMASEL) register must be programmed correspondingly.
3	FDT	R/W	0	Force Data Toggle
				Value Description
				0 No effect.
				Forces the endpoint DT bit to switch and the data packet to be cleared from the FIFO, regardless of whether an ACK was received. This bit can be used by interrupt transmit endpoints that are used to communicate rate feedback for isochronous endpoints.
2	DMAMOD	R/W	0	DMA Request Mode
				Value Description
				O An interrupt is generated after every µDMA packet transfer.
				<ol> <li>An interrupt is generated only after the entire μDMA transfer is complete.</li> </ol>
				<b>Note:</b> This bit must not be cleared either before or in the same cycle as the above DMAEN bit is cleared.
1:0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Register 180: USB Maximum Receive Data Endpoint 1 (USBRXMAXP1), offset 0x114

Register 181: USB Maximum Receive Data Endpoint 2 (USBRXMAXP2), offset 0x124

Register 182: USB Maximum Receive Data Endpoint 3 (USBRXMAXP3), offset 0x134

Register 183: USB Maximum Receive Data Endpoint 4 (USBRXMAXP4), offset 0x144

Register 184: USB Maximum Receive Data Endpoint 5 (USBRXMAXP5), offset 0x154

Register 185: USB Maximum Receive Data Endpoint 6 (USBRXMAXP6), offset 0x164

Register 186: USB Maximum Receive Data Endpoint 7 (USBRXMAXP7), offset 0x174

Register 187: USB Maximum Receive Data Endpoint 8 (USBRXMAXP8), offset 0x184

Register 188: USB Maximum Receive Data Endpoint 9 (USBRXMAXP9), offset 0x194

Register 189: USB Maximum Receive Data Endpoint 10 (USBRXMAXP10), offset 0x1A4

Register 190: USB Maximum Receive Data Endpoint 11 (USBRXMAXP11), offset 0x1B4

Register 191: USB Maximum Receive Data Endpoint 12 (USBRXMAXP12), offset 0x1C4

Register 192: USB Maximum Receive Data Endpoint 13 (USBRXMAXP13), offset 0x1D4

Register 193: USB Maximum Receive Data Endpoint 14 (USBRXMAXP14), offset 0x1E4

Register 194: USB Maximum Receive Data Endpoint 15 (USBRXMAXP15), offset 0x1F4

OTG A /

The **USBRXMAXPn** is a 16-bit register which defines the maximum amount of data that can be transferred through the selected receive endpoint in a single operation.

OTG B /
Device


Bits 10:0 define (in bytes) the maximum payload transmitted in a single transaction. The value set can be up to 1024 bytes but is subject to the constraints placed by the *USB Specification* on packet sizes for bulk, interrupt and isochronous transfers in full-speed operations.

The total amount of data represented by the value written to this register must not exceed the FIFO size for the receive endpoint, and must not exceed half the FIFO size if double-buffering is required.

**Note: USBRXMAXPn** must be set to an even number of bytes for proper interrupt generation in µDMA Basic mode.

USB Maximum Receive Data Endpoint 1 (USBRXMAXP1)

Base 0x4005.0000 Offset 0x114 Type R/W, reset 0x0000



Bit/Field	Name	Туре	Reset	Description
15:11	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
10:0	MAXLOAD	R/W	0x000	Maximum Payload

The maximum payload in bytes per transaction.

Register 195: USB Receive Control and Status Endpoint 1 Low (USBRXCSRL1), offset 0x116

Register 196: USB Receive Control and Status Endpoint 2 Low (USBRXCSRL2), offset 0x126

Register 197: USB Receive Control and Status Endpoint 3 Low (USBRXCSRL3), offset 0x136

Register 198: USB Receive Control and Status Endpoint 4 Low (USBRXCSRL4), offset 0x146

Register 199: USB Receive Control and Status Endpoint 5 Low (USBRXCSRL5), offset 0x156

Register 200: USB Receive Control and Status Endpoint 6 Low (USBRXCSRL6), offset 0x166

Register 201: USB Receive Control and Status Endpoint 7 Low (USBRXCSRL7), offset 0x176

Register 202: USB Receive Control and Status Endpoint 8 Low (USBRXCSRL8), offset 0x186

Register 203: USB Receive Control and Status Endpoint 9 Low (USBRXCSRL9), offset 0x196

Register 204: USB Receive Control and Status Endpoint 10 Low (USBRXCSRL10), offset 0x1A6

Register 205: USB Receive Control and Status Endpoint 11 Low (USBRXCSRL11), offset 0x1B6

Register 206: USB Receive Control and Status Endpoint 12 Low (USBRXCSRL12), offset 0x1C6

Register 207: USB Receive Control and Status Endpoint 13 Low (USBRXCSRL13), offset 0x1D6

Register 208: USB Receive Control and Status Endpoint 14 Low (USBRXCSRL14), offset 0x1E6

Register 209: USB Receive Control and Status Endpoint 15 Low (USBRXCSRL15), offset 0x1F6

OTG A /


**USBRXCSRLn** is an 8-bit register that provides control and status bits for transfers through the currently selected receive endpoint.

OTG B /

## OTG A / Host Mode

USB Receive Control and Status Endpoint 1 Low (USBRXCSRL1)

Base 0x4005.0000 Offset 0x116 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	CLRDT	W1C	0	Clear Data Toggle  Writing a 1 to this bit clears the DT bit in the USBRXCSRHn register.
6	STALLED	R/W	0	Endpoint Stalled
				Value Description
				0 A STALL handshake has not been received.
				A STALL handshake has been received. The EPn bit in the <b>USBRXIS</b> register is also set.
				Software must clear this bit.
5	REQPKT	R/W	0	Request Packet
				Value Description
				0 No request.
				1 Requests an IN transaction.
				This bit is cleared when RXRDY is set.
4	FLUSH	R/W	0	Flush FIFO
				Value Description
				0 No effect.

Flushes the next packet to be read from the endpoint receive FIFO. The FIFO pointer is reset and the RXRDY bit is cleared.

Note that if the FIFO is double-buffered,  ${\tt FLUSH}$  may have to be set twice to completely clear the FIFO.

**Important:** This bit should only be set when the RXRDY bit is set. At other times, it may cause data to be corrupted.


Bit/Field	Name	Туре	Reset	Description
3	DATAERR / NAKTO	R/W	0	Data Error / NAK Timeout
				Value Description
				0 Normal operation.
				1 Isochronous endpoints only: Indicates that RXRDY is set and the data packet has a CRC or bit-stuff error. This bit is cleared when RXRDY is cleared.
				Bulk endpoints only: Indicates that the receive endpoint is halter following the receipt of NAK responses for longer than the time set by the NAKLMT field in the USBRXINTERVALn register. Software must clear this bit to allow the endpoint to continue.
2	ERROR	R/W	0	Error
				Value Description
				0 No error.
				Three attempts have been made to receive a packet and no data packet has been received. The EPn bit in the <b>USBRXIS</b> register is set in this situation.
				Software must clear this bit.
				<b>Note:</b> This bit is only valid when the receive endpoint is operating in Bulk or Interrupt mode. In Isochronous mode, it always returns zero.
1	FULL	RO	0	FIFO Full
•			-	
				Value Description
				0 The receive FIFO is not full.
				No more packets can be loaded into the receive FIFO.
0	RXRDY	R/W	0	Receive Packet Ready
				Value Description
				0 No data packet has been received.
				A data packet has been received. The EPn bit in the <b>USBRXIS</b> register is also set in this situation.
				If the AUTOCIA hit in the USRRYCSRHn register is set, then the this h

If the AUTOCLR bit in the **USBRXCSRHn** register is set, then the this bit is automatically cleared when a packet of **USBRXMAXPn** bytes has been unloaded from the receive FIFO. If the AUTOCLR bit is clear, or if packets of less than the maximum packet size are unloaded, then software must clear this bit manually when the packet has been unloaded from the receive FIFO.

## OTG B / Device Mode

USB Receive Control and Status Endpoint 1 Low (USBRXCSRL1)

Base 0x4005.0000 Offset 0x116 Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7	CLRDT	W1C	0	Clear Data Toggle
				Writing a 1 to this bit clears the DT bit in the <b>USBRXCSRHn</b> register.
6	STALLED	R/W	0	Endpoint Stalled
				Value Description
				0 A STALL handshake has not been transmitted.
				1 A STALL handshake has been transmitted.
				Software must clear this bit.
5	STALL	R/W	0	Send STALL
				Value Description
				0 No effect.
				1 Issues a STALL handshake.
				Software must clear this bit to terminate the STALL condition.
				<b>Note:</b> This bit has no effect where the endpoint is being used for isochronous transfers.
4	FLUSH	R/W	0	Flush FIFO
				Value Description

0 No effect.

1 Flushes the next packet from the endpoint receive FIFO. The FIFO pointer is reset and the RXRDY bit is cleared.

The CPU writes a 1 to this bit to flush the next packet to be read from the endpoint receive FIFO. The FIFO pointer is reset and the RXRDY bit is cleared. Note that if the FIFO is double-buffered, FLUSH may have to be set twice to completely clear the FIFO.

**Important:** This bit should only be set when the RXRDY bit is set. At other times, it may cause data to be corrupted.

Bit/Field	Name	Туре	Reset	Description
3	DATAERR	RO	0	Data Error
				Value Description
				0 Normal operation.
				1 Indicates that RXRDY is set and the data packet has a CRC or bit-stuff error.
				This bit is cleared when RXRDY is cleared.
				<b>Note:</b> This bit is only valid when the endpoint is operating in Isochronous mode. In Bulk mode, it always returns zero.
2	OVER	R/W	0	Overrun
				Value Description
				0 No overrun error.
				1 Indicates that an OUT packet cannot be loaded into the receive FIFO.
				Software must clear this bit.
				<b>Note:</b> This bit is only valid when the endpoint is operating in Isochronous mode. In Bulk mode, it always returns zero.
1	FULL	RO	0	FIFO Full
				Value Description
				0 The receive FIFO is not full.
				1 No more packets can be loaded into the receive FIFO.
0	RXRDY	R/W	0	Receive Packet Ready
				Value Description
				0 No data packet has been received.
				A data packet has been received. The EPn bit in the <b>USBRXIS</b> register is also set in this situation.
				If the AUTOCLR bit in the USBRXCSRHn register is set, then the this bit

If the AUTOCLR bit in the **USBRXCSRHn** register is set, then the this bit is automatically cleared when a packet of **USBRXMAXPn** bytes has been unloaded from the receive FIFO. If the AUTOCLR bit is clear, or if packets of less than the maximum packet size are unloaded, then software must clear this bit manually when the packet has been unloaded from the receive FIFO.

Register 210: USB Receive Control and Status Endpoint 1 High (USBRXCSRH1), offset 0x117

Register 211: USB Receive Control and Status Endpoint 2 High (USBRXCSRH2), offset 0x127

Register 212: USB Receive Control and Status Endpoint 3 High (USBRXCSRH3), offset 0x137

Register 213: USB Receive Control and Status Endpoint 4 High (USBRXCSRH4), offset 0x147

Register 214: USB Receive Control and Status Endpoint 5 High (USBRXCSRH5), offset 0x157

Register 215: USB Receive Control and Status Endpoint 6 High (USBRXCSRH6), offset 0x167

Register 216: USB Receive Control and Status Endpoint 7 High (USBRXCSRH7), offset 0x177

Register 217: USB Receive Control and Status Endpoint 8 High (USBRXCSRH8), offset 0x187

Register 218: USB Receive Control and Status Endpoint 9 High (USBRXCSRH9), offset 0x197

Register 219: USB Receive Control and Status Endpoint 10 High (USBRXCSRH10), offset 0x1A7

Register 220: USB Receive Control and Status Endpoint 11 High (USBRXCSRH11), offset 0x1B7

Register 221: USB Receive Control and Status Endpoint 12 High (USBRXCSRH12), offset 0x1C7

Register 222: USB Receive Control and Status Endpoint 13 High (USBRXCSRH13), offset 0x1D7

Register 223: USB Receive Control and Status Endpoint 14 High (USBRXCSRH14), offset 0x1E7

Register 224: USB Receive Control and Status Endpoint 15 High (USBRXCSRH15), offset 0x1F7

OTG A /

**USBRXCSRHn** is an 8-bit register that provides additional control and status bits for transfers through the currently selected receive endpoint.


OTG B /

#### OTG A / Host Mode

USB Receive Control and Status Endpoint 1 High (USBRXCSRH1)

Base 0x4005.0000 Offset 0x117 Type R/W, reset 0x00

5



Bit/Field	Name	Type	Reset	Description
7	AUTOCL	R/W	0	Auto Clear
				Value Description
				<ol> <li>No effect.</li> </ol>

1 Enables the RXRDY bit to be automatically cleared when a packet of **USBRXMAXPn** bytes has been unloaded from the receive FIFO. When packets of less than the maximum packet size are unloaded, RXRDY must be cleared manually. Care must be taken when using µDMA to unload the receive FIFO as data is read from the receive FIFO in 4 byte chunks regardless of the value of the MAXLOAD field in the **USBRXMAXPn** register, see "DMA Operation" on page 997.

6	AUTORQ	R/W	0	Auto Request
---	--------	-----	---	--------------

Value Description

0 No effect.

1 Enables the REQPKT bit to be automatically set when the RXRDY bit is cleared.

**Note:** This bit is automatically cleared when a short packet is received.

DMAEN R/W 0 DMA Request Enable

Value Description

Note:

0 Disables the  $\mu$ DMA request for the receive endpoint.

1 Enables the μDMA request for the receive endpoint.

3 TX and 3 RX endpoints can be connected to the µDMA module. If this bit is set for a particular endpoint, the DMAARX, DMABRX, Or DMACRX field in the **USB DMA Select** 

DMABRX, OF DMACRX field in the USB DMA Select (USBDMASEL) register must be programmed correspondingly.

4 PIDERR RO 0 PID Error

Value Description

0 No error.

Indicates a PID error in the received packet of an isochronous transaction.


This bit is ignored in bulk or interrupt transactions.

Bit/Field	Name	Туре	Reset	Description
3	DMAMOD	R/W	0	DMA Request Mode
				Value Description
				0 An interrupt is generated after every µDMA packet transfer.
				1 An interrupt is generated only after the entire $\mu DMA$ transfer is complete.
				<b>Note:</b> This bit must not be cleared either before or in the same cycle as the above DMAEN bit is cleared.
2	DTWE	RO	0	Data Toggle Write Enable
				Value Description
				0 The DT bit cannot be written.
				1 Enables the current state of the receive endpoint data to be written (see DT bit).
				This bit is automatically cleared once the new value is written.
1	DT	RO	0	Data Toggle
				When read, this bit indicates the current state of the receive data toggle.
				If DTWE is High, this bit may be written with the required setting of the data toggle. If DTWE is Low, any value written to this bit is ignored. Care should be taken when writing to this bit as it should only be changed to RESET the receive endpoint.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### **OTG B / Device Mode**

USB Receive Control and Status Endpoint 1 High (USBRXCSRH1)

Base 0x4005.0000 Offset 0x117 Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7	AUTOCL	R/W	0	Auto Clear
				Value Description
				0 No effect.
				1 Enables the RXRDY bit to be automatically cleared when a packet of <b>USBRXMAXPn</b> bytes has been unloaded from the receive FIFO. When packets of less than the maximum packet size are unloaded, RXRDY must be cleared manually. Care must be taken when using μDMA to unload the receive FIFO as data is read from the receive FIFO in 4 byte chunks regardless of the value of the MAXLOAD field in the <b>USBRXMAXPn</b> register, see "DMA Operation" on page 997.
6	ISO	R/W	0	Isochronous Transfers
				Value Description
				0 Enables the receive endpoint for isochronous transfers.
				1 Enables the receive endpoint for bulk/interrupt transfers.
5	DMAEN	R/W	0	DMA Request Enable
				Value Description
				0 Disables the μDMA request for the receive endpoint.
				1 Enables the μDMA request for the receive endpoint.
				Note: 3 TX and 3 RX endpoints can be connected to the μDMA module. If this bit is set for a particular endpoint, the DMAARX, DMABRX, or DMACRX field in the USB DMA Select (USBDMASEL) register must be programmed correspondingly.
4	DISNYET / PIDERR	R/W	0	Disable NYET / PID Error
				Value Description
				0 No effect.
				1 For bulk or interrupt transactions: Disables the sending of NYET handshakes. When this bit is set, all successfully received packets are acknowledged, including at the point at which the FIFO becomes full.
				For isochronous transactions: Indicates a PID error in the received packet.
3	DMAMOD	R/W	0	DMA Request Mode
				Value Description
				0 An interrupt is generated after every μDMA packet transfer.
				1 An interrupt is generated only after the entire $\mu DMA$ transfer is complete.
				<b>Note:</b> This bit must not be cleared either before or in the same cycle as the above DMAEN bit is cleared.

Bit/Field	Name	Type	Reset	Description
2:0	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Register 225: USB Receive Byte Count Endpoint 1 (USBRXCOUNT1), offset 0x118

Register 226: USB Receive Byte Count Endpoint 2 (USBRXCOUNT2), offset 0x128

Register 227: USB Receive Byte Count Endpoint 3 (USBRXCOUNT3), offset 0x138

Register 228: USB Receive Byte Count Endpoint 4 (USBRXCOUNT4), offset 0x148

Register 229: USB Receive Byte Count Endpoint 5 (USBRXCOUNT5), offset 0x158

Register 230: USB Receive Byte Count Endpoint 6 (USBRXCOUNT6), offset 0x168

Register 231: USB Receive Byte Count Endpoint 7 (USBRXCOUNT7), offset 0x178

Register 232: USB Receive Byte Count Endpoint 8 (USBRXCOUNT8), offset 0x188

Register 233: USB Receive Byte Count Endpoint 9 (USBRXCOUNT9), offset 0x198

Register 234: USB Receive Byte Count Endpoint 10 (USBRXCOUNT10), offset 0x1A8

Register 235: USB Receive Byte Count Endpoint 11 (USBRXCOUNT11), offset 0x1B8

Register 236: USB Receive Byte Count Endpoint 12 (USBRXCOUNT12), offset 0x1C8

Register 237: USB Receive Byte Count Endpoint 13 (USBRXCOUNT13), offset 0x1D8

Register 238: USB Receive Byte Count Endpoint 14 (USBRXCOUNT14), offset 0x1E8

Register 239: USB Receive Byte Count Endpoint 15 (USBRXCOUNT15), offset 0x1F8

OTG A /


**Note:** The value returned changes as the FIFO is unloaded and is only valid while the RXRDY bit in the **USBRXCSRLn** register is set.

OTG B /

**USBRXCOUNTn** is a 16-bit read-only register that holds the number of data bytes in the packet currently in line to be read from the receive FIFO. If the packet is transmitted as multiple bulk packets, the number given is for the combined packet.

### USB Receive Byte Count Endpoint 1 (USBRXCOUNT1)

Base 0x4005.0000 Offset 0x118 Type RO, reset 0x0000



Bit/Field	Name	Туре	Reset	Description
15:13	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
12:0	COUNT	RO	0x000	Receive Packet Count Indicates the number of bytes in the receive packet.

Register 240: USB Host Transmit Configure Type Endpoint 1 (USBTXTYPE1), offset 0x11A

Register 241: USB Host Transmit Configure Type Endpoint 2 (USBTXTYPE2), offset 0x12A

Register 242: USB Host Transmit Configure Type Endpoint 3 (USBTXTYPE3), offset 0x13A

Register 243: USB Host Transmit Configure Type Endpoint 4 (USBTXTYPE4), offset 0x14A

Register 244: USB Host Transmit Configure Type Endpoint 5 (USBTXTYPE5), offset 0x15A

Register 245: USB Host Transmit Configure Type Endpoint 6 (USBTXTYPE6), offset 0x16A

Register 246: USB Host Transmit Configure Type Endpoint 7 (USBTXTYPE7), offset 0x17A

Register 247: USB Host Transmit Configure Type Endpoint 8 (USBTXTYPE8), offset 0x18A

Register 248: USB Host Transmit Configure Type Endpoint 9 (USBTXTYPE9), offset 0x19A

Register 249: USB Host Transmit Configure Type Endpoint 10 (USBTXTYPE10), offset 0x1AA

Register 250: USB Host Transmit Configure Type Endpoint 11 (USBTXTYPE11), offset 0x1BA

Register 251: USB Host Transmit Configure Type Endpoint 12 (USBTXTYPE12), offset 0x1CA

Register 252: USB Host Transmit Configure Type Endpoint 13 (USBTXTYPE13), offset 0x1DA

Register 253: USB Host Transmit Configure Type Endpoint 14 (USBTXTYPE14), offset 0x1EA


Register 254: USB Host Transmit Configure Type Endpoint 15 (USBTXTYPE15), offset 0x1FA

OTG A /

**USBTXTYPEn** is an 8-bit register that must be written with the endpoint number to be targeted by the endpoint, the transaction protocol to use for the currently selected transmit endpoint, and its operating speed.

### USB Host Transmit Configure Type Endpoint 1 (USBTXTYPE1)

Base 0x4005.0000 Offset 0x11A Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7:6	SPEED	R/W	0x0	Operating Speed This bit field specifies the operating speed of the target Device:
				This bit had opening the operating open of the target bevioe.
				Value Description
				0x0 Default
				The target is assumed to be using the same connection speed as the USB controller.
				0x1 Reserved
				0x2 Full
				0x3 Low
5:4	PROTO	R/W	0x0	Protocol
				Software must configure this bit field to select the required protocol for the transmit endpoint:
				Value Description
				0x0 Control
				0x1 Isochronous
				0x2 Bulk
				0x3 Interrupt
3:0	TEP	R/W	0x0	Target Endpoint Number
				Software must configure this value to the endpoint number contained

Device enumeration.

in the transmit endpoint descriptor returned to the USB controller during

Register 255: USB Host Transmit Interval Endpoint 1 (USBTXINTERVAL1), offset 0x11B

Register 256: USB Host Transmit Interval Endpoint 2 (USBTXINTERVAL2), offset 0x12B

Register 257: USB Host Transmit Interval Endpoint 3 (USBTXINTERVAL3), offset 0x13B

Register 258: USB Host Transmit Interval Endpoint 4 (USBTXINTERVAL4), offset 0x14B

Register 259: USB Host Transmit Interval Endpoint 5 (USBTXINTERVAL5), offset 0x15B

Register 260: USB Host Transmit Interval Endpoint 6 (USBTXINTERVAL6), offset 0x16B

Register 261: USB Host Transmit Interval Endpoint 7 (USBTXINTERVAL7), offset 0x17B

Register 262: USB Host Transmit Interval Endpoint 8 (USBTXINTERVAL8), offset 0x18B

Register 263: USB Host Transmit Interval Endpoint 9 (USBTXINTERVAL9), offset 0x19B

Register 264: USB Host Transmit Interval Endpoint 10 (USBTXINTERVAL10), offset 0x1AB

Register 265: USB Host Transmit Interval Endpoint 11 (USBTXINTERVAL11), offset 0x1BB

Register 266: USB Host Transmit Interval Endpoint 12 (USBTXINTERVAL12), offset 0x1CB

Register 267: USB Host Transmit Interval Endpoint 13 (USBTXINTERVAL13), offset 0x1DB

Register 268: USB Host Transmit Interval Endpoint 14 (USBTXINTERVAL14), offset 0x1EB

Register 269: USB Host Transmit Interval Endpoint 15 (USBTXINTERVAL15), offset 0x1FB

OTG A /


**USBTXINTERVALn** is an 8-bit register that, for interrupt and isochronous transfers, defines the polling interval for the currently selected transmit endpoint. For bulk endpoints, this register defines the number of frames after which the endpoint should time out on receiving a stream of NAK responses.

The **USBTXINTERVALn** register value defines a number of frames, as follows:

Transfer Type	Speed	Valid values (m)	Interpretation
Interrupt	Low-Speed or Full-Speed	0x01 – 0xFF	The polling interval is <i>m</i> frames.
Isochronous	Full-Speed	0x01 – 0x10	The polling interval is 2 <sup>(m-1)</sup> frames.
Bulk	Full-Speed	0x02 – 0x10	The NAK Limit is 2 <sup>(m-1)</sup> frames. A value of 0 or 1 disables the NAK timeout function.

### USB Host Transmit Interval Endpoint 1 (USBTXINTERVAL1)

Base 0x4005.0000 Offset 0x11B Type R/W, reset 0x00



Bit/Field	Name	Type	Reset	Description
7:0	TXPOLL / NAKLMT	R/W	0x00	TX Polling / NAK Limit

The polling interval for interrupt/isochronous transfers; the NAK limit for bulk transfers. See table above for valid entries; other values are reserved.

Register 270: USB Host Configure Receive Type Endpoint 1 (USBRXTYPE1), offset 0x11C

Register 271: USB Host Configure Receive Type Endpoint 2 (USBRXTYPE2), offset 0x12C

Register 272: USB Host Configure Receive Type Endpoint 3 (USBRXTYPE3), offset 0x13C

Register 273: USB Host Configure Receive Type Endpoint 4 (USBRXTYPE4), offset 0x14C

Register 274: USB Host Configure Receive Type Endpoint 5 (USBRXTYPE5), offset 0x15C

Register 275: USB Host Configure Receive Type Endpoint 6 (USBRXTYPE6), offset 0x16C

Register 276: USB Host Configure Receive Type Endpoint 7 (USBRXTYPE7), offset 0x17C

Register 277: USB Host Configure Receive Type Endpoint 8 (USBRXTYPE8), offset 0x18C

Register 278: USB Host Configure Receive Type Endpoint 9 (USBRXTYPE9), offset 0x19C

Register 279: USB Host Configure Receive Type Endpoint 10 (USBRXTYPE10), offset 0x1AC

Register 280: USB Host Configure Receive Type Endpoint 11 (USBRXTYPE11), offset 0x1BC

Register 281: USB Host Configure Receive Type Endpoint 12 (USBRXTYPE12), offset 0x1CC

Register 282: USB Host Configure Receive Type Endpoint 13 (USBRXTYPE13), offset 0x1DC

Register 283: USB Host Configure Receive Type Endpoint 14 (USBRXTYPE14), offset 0x1EC


Register 284: USB Host Configure Receive Type Endpoint 15 (USBRXTYPE15), offset 0x1FC

OTG A /

**USBRXTYPEn** is an 8-bit register that must be written with the endpoint number to be targeted by the endpoint, the transaction protocol to use for the currently selected receive endpoint, and its operating speed.

### USB Host Configure Receive Type Endpoint 1 (USBRXTYPE1)

Base 0x4005.0000 Offset 0x11C Type R/W, reset 0x00



Bit/Field	Name	Туре	Reset	Description
7:6	SPEED	R/W	0x0	Operating Speed This bit field specifies the operating speed of the target Device:
				Value Description
				0x0 Default
				The target is assumed to be using the same connection speed as the USB controller.
				0x1 Reserved
				0x2 Full
				0x3 Low
5:4	PROTO	R/W	0x0	Protocol
				Software must configure this bit field to select the required protocol for the receive endpoint:
				Value Description
				0x0 Control
				0x1 Isochronous
				0x2 Bulk
				0x3 Interrupt
3:0	TEP	R/W	0x0	Target Endpoint Number
				Software must set this value to the endpoint number contained in the

enumeration.

receive endpoint descriptor returned to the USB controller during Device

Register 285: USB Host Receive Polling Interval Endpoint 1 (USBRXINTERVAL1), offset 0x11D

Register 286: USB Host Receive Polling Interval Endpoint 2 (USBRXINTERVAL2), offset 0x12D

Register 287: USB Host Receive Polling Interval Endpoint 3 (USBRXINTERVAL3), offset 0x13D

Register 288: USB Host Receive Polling Interval Endpoint 4 (USBRXINTERVAL4), offset 0x14D

Register 289: USB Host Receive Polling Interval Endpoint 5 (USBRXINTERVAL5), offset 0x15D

Register 290: USB Host Receive Polling Interval Endpoint 6 (USBRXINTERVAL6), offset 0x16D

Register 291: USB Host Receive Polling Interval Endpoint 7 (USBRXINTERVAL7), offset 0x17D

Register 292: USB Host Receive Polling Interval Endpoint 8 (USBRXINTERVAL8), offset 0x18D

Register 293: USB Host Receive Polling Interval Endpoint 9 (USBRXINTERVAL9), offset 0x19D

Register 294: USB Host Receive Polling Interval Endpoint 10 (USBRXINTERVAL10), offset 0x1AD

Register 295: USB Host Receive Polling Interval Endpoint 11 (USBRXINTERVAL11), offset 0x1BD

Register 296: USB Host Receive Polling Interval Endpoint 12 (USBRXINTERVAL12), offset 0x1CD

Register 297: USB Host Receive Polling Interval Endpoint 13 (USBRXINTERVAL13), offset 0x1DD

Register 298: USB Host Receive Polling Interval Endpoint 14 (USBRXINTERVAL14), offset 0x1ED

Register 299: USB Host Receive Polling Interval Endpoint 15 (USBRXINTERVAL15), offset 0x1FD

OTG A / Host **USBRXINTERVALn** is an 8-bit register that, for interrupt and isochronous transfers, defines the polling interval for the currently selected receive endpoint. For bulk endpoints, this register defines the number of frames after which the endpoint should time out on receiving a stream of NAK responses.


The **USBRXINTERVALn** register value defines a number of frames, as follows:

Transfer Type	Speed	Valid values (m)	Interpretation
Interrupt	Low-Speed or Full-Speed	0x01 – 0xFF	The polling interval is <i>m</i> frames.
Isochronous	Full-Speed	0x01 – 0x10	The polling interval is 2 <sup>(m-1)</sup> frames.

Transfer Type	Speed	Valid values (m)	Interpretation
Bulk	Full-Speed	0x02 – 0x10	The NAK Limit is 2 <sup>(m-1)</sup> frames. A value of 0 or 1 disables the NAK timeout function.

### USB Host Receive Polling Interval Endpoint 1 (USBRXINTERVAL1)

Base 0x4005.0000 Offset 0x11D Type R/W, reset 0x00



Bivrieid	Name	туре	Reset	Description
7:0	TXPOLL / NAKLMT	R/W	0x00	RX Polling / NAK Limit

The polling interval for interrupt/isochronous transfers; the NAK limit for bulk transfers. See table above for valid entries; other values are reserved.

Register 300: USB Request Packet Count in Block Transfer Endpoint 1 (USBRQPKTCOUNT1), offset 0x304

Register 301: USB Request Packet Count in Block Transfer Endpoint 2 (USBRQPKTCOUNT2), offset 0x308

Register 302: USB Request Packet Count in Block Transfer Endpoint 3 (USBRQPKTCOUNT3), offset 0x30C

Register 303: USB Request Packet Count in Block Transfer Endpoint 4 (USBRQPKTCOUNT4), offset 0x310

Register 304: USB Request Packet Count in Block Transfer Endpoint 5 (USBRQPKTCOUNT5), offset 0x314

Register 305: USB Request Packet Count in Block Transfer Endpoint 6 (USBRQPKTCOUNT6), offset 0x318

Register 306: USB Request Packet Count in Block Transfer Endpoint 7 (USBRQPKTCOUNT7), offset 0x31C

Register 307: USB Request Packet Count in Block Transfer Endpoint 8 (USBRQPKTCOUNT8), offset 0x320

Register 308: USB Request Packet Count in Block Transfer Endpoint 9 (USBRQPKTCOUNT9), offset 0x324

Register 309: USB Request Packet Count in Block Transfer Endpoint 10 (USBRQPKTCOUNT10), offset 0x328

Register 310: USB Request Packet Count in Block Transfer Endpoint 11 (USBRQPKTCOUNT11), offset 0x32C

Register 311: USB Request Packet Count in Block Transfer Endpoint 12 (USBRQPKTCOUNT12), offset 0x330

Register 312: USB Request Packet Count in Block Transfer Endpoint 13 (USBRQPKTCOUNT13), offset 0x334

Register 313: USB Request Packet Count in Block Transfer Endpoint 14 (USBRQPKTCOUNT14), offset 0x338


Register 314: USB Request Packet Count in Block Transfer Endpoint 15 (USBRQPKTCOUNT15), offset 0x33C

OTG A / Host This 16-bit read/write register is used in Host mode to specify the number of packets that are to be transferred in a block transfer of one or more bulk packets to receive endpoint n. The USB controller uses the value recorded in this register to determine the number of requests to issue where the AUTORO bit in the **USBRXCSRHn** register has been set. See "IN Transactions as a Host" on page 993.

Note: Multiple packets combined into a single bulk packet within the FIFO count as one packet.

#### USB Request Packet Count in Block Transfer Endpoint 1 (USBRQPKTCOUNT1)

Base 0x4005.0000 Offset 0x304 Type R/W, reset 0x0000



Sets the number of packets of the size defined by the MAXLOAD bit field that are to be transferred in a block transfer.

Note: This is only used in Host mode when AUTORQ is set. The bit has no effect in Device mode or when AUTORQ is not set.

# Register 315: USB Receive Double Packet Buffer Disable (USBRXDPKTBUFDIS), offset 0x340

OTG A / Host **USBRXDPKTBUFDIS** is a 16-bit register that indicates which of the receive endpoints have disabled the double-packet buffer functionality (see the section called "Double-Packet Buffering" on page 989).

USB Receive Double Packet Buffer Disable (USBRXDPKTBUFDIS)

OTG B / Device Base 0x4005.0000 Offset 0x340 Type R/W, reset 0x0000

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	reserved
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO
Donot	^	Λ.	Λ.	Λ.	Λ.	0	^	Λ.	Λ	Λ.	Λ.	Λ	Λ.	Λ.	Λ.	0

		_		
Bit/Field	Name	Type	Reset	Description
15	EP15	R/W	0	EP15 RX Double-Packet Buffer Disable
				Value Description
				O Disables double-packet buffering.
				1 Enables double-packet buffering.
14	EP14	R/W	0	EP14 RX Double-Packet Buffer Disable
				Same description as EP15.
13	EP13	R/W	0	EP13 RX Double-Packet Buffer Disable
				Same description as EP15.
12	EP12	R/W	0	EP12 RX Double-Packet Buffer Disable
				Same description as EP15.
11	EP11	R/W	0	EP11 RX Double-Packet Buffer Disable
				Same description as EP15.
10	EP10	R/W	0	EP10 RX Double-Packet Buffer Disable
				Same description as EP15.
9	EP9	R/W	0	EP9 RX Double-Packet Buffer Disable
				Same description as EP15.
8	EP8	R/W	0	EP8 RX Double-Packet Buffer Disable
				Same description as EP15.
7	EP7	R/W	0	EP7 RX Double-Packet Buffer Disable  Same description as EP15.
	ED0	D.44	•	
6	EP6	R/W	0	EP6 RX Double-Packet Buffer Disable  Same description as EP15.
E	CD5	DAM	0	
5	EP5	R/W	0	EP5 RX Double-Packet Buffer Disable Same description as EP15.
4	EP4	R/W	0	EP4 RX Double-Packet Buffer Disable
7	LI 7	17/77	0	Same description as EP15.

Bit/Field	Name	Type	Reset	Description
3	EP3	R/W	0	EP3 RX Double-Packet Buffer Disable Same description as EP15.
2	EP2	R/W	0	EP2 RX Double-Packet Buffer Disable Same description as EP15.
1	EP1	R/W	0	EP1 RX Double-Packet Buffer Disable Same description as EP15.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

# Register 316: USB Transmit Double Packet Buffer Disable (USBTXDPKTBUFDIS), offset 0x342

OTG A /

**USBTXDPKTBUFDIS** is a 16-bit register that indicates which of the transmit endpoints have disabled the double-packet buffer functionality (see the section called "Double-Packet Buffering" on page 988).

USB Transmit Double Packet Buffer Disable (USBTXDPKTBUFDIS)

OTG B / Device Base 0x4005.0000 Offset 0x342 Type R/W, reset 0x0000

	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	reserved
Туре	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	RO

	Neset 0	0 0 0	0 0		U
Bit/Field	Name	Туре	Reset	Description	
15	EP15	R/W	0	EP15 TX Double-Packet Buffer Disable	
				Value Description  0 Disables double-packet buffering.  1 Enables double-packet buffering.	
14	EP14	R/W	0	EP14 TX Double-Packet Buffer Disable Same description as EP15.	
13	EP13	R/W	0	EP13 TX Double-Packet Buffer Disable Same description as EP15.	
12	EP12	R/W	0	EP12 TX Double-Packet Buffer Disable Same description as EP15.	
11	EP11	R/W	0	EP11 TX Double-Packet Buffer Disable Same description as EP15.	
10	EP10	R/W	0	EP10 TX Double-Packet Buffer Disable Same description as EP15.	
9	EP9	R/W	0	EP9 TX Double-Packet Buffer Disable Same description as EP15.	
8	EP8	R/W	0	EP8 TX Double-Packet Buffer Disable Same description as EP15.	
7	EP7	R/W	0	EP7 TX Double-Packet Buffer Disable Same description as EP15.	
6	EP6	R/W	0	EP6 TX Double-Packet Buffer Disable Same description as EP15.	
5	EP5	R/W	0	EP5 TX Double-Packet Buffer Disable Same description as EP15.	
4	EP4	R/W	0	EP4 TX Double-Packet Buffer Disable Same description as EP15.	

Bit/Field	Name	Type	Reset	Description
3	EP3	R/W	0	EP3 TX Double-Packet Buffer Disable Same description as EP15.
2	EP2	R/W	0	EP2 TX Double-Packet Buffer Disable Same description as EP15.
1	EP1	R/W	0	EP1 TX Double-Packet Buffer Disable Same description as EP15.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

### Register 317: USB External Power Control (USBEPC), offset 0x400

OTG A / Host This 32-bit register specifies the function of the two-pin external power interface (USB0EPEN and USB0PFLT). The assertion of the power fault input may generate an automatic action, as controlled by the hardware configuration registers. The automatic action is necessary because the fault condition may require a response faster than one provided by firmware.

OTG B /

D:4/E:414

7

USB External Power Control (USBEPC)

Base 0x4005.0000 Offset 0x400

Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
								rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
			rese	rved			PFLT	TACT	reserved	PFLTAEN	PFLTSEN	PFLTEN	reserved	EPENDE	EP	EN
Туре	RO	RO	RO	RO	RO	RO	R/W	R/W	RO	R/W	R/W	R/W	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	туре	Reset	Description
31:10	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9:8	PFLTACT	R/W	0x0	Power Fault Action

D = = = := #: = =

This bit field specifies how the USBOEPEN signal is changed when detecting a USB power fault.

Value Description 0x0 Unchanged

 $\tt USB0EPEN$  is controlled by the combination of the  $\tt EPEN$  and  $\tt EPENDE$  bits.

0x1 Tristate

USB0EPEN is undriven (tristate).

0x2 Low

USB0EPEN is driven Low.

0x3 High

USB0EPEN is driven High.

reserved RO 0 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
6	PFLTAEN	R/W	0	Power Fault Action Enable  This bit specifies whether a USB power fault triggers any automatic
				corrective action regarding the driven state of the USB0EPEN signal.
				Value Description
				0 Disabled
				USB0EPEN is controlled by the combination of the EPEN and EPENDE bits.
				1 Enabled
				The USB0EPEN output is automatically changed to the state specified by the PFLTACT field.
5	PFLTSEN	R/W	0	Power Fault Sense
				This bit specifies the logical sense of the USB0PFLT input signal that indicates an error condition.
				The complementary state is the inactive state.
				Value Description
				0 Low Fault
				If USBOPFLT is driven Low, the power fault is signaled internally (if enabled by the PFLTEN bit).
				1 High Fault
				If USBOPFLT is driven High, the power fault is signaled internally (if enabled by the PFLTEN bit).
4	PFLTEN	R/W	0	Power Fault Input Enable
				This bit specifies whether the ${\tt USBOPFLT}$ input signal is used in internal logic.
				Value Description
				0 Not Used
				The USBOPFLT signal is ignored.
				1 Used
				The USBOPFLT signal is used internally.
3	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
2	EPENDE	R/W	0	EPEN Drive Enable  This bit specifies whether the USB0EPEN signal is driven or undriven (tristate). When driven, the signal value is specified by the EPEN field. When not driven, the EPEN field is ignored and the USB0EPEN signal is placed in a high-impedance state.
				<ul> <li>Value Description</li> <li>Not Driven         The USB0EPEN signal is high impedance.     </li> <li>Driven         The USB0EPEN signal is driven to the logical value specified by the value of the EPEN field.     </li> </ul>
				The <code>USBOEPEN</code> signal is undriven at reset because the sense of the external power supply enable is unknown. By adding the high-impedance state, system designers may bias the power supply enable to the disabled state using a large resistor (100 k $\Omega$ ) and later configure and drive the output signal to enable the power supply.
1:0	EPEN	R/W	0x0	External Power Supply Enable Configuration  This bit field specifies and controls the logical value driven on the USBOEPEN signal.
				<ul> <li>Value Description</li> <li>0x0 Power Enable Active Low         The USB0EPEN signal is driven Low if the EPENDE bit is set.     </li> <li>0x1 Power Enable Active High         The USB0EPEN signal is driven High if the EPENDE bit is set.     </li> <li>0x2 Power Enable High if VBUS Low         The USB0EPEN signal is driven High when the A device is not recognized.     </li> <li>0x3 Power Enable High if VBUS High         The USB0EPEN signal is driven High when the A device is recognized.     </li> </ul>

## Register 318: USB External Power Control Raw Interrupt Status (USBEPCRIS), offset 0x404




This 32-bit register specifies the unmasked interrupt status of the two-pin external power interface.

USB External Power Control Raw Interrupt Status (USBEPCRIS)

Base 0x4005.0000

Offset 0x404 Type RO, reset 0x0000.0000

OTG B / Device



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	PF	RO	0	USB Power Fault Interrupt Status

Value Description

- 1 A Power Fault status has been detected.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the  ${\tt PF}$  bit in the USBEPCISC register.

# Register 319: USB External Power Control Interrupt Mask (USBEPCIM), offset 0x408

OTG A /


This 32-bit register specifies the interrupt mask of the two-pin external power interface.

USB External Power Control Interrupt Mask (USBEPCIM)

Base 0x4005.0000

Offset 0x408
Type R/W, reset 0x0000.0000

OTG B / Device



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	PF	R/W	0	USB Power Fault Interrupt Mask

Value Description

- 1 The raw interrupt signal from a detected power fault is sent to the interrupt controller.
- 0 A detected power fault does not affect the interrupt status.


# Register 320: USB External Power Control Interrupt Status and Clear (USBEPCISC), offset 0x40C



This 32-bit register specifies the masked interrupt status of the two-pin external power interface. It also provides a method to clear the interrupt state.

USB External Power Control Interrupt Status and Clear (USBEPCISC)

OTG B / Device Base 0x4005.0000 Offset 0x40C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	PF	R/W1C	0	USB Power Fault Interrupt Status and Clear

Value Description

- 1 The PF bits in the USBEPCRIS and USBEPCIM registers are set, providing an interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt PF}$  bit in the **USBEPCRIS** register.


## Register 321: USB Device RESUME Raw Interrupt Status (USBDRRIS), offset 0x410

OTG A / Host The **USBDRRIS** 32-bit register is the raw interrupt status register. On a read, this register gives the current raw status value of the corresponding interrupt prior to masking. A write has no effect.

USB Device RESUME Raw Interrupt Status (USBDRRIS)

OTG B /

Base 0x4005.0000 Offset 0x410 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	RESUME	RO	0	RESUME Interrupt Status

Value Description

- 1 A RESUME status has been detected.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the  ${\tt RESUME}$  bit in the  ${\tt USBDRISC}$  register.

### Register 322: USB Device RESUME Interrupt Mask (USBDRIM), offset 0x414



The **USBDRIM** 32-bit register is the masked interrupt status register. On a read, this register gives the current value of the mask on the corresponding interrupt. Setting a bit sets the mask, preventing the interrupt from being signaled to the interrupt controller. Clearing a bit clears the corresponding mask, enabling the interrupt to be sent to the interrupt controller.

OTG B /
Device

USB Device RESUME Interrupt Mask (USBDRIM)

Base 0x4005.0000

Offset 0x414 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1	1				rese	rved							'
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0							
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		•		•				reserved	'	'						RESUME
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W 0							

Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	RESUME	R/W	0	RESUME Interrupt Mask

#### Value Description


- 1 The raw interrupt signal from a detected RESUME is sent to the interrupt controller. This bit should only be set when a SUSPEND has been detected (the SUSPEND bit in the **USBIS** register is set).
- 0 A detected RESUME does not affect the interrupt status.

## Register 323: USB Device RESUME Interrupt Status and Clear (USBDRISC), offset 0x418

OTG A / Host The **USBDRISC** 32-bit register is the interrupt clear register. On a write of 1, the corresponding interrupt is cleared. A write of 0 has no effect.

USB Device RESUME Interrupt Status and Clear (USBDRISC)

OTG B / Device Base 0x4005.0000 Offset 0x418 Type W1C, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	RESUME	R/W1C	0	RESUME Interrupt Status and Clear

Value Description

- 1 The RESUME bits in the **USBDRRIS** and **USBDRCIM** registers are set, providing an interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt RESUME}$  bit in the  ${\tt USBDRCRIS}$  register.

## Register 324: USB General-Purpose Control and Status (USBGPCS), offset 0x41C

OTG A / Host



**USBGPCS** provides the state of the internal ID signal.


When used in OTG mode, USB0VBUS and USB0ID do not require any configuration as they are dedicated pins for the USB controller and directly connect to the USB connector's VBUS and ID signals. If the USB controller is used as either a dedicated Host or Device, the DEVMODOTG and DEVMOD bits in the **USB General-Purpose Control and Status** (USBGPCS) register can be used to connect the USB0VBUS and USB0ID inputs to fixed levels internally, freeing the PB0 and PB1 pins for GPIO use. For proper self-powered Device operation, the VBUS value must still be monitored to assure that if the Host removes VBUS, the self-powered Device disables the D+/D- pull-up resistors. This function can be accomplished by connecting a standard GPIO to VBUS.

The termination resistors for the USB PHY have been added internally, and thus there is no need for external resistors. For a device, there is a 1.5 KOhm pull-up on the D+ and for a host there are 15 KOhm pull-downs on both D+ and D-.

#### USB General-Purpose Control and Status (USBGPCS)

Base 0x4005.0000 Offset 0x41C

Type R/W, reset 0x0000.0001



0. 0		o o	· ·	
Bit/Field	Name	Туре	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	DEVMODOTG	R/W	0	Enable Device Mode
				This bit enables the ${\tt DEVMOD}$ bit to control the state of the internal ID signal in OTG mode.
				Value Description
				The mode is specified by the state of the internal ID signal.
				1 This bit enables the DEVMOD bit to control the internal ID signal.
0	DEVMOD	R/W	1	Device Mode
				This bit specifies the state of the internal ID signal in Host mode and in OTG mode when the DEVMODOTG bit is set.
				In Device mode this bit is ignored (assumed set).
				Value Description
				0 Host mode
				1 Device mode

### Register 325: USB VBUS Droop Control (USBVDC), offset 0x430




This 32-bit register enables a controlled masking of VBUS to compensate for any in-rush current by a Device that is connected to the Host controller. The in-rush current can cause VBUS to droop, causing the USB controller's behavior to be unexpected. The USB Host controller allows VBUS to fall lower than the VBUS Valid level (4.75 V) but not below AValid (2.0 V) for 65 microseconds without signaling a VBUSERR interrupt in the controller. Without this, any glitch on VBUS would force the USB Host controller to remove power from VBUS and then re-enumerate the Device.

#### USB VBUS Droop Control (USBVDC)

Base 0x4005.0000 Offset 0x430

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	VRDEN	R/W	0	VRUS Droon Enable

Value Description

- 0 No effect.
- Any changes from VBUSVALID are masked when VBUS goes below 4.75 V but not lower than 2.0 V for 65 microseconds. During this time, the VBUS state indicates VBUSVALID.

### Register 326: USB VBUS Droop Control Raw Interrupt Status (USBVDCRIS), offset 0x434




This 32-bit register specifies the unmasked interrupt status of the VBUS droop limit of 65 microseconds.

USB VBUS Droop Control Raw Interrupt Status (USBVDCRIS)

Base 0x4005.0000

Offset 0x434 Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	VD	RO	0	VBUS Droop Raw Interrupt Status

Value Description

- A VBUS droop lasting for 65 microseconds has been detected.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the VD bit in the USBVDCISC register.

## Register 327: USB VBUS Droop Control Interrupt Mask (USBVDCIM), offset 0x438


OTG A /

This 32-bit register specifies the interrupt mask of the VBUS droop.

USB VBUS Droop Control Interrupt Mask (USBVDCIM)

Base 0x4005.0000

Offset 0x438
Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	VD	R/W	0	VBUS Droop Interrupt Mask

Value Description

- 1 The raw interrupt signal from a detected VBUS droop is sent to the interrupt controller.
- 0 A detected VBUS droop does not affect the interrupt status.

# Register 328: USB VBUS Droop Control Interrupt Status and Clear (USBVDCISC), offset 0x43C




This 32-bit register specifies the masked interrupt status of the VBUS droop and provides a method to clear the interrupt state.

USB VBUS Droop Control Interrupt Status and Clear (USBVDCISC)

Base 0x4005.0000

Offset 0x43C



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	VD	R/W1C	0	VBUS Droop Interrupt Status and Clear

Value Description

- 1 The VD bits in the USBVDCRIS and USBVDCIM registers are set, providing an interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  $\mathtt{V}\mathtt{D}$  bit in the USBVDCRIS register.


# Register 329: USB ID Valid Detect Raw Interrupt Status (USBIDVRIS), offset 0x444


OTG

This 32-bit register specifies whether the unmasked interrupt status of the ID value is valid.

USB ID Valid Detect Raw Interrupt Status (USBIDVRIS)

Base 0x4005.0000





Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ID	RO	0	ID Valid Detect Raw Interrupt Status

Value Description

- 1 A valid ID has been detected.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the  ${\tt ID}$  bit in the USBIDVISC register.

## Register 330: USB ID Valid Detect Interrupt Mask (USBIDVIM), offset 0x448


OTG

This 32-bit register specifies the interrupt mask of the ID valid detection.

USB ID Valid Detect Interrupt Mask (USBIDVIM)

Base 0x4005.0000 Offset 0x448

Type R/W, reset 0x0000.0000



Bit/Field	Name	туре	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ID	R/W	0	ID Valid Detect Interrunt Mask

#### Value Description

- The raw interrupt signal from a detected ID valid is sent to the interrupt controller.
- 0 A detected ID valid does not affect the interrupt status.

### Register 331: USB ID Valid Detect Interrupt Status and Clear (USBIDVISC), offset 0x44C


**OTG** 

This 32-bit register specifies the masked interrupt status of the ID valid detect. It also provides a method to clear the interrupt state.

USB ID Valid Detect Interrupt Status and Clear (USBIDVISC)

Base 0x4005.0000

Offset 0x44C Type R/W1C, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ID	R/W1C	0	ID Valid Detect Interrupt Status and Clear

Value Description

- The  ${\tt ID}$  bits in the **USBIDVRIS** and **USBIDVIM** registers are set, providing an interrupt to the interrupt controller.
- No interrupt has occurred or the interrupt is masked. 0

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt ID}$  bit in the USBIDVRIS register.

### Register 332: USB DMA Select (USBDMASEL), offset 0x450




This 32-bit register specifies which endpoints are mapped to the 6 allocated µDMA channels, see Table 7-1 on page 348 for more information on channel assignments.

USB DMA Select (USBDMASEL)

OTG B /
Device

Base 0x4005.0000 Offset 0x450 Type R/W, reset 0x0033.2211



Bit/Field	Name	Type	Reset	Description
31:24	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
23:20	DMACTX	R/W	0x3	DMA C.TX Select

Specifies the TX mapping of the third USB endpoint on  $\mu$ DMA channel 5 (primary assignment).

Value Description 0x0 reserved 0x1 Endpoint 1 TX 0x2 Endpoint 2 TX Endpoint 3 TX 0x3 Endpoint 4 TX 0x4 0x5 Endpoint 5 TX 0x6 Endpoint 6 TX Endpoint 7 TX 0x7 0x8 Endpoint 8 TX Endpoint 9 TX 0x9 Endpoint 10 TX 0xA 0xB Endpoint 11 TX 0xC Endpoint 12 TX Endpoint 13 TX 0xD Endpoint 14 TX 0xE 0xF Endpoint 15 TX

Bit/Field	Name	Туре	Reset	Description
19:16	DMACRX	R/W	0x3	DMA C RX Select
				Specifies the RX and TX mapping of the third USB endpoint on $\mu\text{DMA}$ channel 4 (primary assignment).
				Value Description
				0x0 reserved
				0x1 Endpoint 1 RX
				0x2 Endpoint 2 RX
				0x3 Endpoint 3 RX
				0x4 Endpoint 4 RX
				0x5 Endpoint 5 RX
				0x6 Endpoint 6 RX
				0x7 Endpoint 7 RX
				0x8 Endpoint 8 RX
				0x9 Endpoint 9 RX
				0xA Endpoint 10 RX
				0xB Endpoint 11 RX
				0xC Endpoint 12 RX
				0xD Endpoint 13 RX
				0xE Endpoint 14 RX
				0xF Endpoint 15 RX
15:12	DMABTX	R/W	0x2	DMA B TX Select
				Specifies the TX mapping of the second USB endpoint on µDMA channel 3 (primary assignment).
				Same bit definitions as the DMACTX field.
11:8	DMABRX	R/W	0x2	DMA B RX Select
				Specifies the RX mapping of the second USB endpoint on µDMA channel 2 (primary assignment).
				Same bit definitions as the DMACRX field.
7:4	DMAATX	R/W	0x1	DMA A TX Select
				Specifies the TX mapping of the first USB endpoint on $\mu DMA$ channel 1 (primary assignment).
				Same bit definitions as the DMACTX field.
3:0	DMAARX	R/W	0x1	DMA A RX Select
				Specifies the RX mapping of the first USB endpoint on $\mu DMA$ channel 0 (primary assignment).
				Same bit definitions as the DMACRX field.

## 20 Analog Comparators

An analog comparator is a peripheral that compares two analog voltages and provides a logical output that signals the comparison result.

**Note:** Not all comparators have the option to drive an output pin. See "Signal Description" on page 1123 for more information.

The comparator can provide its output to a device pin, acting as a replacement for an analog comparator on the board. In addition, the comparator can signal the application via interrupts or trigger the start of a sample sequence in the ADC. The interrupt generation and ADC triggering logic is separate and independent. This flexibility means, for example, that an interrupt can be generated on a rising edge and the ADC triggered on a falling edge.

The Stellaris<sup>®</sup> LM3S9D96 microcontroller provides three independent integrated analog comparators with the following functions:

- Compare external pin input to external pin input or to internal programmable voltage reference
- Compare a test voltage against any one of the following voltages:
  - An individual external reference voltage
  - A shared single external reference voltage
  - A shared internal reference voltage

## 20.1 Block Diagram




Figure 20-1. Analog Comparator Module Block Diagram

## 20.2 Signal Description

The following table lists the external signals of the Analog Comparators and describes the function of each. The Analog Comparator output signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for the Analog Comparator signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the Analog Comparator function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the Analog Comparator signal to the specified GPIO port pin. The positive and negative input signals are configured by clearing the DEN bit in the **GPIO Digital Enable (GPIODEN)** register. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 20-1. Analog Comparators Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
C0+	90	PB6	1	Analog	Analog comparator 0 positive input.
C0-	92	PB4	!	Analog	Analog comparator 0 negative input.

Table 20-1. Analog Comparators Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
C0o	24	PC5 (3)	0	TTL	Analog comparator 0 output.
	42	PF4 (2)			
	90	PB6 (3)			
	91	PB5 (1)			
	100	PD7 (2)			
C1+	24	PC5	1	Analog	Analog comparator 1 positive input.
C1-	91	PB5	1	Analog	Analog comparator 1 negative input.
Clo	2	PE6 (2)	0	TTL	Analog comparator 1 output.
	22	PC7 (7)			
	24	PC5 (2)			
	41	PF5 (2)			
	84	PH2 (2)			
C2+	23	PC6	1	Analog	Analog comparator 2 positive input.
C2-	22	PC7	1	Analog	Analog comparator 2 negative input.
C20	1	PE7 (2)	0	TTL	Analog comparator 2 output.
	23	PC6 (3)			

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 20-2. Analog Comparators Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
C0+	A7	PB6	I	Analog	Analog comparator 0 positive input.
C0-	A6	PB4	ļ	Analog	Analog comparator 0 negative input.
COo	M1 K4 A7 B7 A2	PC5 (3) PF4 (2) PB6 (3) PB5 (1) PD7 (2)	0	TTL	Analog comparator 0 output.
C1+	M1	PC5	I	Analog	Analog comparator 1 positive input.
C1-	B7	PB5	ļ	Analog	Analog comparator 1 negative input.
Clo	A1 L2 M1 K3 D11	PE6 (2) PC7 (7) PC5 (2) PF5 (2) PH2 (2)	0	TTL	Analog comparator 1 output.
C2+	M2	PC6	1	Analog	Analog comparator 2 positive input.
C2-	L2	PC7	I	Analog	Analog comparator 2 negative input.
C20	B1 M2	PE7 (2) PC6 (3)	0	TTL	Analog comparator 2 output.


a. The TTL designation indicates the pin has TTL-compatible voltage levels.

## 20.3 Functional Description

The comparator compares the VIN- and VIN+ inputs to produce an output, VOUT.

As shown in Figure 20-2 on page 1125, the input source for VIN- is an external input, Cn-. In addition to an external input, Cn+, input sources for VIN+ can be the C0+ or an internal reference,  $V_{IRFF}$ .

Figure 20-2. Structure of Comparator Unit



A comparator is configured through two status/control registers, Analog Comparator Control (ACCTL) and Analog Comparator Status (ACSTAT). The internal reference is configured through one control register, Analog Comparator Reference Voltage Control (ACREFCTL). Interrupt status and control are configured through three registers, Analog Comparator Masked Interrupt Status (ACMIS), Analog Comparator Raw Interrupt Status (ACRIS), and Analog Comparator Interrupt Enable (ACINTEN).


Typically, the comparator output is used internally to generate an interrupt as controlled by the ISEN bit in the **ACCTL** register. The output may also be used to drive an external pin, Co or generate an analog-to-digital converter (ADC) trigger.

Important: The ASRCP bits in the ACCTL register must be set before using the analog comparators.

### 20.3.1 Internal Reference Programming

The structure of the internal reference is shown in Figure 20-3 on page 1125. The internal reference is controlled by a single configuration register (**ACREFCTL**).

Figure 20-3. Comparator Internal Reference Structure



The internal reference can be programmed in one of two modes (low range or high range) depending on the RNG bit in the **ACREFCTL** register. When RNG is clear, the internal reference is in high-range mode, and when RNG is set the internal reference is in low-range mode.

In each range, the internal reference,  $V_{IREF}$ , has 16 pre-programmed thresholds or step values. The threshold to be used to compare the external input voltage against is selected using the VREF field in the **ACREFCTL** register.

In the high-range mode, the  $V_{IREF}$  threshold voltages start at the ideal high-range starting voltage of  $V_{DDA}/3.875$  and increase in ideal constant voltage steps of  $V_{DDA}/31$ .

In the low-range mode, the  $V_{IREF}$  threshold voltages start at:0V and increase in ideal constant voltage steps of  $V_{DDA}/23$ . The ideal  $V_{IREF}$  step voltages for each mode and their dependence on the RNG and VREF fields are summarized in Table 20-3 on page 1126.

Table 20-3. Internal Reference Voltage and ACREFCTL Field Values

ACREFCTL	. Register	
EN Bit Value	RNG Bit Value	Output Reference Voltage Based on VREF Field Value
EN=0	RNG=X	0 V (GND) for any value of ${\tt VREF}.$ It is recommended that ${\tt RNG=1}$ and ${\tt VREF=0}$ to minimize noise on the reference ground.
	RNG=0	Total resistance in ladder is 31 R. $V_{IREF} = V_{DDA} \times \frac{R_{VREF}}{R_{T}}$
	$V_{IREF} = V_{DDA} \times \frac{(VREF + 8)}{31}$	
	$V_{IREF} = 0.85 + 0.106 \times VREF$	
		The range of internal reference in this mode is 0.85-2.448 V.
EN=1	RNG=1	Total resistance in ladder is 23 R.
		$V_{IREF} = V_{DDA}  imes rac{R_{VREF}}{R_{T}}$
		$V_{IREF} = V_{DDA} \times \frac{VREF}{23}$
		VIREF = 0.143 × VREF
		The range of internal reference for this mode is 0-2.152 V.

## 20.4 Initialization and Configuration

The following example shows how to configure an analog comparator to read back its output value from an internal register.

- 1. Enable the analog comparator clock by writing a value of 0x0010.0000 to the **RCGC1** register in the System Control module (see page 272).
- **2.** Enable the clock to the appropriate GPIO modules via the **RCGC2** register (see page 284). To find out which GPIO ports to enable, refer to Table 24-5 on page 1270.
- **3.** In the GPIO module, enable the GPIO port/pin associated with the input signals as GPIO inputs. To determine which GPIO to configure, see Table 24-4 on page 1261.
- **4.** Configure the PMCn fields in the **GPIOPCTL** register to assign the analog comparator output signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).
- Configure the internal voltage reference to 1.65 V by writing the ACREFCTL register with the value 0x0000.030C.
- **6.** Configure the comparator to use the internal voltage reference and to *not* invert the output by writing the **ACCTLn** register with the value of 0x0000.040C.
- 7. Delay for 10 µs.
- 8. Read the comparator output value by reading the ACSTATn register's OVAL value.

Change the level of the comparator negative input signal C- to see the OVAL value change.

## 20.5 Register Map

Table 20-4 on page 1127 lists the comparator registers. The offset listed is a hexadecimal increment to the register's address, relative to the Analog Comparator base address of 0x4003.C000. Note that the analog comparator clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the analog comparator module clock is enabled before any analog comparator module registers are accessed.

Table 20-4. Analog Comparators Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	ACMIS	R/W1C	0x0000.0000	Analog Comparator Masked Interrupt Status	1129
0x004	ACRIS	RO	0x0000.0000	Analog Comparator Raw Interrupt Status	1130
0x008	ACINTEN	R/W	0x0000.0000	Analog Comparator Interrupt Enable	1131
0x010	ACREFCTL	R/W	0x0000.0000	Analog Comparator Reference Voltage Control	1132
0x020	ACSTAT0	RO	0x0000.0000	Analog Comparator Status 0	1133
0x024	ACCTL0	R/W	0x0000.0000	Analog Comparator Control 0	1134
0x040	ACSTAT1	RO	0x0000.0000	Analog Comparator Status 1	1133
0x044	ACCTL1	R/W	0x0000.0000	Analog Comparator Control 1	1134
0x060	ACSTAT2	RO	0x0000.0000	Analog Comparator Status 2	1133
0x064	ACCTL2	R/W	0x0000.0000	Analog Comparator Control 2	1134

## 20.6 Register Descriptions

The remainder of this section lists and describes the Analog Comparator registers, in numerical order by address offset.


## Register 1: Analog Comparator Masked Interrupt Status (ACMIS), offset 0x000

This register provides a summary of the interrupt status (masked) of the comparators.

Analog Comparator Masked Interrupt Status (ACMIS)

Base 0x4003.C000 Offset 0x000

Type R/W1C, reset 0x0000.0000



. •			v	
Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	IN2	R/W1C	0	Comparator 2 Masked Interrupt Status
				Value Description
				1 The IN2 bits in the <b>ACRIS</b> register and the <b>ACINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt IN2}$ bit in the $\textbf{ACRIS}$ register.
1	IN1	R/W1C	0	Comparator 1 Masked Interrupt Status
				Value Description
				1 The IN1 bits in the <b>ACRIS</b> register and the <b>ACINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the ${\tt IN1}$ bit in the ${\textbf{ACRIS}}$ register.
0	IN0	R/W1C	0	Comparator 0 Masked Interrupt Status

#### Value Description

- 1 The INO bits in the **ACRIS** register and the **ACINTEN** registers are set, providing an interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt IN0}$  bit in the **ACRIS** register.


## Register 2: Analog Comparator Raw Interrupt Status (ACRIS), offset 0x004

This register provides a summary of the interrupt status (raw) of the comparators. The bits in this register must be enabled to generate interrupts using the **ACINTEN** register.

Analog Comparator Raw Interrupt Status (ACRIS)

Base 0x4003.C000

Offset 0x004 Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:3	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	IN2	RO	0	Comparator 2 Interrupt Status
				Value Description
				1 Comparator 2 has generated an interrupt for an event as configured by the ISEN bit in the ACCTL2 register.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the IN2 bit in the <b>ACMIS</b> register.
1	IN1	RO	0	Comparator 1 Interrupt Status
				Value Description
				1 Comparator 1 has generated an interruptfor an event as configured by the ISEN bit in the ACCTL1 register.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the IN1 bit in the <b>ACMIS</b> register.
0	IN0	RO	0	Comparator 0 Interrupt Status
				Value Description
				1 Comparator 0 has gonerated an interrupt for an event as

- 1 Comparator 0 has generated an interrupt for an event as configured by the ISEN bit in the ACCTL0 register.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the INO bit in the ACMIS register.


### Register 3: Analog Comparator Interrupt Enable (ACINTEN), offset 0x008

This register provides the interrupt enable for the comparators.

Analog Comparator Interrupt Enable (ACINTEN)

Base 0x4003.C000 Offset 0x008

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:3	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
2	IN2	R/W	0	Comparator 2 Interrupt Enable
				Value Description
				1 The raw interrupt signal comparator 2 is sent to the interrupt controller.
				O A comparator 2 interrupt does not affect the interrupt status.
1	IN1	R/W	0	Comparator 1 Interrupt Enable
				Value Description
				1 The raw interrupt signal comparator 1 is sent to the interrupt controller.
				A comparator 1 interrupt does not affect the interrupt status.
0	IN0	R/W	0	Comparator 0 Interrupt Enable

#### Value Description

- 1 The raw interrupt signal comparator 0 is sent to the interrupt controller.
- 0 A comparator 0 interrupt does not affect the interrupt status.


### Register 4: Analog Comparator Reference Voltage Control (ACREFCTL), offset 0x010

This register specifies whether the resistor ladder is powered on as well as the range and tap.

Analog Comparator Reference Voltage Control (ACREFCTL)

Base 0x4003.C000

Offset 0x010 Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:10	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
9	EN	R/W	0	Resistor Ladder Enable
				Value Description
				0 The resistor ladder is unpowered.
				1 Powers on the resistor ladder. The resistor ladder is connected to $\ensuremath{V_{DDA}}.$
				This bit is cleared at reset so that the internal reference consumes the least amount of power if it is not used.
8	RNG	R/W	0	Resistor Ladder Range
				Value Description
				0 The resistor ladder has a total resistance of 31 R.
				1 The resistor ladder has a total resistance of 23 R.
7:4	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3:0	VREF	R/W	0x0	Resistor Ladder Voltage Ref
				The VREF bit field specifies the resistor ladder tap that is passed through

an analog multiplexer. The voltage corresponding to the tap position is the internal reference voltage available for comparison. See Table 20-3 on page 1126 for some output reference voltage examples.

Register 5: Analog Comparator Status 0 (ACSTAT0), offset 0x020

Register 6: Analog Comparator Status 1 (ACSTAT1), offset 0x040


Register 7: Analog Comparator Status 2 (ACSTAT2), offset 0x060

These registers specify the current output value of the comparator.

## Analog Comparator Status 0 (ACSTAT0)

Base 0x4003.C000 Offset 0x020

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	OVAL	RO	0	Comparator Output Value  Value Description  0 VIN- > VIN+  1 VIN- < VIN+
				VIN - is the voltage on the ${\tt Cn-}$ pin. VIN+ is the voltage on the ${\tt Cn+}$ pin, the C0+ pin, or the internal voltage reference (V <sub>IREF</sub> ) as defined by the ASRCP bit in the <b>ACCTL</b> register.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## Register 8: Analog Comparator Control 0 (ACCTL0), offset 0x024 Register 9: Analog Comparator Control 1 (ACCTL1), offset 0x044 Register 10: Analog Comparator Control 2 (ACCTL2), offset 0x064

These registers configure the comparator's input and output.

25


### Analog Comparator Control 0 (ACCTL0)

Base 0x4003.C000 Offset 0x024

8

reserved

Type R/W, reset 0x0000.0000



0x3 Reserved

0 Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

**TSLVAL** R/W Trigger Sense Level Value

RO

#### Value Description

- 0 An ADC event is generated if the comparator output is Low.
- An ADC event is generated if the comparator output is High.

Bit/Field	Name	Туре	Reset	Description
6:5	TSEN	R/W	0x0	Trigger Sense The TSEN field specifies the sense of the comparator output that generates an ADC event. The sense conditioning is as follows:
				Value Description  0x0 Level sense, see TSLVAL  0x1 Falling edge  0x2 Rising edge  0x3 Either edge
4	ISLVAL	R/W	0	Interrupt Sense Level Value
				Value Description  O An interrupt is generated if the comparator output is Low.  An interrupt is generated if the comparator output is High.
3:2	ISEN	R/W	0x0	Interrupt Sense The ISEN field specifies the sense of the comparator output that generates an interrupt. The sense conditioning is as follows:
				Value Description
				0x0 Level sense, see ISLVAL
				0x1 Falling edge
				0x2 Rising edge
				0x3 Either edge
1	CINV	R/W	0	Comparator Output Invert
				Value Description
				0 The output of the comparator is unchanged.
				The output of the comparator is inverted prior to being processed by hardware.
0	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

## 21 Pulse Width Modulator (PWM)

Pulse width modulation (PWM) is a powerful technique for digitally encoding analog signal levels. High-resolution counters are used to generate a square wave, and the duty cycle of the square wave is modulated to encode an analog signal. Typical applications include switching power supplies and motor control.

The Stellaris<sup>®</sup> microcontroller contains one PWM module, with four PWM generator blocks and a control block, for a total of 8 PWM outputs. The control block determines the polarity of the PWM signals, and which signals are passed through to the pins.

Each PWM generator block produces two PWM signals that share the same timer and frequency and can either be programmed with independent actions or as a single pair of complementary signals with dead-band delays inserted. The output signals, pwmA' and pwmB', of the PWM generation blocks are managed by the output control block before being passed to the device pins as PWM0 and PWM1 or PWM2 and PWM3, and so on.

The Stellaris PWM module provides a great deal of flexibility and can generate simple PWM signals, such as those required by a simple charge pump as well as paired PWM signals with dead-band delays, such as those required by a half-H bridge driver. Three generator blocks can also generate the full six channels of gate controls required by a 3-phase inverter bridge.

Each PWM generator block has the following features:

- Four fault-condition handling inputs to quickly provide low-latency shutdown and prevent damage to the motor being controlled
- One 16-bit counter
  - Runs in Down or Up/Down mode
  - Output frequency controlled by a 16-bit load value
  - Load value updates can be synchronized
  - Produces output signals at zero and load value
- Two PWM comparators
  - Comparator value updates can be synchronized
  - Produces output signals on match
- PWM signal generator
  - Output PWM signal is constructed based on actions taken as a result of the counter and PWM comparator output signals
  - Produces two independent PWM signals
- Dead-band generator
  - Produces two PWM signals with programmable dead-band delays suitable for driving a half-H bridge
  - Can be bypassed, leaving input PWM signals unmodified

■ Can initiate an ADC sample sequence

The control block determines the polarity of the PWM signals and which signals are passed through to the pins. The output of the PWM generation blocks are managed by the output control block before being passed to the device pins. The PWM control block has the following options:

- PWM output enable of each PWM signal
- Optional output inversion of each PWM signal (polarity control)
- Optional fault handling for each PWM signal
- Synchronization of timers in the PWM generator blocks
- Synchronization of timer/comparator updates across the PWM generator blocks
- Extended PWM synchronization of timer/comparator updates across the PWM generator blocks
- Interrupt status summary of the PWM generator blocks
- Extended PWM fault handling, with multiple fault signals, programmable polarities, and filtering
- PWM generators can be operated independently or synchronized with other generators

## 21.1 Block Diagram

Figure 21-1 on page 1138 provides the Stellaris PWM module diagram and Figure 21-2 on page 1138 provides a more detailed diagram of a Stellaris PWM generator. The LM3S9D96 controller contains four generator blocks that generate eight independent PWM signals or four paired PWM signals with dead-band delays inserted.





Figure 21-1. PWM Module Diagram

Figure 21-2. PWM Generator Block Diagram



## 21.2 Signal Description

The following table lists the external signals of the PWM module and describes the function of each. The PWM controller signals are alternate functions for some GPIO signals and default to be GPIO

signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for these PWM signals. The AFSEL bit in the **GPIO Alternate Function Select (GPIOAFSEL)** register (page 430) should be set to choose the PWM function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control (GPIOPCTL)** register (page 448) to assign the PWM signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

Table 21-1. PWM Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
Fault0	6 39 42 65 75 83 99	PE4 (4) PJ2 (10) PF4 (4) PB3 (2) PE1 (3) PH3 (2) PD6 (1)	I	TTL	PWM Fault 0.
Fault1	90	PB6 (4)	I	TTL	PWM Fault 1.
Fault2	24 63	PC5 (4) PH5 (10)	I	TTL	PWM Fault 2.
Fault3	65 84	PB3 (4) PH2 (4)	I	TTL	PWM Fault 3.
PWM0	10 14 19 34 47	PD0 (1) PJ0 (10) PG0 (2) PA6 (4) PF0 (3)	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
PWM1	11 18 35 61 87	PD1 (1) PG1 (2) PA7 (4) PF1 (3) PJ1 (10)	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
PWM2	12 60 66 86	PD2 (3) PF2 (4) PB0 (2) PH0 (2)	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
PWM3	13 59 67 85	PD3 (3) PF3 (4) PB1 (2) PH1 (2)	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
PWM4	2 19 28 34 60 62 74 86	PE6 (1) PG0 (4) PA2 (4) PA6 (5) PF2 (2) PH6 (10) PE0 (1) PH0 (9)	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
PWM5	1 15 18 29 35 59 75 85	PE7 (1) PH7 (10) PG1 (4) PA3 (4) PA7 (5) PF3 (2) PE1 (1) PH1 (9)	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.

Table 21-1. PWM Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PWM6	25 30	PC4 (4) PA4 (4)	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
PWM7	23 31 36	PC6 (4) PA5 (4) PG7 (4)	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### Table 21-2. PWM Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
Fault0	B2 K6 K4 E11 A12 D10 A3	PE4 (4) PJ2 (10) PF4 (4) PB3 (2) PE1 (3) PH3 (2) PD6 (1)	ı	TTL	PWM Fault 0.
Fault1	A7	PB6 (4)	I	TTL	PWM Fault 1.
Fault2	M1 F10	PC5 (4) PH5 (10)	I	TTL	PWM Fault 2.
Fault3	E11 D11	PB3 (4) PH2 (4)	I	TTL	PWM Fault 3.
PWMO	G1 F3 K1 L6 M9	PD0 (1) PJ0 (10) PG0 (2) PA6 (4) PF0 (3)	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
PWM1	G2 K2 M6 H12 B6	PD1 (1) PG1 (2) PA7 (4) PF1 (3) PJ1 (10)	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
PWM2	H2 J11 E12 C9	PD2 (3) PF2 (4) PB0 (2) PH0 (2)	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
PWM3	H1 J12 D12 C8	PD3 (3) PF3 (4) PB1 (2) PH1 (2)	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
PWM4	A1 K1 M4 L6 J11 G3 B11 C9	PE6 (1) PG0 (4) PA2 (4) PA6 (5) PF2 (2) PH6 (10) PE0 (1) PH0 (9)	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PWM5	B1 H3 K2 L4 M6 J12 A12 C8	PE7 (1) PH7 (10) PG1 (4) PA3 (4) PA7 (5) PF3 (2) PE1 (1) PH1 (9)	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
PWM6	L1 L5	PC4 (4) PA4 (4)	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
РWM7	M2 M5 C10	PC6 (4) PA5 (4) PG7 (4)	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.

Table 21-2. PWM Signals (108BGA) (continued)

### 21.3 Functional Description

#### 21.3.1 **PWM Timer**

The timer in each PWM generator runs in one of two modes: Count-Down mode or Count-Up/Down mode. In Count-Down mode, the timer counts from the load value to zero, goes back to the load value, and continues counting down. In Count-Up/Down mode, the timer counts from zero up to the load value, back down to zero, back up to the load value, and so on. Generally, Count-Down mode is used for generating left- or right-aligned PWM signals, while the Count-Up/Down mode is used for generating center-aligned PWM signals.

The timers output three signals that are used in the PWM generation process: the direction signal (this is always Low in Count-Down mode, but alternates between Low and High in Count-Up/Down mode), a single-clock-cycle-width High pulse when the counter is zero, and a single-clock-cycle-width High pulse when the counter is equal to the load value. Note that in Count-Down mode, the zero pulse is immediately followed by the load pulse. In the figures in this chapter, these signals are labelled "dir," "zero," and "load."

### 21.3.2 PWM Comparators

Each PWM generator has two comparators that monitor the value of the counter; when either comparator matches the counter, they output a single-clock-cycle-width High pulse, labelled "cmpA" and "cmpB" in the figures in this chapter. When in Count-Up/Down mode, these comparators match both when counting up and when counting down, and thus are qualified by the counter direction signal. These qualified pulses are used in the PWM generation process. If either comparator match value is greater than the counter load value, then that comparator never outputs a High pulse.

Figure 21-3 on page 1142 shows the behavior of the counter and the relationship of these pulses when the counter is in Count-Down mode. Figure 21-4 on page 1142 shows the behavior of the counter and the relationship of these pulses when the counter is in Count-Up/Down mode. In these figures, the following definitions apply:

- LOAD is the value in the PWMnLOAD register
- COMPA is the value in the PWMnCMPA register
- COMPB is the value in the PWMnCMPB register

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

- 0 is the value zero
- load is the internal signal that has a single-clock-cycle-width High pulse when the counter is equal to the load value
- zero is the internal signal that has a single-clock-cycle-width High pulse when the counter is zero
- cmpA is the internal signal that has a single-clock-cycle-width High pulse when the counter is equal to COMPA
- cmpB is the internal signal that has a single-clock-cycle-width High pulse when the counter is equal to COMPB
- dir is the internal signal that indicates the count direction

Figure 21-3. PWM Count-Down Mode





Figure 21-4. PWM Count-Up/Down Mode



### 21.3.3 PWM Signal Generator

Each PWM generator takes the load, zero, cmpA, and cmpB pulses (qualified by the dir signal) and generates two internal PWM signals, pwmA and pwmB. In Count-Down mode, there are four events that can affect these signals: zero, load, match A down, and match B down. In Count-Up/Down mode, there are six events that can affect these signals: zero, load, match A down, match A up, match B down, and match B up. The match A or match B events are ignored when they coincide with the zero or load events. If the match A and match B events coincide, the first signal, pwmA, is generated based only on the match A event, and the second signal, pwmB, is generated based only on the match B event.

For each event, the effect on each output PWM signal is programmable: it can be left alone (ignoring the event), it can be toggled, it can be driven Low, or it can be driven High. These actions can be used to generate a pair of PWM signals of various positions and duty cycles, which do or do not overlap. Figure 21-5 on page 1143 shows the use of Count-Up/Down mode to generate a pair of center-aligned, overlapped PWM signals that have different duty cycles. This figure shows the pwmA and pwmB signals before they have passed through the dead-band generator.




Figure 21-5. PWM Generation Example In Count-Up/Down Mode


In this example, the first generator is set to drive High on match A up, drive Low on match A down, and ignore the other four events. The second generator is set to drive High on match B up, drive Low on match B down, and ignore the other four events. Changing the value of comparator A changes the duty cycle of the pwmA signal, and changing the value of comparator B changes the duty cycle of the pwmB signal.

### 21.3.4 Dead-Band Generator

The pwmA and pwmB signals produced by each PWM generator are passed to the dead-band generator. If the dead-band generator is disabled, the PWM signals simply pass through to the pwmA' and pwmB' signals unmodified. If the dead-band generator is enabled, the pwmB signal is lost and two PWM signals are generated based on the pwmA signal. The first output PWM signal, pwmA' is the pwmA signal with the rising edge delayed by a programmable amount. The second output PWM signal, pwmB', is the inversion of the pwmA signal with a programmable delay added between the falling edge of the pwmA signal and the rising edge of the pwmB' signal.

The resulting signals are a pair of active High signals where one is always High, except for a programmable amount of time at transitions where both are Low. These signals are therefore suitable for driving a half-H bridge, with the dead-band delays preventing shoot-through current from damaging the power electronics. Figure 21-6 on page 1144 shows the effect of the dead-band generator on the pwmA signal and the resulting pwmA' and pwmB' signals that are transmitted to the output control block.

Figure 21-6. PWM Dead-Band Generator



### 21.3.5 Interrupt/ADC-Trigger Selector

Each PWM generator also takes the same four (or six) counter events and uses them to generate an interrupt or an ADC trigger. Any of these events or a set of these events can be selected as a source for an interrupt; when any of the selected events occur, an interrupt is generated. Additionally, the same event, a different event, the same set of events, or a different set of events can be selected as a source for an ADC trigger; when any of these selected events occur, an ADC trigger pulse is generated. The selection of events allows the interrupt or ADC trigger to occur at a specific position within the pwmA or pwmB signal. Note that interrupts and ADC triggers are based on the raw events; delays in the PWM signal edges caused by the dead-band generator are not taken into account.

### 21.3.6 Synchronization Methods

The PWM module provides four PWM generators, each providing two PWM outputs that may be used in a wide variety of applications. Generally speaking, the PWM is used in one of two categories of operation:

- **Unsynchronized.** The PWM generator and its two output signals are used alone, independent of other PWM generators.
- **Synchronized.** The PWM generator and its two outputs signals are used in conjunction with other PWM generators using a common, unified time base. If multiple PWM generators are configured with the same counter load value, synchronization can be used to guarantee that they also have the same count value (the PWM generators must be configured before they are synchronized). With this feature, more than two PWMn signals can be produced with a known relationship between the edges of those signals because the counters always have the same values. Other states in the module provide mechanisms to maintain the common time base and mutual synchronization.

The counter in a PWM generator can be reset to zero by writing the **PWM Time Base Sync** (**PWMSYNC**) register and setting the SYNCn bit associated with the generator. Multiple PWM generators can be synchronized together by setting all necessary SYNCn bits in one access. For example, setting the SYNC0 and SYNC1 bits in the **PWMSYNC** register causes the counters in PWM generators 0 and 1 to reset together.

Additional synchronization can occur between multiple PWM generators by updating register contents in one of the following three ways:

- Immediately. The write value has immediate effect, and the hardware reacts immediately.
- Locally Synchronized. The write value does not affect the logic until the counter reaches the value zero at the end of the PWM cycle. In this case, the effect of the write is deferred, providing a guaranteed defined behavior and preventing overly short or overly long output PWM pulses.
- **Globally Synchronized.** The write value does not affect the logic until two sequential events have occurred: (1) the Update mode for the generator function is programmed for global

synchronization in the **PWMnCTL** register, and (2) the counter reaches zero at the end of the PWM cycle. In this case, the effect of the write is deferred until the end of the PWM cycle following the end of all updates. This mode allows multiple items in multiple PWM generators to be updated simultaneously without odd effects during the update; everything runs from the old values until a point at which they all run from the new values. The Update mode of the load and comparator match values can be individually configured in each PWM generator block. It typically makes sense to use the synchronous update mechanism across PWM generator blocks when the timers in those blocks are synchronized, although this is not required in order for this mechanism to function properly.

The following registers provide either local or global synchronization based on the state of various Update mode bits and fields in the PWMnCTL register (LOADUPD; CMPAUPD):

■ Generator Registers: PWMnLOAD, PWMnCMPA, and PWMnCMPB

The following registers default to immediate update, but are provided with the optional functionality of synchronously updating rather than having all updates take immediate effect:

- Module-Level Register: **PWMENABLE** (based on the state of the ENUPDn bits in the PWMENUPD register).
- Generator Register: PWMnGENA, PWMnGENB, PWMnDBCTL, PWMnDBRISE, and PWMnDBFALL (based on the state of various Update mode bits and fields in the PWMnCTL register (GENAUPD; GENBUPD; DBCTLUPD; DBRISEUPD; DBFALLUPD)).

All other registers are considered statically provisioned for the execution of an application or are used dynamically for purposes unrelated to maintaining synchronization and therefore do not need synchronous update functionality.

### 21.3.7 Fault Conditions

A fault condition is one in which the controller must be signaled to stop normal PWM function and then set the PWMn signals to a safe state. Two basic situations cause fault conditions:

- The microcontroller is stalled and cannot perform the necessary computation in the time required for motion control
- An external error or event is detected

The PWM generator can use the following inputs to generate a fault condition, including:

- FAULTn pin assertion
- A stall of the controller generated by the debugger
- The trigger of an ADC digital comparator

Fault conditions are calculated on a per-PWM generator basis. Each PWM generator configures the necessary conditions to indicate a fault condition exists. This method allows the development of applications with dependent and independent control.

Four fault input pins (FAULT0-FAULT3) are available. These inputs may be used with circuits that generate an active High or active Low signal to indicate an error condition. A FAULTn pins may be individually programmed for the appropriate logic sense using the **PWMnFLTSEN** register.

The PWM generator's mode control, including fault condition handling, is provided in the **PWMnCTL** register. This register determines whether the input or a combination of FAULTn input signals and/or digital comparator triggers (as configured by the **PWMnFLTSRC0** and **PWMnFLTSRC1** registers) is used to generate a fault condition. The **PWMnCTL** register also selects whether the fault condition is maintained as long as the external condition lasts or if it is latched until the fault condition until cleared by software. Finally, this register also enables a counter that may be used to extend the period of a fault condition for external events to assure that the duration is a minimum length. The minimum fault period count is specified in the **PWMnMINFLTPER** register.

Status regarding the specific fault cause is provided in the **PWMnFLTSTAT0** and **PWMnFLTSTAT1** registers.

PWM generator fault conditions may be promoted to a controller interrupt using the **PWMINTEN** register.

### 21.3.8 Output Control Block

The output control block takes care of the final conditioning of the pwmA' and pwmB' signals before they go to the pins as the PWMn signals. Via a single register, the **PWM Output Enable** (**PWNENABLE**) register, the set of PWM signals that are actually enabled to the pins can be modified. This function can be used, for example, to perform commutation of a brushless DC motor with a single register write (and without modifying the individual PWM generators, which are modified by the feedback control loop). In addition, the updating of the bits in the **PWMENABLE** register can be configured to be immediate or locally or globally synchronized to the next synchronous update using the **PWM Enable Update (PWMENUPD)** register.

During fault conditions, the PWM output signals, PWMn, usually must be driven to safe values so that external equipment may be safely controlled. The **PWMFAULT** register specifies whether during a fault condition, the generated signal continues to be passed driven or to an encoding specified in the **PWMFAULTVAL** register.

A final inversion can be applied to any of the PWMn signals, making them active Low instead of the default active High using the **PWM Output Inversion (PWMINVERT)**. The inversion is applied even if a value has been enabled in the **PWMFAULT** register and specified in the **PWMFAULTVAL** register. In other words, if a bit is set in the **PWMFAULT, PWMFAULTVAL**, and **PWMINVERT** registers, the output on the PWMn signal is 0, not 1 as specified in the **PWMFAULTVAL** register.

## 21.4 Initialization and Configuration

The following example shows how to initialize PWM Generator 0 with a 25-kHz frequency, a 25% duty cycle on the PWM0 pin, and a 75% duty cycle on the PWM1 pin. This example assumes the system clock is 20 MHz.

- 1. Enable the PWM clock by writing a value of 0x0010.0000 to the **RCGC0** register in the System Control module (see page 264).
- 2. Enable the clock to the appropriate GPIO module via the RCGC2 register in the System Control module (see page 284).
- 3. In the GPIO module, enable the appropriate pins for their alternate function using the **GPIOAFSEL** register. To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the PMCn fields in the **GPIOPCTL** register to assign the PWM signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).

- 5. Configure the Run-Mode Clock Configuration (RCC) register in the System Control module to use the PWM divide (USEPWMDIV) and set the divider (PWMDIV) to divide by 2 (000).
- **6.** Configure the PWM generator for countdown mode with immediate updates to the parameters.
  - Write the **PWM0CTL** register with a value of 0x0000.0000.
  - Write the **PWM0GENA** register with a value of 0x0000.008C.
  - Write the **PWM0GENB** register with a value of 0x0000.080C.
- 7. Set the period. For a 25-KHz frequency, the period = 1/25,000, or 40 microseconds. The PWM clock source is 10 MHz; the system clock divided by 2. Thus there are 400 clock ticks per period. Use this value to set the **PWM0LOAD** register. In Count-Down mode, set the LOAD field in the **PWM0LOAD** register to the requested period minus one.
  - Write the **PWM0LOAD** register with a value of 0x0000.018F.
- 8. Set the pulse width of the PWM0 pin for a 25% duty cycle.
  - Write the **PWM0CMPA** register with a value of 0x0000.012B.
- 9. Set the pulse width of the PWM1 pin for a 75% duty cycle.
  - Write the **PWM0CMPB** register with a value of 0x0000.0063.
- 10. Start the timers in PWM generator 0.
  - Write the **PWM0CTL** register with a value of 0x0000.0001.
- 11. Enable PWM outputs.
  - Write the **PWMENABLE** register with a value of 0x0000.0003.

## 21.5 Register Map

Table 21-3 on page 1147 lists the PWM registers. The offset listed is a hexadecimal increment to the register's address, relative to the PWM module's base address:

■ PWM0: 0x4002.8000

Note that the PWM module clock must be enabled before the registers can be programmed (see page 264). There must be a delay of 3 system clocks after the PWM module clock is enabled before any PWM module registers are accessed.

Table 21-3. PWM Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	PWMCTL	R/W	0x0000.0000	PWM Master Control	1151
0x004	PWMSYNC	R/W	0x0000.0000	PWM Time Base Sync	1153
0x008	PWMENABLE	R/W	0x0000.0000	PWM Output Enable	1154
0x00C	PWMINVERT	R/W	0x0000.0000	PWM Output Inversion	1156

Table 21-3. PWM Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x010	PWMFAULT	R/W	0x0000.0000	PWM Output Fault	1158
0x014	PWMINTEN	R/W	0x0000.0000	PWM Interrupt Enable	1160
0x018	PWMRIS	RO	0x0000.0000	PWM Raw Interrupt Status	1162
0x01C	PWMISC	R/W1C	0x0000.0000	PWM Interrupt Status and Clear	1165
0x020	PWMSTATUS	RO	0x0000.0000	PWM Status	1168
0x024	PWMFAULTVAL	R/W	0x0000.0000	PWM Fault Condition Value	1170
0x028	PWMENUPD	R/W	0x0000.0000	PWM Enable Update	1172
0x040	PWM0CTL	R/W	0x0000.0000	PWM0 Control	1176
0x044	PWM0INTEN	R/W	0x0000.0000	PWM0 Interrupt and Trigger Enable	1181
0x048	PWM0RIS	RO	0x0000.0000	PWM0 Raw Interrupt Status	1184
0x04C	PWM0ISC	R/W1C	0x0000.0000	PWM0 Interrupt Status and Clear	1186
0x050	PWM0LOAD	R/W	0x0000.0000	PWM0 Load	1188
0x054	PWM0COUNT	RO	0x0000.0000	PWM0 Counter	1189
0x058	PWM0CMPA	R/W	0x0000.0000	PWM0 Compare A	1190
0x05C	PWM0CMPB	R/W	0x0000.0000	PWM0 Compare B	1191
0x060	PWM0GENA	R/W	0x0000.0000	PWM0 Generator A Control	1192
0x064	PWM0GENB	R/W	0x0000.0000	PWM0 Generator B Control	1195
0x068	PWM0DBCTL	R/W	0x0000.0000	PWM0 Dead-Band Control	1198
0x06C	PWM0DBRISE	R/W	0x0000.0000	PWM0 Dead-Band Rising-Edge Delay	1199
0x070	PWM0DBFALL	R/W	0x0000.0000	PWM0 Dead-Band Falling-Edge-Delay	1200
0x074	PWM0FLTSRC0	R/W	0x0000.0000	PWM0 Fault Source 0	1201
0x078	PWM0FLTSRC1	R/W	0x0000.0000	PWM0 Fault Source 1	1203
0x07C	PWM0MINFLTPER	R/W	0x0000.0000	PWM0 Minimum Fault Period	1206
0x080	PWM1CTL	R/W	0x0000.0000	PWM1 Control	1176
0x084	PWM1INTEN	R/W	0x0000.0000	PWM1 Interrupt and Trigger Enable	1181
0x088	PWM1RIS	RO	0x0000.0000	PWM1 Raw Interrupt Status	1184
0x08C	PWM1ISC	R/W1C	0x0000.0000	PWM1 Interrupt Status and Clear	1186
0x090	PWM1LOAD	R/W	0x0000.0000	PWM1 Load	1188
0x094	PWM1COUNT	RO	0x0000.0000	PWM1 Counter	1189
0x098	PWM1CMPA	R/W	0x0000.0000	PWM1 Compare A	1190
0x09C	PWM1CMPB	R/W	0x0000.0000	PWM1 Compare B	1191
0x0A0	PWM1GENA	R/W	0x0000.0000	PWM1 Generator A Control	1192

Table 21-3. PWM Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x0A4	PWM1GENB	R/W	0x0000.0000	PWM1 Generator B Control	1195
0x0A8	PWM1DBCTL	R/W	0x0000.0000	PWM1 Dead-Band Control	1198
0x0AC	PWM1DBRISE	R/W	0x0000.0000	PWM1 Dead-Band Rising-Edge Delay	1199
0x0B0	PWM1DBFALL	R/W	0x0000.0000	PWM1 Dead-Band Falling-Edge-Delay	1200
0x0B4	PWM1FLTSRC0	R/W	0x0000.0000	PWM1 Fault Source 0	1201
0x0B8	PWM1FLTSRC1	R/W	0x0000.0000	PWM1 Fault Source 1	1203
0x0BC	PWM1MINFLTPER	R/W	0x0000.0000	PWM1 Minimum Fault Period	1206
0x0C0	PWM2CTL	R/W	0x0000.0000	PWM2 Control	1176
0x0C4	PWM2INTEN	R/W	0x0000.0000	PWM2 Interrupt and Trigger Enable	1181
0x0C8	PWM2RIS	RO	0x0000.0000	PWM2 Raw Interrupt Status	1184
0x0CC	PWM2ISC	R/W1C	0x0000.0000	PWM2 Interrupt Status and Clear	1186
0x0D0	PWM2LOAD	R/W	0x0000.0000	PWM2 Load	1188
0x0D4	PWM2COUNT	RO	0x0000.0000	PWM2 Counter	1189
0x0D8	PWM2CMPA	R/W	0x0000.0000	PWM2 Compare A	1190
0x0DC	PWM2CMPB	R/W	0x0000.0000	PWM2 Compare B	1191
0x0E0	PWM2GENA	R/W	0x0000.0000	PWM2 Generator A Control	1192
0x0E4	PWM2GENB	R/W	0x0000.0000	PWM2 Generator B Control	1195
0x0E8	PWM2DBCTL	R/W	0x0000.0000	PWM2 Dead-Band Control	1198
0x0EC	PWM2DBRISE	R/W	0x0000.0000	PWM2 Dead-Band Rising-Edge Delay	1199
0x0F0	PWM2DBFALL	R/W	0x0000.0000	PWM2 Dead-Band Falling-Edge-Delay	1200
0x0F4	PWM2FLTSRC0	R/W	0x0000.0000	PWM2 Fault Source 0	1201
0x0F8	PWM2FLTSRC1	R/W	0x0000.0000	PWM2 Fault Source 1	1203
0x0FC	PWM2MINFLTPER	R/W	0x0000.0000	PWM2 Minimum Fault Period	1206
0x100	PWM3CTL	R/W	0x0000.0000	PWM3 Control	1176
0x104	PWM3INTEN	R/W	0x0000.0000	PWM3 Interrupt and Trigger Enable	1181
0x108	PWM3RIS	RO	0x0000.0000	PWM3 Raw Interrupt Status	1184
0x10C	PWM3ISC	R/W1C	0x0000.0000	PWM3 Interrupt Status and Clear	1186
0x110	PWM3LOAD	R/W	0x0000.0000	PWM3 Load	1188
0x114	PWM3COUNT	RO	0x0000.0000	PWM3 Counter	1189
0x118	PWM3CMPA	R/W	0x0000.0000	PWM3 Compare A	1190
0x11C	PWM3CMPB	R/W	0x0000.0000	PWM3 Compare B	1191
0x120	PWM3GENA	R/W	0x0000.0000	PWM3 Generator A Control	1192

Table 21-3. PWM Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x124	PWM3GENB	R/W	0x0000.0000	PWM3 Generator B Control	1195
0x128	PWM3DBCTL	R/W	0x0000.0000	PWM3 Dead-Band Control	1198
0x12C	PWM3DBRISE	R/W	0x0000.0000	PWM3 Dead-Band Rising-Edge Delay	1199
0x130	PWM3DBFALL	R/W	0x0000.0000	PWM3 Dead-Band Falling-Edge-Delay	1200
0x134	PWM3FLTSRC0	R/W	0x0000.0000	PWM3 Fault Source 0	1201
0x138	PWM3FLTSRC1	R/W	0x0000.0000	PWM3 Fault Source 1	1203
0x13C	PWM3MINFLTPER	R/W	0x0000.0000	PWM3 Minimum Fault Period	1206
0x800	PWM0FLTSEN	R/W	0x0000.0000	PWM0 Fault Pin Logic Sense	1207
0x804	PWM0FLTSTAT0	-	0x0000.0000	PWM0 Fault Status 0	1208
0x808	PWM0FLTSTAT1	-	0x0000.0000	PWM0 Fault Status 1	1210
0x880	PWM1FLTSEN	R/W	0x0000.0000	PWM1 Fault Pin Logic Sense	1207
0x884	PWM1FLTSTAT0	-	0x0000.0000	PWM1 Fault Status 0	1208
0x888	PWM1FLTSTAT1	-	0x0000.0000	PWM1 Fault Status 1	1210
0x900	PWM2FLTSEN	R/W	0x0000.0000	PWM2 Fault Pin Logic Sense	1207
0x904	PWM2FLTSTAT0	-	0x0000.0000	PWM2 Fault Status 0	1208
0x908	PWM2FLTSTAT1	-	0x0000.0000	PWM2 Fault Status 1	1210
0x980	PWM3FLTSEN	R/W	0x0000.0000	PWM3 Fault Pin Logic Sense	1207
0x984	PWM3FLTSTAT0	-	0x0000.0000	PWM3 Fault Status 0	1208
0x988	PWM3FLTSTAT1	-	0x0000.0000	PWM3 Fault Status 1	1210

## 21.6 Register Descriptions

The remainder of this section lists and describes the PWM registers, in numerical order by address offset.

### Register 1: PWM Master Control (PWMCTL), offset 0x000

This register provides master control over the PWM generation blocks.


PWM Master Control (PWMCTL)

PWM0 base: 0x4002.8000 Offset 0x000

3

**GLOBALSYNC3** 

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

0

#### Value Description

Update PWM Generator 3

- Any queued update to a load or comparator register in PWM generator 3 is applied the next time the corresponding counter becomes zero.
- 0 No effect.

This bit automatically clears when the updates have completed; it cannot be cleared by software.

2 GLOBALSYNC2 R/W 0 Update PWM Generator 2

R/W

#### Value Description

- Any queued update to a load or comparator register in PWM generator 2 is applied the next time the corresponding counter becomes zero.
- No effect. 0

This bit automatically clears when the updates have completed; it cannot be cleared by software.

Bit/Field	Name	Туре	Reset	Description
1	GLOBALSYNC1	R/W	0	Update PWM Generator 1
				Value Description
				Any queued update to a load or comparator register in PWM generator 1 is applied the next time the corresponding counter becomes zero.
				0 No effect.
				This bit automatically clears when the updates have completed; it cannot be cleared by software.
0	GLOBALSYNC0	R/W	0	Update PWM Generator 0
				Value Description
				Any queued update to a load or comparator register in PWM generator 0 is applied the next time the corresponding counter becomes zero.
				0 No effect.
				This bit automatically clears when the updates have completed; it cannot

be cleared by software.

be


# Register 2: PWM Time Base Sync (PWMSYNC), offset 0x004

This register provides a method to perform synchronization of the counters in the PWM generation blocks. Setting a bit in this register causes the specified counter to reset back to 0; setting multiple bits resets multiple counters simultaneously. The bits auto-clear after the reset has occurred; reading them back as zero indicates that the synchronization has completed.

PWM Time Base Sync (PWMSYNC)

PWM0 base: 0x4002.8000

Offset 0x004 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.
3	SYNC3	R/W	0	Reset Generator 3 Counter
				Value Description
				1 Resets the PWM generator 3 counter.
				0 No effect.
2	SYNC2	R/W	0	Reset Generator 2 Counter
				Value Description
				1 Resets the PWM generator 2 counter.
				0 No effect.
1	SYNC1	R/W	0	Reset Generator 1 Counter
				Value Description
				1 Resets the PWM generator 1 counter.
				0 No effect.
0	SYNC0	R/W	0	Reset Generator 0 Counter
				Value Description
				1 Resets the PWM generator 0 counter.
				0 No effect.

# Register 3: PWM Output Enable (PWMENABLE), offset 0x008


This register provides a master control of which generated pwmA' and pwmB' signals are output to the PWMn pins. By disabling a PWM output, the generation process can continue (for example, when the time bases are synchronized) without driving PWM signals to the pins. When bits in this register are set, the corresponding pwmA' or pwmB' signal is passed through to the output stage. When bits are clear, the pwmA' or pwmB' signal is replaced by a zero value which is also passed to the output stage. The **PWMINVERT** register controls the output stage, so if the corresponding bit is set in that register, the value seen on the PWMn signal is inverted from what is configured by the bits in this register. Updates to the bits in this register can be immediate or locally or globally synchronized to the next synchronous update as controlled by the ENUPDn fields in the **PWMENUPD** register.

#### PWM Output Enable (PWMENABLE)

PWM0 base: 0x4002.8000

Offset 0x008

Type R/W, reset 0x0000.0000



1

0

The generated pwm2B' signal is passed to the PWM5 pin.

The PWM5 signal has a zero value.

Bit/Field	Name	Туре	Reset	Description
4	PWM4EN	R/W	0	₽₩M4 Output Enable
				Value Description  The generated pwm2A' signal is passed to the PWM4 pin.  The PWM4 signal has a zero value.
3	PWM3EN	R/W	0	PWM3 Output Enable
				Value Description  The generated pwm1B' signal is passed to the PWM3 pin.  The PWM3 signal has a zero value.
2	PWM2EN	R/W	0	PWM2 Output Enable
				Value Description  The generated pwm1A' signal is passed to the PWM2 pin.  The PWM2 signal has a zero value.
1	PWM1EN	R/W	0	PWM1 Output Enable
				Value Description  The generated pwm0B' signal is passed to the PWM1 pin.  The PWM1 signal has a zero value.
0	PWM0EN	R/W	0	₽wмо Output Enable
				Value Description  The generated pwm0A' signal is passed to the PWM0 pin.  The PWM0 signal has a zero value.

# Register 4: PWM Output Inversion (PWMINVERT), offset 0x00C


This register provides a master control of the polarity of the PWMn signals on the device pins. The pwmA' and pwmB' signals generated by the PWM generator are active High; but can be made active Low via this register. Disabled PWM channels are also passed through the output inverter (if so configured) so that inactive signals can be High. In addition, if the **PWMFAULT** register enables a specific value to be placed on the PWMn signals during a fault condition, that value is inverted if the corresponding bit in this register is set.

## PWM Output Inversion (PWMINVERT)

PWM0 base: 0x4002.8000

Offset 0x00C

Type R/W, reset 0x0000.0000



0

The PWM4 signal is not inverted.

Bit/Field	Name	Туре	Reset	Description
3	PWM3INV	R/W	0	Invert PWM3 Signal
				Value Description  1 The PWM3 signal is inverted.
				0 The PWM3 signal is not inverted.
2	PWM2INV	R/W	0	Invert PWM2 Signal
				Value Description  1 The PWM2 signal is inverted.  0 The PWM2 signal is not inverted.
				0 The PWM2 signal is not inverted.
1	PWM1INV	R/W	0	Invert PWM1 Signal
				Value Description  1 The PWM1 signal is inverted.  0 The PWM1 signal is not inverted.
0	PWM0INV	R/W	0	Invert PWM0 Signal
				Value Description
				1 The PWM0 signal is inverted.
				0 The PWM0 signal is not inverted.

## Register 5: PWM Output Fault (PWMFAULT), offset 0x010

25

This register controls the behavior of the PWMn outputs in the presence of fault conditions. Both the fault inputs (FAULTn pins and digital comparator outputs) and debug events are considered fault conditions. On a fault condition, each pwmA' or pwmB' signal can be passed through unmodified or driven to the value specified by the corresponding bit in the **PWMFAULTVAL** register. For outputs that are configured for pass-through, the debug event handling on the corresponding PWM generator also determines if the pwmA' or pwmB' signal continues to be generated.

Fault condition control occurs before the output inverter, so PWM signals driven to a specified value on fault are inverted if the channel is configured for inversion (therefore, the pin is driven to the logical complement of the specified value on a fault condition).

22

20

19

18

17

16

### PWM Output Fault (PWMFAULT)

30

28

27


PWM0 base: 0x4002.8000

Offset 0x010

6

5

Type R/W, reset 0x0000.0000



PWM6 Fault

Value Description

The PWM6 output signal is driven to the value specified by the PWM6 bit in the **PWMFAULTVAL** register.

The generated pwm3A' signal is passed to the PWM6 pin.

FAULT5 R/W 0 PWM5 Fault

R/W

0

FAULT6

- The PWM5 output signal is driven to the value specified by the PWM5 bit in the **PWMFAULTVAL** register.
- The generated pwm2B' signal is passed to the PWM5 pin.

Bit/Field	Name	Туре	Reset	Description
4	FAULT4	R/W	0	PWM4 Fault
				Value Description
				The PWM4 output signal is driven to the value specified by the PWM4 bit in the <b>PWMFAULTVAL</b> register.
				0 The generated pwm2A' signal is passed to the PWM4 pin.
3	FAULT3	R/W	0	PWM3 Fault
				Value Description
				The PWM3 output signal is driven to the value specified by the PWM3 bit in the <b>PWMFAULTVAL</b> register.
				0 The generated pwm1B' signal is passed to the PWM3 pin.
2	FAULT2	R/W	0	PWM2 Fault
				Value Description
				The PWM2 output signal is driven to the value specified by the PWM2 bit in the <b>PWMFAULTVAL</b> register.
				0 The generated pwm1A' signal is passed to the PWM2 pin.
1	FAULT1	R/W	0	PWM1 Fault
				Value Description
				The PWM1 output signal is driven to the value specified by the PWM1 bit in the <b>PWMFAULTVAL</b> register.
				0 The generated pwm0B' signal is passed to the PWM1 pin.
0	FAULT0	R/W	0	PWM0 Fault
				Value Description
				The PWM0 output signal is driven to the value specified by the PWM0 bit in the <b>PWMFAULTVAL</b> register.
				0 The generated pwm0A' signal is passed to the ₽WM0 pin.

## Register 6: PWM Interrupt Enable (PWMINTEN), offset 0x014

This register controls the global interrupt generation capabilities of the PWM module. The events that can cause an interrupt are the fault input and the individual interrupts from the PWM generators.

**Note:** The "n" in the INTFAULTn and INTPWMn bits in this register correspond to the PWM generators, not to the FAULTn signals.

## PWM Interrupt Enable (PWMINTEN)


INTFAULT3

PWM0 base: 0x4002.8000

Offset 0x014

19

Type R/W, reset 0x0000.0000



# Interrupt Fault 3 Value Description

1 An interrupt is sent to the interrupt controller when the fault condition for PWM generator 3 is asserted.

preserved across a read-modify-write operation.

- The fault condition for PWM generator 3 is suppressed and not sent to the interrupt controller.
- 18 INTFAULT2 R/W 0 Interrupt Fault 2

R/W

0

## Value Description

- An interrupt is sent to the interrupt controller when the fault condition for PWM generator 2 is asserted.
- The fault condition for PWM generator 2 is suppressed and not sent to the interrupt controller.
- 17 INTFAULT1 R/W 0 Interrupt Fault 1

- An interrupt is sent to the interrupt controller when the fault condition for PWM generator 1 is asserted.
- The fault condition for PWM generator 1 is suppressed and not sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
16	INTFAULT0	R/W	0	Interrupt Fault 0
				Value Description
				An interrupt is sent to the interrupt controller when the fault condition for PWM generator 0 is asserted.
				O The fault condition for PWM generator 0 is suppressed and not sent to the interrupt controller.
15:4	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INTPWM3	R/W	0	PWM3 Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the PWM generator 3 block asserts an interrupt.
				The PWM generator 3 interrupt is suppressed and not sent to the interrupt controller.
2	INTPWM2	R/W	0	PWM2 Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the PWM generator 2 block asserts an interrupt.
				0 The PWM generator 2 interrupt is suppressed and not sent to the interrupt controller.
1	INTPWM1	R/W	0	PWM1 Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the PWM generator 1 block asserts an interrupt.
				The PWM generator 1 interrupt is suppressed and not sent to the interrupt controller.
0	INTPWM0	R/W	0	PWM0 Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the PWM generator 0 block asserts an interrupt.
				0 The PWM generator 0 interrupt is suppressed and not sent to the interrupt controller.

# Register 7: PWM Raw Interrupt Status (PWMRIS), offset 0x018

This register provides the current set of interrupt sources that are asserted, regardless of whether they are enabled to cause an interrupt to be asserted to the interrupt controller. The fault interrupt is asserted based on the fault condition source that is specified by the **PWMnCTL**, **PWMnFLTSRC0** and **PWMnFLTSRC1** registers. The fault interrupt is latched on detection and must be cleared through the **PWM Interrupt Status and Clear (PWMISC)** register. The actual value of the FAULTn signals can be observed using the **PWMSTATUS** register.


The PWM generator interrupts simply reflect the status of the PWM generators and are cleared via the interrupt status register in the PWM generator blocks. If a bit is set, the event is active; if a bit is clear the event is not active.

### PWM Raw Interrupt Status (PWMRIS)

Name

PWM0 base: 0x4002.8000 Offset 0x018

Bit/Field



Description

31:20	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19	INTFAULT3	RO	0	Interrupt Fault PWM 3
				Value Description

Reset

1 The fault condition for PWM generator 3 is asserted.

0 The fault condition for PWM generator 3 has not been asserted.

This bit is cleared by writing a 1 to the  ${\tt INTFAULT3}$  bit in the **PWMISC** register.

18 INTFAULT2 RO 0 Interrupt Fault PWM 2

Type

#### Value Description

- 1 The fault condition for PWM generator 2 is asserted.
- 0 The fault condition for PWM generator 2 has not been asserted.

This bit is cleared by writing a 1 to the  ${\tt INTFAULT2}$  bit in the  ${\tt PWMISC}$  register.

Bit/Field	Name	Туре	Reset	Description
17	INTFAULT1	RO	0	Interrupt Fault PWM 1
				Value Description
				1 The fault condition for PWM generator 1 is asserted.
				The fault condition for PWM generator 1 has not been asserted.
				This bit is cleared by writing a 1 to the INTFAULT1 bit in the <b>PWMISC</b> register.
16	INTFAULT0	RO	0	Interrupt Fault PWM 0
				Value Description
				1 The fault condition for PWM generator 0 is asserted.
				0 The fault condition for PWM generator 0 has not been asserted.
				This bit is cleared by writing a 1 to the INTFAULT0 bit in the <b>PWMISC</b> register.
15:4	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INTPWM3	RO	0	PWM3 Interrupt Asserted
				Value Description
				1 The PWM generator 3 block interrupt is asserted.
				The PWM generator 3 block interrupt has not been asserted.
				The <b>PWM3RIS</b> register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the <b>PWM3ISC</b> register.
2	INTPWM2	RO	0	PWM2 Interrupt Asserted
				Value Description
				The PWM generator 2 block interrupt is asserted.
				The PWM generator 2 block interrupt has not been asserted.
				The <b>PWM2RIS</b> register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the <b>PWM2ISC</b> register.
1	INTPWM1	RO	0	PWM1 Interrupt Asserted
				Value Description
				<ol> <li>The PWM generator 1 block interrupt is asserted.</li> </ol>
				The PWM generator 1 block interrupt has not been asserted.

The **PWM1RIS** register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the **PWM1ISC** register.

Bit/Field		Туре	Reset	Description
0 IN	TPWM0	RO	0	PWM0 Interrupt Asserted
				Value Description  1 The PWM generator 0 block interrupt is asserted.  0 The PWM generator 0 block interrupt has not been asserted.  The PWM0RIS register shows the source of this interrupt. This bit is

The **PWM0RIS** register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the **PWM0ISC** register.

# Register 8: PWM Interrupt Status and Clear (PWMISC), offset 0x01C

This register provides a summary of the interrupt status of the individual PWM generator blocks. If a fault interrupt is set, the corresponding FAULTn input has caused an interrupt. For the fault interrupt, a write of 1 to that bit position clears the latched interrupt status. If an block interrupt bit is set, the corresponding generator block is asserting an interrupt. The individual interrupt status registers, **PWMnISC**, in each block must be consulted to determine the reason for the interrupt and used to clear the interrupt.

PWM Interrupt Status and Clear (PWMISC)

PWM0 base: 0x4002.8000

Offset 0x01C

Type R/W1C, reset 0x0000.0000

,,	,															
_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
				1	i I	res	erved			'	1	1	INTFAULT3	INTFAULT2	INTFAULT1	INTFAULT0
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W1C 0	R/W1C 0	R/W1C 0	R/W1C 0
Reset	U	U	U	U	U	U	U	U	U	U	U	U	U	U	U	U
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	1		ı	1	' 	reserved				'	1	1	INTPWM3	INTPWM2	INTPWM1	INTPWM0
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO 0	RO	RO	RO 0	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	U	0	0	U	0	0	0
В	Bit/Field		Nam	ne	Ту	ре	Reset	Des	cription							
	31:20		reserv	ved	RO		0x000	com	Software should not rely on the value of a reserved bit. To provid compatibility with future products, the value of a reserved bit should preserved across a read-modify-write operation.							
	19		INTFAL	JLT3	R/W	R/W1C		FAU	FAULT3 Interrupt Asserted							
								Valu	ie Desc	cription						
								1			nterrupt to		ult condi	ition for F	PWM ge	nerator
								0		fault con not enal		PWM ge	enerator	3 has no	t been a	sserted
								Writi regis	-	o this bit	clears it	and the	INTFAU	LT3 bit i	n the PV	VMRIS
	18		INTFAL	JLT2	R/W	/1C	0	FAU	LT2 Inte	errupt As	serted					
								Valu	ie Desc	cription						
								1	An e	nabled i	nterrupt 1	for the fa	ult condi	ition for F	PWM ge	nerator

- An enabled interrupt for the fault condition for PWM generator 2 is asserted or is latched.
- The fault condition for PWM generator 2 has not been asserted or is not enabled.

Writing a 1 to this bit clears it and the  ${\tt INTFAULT2}$  bit in the PWMRIS register.

Bit/Field	Name	Туре	Reset	Description
17	INTFAULT1	R/W1C	0	FAULT1 Interrupt Asserted
				Value Description
				An enabled interrupt for the fault condition for PWM generator 1 is asserted or is latched.
				The fault condition for PWM generator 1 has not been asserted or is not enabled.
				Writing a 1 to this bit clears it and the INTFAULT1 bit in the <b>PWMRIS</b> register.
16	INTFAULT0	R/W1C	0	FAULT0 Interrupt Asserted
				Value Description
				An enabled interrupt for the fault condition for PWM generator 0 is asserted or is latched.
				The fault condition for PWM generator 0 has not been asserted or is not enabled.
				Writing a 1 to this bit clears it and the INTFAULTO bit in the <b>PWMRIS</b> register.
15:4	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INTPWM3	RO	0	PWM3 Interrupt Status
				Value Description
				1 An enabled interrupt for the PWM generator 3 block is asserted.
				The PWM generator 3 block interrupt is not asserted or is not enabled.
				The <b>PWM3RIS</b> register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the <b>PWM3ISC</b> register.
2	INTPWM2	RO	0	PWM2 Interrupt Status
				Value Description
				1 An enabled interrupt for the PWM generator 2 block is asserted.
				The PWM generator 2 block interrupt is not asserted or is not enabled.
				The <b>PWM2RIS</b> register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the <b>PWM2ISC</b> register.
1	INTPWM1	RO	0	PWM1 Interrupt Status
				Value Description
				1 An enabled interrupt for the PWM generator 1 block is asserted.
				The PWM generator 1 block interrupt is not asserted or is not enabled.
				The <b>PWM1RIS</b> register shows the source of this interrupt. This bit is

cleared by writing a 1 to the corresponding bit in the **PWM1ISC** register.

Bit/Field	Name	Туре	Reset	Description
0	INTPWM0	RO	0	PWM0 Interrupt Status
				<ul> <li>Value Description</li> <li>An enabled interrupt for the PWM generator 0 block is asserted.</li> <li>The PWM generator 0 block interrupt is not asserted or is not enabled.</li> </ul>
				The <b>PWM0RIS</b> register shows the source of this interrupt. This bit is cleared by writing a 1 to the corresponding bit in the <b>PWM0ISC</b> register.

# Register 9: PWM Status (PWMSTATUS), offset 0x020


This register provides the unlatched status of the PWM generator fault condition.

## PWM Status (PWMSTATUS)

PWM0 base: 0x4002.8000

Offset 0x020

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	FAULT3	RO	0	Generator 3 Fault Status
				Value Description
				1 The fault condition for PWM generator 3 is asserted.
				If the FLTSRC bit in the <b>PWM3CTL</b> register is clear, the input is the source of the fault condition, and is therefore asserted.
				The fault condition for PWM generator 3 is not asserted.
2	FAULT2	RO	0	Generator 2 Fault Status
				Value Description
				1 The fault condition for PWM generator 2 is asserted.
				If the FLTSRC bit in the <b>PWM2CTL</b> register is clear, the input is the source of the fault condition, and is therefore asserted.
				0 The fault condition for PWM generator 2 is not asserted.
1	FAULT1	RO	0	Generator 1 Fault Status

- The fault condition for PWM generator 1 is asserted.

  If the FLTSRC bit in the **PWM1CTL** register is clear, the input is the source of the fault condition, and is therefore asserted.
- 0 The fault condition for PWM generator 1 is not asserted.

Bit/Field	Name	Туре	Reset	Description			
0	FAULT0	RO	0	Generator 0 Fault Status			
				Value Description  The fault condition for PWM generator 0 is asserted.  If the FLTSRC bit in the <b>PWM0CTL</b> register is clear, the input is the source of the fault condition, and is therefore asserted.  The fault condition for PWM generator 0 is not asserted.			

# Register 10: PWM Fault Condition Value (PWMFAULTVAL), offset 0x024

This register specifies the output value driven on the PWMn signals during a fault condition if enabled by the corresponding bit in the **PWMFAULT** register. Note that if the corresponding bit in the **PWMINVERT** register is set, the output value is driven to the logical NOT of the bit value in this register.


## PWM Fault Condition Value (PWMFAULTVAL)

PWM0 base: 0x4002.8000

Offset 0x024

6

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description	
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.	
7	PWM7	R/W	0	РWM7 Fault Value	
				Value Description	
				The PWM7 output signal is driven High during fault conditions if the FAULT7 bit in the <b>PWMFAULT</b> register is set.	
				The PWM7 output signal is driven Low during fault conditions if the FAULT7 bit in the <b>PWMFAULT</b> register is set.	

PWM6 R/W 0 PWM6 Fault Value

#### Value Description

- 1 The PWM6 output signal is driven High during fault conditions if the FAULT6 bit in the PWMFAULT register is set.
- The PWM6 output signal is driven Low during fault conditions if the FAULT6 bit in the PWMFAULT register is set.
- 5 PWM5 R/W 0 PWM5 Fault Value

- 1 The PWM5 output signal is driven High during fault conditions if the FAULT5 bit in the PWMFAULT register is set.
- The PWM5 output signal is driven Low during fault conditions if the FAULT5 bit in the PWMFAULT register is set.

Bit/Field	Name	Type	Reset	Description
4	PWM4	R/W	0	₽₩M4 Fault Value
				Value Description
				The PWM4 output signal is driven High during fault conditions if the FAULT4 bit in the PWMFAULT register is set.
				O The PWM4 output signal is driven Low during fault conditions if the FAULT4 bit in the <b>PWMFAULT</b> register is set.
3	PWM3	R/W	0	PWM3 Fault Value
				Value Description
				1 The PWM3 output signal is driven High during fault conditions if the FAULT3 bit in the PWMFAULT register is set.
				O The PWM3 output signal is driven Low during fault conditions if the FAULT3 bit in the <b>PWMFAULT</b> register is set.
2	PWM2	R/W	0	PWM2 Fault Value
				Value Description
				The PWM2 output signal is driven High during fault conditions if the FAULT2 bit in the PWMFAULT register is set.
				O The PWM2 output signal is driven Low during fault conditions if the FAULT2 bit in the <b>PWMFAULT</b> register is set.
1	PWM1	R/W	0	PWM1 Fault Value
				Value Description
				The PWM1 output signal is driven High during fault conditions if the FAULT1 bit in the PWMFAULT register is set.
				O The PWM1 output signal is driven Low during fault conditions if the FAULT1 bit in the <b>PWMFAULT</b> register is set.
0	PWM0	R/W	0	PWM0 Fault Value
				Value Description
				1 The PWM0 output signal is driven High during fault conditions if the FAULT0 bit in the <b>PWMFAULT</b> register is set.
				The PWM0 output signal is driven Low during fault conditions if the FAULT0 bit in the PWMFAULT register is set.

# Register 11: PWM Enable Update (PWMENUPD), offset 0x028


This register specifies when updates to the PWMnEN bit in the **PWMENABLE** register are performed. The PWMnEN bit enables the pwmA' or pwmB' output to be passed to the microcontroller's pin. Updates can be immediate or locally or globally synchronized to the next synchronous update.

## PWM Enable Update (PWMENUPD)

PWM0 base: 0x4002.8000

Offset 0x028

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:14	FNUPD7	R/W	0	PWM7 Fnable Undate Mode

Value Description

0x0 Immediate

Writes to the PWM7EN bit in the **PWMENABLE** register are used by the PWM generator immediately.

0x1 Reserved

0x2 Locally Synchronized

Writes to the PWM7EN bit in the **PWMENABLE** register are used by the PWM generator the next time the counter is 0.

0x3 Globally Synchronized

Writes to the PWM7EN bit in the **PWMENABLE** register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control (**PWMCTL**) register.

Bit/Field	Name	Туре	Reset	Description
13:12	ENUPD6	R/W	0	PWM6 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM6EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM6EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM6EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.
11:10	ENUPD5	R/W	0	PWM5 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM5EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM5EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM5EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.
9:8	ENUPD4	R/W	0	PWM4 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM4EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM4EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM4EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.

Bit/Field	Name	Туре	Reset	Description
7:6	ENUPD3	R/W	0	PWM3 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM3EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM3EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM3EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.
5:4	ENUPD2	R/W	0	PWM2 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM2EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM2EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM2EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.
3:2	ENUPD1	R/W	0	PWM1 Enable Update Mode
				Value Description
				0x0 Immediate
				Writes to the PWM1EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.
				0x1 Reserved
				0x2 Locally Synchronized
				Writes to the PWM1EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.
				0x3 Globally Synchronized
				Writes to the PWM1EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.

Bit/Field	Name	Туре	Reset	Description				
1:0	ENUPD0	R/W	0	PWM0 Enable Update Mode				
				Value Description				
				0x0 Immediate				
				Writes to the PWM0EN bit in the <b>PWMENABLE</b> register are used by the PWM generator immediately.				
				0x1 Reserved				
				0x2 Locally Synchronized				
				Writes to the PWM0EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0.				
				0x3 Globally Synchronized				
				Writes to the PWM0EN bit in the <b>PWMENABLE</b> register are used by the PWM generator the next time the counter is 0 after a synchronous update has been requested through the PWM Master Control ( <b>PWMCTL</b> ) register.				

Register 12: PWM0 Control (PWM0CTL), offset 0x040

Register 13: PWM1 Control (PWM1CTL), offset 0x080

Register 14: PWM2 Control (PWM2CTL), offset 0x0C0

Register 15: PWM3 Control (PWM3CTL), offset 0x100

These registers configure the PWM signal generation blocks (PWM0CTL controls the PWM generator 0 block, and so on). The Register Update mode, Debug mode, Counting mode, and Block Enable mode are all controlled via these registers. The blocks produce the PWM signals, which can be either two independent PWM signals (from the same counter), or a paired set of PWM signals with dead-band delays added.

The PWM0 block produces the PWM0 and PWM1 outputs, the PWM1 block produces the PWM2 and PWM3 outputs, the PWM2 block produces the PWM4 and PWM5 outputs, and the PWM3 block produces the PWM6 and PWM7 outputs.

## PWM0 Control (PWM0CTL)

PWM0 base: 0x4002.8000 Offset 0x040 Type R/W, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
							reserved				1			LATCH	MINFLTPER	FLTSRC
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W	R/W	R/W
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	DBFAL	LUPD	DBRIS	EUPD	DBCT	LUPD	GEN	BUPD	GENA	AUPD	CMPBUPD	CMPAUPD	LOADUPD	DEBUG	MODE	ENABLE
Type	R/W 0	R/W	R/W	R/W	R/W 0	R/W	R/W 0	R/W 0	R/W 0	R/W	R/W	R/W 0	R/W	R/W	R/W	R/W 0
Reset	U	U	0	U	U	U	U	U	U	U	0	U	0	U	U	U

Bit/Field	Name	Type	Reset	Description
31:19	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
18	LATCH	R/W	0	Latch Fault Input

- Fault Condition Not Latched
   A fault condition is in effect for as long as the generating source is asserting.
- Fault Condition Latched

  A fault condition is set as the result of the assertion of the faulting source and is held (latched) while the **PWMISC**INTFAULTD bit is set. Clearing the INTFAULTD bit clears the fault condition.

Bit/Field	Name	Туре	Reset	Description
17	MINFLTPER	R/W	0	Minimum Fault Period
				This bit specifies that the PWM generator enables a one-shot counter to provide a minimum fault condition period.
				The timer begins counting on the rising edge of the fault condition to extend the condition for a minimum duration of the count value. The timer ignores the state of the fault condition while counting.
				The minimum fault delay is in effect only when the MINFLTPER bit is set. If a detected fault is in the process of being extended when the MINFLTPER bit is cleared, the fault condition extension is aborted.
				The delay time is specified by the <b>PWMnMINFLTPER</b> register MFP field value. The effect of this is to pulse stretch the fault condition input.
				The delay value is defined by the PWM clock period. Because the fault input is not synchronized to the PWM clock, the period of the time is PWMClock * (MFP value + 1) or PWMClock * (MFP value + 2).
				The delay function makes sense only if the fault source is unlatched. A latched fault source makes the fault condition appear asserted until cleared by software and negates the utility of the extend feature. It applies to all fault condition sources as specified in the FLTSRC field.
				Value Description
				The FAULT input deassertion is unaffected.
				The <b>PWMnMINFLTPER</b> one-shot counter is active and extends the period of the fault condition to a minimum period.
16	FLTSRC	R/W	0	Fault Condition Source
				Value Description
				0 The Fault condition is determined by the Fault0 input.
				The Fault condition is determined by the configuration of the <b>PWMnFLTSRC0</b> and <b>PWMnFLTSRC1</b> registers.
15:14	DBFALLUPD	R/W	0x0	PWMnDBFALL Update Mode
				Value Description
				0x0 Immediate
				The <b>PWMnDBFALL</b> register value is immediately updated on a write.
				0x1 Reserved
				0x2 Locally Synchronized
				Updates to the register are reflected to the generator the next time the counter is 0.
				0x3 Globally Synchronized
				Updates to the register are delayed until the next time the counter is 0 after a synchronous update has been requested through the <b>PWMCTL</b> register.

Bit/Field	Name	Туре	Reset	Description				
13:12	DBRISEUPD	R/W	0x0	PWMnDBRISE Update Mode				
				Value Description  0x0 Immediate     The PWMnDBRISE register value is immediately updated on a write.  0x1 Reserved  0x2 Locally Synchronized     Updates to the register are reflected to the generator the next time the counter is 0.  0x3 Globally Synchronized     Updates to the register are delayed until the next time the counter is 0 after a synchronous update has been requested through the PWMCTL register.				
11:10	DBCTLUPD	R/W	0x0	PWMnDBCTL Update Mode  Value Description  0x0 Immediate     The PWMnDBCTL register value is immediately updated on a write.  0x1 Reserved  0x2 Locally Synchronized     Updates to the register are reflected to the generator the next time the counter is 0.  0x3 Globally Synchronized     Updates to the register are delayed until the next time the counter is 0 after a synchronous update has been requested through the PWMCTL register.				
9:8	GENBUPD	R/W	0x0	PWMnGENB Update Mode  Value Description  0x0 Immediate     The PWMnGENB register value is immediately updated on a write.  0x1 Reserved  0x2 Locally Synchronized     Updates to the register are reflected to the generator the next time the counter is 0.  0x3 Globally Synchronized     Updates to the register are delayed until the next time the counter is 0 after a synchronous update has been requested through the PWMCTL register.				

Bit/Field	Name	Туре	Reset	Description	
7:6	GENAUPD	R/W	0x0	PWMnGENA Update M	lode
				Value Description	on
				0x0 Immediate	e
				The <b>PWM</b> on a write	InGENA register value is immediately updated s.
				0x1 Reserved	
				0x2 Locally Sy	ynchronized
				·	o the register are reflected to the generator the the counter is 0.
				0x3 Globally S	Synchronized
				the count	to the register are delayed until the next time er is 0 after a synchronous update has been at through the <b>PWMCTL</b> register.
5	CMPBUPD	R/W	0	Comparator B Update N	Mode
				Value Description	
				0 Locally Synchro	nized
				•	<b>PWMnCMPB</b> register are reflected to the ext time the counter is 0.
				1 Globally Synchr	onized
				•	register are delayed until the next time the r a synchronous update has been requested MCTL register.
4	CMPAUPD	R/W	0	Comparator A Update N	Mode
				Value Description	
				0 Locally Synchro	nized
				•	PWMnCMPA register are reflected to the ext time the counter is 0.
				1 Globally Synchr	onized
				-	register are delayed until the next time the or a synchronous update has been requested MCTL register.
3	LOADUPD	R/W	0	Load Register Update N	Mode
				Value Description	
				0 Locally Synchro	nized
				Updates to the	<b>PWMnLOAD</b> register are reflected to the ext time the counter is 0.
				1 Globally Synchr	onized
					register are delayed until the next time the er a synchronous update has been requested MCTL register.

Bit/Field	Name	Туре	Reset	Description
2	DEBUG	R/W	0	Debug Mode
				Value Description
				The counter stops running when it next reaches 0 and continues running again when no longer in Debug mode.
				1 The counter always runs when in Debug mode.
1	MODE	R/W	0	Counter Mode
				Value Description
				The counter counts down from the load value to 0 and then wraps back to the load value (Count-Down mode).
				1 The counter counts up from 0 to the load value, back down to 0, and then repeats (Count-Up/Down mode).
0	ENABLE	R/W	0	PWM Block Enable
				Value Description
				0 The entire PWM generation block is disabled and not clocked.

1

signals.

The PWM generation block is enabled and produces PWM

Register 16: PWM0 Interrupt and Trigger Enable (PWM0INTEN), offset 0x044 Register 17: PWM1 Interrupt and Trigger Enable (PWM1INTEN), offset 0x084 Register 18: PWM2 Interrupt and Trigger Enable (PWM2INTEN), offset 0x0C4 Register 19: PWM3 Interrupt and Trigger Enable (PWM3INTEN), offset 0x104

These registers control the interrupt and ADC trigger generation capabilities of the PWM generators (**PWM0INTEN** controls the PWM generator 0 block, and so on). The events that can cause an interrupt,or an ADC trigger are:

- The counter being equal to the load register
- The counter being equal to zero
- The counter being equal to the **PWMnCMPA** register while counting up
- The counter being equal to the **PWMnCMPA** register while counting down
- The counter being equal to the **PWMnCMPB** register while counting up
- The counter being equal to the **PWMnCMPB** register while counting down


Any combination of these events can generate either an interrupt or an ADC trigger, though no determination can be made as to the actual event that caused an ADC trigger if more than one is specified. The **PWMnRIS** register provides information about which events have caused raw interrupts.

#### PWM0 Interrupt and Trigger Enable (PWM0INTEN)

PWM0 base: 0x4002.8000

Offset 0x044

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:14	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	TRCMPBD	R/W	0	Trigger for Counter= <b>PWMnCMPB</b> Down

- An ADC trigger pulse is output when the counter matches the value in the **PWMnCMPB** register value while counting down.
- 0 No ADC trigger is output.

Bit/Field	Name	Туре	Reset	Description
12	TRCMPBU	R/W	0	Trigger for Counter= <b>PWMnCMPB</b> Up
				Value Description
				An ADC trigger pulse is output when the counter matches the value in the <b>PWMnCMPB</b> register value while counting up.
				0 No ADC trigger is output.
11	TRCMPAD	R/W	0	Trigger for Counter= <b>PWMnCMPA</b> Down
				Value Description
				An ADC trigger pulse is output when the counter matches the value in the <b>PWMnCMPA</b> register value while counting down.
				0 No ADC trigger is output.
10	TRCMPAU	R/W	0	Trigger for Counter= <b>PWMnCMPA</b> Up
				Value Description
				An ADC trigger pulse is output when the counter matches the value in the <b>PWMnCMPA</b> register value while counting up.
				0 No ADC trigger is output.
9	TRCNTLOAD	R/W	0	Trigger for Counter= <b>PWMnLOAD</b>
				Value Description
				1 An ADC trigger pulse is output when the counter matches the PWMnLOAD register.
				0 No ADC trigger is output.
8	TRCNTZERO	R/W	0	Trigger for Counter=0
				Value Description
				1 An ADC trigger pulse is output when the counter is 0.
				0 No ADC trigger is output.
7:6	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
5	INTCMPBD	R/W	0	Interrupt for Counter= <b>PWMnCMPB</b> Down
				Value Description
				A raw interrupt occurs when the counter matches the value in the <b>PWMnCMPB</b> register value while counting down.
				0 No interrupt.

Bit/Field	Name	Туре	Reset	Description
4	INTCMPBU	R/W	0	Interrupt for Counter= <b>PWMnCMPB</b> Up
				Value Description
				A raw interrupt occurs when the counter matches the value in the <b>PWMnCMPB</b> register value while counting up.
				0 No interrupt.
3	INTCMPAD	R/W	0	Interrupt for Counter= <b>PWMnCMPA</b> Down
				Value Description
				A raw interrupt occurs when the counter matches the value in the <b>PWMnCMPA</b> register value while counting down.
				0 No interrupt.
2	INTCMPAU	R/W	0	Interrupt for Counter= <b>PWMnCMPA</b> Up
				Value Description
				A raw interrupt occurs when the counter matches the value in the <b>PWMnCMPA</b> register value while counting up.
				0 No interrupt.
1	INTCNTLOAD	R/W	0	Interrupt for Counter= <b>PWMnLOAD</b>
				Value Description
				A raw interrupt occurs when the counter matches the value in the <b>PWMnLOAD</b> register value.
				0 No interrupt.
0	INTCNTZERO	R/W	0	Interrupt for Counter=0
				Value Description
				1 A raw interrupt occurs when the counter is zero.
				0 No interrupt.

Register 20: PWM0 Raw Interrupt Status (PWM0RIS), offset 0x048

Register 21: PWM1 Raw Interrupt Status (PWM1RIS), offset 0x088

Register 22: PWM2 Raw Interrupt Status (PWM2RIS), offset 0x0C8

Register 23: PWM3 Raw Interrupt Status (PWM3RIS), offset 0x108

These registers provide the current set of interrupt sources that are asserted, regardless of whether they cause an interrupt to be asserted to the controller (**PWM0RIS** controls the PWM generator 0 block, and so on). If a bit is set, the event has occurred; if a bit is clear, the event has not occurred. Bits in this register are cleared by writing a 1 to the corresponding bit in the **PWMnISC** register.

#### PWM0 Raw Interrupt Status (PWM0RIS)

Name

PWM0 base: 0x4002.8000 Offset 0x048

Bit/Field

Type RO, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1	1	i			rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1	'	•	rese	rved		1			INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

31:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Description

5 INTCMPBD RO 0 Comparator B Down Interrupt Status

Reset

Type

Value Description

- 1 The counter has matched the value in the **PWMnCMPB** register while counting down.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the  ${\tt INTCMPBD}$  bit in the  ${\tt PWMnISC}$  register.

4 INTCMPBU RO 0 Comparator B Up Interrupt Status

Value Description

- The counter has matched the value in the **PWMnCMPB** register while counting up.
- 0 An interrupt has not occurred.

This bit is cleared by writing a 1 to the  ${\tt INTCMPBU}$  bit in the  ${\tt PWMnISC}$  register.

Bit/Field	Name	Туре	Reset	Description
3	INTCMPAD	RO	0	Comparator A Down Interrupt Status
				Value Description
				The counter has matched the value in the <b>PWMnCMPA</b> register while counting down.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the INTCMPAD bit in the <b>PWMnISC</b> register.
2	INTCMPAU	RO	0	Comparator A Up Interrupt Status
				Value Description
				The counter has matched the value in the <b>PWMnCMPA</b> register while counting up.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the INTCMPAU bit in the <b>PWMnISC</b> register.
1	INTCNTLOAD	RO	0	Counter=Load Interrupt Status
				Value Description
				1 The counter has matched the value in the <b>PWMnLOAD</b> register.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the INTCNTLOAD bit in the <b>PWMnISC</b> register.
0	INTCNTZERO	RO	0	Counter=0 Interrupt Status
				Value Description
				1 The counter has matched zero.
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the INTCNTZERO bit in the <b>PWMnISC</b> register.

Register 24: PWM0 Interrupt Status and Clear (PWM0ISC), offset 0x04C Register 25: PWM1 Interrupt Status and Clear (PWM1ISC), offset 0x08C Register 26: PWM2 Interrupt Status and Clear (PWM2ISC), offset 0x0CC Register 27: PWM3 Interrupt Status and Clear (PWM3ISC), offset 0x10C

These registers provide the current set of interrupt sources that are asserted to the interrupt controller (PWM0ISC controls the PWM generator 0 block, and so on). A bit is set if the event has occurred and is enabled in the **PWMnINTEN** register; if a bit is clear, the event has not occurred or is not enabled. These are R/W1C registers; writing a 1 to a bit position clears the corresponding interrupt reason.

## PWM0 Interrupt Status and Clear (PWM0ISC)

**INTCMPBD** 

PWM0 base: 0x4002.8000

Offset 0x04C

5

Type R/W1C, reset 0x0000.0000

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1					rese	rved		1		1	1		'
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1	'		rese	rved			 		INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	R/W1C	R/W1C	R/W1C	R/W1C	R/W1C	R/W1C
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
31:6	reserved	RO	0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

#### Value Description

Comparator B Down Interrupt

- The INTCMPBD bits in the **PWMnRIS** and **PWMnINTEN** registers are set, providing an interrupt to the interrupt controller.
- No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the INTCMPBD bit in the PWMnRIS register.

INTCMPBU R/W1C 0 Comparator B Up Interrupt

R/W1C

#### Value Description

- The INTCMPBU bits in the PWMnRIS and PWMnINTEN registers are set, providing an interrupt to the interrupt controller.
- No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the INTCMPBU bit in the PWMnRIS register.

Bit/Field	Name	Туре	Reset	Description
3	INTCMPAD	R/W1C	0	Comparator A Down Interrupt
				Value Description  The INTCMPAD bits in the <b>PWMnRIS</b> and <b>PWMnINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				<ul> <li>No interrupt has occurred or the interrupt is masked.</li> <li>This bit is cleared by writing a 1. Clearing this bit also clears the INTCMPAD bit in the <b>PWMnRIS</b> register.</li> </ul>
2	INTCMPAU	R/W1C	0	Comparator A Up Interrupt
				Value Description
				The INTCMPAU bits in the <b>PWMnRIS</b> and <b>PWMnINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the INTCMPAU bit in the <b>PWMnRIS</b> register.
1	INTCNTLOAD	R/W1C	0	Counter=Load Interrupt
				Value Description
				The INTCNTLOAD bits in the <b>PWMnRIS</b> and <b>PWMnINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the INTCNTLOAD bit in the <b>PWMnRIS</b> register.
0	INTCNTZERO	R/W1C	0	Counter=0 Interrupt
				Value Description
				The INTCNTZERO bits in the <b>PWMnRIS</b> and <b>PWMnINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the INTCNTZERO bit in the <b>PWMnRIS</b> register.

Register 28: PWM0 Load (PWM0LOAD), offset 0x050

Register 29: PWM1 Load (PWM1LOAD), offset 0x090

Register 30: PWM2 Load (PWM2LOAD), offset 0x0D0

Register 31: PWM3 Load (PWM3LOAD), offset 0x110

These registers contain the load value for the PWM counter (**PWM0LOAD** controls the PWM generator 0 block, and so on). Based on the counter mode configured by the MODE bit in the **PWMnCTL** register, this value is either loaded into the counter after it reaches zero or is the limit of up-counting after which the counter decrements back to zero. When this value matches the counter, a pulse is output which can be configured to drive the generation of the pwmA and/or pwmB signal (via the **PWMnGENA/PWMnGENB** register) or drive an interruptor ADC trigger (via the **PWMnINTEN** register).


If the Load Value Update mode is locally synchronized (based on the LOADUPD field encoding in the **PWMnCTL** register), the 16-bit LOAD value is used the next time the counter reaches zero. If the update mode is globally synchronized, it is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is re-written before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Load (PWM0LOAD)

PWM0 base: 0x4002.8000

Offset 0x050

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	LOAD	R/W	0x0000	Counter Load Value

The counter load value.

Register 32: PWM0 Counter (PWM0COUNT), offset 0x054

Register 33: PWM1 Counter (PWM1COUNT), offset 0x094

Register 34: PWM2 Counter (PWM2COUNT), offset 0x0D4

Register 35: PWM3 Counter (PWM3COUNT), offset 0x114

These registers contain the current value of the PWM counter (**PWM0COUNT** is the value of the PWM generator 0 block, and so on). When this value matches zero or the value in the **PWMnLOAD**, **PWMnCMPA**, or **PWMnCMPB** registers, a pulse is output which can be configured to drive the generation of a PWM signal or drive an interrupt or ADC trigger.

#### PWM0 Counter (PWM0COUNT)

PWM0 base: 0x4002.8000 Offset 0x054

Type RO, reset 0x0000.0000

	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
		1	1		i			rese	rved							
Type	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	COUNT															
Туре	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	COUNT	RO	0x0000	Counter Value

The current value of the counter.

Register 36: PWM0 Compare A (PWM0CMPA), offset 0x058

Register 37: PWM1 Compare A (PWM1CMPA), offset 0x098

Register 38: PWM2 Compare A (PWM2CMPA), offset 0x0D8

Register 39: PWM3 Compare A (PWM3CMPA), offset 0x118

These registers contain a value to be compared against the counter (**PWM0CMPA** controls the PWM generator 0 block, and so on). When this value matches the counter, a pulse is output which can be configured to drive the generation of the pwmA and pwmB signals (via the **PWMnGENA** and **PWMnGENB** registers) or drive an interrupt or ADC trigger (via the **PWMnINTEN** register). If the value of this register is greater than the **PWMnLOAD** register (see page 1188), then no pulse is ever output.


If the comparator A update mode is locally synchronized (based on the CMPAUPD bit in the **PWMnCTL** register), the 16-bit COMPA value is used the next time the counter reaches zero. If the update mode is globally synchronized, it is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Compare A (PWM0CMPA)

PWM0 base: 0x4002.8000

Offset 0x058

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:16	reserved	RO	0x00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	COMPA	R/W	0x00	Comparator A Value

The value to be compared against the counter.

Register 40: PWM0 Compare B (PWM0CMPB), offset 0x05C

Register 41: PWM1 Compare B (PWM1CMPB), offset 0x09C

Register 42: PWM2 Compare B (PWM2CMPB), offset 0x0DC

Register 43: PWM3 Compare B (PWM3CMPB), offset 0x11C


These registers contain a value to be compared against the counter (**PWM0CMPB** controls the PWM generator 0 block, and so on). When this value matches the counter, a pulse is output which can be configured to drive the generation of the pwmA and pwmB signals (via the **PWMnGENA** and **PWMnGENB** registers) or drive an interrupt or ADC trigger (via the **PWMnINTEN** register). If the value of this register is greater than the **PWMnLOAD** register, no pulse is ever output.

If the comparator B update mode is locally synchronized (based on the CMPBUPD bit in the **PWMnCTL** register), the 16-bit COMPB value is used the next time the counter reaches zero. If the update mode is globally synchronized, it is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Compare B (PWM0CMPB)

PWM0 base: 0x4002.8000 Offset 0x05C

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	СОМРВ	R/W	0x0000	Comparator B Value

The value to be compared against the counter.

Register 44: PWM0 Generator A Control (PWM0GENA), offset 0x060

Register 45: PWM1 Generator A Control (PWM1GENA), offset 0x0A0

Register 46: PWM2 Generator A Control (PWM2GENA), offset 0x0E0

Register 47: PWM3 Generator A Control (PWM3GENA), offset 0x120

These registers control the generation of the pwmA signal based on the load and zero output pulses from the counter, as well as the compare A and compare B pulses from the comparators (**PWM0GENA** controls the PWM generator 0 block, and so on). When the counter is running in Count-Down mode, only four of these events occur; when running in Count-Up/Down mode, all six occur. These events provide great flexibility in the positioning and duty cycle of the resulting PWM signal.

The **PWM0GENA** register controls generation of the pwm0A signal; **PWM1GENA**, the pwm1A signal; **PWM2GENA**, the pwm2A signal; and **PWM3GENA**, the pwm3A signal.

If a zero or load event coincides with a compare A or compare B event, the zero or load action is taken and the compare A or compare B action is ignored. If a compare A event coincides with a compare B event, the compare A action is taken and the compare B action is ignored.

If the Generator A update mode is immediate (based on the GENAUPD field encoding in the **PWMnCTL** register), the ACTCMPBD, ACTCMPBU, ACTCMPAD, ACTCMPAU, ACTLOAD, and ACTZERO values are used immediately. If the update mode is locally synchronized, these values are used the next time the counter reaches zero. If the update mode is globally synchronized, these values are used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.


#### PWM0 Generator A Control (PWM0GENA)

PWM0 base: 0x4002.8000

Offset 0x060

31:12

Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset Description

reserved

RO

0.0000x0

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Type	Reset	Description
11:10	ACTCMPBD	R/W	0x0	Action for Comparator B Down
				This field specifies the action to be taken when the counter matches comparator B while counting down.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmA.
				0x2 Drive pwmA Low.
				0x3 Drive pwmA High.
9:8	ACTCMPBU	R/W	0x0	Action for Comparator B Up
				This field specifies the action to be taken when the counter matches comparator B while counting up. This action can only occur when the MODE bit in the <b>PWMnCTL</b> register is set.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmA.
				0x2 Drive pwmA Low.
				0x3 Drive pwmA High.
7:6	ACTCMPAD	R/W	0x0	Action for Comparator A Down
				This field specifies the action to be taken when the counter matches comparator A while counting down.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmA.
				0x2 Drive pwmA Low.
				0x3 Drive pwmA High.
5:4	ACTCMPAU	R/W	0x0	Action for Comparator A Up  This field specifies the action to be taken when the counter matches comparator A while counting up. This action can only occur when the MODE bit in the <b>PWMnCTL</b> register is set.
				Value Description
				Value Description
				0x0 Do nothing. 0x1 Invert pwmA.
				0x2 Drive pwmA Low.
				0x3 Drive pwmA High.
				ONO DITVE PWITTA LIIGIT.

Bit/Field	Name	Туре	Reset	Description
3:2	ACTLOAD	R/W	0x0	Action for Counter=LOAD  This field specifies the action to be taken when the counter matches the value in the <b>PWMnLOAD</b> register.
				Value Description  0x0 Do nothing.  0x1 Invert pwmA.  0x2 Drive pwmA Low.  0x3 Drive pwmA High.
1:0	ACTZERO	R/W	0x0	Action for Counter=0 This field specifies the action to be taken when the counter is zero.  Value Description 0x0 Do nothing. 0x1 Invert pwmA. 0x2 Drive pwmA Low. 0x3 Drive pwmA High.

Register 48: PWM0 Generator B Control (PWM0GENB), offset 0x064 Register 49: PWM1 Generator B Control (PWM1GENB), offset 0x0A4 Register 50: PWM2 Generator B Control (PWM2GENB), offset 0x0E4 Register 51: PWM3 Generator B Control (PWM3GENB), offset 0x124

These registers control the generation of the pwmB signal based on the load and zero output pulses from the counter, as well as the compare A and compare B pulses from the comparators (**PWM0GENB** controls the PWM generator 0 block, and so on). When the counter is running in Count-Down mode, only four of these events occur; when running in Count-Up/Down mode, all six occur. These events provide great flexibility in the positioning and duty cycle of the resulting PWM signal.

The **PWM0GENB** register controls generation of the pwm0B signal; **PWM1GENB**, the pwm1B signal; **PWM2GENB**, the pwm2B signal; and **PWM3GENB**, the pwm3B signal.

If a zero or load event coincides with a compare A or compare B event, the zero or load action is taken and the compare A or compare B action is ignored. If a compare A event coincides with a compare B event, the compare B action is taken and the compare A action is ignored.

If the Generator B update mode is immediate (based on the GENBUPD field encoding in the **PWMnCTL** register), the ACTCMPBD, ACTCMPBU, ACTCMPAD, ACTCMPAU, ACTLOAD, and ACTZERO values are used immediately. If the update mode is locally synchronized, these values are used the next time the counter reaches zero. If the update mode is globally synchronized, these values are used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.


#### PWM0 Generator B Control (PWM0GENB)

PWM0 base: 0x4002.8000

Offset 0x064

31:12

Type R/W, reset 0x0000.0000



Bit/Field Name Type Reset Description

reserved

RO

0.0000x0

Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

Bit/Field	Name	Туре	Reset	Description
11:10	ACTCMPBD	R/W	0x0	Action for Comparator B Down
				This field specifies the action to be taken when the counter matches comparator B while counting down.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmB.
				0x2 Drive pwmB Low.
				0x3 Drive pwmB High.
9:8	ACTCMPBU	R/W	0x0	Action for Comparator B Up
				This field specifies the action to be taken when the counter matches comparator B while counting up. This action can only occur when the MODE bit in the <b>PWMnCTL</b> register is set.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmB.
				0x2 Drive pwmB Low.
				0x3 Drive pwmB High.
7:6	ACTCMPAD	R/W	0x0	Action for Comparator A Down
				This field specifies the action to be taken when the counter matches comparator A while counting down.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmB.
				0x2 Drive pwmB Low.
				0x3 Drive pwmB High.
5:4	ACTCMPAU	R/W	0x0	Action for Comparator A Up  This field specifies the action to be taken when the counter matches comparator A while counting up. This action can only occur when the MODE bit in the <b>PWMnCTL</b> register is set.
				Value Description
				0x0 Do nothing.
				0x1 Invert pwmB.
				0x2 Drive pwmB Low.
				0x3 Drive pwmB High.

Bit/Field	Name	Туре	Reset	Description
3:2	ACTLOAD	R/W	0x0	Action for Counter=LOAD  This field specifies the action to be taken when the counter matches the load value.
				Value Description 0x0 Do nothing. 0x1 Invert pwmB. 0x2 Drive pwmB Low. 0x3 Drive pwmB High.
1:0	ACTZERO	R/W	0x0	Action for Counter=0 This field specifies the action to be taken when the counter is 0.  Value Description 0x0 Do nothing. 0x1 Invert pwmB. 0x2 Drive pwmB Low. 0x3 Drive pwmB High.

Register 52: PWM0 Dead-Band Control (PWM0DBCTL), offset 0x068

Register 53: PWM1 Dead-Band Control (PWM1DBCTL), offset 0x0A8

Register 54: PWM2 Dead-Band Control (PWM2DBCTL), offset 0x0E8

Register 55: PWM3 Dead-Band Control (PWM3DBCTL), offset 0x128

The **PWMnDBCTL** register controls the dead-band generator, which produces the PWMn signals based on the pwmA and pwmB signals. When disabled, the pwmA signal passes through to the pwmA' signal and the pwmB signal passes through to the pwmB' signal. When dead-band control is enabled, the pwmB signal is ignored, the pwmA' signal is generated by delaying the rising edge(s) of the pwmA signal by the value in the **PWMnDBRISE** register (see page 1199), and the pwmB' signal is generated by inverting the pwmA signal and delaying the falling edge(s) of the pwmA signal by the value in the **PWMnDBFALL** register (see page 1200). The Output Control block outputs the pwm0A' signal on the PWM0 signal and the pwm0B' signal on the PWM1 signal. In a similar manner, PWM2 and PWM3 are produced from the pwm1A' and pwm1B' signals, PWM4 and PWM5 are produced from the pwm2A' and pwm2B' signals, and PWM6 and PWM7 are produced from the pwm3A' and pwm3B' signals.


If the Dead-Band Control mode is immediate (based on the DBCTLUPD field encoding in the **PWMnCTL** register), the ENABLE bit value is used immediately. If the update mode is locally synchronized, this value is used the next time the counter reaches zero. If the update mode is globally synchronized, this value is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Dead-Band Control (PWM0DBCTL)

PWM0 base: 0x4002.8000

Offset 0x068

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:1	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
0	ENABLE	R/W	0	Dead-Band Generator Enable

#### Value Description

- The dead-band generator modifies the pwmA signal by inserting dead bands into the pwmA' and pwmB' signals.
- The pwmA and pwmB signals pass through to the pwmA' and pwmB' signals unmodified.

Register 56: PWM0 Dead-Band Rising-Edge Delay (PWM0DBRISE), offset 0x06C

Register 57: PWM1 Dead-Band Rising-Edge Delay (PWM1DBRISE), offset 0x0AC

Register 58: PWM2 Dead-Band Rising-Edge Delay (PWM2DBRISE), offset 0x0EC


# Register 59: PWM3 Dead-Band Rising-Edge Delay (PWM3DBRISE), offset 0x12C

The **PWMnDBRISE** register contains the number of clock cycles to delay the rising edge of the pwmA signal when generating the pwmA' signal. If the dead-band generator is disabled through the **PWMnDBCTL** register, this register is ignored. If the value of this register is larger than the width of a High pulse on the pwmA signal, the rising-edge delay consumes the entire High time of the signal, resulting in no High time on the output. Care must be taken to ensure that the pwmA High time always exceeds the rising-edge delay.

If the Dead-Band Rising-Edge Delay mode is immediate (based on the DBRISEUPD field encoding in the **PWMnCTL** register), the 12-bit RISEDELAY value is used immediately. If the update mode is locally synchronized, this value is used the next time the counter reaches zero. If the update mode is globally synchronized, this value is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Dead-Band Rising-Edge Delay (PWM0DBRISE)

PWM0 base: 0x4002.8000 Offset 0x06C Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:12	reserved	RO	0x0000.0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
11:0	RISEDELAY	R/W	0x000	Dead-Band Rise Delay

The number of clock cycles to delay the rising edge of pwmA' after the rising edge of pwmA.

Register 60: PWM0 Dead-Band Falling-Edge-Delay (PWM0DBFALL), offset 0x070

Register 61: PWM1 Dead-Band Falling-Edge-Delay (PWM1DBFALL), offset 0x0B0

Register 62: PWM2 Dead-Band Falling-Edge-Delay (PWM2DBFALL), offset 0x0F0

# Register 63: PWM3 Dead-Band Falling-Edge-Delay (PWM3DBFALL), offset 0x130


The **PWMnDBFALL** register contains the number of clock cycles to delay the rising edge of the pwmB' signal from the falling edge of the pwmA signal. If the dead-band generator is disabled through the **PWMnDBCTL** register, this register is ignored. If the value of this register is larger than the width of a Low pulse on the pwmA signal, the falling-edge delay consumes the entire Low time of the signal, resulting in no Low time on the output. Care must be taken to ensure that the pwmA Low time always exceeds the falling-edge delay.

If the Dead-Band Falling-Edge-Delay mode is immediate (based on the DBFALLUP field encoding in the **PWMnCTL** register), the 12-bit FALLDELAY value is used immediately. If the update mode is locally synchronized, this value is used the next time the counter reaches zero. If the update mode is globally synchronized, this value is used the next time the counter reaches zero after a synchronous update has been requested through the **PWM Master Control (PWMCTL)** register (see page 1151). If this register is rewritten before the actual update occurs, the previous value is never used and is lost.

#### PWM0 Dead-Band Falling-Edge-Delay (PWM0DBFALL)

PWM0 base: 0x4002.8000 Offset 0x070

Type R/W, reset 0x0000.0000



rising edge of pwmA.

The number of clock cycles to delay the falling edge of pwmB' from the

Register 64: PWM0 Fault Source 0 (PWM0FLTSRC0), offset 0x074

Register 65: PWM1 Fault Source 0 (PWM1FLTSRC0), offset 0x0B4

Register 66: PWM2 Fault Source 0 (PWM2FLTSRC0), offset 0x0F4

Register 67: PWM3 Fault Source 0 (PWM3FLTSRC0), offset 0x134


This register specifies which fault pin inputs are used to generate a fault condition. Each bit in the following register indicates whether the corresponding fault pin is included in the fault condition. All enabled fault pins are ORed together to form the **PWMnFLTSRC0** portion of the fault condition. The **PWMnFLTSRC0** fault condition is then ORed with the **PWMnFLTSRC1** fault condition to generate the final fault condition for the PWM generator.

If the FLTSRC bit in the **PWMnCTL** register (see page 1176) is clear, only the Faulto signal affects the fault condition generated. Otherwise, sources defined in **PWMnFLTSRC0** and **PWMnFLTSRC1** affect the fault condition generated.

#### PWM0 Fault Source 0 (PWM0FLTSRC0)

PWM0 base: 0x4002.8000

Offset 0x074 Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	FAULT3	R/W	0	Fault3 Input

#### Value Description

- The Fault3 signal is suppressed and cannot generate a fault condition.
- 1 The Fault3 signal value is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).

**Note:** The FLTSRC bit in the **PWMnCTL** register must be set for this bit to affect fault condition generation.

Bit/Field	Name	Туре	Reset	Descrip	ption
2	FAULT2	R/W	0	Fault	2 Input
				Value	Description
				0	The ${\tt Fault2}$ signal is suppressed and cannot generate a fault condition.
				1	The Fault2 signal value is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				Note:	The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
1	FAULT1	R/W	0	Fault	1 Input
				Value	Description
				0	The Fault1 signal is suppressed and cannot generate a fault condition.
				1	The Fault1 signal value is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				Note:	The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
0	FAULT0	R/W	0	Fault	0 Input
				Value	Description
				0	The ${\tt Fault0}$ signal is suppressed and cannot generate a fault condition.
				1	The Fault0 signal value is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				Note:	The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.

Register 68: PWM0 Fault Source 1 (PWM0FLTSRC1), offset 0x078

Register 69: PWM1 Fault Source 1 (PWM1FLTSRC1), offset 0x0B8

Register 70: PWM2 Fault Source 1 (PWM2FLTSRC1), offset 0x0F8

Register 71: PWM3 Fault Source 1 (PWM3FLTSRC1), offset 0x138


This register specifies which digital comparator triggers from the ADC are used to generate a fault condition. Each bit in the following register indicates whether the corresponding digital comparator trigger is included in the fault condition. All enabled digital comparator triggers are ORed together to form the **PWMnFLTSRC1** portion of the fault condition. The **PWMnFLTSRC1** fault condition is then ORed with the **PWMnFLTSRC0** fault condition to generate the final fault condition for the PWM generator.

If the FLTSRC bit in the **PWMnCTL** register (see page 1176) is clear, only the PWM Fault0 pin affects the fault condition generated. Otherwise, sources defined in **PWMnFLTSRC0** and **PWMnFLTSRC1** affect the fault condition generated.

#### PWM0 Fault Source 1 (PWM0FLTSRC1)

PWM0 base: 0x4002.8000 Offset 0x078

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
7	DCMP7	R/W	0	Digital Comparator 7

#### Value Description

- The trigger from digital comparator 7 is suppressed and cannot generate a fault condition.
- 1 The trigger from digital comparator 7 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).

**Note:** The FLTSRC bit in the **PWMnCTL** register must be set for this bit to affect fault condition generation.

Bit/Field	Name	Туре	Reset	Description
6	DCMP6	R/W	0	Digital Comparator 6
				Value Description
				The trigger from digital comparator 6 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 6 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
5	DCMP5	R/W	0	Digital Comparator 5
				Value Description
				The trigger from digital comparator 5 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 5 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
4	DCMP4	R/W	0	Digital Comparator 4
				Value Description
				The trigger from digital comparator 4 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 4 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
3	DCMP3	R/W	0	Digital Comparator 3
				Value Description
				The trigger from digital comparator 3 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 3 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.

Bit/Field	Name	Туре	Reset	Description
2	DCMP2	R/W	0	Digital Comparator 2
				Value Description
				O The trigger from digital comparator 2 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 2 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.
1	DCMP1	R/W	0	Digital Comparator 1
				Value Description
				The trigger from digital comparator 1 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 1 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				Note: The FLTSRC bit in the PWMnCTL register must be set for this bit to affect fault condition generation.
0	DCMP0	R/W	0	Digital Comparator 0
				Value Description
				0 The trigger from digital comparator 0 is suppressed and cannot generate a fault condition.
				1 The trigger from digital comparator 0 is ORed with all other fault condition generation inputs (Faultn signals and digital comparators).
				<b>Note:</b> The FLTSRC bit in the <b>PWMnCTL</b> register must be set for this bit to affect fault condition generation.

Register 72: PWM0 Minimum Fault Period (PWM0MINFLTPER), offset 0x07C Register 73: PWM1 Minimum Fault Period (PWM1MINFLTPER), offset 0x0BC Register 74: PWM2 Minimum Fault Period (PWM2MINFLTPER), offset 0x0FC Register 75: PWM3 Minimum Fault Period (PWM3MINFLTPER), offset 0x13C

If the MINFLTPER bit in the **PWMnCTL** register is set, this register specifies the 16-bit time-extension value to be used in extending the fault condition. The value is loaded into a 16-bit down counter, and the counter value is used to extend the fault condition. The fault condition is released in the clock immediately after the counter value reaches 0. The fault condition is asynchronous to the PWM clock; and the delay value is the product of the PWM clock period and the (MFP field value + 1) or (MFP field value + 2) depending on when the fault condition asserts with respect to the PWM clock. The counter decrements at the PWM clock rate, without pause or condition.

#### PWM0 Minimum Fault Period (PWM0MINFLTPER)

PWM0 base: 0x4002.8000 Offset 0x07C Type R/W, reset 0x0000.0000

_	31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
				1				rese	rved							
Time	DO.	DO	RO	RO	RO	RO	RO	RO		DO	RO	DO		RO	DO	
Type	RO	RO		RO		RU			RO	RO		RO	RO		RO	RO
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
_	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ĺ				1												
								M	FP							
ı					L											
Type	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W	R/W							
Reset	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0

Bit/Field	Name	Туре	Reset	Description
31:16	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
15:0	MFP	R/W	0x0000	Minimum Fault Period

The number of PWM clocks by which a fault condition is extended when the delay is enabled by **PWMnCTL** MINFLTPER.

Register 76: PWM0 Fault Pin Logic Sense (PWM0FLTSEN), offset 0x800 Register 77: PWM1 Fault Pin Logic Sense (PWM1FLTSEN), offset 0x880 Register 78: PWM2 Fault Pin Logic Sense (PWM2FLTSEN), offset 0x900 Register 79: PWM3 Fault Pin Logic Sense (PWM3FLTSEN), offset 0x980

This register defines the PWM fault pin logic sense.

26

#### PWM0 Fault Pin Logic Sense (PWM0FLTSEN)

PWM0 base: 0x4002.8000

Offset 0x800

Type R/W, reset 0x0000.0000

		'	•				1	rese	rved							•
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0
	15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		1	1			re	served				1		FAULT3	FAULT2	FAULT1	FAULT0
Type Reset	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	RO 0	R/W 0	R/W 0	R/W 0	R/W 0
E	Bit/Field		Nam	ne	Тур	е	Reset	Des	cription							
	31:4		reserv	ved	RC	)	0x0000.000	com	Software should not rely on the valu compatibility with future products, th preserved across a read-modify-wri		ucts, the	value of	a reserv			
	3		FAUL	.T3	R/V	V	0	Fau	lt3 Sens	Э						
									ue Desc	ription						
								0					ult3 <b>sig</b>			
								1	An e	ror is in	dicated if	the Fa	ult3 <b>sig</b>	nal is Lo	W.	
	2		FAUL	.T2	R/V	V	0	Fau	lt2 Sense	Э						
								Val	ue Desc	ription						
								0	An e	ror is in	dicated it	f the Fa	ult2 <b>sig</b>	nal is Hiç	gh.	
								1	An e	ror is in	dicated if	f <b>the</b> Fa	ult2 <b>sig</b>	nal is Lo	W.	
	1		FAUL	.T1	R/V	V	0	Fau	lt1 Sense	Э						
								Val	ue Desc	ription						
								0	An e	ror is in	dicated if	f the Fa	ult1 <b>sig</b>	nal is Hiç	gh.	
								1	An e	ror is in	dicated if	f the Fa	ult1 <b>sig</b>	nal is Lo	W.	
	0		FAUL	.T0	R/V	V	0	Fau	lt0 Sense	Э						
								Val	ue Desc	ription						
								0	An e	ror is in	dicated if	f the Fa	ult0 <b>sig</b>	nal is Hiç	gh.	
								1	An e	ror is in	dicated if	f the Fa	ult0 <b>sig</b>	nal is Lo	W.	

Register 80: PWM0 Fault Status 0 (PWM0FLTSTAT0), offset 0x804

Register 81: PWM1 Fault Status 0 (PWM1FLTSTAT0), offset 0x884

Register 82: PWM2 Fault Status 0 (PWM2FLTSTAT0), offset 0x904

Register 83: PWM3 Fault Status 0 (PWM3FLTSTAT0), offset 0x984

Along with the **PWMnFLTSTAT1** register, this register provides status regarding the fault condition inputs.

If the LATCH bit in the **PWMnCTL** register is clear, the contents of the **PWMnFLTSTAT0** register are read-only (RO) and provide the current state of the FAULTn inputs.

If the LATCH bit in the **PWMnCTL** register is set, the contents of the **PWMnFLTSTAT0** register are read / write 1 to clear (R/W1C) and provide a latched version of the FAULTn inputs. In this mode, the register bits are cleared by writing a 1 to a set bit. The FAULTn inputs are recorded after their sense is adjusted in the generator.


The contents of this register can only be written if the fault source extensions are enabled (the FLTSRC bit in the **PWMnCTL** register is set).

#### PWM0 Fault Status 0 (PWM0FLTSTAT0)

PWM0 base: 0x4002.8000 Offset 0x804

Type -, reset 0x0000.0000

3



Bit/Field	Name	Туре	Reset	Description
31:4	reserved	RO	0x0000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

FAULT3 - 0 Fault Input 3

ault input 3

If the **PWMnCTL** register LATCH bit is clear, this bit is RO and represents the current state of the FAULT3 input signal after the logic sense adjustment.

If the <code>PWMnCTL</code> register LATCH bit is set, this bit is R/W1C and represents a sticky version of the <code>FAULT3</code> input signal after the logic sense adjustment.

- If FAULT3 is set, the input transitioned to the active state previously.
- If FAULT3 is clear, the input has not transitioned to the active state since the last time it was cleared.
- The FAULT3 bit is cleared by writing it with the value 1.

Bit/Field	Name	Туре	Reset	Description
2	FAULT2	-	0	Fault Input 2  If the <b>PWMnCTL</b> register LATCH bit is clear, this bit is RO and represents the current state of the FAULT2 input signal after the logic sense adjustment.  If the <b>PWMnCTL</b> register LATCH bit is set, this bit is R/W1C and represents a sticky version of the FAULT2 input signal after the logic sense adjustment.  If FAULT2 is set, the input transitioned to the active state previously.
				If FAULT2 is clear, the input has not transitioned to the active state since the last time it was cleared.
				■ The FAULT2 bit is cleared by writing it with the value 1.
1	FAULT1	-	0	Fault Input 1  If the <b>PWMnCTL</b> register LATCH bit is clear, this bit is RO and represents the current state of the FAULT1 input signal after the logic sense adjustment.  If the <b>PWMnCTL</b> register LATCH bit is set, this bit is R/W1C and represents a sticky version of the FAULT1 input signal after the logic sense adjustment.  If FAULT1 is set, the input transitioned to the active state previously.  If FAULT1 is clear, the input has not transitioned to the active state since the last time it was cleared.  The FAULT1 bit is cleared by writing it with the value 1.
0	FAULT0	-	0	Fault Input 0  If the PWMnCTL register LATCH bit is clear, this bit is RO and represents the current state of the input signal after the logic sense adjustment. If the PWMnCTL register LATCH bit is set, this bit is R/W1C and represents a sticky version of the input signal after the logic sense adjustment.  If FAULT0 is set, the input transitioned to the active state previously.  If FAULT0 is clear, the input has not transitioned to the active state since the last time it was cleared.  The FAULT0 bit is cleared by writing it with the value 1.

Register 84: PWM0 Fault Status 1 (PWM0FLTSTAT1), offset 0x808

Register 85: PWM1 Fault Status 1 (PWM1FLTSTAT1), offset 0x888

Register 86: PWM2 Fault Status 1 (PWM2FLTSTAT1), offset 0x908

Register 87: PWM3 Fault Status 1 (PWM3FLTSTAT1), offset 0x988

Along with the **PWMnFLTSTAT0** register, this register provides status regarding the fault condition inputs.

If the LATCH bit in the **PWMnCTL** register is clear, the contents of the **PWMnFLTSTAT1** register are read-only (RO) and provide the current state of the digital comparator triggers.


If the LATCH bit in the **PWMnCTL** register is set, the contents of the **PWMnFLTSTAT1** register are read / write 1 to clear (R/W1C) and provide a latched version of the digital comparator triggers. In this mode, the register bits are cleared by writing a 1 to a set bit. The contents of this register can only be written if the fault source extensions are enabled (the FLTSRC bit in the **PWMnCTL** register is set).

#### PWM0 Fault Status 1 (PWM0FLTSTAT1)

DCMP7

PWM0 base: 0x4002.8000 Offset 0x808 Type -, reset 0x0000.0000

7



Bit/Field	Name	Type	Reset	Description
31:8	reserved	RO	0x0000.00	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.

0

Digital Comparator 7 Trigger

If the **PWMnCTL** register LATCH bit is clear, this bit represents the current state of the Digital Comparator 7 trigger input.

If the  ${\bf PWMnCTL}$  register  ${\tt LATCH}$  bit is set, this bit represents a sticky version of the trigger.

- If DCMP7 is set, the trigger transitioned to the active state previously.
- If DCMP7 is clear, the trigger has not transitioned to the active state since the last time it was cleared.
- The DCMP7 bit is cleared by writing it with the value 1.

Bit/Field	Name	Туре	Reset	Description
6	DCMP6	-	0	Digital Comparator 6 Trigger  If the <b>PWMnCTL</b> register LATCH bit is clear, this bit represents the current state of the Digital Comparator 6 trigger input.  If the <b>PWMnCTL</b> register LATCH bit is set, this bit represents a sticky version of the trigger.  If DCMP6 is set, the trigger transitioned to the active state previously.  If DCMP6 is clear, the trigger has not transitioned to the active state since the last time it was cleared.  The DCMP6 bit is cleared by writing it with the value 1.
5	DCMP5	-	0	Digital Comparator 5 Trigger  If the PWMnCTL register LATCH bit is clear, this bit represents the current state of the Digital Comparator 5 trigger input.  If the PWMnCTL register LATCH bit is set, this bit represents a sticky version of the trigger.  If DCMP5 is set, the trigger transitioned to the active state previously.  If DCMP5 is clear, the trigger has not transitioned to the active state since the last time it was cleared.  The DCMP5 bit is cleared by writing it with the value 1.
4	DCMP4	-	0	Digital Comparator 4 Trigger  If the PWMnCTL register LATCH bit is clear, this bit represents the current state of the Digital Comparator 4 trigger input.  If the PWMnCTL register LATCH bit is set, this bit represents a sticky version of the trigger.  If DCMP4 is set, the trigger transitioned to the active state previously.  If DCMP4 is clear, the trigger has not transitioned to the active state since the last time it was cleared.  The DCMP4 bit is cleared by writing it with the value 1.
3	DCMP3	-	0	Digital Comparator 3 Trigger  If the PWMnCTL register LATCH bit is clear, this bit represents the current state of the Digital Comparator 3 trigger input.  If the PWMnCTL register LATCH bit is set, this bit represents a sticky version of the trigger.  If DCMP3 is set, the trigger transitioned to the active state previously.  If DCMP3 is clear, the trigger has not transitioned to the active state since the last time it was cleared.  The DCMP3 bit is cleared by writing it with the value 1.

Bit/Field	Name	Туре	Reset	Description
2	DCMP2	-	0	Digital Comparator 2 Trigger  If the PWMnCTL register LATCH bit is clear, this bit represents the current state of the Digital Comparator 2 trigger input.  If the PWMnCTL register LATCH bit is set, this bit represents a sticky version of the trigger.  If DCMP2 is set, the trigger transitioned to the active state previously.  If DCMP2 is clear, the trigger has not transitioned to the active state since the last time it was cleared.
				■ The DCMP2 bit is cleared by writing it with the value 1.
1	DCMP1	-	0	Digital Comparator 1 Trigger
				If the <b>PWMnCTL</b> register LATCH bit is clear, this bit represents the current state of the Digital Comparator 1 trigger input.  If the <b>PWMnCTL</b> register LATCH bit is set, this bit represents a sticky
				version of the trigger.
				If DCMP1 is set, the trigger transitioned to the active state previously.
				If DCMP1 is clear, the trigger has not transitioned to the active state since the last time it was cleared.
				■ The DCMP1 bit is cleared by writing it with the value 1.
0	DCMP0	-	0	Digital Comparator 0 Trigger
				If the <b>PWMnCTL</b> register LATCH bit is clear, this bit represents the current state of the Digital Comparator 0 trigger input.
				If the <b>PWMnCTL</b> register LATCH bit is set, this bit represents a sticky version of the trigger.
				■ If DCMP0 is set, the trigger transitioned to the active state previously.
				If DCMP0 is clear, the trigger has not transitioned to the active state since the last time it was cleared.
				■ The DCMP0 bit is cleared by writing it with the value 1.

# 22 Quadrature Encoder Interface (QEI)

A quadrature encoder, also known as a 2-channel incremental encoder, converts linear displacement into a pulse signal. By monitoring both the number of pulses and the relative phase of the two signals, you can track the position, direction of rotation, and speed. In addition, a third channel, or index signal, can be used to reset the position counter.

The LM3S9D96 microcontroller includes two quadrature encoder interface (QEI) modules. Each QEI module interprets the code produced by a quadrature encoder wheel to integrate position over time and determine direction of rotation. In addition, it can capture a running estimate of the velocity of the encoder wheel.

The Stellaris<sup>®</sup> LM3S9D96 microcontroller includes two QEI modules providing control of two motors at the same time with the following features:

- Position integrator that tracks the encoder position
- Programmable noise filter on the inputs
- Velocity capture using built-in timer
- The input frequency of the QEI inputs may be as high as 1/4 of the processor frequency (for example, 12.5 MHz for a 50-MHz system)
- Interrupt generation on:
  - Index pulse
  - Velocity-timer expiration
  - Direction change
  - Quadrature error detection

### 22.1 Block Diagram

Figure 22-1 on page 1214 provides a block diagram of a Stellaris QEI module.

QEILOAD Control & Status Velocity Timer QEITIME Velocity Accumulator Velocity QEICOUNT Predivider QEISPEED clk QEIMAXPOS PhA Quadrature Position Integrator Encoder dir PhB QEIPOS IDX QEIINTEN Interrupt Control Interrupt

Figure 22-1. QEI Block Diagram

### 22.2 Signal Description

The following table lists the external signals of the QEI module and describes the function of each. The QEI signals are alternate functions for some GPIO signals and default to be GPIO signals at reset. The column in the table below titled "Pin Mux/Pin Assignment" lists the possible GPIO pin placements for these QEI signals. The AFSEL bit in the **GPIO Alternate Function Select** (**GPIOAFSEL**) register (page 430) should be set to choose the QEI function. The number in parentheses is the encoding that must be programmed into the PMCn field in the **GPIO Port Control** (**GPIOPCTL**) register (page 448) to assign the QEI signal to the specified GPIO port pin. For more information on configuring GPIOs, see "General-Purpose Input/Outputs (GPIOs)" on page 407.

QEIRIS QEIISC

Table 22-1. QEI Signals (100LQFP)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
IDX0	10	PD0 (3)	1	TTL	QEI module 0 index.
	72	PB2 (2)			
	90	PB6 (5)			
	92	PB4 (6)			
	100	PD7 (1)			
IDX1	61	PF1 (2)	1	TTL	QEI module 1 index.
	84	PH2 (1)			
PhA0	11	PD1 (3)	I	TTL	QEI module 0 phase A.
	25	PC4 (2)			· ·
	95	PE2 (4)			
PhA1	96	PE3 (3)	1	TTL	QEI module 1 phase A.

Table 22-1. QEI Signals (100LQFP) (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PhB0	22 23 47 83 96	PC7 (2) PC6 (2) PF0 (2) PH3 (1) PE3 (4)	I	TTL	QEI module 0 phase B.
PhB1	11 36 95	PD1 (11) PG7 (1) PE2 (3)	1	TTL	QEI module 1 phase B.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

Table 22-2. QEI Signals (108BGA)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
IDX0	G1 A11 A7 A6 A2	PD0 (3) PB2 (2) PB6 (5) PB4 (6) PD7 (1)	I	TTL	QEI module 0 index.
IDX1	H12 D11	PF1 (2) PH2 (1)	I	TTL	QEI module 1 index.
PhA0	G2 L1 A4	PD1 (3) PC4 (2) PE2 (4)	I	TTL	QEI module 0 phase A.
PhA1	B4	PE3 (3)	I	TTL	QEI module 1 phase A.
PhB0	L2 M2 M9 D10 B4	PC7 (2) PC6 (2) PF0 (2) PH3 (1) PE3 (4)	I	TTL	QEI module 0 phase B.
PhB1	G2 C10 A4	PD1 (11) PG7 (1) PE2 (3)	I	TTL	QEI module 1 phase B.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 22.3 Functional Description

The QEI module interprets the two-bit gray code produced by a quadrature encoder wheel to integrate position over time and determine direction of rotation. In addition, it can capture a running estimate of the velocity of the encoder wheel.

The position integrator and velocity capture can be independently enabled, though the position integrator must be enabled before the velocity capture can be enabled. The two phase signals, PhA and PhB, can be swapped before being interpreted by the QEI module to change the meaning of forward and backward and to correct for miswiring of the system. Alternatively, the phase signals can be interpreted as a clock and direction signal as output by some encoders.

The QEI module input signals have a digital noise filter on them that can be enabled to prevent spurious operation. The noise filter requires that the inputs be stable for a specified number of consecutive clock cycles before updating the edge detector. The filter is enabled by the FILTEN bit in the QEI Control (QEICTL) register. The frequency of the input update is programmable using the FILTCNT bit field in the QEICTL register.

The QEI module supports two modes of signal operation: quadrature phase mode and clock/direction mode. In quadrature phase mode, the encoder produces two clocks that are 90 degrees out of phase; the edge relationship is used to determine the direction of rotation. In clock/direction mode, the encoder produces a clock signal to indicate steps and a direction signal to indicate the direction of rotation. This mode is determined by the SIGMODE bit of the **QEICTL** register (see page 1220).

When the QEI module is set to use the quadrature phase mode (SIGMODE bit is clear), the capture mode for the position integrator can be set to update the position counter on every edge of the PhA signal or to update on every edge of both PhA and PhB. Updating the position counter on every PhA and PhB edge provides more positional resolution at the cost of less range in the positional counter.

When edges on PhA lead edges on PhB, the position counter is incremented. When edges on PhB lead edges on PhA, the position counter is decremented. When a rising and falling edge pair is seen on one of the phases without any edges on the other, the direction of rotation has changed.

The positional counter is automatically reset on one of two conditions: sensing the index pulse or reaching the maximum position value. The reset mode is determined by the RESMODE bit of the **QEICTL** register.

When RESMODE is set, the positional counter is reset when the index pulse is sensed. This mode limits the positional counter to the values [0:N-1], where N is the number of phase edges in a full revolution of the encoder wheel. The **QEI Maximum Position (QEIMAXPOS)** register must be programmed with N-1 so that the reverse direction from position 0 can move the position counter to N-1. In this mode, the position register contains the absolute position of the encoder relative to the index (or home) position once an index pulse has been seen.

When RESMODE is clear, the positional counter is constrained to the range [0:M], where M is the programmable maximum value. The index pulse is ignored by the positional counter in this mode.

Velocity capture uses a configurable timer and a count register. The timer counts the number of phase edges (using the same configuration as for the position integrator) in a given time period. The edge count from the previous time period is available to the controller via the **QEI Velocity** (**QEISPEED**) register, while the edge count for the current time period is being accumulated in the **QEI Velocity Counter** (**QEICOUNT**) register. As soon as the current time period is complete, the total number of edges counted in that time period is made available in the **QEISPEED** register (overwriting the previous value), the **QEICOUNT** register is cleared, and counting commences on a new time period. The number of edges counted in a given time period is directly proportional to the velocity of the encoder.

Figure 22-2 on page 1216 shows how the Stellaris quadrature encoder converts the phase input signals into clock pulses, the direction signal, and how the velocity predivider operates (in Divide by 4 mode).




Figure 22-2. Quadrature Encoder and Velocity Predivider Operation

The period of the timer is configurable by specifying the load value for the timer in the **QEI Timer Load (QEILOAD)** register. When the timer reaches zero, an interrupt can be triggered, and the

hardware reloads the timer with the **QEILOAD** value and continues to count down. At lower encoder speeds, a longer timer period is required to be able to capture enough edges to have a meaningful result. At higher encoder speeds, both a shorter timer period and/or the velocity predivider can be used.

The following equation converts the velocity counter value into an rpm value:

```
rpm = (clock * (2 ^ VELDIV) * SPEED * 60) ÷ (LOAD * ppr * edges)
```

where:

clock is the controller clock rate

ppr is the number of pulses per revolution of the physical encoder

edges is 2 or 4, based on the capture mode set in the **QEICTL** register (2 for CAPMODE clear and 4 for CAPMODE set)

For example, consider a motor running at 600 rpm. A 2048 pulse per revolution quadrature encoder is attached to the motor, producing 8192 phase edges per revolution. With a velocity predivider of ÷1 (VELDIV is clear) and clocking on both PhA and PhB edges, this results in 81,920 pulses per second (the motor turns 10 times per second). If the timer were clocked at 10,000 Hz, and the load value was 2,500 (¼ of a second), it would count 20,480 pulses per update. Using the above equation:

```
rpm = (10000 * 1 * 20480 * 60) \div (2500 * 2048 * 4) = 600 rpm
```

Now, consider that the motor is sped up to 3000 rpm. This results in 409,600 pulses per second, or 102,400 every  $\frac{1}{4}$  of a second. Again, the above equation gives:

```
rpm = (10000 * 1 * 102400 * 60) \div (2500 * 2048 * 4) = 3000 rpm
```

Care must be taken when evaluating this equation because intermediate values may exceed the capacity of a 32-bit integer. In the above examples, the clock is 10,000 and the divider is 2,500; both could be predivided by 100 (at compile time if they are constants) and therefore be 100 and 25. In fact, if they were compile-time constants, they could also be reduced to a simple multiply by 4, cancelled by the ÷4 for the edge-count factor.

**Important:** Reducing constant factors at compile time is the best way to control the intermediate values of this equation and reduce the processing requirement of computing this equation.

The division can be avoided by selecting a timer load value such that the divisor is a power of 2; a simple shift can therefore be done in place of the division. For encoders with a power of 2 pulses per revolution, the load value can be a power of 2. For other encoders, a load value must be selected such that the product is very close to a power of 2. For example, a 100 pulse-per-revolution encoder could use a load value of 82, resulting in 32,800 as the divisor, which is 0.09% above 2<sup>14</sup>. In this case a shift by 15 would be an adequate approximation of the divide in most cases. If absolute accuracy were required, the microcontroller's divide instruction could be used.

The QEI module can produce a controller interrupt on several events: phase error, direction change, reception of the index pulse, and expiration of the velocity timer. Standard masking, raw interrupt status, interrupt status, and interrupt clear capabilities are provided.

## 22.4 Initialization and Configuration

The following example shows how to configure the Quadrature Encoder module to read back an absolute position:

- 1. Enable the QEI clock by writing a value of 0x0000.0100 to the **RCGC1** register in the System Control module (see page 272).
- 2. Enable the clock to the appropriate GPIO module via the RCGC2 register in the System Control module (see page 284).
- 3. In the GPIO module, enable the appropriate pins for their alternate function using the **GPIOAFSEL** register. To determine which GPIOs to configure, see Table 24-4 on page 1261.
- **4.** Configure the PMCn fields in the **GPIOPCTL** register to assign the QEI signals to the appropriate pins (see page 448 and Table 24-5 on page 1270).
- **5.** Configure the quadrature encoder to capture edges on both signals and maintain an absolute position by resetting on index pulses. A 1000-line encoder with four edges per line, results in 4000 pulses per revolution; therefore, set the maximum position to 3999 (0xF9F) as the count is zero-based.
  - Write the **QEICTL** register with the value of 0x0000.0018.
  - Write the **QEIMAXPOS** register with the value of 0x0000.0F9F.
- **6.** Enable the quadrature encoder by setting bit 0 of the **QEICTL** register.
- 7. Delay until the encoder position is required.
- 8. Read the encoder position by reading the QEI Position (QEIPOS) register value.

### 22.5 Register Map

Table 22-3 on page 1218 lists the QEI registers. The offset listed is a hexadecimal increment to the register's address, relative to the module's base address:

QEI0: 0x4002.C000QEI1: 0x4002.D000

Note that the QEI module clock must be enabled before the registers can be programmed (see page 272). There must be a delay of 3 system clocks after the QEI module clock is enabled before any QEI module registers are accessed.

Table 22-3. QEI Register Map

Offset	Name	Туре	Reset	Description	See page
0x000	QEICTL	R/W	0x0000.0000	QEI Control	1220
0x004	QEISTAT	RO	0x0000.0000	QEI Status	1223
800x0	QEIPOS	R/W	0x0000.0000	QEI Position	1224
0x00C	QEIMAXPOS	R/W	0x0000.0000	QEI Maximum Position	1225
0x010	QEILOAD	R/W	0x0000.0000	QEI Timer Load	1226
0x014	QEITIME	RO	0x0000.0000	QEI Timer	1227
0x018	QEICOUNT	RO	0x0000.0000	QEI Velocity Counter	1228
0x01C	QEISPEED	RO	0x0000.0000	QEI Velocity	1229

Table 22-3. QEI Register Map (continued)

Offset	Name	Туре	Reset	Description	See page
0x020	QEIINTEN	R/W	0x0000.0000	QEI Interrupt Enable	1230
0x024	QEIRIS	RO	0x0000.0000	QEI Raw Interrupt Status	1232
0x028	QEIISC	R/W1C	0x0000.0000	QEI Interrupt Status and Clear	1234

# 22.6 Register Descriptions

The remainder of this section lists and describes the QEI registers, in numerical order by address offset.

### Register 1: QEI Control (QEICTL), offset 0x000


This register contains the configuration of the QEI module. Separate enables are provided for the quadrature encoder and the velocity capture blocks; the quadrature encoder must be enabled in order to capture the velocity, but the velocity does not need to be captured in applications that do not need it. The phase signal interpretation, phase swap, Position Update mode, Position Reset mode, and velocity predivider are all set via this register.

#### QEI Control (QEICTL)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000

Offset 0x000

Type R/W, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:20	reserved	RO	0x000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
19:16	FILTCNT	R/W	0x0	Input Filter Prescale Count
				This field controls the frequency of the input update.
				When this field is clear, the input is sampled after 2 system clocks. When this field ix 0x1, the input is sampled after 3 system clocks. Similarly, when this field is 0xF, the input is sampled after 17 clocks.
15:14	reserved	RO	0x0	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
13	FILTEN	R/W	0	Enable Input Filter
				Value Description
				0 The QEI inputs are not filtered.
				Enables the digital noise filter on the QEI input signals. Inputs must be stable for 3 consecutive clock edges before the edge detector is updated.
12	STALLEN	R/W	0	Stall QEI

#### Value Description

- The QEI module does not stall when the microcontroller is stopped by a debugger.
- The QEI module stalls when the microcontroller is stopped by a debugger.

Bit/Field	Name	Туре	Reset	Description
11	INVI	R/W	0	Invert Index Pulse
				Value Description  0 No effect.  1 Inverts the IDX input.
10	INVB	R/W	0	Invert PhB
				Value Description  No effect.  Inverts the PhB input.
9	INVA	R/W	0	Invert PhA
				Value Description  0 No effect.  1 Inverts the PhA input.
8:6	VELDIV	R/W	0x0	Predivide Velocity  This field defines the predivider of the input quadrature pulses before being applied to the <b>QEICOUNT</b> accumulator.
				Value Predivider  0x0 ÷1  0x1 ÷2  0x2 ÷4  0x3 ÷8  0x4 ÷16  0x5 ÷32  0x6 ÷64  0x7 ÷128
5	VELEN	R/W	0	Capture Velocity  Value Description  0 No effect.  1 Enables capture of the velocity of the quadrature encoder.
4	RESMODE	R/W	0	Reset Mode  Value Description
				The position counter is reset when it reaches the maximum as defined by the MAXPOS field in the <b>QEIMAXPOS</b> register.
				The position counter is reset when the index pulse is captured.

Bit/Field	Name	Туре	Reset	Description
3	CAPMODE	R/W	0	Capture Mode
				Value Description
				0 Only the PhA edges are counted.
				1 The PhA and PhB edges are counted, providing twice the positional resolution but half the range.
2	SIGMODE	R/W	0	Signal Mode
				Value Description
				0 The PhA and PhB signals operate as quadrature phase signals.
				1 The PhA and PhB signals operate as clock and direction.
1	SWAP	R/W	0	Swap Signals
				Value Description
				0 No effect.
				1 Swaps the PhA and PhB signals.
0	ENABLE	R/W	0	Enable QEI
				Value Description
				0 No effect.
				1 Enables the quadrature encoder module.


### Register 2: QEI Status (QEISTAT), offset 0x004

This register provides status about the operation of the QEI module.

#### QEI Status (QEISTAT)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000 Offset 0x004

Type RO, reset 0x0000.0000



Bit/Field	Name	Туре	Reset	Description
31:2	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
1	DIRECTION	RO	0	Direction of Rotation Indicates the direction the encoder is rotating.
				Value Description
				The encoder is rotating forward.
				1 The encoder is rotating in reverse.
0	ERROR	RO	0	Error Detected

Value Description

0 No error.

An error was detected in the gray code sequence (that is, both signals changing at the same time). **POSITION** 

R/W

## Register 3: QEI Position (QEIPOS), offset 0x008


This register contains the current value of the position integrator. The value is updated by the status of the QEI phase inputs and can be set to a specific value by writing to it.

#### QEI Position (QEIPOS)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000 Offset 0x008

31:0

Type R/W, reset 0x0000.0000



0x0000.0000 Current Position Integrator Value

The current value of the position integrator.

## Register 4: QEI Maximum Position (QEIMAXPOS), offset 0x00C


This register contains the maximum value of the position integrator. When moving forward, the position register resets to zero when it increments past this value. When moving in reverse, the position register resets to this value when it decrements from zero.

QEI Maximum Position (QEIMAXPOS)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000

Offset 0x00C

Type R/W, reset 0x0000.0000



The maximum value of the position integrator.

## Register 5: QEI Timer Load (QEILOAD), offset 0x010

This register contains the load value for the velocity timer. Because this value is loaded into the timer on the clock cycle after the timer is zero, this value should be one less than the number of clocks in the desired period. So, for example, to have 2000 decimal clocks per timer period, this register should contain 1999 decimal.

#### QEI Timer Load (QEILOAD)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000 Offset 0x010


31:0

LOAD

R/W

0x0000.0000

Type R/W, reset 0x0000.0000



The load value for the velocity timer.

Velocity Timer Load Value

## Register 6: QEI Timer (QEITIME), offset 0x014

This register contains the current value of the velocity timer. This counter does not increment when the VELEN bit in the QEICTL register is clear.

QEI Timer (QEITIME)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000


Offset 0x014

31:0

TIME

RO

Type RO, reset 0x0000.0000



0x0000.0000 Velocity Timer Current Value


The current value of the velocity timer.

## Register 7: QEI Velocity Counter (QEICOUNT), offset 0x018

This register contains the running count of velocity pulses for the current time period. Because this count is a running total, the time period to which it applies cannot be known with precision (that is, a read of this register does not necessarily correspond to the time returned by the **QEITIME** register because there is a small window of time between the two reads, during which either value may have changed). The **QEISPED** register should be used to determine the actual encoder velocity; this register is provided for information purposes only. This counter does not increment when the VELEN bit in the **QEICTL** register is clear.

### QEI Velocity Counter (QEICOUNT)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000 Offset 0x018 Type RO, reset 0x0000.0000



The running total of encoder pulses during this velocity timer period.

# Register 8: QEI Velocity (QEISPEED), offset 0x01C


This register contains the most recently measured velocity of the quadrature encoder. This value corresponds to the number of velocity pulses counted in the previous velocity timer period. This register does not update when the VELEN bit in the **QEICTL** register is clear.

### QEI Velocity (QEISPEED)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000

Offset 0x01C

Type RO, reset 0x0000.0000



The measured speed of the quadrature encoder in pulses per period.

## Register 9: QEI Interrupt Enable (QEIINTEN), offset 0x020


This register contains enables for each of the QEI module interrupts. An interrupt is asserted to the interrupt controller if the corresponding bit in this register is set.

### QEI Interrupt Enable (QEIINTEN)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000

Offset 0x020

Type R/W, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INTERROR	R/W	0	Phase Error Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the INTERROR bit in the <b>QEIRIS</b> register is set.
				O The INTERROR interrupt is suppressed and not sent to the interrupt controller.
2	INTDIR	R/W	0	Direction Change Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the INTDIR bit in the <b>QEIRIS</b> register is set.
				O The INTDIR interrupt is suppressed and not sent to the interrupt controller.
1	INTTIMER	R/W	0	Timer Expires Interrupt Enable

#### Value Description

- 1 An interrupt is sent to the interrupt controller when the INTTIMER bit in the QEIRIS register is set.
- The INTTIMER interrupt is suppressed and not sent to the interrupt controller.

Bit/Field	Name	Туре	Reset	Description
0	INTINDEX	R/W	0	Index Pulse Detected Interrupt Enable
				Value Description
				An interrupt is sent to the interrupt controller when the INTINDEX bit in the <b>QEIRIS</b> register is set.
				O The INTINDEX interrupt is suppressed and not sent to the interrupt controller.


## Register 10: QEI Raw Interrupt Status (QEIRIS), offset 0x024

This register provides the current set of interrupt sources that are asserted, regardless of whether they cause an interrupt to be asserted to the controller (configured through the QEIINTEN register). If a bit is set, the latched event has occurred; if a bit is clear, the event in question has not occurred.

QEI Raw Interrupt Status (QEIRIS)

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000 Offset 0x024

Type RO, reset 0x0000.0000



Bit/Field	Name	Type	Reset	Description
31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
3	INTERROR	RO	0	Phase Error Detected
				Value Description  1 A phase error has been detected.
				O An interrupt has not occurred.
				This bit is cleared by writing a 1 to the INTERROR bit in the <b>QEIISC</b> register.
2	INTDIR	RO	0	Direction Change Detected
				Value Description
				1 The rotation direction has changed
				0 An interrupt has not occurred.
				This bit is cleared by writing a 1 to the ${\tt INTDIR}$ bit in the ${\tt QEIISC}$ register.
1	INTTIMER	RO	0	Velocity Timer Expired
				Value Description

This bit is cleared by writing a 1 to the  ${\tt INTTIMER}$  bit in the **QEIISC** register.

The velocity timer has expired.

An interrupt has not occurred.

1

0

Bit/Field	Name	Туре	Reset	Description
0	INTINDEX	RO	0	Index Pulse Asserted
				Value Description  1 The index pulse has occurred.  0 An interrupt has not occurred.  This bit is cleared by writing a 1 to the INTINDEX bit in the QEIISC register.

## Register 11: QEI Interrupt Status and Clear (QEIISC), offset 0x028

This register provides the current set of interrupt sources that are asserted to the controller. If a bit is set, the latched event has occurred and is enabled to generate an interrupt; if a bit is clear the event in question has not occurred or is not enabled to generate an interrupt. This register is R/W1C; writing a 1 to a bit position clears the bit and the corresponding interrupt reason.

QEI Interrupt Status and Clear (QEIISC)

Namo

Type


Docot

QEI0 base: 0x4002.C000 QEI1 base: 0x4002.D000

Offset 0x028

Dit/Eiold

Type R/W1C, reset 0x0000.0000



Description

compatibility with future products, the value of a reserved bit shou preserved across a read-modify-write operation.  3 INTERROR R/W1C 0 Phase Error Interrupt  Value Description  1 The INTERROR bits in the QEIRIS register and the QEININ	Bit/Field	Name	туре	Reset	Description
Value Description  1 The INTERROR bits in the QEIRIS register and the QEIINT registers are set, providing an interrupt to the interrupt control  0 No interrupt has occurred or the interrupt is masked.  This bit is cleared by writing a 1. Clearing this bit also clears the INTERROR bit in the QEIRIS register.	31:4	reserved	RO	0x0000.000	Software should not rely on the value of a reserved bit. To provide compatibility with future products, the value of a reserved bit should be preserved across a read-modify-write operation.
The INTERROR bits in the QEIRIS register and the QEIINT registers are set, providing an interrupt to the interrupt control.  No interrupt has occurred or the interrupt is masked.  This bit is cleared by writing a 1. Clearing this bit also clears the INTERROR bit in the QEIRIS register.	3	INTERROR	R/W1C	0	Phase Error Interrupt
registers are set, providing an interrupt to the interrupt control  No interrupt has occurred or the interrupt is masked.  This bit is cleared by writing a 1. Clearing this bit also clears the INTERROR bit in the QEIRIS register.					Value Description
This bit is cleared by writing a 1. Clearing this bit also clears the INTERROR bit in the <b>QEIRIS</b> register.					1 The INTERROR bits in the <b>QEIRIS</b> register and the <b>QEIINTEN</b> registers are set, providing an interrupt to the interrupt controller.
INTERROR bit in the QEIRIS register.					0 No interrupt has occurred or the interrupt is masked.
2 INTDIR R/W1C 0 Direction Change Interrupt					, ,
	2	INTDIR	R/W1C	0	Direction Change Interrupt

#### Value Description

- 1 The INTDIR bits in the QEIRIS register and the QEIINTEN registers are set, providing an interrupt to the interrupt controller.
- No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt INTDIR}$  bit in the  ${\tt QEIRIS}$  register.

1 INTTIMER R/W1C 0 Velocity Timer Expired Interrupt

#### Value Description

- 1 The INTTIMER bits in the QEIRIS register and the QEIINTEN registers are set, providing an interrupt to the interrupt controller.
- 0 No interrupt has occurred or the interrupt is masked.

This bit is cleared by writing a 1. Clearing this bit also clears the  ${\tt INTTIMER}$  bit in the **QEIRIS** register.

Bit/Field	Name	Туре	Reset	Description
0	INTINDEX	R/W1C	0	Index Pulse Interrupt
				Value Description
				1 The INTINDEX bits in the <b>QEIRIS</b> register and the <b>QEIINTEN</b> registers are set, providing an interrupt to the interrupt controller.
				0 No interrupt has occurred or the interrupt is masked.
				This bit is cleared by writing a 1. Clearing this bit also clears the INTINDEX bit in the <b>QEIRIS</b> register.

# 23 Pin Diagram

The LM3S9D96 microcontroller pin diagram is shown below.

Each GPIO signal is identified by its GPIO port unless it defaults to an alternate function on reset. In this case, the GPIO port name is followed by the default alternate function. To see a complete list of possible functions for each pin, see Table 24-5 on page 1270.

Figure 23-1. 100-Pin LQFP Package Pin Diagram




Figure 23-2. 108-Ball BGA Package Pin Diagram (Top View)

	1	2	3	4	5	6	7	8	9	10	11	12	
Α	PE6	PD7	PD6	PE2	GNDA	PB4	РВ6	PB7	PC0 TCK SWCLK	PC3 TDO SWO	PB2 I2C0SCL	PE1	Α
В	PE7	PE4	PE5	PE3	PD4	PJ1	PB5	PC2 TDI	PC1 TMS SWDIO	PH4	PEO	(SBORBIAS	В
С	NC (	NC	VDDC	GND	GND	PD5	VDDA	PH1	РНО	PG7	USB0DM)	USB0DP	С
D	NC (	NC	VDDC							РНЗ	РН2	PB1 USBOVBUS	D
Е	NC (	NC	LDO							VDD	PB3 I2COSDA	PB0 USB0ID	Е
F	NC (	NC	РЈ0							PH5	GND	GND	F
G	PD0	PD1	РН6			LM3S	89D96			VDD	VDD	VDD	G
Н	PD3	PD2	PH7							VDD	RST	PF1	Н
J	XTALNPHY X	KTALPPHY	ERBIAS							GND	PF2	PF3	J
K	PG0	PG1	PF5	PF4	GND	РЈ2	VDD	VDD	VDD	GND	PJ4	PJ5	K
L	PC4	PC7	PA0 UORx	PA3 SSI0Fss	PA4 SSIORX	PA6	RXIN	TXON	MDIO	РЈ6	OSC0	PJ7	L
М	PC5	PC6	PA1 UOTx	PA2 SSIOC1k	PA5 SSIOTx	PA7	RXIP	TXOP	PF0	РЈ3	OSC1	NC	М
	1	2	3	4	5	6	7	8	9	10	11	12	

# 24 Signal Tables

The following tables list the signals available for each pin. Signals are configured as GPIOs on reset, except for those noted below. Use the **GPIOAMSEL** register (see page 446) to select analog mode. For a GPIO pin to be used for an alternate digital function, the corresponding bit in the **GPIOAFSEL** register (see page 430) must be set. Further pin muxing options are provided through the PMCx bit field in the **GPIOPCTL** register (see page 448), which selects one of several available peripheral functions for that GPIO.

Important: All GPIO pins are configured as GPIOs by default with the exception of the pins shown in the table below. A Power-On-Reset (POR) or asserting RST puts the pins back to their default state.

**GPIO Pin Default State GPIOAFSEL Bit GPIOPCTL PMCx Bit Field** PA[1:0] **UARTO** 0 0x1 PA[5:2] SSI0 0 0x1 I<sup>2</sup>C0 0 PB[3:2] 0x1 JTAG/SWD PC[3:0] 1 0x3

Table 24-1. GPIO Pins With Default Alternate Functions

Table 24-2 on page 1239 shows the pin-to-signal-name mapping, including functional characteristics of the signals. Each possible alternate analog and digital function is listed for each pin.

Table 24-3 on page 1251 lists the signals in alphabetical order by signal name. If it is possible for a signal to be on multiple pins, each possible pin assignment is listed. The "Pin Mux" column indicates the GPIO and the encoding needed in the PMCx bit field in the **GPIOPCTL** register.

Table 24-4 on page 1261 groups the signals by functionality, except for GPIOs. If it is possible for a signal to be on multiple pins, each possible pin assignment is listed.

Table 24-5 on page 1270 lists the GPIO pins and their analog and digital alternate functions. The AINx and VREFA analog signals are not 5-V tolerant and go through an isolation circuit before reaching their circuitry. These signals are configured by clearing the corresponding DEN bit in the **GPIO Digital Enable (GPIODEN)** register and setting the corresponding AMSEL bit in the **GPIO Analog Mode Select (GPIOAMSEL)** register. Other analog signals are 5-V tolerant and are connected directly to their circuitry (C0-, C0+, C1-, C1+, C2-, C2+, USB0VBUS, USB0ID). These signals are configured by clearing the DEN bit in the **GPIO Digital Enable (GPIODEN)** register. The digital signals are enabled by setting the appropriate bit in the **GPIO Alternate Function Select (GPIOAFSEL)** and **GPIODEN** registers and configuring the PMCx bit field in the **GPIO Port Control (GPIOPCTL)** register to the numeric enoding shown in the table below. Table entries that are shaded gray are the default values for the corresponding GPIO pin.

Table 24-6 on page 1273 lists the signals based on number of possible pin assignments. This table can be used to plan how to configure the pins for a particular functionality. Application Note AN01274 Configuring Stellaris<sup>®</sup> Microcontrollers with Pin Multiplexing provides an overview of the pin muxing implementation, an explanation of how a system designer defines a pin configuration, and examples of the pin configuration process.

**Note:** All digital inputs are Schmitt triggered.

# 24.1 100-Pin LQFP Package Pin Tables

## 24.1.1 Signals by Pin Number

Table 24-2. Signals by Pin Number

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PE7	I/O	TTL	GPIO port E bit 7.
	AIN0	ı	Analog	Analog-to-digital converter input 0.
1	C2o	0	TTL	Analog comparator 2 output.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	U1DCD	ı	TTL	UART module 1 Data Carrier Detect modem status input signal.
	PE6	I/O	TTL	GPIO port E bit 6.
	AIN1	I	Analog	Analog-to-digital converter input 1.
2	Clo	0	TTL	Analog comparator 1 output.
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	U1CTS	I	TTL	UART module 1 Clear To Send modem flow control input signal.
3	VDDA	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
4	GNDA	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
	PE5	I/O	TTL	GPIO port E bit 5.
5	AIN2	I	Analog	Analog-to-digital converter input 2.
3	CCP5	I/O	TTL	Capture/Compare/PWM 5.
	I2SOTXSD	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
	PE4	I/O	TTL	GPIO port E bit 4.
	AIN3	I	Analog	Analog-to-digital converter input 3.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
6	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	Fault0	I	TTL	PWM Fault 0.
	I2SOTXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
7	LDO	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).
8	VDD	-	Power	Positive supply for I/O and some logic.
9	GND	-	Power	Ground reference for logic and I/O pins.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PD0	I/O	TTL	GPIO port D bit 0.
	AIN15	I	Analog	Analog-to-digital converter input 15.
	CAN0Rx	I	TTL	CAN module 0 receive.
	CCP6	I/O	TTL	Capture/Compare/PWM 6.
	I2S0RXSCK	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
10	IDX0	I	TTL	QEI module 0 index.
	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
	Ulcts	I	TTL	UART module 1 Clear To Send modem flow control input signal.
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
	PD1	I/O	TTL	GPIO port D bit 1.
	AIN14	I	Analog	Analog-to-digital converter input 14.
	CAN0Tx	0	TTL	CAN module 0 transmit.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
	CCP7	I/O	TTL	Capture/Compare/PWM 7.
	I2S0RXWS	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
11	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
	PhA0	I	TTL	QEI module 0 phase A.
	PhB1	I	TTL	QEI module 1 phase B.
	U1DCD	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
	PD2	I/O	TTL	GPIO port D bit 2.
	AIN13	I	Analog	Analog-to-digital converter input 13.
	CCP5	I/O	TTL	Capture/Compare/PWM 5.
12	CCP6	I/O	TTL	Capture/Compare/PWM 6.
	EPI0S20	I/O	TTL	EPI module 0 signal 20.
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
	UlRx	1	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	PD3	I/O	TTL	GPIO port D bit 3.
	AIN12	I	Analog	Analog-to-digital converter input 12.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
13	CCP7	I/O	TTL	Capture/Compare/PWM 7.
	EPI0S21	I/O	TTL	EPI module 0 signal 21.
	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PJ0	I/O	TTL	GPIO port J bit 0.
	EPIOS16	I/O	TTL	EPI module 0 signal 16.
14	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.
	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
	PH7	I/O	TTL	GPIO port H bit 7.
15	EPIOS27	I/O	TTL	EPI module 0 signal 27.
15	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	SSI1Tx	0	TTL	SSI module 1 transmit.
16	XTALPPHY	I	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.
17	XTALNPHY	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
	PG1	I/O	TTL	GPIO port G bit 1.
	EPIOS14	I/O	TTL	EPI module 0 signal 14.
	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.
18	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
	PG0	I/O	TTL	GPIO port G bit 0.
	EPIOS13	I/O	TTL	EPI module 0 signal 13.
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.
40	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
19	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
20	VDD	-	Power	Positive supply for I/O and some logic.
21	GND	-	Power	Ground reference for logic and I/O pins.
	PC7	I/O	TTL	GPIO port C bit 7.
	Clo	0	TTL	Analog comparator 1 output.
	C2-	I	Analog	Analog comparator 2 negative input.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
25	CCP4	I/O	TTL	Capture/Compare/PWM 4.
22	EPIOS5	I/O	TTL	EPI module 0 signal 5.
Ī	PhB0	I	TTL	QEI module 0 phase B.
Ī	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PC6	I/O	TTL	GPIO port C bit 6.
	C2+	I	Analog	Analog comparator 2 positive input.
	C2o	0	TTL	Analog comparator 2 output.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
	CCP3	I/O	TTL	Capture/Compare/PWM 3.
23	EPI0S4	I/O	TTL	EPI module 0 signal 4.
	РWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.
	PhB0	I	TTL	QEI module 0 phase B.
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
	PC5	I/O	TTL	GPIO port C bit 5.
	C0o	0	TTL	Analog comparator 0 output.
	C1+	I	Analog	Analog comparator 1 positive input.
	C1o	0	TTL	Analog comparator 1 output.
24	CCP1	I/O	TTL	Capture/Compare/PWM 1.
	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	EPIOS3	I/O	TTL	EPI module 0 signal 3.
	Fault2	I	TTL	PWM Fault 2.
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
	PC4	I/O	TTL	GPIO port C bit 4.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
25	CCP4	I/O	TTL	Capture/Compare/PWM 4.
25	CCP5	I/O	TTL	Capture/Compare/PWM 5.
	EPI0S2	I/O	TTL	EPI module 0 signal 2.
	РWМ6	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
	PhA0	I	TTL	QEI module 0 phase A.
	PA0	I/O	TTL	GPIO port A bit 0.
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.
26	UORx	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	PA1	I/O	TTL	GPIO port A bit 1.
	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.
27	UOTx	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.
	U1Tx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PA2	I/O	TTL	GPIO port A bit 2.
	I2S0RXSD	I/O	TTL	I <sup>2</sup> S module 0 receive data.
28	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	SSIOClk	I/O	TTL	SSI module 0 clock
	PA3	I/O	TTL	GPIO port A bit 3.
00	I2S0RXMCLK	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
29	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	SSIOFss	I/O	TTL	SSI module 0 frame signal
	PA4	I/O	TTL	GPIO port A bit 4.
	CAN0Rx	ı	TTL	CAN module 0 receive.
30	I2S0TXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	PWM6	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
	SSI0Rx	ı	TTL	SSI module 0 receive
	PA5	I/O	TTL	GPIO port A bit 5.
	CAN0Tx	0	TTL	CAN module 0 transmit.
31	I2S0TXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	PWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.
32	SSI0Tx	0	TTL	SSI module 0 transmit
32	VDD	-	Power	Positive supply for I/O and some logic.
33	ERBIAS	0	Analog	12.4-kΩ resistor (1% precision) used internally for Ethernet PHY.
	PA6	I/O	TTL	GPIO port A bit 6.
	CAN0Rx	ı	TTL	CAN module 0 receive.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.
34	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	U1CTS	ı	TTL	UART module 1 Clear To Send modem flow control input signal.
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
	PA7	I/O	TTL	GPIO port A bit 7.
	CAN0Tx	0	TTL	CAN module 0 transmit.
	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	CCP4	I/O	TTL	Capture/Compare/PWM 4.
35	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	U1DCD	ı	TTL	UART module 1 Data Carrier Detect modem status input signal.
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PG7	I/O	TTL	GPIO port G bit 7.	
	CCP5	I/O	TTL	Capture/Compare/PWM 5.	
36	EPI0S31	I/O	TTL	EPI module 0 signal 31.	
	PWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.	
	PhB1	1	TTL	QEI module 1 phase B.	
37	RXIN	I	Analog	RXIN of the Ethernet PHY.	
38	VDDC	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .	
	PJ2	I/O	TTL	GPIO port J bit 2.	
39	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
39	EPIOS18	I/O	TTL	EPI module 0 signal 18.	
	Fault0	I	TTL	PWM Fault 0.	
40	RXIP	I	Analog	RXIP of the Ethernet PHY.	
	PF5	I/O	TTL	GPIO port F bit 5.	
	C1o	0	TTL	Analog comparator 1 output.	
41	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
	EPI0S15	I/O	TTL	EPI module 0 signal 15.	
	SSI1Tx	0	TTL	SSI module 1 transmit.	
	PF4	I/O	TTL	GPIO port F bit 4.	
	COo	0	TTL	Analog comparator 0 output.	
42	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
42	EPI0S12	I/O	TTL	EPI module 0 signal 12.	
	Fault0	I	TTL	PWM Fault 0.	
	SSI1Rx	I	TTL	SSI module 1 receive.	
43	TXOP	0	TTL	TXOP of the Ethernet PHY.	
44	VDD	-	Power	Positive supply for I/O and some logic.	
45	GND	-	Power	Ground reference for logic and I/O pins.	
46	TXON	0	TTL	TXON of the Ethernet PHY.	
	PF0	I/O	TTL	GPIO port F bit 0.	
	CAN1Rx	I	TTL	CAN module 1 receive.	
47	I2S0TXSD	I/O	TTL	I <sup>2</sup> S module 0 transmit data.	
47	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.	
	PhB0	1	TTL	QEI module 0 phase B.	
-	Uldsr	1	TTL	UART module 1 Data Set Ready modem output control line.	
48	OSC0	ı	Analog	Main oscillator crystal input or an external clock reference input.	
49	OSC1	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.	

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description			
	PJ3	I/O	TTL	GPIO port J bit 3.			
	CCP6	I/O	TTL	Capture/Compare/PWM 6.			
50	EPIOS19	I/O	TTL	EPI module 0 signal 19.			
	U1CTS	I	TTL	UART module 1 Clear To Send modem flow control input signal.			
51	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.			
	рЈ4	I/O	TTL	GPIO port J bit 4.			
50	CCP4	I/O	TTL	Capture/Compare/PWM 4.			
52	EPIOS28	I/O	TTL	EPI module 0 signal 28.			
	U1DCD	I	TTL	UART module 1 Data Carrier Detect modem status input signal.			
	PJ5	I/O	TTL	GPIO port J bit 5.			
F0.	CCP2	I/O	TTL	Capture/Compare/PWM 2.			
53	EPIOS29	I/O	TTL	EPI module 0 signal 29.			
	U1DSR	I	TTL	UART module 1 Data Set Ready modem output control line.			
	PJ6	I/O	TTL	GPIO port J bit 6.			
F4	CCP1	I/O	TTL	Capture/Compare/PWM 1.			
54	EPIOS30	I/O	TTL	EPI module 0 signal 30.			
	U1RTS	0	TTL	UART module 1 Request to Send modem flow control output line.			
	РЈ7	I/O	TTL	GPIO port J bit 7.			
55	CCP0	I/O	TTL	Capture/Compare/PWM 0.			
	U1DTR	0	TTL	UART module 1 Data Terminal Ready modem status input signa			
56	VDD	-	Power	Positive supply for I/O and some logic.			
57	GND	-	Power	Ground reference for logic and I/O pins.			
58	MDIO	I/O	OD	MDIO of the Ethernet PHY.			
	PF3	I/O	TTL	GPIO port F bit 3.			
	LED0	0	TTL	Ethernet LED 0.			
59	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.			
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.			
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.			
	PF2	I/O	TTL	GPIO port F bit 2.			
	LED1	0	TTL	Ethernet LED 1.			
60	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.			
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.			
	SSI1Clk	I/O	TTL	SSI module 1 clock.			
	PF1	I/O	TTL	GPIO port F bit 1.			
	CAN1Tx	0	TTL	CAN module 1 transmit.			
	CCP3	I/O	TTL	Capture/Compare/PWM 3.			
61	I2S0TXMCLK	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.			
	IDX1	I	TTL	QEI module 1 index.			
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.			
	U1RTS	0	TTL	UART module 1 Request to Send modem flow control output line.			

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	РНб	I/O	TTL	GPIO port H bit 6.	
	EPIOS26	I/O	TTL	EPI module 0 signal 26.	
62	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.	
	SSI1Rx	I	TTL	SSI module 1 receive.	
	РН5	I/O	TTL	GPIO port H bit 5.	
62	EPIOS11	I/O	TTL	EPI module 0 signal 11.	
63	Fault2	I	TTL	PWM Fault 2.	
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.	
64	RST	I	TTL	System reset input.	
	PB3	I/O	TTL	GPIO port B bit 3.	
	Fault0	I	TTL	PWM Fault 0.	
65	Fault3	Į.	TTL	PWM Fault 3.	
	I2C0SDA	I/O	OD	I <sup>2</sup> C module 0 data.	
-	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
	PB0	I/O	TTL	GPIO port B bit 0. This pin is not 5-V tolerant.	
	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.	
66	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.	
	USB0ID	I	Analog	This signal senses the state of the USB ID signal. The USB PH enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).	
	PB1	I/O	TTL	GPIO port B bit 1. This pin is not 5-V tolerant.	
	CCP1	I/O	TTL	Capture/Compare/PWM 1.	
	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
0-7	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.	
67 -	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.	
-	USB0VBUS	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.	
68	VDD	-	Power	Positive supply for I/O and some logic.	
69	GND	-	Power	Ground reference for logic and I/O pins.	
70	USB0DM	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.	
71	USB0DP	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.	

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PB2	I/O	TTL	GPIO port B bit 2.	
-	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
	CCP3	I/O	TTL	Capture/Compare/PWM 3.	
72	I2C0SCL	I/O	OD	I <sup>2</sup> C module 0 clock.	
	IDX0	I	TTL	QEI module 0 index.	
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.	
73	USB0RBIAS	0	Analog	9.1-kΩ resistor (1% precision) used internally for USB analog circuitry.	
	PE0	I/O	TTL	GPIO port E bit 0.	
	CCP3	I/O	TTL	Capture/Compare/PWM 3.	
-	EPI0S8	I/O	TTL	EPI module 0 signal 8.	
74	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.	
	SSI1Clk	I/O	TTL	SSI module 1 clock.	
	USB0PFLT	1	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
	PE1	I/O	TTL	GPIO port E bit 1.	
	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
	CCP6	I/O	TTL	Capture/Compare/PWM 6.	
75	EPI0S9	I/O	TTL	EPI module 0 signal 9.	
	Fault0	I	TTL	PWM Fault 0.	
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.	
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.	
	PH4	I/O	TTL	GPIO port H bit 4.	
-	EPI0S10	I/O	TTL	EPI module 0 signal 10.	
76	SSI1Clk	I/O	TTL	SSI module 1 clock.	
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
	PC3	I/O	TTL	GPIO port C bit 3.	
77	SWO	0	TTL	JTAG TDO and SWO.	
	TDO	0	TTL	JTAG TDO and SWO.	
70	PC2	I/O	TTL	GPIO port C bit 2.	
78	TDI	ı	TTL	JTAG TDI.	
	PC1	I/O	TTL	GPIO port C bit 1.	
79	SWDIO	I/O	TTL	JTAG TMS and SWDIO.	
	TMS	I	TTL	JTAG TMS and SWDIO.	
	PC0	I/O	TTL	GPIO port C bit 0.	
80	SWCLK	I	TTL	JTAG/SWD CLK.	
	TCK	ı	TTL	JTAG/SWD CLK.	
81	VDD	-	Power	Positive supply for I/O and some logic.	
82	GND	-	Power	Ground reference for logic and I/O pins.	

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	РН3	I/O	TTL	GPIO port H bit 3.	
	EPI0S0	I/O	TTL	EPI module 0 signal 0.	
83	Fault0	I	TTL	PWM Fault 0.	
	PhB0	I	TTL	QEI module 0 phase B.	
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.	
	PH2	I/O	TTL	GPIO port H bit 2.	
	Clo	0	TTL	Analog comparator 1 output.	
84	EPIOS1	I/O	TTL	EPI module 0 signal 1.	
	Fault3	I	TTL	PWM Fault 3.	
	IDX1	I	TTL	QEI module 1 index.	
	PH1	I/O	TTL	GPIO port H bit 1.	
	CCP7	I/O	TTL	Capture/Compare/PWM 7.	
85	EPIOS7	I/O	TTL	EPI module 0 signal 7.	
	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.	
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.	
	РН0	I/O	TTL	GPIO port H bit 0.	
	CCP6	I/O	TTL	Capture/Compare/PWM 6.	
86	EPIOS6	I/O	TTL	EPI module 0 signal 6.	
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.	
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.	
	PJ1	I/O	TTL	GPIO port J bit 1.	
	EPIOS17	I/O	TTL	EPI module 0 signal 17.	
87	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.	
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.	
	USB0PFLT	1	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
88	VDDC	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .	
89	PB7	I/O	TTL	GPIO port B bit 7.	
09	NMI	I	TTL	Non-maskable interrupt.	

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PB6	I/O	TTL	GPIO port B bit 6.	
	C0+	I	Analog	Analog comparator 0 positive input.	
	C0o	0	TTL	Analog comparator 0 output.	
	CCP1	I/O	TTL	Capture/Compare/PWM 1.	
	CCP5	I/O	TTL	Capture/Compare/PWM 5.	
	CCP7	I/O	TTL	Capture/Compare/PWM 7.	
90	Fault1	I	TTL	PWM Fault 1.	
	I2SOTXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.	
	IDX0	I	TTL	QEI module 0 index.	
	VREFA	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.	
	PB5	I/O	TTL	GPIO port B bit 5.	
	AIN11	I	Analog	Analog-to-digital converter input 11.	
	C0o	0	TTL	Analog comparator 0 output.	
	C1-	I	Analog	Analog comparator 1 negative input.	
	CAN0Tx	0	TTL	CAN module 0 transmit.	
91	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
	CCP5	I/O	TTL	Capture/Compare/PWM 5.	
	CCP6	I/O	TTL	Capture/Compare/PWM 6.	
	EPI0S22	I/O	TTL	EPI module 0 signal 22.	
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.	
	PB4	I/O	TTL	GPIO port B bit 4.	
	AIN10	I	Analog	Analog-to-digital converter input 10.	
	C0-	I	Analog	Analog comparator 0 negative input.	
	CAN0Rx	I	TTL	CAN module 0 receive.	
92	EPI0S23	I/O	TTL	EPI module 0 signal 23.	
	IDX0	I	TTL	QEI module 0 index.	
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.	
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.	
93	VDD	-	Power	Positive supply for I/O and some logic.	
94	GND	-	Power	Ground reference for logic and I/O pins.	

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PE2	I/O	TTL	GPIO port E bit 2.
	AIN9	ı	Analog	Analog-to-digital converter input 9.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
95	CCP4	I/O	TTL	Capture/Compare/PWM 4.
95	EPI0S24	I/O	TTL	EPI module 0 signal 24.
	PhA0	ı	TTL	QEI module 0 phase A.
	PhB1	I	TTL	QEI module 1 phase B.
	SSI1Rx	I	TTL	SSI module 1 receive.
	PE3	I/O	TTL	GPIO port E bit 3.
	AIN8	I	Analog	Analog-to-digital converter input 8.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
96	CCP7	I/O	TTL	Capture/Compare/PWM 7.
90 _	EPIOS25	I/O	TTL	EPI module 0 signal 25.
Γ	PhA1	I	TTL	QEI module 1 phase A.
	PhB0	ı	TTL	QEI module 0 phase B.
	SSI1Tx	0	TTL	SSI module 1 transmit.
	PD4	I/O	TTL	GPIO port D bit 4.
	AIN7	ı	Analog	Analog-to-digital converter input 7.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
97	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	EPIOS19	I/O	TTL	EPI module 0 signal 19.
	I2S0RXSD	I/O	TTL	I <sup>2</sup> S module 0 receive data.
	U1RI	I	TTL	UART module 1 Ring Indicator modem status input signal.
	PD5	I/O	TTL	GPIO port D bit 5.
	AIN6	I	Analog	Analog-to-digital converter input 6.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
98	CCP4	I/O	TTL	Capture/Compare/PWM 4.
	EPIOS28	I/O	TTL	EPI module 0 signal 28.
	I2S0RXMCLK	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
	PD6	I/O	TTL	GPIO port D bit 6.
	AIN5	ı	Analog	Analog-to-digital converter input 5.
	EPIOS29	I/O	TTL	EPI module 0 signal 29.
99	Fault0	ı	TTL	PWM Fault 0.
	I2S0TXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.

Table 24-2. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PD7	I/O	TTL	GPIO port D bit 7.	
	AIN4	I	Analog	Analog-to-digital converter input 4.	
	C0o	0	TTL	Analog comparator 0 output.	
100	CCP1	I/O	TTL	Capture/Compare/PWM 1.	
100	EPIOS30	I/O	TTL	EPI module 0 signal 30.	
	I2SOTXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.	
	IDX0	I	TTL	QEI module 0 index.	
	U1DTR	0	TTL	UART module 1 Data Terminal Ready modem status input signal.	

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

## 24.1.2 Signals by Signal Name

Table 24-3. Signals by Signal Name

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN0	1	PE7	I	Analog	Analog-to-digital converter input 0.
AIN1	2	PE6	I	Analog	Analog-to-digital converter input 1.
AIN2	5	PE5	I	Analog	Analog-to-digital converter input 2.
AIN3	6	PE4	I	Analog	Analog-to-digital converter input 3.
AIN4	100	PD7	ļ	Analog	Analog-to-digital converter input 4.
AIN5	99	PD6	I	Analog	Analog-to-digital converter input 5.
AIN6	98	PD5	I	Analog	Analog-to-digital converter input 6.
AIN7	97	PD4	ļ	Analog	Analog-to-digital converter input 7.
AIN8	96	PE3	I	Analog	Analog-to-digital converter input 8.
AIN9	95	PE2	ļ	Analog	Analog-to-digital converter input 9.
AIN10	92	PB4	I	Analog	Analog-to-digital converter input 10.
AIN11	91	PB5	ļ	Analog	Analog-to-digital converter input 11.
AIN12	13	PD3	ļ	Analog	Analog-to-digital converter input 12.
AIN13	12	PD2	I	Analog	Analog-to-digital converter input 13.
AIN14	11	PD1	ļ	Analog	Analog-to-digital converter input 14.
AIN15	10	PD0	I	Analog	Analog-to-digital converter input 15.
C0+	90	PB6	I	Analog	Analog comparator 0 positive input.
C0-	92	PB4	I	Analog	Analog comparator 0 negative input.
COo	24 42 90 91 100	PC5 (3) PF4 (2) PB6 (3) PB5 (1) PD7 (2)	0	TTL	Analog comparator 0 output.
C1+	24	PC5	I	Analog	Analog comparator 1 positive input.
C1-	91	PB5	I	Analog	Analog comparator 1 negative input.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
Clo	2 22 24 41 84	PE6 (2) PC7 (7) PC5 (2) PF5 (2) PH2 (2)	0	TTL	Analog comparator 1 output.
C2+	23	PC6	I	Analog	Analog comparator 2 positive input.
C2-	22	PC7	I	Analog	Analog comparator 2 negative input.
C2o	1 23	PE7 (2) PC6 (3)	0	TTL	Analog comparator 2 output.
CANORX	10 30 34 92	PD0 (2) PA4 (5) PA6 (6) PB4 (5)	I	TTL	CAN module 0 receive.
CAN0Tx	11 31 35 91	PD1 (2) PA5 (5) PA7 (6) PB5 (5)	0	TTL	CAN module 0 transmit.
CAN1Rx	47	PF0 (1)	I	TTL	CAN module 1 receive.
CAN1Tx	61	PF1 (1)	0	TTL	CAN module 1 transmit.
CCP0	13 22 23 39 42 55 66 72 91 97	PD3 (4) PC7 (4) PC6 (6) PJ2 (9) PF4 (1) PJ7 (10) PB0 (1) PB2 (5) PB5 (4) PD4 (1)	I/O	TTL	Capture/Compare/PWM 0.
CCP1	24 25 34 54 67 90 96 100	PC5 (1) PC4 (9) PA6 (2) PJ6 (10) PB1 (4) PB6 (1) PE3 (1) PD7 (3)	I/O	TTL	Capture/Compare/PWM 1.
CCP2	6 11 25 41 53 67 75 91 95	PE4 (6) PD1 (10) PC4 (5) PF5 (1) PJ5 (10) PB1 (1) PE1 (4) PB5 (6) PE2 (5) PD5 (1)	I/O	TTL	Capture/Compare/PWM 2.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP3	6	PE4 (1)	I/O	TTL	Capture/Compare/PWM 3.
	23 24	PC6 (1) PC5 (5)			
	35	PA7 (7)			
	61	PF1 (10)			
	72 74	PB2 (4) PE0 (3)			
	97	PD4 (2)			
CCP4	22	PC7 (1)	I/O	TTL	Capture/Compare/PWM 4.
	25 35	PC4 (6) PA7 (2)			
	52	PJ4 (10)			
	95	PE2 (1)			
	98	PD5 (2)	1/0	TT1	O - 11 - 12 - 12 - 12 - 12 - 12 - 12 - 1
CCP5	5 12	PE5 (1) PD2 (4)	I/O	TTL	Capture/Compare/PWM 5.
	25	PC4 (1)			
	36	PG7 (8)			
	90 91	PB6 (6) PB5 (2)			
CCP6	10	PD0 (6)	I/O	TTL	Capture/Compare/PWM 6.
	12	PD2 (2)			
	50 75	PJ3 (10) PE1 (5)			
	86	PH0 (1)			
	91	PB5 (3)			
CCP7	11 13	PD1 (6)	I/O	TTL	Capture/Compare/PWM 7.
	85	PD3 (2) PH1 (1)			
	90	PB6 (2)			
	96	PE3 (5)			
EPI0S0	83	PH3 (8)	1/0	TTL	EPI module 0 signal 0.
EPIOS1	84	PH2 (8)	1/0	TTL	EPI module 0 signal 1.
EPI0S2	25	PC4 (8)	1/0	TTL	EPI module 0 signal 2.
EPIOS3	24	PC5 (8)	1/0	TTL	EPI module 0 signal 3.
EPI0S4	23	PC6 (8)	1/0	TTL	EPI module 0 signal 4.
EPI0S5	22	PC7 (8)	1/0	TTL	EPI module 0 signal 5.
EPI0S6	86	PH0 (8)	1/0	TTL	EPI module 0 signal 6.
EPIOS7	85	PH1 (8)	1/0	TTL	EPI module 0 signal 7.
EPIOS8	74	PE0 (8)	I/O	TTL	EPI module 0 signal 8.
EPIOS9	75	PE1 (8)	I/O	TTL	EPI module 0 signal 9.
EPIOS10	76	PH4 (8)	I/O	TTL	EPI module 0 signal 10.
EPIOS11	63	PH5 (8)	1/0	TTL	EPI module 0 signal 11.
EPIOS12	42	PF4 (8)	1/0	TTL	EPI module 0 signal 12.
EPIOS13	19	PG0 (8)	1/0	TTL	EPI module 0 signal 13.
EPIOS14	18	PG1 (8)	1/0	TTL	EPI module 0 signal 14.
EPIOS15	41	PF5 (8)	1/0	TTL	EPI module 0 signal 15.
EPIOS16	14	PJ0 (8)	1/0	TTL	EPI module 0 signal 16.
EPIOS17	87	PJ1 (8)	I/O	TTL	EPI module 0 signal 17.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPIOS18	39	PJ2 (8)	I/O	TTL	EPI module 0 signal 18.
EPIOS19	50 97	PJ3 (8) PD4 (10)	I/O	TTL	EPI module 0 signal 19.
EPIOS20	12	PD2 (8)	I/O	TTL	EPI module 0 signal 20.
EPIOS21	13	PD3 (8)	I/O	TTL	EPI module 0 signal 21.
EPIOS22	91	PB5 (8)	I/O	TTL	EPI module 0 signal 22.
EPIOS23	92	PB4 (8)	I/O	TTL	EPI module 0 signal 23.
EPIOS24	95	PE2 (8)	I/O	TTL	EPI module 0 signal 24.
EPIOS25	96	PE3 (8)	I/O	TTL	EPI module 0 signal 25.
EPIOS26	62	PH6 (8)	I/O	TTL	EPI module 0 signal 26.
EPIOS27	15	PH7 (8)	I/O	TTL	EPI module 0 signal 27.
EPIOS28	52 98	PJ4 (8) PD5 (10)	I/O	TTL	EPI module 0 signal 28.
EPIOS29	53 99	PJ5 (8) PD6 (10)	I/O	TTL	EPI module 0 signal 29.
EPIOS30	54 100	PJ6 (8) PD7 (10)	I/O	TTL	EPI module 0 signal 30.
EPIOS31	36	PG7 (9)	I/O	TTL	EPI module 0 signal 31.
ERBIAS	33	fixed	0	Analog	12.4-k $\Omega$ resistor (1% precision) used internally for Ethernet PHY.
Fault0	6 39 42 65 75 83 99	PE4 (4) PJ2 (10) PF4 (4) PB3 (2) PE1 (3) PH3 (2) PD6 (1)	ľ	TTL	PWM Fault 0.
Fault1	90	PB6 (4)	1	TTL	PWM Fault 1.
Fault2	24 63	PC5 (4) PH5 (10)	1	TTL	PWM Fault 2.
Fault3	65 84	PB3 (4) PH2 (4)	1	TTL	PWM Fault 3.
GND	9 21 45 57 69 82 94	fixed	-	Power	Ground reference for logic and I/O pins.
GNDA	4	fixed	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
I2C0SCL	72	PB2 (1)	I/O	OD	I <sup>2</sup> C module 0 clock.
I2C0SDA	65	PB3 (1)	I/O	OD	I <sup>2</sup> C module 0 data.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
I2C1SCL	14 19 26 34	PJ0 (11) PG0 (3) PA0 (8) PA6 (1)	I/O	OD	I <sup>2</sup> C module 1 clock.
I2C1SDA	18 27 35 87	PG1 (3) PA1 (8) PA7 (1) PJ1 (11)	I/O	OD	I <sup>2</sup> C module 1 data.
I2S0RXMCLK	29 98	PA3 (9) PD5 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
I2S0RXSCK	10	PD0 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
I2S0RXSD	28 97	PA2 (9) PD4 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive data.
I2S0RXWS	11	PD1 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
I2S0TXMCLK	61	PF1 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
I2SOTXSCK	30 90 99	PA4 (9) PB6 (9) PD6 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
I2SOTXSD	5 47	PE5 (9) PF0 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
I2SOTXWS	6 31 100	PE4 (9) PA5 (9) PD7 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
IDX0	10 72 90 92 100	PD0 (3) PB2 (2) PB6 (5) PB4 (6) PD7 (1)	I	TTL	QEI module 0 index.
IDX1	61 84	PF1 (2) PH2 (1)	I	TTL	QEI module 1 index.
LDO	7	fixed	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).
LED0	59	PF3 (1)	0	TTL	Ethernet LED 0.
LED1	60	PF2 (1)	0	TTL	Ethernet LED 1.
MDIO	58	fixed	I/O	OD	MDIO of the Ethernet PHY.
NC	51	fixed	-	-	No connect. Leave the pin electrically unconnected/isolated.
NMI	89	PB7 (4)	I	TTL	Non-maskable interrupt.
OSC0	48	fixed	I	Analog	Main oscillator crystal input or an external clock reference input.
OSC1	49	fixed	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
PA0	26	-	I/O	TTL	GPIO port A bit 0.
PA1	27	-	I/O	TTL	GPIO port A bit 1.
PA2	28	-	I/O	TTL	GPIO port A bit 2.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PA3	29	-	I/O	TTL	GPIO port A bit 3.
PA4	30	-	I/O	TTL	GPIO port A bit 4.
PA5	31	-	I/O	TTL	GPIO port A bit 5.
PA6	34	-	I/O	TTL	GPIO port A bit 6.
PA7	35	-	I/O	TTL	GPIO port A bit 7.
PB0	66	-	I/O	TTL	GPIO port B bit 0. This pin is not 5-V tolerant.
PB1	67	-	I/O	TTL	GPIO port B bit 1. This pin is not 5-V tolerant.
PB2	72	-	I/O	TTL	GPIO port B bit 2.
PB3	65	-	I/O	TTL	GPIO port B bit 3.
PB4	92	-	I/O	TTL	GPIO port B bit 4.
PB5	91	-	I/O	TTL	GPIO port B bit 5.
PB6	90	-	I/O	TTL	GPIO port B bit 6.
PB7	89	-	I/O	TTL	GPIO port B bit 7.
PC0	80	-	I/O	TTL	GPIO port C bit 0.
PC1	79	-	I/O	TTL	GPIO port C bit 1.
PC2	78	-	I/O	TTL	GPIO port C bit 2.
PC3	77	-	I/O	TTL	GPIO port C bit 3.
PC4	25	-	I/O	TTL	GPIO port C bit 4.
PC5	24	-	I/O	TTL	GPIO port C bit 5.
PC6	23	-	I/O	TTL	GPIO port C bit 6.
PC7	22	-	I/O	TTL	GPIO port C bit 7.
PD0	10	-	I/O	TTL	GPIO port D bit 0.
PD1	11	-	I/O	TTL	GPIO port D bit 1.
PD2	12	-	I/O	TTL	GPIO port D bit 2.
PD3	13	-	I/O	TTL	GPIO port D bit 3.
PD4	97	-	I/O	TTL	GPIO port D bit 4.
PD5	98	-	I/O	TTL	GPIO port D bit 5.
PD6	99	-	I/O	TTL	GPIO port D bit 6.
PD7	100	-	I/O	TTL	GPIO port D bit 7.
PE0	74	-	I/O	TTL	GPIO port E bit 0.
PE1	75	-	I/O	TTL	GPIO port E bit 1.
PE2	95	-	I/O	TTL	GPIO port E bit 2.
PE3	96	-	I/O	TTL	GPIO port E bit 3.
PE4	6	-	I/O	TTL	GPIO port E bit 4.
PE5	5	-	I/O	TTL	GPIO port E bit 5.
PE6	2	-	I/O	TTL	GPIO port E bit 6.
PE7	1	-	I/O	TTL	GPIO port E bit 7.
PF0	47	-	I/O	TTL	GPIO port F bit 0.
PF1	61	-	I/O	TTL	GPIO port F bit 1.
PF2	60	-	I/O	TTL	GPIO port F bit 2.
PF3	59	-	I/O	TTL	GPIO port F bit 3.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PF4	42	-	I/O	TTL	GPIO port F bit 4.
PF5	41	-	I/O	TTL	GPIO port F bit 5.
PG0	19	-	I/O	TTL	GPIO port G bit 0.
PG1	18	-	I/O	TTL	GPIO port G bit 1.
PG7	36	-	I/O	TTL	GPIO port G bit 7.
РН0	86	-	I/O	TTL	GPIO port H bit 0.
PH1	85	-	I/O	TTL	GPIO port H bit 1.
PH2	84	-	I/O	TTL	GPIO port H bit 2.
PH3	83	-	I/O	TTL	GPIO port H bit 3.
PH4	76	-	I/O	TTL	GPIO port H bit 4.
PH5	63	-	I/O	TTL	GPIO port H bit 5.
РН6	62	-	I/O	TTL	GPIO port H bit 6.
PH7	15	-	I/O	TTL	GPIO port H bit 7.
PhA0	11 25 95	PD1 (3) PC4 (2) PE2 (4)	I	TTL	QEI module 0 phase A.
PhA1	96	PE3 (3)	Į	TTL	QEI module 1 phase A.
PhB0	22 23 47 83 96	PC7 (2) PC6 (2) PF0 (2) PH3 (1) PE3 (4)	I	TTL	QEI module 0 phase B.
PhB1	11 36 95	PD1 (11) PG7 (1) PE2 (3)	I	TTL	QEI module 1 phase B.
PJ0	14	-	I/O	TTL	GPIO port J bit 0.
PJ1	87	-	I/O	TTL	GPIO port J bit 1.
PJ2	39	-	I/O	TTL	GPIO port J bit 2.
PJ3	50	-	I/O	TTL	GPIO port J bit 3.
PJ4	52	-	I/O	TTL	GPIO port J bit 4.
PJ5	53	-	I/O	TTL	GPIO port J bit 5.
PJ6	54	-	I/O	TTL	GPIO port J bit 6.
PJ7	55	-	I/O	TTL	GPIO port J bit 7.
РWМ0	10 14 19 34 47	PD0 (1) PJ0 (10) PG0 (2) PA6 (4) PF0 (3)	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
PWM1	11 18 35 61 87	PD1 (1) PG1 (2) PA7 (4) PF1 (3) PJ1 (10)	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PWM2	12	PD2 (3)	0	TTL	PWM 2. This signal is controlled by PWM Generator
	60 66	PF2 (4) PB0 (2)			1.
	86	PH0 (2)			
PWM3	13	PD3 (3)	0	TTL	PWM 3. This signal is controlled by PWM Generator
	59	PF3 (4)			1.
	67 85	PB1 (2) PH1 (2)			
PWM4	2	PE6 (1)	0	TTL	PWM 4. This signal is controlled by PWM Generator
L WITT	19	PG0 (4)	Ü	112	2.
	28	PA2 (4)			
	34	PA6 (5)			
	60	PF2 (2)			
	62 74	PH6 (10) PE0 (1)			
	86	PH0 (9)			
PWM5	1	PE7 (1)	0	TTL	PWM 5. This signal is controlled by PWM Generator
	15	PH7 (10)			2.
	18	PG1 (4)			
	29 35	PA3 (4) PA7 (5)			
	59	PF3 (2)			
	75	PE1 (1)			
	85	PH1 (9)			
PWM6	25	PC4 (4)	0	TTL	PWM 6. This signal is controlled by PWM Generator
	30	PA4 (4)			3.
PWM7	23	PC6 (4)	0	TTL	PWM 7. This signal is controlled by PWM Generator
	31 36	PA5 (4) PG7 (4)			3.
RST	64	fixed	1	TTL	System reset input.
RXIN	37	fixed	I	Analog	RXIN of the Ethernet PHY.
RXIP	40	fixed	I	Analog	RXIP of the Ethernet PHY.
SSI0Clk	28	PA2 (1)	I/O	TTL	SSI module 0 clock
SSI0Fss	29	PA3 (1)	I/O	TTL	SSI module 0 frame signal
SSIORx	30	PA4 (1)	1	TTL	SSI module 0 receive
SSIOTx	31	PA5 (1)	0	TTL	SSI module 0 transmit
SSI1Clk	60	PF2 (9)	I/O	TTL	SSI module 1 clock.
	74 76	PE0 (2) PH4 (11)			
SSI1Fss	59	PF3 (9)	I/O	TTL	SSI module 1 frame signal.
	63	PH5 (11)			
	75	PE1 (2)			
SSI1Rx	42	PF4 (9)	1	TTL	SSI module 1 receive.
	62 05	PH6 (11)			
	95	PE2 (2)		TT:	001
SSI1Tx	15 41	PH7 (11) PF5 (9)	0	TTL	SSI module 1 transmit.
	96	PE3 (2)			
SWCLK	80	PC0 (3)	1	TTL	JTAG/SWD CLK.
		PC1 (3)		<del>                                     </del>	

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SWO	77	PC3 (3)	0	TTL	JTAG TDO and SWO.
TCK	80	PC0 (3)	I	TTL	JTAG/SWD CLK.
TDI	78	PC2 (3)	I	TTL	JTAG TDI.
TDO	77	PC3 (3)	0	TTL	JTAG TDO and SWO.
TMS	79	PC1 (3)	I	TTL	JTAG TMS and SWDIO.
TXON	46	fixed	0	TTL	TXON of the Ethernet PHY.
TXOP	43	fixed	0	TTL	TXOP of the Ethernet PHY.
U0Rx	26	PA0 (1)	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
UOTx	27	PA1 (1)	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.
U1CTS	2 10 34 50	PE6 (9) PD0 (9) PA6 (9) PJ3 (9)	I	TTL	UART module 1 Clear To Send modem flow control input signal.
U1DCD	1 11 35 52	PE7 (9) PD1 (9) PA7 (9) PJ4 (9)	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
U1DSR	47 53	PF0 (9) PJ5 (9)	I	TTL	UART module 1 Data Set Ready modem output control line.
U1DTR	55 100	PJ7 (9) PD7 (9)	0	TTL	UART module 1 Data Terminal Ready modem status input signal.
U1RI	97	PD4 (9)	ı	TTL	UART module 1 Ring Indicator modem status input signal.
U1RTS	54 61	PJ6 (9) PF1 (9)	0	TTL	UART module 1 Request to Send modem flow control output line.
UlRx	10 12 23 26 66 92	PD0 (5) PD2 (1) PC6 (5) PA0 (9) PB0 (5) PB4 (7)	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
UlTx	11 13 22 27 67 91	PD1 (5) PD3 (1) PC7 (5) PA1 (9) PB1 (5) PB5 (7)	O	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
U2Rx	10 19 92 98	PD0 (4) PG0 (1) PB4 (4) PD5 (9)	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
U2Tx	6 11 18 99	PE4 (5) PD1 (4) PG1 (1) PD6 (9)	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
USB0DM	70	fixed	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
USB0DP	71	fixed	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
USB0EPEN	19 24 34 72 83	PG0 (7) PC5 (6) PA6 (8) PB2 (8) PH3 (4)	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USB0ID	66	PB0	ı	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).
USBOPFLT	22 23 35 65 74 76 87	PC7 (6) PC6 (7) PA7 (8) PB3 (8) PE0 (9) PH4 (4) PJ1 (9)	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
USB0RBIAS	73	fixed	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
USB0VBUS	67	PB1	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.
VDD	8 20 32 44 56 68 81 93	fixed	-	Power	Positive supply for I/O and some logic.
VDDA	3	fixed	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
VDDC	38 88	fixed	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The $\mathtt{VDDC}$ pins should only be connected to the $\mathtt{LDO}$ pin and an external capacitor as specified in .
VREFA	90	PB6	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.

Table 24-3. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
XTALNPHY	17	fixed	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
XTALPPHY	16	fixed	ĺ		Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### 24.1.3 Signals by Function, Except for GPIO

Table 24-4. Signals by Function, Except for GPIO

Function	Pin Name	Pin Number Pin Type Buffer Type <sup>a</sup> Description					
	AIN0	1	I	Analog	Analog-to-digital converter input 0.		
	AIN1	2	I	Analog	Analog-to-digital converter input 1.		
	AIN2	5	I	Analog	Analog-to-digital converter input 2.		
	AIN3	6	I	Analog	Analog-to-digital converter input 3.		
	AIN4	100	I	Analog	Analog-to-digital converter input 4.		
	AIN5	99	I	Analog	Analog-to-digital converter input 5.		
	AIN6	98	I	Analog	Analog-to-digital converter input 6.		
	AIN7	97	I	Analog	Analog-to-digital converter input 7.		
	AIN8	96	I	Analog	Analog-to-digital converter input 8.		
	AIN9	95	I	I Analog Analog-to-digital converter in			
ADC	AIN10	92	I	I Analog Analog-to-digital converter inpu			
	AIN11	91	l	Analog	Analog-to-digital converter input 11.		
	AIN12	13	I	Analog	Analog-to-digital converter input 12.		
	AIN13	12	I	Analog	Analog-to-digital converter input 13.		
	AIN14	11	I	Analog	Analog-to-digital converter input 14.		
	AIN15	10	I	Analog	Analog-to-digital converter input 15.		
	VREFA	90	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.		

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	C0+	90	Ι	Analog	Analog comparator 0 positive input.
	C0-	92	Ι	Analog	Analog comparator 0 negative input.
	C0o	24 42 90 91 100	0	TTL	Analog comparator 0 output.
	C1+	24	I	Analog	Analog comparator 1 positive input.
Analog Comparators	C1-	91	I	Analog	Analog comparator 1 negative input.
	Clo	2 22 24 41 84	0	TTL	Analog comparator 1 output.
	C2+	23	I	Analog	Analog comparator 2 positive input.
	C2-	22	I	Analog	Analog comparator 2 negative input.
	C20	1 23	0	TTL	Analog comparator 2 output.
	CAN0Rx	10 30 34 92	I	TTL	CAN module 0 receive.
Controller Area Network	CAN0Tx	11 31 35 91	0	TTL	CAN module 0 transmit.
	CAN1Rx	47	I	TTL	CAN module 1 receive.
	CAN1Tx	61	0	TTL	CAN module 1 transmit.
	ERBIAS	33	0	Analog	12.4- $k\Omega$ resistor (1% precision) used internally for Ethernet PHY.
	LED0	59	0	TTL	Ethernet LED 0.
	LED1	60	0	TTL	Ethernet LED 1.
	MDIO	58	I/O	OD	MDIO of the Ethernet PHY.
	RXIN	37	I	Analog	RXIN of the Ethernet PHY.
Ethernet	RXIP	40	-	Analog	RXIP of the Ethernet PHY.
Ethernet	TXON	46	0	TTL	TXON of the Ethernet PHY.
	TXOP	43	0	TTL	TXOP of the Ethernet PHY.
	XTALNPHY	17	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
	ХТАГРЬНА	16	I	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Function Pin Name		Pin Type	Buffer Type <sup>a</sup>	Description
	EPI0S0	83	I/O	TTL	EPI module 0 signal 0.
	EPIOS1	84	I/O	TTL	EPI module 0 signal 1.
	EPI0S2	25	I/O	TTL	EPI module 0 signal 2.
	EPIOS3	24	I/O	TTL	EPI module 0 signal 3.
	EPI0S4	23	I/O	TTL	EPI module 0 signal 4.
	EPIOS5	22	I/O	TTL	EPI module 0 signal 5.
	EPIOS6	86	I/O	TTL	EPI module 0 signal 6.
	EPIOS7	85	I/O	TTL	EPI module 0 signal 7.
	EPIOS8	74	I/O	TTL	EPI module 0 signal 8.
	EPIOS9	75	I/O	TTL	EPI module 0 signal 9.
	EPIOS10	76	I/O	TTL	EPI module 0 signal 10.
	EPIOS11	63	I/O	TTL	EPI module 0 signal 11.
	EPIOS12	42	I/O	TTL	EPI module 0 signal 12.
	EPIOS13	19	I/O	TTL	EPI module 0 signal 13.
	EPIOS14	18	I/O	TTL	EPI module 0 signal 14.
	EPIOS15	41	I/O	TTL	EPI module 0 signal 15.
Fishermal Devices and	EPIOS16	14	I/O	TTL	EPI module 0 signal 16.
External Peripheral Interface	EPIOS17	87	I/O	TTL	EPI module 0 signal 17.
	EPIOS18	39	I/O	TTL	EPI module 0 signal 18.
	EPIOS19	50 97	I/O	TTL	EPI module 0 signal 19.
	EPI0S20	12	I/O	TTL	EPI module 0 signal 20.
	EPI0S21	13	I/O	TTL	EPI module 0 signal 21.
	EPI0S22	91	I/O	TTL	EPI module 0 signal 22.
	EPI0S23	92	I/O	TTL	EPI module 0 signal 23.
	EPI0S24	95	I/O	TTL	EPI module 0 signal 24.
	EPI0S25	96	I/O	TTL	EPI module 0 signal 25.
	EPI0S26	62	I/O	TTL	EPI module 0 signal 26.
	EPI0S27	15	I/O	TTL	EPI module 0 signal 27.
	EPIOS28	52 98	I/O	TTL	EPI module 0 signal 28.
	EPIOS29	53 99	I/O	TTL	EPI module 0 signal 29.
	EPIOS30	54 100	I/O	TTL	EPI module 0 signal 30.
	EPIOS31	36	I/O	TTL	EPI module 0 signal 31.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	CCP0	13 22 23 39 42 55 66 72 91	I/O	TTL	Capture/Compare/PWM 0.
	CCP1	24 25 34 54 67 90 96 100	I/O	TTL	Capture/Compare/PWM 1.
General-Purpose	CCP2	6 11 25 41 53 67 75 91 95	I/O	TTL	Capture/Compare/PWM 2.
Timers	CCP3	6 23 24 35 61 72 74	I/O	TTL	Capture/Compare/PWM 3.
	CCP4	22 25 35 52 95 98	I/O	TTL	Capture/Compare/PWM 4.
	CCP5	5 12 25 36 90 91	I/O	TTL	Capture/Compare/PWM 5.
	CCP6	10 12 50 75 86 91	I/O	TTL	Capture/Compare/PWM 6.
	CCP7		I/O	TTL	Capture/Compare/PWM 7.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
		11 13 85 90 96			
	I2C0SCL	72	I/O	OD	I <sup>2</sup> C module 0 clock.
	I2C0SDA	65	I/O	OD	I <sup>2</sup> C module 0 data.
12C	I2C1SCL	14 19 26 34	I/O	OD	I <sup>2</sup> C module 1 clock.
	I2C1SDA	18 27 35 87	I/O	OD	I <sup>2</sup> C module 1 data.
	I2S0RXMCLK	29 98	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
	I2S0RXSCK	10	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
	I2S0RXSD	28 97	I/O	TTL	I <sup>2</sup> S module 0 receive data.
	I2S0RXWS	11	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
128	I2S0TXMCLK	61	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
123	I2SOTXSCK	30 90 99	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	I2SOTXSD	5 47	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
	I2SOTXWS	6 31 100	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	SWCLK	80	I	TTL	JTAG/SWD CLK.
	SWDIO	79	I/O	TTL	JTAG TMS and SWDIO.
	SWO	77	0	TTL	JTAG TDO and SWO.
JTAG/SWD/SWO	TCK	80	I	TTL	JTAG/SWD CLK.
	TDI	78	I	TTL	JTAG TDI.
	TDO	77	0	TTL	JTAG TDO and SWO.
	TMS	79	I	TTL	JTAG TMS and SWDIO.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	Fault0	6 39 42 65 75 83 99	I	TTL	PWM Fault 0.
	Fault1	90	I	TTL	PWM Fault 1.
	Fault2	24 63	I	TTL	PWM Fault 2.
	Fault3	65 84	I	TTL	PWM Fault 3.
	РWМО	10 14 19 34 47	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
	PWM1	11 18 35 61 87	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
PWM	PWM2	12 60 66 86	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
	PWM3	13 59 67 85	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
	PWM4	2 19 28 34 60 62 74 86	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	РWM5	1 15 18 29 35 59 75 85	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	РWМ6	25 30	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
	РWM7	23 31 36	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	GND	9 21 45 57 69 82 94	-	Power	Ground reference for logic and I/O pins.
	GNDA	4	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
	LDO	7	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).
Power	VDD	8 20 32 44 56 68 81 93	-	Power	Positive supply for I/O and some logic.
	VDDA	3	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
	VDDC	38 88	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	IDX0	10 72 90 92 100	I	TTL	QEI module 0 index.
	IDX1	61 84	I	TTL	QEI module 1 index.
QEI	PhA0	11 25 95	I	TTL	QEI module 0 phase A.
	PhA1	96	I	TTL	QEI module 1 phase A.
	PhB0	22 23 47 83 96	I	TTL	QEI module 0 phase B.
	PhB1	11 36 95	I	TTL	QEI module 1 phase B.
	SSI0Clk	28	I/O	TTL	SSI module 0 clock
	SSI0Fss	29	I/O	TTL	SSI module 0 frame signal
	SSI0Rx	30	I	TTL	SSI module 0 receive
	SSI0Tx	31	0	TTL	SSI module 0 transmit
	SSI1Clk	60 74 76	I/O	TTL	SSI module 1 clock.
SSI	SSI1Fss	59 63 75	I/O	TTL	SSI module 1 frame signal.
	SSI1Rx	42 62 95	I	TTL	SSI module 1 receive.
	SSI1Tx	15 41 96	0	TTL	SSI module 1 transmit.
	NMI	89	I	TTL	Non-maskable interrupt.
System Control &	osc0	48	I	Analog	Main oscillator crystal input or an external clock reference input.
Clocks	osc1	49	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
	RST	64	ı	TTL	System reset input.

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description		
	U0Rx	26	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.		
	UOTx	27	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.		
	U1CTS	2 10 34 50	I	TTL	UART module 1 Clear To Send modem flow control input signal.		
	U1DCD	1 11 35 52	I	TTL	UART module 1 Data Carrier Detect modem status input signal.		
	U1DSR	47 53	ı	TTL	UART module 1 Data Set Ready modem output control line.		
	U1DTR	55 100	0	TTL	UART module 1 Data Terminal Ready modem status input signal.		
	U1RI	97	I	TTL	UART module 1 Ring Indicator modem status inp signal.		
UART	U1RTS	54 61	0	TTL	UART module 1 Request to Send modem flow control output line.		
	UlRx	10 12 23 26 66 92	l	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.		
	UlTx	11 13 22 27 67 91	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.		
	U2Rx	10 19 92 98	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.		
	U2Tx	6 11 18 99	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.		

Table 24-4. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	USB0DM	70	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
	USB0DP	71	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
	USB0EPEN	19 24 34 72 83	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USB	USB0ID	66	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).
	USB0PFLT	22 23 35 65 74 76 87	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
	USB0RBIAS	73	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
	USB0VBUS	67	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

# 24.1.4 GPIO Pins and Alternate Functions

**Table 24-5. GPIO Pins and Alternate Functions** 

10	Pin	Analog			Digi	tal Functi	ion (GPIO	PCTL PM	Cx Bit Fie	ld Encodi	ng) <sup>a</sup>		
10	PIII	Function	1	2	3	4	5	6	7	8	9	10	11
PA0	26	-	U0Rx	-	-	-	-	-	-	I2C1SCL	U1Rx	-	-
PA1	27	-	U0Tx	-	-	-	-	-	-	I2C1SDA	UlTx	-	-
PA2	28	-	SSI0Clk	-	-	PWM4	-	-	-	-	I2S0RXSD	-	-
PA3	29	-	SSI0Fss	-	-	PWM5	-	-	-	-	I2SORXMCLK	-	-
PA4	30	-	SSI0Rx	-	-	PWM6	CAN0Rx	-	-	-	I2SOTXSCK	-	-
PA5	31	-	SSIOTx	-	-	PWM7	CAN0Tx	-	-	-	I2SOTXWS	-	-
PA6	34	-	I2C1SCL	CCP1	-	PWM0	PWM4	CAN0Rx	-	USB0EPEN	U1CTS	-	-
PA7	35	-	I2C1SDA	CCP4	-	PWM1	PWM5	CAN0Tx	CCP3	USB0PFLT	U1DCD	-	-
PB0	66	USB0ID	CCP0	PWM2	-	-	U1Rx	-	-	-	-	-	-
PB1	67	USB0VBUS	CCP2	PWM3	-	CCP1	U1Tx	-	-	-	-	-	-
PB2	72	-	I2C0SCL	IDX0	-	CCP3	CCP0	-	-	USB0EPEN	-	-	-
PB3	65	-	I2C0SDA	Fault0	-	Fault3	-	-	-	USB0PFLT	-	-	-
PB4	92	AIN10 CO-	-	-	-	U2Rx	CAN0Rx	IDX0	U1Rx	EPI0S23	-	-	-

Table 24-5. GPIO Pins and Alternate Functions (continued)

10	D:	Analog Digital Function (GPIOPCTL PMCx Bit Field Encoding) <sup>a</sup>											
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PB5	91	AIN11 C1-	C0o	CCP5	CCP6	CCP0	CAN0Tx	CCP2	U1Tx	EPI0S22	-	-	-
PB6	90	VREFA C0+	CCP1	CCP7	C00	Fault1	IDX0	CCP5	-	-	I2SOTXSCK	-	-
PB7	89	-	-	-	-	NMI	-	-	-	-	-	-	-
PC0	80	-	-	-	TCK SWCLK	-	-	-	-	-	-	-	-
PC1	79	-	-	-	TMS SWDIO	-	-	-	-	-	-	-	-
PC2	78	-	-	-	TDI	-	-	-	-	-	-	-	-
PC3	77	-	-	-	TDO SWO	-	-	-	-	-	-	-	-
PC4	25	-	CCP5	PhA0	-	PWM6	CCP2	CCP4	-	EPI0S2	CCP1	-	-
PC5	24	C1+	CCP1	C1o	C0o	Fault2	CCP3	USB0EPEN	-	EPI0S3	-	-	-
PC6	23	C2+	CCP3	PhB0	C20	PWM7	U1Rx	CCP0	USB0PFLT	EPI0S4	-	-	-
PC7	22	C2-	CCP4	PhB0	-	CCP0	U1Tx	USB0PFLT	C10	EPI0S5	-	-	-
PD0	10	AIN15	PWM0	CAN0Rx	IDX0	U2Rx	U1Rx	CCP6	-	I2SORXSCK	U1CTS	-	-
PD1	11	AIN14	PWM1	CAN0Tx	PhA0	U2Tx	U1Tx	CCP7	-	I2SORXWS	U1DCD	CCP2	PhB1
PD2	12	AIN13	U1Rx	CCP6	PWM2	CCP5	-	-	-	EPI0S20	-	-	-
PD3	13	AIN12	U1Tx	CCP7	PWM3	CCP0	-	-	-	EPI0S21	-	-	-
PD4	97	AIN7	CCP0	CCP3	-	-	-	-	-	I2S0RXSD	U1RI	EPIOS19	-
PD5	98	AIN6	CCP2	CCP4	-	-	-	-	-	I2SORXMCLK	U2Rx	EPIOS28	-
PD6	99	AIN5	Fault0	-	-	-	-	-	-	I2SOTXSCK	U2Tx	EPIOS29	-
PD7	100	AIN4	IDX0	C0o	CCP1	-	-	-	-	I2SOTXWS	U1DTR	EPIOS30	-
PE0	74	-	PWM4	SSI1Clk	CCP3	-	-	-	-	EPIOS8	USB0PFLT	-	-
PE1	75	-	PWM5	SSI1Fss	Fault0	CCP2	CCP6	-	-	EPIOS9	-	-	-
PE2	95	AIN9	CCP4	SSI1Rx	PhB1	PhA0	CCP2	-	-	EPI0S24	-	-	-
PE3	96	AIN8	CCP1	SSI1Tx	PhA1	PhB0	CCP7	-	-	EPI0S25	-	-	-
PE4	6	AIN3	CCP3	-	-	Fault0	U2Tx	CCP2	-	-	I2SOTXWS	-	-
PE5	5	AIN2	CCP5	-	-	-	-	-	-	-	I2SOTXSD	-	-
PE6	2	AIN1	PWM4	C1o	-	-	-	-	-	-	Ulcts	-	-
PE7	1	AIN0	РWМ5	C20	-	-	-	-	-	-	UldCd	-	-
PF0	47	-	CAN1Rx	PhB0	PWM0	-	-	-	-	I2SOTXSD	U1DSR	-	-
PF1	61	-	CAN1Tx	IDX1	PWM1	-	-	-	-	I2SOTXMCLK	Ulrts	CCP3	-
PF2	60	-	LED1	PWM4	-	PWM2	-	-	-	-	SSI1Clk	-	-
PF3	59	-	LED0	PWM5	-	PWM3	-	-	-	-	SSI1Fss	-	-
PF4	42	-	CCP0	C0o	-	Fault0	-	-	-	EPI0S12	SSI1Rx	-	-
PF5	41	-	CCP2	C1o	-	-	-	-	-	EPIOS15	SSI1Tx	-	-
PG0	19	-	U2Rx	PWM0	I2C1SCL	PWM4	-	-	USB0EPEN	EPIOS13	-	-	-
PG1	18	-	U2Tx	PWM1	I2C1SDA	PWM5	-	-	-	EPIOS14	-	-	-
PG7	36	-	PhB1	-	-	PWM7	-	-	-	CCP5	EPIOS31	-	-
PH0	86	-	CCP6	PWM2	-	-	-	-	-	EPI0S6	PWM4	-	-

Table 24-5. GPIO Pins and Alternate Functions (continued)

10	Digital Function (GPIOPCTL PMCx Bit Field Encoding)						ng) <sup>a</sup>						
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PH1	85	-	CCP7	PWM3	-	-	-	-	-	EPI0S7	PWM5	-	-
PH2	84	-	IDX1	C1o	-	Fault3	-	-	-	EPI0S1	-	-	-
PH3	83	-	PhB0	Fault0	-	USB0EPEN	-	-	-	EPI0S0	-	-	-
PH4	76	-	-	-	-	USB0PFLT	-	-	-	EPI0S10	-	-	SSI1Clk
PH5	63	-	-	-	-	-	-	-	-	EPI0S11	-	Fault2	SSI1Fss
РН6	62	-	-	-	-	-	-	-	-	EPI0S26	-	PWM4	SSI1Rx
PH7	15	-	-	-	-	-	-	-	-	EPI0S27	-	PWM5	SSI1Tx
PJ0	14	-	-	-	-	-	-	-	-	EPIOS16	-	PWM0	I2C1SCL
PJ1	87	-	-	-	-	-	-	-	-	EPI0S17	USB0PFLT	PWM1	I2C1SDA
PJ2	39	-	-	-	-	-	-	-	-	EPIOS18	CCP0	Fault0	-
РЈ3	50	-	-	-	-	-	-	-	-	EPIOS19	Ulcts	CCP6	-
PJ4	52	-	-	-	-	-	-	-	-	EPI0S28	U1DCD	CCP4	-
PJ5	53	-	-	-	-	-	-	-	-	EPI0S29	U1DSR	CCP2	-
РЈ6	54	-	-	-	-	-	-	-	-	EPI0S30	Ulrts	CCP1	-
PJ7	55	-	-	-	-	-	-	-	-	-	U1DTR	CCP0	-

a. The digital signals that are shaded gray are the power-on default values for the corresponding GPIO pin.

## 24.1.5 Possible Pin Assignments for Alternate Functions

Table 24-6. Possible Pin Assignments for Alternate Functions

	Alternate Function	GPIO Function				
	AIN0	PE7				
	AIN1	PE6				
	AIN10	PB4				
	AIN11	PB5				
	AIN12	PD3				
	AIN13	PD2				
	AIN14	PD1				
	AIN15	PD0				
	AIN2	PE5				
	AIN3	PE4				
	AIN4	PD7				
	AIN5	PD6				
	AIN6	PD5				
	AIN7	PD4				
	AIN8	PE3				
	AIN9	PE2				
	C0+	PB6				
	C0-	PB4				
	C1+	PC5				
one	C1-	PB5				
	C2+	PC6				
	C2-	PC7				
	CAN1Rx	PF0				
	CAN1Tx	PF1				
	EPI0S0	PH3				
	EPI0S1	PH2				
	EPIOS10	PH4				
	EPIOS11	PH5				
	EPI0S12	PF4				
	EPIOS13	PG0				
	EPIOS14	PG1				
Γ	EPI0S15	PF5				
	EPIOS16	PJ0				
Γ	EPI0S17	PJ1				
	EPIOS18	PJ2				
Γ	EPI0S2	PC4				
Γ	EPI0S20	PD2				
Γ	EPI0S21	PD3				
	EPI0S22	PB5				

Table 24-6. Possible Pin Assignments for Alternate Functions (continued)

# of Possible Assignments	Alternate Function	GPIO Function
	EPI0S23	PB4
	EPI0S24	PE2
	EPIOS25	PE3
	EPIOS26	PH6
	EPI0S27	PH7
	EPIOS3	PC5
	EPIOS31	PG7
	EPI0S4	PC6
	EPIOS5	PC7
	EPI0S6	PH0
	EPIOS7	PH1
	EPIOS8	PE0
	EPIOS9	PE1
	Fault1	PB6
	I2C0SCL	PB2
	I2C0SDA	PB3
	I2S0RXSCK	PD0
	I2S0RXWS	PD1
	I2S0TXMCLK	PF1
	LED0	PF3
	LED1	PF2
	NMI	PB7
	PhA1	PE3
	SSIOClk	PA2
	SSIOFss	PA3
	SSIORx	PA4
	SSIOTx	PA5
	SWCLK	PC0
	SWDIO	PC1
	SWO	PC3
	TCK	PC0
	TDI	PC2
	TDO	PC3
	TMS	PC1
	UORx	PA0
	UOTx	PA1
	U1RI	PD4
	USB0ID	PB0
	USB0VBUS	PB1
	VREFA	PB6

Table 24-6. Possible Pin Assignments for Alternate Functions (continued)

# of Possible Assignments	Alternate Function	GPIO Function		
	C2o	PC6 PE7		
	EPIOS19	PD4 PJ3		
	EPI0S28	PD5 PJ4		
	EPIOS29	PD6 PJ5		
	EPI0S30	PD7 PJ6		
	Fault2	PC5 PH5		
	Fault3	PB3 PH2		
two	I2S0RXMCLK	PA3 PD5		
	I2S0RXSD	PA2 PD4		
	I2S0TXSD	PE5 PF0		
	IDX1	PF1 PH2		
	PWM6	PA4 PC4		
	U1DSR	PF0 PJ5		
	U1DTR	PD7 PJ7		
	U1RTS	PF1 PJ6		
	I2S0TXSCK	PA4 PB6 PD6		
	I2SOTXWS	PA5 PD7 PE4		
	PWM7	PA5 PC6 PG7		
	PhA0	PC4 PD1 PE2		
three	PhB1	PD1 PE2 PG7		
	SSI1Clk	PE0 PF2 PH4		
	SSI1Fss	PE1 PF3 PH5		
	SSI1Rx	PE2 PF4 PH6		
	SSI1Tx	PE3 PF5 PH7		
	CAN0Rx	PA4 PA6 PB4 PD0		
	CAN0Tx	PA5 PA7 PB5 PD1		
	I2C1SCL	PA0 PA6 PG0 PJ0		
	I2C1SDA	PA1 PA7 PG1 PJ1		
four	PWM2	PB0 PD2 PF2 PH0		
Ioui	PWM3	PB1 PD3 PF3 PH1		
	U1CTS	PA6 PD0 PE6 PJ3		
Γ	U1DCD	PA7 PD1 PE7 PJ4		
	U2Rx	PB4 PD0 PD5 PG0		
	U2Tx	PD1 PD6 PE4 PG1		

Table 24-6. Possible Pin Assignments for Alternate Functions (continued)

# of Possible Assignments	Alternate Function	GPIO Function			
	C0o	PB5 PB6 PC5 PD7 PF4			
	Clo	PC5 PC7 PE6 PF5 PH2			
	CCP7	PB6 PD1 PD3 PE3 PH1			
five	IDX0	PB2 PB4 PB6 PD0 PD7			
live	PWM0	PA6 PD0 PF0 PG0 PJ0			
	PWM1	PA7 PD1 PF1 PG1 PJ1			
	PhB0	PC6 PC7 PE3 PF0 PH3			
	USB0EPEN	PA6 PB2 PC5 PG0 PH3			
	CCP4	PA7 PC4 PC7 PD5 PE2 PJ4			
	CCP5	PB5 PB6 PC4 PD2 PE5 PG7			
SiX	CCP6	PB5 PD0 PD2 PE1 PH0 PJ3			
	U1Rx	PA0 PB0 PB4 PC6 PD0 PD2			
	UlTx	PA1 PB1 PB5 PC7 PD1 PD3			
aayan	Fault0	PB3 PD6 PE1 PE4 PF4 PH3 PJ2			
seven	USB0PFLT	PA7 PB3 PC6 PC7 PE0 PH4 PJ1			
	CCP1	PA6 PB1 PB6 PC4 PC5 PD7 PE3 PJ6			
oight	CCP3	PA7 PB2 PC5 PC6 PD4 PE0 PE4 PF1			
eight -	PWM4	PA2 PA6 PE0 PE6 PF2 PG0 PH0 PH6			
	PWM5	PA3 PA7 PE1 PE7 PF3 PG1 PH1 PH7			
ten	CCP0	PB0 PB2 PB5 PC6 PC7 PD3 PD4 PF4 PJ2 PJ7			
ten	CCP2	PB1 PB5 PC4 PD1 PD5 PE1 PE2 PE4 PF5 PJ5			

# 24.2 108-Ball BGA Package Pin Tables

## 24.2.1 Signals by Pin Number

Table 24-7. Signals by Pin Number

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PE6	I/O	TTL	GPIO port E bit 6.
	AIN1	I	Analog	Analog-to-digital converter input 1.
A1	C1o	0	TTL	Analog comparator 1 output.
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	U1CTS	I	TTL	UART module 1 Clear To Send modem flow control input signal.
	PD7	I/O	TTL	GPIO port D bit 7.
	AIN4	I	Analog	Analog-to-digital converter input 4.
	C0o	0	TTL	Analog comparator 0 output.
A2	CCP1	I/O	TTL	Capture/Compare/PWM 1.
AZ	EPIOS30	I/O	TTL	EPI module 0 signal 30.
	I2SOTXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	IDX0	I	TTL	QEI module 0 index.
	U1DTR	0	TTL	UART module 1 Data Terminal Ready modem status input signal.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PD6	I/O	TTL	GPIO port D bit 6.
	AIN5	I	Analog	Analog-to-digital converter input 5.
	EPIOS29	I/O	TTL	EPI module 0 signal 29.
A3	Fault0	I	TTL	PWM Fault 0.
	I2S0TXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
	PE2	I/O	TTL	GPIO port E bit 2.
	AIN9	I	Analog	Analog-to-digital converter input 9.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
	CCP4	I/O	TTL	Capture/Compare/PWM 4.
A4	EPI0S24	I/O	TTL	EPI module 0 signal 24.
	PhA0	I	TTL	QEI module 0 phase A.
	PhB1	I	TTL	QEI module 1 phase B.
	SSI1Rx	I	TTL	SSI module 1 receive.
A5	GNDA	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
	PB4	I/O	TTL	GPIO port B bit 4.
	AIN10	I	Analog	Analog-to-digital converter input 10.
	C0-	I	Analog	Analog comparator 0 negative input.
	CAN0Rx	I	TTL	CAN module 0 receive.
A6	EPI0S23	I/O	TTL	EPI module 0 signal 23.
	IDX0	I	TTL	QEI module 0 index.
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
	PB6	I/O	TTL	GPIO port B bit 6.
	C0+	I	Analog	Analog comparator 0 positive input.
	C0o	0	TTL	Analog comparator 0 output.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
	CCP5	I/O	TTL	Capture/Compare/PWM 5.
	CCP7	I/O	TTL	Capture/Compare/PWM 7.
A7	Fault1	I	TTL	PWM Fault 1.
	I2S0TXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	IDX0	Į.	TTL	QEI module 0 index.
	VREFA	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
4.0	PB7	I/O	TTL	GPIO port B bit 7.
A8 -	NMI	I	TTL	Non-maskable interrupt.
	PC0	I/O	TTL	GPIO port C bit 0.
A9	SWCLK	I	TTL	JTAG/SWD CLK.
-	TCK	I	TTL	JTAG/SWD CLK.
	PC3	I/O	TTL	GPIO port C bit 3.
A10	SWO	0	TTL	JTAG TDO and SWO.
	TDO	0	TTL	JTAG TDO and SWO.
	PB2	I/O	TTL	GPIO port B bit 2.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
	CCP3	I/O	TTL	Capture/Compare/PWM 3.
A11	I2C0SCL	I/O	OD	I <sup>2</sup> C module 0 clock.
-	IDX0	I	TTL	QEI module 0 index.
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
	PE1	I/O	TTL	GPIO port E bit 1.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
	CCP6	I/O	TTL	Capture/Compare/PWM 6.
A12	EPI0S9	I/O	TTL	EPI module 0 signal 9.
	Fault0	1	TTL	PWM Fault 0.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.
	PE7	I/O	TTL	GPIO port E bit 7.
	AIN0	I	Analog	Analog-to-digital converter input 0.
B1	C2o	0	TTL	Analog comparator 2 output.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	U1DCD	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
	PE4	I/O	TTL	GPIO port E bit 4.
	AIN3	1	Analog	Analog-to-digital converter input 3.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
B2	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	Fault0	I	TTL	PWM Fault 0.
	I2SOTXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
	PE5	I/O	TTL	GPIO port E bit 5.
В3	AIN2	1	Analog	Analog-to-digital converter input 2.
د د	CCP5	I/O	TTL	Capture/Compare/PWM 5.
	I2S0TXSD	I/O	TTL	I <sup>2</sup> S module 0 transmit data.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PE3	I/O	TTL	GPIO port E bit 3.
	AIN8	I	Analog	Analog-to-digital converter input 8.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
B4	CCP7	I/O	TTL	Capture/Compare/PWM 7.
D4	EPI0S25	I/O	TTL	EPI module 0 signal 25.
	PhA1	I	TTL	QEI module 1 phase A.
	PhB0	I	TTL	QEI module 0 phase B.
	SSI1Tx	0	TTL	SSI module 1 transmit.
	PD4	I/O	TTL	GPIO port D bit 4.
	AIN7	I	Analog	Analog-to-digital converter input 7.
	CCP0	I/O	TTL	Capture/Compare/PWM 0.
B5	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	EPIOS19	I/O	TTL	EPI module 0 signal 19.
	I2S0RXSD	I/O	TTL	I <sup>2</sup> S module 0 receive data.
	U1RI	ı	TTL	UART module 1 Ring Indicator modem status input signal.
	PJ1	I/O	TTL	GPIO port J bit 1.
	EPI0S17	I/O	TTL	EPI module 0 signal 17.
B6	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
	USB0PFLT	ı	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
	PB5	I/O	TTL	GPIO port B bit 5.
	AIN11	I	Analog	Analog-to-digital converter input 11.
	C0o	0	TTL	Analog comparator 0 output.
	C1-	I	Analog	Analog comparator 1 negative input.
	CAN0Tx	0	TTL	CAN module 0 transmit.
В7	CCP0	I/O	TTL	Capture/Compare/PWM 0.
<u> </u>	CCP2	I/O	TTL	Capture/Compare/PWM 2.
	CCP5	I/O	TTL	Capture/Compare/PWM 5.
	CCP6	I/O	TTL	Capture/Compare/PWM 6.
	EPI0S22	I/O	TTL	EPI module 0 signal 22.
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
D0	PC2	I/O	TTL	GPIO port C bit 2.
B8  -	TDI	I	TTL	JTAG TDI.
	PC1	I/O	TTL	GPIO port C bit 1.
В9	SWDIO	I/O	TTL	JTAG TMS and SWDIO.
	TMS	I	TTL	JTAG TMS and SWDIO.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PH4	I/O	TTL	GPIO port H bit 4.
D10	EPIOS10	I/O	TTL	EPI module 0 signal 10.
B10	SSI1Clk	I/O	TTL	SSI module 1 clock.
	USB0PFLT	1	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
	PE0	I/O	TTL	GPIO port E bit 0.
	CCP3	I/O	TTL	Capture/Compare/PWM 3.
	EPI0S8	I/O	TTL	EPI module 0 signal 8.
B11	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	SSI1Clk	I/O	TTL	SSI module 1 clock.
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
B12	USB0RBIAS	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
C1	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.
C2	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.
C3	VDDC	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .
C4	GND	-	Power	Ground reference for logic and I/O pins.
C5	GND	-	Power	Ground reference for logic and I/O pins.
	PD5	I/O	TTL	GPIO port D bit 5.
	AIN6	I	Analog	Analog-to-digital converter input 6.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
C6	CCP4	I/O	TTL	Capture/Compare/PWM 4.
	EPI0S28	I/O	TTL	EPI module 0 signal 28.
	I2S0RXMCLK	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
	U2Rx	1	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
C7	VDDA	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
	PH1	I/O	TTL	GPIO port H bit 1.
	CCP7	I/O	TTL	Capture/Compare/PWM 7.
C8	EPI0S7	I/O	TTL	EPI module 0 signal 7.
	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description
	PH0	I/O	TTL	GPIO port H bit 0.
	CCP6	I/O	TTL	Capture/Compare/PWM 6.
C9	EPIOS6	I/O	TTL	EPI module 0 signal 6.
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	PG7	I/O	TTL	GPIO port G bit 7.
	CCP5	I/O	TTL	Capture/Compare/PWM 5.
C10	EPIOS31	I/O	TTL	EPI module 0 signal 31.
	PWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.
	PhB1	I	TTL	QEI module 1 phase B.
C11	USB0DM	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
C12	USB0DP	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
D1	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.
D2	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.
D3	VDDC	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .
	РН3	I/O	TTL	GPIO port H bit 3.
	EPI0S0	I/O	TTL	EPI module 0 signal 0.
D10	Fault0	I	TTL	PWM Fault 0.
	PhB0	I	TTL	QEI module 0 phase B.
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
	PH2	I/O	TTL	GPIO port H bit 2.
	Clo	0	TTL	Analog comparator 1 output.
D11	EPIOS1	I/O	TTL	EPI module 0 signal 1.
	Fault3	I	TTL	PWM Fault 3.
	IDX1	I	TTL	QEI module 1 index.
	PB1	I/O	TTL	GPIO port B bit 1. This pin is not 5-V tolerant.
	CCP1	I/O	TTL	Capture/Compare/PWM 1.
	CCP2	I/O	TTL	Capture/Compare/PWM 2.
D12	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
DIZ	U1Tx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
	USB0VBUS	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.
E1	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.
E2	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description		
E3	LDO	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).		
E10	VDD	-	Power	Positive supply for I/O and some logic.		
	PB3	I/O	TTL	GPIO port B bit 3.		
	Fault0	I	TTL	PWM Fault 0.		
E11	Fault3	I	TTL	PWM Fault 3.		
	I2C0SDA	I/O	OD	I <sup>2</sup> C module 0 data.		
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.		
	PB0	I/O	TTL	GPIO port B bit 0. This pin is not 5-V tolerant.		
	CCP0	I/O	TTL	Capture/Compare/PWM 0.		
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.		
E12	UlRx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.		
	USB0ID	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).		
F1	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.		
F2	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.		
	PJ0	I/O	TTL	GPIO port J bit 0.		
F3	EPIOS16	I/O	TTL	EPI module 0 signal 16.		
13	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.		
	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.		
	PH5	I/O	TTL	GPIO port H bit 5.		
F10	EPIOS11	I/O	TTL	EPI module 0 signal 11.		
1 10	Fault2	1	TTL	PWM Fault 2.		
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.		
F11	GND	-	Power	Ground reference for logic and I/O pins.		
F12	GND	-	Power	Ground reference for logic and I/O pins.		
	PD0	I/O	TTL	GPIO port D bit 0.		
	AIN15	I	Analog	Analog-to-digital converter input 15.		
	CAN0Rx	1	TTL	CAN module 0 receive.		
	CCP6	I/O	TTL	Capture/Compare/PWM 6.		
	I2S0RXSCK	I/O	TTL	I <sup>2</sup> S module 0 receive clock.		
G1	IDX0	1	TTL	QEI module 0 index.		
	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.		
	U1CTS	1	TTL	UART module 1 Clear To Send modem flow control input signal.		
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.		
	U2Rx	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.		

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description		
	PD1	I/O	TTL	GPIO port D bit 1.		
	AIN14	1	Analog	Analog-to-digital converter input 14.		
	CAN0Tx	0	TTL	CAN module 0 transmit.		
	CCP2	I/O	TTL	Capture/Compare/PWM 2.		
	CCP7	I/O	TTL	Capture/Compare/PWM 7.		
	I2S0RXWS	I/O	TTL	I <sup>2</sup> S module 0 receive word select.		
G2	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.		
	PhA0	I	TTL	QEI module 0 phase A.		
	PhB1	I	TTL	QEI module 1 phase B.		
	U1DCD	I	TTL	UART module 1 Data Carrier Detect modem status input signal.		
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.		
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.		
	РН6	I/O	TTL	GPIO port H bit 6.		
G3	EPI0S26	I/O	TTL	EPI module 0 signal 26.		
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.		
	SSI1Rx	I	TTL	SSI module 1 receive.		
G10	VDD	-	Power	Positive supply for I/O and some logic.		
G11	VDD	-	Power	Positive supply for I/O and some logic.		
G12	VDD	-	Power	Positive supply for I/O and some logic.		
	PD3	I/O	TTL	GPIO port D bit 3.		
	AIN12	I	Analog	Analog-to-digital converter input 12.		
	CCP0	I/O	TTL	Capture/Compare/PWM 0.		
H1	CCP7	I/O	TTL	Capture/Compare/PWM 7.		
	EPI0S21	I/O	TTL	EPI module 0 signal 21.		
	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.		
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.		
	PD2	I/O	TTL	GPIO port D bit 2.		
	AIN13	I	Analog	Analog-to-digital converter input 13.		
	CCP5	I/O	TTL	Capture/Compare/PWM 5.		
H2	CCP6	I/O	TTL	Capture/Compare/PWM 6.		
	EPI0S20	I/O	TTL	EPI module 0 signal 20.		
	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.		
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.		
	PH7	I/O	TTL	GPIO port H bit 7.		
H3	EPI0S27	I/O	TTL	EPI module 0 signal 27.		
110	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.		
	SSI1Tx	0	TTL	SSI module 1 transmit.		
H10	VDD	-	Power	Positive supply for I/O and some logic.		

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description		
H11	RST	I	TTL	System reset input.		
	PF1	I/O	TTL	GPIO port F bit 1.		
	CAN1Tx	0	TTL	CAN module 1 transmit.		
H12	CCP3	I/O	TTL	Capture/Compare/PWM 3.		
	I2S0TXMCLK	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.		
	IDX1	I	TTL	QEI module 1 index.		
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.		
	U1RTS	0	TTL	UART module 1 Request to Send modem flow control output line.		
J1	XTALNPHY	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.		
J2	XTALPPHY	I	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.		
J3	ERBIAS	0	Analog	12.4-kΩ resistor (1% precision) used internally for Ethernet PHY.		
J10	GND	-	Power	Ground reference for logic and I/O pins.		
	PF2	I/O	TTL	GPIO port F bit 2.		
	LED1	0	TTL	Ethernet LED 1.		
J11	PWM2	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.		
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.		
	SSI1Clk	I/O	TTL	SSI module 1 clock.		
	PF3	I/O	TTL	GPIO port F bit 3.		
	LED0	0	TTL	Ethernet LED 0.		
J12	PWM3	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.		
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.		
	SSI1Fss	I/O	TTL	SSI module 1 frame signal.		
	PG0	I/O	TTL	GPIO port G bit 0.		
	EPIOS13	I/O	TTL	EPI module 0 signal 13.		
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.		
	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.		
K1	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.		
	U2Rx	ı	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.		
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.		
	PG1	I/O	TTL	GPIO port G bit 1.		
	EPIOS14	I/O	TTL	EPI module 0 signal 14.		
	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.		
K2	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.		
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.		
	U2Tx	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.		

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PF5	I/O	TTL	GPIO port F bit 5.	
	Clo	0	TTL	Analog comparator 1 output.	
К3	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
	EPIOS15	I/O	TTL	EPI module 0 signal 15.	
	SSI1Tx	0	TTL	SSI module 1 transmit.	
	PF4	I/O	TTL	GPIO port F bit 4.	
	C0o	0	TTL	Analog comparator 0 output.	
K4	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
114	EPIOS12	I/O	TTL	EPI module 0 signal 12.	
	Fault0	1	TTL	PWM Fault 0.	
	SSI1Rx	1	TTL	SSI module 1 receive.	
K5	GND	-	Power	Ground reference for logic and I/O pins.	
	PJ2	I/O	TTL	GPIO port J bit 2.	
K6	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
I NO	EPIOS18	I/O	TTL	EPI module 0 signal 18.	
	Fault0	1	TTL	PWM Fault 0.	
K7	VDD	-	Power	Positive supply for I/O and some logic.	
K8	VDD	-	Power	Positive supply for I/O and some logic.	
K9	VDD	-	Power	Positive supply for I/O and some logic.	
K10	GND	-	Power	Ground reference for logic and I/O pins.	
	РЈ4	I/O	TTL	GPIO port J bit 4.	
K11	CCP4	I/O	TTL	Capture/Compare/PWM 4.	
KII	EPIOS28	I/O	TTL	EPI module 0 signal 28.	
	U1DCD	1	TTL	UART module 1 Data Carrier Detect modem status input signal.	
	PJ5	I/O	TTL	GPIO port J bit 5.	
K12	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
IXIZ	EPIOS29	I/O	TTL	EPI module 0 signal 29.	
	U1DSR	I	TTL	UART module 1 Data Set Ready modem output control line.	
	PC4	I/O	TTL	GPIO port C bit 4.	
	CCP1	I/O	TTL	Capture/Compare/PWM 1.	
	CCP2	I/O	TTL	Capture/Compare/PWM 2.	
L1	CCP4	I/O	TTL	Capture/Compare/PWM 4.	
	CCP5	I/O	TTL	Capture/Compare/PWM 5.	
	EPI0S2	I/O	TTL	EPI module 0 signal 2.	
	PWM6	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.	
	PhA0	I	TTL	QEI module 0 phase A.	

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description		
	PC7	I/O	TTL	GPIO port C bit 7.		
	Clo	0	TTL	Analog comparator 1 output.		
	C2-	ı	Analog	Analog comparator 2 negative input.		
	CCP0	I/O	TTL	Capture/Compare/PWM 0.		
	CCP4	I/O	TTL	Capture/Compare/PWM 4.		
L2	EPIOS5	I/O	TTL	EPI module 0 signal 5.		
	PhB0	ı	TTL	QEI module 0 phase B.		
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.		
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.		
	PA0	I/O	TTL	GPIO port A bit 0.		
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.		
L3	U0Rx	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.		
	UlRx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.		
	PA3	I/O	TTL	GPIO port A bit 3.		
L4	I2S0RXMCLK	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.		
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.		
	SSI0Fss	I/O	TTL	SSI module 0 frame signal		
	PA4	I/O	TTL	GPIO port A bit 4.		
	CAN0Rx	I	TTL	CAN module 0 receive.		
L5	I2SOTXSCK	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.		
	PWM6	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.		
	SSI0Rx	I	TTL	SSI module 0 receive		
	PA6	I/O	TTL	GPIO port A bit 6.		
	CAN0Rx	I	TTL	CAN module 0 receive.		
	CCP1	I/O	TTL	Capture/Compare/PWM 1.		
	I2C1SCL	I/O	OD	I <sup>2</sup> C module 1 clock.		
L6	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.		
	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.		
	U1CTS	I	TTL	UART module 1 Clear To Send modem flow control input signal.		
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.		
L7	RXIN	I	Analog	RXIN of the Ethernet PHY.		
L8	TXON	0	TTL	TXON of the Ethernet PHY.		
L9	MDIO	I/O	OD	MDIO of the Ethernet PHY.		
	PJ6	I/O	TTL	GPIO port J bit 6.		
L10	CCP1	I/O	TTL	Capture/Compare/PWM 1.		
	EPIOS30	I/O	TTL	EPI module 0 signal 30.		
	U1RTS	0	TTL	UART module 1 Request to Send modem flow control output line.		
L11	OSC0	I	Analog	Main oscillator crystal input or an external clock reference input.		

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PJ7	I/O	TTL	GPIO port J bit 7.	
L12	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
	U1DTR	0	TTL	UART module 1 Data Terminal Ready modem status input signal.	
	PC5	I/O	TTL	GPIO port C bit 5.	
	C0o	0	TTL	Analog comparator 0 output.	
	C1+	I	Analog	Analog comparator 1 positive input.	
	Clo	0	TTL	Analog comparator 1 output.	
M1	CCP1	I/O	TTL	Capture/Compare/PWM 1.	
	CCP3	I/O	TTL	Capture/Compare/PWM 3.	
	EPIOS3	I/O	TTL	EPI module 0 signal 3.	
	Fault2	I	TTL	PWM Fault 2.	
	USB0EPEN	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.	
	PC6	I/O	TTL	GPIO port C bit 6.	
	C2+	I	Analog	Analog comparator 2 positive input.	
	C2o	0	TTL	Analog comparator 2 output.	
	CCP0	I/O	TTL	Capture/Compare/PWM 0.	
	CCP3	I/O	TTL	Capture/Compare/PWM 3.	
M2	EPI0S4	I/O	TTL	EPI module 0 signal 4.	
	PWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.	
	PhB0	I	TTL	QEI module 0 phase B.	
	U1Rx	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.	
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
	PA1	I/O	TTL	GPIO port A bit 1.	
	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.	
M3	UOTx	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.	
	UlTx	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.	
	PA2	I/O	TTL	GPIO port A bit 2.	
M4	I2S0RXSD	I/O	TTL	I <sup>2</sup> S module 0 receive data.	
1014	PWM4	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.	
	SSI0Clk	I/O	TTL	SSI module 0 clock	
	PA5	I/O	TTL	GPIO port A bit 5.	
	CAN0Tx	0	TTL	CAN module 0 transmit.	
M5	I2SOTXWS	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.	
	PWM7	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.	
	SSIOTx	0	TTL	SSI module 0 transmit	

Table 24-7. Signals by Pin Number (continued)

Pin Number	Pin Name	Pin Type	Buffer Type <sup>a</sup>	Description	
	PA7	I/O	TTL	GPIO port A bit 7.	
	CAN0Tx	NOTX O		CAN module 0 transmit.	
	CCP3	I/O	TTL	Capture/Compare/PWM 3.	
	CCP4	I/O	TTL	Capture/Compare/PWM 4.	
M6	I2C1SDA	I/O	OD	I <sup>2</sup> C module 1 data.	
	PWM1	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.	
	PWM5	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.	
	U1DCD	I	TTL	UART module 1 Data Carrier Detect modem status input signal.	
	USB0PFLT	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.	
M7	RXIP	I	Analog	RXIP of the Ethernet PHY.	
M8	TXOP	0	TTL	TXOP of the Ethernet PHY.	
	PF0	I/O	TTL	GPIO port F bit 0.	
	CAN1Rx	1	TTL	CAN module 1 receive.	
M9	I2S0TXSD	I/O	TTL	I <sup>2</sup> S module 0 transmit data.	
IVI9	PWM0	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.	
	PhB0	1	TTL	QEI module 0 phase B.	
	U1DSR	I	TTL	UART module 1 Data Set Ready modem output control line.	
	РЈ3	I/O	TTL	GPIO port J bit 3.	
M10	CCP6	I/O	TTL	Capture/Compare/PWM 6.	
IVITO	EPIOS19	I/O	TTL	EPI module 0 signal 19.	
	Ulcts	I	TTL	UART module 1 Clear To Send modem flow control input signal.	
M11	OSC1	0	Analog	Main oscillator crystal output. Leave unconnected when using single-ended clock source.	
M12	NC	-	-	No connect. Leave the pin electrically unconnected/isolated.	

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### 24.2.2 Signals by Signal Name

Table 24-8. Signals by Signal Name

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN0	B1	PE7	1	Analog	Analog-to-digital converter input 0.
AIN1	A1	PE6	1	Analog	Analog-to-digital converter input 1.
AIN2	В3	PE5	1	Analog	Analog-to-digital converter input 2.
AIN3	B2	PE4	1	Analog	Analog-to-digital converter input 3.
AIN4	A2	PD7	1	Analog	Analog-to-digital converter input 4.
AIN5	A3	PD6	1	Analog	Analog-to-digital converter input 5.
AIN6	C6	PD5	1	Analog	Analog-to-digital converter input 6.
AIN7	B5	PD4	1	Analog	Analog-to-digital converter input 7.
AIN8	B4	PE3	1	Analog	Analog-to-digital converter input 8.
AIN9	A4	PE2	1	Analog	Analog-to-digital converter input 9.
AIN10	A6	PB4	1	Analog	Analog-to-digital converter input 10.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
AIN11	B7	PB5	Į	Analog	Analog-to-digital converter input 11.
AIN12	H1	PD3	Į	Analog	Analog-to-digital converter input 12.
AIN13	H2	PD2	I	Analog	Analog-to-digital converter input 13.
AIN14	G2	PD1	Į	Analog	Analog-to-digital converter input 14.
AIN15	G1	PD0	Į	Analog	Analog-to-digital converter input 15.
C0+	A7	PB6	I	Analog	Analog comparator 0 positive input.
C0-	A6	PB4	I	Analog	Analog comparator 0 negative input.
C0o	M1 K4 A7 B7 A2	PC5 (3) PF4 (2) PB6 (3) PB5 (1) PD7 (2)	0	TTL	Analog comparator 0 output.
C1+	M1	PC5	I	Analog	Analog comparator 1 positive input.
C1-	B7	PB5	I	Analog	Analog comparator 1 negative input.
Clo	A1 L2 M1 K3 D11	PE6 (2) PC7 (7) PC5 (2) PF5 (2) PH2 (2)	0	TTL	Analog comparator 1 output.
C2+	M2	PC6	Į	Analog	Analog comparator 2 positive input.
C2-	L2	PC7	I	Analog	Analog comparator 2 negative input.
C2o	B1 M2	PE7 (2) PC6 (3)	0	TTL	Analog comparator 2 output.
CANORX	G1 L5 L6 A6	PD0 (2) PA4 (5) PA6 (6) PB4 (5)	I	TTL	CAN module 0 receive.
CANOTX	G2 M5 M6 B7	PD1 (2) PA5 (5) PA7 (6) PB5 (5)	0	TTL	CAN module 0 transmit.
CAN1Rx	M9	PF0 (1)	I	TTL	CAN module 1 receive.
CAN1Tx	H12	PF1 (1)	0	TTL	CAN module 1 transmit.
CCPO	H1 L2 M2 K6 K4 L12 E12 A11 B7 B5	PD3 (4) PC7 (4) PC6 (6) PJ2 (9) PF4 (1) PJ7 (10) PB0 (1) PB2 (5) PB5 (4) PD4 (1)	I/O	TTL	Capture/Compare/PWM 0.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
CCP1	M1 L1 L6 L10 D12 A7 B4 A2	PC5 (1) PC4 (9) PA6 (2) PJ6 (10) PB1 (4) PB6 (1) PE3 (1) PD7 (3)	I/O	TTL	Capture/Compare/PWM 1.
CCP2	B2 G2 L1 K3 K12 D12 A12 B7 A4 C6	PE4 (6) PD1 (10) PC4 (5) PF5 (1) PJ5 (10) PB1 (1) PE1 (4) PB5 (6) PE2 (5) PD5 (1)	I/O	TTL	Capture/Compare/PWM 2.
CCP3	B2 M2 M1 M6 H12 A11 B11 B5	PE4 (1) PC6 (1) PC5 (5) PA7 (7) PF1 (10) PB2 (4) PE0 (3) PD4 (2)	I/O	TTL	Capture/Compare/PWM 3.
CCP4	L2 L1 M6 K11 A4 C6	PC7 (1) PC4 (6) PA7 (2) PJ4 (10) PE2 (1) PD5 (2)	I/O	TTL	Capture/Compare/PWM 4.
CCP5	B3 H2 L1 C10 A7 B7	PE5 (1) PD2 (4) PC4 (1) PG7 (8) PB6 (6) PB5 (2)	I/O	TTL	Capture/Compare/PWM 5.
CCP6	G1 H2 M10 A12 C9 B7	PD0 (6) PD2 (2) PJ3 (10) PE1 (5) PH0 (1) PB5 (3)	I/O	TTL	Capture/Compare/PWM 6.
CCP7	G2 H1 C8 A7 B4	PD1 (6) PD3 (2) PH1 (1) PB6 (2) PE3 (5)	I/O	TTL	Capture/Compare/PWM 7.
EPI0S0	D10	PH3 (8)	I/O	TTL	EPI module 0 signal 0.
EPI0S1	D11	PH2 (8)	I/O	TTL	EPI module 0 signal 1.
EPI0S2	L1	PC4 (8)	I/O	TTL	EPI module 0 signal 2.
EPIOS3	M1	PC5 (8)	I/O	TTL	EPI module 0 signal 3.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
EPI0S4	M2	PC6 (8)	I/O	TTL	EPI module 0 signal 4.
EPI0S5	L2	PC7 (8)	I/O	TTL	EPI module 0 signal 5.
EPI0S6	C9	PH0 (8)	I/O	TTL	EPI module 0 signal 6.
EPIOS7	C8	PH1 (8)	I/O	TTL	EPI module 0 signal 7.
EPIOS8	B11	PE0 (8)	I/O	TTL	EPI module 0 signal 8.
EPIOS9	A12	PE1 (8)	I/O	TTL	EPI module 0 signal 9.
EPIOS10	B10	PH4 (8)	I/O	TTL	EPI module 0 signal 10.
EPIOS11	F10	PH5 (8)	I/O	TTL	EPI module 0 signal 11.
EPIOS12	K4	PF4 (8)	I/O	TTL	EPI module 0 signal 12.
EPIOS13	K1	PG0 (8)	I/O	TTL	EPI module 0 signal 13.
EPIOS14	K2	PG1 (8)	I/O	TTL	EPI module 0 signal 14.
EPIOS15	K3	PF5 (8)	I/O	TTL	EPI module 0 signal 15.
EPIOS16	F3	PJ0 (8)	I/O	TTL	EPI module 0 signal 16.
EPIOS17	В6	PJ1 (8)	I/O	TTL	EPI module 0 signal 17.
EPIOS18	K6	PJ2 (8)	I/O	TTL	EPI module 0 signal 18.
EPIOS19	M10 B5	PJ3 (8) PD4 (10)	I/O	TTL	EPI module 0 signal 19.
EPI0S20	H2	PD2 (8)	I/O	TTL	EPI module 0 signal 20.
EPIOS21	H1	PD3 (8)	I/O	TTL	EPI module 0 signal 21.
EPI0S22	B7	PB5 (8)	I/O	TTL	EPI module 0 signal 22.
EPIOS23	A6	PB4 (8)	I/O	TTL	EPI module 0 signal 23.
EPIOS24	A4	PE2 (8)	I/O	TTL	EPI module 0 signal 24.
EPI0S25	B4	PE3 (8)	I/O	TTL	EPI module 0 signal 25.
EPIOS26	G3	PH6 (8)	I/O	TTL	EPI module 0 signal 26.
EPI0S27	H3	PH7 (8)	I/O	TTL	EPI module 0 signal 27.
EPIOS28	K11 C6	PJ4 (8) PD5 (10)	I/O	TTL	EPI module 0 signal 28.
EPIOS29	K12 A3	PJ5 (8) PD6 (10)	I/O	TTL	EPI module 0 signal 29.
EPIOS30	L10 A2	PJ6 (8) PD7 (10)	I/O	TTL	EPI module 0 signal 30.
EPIOS31	C10	PG7 (9)	I/O	TTL	EPI module 0 signal 31.
ERBIAS	J3	fixed	0	Analog	12.4-k $\Omega$ resistor (1% precision) used internally for Ethernet PHY.
Fault0	B2 K6 K4 E11 A12 D10	PE4 (4) PJ2 (10) PF4 (4) PB3 (2) PE1 (3) PH3 (2) PD6 (1)	l	TTL	PWM Fault 0.
Fault1	A7	PB6 (4)	I	TTL	PWM Fault 1.
Fault2	M1 F10	PC5 (4) PH5 (10)	I	TTL	PWM Fault 2.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
Fault3	E11 D11	PB3 (4) PH2 (4)	I	TTL	PWM Fault 3.
GND	C4 C5 K5 K10 J10 F11 F12	fixed	-	Power	Ground reference for logic and I/O pins.
GNDA	A5	fixed	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
I2C0SCL	A11	PB2 (1)	I/O	OD	I <sup>2</sup> C module 0 clock.
I2C0SDA	E11	PB3 (1)	I/O	OD	I <sup>2</sup> C module 0 data.
I2C1SCL	F3 K1 L3 L6	PJ0 (11) PG0 (3) PA0 (8) PA6 (1)	I/O	OD	I <sup>2</sup> C module 1 clock.
I2C1SDA	K2 M3 M6 B6	PG1 (3) PA1 (8) PA7 (1) PJ1 (11)	I/O	OD	I <sup>2</sup> C module 1 data.
I2S0RXMCLK	L4 C6	PA3 (9) PD5 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
I2S0RXSCK	G1	PD0 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
I2S0RXSD	M4 B5	PA2 (9) PD4 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive data.
I2S0RXWS	G2	PD1 (8)	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
I2SOTXMCLK	H12	PF1 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
I2SOTXSCK	L5 A7 A3	PA4 (9) PB6 (9) PD6 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
I2S0TXSD	B3 M9	PE5 (9) PF0 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
I2S0TXWS	B2 M5 A2	PE4 (9) PA5 (9) PD7 (8)	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
IDX0	G1 A11 A7 A6 A2	PD0 (3) PB2 (2) PB6 (5) PB4 (6) PD7 (1)	I	TTL	QEI module 0 index.
IDX1	H12 D11	PF1 (2) PH2 (1)	I	TTL	QEI module 1 index.
LDO	E3	fixed	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
LED0	J12	PF3 (1)	0	TTL	Ethernet LED 0.
LED1	J11	PF2 (1)	0	TTL	Ethernet LED 1.
MDIO	L9	fixed	I/O	OD	MDIO of the Ethernet PHY.
NC	M12 C1 C2 D2 D1 E1 E2 F1 F2	fixed	-	-	No connect. Leave the pin electrically unconnected/isolated.
NMI	A8	PB7 (4)	I	TTL	Non-maskable interrupt.
OSC0	L11	fixed	I	Analog	Main oscillator crystal input or an external clock reference input.
OSC1	M11	fixed	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
PA0	L3	-	I/O	TTL	GPIO port A bit 0.
PA1	M3	-	I/O	TTL	GPIO port A bit 1.
PA2	M4	-	I/O	TTL	GPIO port A bit 2.
PA3	L4	-	I/O	TTL	GPIO port A bit 3.
PA4	L5	-	I/O	TTL	GPIO port A bit 4.
PA5	M5	-	I/O	TTL	GPIO port A bit 5.
PA6	L6	-	I/O	TTL	GPIO port A bit 6.
PA7	M6	-	I/O	TTL	GPIO port A bit 7.
PB0	E12	-	I/O	TTL	GPIO port B bit 0. This pin is not 5-V tolerant.
PB1	D12	-	I/O	TTL	GPIO port B bit 1. This pin is not 5-V tolerant.
PB2	A11	-	I/O	TTL	GPIO port B bit 2.
PB3	E11	-	I/O	TTL	GPIO port B bit 3.
PB4	A6	-	I/O	TTL	GPIO port B bit 4.
PB5	B7	-	I/O	TTL	GPIO port B bit 5.
PB6	A7	-	I/O	TTL	GPIO port B bit 6.
PB7	A8	-	I/O	TTL	GPIO port B bit 7.
PC0	A9	-	I/O	TTL	GPIO port C bit 0.
PC1	В9	-	I/O	TTL	GPIO port C bit 1.
PC2	B8	-	I/O	TTL	GPIO port C bit 2.
PC3	A10	-	I/O	TTL	GPIO port C bit 3.
PC4	L1	-	I/O	TTL	GPIO port C bit 4.
PC5	M1	-	I/O	TTL	GPIO port C bit 5.
PC6	M2	-	I/O	TTL	GPIO port C bit 6.
PC7	L2	-	I/O	TTL	GPIO port C bit 7.
PD0	G1	-	I/O	TTL	GPIO port D bit 0.
PD1	G2	-	I/O	TTL	GPIO port D bit 1.
PD2	H2	-	I/O	TTL	GPIO port D bit 2.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PD3	H1	-	I/O	TTL	GPIO port D bit 3.
PD4	B5	-	I/O	TTL	GPIO port D bit 4.
PD5	C6	-	I/O	TTL	GPIO port D bit 5.
PD6	A3	-	I/O	TTL	GPIO port D bit 6.
PD7	A2	-	I/O	TTL	GPIO port D bit 7.
PE0	B11	-	I/O	TTL	GPIO port E bit 0.
PE1	A12	-	I/O	TTL	GPIO port E bit 1.
PE2	A4	-	I/O	TTL	GPIO port E bit 2.
PE3	B4	-	I/O	TTL	GPIO port E bit 3.
PE4	B2	-	I/O	TTL	GPIO port E bit 4.
PE5	В3	-	I/O	TTL	GPIO port E bit 5.
PE6	A1	-	I/O	TTL	GPIO port E bit 6.
PE7	B1	-	I/O	TTL	GPIO port E bit 7.
PF0	M9	-	I/O	TTL	GPIO port F bit 0.
PF1	H12	-	I/O	TTL	GPIO port F bit 1.
PF2	J11	-	I/O	TTL	GPIO port F bit 2.
PF3	J12	-	I/O	TTL	GPIO port F bit 3.
PF4	K4	-	I/O	TTL	GPIO port F bit 4.
PF5	K3	-	I/O	TTL	GPIO port F bit 5.
PG0	K1	-	I/O	TTL	GPIO port G bit 0.
PG1	K2	-	I/O	TTL	GPIO port G bit 1.
PG7	C10	-	I/O	TTL	GPIO port G bit 7.
PH0	C9	-	I/O	TTL	GPIO port H bit 0.
PH1	C8	-	I/O	TTL	GPIO port H bit 1.
PH2	D11	-	I/O	TTL	GPIO port H bit 2.
PH3	D10	-	I/O	TTL	GPIO port H bit 3.
PH4	B10	-	I/O	TTL	GPIO port H bit 4.
PH5	F10	-	I/O	TTL	GPIO port H bit 5.
РН6	G3	-	I/O	TTL	GPIO port H bit 6.
PH7	H3	-	I/O	TTL	GPIO port H bit 7.
PhA0	G2 L1 A4	PD1 (3) PC4 (2) PE2 (4)	I	TTL	QEI module 0 phase A.
PhA1	B4	PE3 (3)	ļ	TTL	QEI module 1 phase A.
PhB0	L2 M2 M9 D10 B4	PC7 (2) PC6 (2) PF0 (2) PH3 (1) PE3 (4)	I	TTL	QEI module 0 phase B.
PhB1	G2 C10 A4	PD1 (11) PG7 (1) PE2 (3)	I	TTL	QEI module 1 phase B.
PJ0	F3	-	I/O	TTL	GPIO port J bit 0.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
PJ1	B6	- Assignment	I/O	TTL	GPIO port J bit 1.
РЈ2	K6	-	I/O	TTL	GPIO port J bit 2.
РЈ3	M10	-	I/O	TTL	GPIO port J bit 3.
РЈ4	K11	-	I/O	TTL	GPIO port J bit 4.
PJ5	K12	-	I/O	TTL	GPIO port J bit 5.
PJ6	L10	-	I/O	TTL	GPIO port J bit 6.
РЈ7	L12	-	I/O	TTL	GPIO port J bit 7.
PWM0	G1 F3 K1 L6 M9	PD0 (1) PJ0 (10) PG0 (2) PA6 (4) PF0 (3)	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
PWM1	G2 K2 M6 H12 B6	PD1 (1) PG1 (2) PA7 (4) PF1 (3) PJ1 (10)	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
PWM2	H2 J11 E12 C9	PD2 (3) PF2 (4) PB0 (2) PH0 (2)	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
PWM3	H1 J12 D12 C8	PD3 (3) PF3 (4) PB1 (2) PH1 (2)	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
РWМ4	A1 K1 M4 L6 J11 G3 B11 C9	PE6 (1) PG0 (4) PA2 (4) PA6 (5) PF2 (2) PH6 (10) PE0 (1) PH0 (9)	0	TTL	PWM 4. This signal is controlled by PWM Generator 2.
PWM5	B1 H3 K2 L4 M6 J12 A12 C8	PE7 (1) PH7 (10) PG1 (4) PA3 (4) PA7 (5) PF3 (2) PE1 (1) PH1 (9)	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
РММб	L1 L5	PC4 (4) PA4 (4)	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
PWM7	M2 M5 C10	PC6 (4) PA5 (4) PG7 (4)	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.
RST	H11	fixed	I	TTL	System reset input.
RXIN	L7	fixed	I	Analog	RXIN of the Ethernet PHY.
RXIP	M7	fixed	I	Analog	RXIP of the Ethernet PHY.
SSI0Clk	M4	PA2 (1)	I/O	TTL	SSI module 0 clock

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
SSI0Fss	L4	PA3 (1)	I/O	TTL	SSI module 0 frame signal
SSIORx	L5	PA4 (1)	I	TTL	SSI module 0 receive
SSIOTx	M5	PA5 (1)	0	TTL	SSI module 0 transmit
SSI1Clk	J11 B11 B10	PF2 (9) PE0 (2) PH4 (11)	I/O	TTL	SSI module 1 clock.
SSI1Fss	J12 F10 A12	PF3 (9) PH5 (11) PE1 (2)	I/O	TTL	SSI module 1 frame signal.
SSI1Rx	K4 G3 A4	PF4 (9) PH6 (11) PE2 (2)	I	TTL	SSI module 1 receive.
SSI1Tx	H3 K3 B4	PH7 (11) PF5 (9) PE3 (2)	0	TTL	SSI module 1 transmit.
SWCLK	A9	PC0 (3)	I	TTL	JTAG/SWD CLK.
SWDIO	В9	PC1 (3)	I/O	TTL	JTAG TMS and SWDIO.
SWO	A10	PC3 (3)	0	TTL	JTAG TDO and SWO.
TCK	A9	PC0 (3)	I	TTL	JTAG/SWD CLK.
TDI	B8	PC2 (3)	Ţ	TTL	JTAG TDI.
TDO	A10	PC3 (3)	0	TTL	JTAG TDO and SWO.
TMS	В9	PC1 (3)	I	TTL	JTAG TMS and SWDIO.
TXON	L8	fixed	0	TTL	TXON of the Ethernet PHY.
TXOP	M8	fixed	0	TTL	TXOP of the Ethernet PHY.
U0Rx	L3	PA0 (1)	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
UOTx	M3	PA1 (1)	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.
U1CTS	A1 G1 L6 M10	PE6 (9) PD0 (9) PA6 (9) PJ3 (9)	I	TTL	UART module 1 Clear To Send modem flow control input signal.
UlDCD	B1 G2 M6 K11	PE7 (9) PD1 (9) PA7 (9) PJ4 (9)	ı	TTL	UART module 1 Data Carrier Detect modem status input signal.
U1DSR	M9 K12	PF0 (9) PJ5 (9)	I	TTL	UART module 1 Data Set Ready modem output control line.
U1DTR	L12 A2	PJ7 (9) PD7 (9)	0	TTL	UART module 1 Data Terminal Ready modem status input signal.
U1RI	B5	PD4 (9)	I	TTL	UART module 1 Ring Indicator modem status input signal.
U1RTS	L10 H12	PJ6 (9) PF1 (9)	0	TTL	UART module 1 Request to Send modem flow control output line.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
U1Rx	G1 H2 M2 L3 E12 A6	PD0 (5) PD2 (1) PC6 (5) PA0 (9) PB0 (5) PB4 (7)	I	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
U1Tx	G2 H1 L2 M3 D12 B7	PD1 (5) PD3 (1) PC7 (5) PA1 (9) PB1 (5) PB5 (7)	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
U2Rx	G1 K1 A6 C6	PD0 (4) PG0 (1) PB4 (4) PD5 (9)	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
U2Tx	B2 G2 K2 A3	PE4 (5) PD1 (4) PG1 (1) PD6 (9)	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.
USB0DM	C11	fixed	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
USB0DP	C12	fixed	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
USB0EPEN	K1 M1 L6 A11 D10	PG0 (7) PC5 (6) PA6 (8) PB2 (8) PH3 (4)	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USB0ID	E12	PB0	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).
USB0PFLT	L2 M2 M6 E11 B11 B10 B6	PC7 (6) PC6 (7) PA7 (8) PB3 (8) PE0 (9) PH4 (4) PJ1 (9)	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
USB0RBIAS	B12	fixed	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
USB0VBUS	D12	PB1	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.

Table 24-8. Signals by Signal Name (continued)

Pin Name	Pin Number	Pin Mux / Pin Assignment	Pin Type	Buffer Type <sup>a</sup>	Description
VDD	K7 G12 K8 K9 H10 G10 E10	fixed	-	Power	Positive supply for I/O and some logic.
VDDA	C7	fixed	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
VDDC	D3 C3	fixed	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .
VREFA	A7	PB6	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.
XTALNPHY	J1	fixed	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
XTALPPHY	J2	fixed	1	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### 24.2.3 Signals by Function, Except for GPIO

Table 24-9. Signals by Function, Except for GPIO

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	AIN0	B1	I	Analog	Analog-to-digital converter input 0.
	AIN1	A1	I	Analog	Analog-to-digital converter input 1.
	AIN2	В3	I	Analog	Analog-to-digital converter input 2.
	AIN3	B2	I	Analog	Analog-to-digital converter input 3.
	AIN4	A2	I	Analog	Analog-to-digital converter input 4.
	AIN5	A3	I	Analog	Analog-to-digital converter input 5.
	AIN6	C6	I	Analog	Analog-to-digital converter input 6.
	AIN7	B5	I	Analog	Analog-to-digital converter input 7.
	AIN8	B4	I	Analog	Analog-to-digital converter input 8.
	AIN9	A4	I	Analog	Analog-to-digital converter input 9.
ADC	AIN10	A6	I	Analog	Analog-to-digital converter input 10.
	AIN11	B7	I	Analog	Analog-to-digital converter input 11.
	AIN12	H1	I	Analog	Analog-to-digital converter input 12.
	AIN13	H2	I	Analog	Analog-to-digital converter input 13.
	AIN14	G2	I	Analog	Analog-to-digital converter input 14.
	AIN15	G1	I	Analog	Analog-to-digital converter input 15.
	VREFA	A7	I	Analog	This input provides a reference voltage used to specify the input voltage at which the ADC converts to a maximum value. In other words, the voltage that is applied to VREFA is the voltage with which an AINn signal is converted to 4095. The VREFA input is limited to the range specified in Table 26-23 on page 1333.
	C0+	A7	I	Analog	Analog comparator 0 positive input.
	C0-	A6	I	Analog	Analog comparator 0 negative input.
	C0o	M1 K4 A7 B7 A2	0	TTL	Analog comparator 0 output.
	C1+	M1	I	Analog	Analog comparator 1 positive input.
Analog Comparators	C1-	B7	I	Analog	Analog comparator 1 negative input.
Analog Comparators	Clo	A1 L2 M1 K3 D11	0	TTL	Analog comparator 1 output.
	C2+	M2	I	Analog	Analog comparator 2 positive input.
	C2-	L2	I	Analog	Analog comparator 2 negative input.
	C20	B1 M2	0	TTL	Analog comparator 2 output.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	CANORX	G1 L5 L6 A6	I	TTL	CAN module 0 receive.
Controller Area Network	CANOTX	G2 M5 M6 B7	0	TTL	CAN module 0 transmit.
	CAN1Rx	M9	I	TTL	CAN module 1 receive.
	CAN1Tx	H12	0	TTL	CAN module 1 transmit.
	ERBIAS	J3	0	Analog	12.4-k $\Omega$ resistor (1% precision) used internally for Ethernet PHY.
	LED0	J12	0	TTL	Ethernet LED 0.
	LED1	J11	0	TTL	Ethernet LED 1.
	MDIO	L9	I/O	OD	MDIO of the Ethernet PHY.
	RXIN	L7	1	Analog	RXIN of the Ethernet PHY.
Ethernet	RXIP	M7	_	Analog	RXIP of the Ethernet PHY.
Luiemet	TXON	L8	0	TTL	TXON of the Ethernet PHY.
	TXOP	M8	0	TTL	TXOP of the Ethernet PHY.
	XTALNPHY	J1	0	Analog	Ethernet PHY XTALN 25-MHz oscillator crystal output. Leave this pin unconnected when using a single-ended 25-MHz clock input connected to the XTALPPHY pin.
	XTALPPHY	J2	I	Analog	Ethernet PHY XTALP 25-MHz oscillator crystal input or external clock reference input.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	EPIOSO	D10	I/O	TTL	EPI module 0 signal 0.
	EPI0S1	D11	I/O	TTL	EPI module 0 signal 1.
	EPI0S2	L1	I/O	TTL	EPI module 0 signal 2.
	EPIOS3	M1	I/O	TTL	EPI module 0 signal 3.
	EPIOS4	M2	I/O	TTL	EPI module 0 signal 4.
	EPIOS5	L2	I/O	TTL	EPI module 0 signal 5.
	EPI0S6	C9	I/O	TTL	EPI module 0 signal 6.
	EPIOS7	C8	I/O	TTL	EPI module 0 signal 7.
	EPIOS8	B11	I/O	TTL	EPI module 0 signal 8.
	EPIOS9	A12	I/O	TTL	EPI module 0 signal 9.
	EPIOS10	B10	I/O	TTL	EPI module 0 signal 10.
	EPIOS11	F10	I/O	TTL	EPI module 0 signal 11.
	EPIOS12	K4	I/O	TTL	EPI module 0 signal 12.
	EPIOS13	K1	I/O	TTL	EPI module 0 signal 13.
	EPIOS14	K2	I/O	TTL	EPI module 0 signal 14.
	EPIOS15	K3	I/O	TTL	EPI module 0 signal 15.
External Derinberal	EPIOS16	F3	I/O	TTL	EPI module 0 signal 16.
External Peripheral Interface	EPIOS17	B6	I/O	TTL	EPI module 0 signal 17.
	EPIOS18	K6	I/O	TTL	EPI module 0 signal 18.
	EPIOS19	M10 B5	I/O	TTL	EPI module 0 signal 19.
	EPI0S20	H2	I/O	TTL	EPI module 0 signal 20.
	EPIOS21	H1	I/O	TTL	EPI module 0 signal 21.
	EPI0S22	B7	I/O	TTL	EPI module 0 signal 22.
	EPIOS23	A6	I/O	TTL	EPI module 0 signal 23.
	EPIOS24	A4	I/O	TTL	EPI module 0 signal 24.
	EPI0S25	B4	I/O	TTL	EPI module 0 signal 25.
	EPI0S26	G3	I/O	TTL	EPI module 0 signal 26.
	EPIOS27	H3	I/O	TTL	EPI module 0 signal 27.
	EPIOS28	K11 C6	I/O	TTL	EPI module 0 signal 28.
	EPIOS29	K12 A3	I/O	TTL	EPI module 0 signal 29.
	EPIOS30	L10 A2	I/O	TTL	EPI module 0 signal 30.
	EPIOS31	C10	I/O	TTL	EPI module 0 signal 31.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	CCP0	H1 L2 M2 K6 K4 L12 E12 A11 B7 B5	I/O	TTL	Capture/Compare/PWM 0.
	CCP1	M1 L1 L6 L10 D12 A7 B4 A2	I/O	TTL	Capture/Compare/PWM 1.
General-Purpose	CCP2	B2 G2 L1 K3 K12 D12 A12 B7 A4 C6	I/O	TTL	Capture/Compare/PWM 2.
Timers	CCP3	B2 M2 M1 M6 H12 A11 B11 B5	I/O	TTL	Capture/Compare/PWM 3.
	CCP4	L2 L1 M6 K11 A4 C6	I/O	TTL	Capture/Compare/PWM 4.
	CCP5	B3 H2 L1 C10 A7 B7	I/O	TTL	Capture/Compare/PWM 5.
	CCP6	G1 H2 M10 A12 C9 B7	I/O	TTL	Capture/Compare/PWM 6.
	CCP7		I/O	TTL	Capture/Compare/PWM 7.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
		G2 H1 C8 A7 B4			
	I2C0SCL	A11	I/O	OD	I <sup>2</sup> C module 0 clock.
	I2C0SDA	E11	I/O	OD	I <sup>2</sup> C module 0 data.
12C	I2C1SCL	F3 K1 L3 L6	I/O	OD	I <sup>2</sup> C module 1 clock.
	I2C1SDA	K2 M3 M6 B6	I/O	OD	I <sup>2</sup> C module 1 data.
	I2S0RXMCLK	L4 C6	I/O	TTL	I <sup>2</sup> S module 0 receive master clock.
	I2S0RXSCK	G1	I/O	TTL	I <sup>2</sup> S module 0 receive clock.
	I2S0RXSD	M4 B5	I/O	TTL	I <sup>2</sup> S module 0 receive data.
	I2S0RXWS	G2	I/O	TTL	I <sup>2</sup> S module 0 receive word select.
li2S	I2S0TXMCLK	H12	I/O	TTL	I <sup>2</sup> S module 0 transmit master clock.
	I2SOTXSCK	L5 A7 A3	I/O	TTL	I <sup>2</sup> S module 0 transmit clock.
	I2SOTXSD	B3 M9	I/O	TTL	I <sup>2</sup> S module 0 transmit data.
	I2SOTXWS	B2 M5 A2	I/O	TTL	I <sup>2</sup> S module 0 transmit word select.
	SWCLK	A9	I	TTL	JTAG/SWD CLK.
	SWDIO	В9	I/O	TTL	JTAG TMS and SWDIO.
	SWO	A10	0	TTL	JTAG TDO and SWO.
JTAG/SWD/SWO	TCK	A9	I	TTL	JTAG/SWD CLK.
	TDI	B8	ı	TTL	JTAG TDI.
	TDO	A10	0	TTL	JTAG TDO and SWO.
	TMS	B9	I	TTL	JTAG TMS and SWDIO.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	Fault0	B2 K6 K4 E11 A12 D10 A3	I	TTL	PWM Fault 0.
	Fault1	A7	ı	TTL	PWM Fault 1.
	Fault2	M1 F10	I	TTL	PWM Fault 2.
	Fault3	E11 D11	I	TTL	PWM Fault 3.
	PWM0	G1 F3 K1 L6 M9	0	TTL	PWM 0. This signal is controlled by PWM Generator 0.
	PWM1	G2 K2 M6 H12 B6	0	TTL	PWM 1. This signal is controlled by PWM Generator 0.
PWM	PWM2	H2 J11 E12 C9	0	TTL	PWM 2. This signal is controlled by PWM Generator 1.
	РWМ3	H1 J12 D12 C8	0	TTL	PWM 3. This signal is controlled by PWM Generator 1.
	PWM4	A1 K1 M4 L6 J11 G3 B11	O	TTL	PWM 4. This signal is controlled by PWM Generator 2.
	PWM5	B1 H3 K2 L4 M6 J12 A12 C8	0	TTL	PWM 5. This signal is controlled by PWM Generator 2.
	РWM6	L1 L5	0	TTL	PWM 6. This signal is controlled by PWM Generator 3.
	РWM7	M2 M5 C10	0	TTL	PWM 7. This signal is controlled by PWM Generator 3.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	GND	C4 C5 K5 K10 J10 F11 F12	-	Power	Ground reference for logic and I/O pins.
	GNDA	A5	-	Power	The ground reference for the analog circuits (ADC, Analog Comparators, etc.). These are separated from GND to minimize the electrical noise contained on VDD from affecting the analog functions.
	LDO	E3	-	Power	Low drop-out regulator output voltage. This pin requires an external capacitor between the pin and GND of 1 $\mu$ F or greater. The LDO pin must also be connected to the VDDC pins at the board level in addition to the decoupling capacitor(s).
Power	VDD	K7 G12 K8 K9 H10 G10 E10 G11	-	Power	Positive supply for I/O and some logic.
	VDDA	C7	-	Power	The positive supply for the analog circuits (ADC, Analog Comparators, etc.). These are separated from VDD to minimize the electrical noise contained on VDD from affecting the analog functions. VDDA pins must be supplied with a voltage that meets the specification in Table 26-2 on page 1317, regardless of system implementation.
	VDDC	D3 C3	-	Power	Positive supply for most of the logic function, including the processor core and most peripherals. The voltage on this pin is 1.3 V and is supplied by the on-chip LDO. The VDDC pins should only be connected to the LDO pin and an external capacitor as specified in .

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	IDX0	G1 A11 A7 A6 A2	I	TTL	QEI module 0 index.
	IDX1	H12 D11	1	TTL	QEI module 1 index.
QEI	PhA0	G2 L1 A4	I	TTL	QEI module 0 phase A.
	PhA1	B4	I	TTL	QEI module 1 phase A.
	PhB0	L2 M2 M9 D10 B4	ı	TTL	QEI module 0 phase B.
	PhB1	G2 C10 A4	I	TTL	QEI module 1 phase B.
	SSI0Clk	M4	I/O	TTL	SSI module 0 clock
	SSI0Fss	L4	I/O	TTL	SSI module 0 frame signal
	SSI0Rx	L5	I	TTL	SSI module 0 receive
	SSIOTx	M5	0	TTL	SSI module 0 transmit
	SSI1Clk	J11 B11 B10	I/O	TTL	SSI module 1 clock.
SSI	SSI1Fss	J12 F10 A12	I/O	TTL	SSI module 1 frame signal.
	SSI1Rx	K4 G3 A4	I	TTL	SSI module 1 receive.
	SSI1Tx	H3 K3 B4	0	TTL	SSI module 1 transmit.
	NMI	A8	I	TTL	Non-maskable interrupt.
System Control &	osc0	L11	1	Analog	Main oscillator crystal input or an external clock reference input.
Clocks	osc1	M11	0	Analog	Main oscillator crystal output. Leave unconnected when using a single-ended clock source.
	RST	H11	I	TTL	System reset input.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	U0Rx	L3	I	TTL	UART module 0 receive. When in IrDA mode, this signal has IrDA modulation.
	UOTx	M3	0	TTL	UART module 0 transmit. When in IrDA mode, this signal has IrDA modulation.
	U1CTS	A1 G1 L6 M10	I	TTL	UART module 1 Clear To Send modem flow control input signal.
	U1DCD	B1 G2 M6 K11	I	TTL	UART module 1 Data Carrier Detect modem status input signal.
	U1DSR	M9 K12	ı	TTL	UART module 1 Data Set Ready modem output control line.
	U1DTR	L12 A2	0	TTL	UART module 1 Data Terminal Ready modem status input signal.
	U1RI	B5	I	TTL	UART module 1 Ring Indicator modem status input signal.
UART	U1RTS	L10 H12	0	TTL	UART module 1 Request to Send modem flow control output line.
	UlRx	G1 H2 M2 L3 E12 A6	l	TTL	UART module 1 receive. When in IrDA mode, this signal has IrDA modulation.
	UlTx	G2 H1 L2 M3 D12 B7	0	TTL	UART module 1 transmit. When in IrDA mode, this signal has IrDA modulation.
	U2Rx	G1 K1 A6 C6	I	TTL	UART module 2 receive. When in IrDA mode, this signal has IrDA modulation.
	U2Tx	B2 G2 K2 A3	0	TTL	UART module 2 transmit. When in IrDA mode, this signal has IrDA modulation.

Table 24-9. Signals by Function, Except for GPIO (continued)

Function	Pin Name	Pin Number	Pin Type	Buffer Type <sup>a</sup>	Description
	USB0DM	C11	I/O	Analog	Bidirectional differential data pin (D- per USB specification) for USB0.
	USB0DP	C12	I/O	Analog	Bidirectional differential data pin (D+ per USB specification) for USB0.
	USB0EPEN	K1 M1 L6 A11 D10	0	TTL	Optionally used in Host mode to control an external power source to supply power to the USB bus.
USB	USB0ID	E12	I	Analog	This signal senses the state of the USB ID signal. The USB PHY enables an integrated pull-up, and an external element (USB connector) indicates the initial state of the USB controller (pulled down is the A side of the cable and pulled up is the B side).
USB	USB0PFLT	L2 M2 M6 E11 B11 B10 B6	I	TTL	Optionally used in Host mode by an external power source to indicate an error state by that power source.
	USB0RBIAS	B12	0	Analog	9.1-k $\Omega$ resistor (1% precision) used internally for USB analog circuitry.
	USB0VBUS	D12	I/O	Analog	This signal is used during the session request protocol. This signal allows the USB PHY to both sense the voltage level of VBUS, and pull up VBUS momentarily during VBUS pulsing.

a. The TTL designation indicates the pin has TTL-compatible voltage levels.

### 24.2.4 GPIO Pins and Alternate Functions

Table 24-10. GPIO Pins and Alternate Functions

10	Pin	Analog			Digi	ital Functi	ion (GPIO	PCTL PM	Cx Bit Fie	ld Encodi	ng) <sup>a</sup>		
10	PIII	Function	1	2	3	4	5	6	7	8	9	10	11
PA0	L3	-	U0Rx	-	-	-	-	-	-	I2C1SCL	U1Rx	-	-
PA1	МЗ	-	U0Tx	-	-	-	-	-	-	I2C1SDA	UlTx	-	-
PA2	M4	-	SSI0Clk	-	-	PWM4	-	-	-	-	I2S0RXSD	-	-
PA3	L4	-	SSI0Fss	-	-	PWM5	-	-	-	-	12SORXMOLK	-	-
PA4	L5	-	SSI0Rx	-	-	РИМб	CAN0Rx	-	-	-	I2SOTXSCK	-	-
PA5	M5	-	SSIOTx	-	-	PWM7	CANOTX	-	-	-	I2SOTXWS	-	-
PA6	L6	-	I2C1SCL	CCP1	-	PWM0	PWM4	CAN0Rx	-	USB0EPEN	Ulcts	-	-
PA7	M6	-	I2C1SDA	CCP4	-	PWM1	PWM5	CAN0Tx	CCP3	USB0PFLT	U1DCD	-	-
PB0	E12	USB0ID	CCP0	PWM2	-	-	U1Rx	-	-	-	-	-	-
PB1	D12	USB0VBUS	CCP2	PWM3	-	CCP1	U1Tx	-	-	-	-	-	-
PB2	A11	-	I2C0SCL	IDX0	-	CCP3	CCP0	-	-	USB0EPEN	-	-	-
PB3	E11	-	I2C0SDA	Fault0	-	Fault3	-	-	-	USB0PFLT	-	-	-
PB4	A6	AIN10 CO-	-	-	-	U2Rx	CAN0Rx	IDX0	U1Rx	EPI0S23	-	-	-

Table 24-10. GPIO Pins and Alternate Functions (continued)

		Analog			Digi	tal Functi	on (GPIO	PCTL PM	Cx Bit Fiel	d Encodi	ng) <sup>a</sup>		
Ю	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PB5	В7	AIN11 C1-	C0o	CCP5	CCP6	CCP0	CAN0Tx	CCP2	U1Tx	EPI0S22	-	-	-
PB6	A7	VREFA C0+	CCP1	CCP7	C00	Fault1	IDX0	CCP5	-	-	I2S0IXSCK	-	-
PB7	A8	-	-	-	-	NMI	-	-	-	-	-	-	-
PC0	A9	-	-	-	TCK SWCLK	-	-	-	-	-	-	-	-
PC1	В9	-	-	-	TMS SWDIO	-	-	-	-	-	-	-	-
PC2	B8	-	-	-	TDI	-	-	-	-	-	-	-	-
PC3	A10	-	-	-	TDO SWO	-	-	-	-	-	-	-	-
PC4	L1	-	CCP5	PhA0	-	PWM6	CCP2	CCP4	-	EPI0S2	CCP1	-	-
PC5	M1	C1+	CCP1	C1o	C0o	Fault2	CCP3	USB0EPEN	-	EPIOS3	-	-	-
PC6	M2	C2+	CCP3	PhB0	C20	PWM7	U1Rx	CCP0	USB0PFLT	EPI0S4	-	-	-
PC7	L2	C2-	CCP4	PhB0	-	CCP0	U1Tx	USB0PFLT	C1o	EPIOS5	-	-	-
PD0	G1	AIN15	PWM0	CAN0Rx	IDX0	U2Rx	U1Rx	CCP6	-	I2SORXSCK	U1CTS	-	-
PD1	G2	AIN14	PWM1	CAN0Tx	PhA0	U2Tx	U1Tx	CCP7	-	I2SORXWS	U1DCD	CCP2	PhB1
PD2	H2	AIN13	U1Rx	CCP6	PWM2	CCP5	-	-	-	EPI0S20	-	-	-
PD3	H1	AIN12	U1Tx	CCP7	PWM3	CCP0	-	-	-	EPI0S21	-	-	-
PD4	B5	AIN7	CCP0	CCP3	-	-	-	-	-	I2S0RXSD	U1RI	EPIOS19	-
PD5	C6	AIN6	CCP2	CCP4	-	-	-	-	-	I2SORXMOLK	U2Rx	EPI0S28	-
PD6	А3	AIN5	Fault0	-	-	-	-	-	-	I2SOTXSCK	U2Tx	EPI0S29	-
PD7	A2	AIN4	IDX0	C0o	CCP1	-	-	-	-	I2SOTXWS	U1DTR	EPIOS30	-
PE0	B11	-	PWM4	SSI1Clk	CCP3	-	-	-	-	EPIOS8	USB0PFLT	-	-
PE1	A12	-	PWM5	SSI1Fss	Fault0	CCP2	CCP6	-	-	EPIOS9	-	-	-
PE2	A4	AIN9	CCP4	SSI1Rx	PhB1	PhA0	CCP2	-	-	EPI0S24	-	-	-
PE3	B4	AIN8	CCP1	SSI1Tx	PhA1	PhB0	CCP7	-	-	EPI0S25	-	-	-
PE4	B2	AIN3	CCP3	-	-	Fault0	U2Tx	CCP2	-	-	I2SOTXWS	-	-
PE5	В3	AIN2	CCP5	-	-	-	-	-	-	-	I2SOTXSD	-	-
PE6	A1	AIN1	РWМ4	C1o	-	-	-	-	-	-	Ulcts	-	-
PE7	B1	AIN0	РWМ5	C20	-	-	-	-	-	-	U1DCD	-	-
PF0	M9	-	CAN1Rx	PhB0	PWM0	-	-	-	-	I2S0TXSD	U1DSR	-	-
PF1	H12	-	CAN1Tx	IDX1	PWM1	-	-	-	-	I2SOIXMOLK	Ulrts	CCP3	-
PF2	J11	-	LED1	PWM4	-	PWM2	-	-	-	-	SSI1Clk	-	-
PF3	J12	-	LED0	PWM5	-	PWM3	-	-	-	-	SSI1Fss	-	-
PF4	K4	-	CCP0	C0o	-	Fault0	-	-	-	EPIOS12	SSI1Rx	-	-
PF5	K3	-	CCP2	C1o	-	-	-	-	-	EPIOS15	SSI1Tx	-	-
PG0	K1	-	U2Rx	PWM0	I2C1SCL	PWM4	-	-	USB0EPEN	EPIOS13	-	-	-
PG1	K2	-	U2Tx	PWM1	I2C1SDA	PWM5	-	-	-	EPIOS14	-	-	-
PG7	C10	-	PhB1	-	-	PWM7	-	-	-	CCP5	EPIOS31	-	-
PH0	C9	-	CCP6	PWM2	-	-	-	-	-	EPI0S6	PWM4	-	-

Table 24-10. GPIO Pins and Alternate Functions (continued)

10	Pin	Analog			Dig	ital Functi	on (GPIO	PCTL PM	Cx Bit Fie	ld Encodi	ng) <sup>a</sup>		
10	Pin	Function	1	2	3	4	5	6	7	8	9	10	11
PH1	C8	-	CCP7	PWM3	-	-	-	-	-	EPI0S7	PWM5	-	-
PH2	D11	-	IDX1	C1o	-	Fault3	-	-	-	EPI0S1	-	-	-
РН3	D10	-	PhB0	Fault0	-	USB0EPEN	-	-	-	EPI0S0	-	-	-
PH4	B10	-	-	-	-	USB0PFLT	-	-	-	EPIOS10	-	-	SSI1Clk
PH5	F10	-	-	-	-	-	-	-	-	EPIOS11	-	Fault2	SSI1Fss
РН6	G3	-	-	-	-	-	-	-	-	EPIOS26	-	PWM4	SSI1Rx
PH7	НЗ	-	-	-	-	-	-	-	-	EPI0S27	-	PWM5	SSI1Tx
рј0	F3	-	-	-	-	-	-	-	-	EPIOS16	-	PWM0	I2C1SCL
PJ1	В6	-	-	-	-	-	-	-	-	EPIOS17	USB0PFLT	PWM1	I2C1SDA
РЈ2	K6	-	-	-	-	-	-	-	-	EPIOS18	CCP0	Fault0	-
рЈ3	M10	-	-	-	-	-	-	-	-	EPIOS19	Ulcts	CCP6	-
рј4	K11	-	-	-	-	-	-	-	-	EPIOS28	U1DCD	CCP4	-
PJ5	K12	-	-	-	-	-	-	-	-	EPIOS29	U1DSR	CCP2	-
PJ6	L10	-	-	-	-	-	-	-	-	EPIOS30	Ulrts	CCP1	-
PJ7	L12	-	-	-	-	-	-	-	-	-	U1DTR	CCP0	-

a. The digital signals that are shaded gray are the power-on default values for the corresponding GPIO pin.

### 24.2.5 Possible Pin Assignments for Alternate Functions

Table 24-11. Possible Pin Assignments for Alternate Functions

	Alternate Function	GPIO Function
	AIN0	PE7
	AIN1	PE6
	AIN10	PB4
	AIN11	PB5
	AIN12	PD3
	AIN13	PD2
	AIN14	PD1
	AIN15	PD0
	AIN2	PE5
	AIN3	PE4
	AIN4	PD7
	AIN5	PD6
	AIN6	PD5
	AIN7	PD4
	AIN8	PE3
	AIN9	PE2
	C0+	PB6
	C0-	PB4
	C1+	PC5
one	C1-	PB5
	C2+	PC6
	C2-	PC7
	CAN1Rx	PF0
	CAN1Tx	PF1
	EPI0S0	PH3
	EPIOS1	PH2
	EPIOS10	PH4
	EPIOS11	PH5
	EPIOS12	PF4
	EPIOS13	PG0
	EPIOS14	PG1
	EPIOS15	PF5
	EPIOS16	PJ0
	EPIOS17	PJ1
	EPIOS18	PJ2
	EPI0S2	PC4
	EPIOS20	PD2
	EPIOS21	PD3
	EPIOS22	PB5

Table 24-11. Possible Pin Assignments for Alternate Functions (continued)

# of Possible Assignments	Alternate Function	GPIO Function
	EPIOS23	PB4
	EPIOS24	PE2
	EPIOS25	PE3
	EPIOS26	PH6
	EPIOS27	PH7
	EPIOS3	PC5
	EPIOS31	PG7
	EPI0S4	PC6
	EPI0S5	PC7
	EPI0S6	PH0
	EPIOS7	PH1
	EPIOS8	PE0
	EPIOS9	PE1
	Fault1	PB6
	I2C0SCL	PB2
	I2C0SDA	PB3
	I2S0RXSCK	PD0
	I2S0RXWS	PD1
	I2S0TXMCLK	PF1
	LED0	PF3
	LED1	PF2
	NMI	PB7
	PhA1	PE3
	SSI0Clk	PA2
	SSIOFss	PA3
	SSIORx	PA4
	SSIOTx	PA5
	SWCLK	PC0
	SWDIO	PC1
	SWO	PC3
	TCK	PC0
	TDI	PC2
	TDO	PC3
	TMS	PC1
	U0Rx	PA0
	UOTx	PA1
	U1RI	PD4
	USB0ID	PB0
	USB0VBUS	PB1
	VREFA	PB6

Table 24-11. Possible Pin Assignments for Alternate Functions (continued)

C20   PET PC6	# of Possible Assignments	Alternate Function	GPIO Function			
EPI0S28   PJ4 PD5		C20	PE7 PC6			
RPI0S29		EPIOS19	PJ3 PD4			
Fault2		EPI0S28	PJ4 PD5			
Fault2		EPI0S29	PJ5 PD6			
two		EPIOS30	PJ6 PD7			
two		Fault2	PC5 PH5			
1250RXSD		Fault3	PB3 PH2			
IDX1	two	I2S0RXMCLK	PA3 PD5			
IDX1		I2S0RXSD	PA2 PD4			
PWM6		I2S0TXSD	PE5 PF0			
UIDSR		IDX1	PF1 PH2			
Uldtr		PWM6	PC4 PA4			
UIRTS		U1DSR	PF0 PJ5			
I 2SOTXSCK		U1DTR	PJ7 PD7			
12SOTXWS		U1RTS	PJ6 PF1			
### PWM7 PC6 PA5 PG7    PhA0 PD1 PC4 PE2		I2S0TXSCK	PA4 PB6 PD6			
Pha0         PD1 PC4 PE2           PhB1         PD1 PG7 PE2           SSI1Clk         PF2 PE0 PH4           SSI1Fss         PF3 PH5 PE1           SSI1Rx         PF4 PH6 PE2           SSI1Tx         PH7 PF5 PE3           CANORX         PD0 PA4 PA6 PB4           CANOTX         PD1 PA5 PA7 PB5           I2C1SCL         PJ0 PG0 PA0 PA6           I2C1SDA         PG1 PA1 PA7 PJ1           PWM2         PD2 PF2 PB0 PH0           PWM3         PD3 PF3 PB1 PH1           U1CTS         PE6 PD0 PA6 PJ3           U1DCD         PE7 PD1 PA7 PJ4           U2Rx         PD0 PG0 PB4 PD5		I2SOTXWS	PE4 PA5 PD7			
three PhB1 PD1 PG7 PE2  SSI1Clk PF2 PE0 PH4  SSI1Fss PF3 PH5 PE1  SSI1Rx PF4 PH6 PE2  SSI1Tx PH7 PF5 PE3  CANORX PD0 PA4 PA6 PB4  CANOTX PD1 PA5 PA7 PB5  I2ClSCL PJ0 PG0 PA0 PA6  I2ClSDA PG1 PA1 PA7 PJ1  PWM2 PD2 PF2 PB0 PH0  PWM3 PD3 PF3 PB1 PH1  U1CTS PE6 PD0 PA6 PJ3  U1DCD PE7 PD1 PA7 PJ4  U2RX PD0 PG0 PB4 PD5		PWM7	PC6 PA5 PG7			
SSI1Clk		PhA0	PD1 PC4 PE2			
SSI1FSS	three	PhB1	PD1 PG7 PE2			
SSI1Rx		SSI1Clk	PF2 PE0 PH4			
SSI1Tx		SSI1Fss	PF3 PH5 PE1			
Four   PD0 PA4 PA6 PB4		SSI1Rx	PF4 PH6 PE2			
CANOTX PD1 PA5 PA7 PB5  I2C1SCL PJ0 PG0 PA0 PA6  I2C1SDA PG1 PA1 PA7 PJ1  PWM2 PD2 PF2 PB0 PH0  PWM3 PD3 PF3 PB1 PH1  U1CTS PE6 PD0 PA6 PJ3  U1DCD PE7 PD1 PA7 PJ4  U2RX PD0 PG0 PB4 PD5		SSI1Tx	PH7 PF5 PE3			
Four Four PJ0 PG0 PA0 PA6  I2C1SDA PG1 PA1 PA7 PJ1  PWM2 PD2 PF2 PB0 PH0  PWM3 PD3 PF3 PB1 PH1  U1CTS PE6 PD0 PA6 PJ3  U1DCD PE7 PD1 PA7 PJ4  U2Rx PD0 PG0 PB4 PD5		CAN0Rx	PD0 PA4 PA6 PB4			
Four Four PG1 PA1 PA7 PJ1  PWM2 PD2 PF2 PB0 PH0  PWM3 PD3 PF3 PB1 PH1  U1CTS PE6 PD0 PA6 PJ3  U1DCD PE7 PD1 PA7 PJ4  U2Rx PD0 PG0 PB4 PD5		CAN0Tx	PD1 PA5 PA7 PB5			
Four PD2 PF2 PB0 PH0 PWM3 PD3 PF3 PB1 PH1 U1CTS PE6 PD0 PA6 PJ3 U1DCD PE7 PD1 PA7 PJ4 U2Rx PD0 PG0 PB4 PD5		I2C1SCL	PJ0 PG0 PA0 PA6			
Four  PWM3  PD3 PF3 PB1 PH1  U1CTS  PE6 PD0 PA6 PJ3  U1DCD  PE7 PD1 PA7 PJ4  U2Rx  PD0 PG0 PB4 PD5		I2C1SDA	PG1 PA1 PA7 PJ1			
PWM3 PD3 PF3 PB1 PH1  U1CTS PE6 PD0 PA6 PJ3  U1DCD PE7 PD1 PA7 PJ4  U2Rx PD0 PG0 PB4 PD5	four	PWM2	PD2 PF2 PB0 PH0			
U1DCD         PE7 PD1 PA7 PJ4           U2Rx         PD0 PG0 PB4 PD5	ioui –	PWM3	PD3 PF3 PB1 PH1			
U2Rx PD0 PG0 PB4 PD5		U1CTS	PE6 PD0 PA6 PJ3			
		U1DCD	PE7 PD1 PA7 PJ4			
U2Tx PE4 PD1 PG1 PD6		U2Rx	PD0 PG0 PB4 PD5			
		U2Tx	PE4 PD1 PG1 PD6			

Table 24-11. Possible Pin Assignments for Alternate Functions (continued)

# of Possible Assignments	Alternate Function	GPIO Function
	C0o	PC5 PF4 PB6 PB5 PD7
	Clo	PE6 PC7 PC5 PF5 PH2
	CCP7	PD1 PD3 PH1 PB6 PE3
five	IDX0	PD0 PB2 PB6 PB4 PD7
live	PWM0	PD0 PJ0 PG0 PA6 PF0
	PWM1	PD1 PG1 PA7 PF1 PJ1
	PhB0	PC7 PC6 PF0 PH3 PE3
	USB0EPEN	PG0 PC5 PA6 PB2 PH3
	CCP4	PC7 PC4 PA7 PJ4 PE2 PD5
	CCP5	PE5 PD2 PC4 PG7 PB6 PB5
six	CCP6	PD0 PD2 PJ3 PE1 PH0 PB5
	U1Rx	PD0 PD2 PC6 PA0 PB0 PB4
	UlTx	PD1 PD3 PC7 PA1 PB1 PB5
aayan	Fault0	PE4 PJ2 PF4 PB3 PE1 PH3 PD6
seven	USB0PFLT	PC7 PC6 PA7 PB3 PE0 PH4 PJ1
	CCP1	PC5 PC4 PA6 PJ6 PB1 PB6 PE3 PD7
oight	CCP3	PE4 PC6 PC5 PA7 PF1 PB2 PE0 PD4
eight -	PWM4	PE6 PG0 PA2 PA6 PF2 PH6 PE0 PH0
	PWM5	PE7 PH7 PG1 PA3 PA7 PF3 PE1 PH1
ton	CCP0	PD3 PC7 PC6 PJ2 PF4 PJ7 PB0 PB2 PB5 PD4
ten	CCP2	PE4 PD1 PC4 PF5 PJ5 PB1 PE1 PB5 PE2 PD5

### 24.3 Connections for Unused Signals

Table 24-12 on page 1314 shows how to handle signals for functions that are not used in a particular system implementation for devices that are in a 100-pin LQFP package. Two options are shown in the table: an acceptable practice and a preferred practice for reduced power consumption and improved EMC characteristics. If a module is not used in a system, and its inputs are grounded, it is important that the clock to the module is never enabled by setting the corresponding bit in the **RCGCx** register.

Table 24-12. Connections for Unused Signals (100-Pin LQFP)

Function	Signal Name	Pin Number	Acceptable Practice	Preferred Practice	
	ERBIAS 33		Connect to GND through 12.4-kΩ resistor.	Connect to GND through 12.4-kΩ resistor.	
	RXIN	37	NC	GND	
[	RXIP	40	NC	GND	
Ethernet	TXON	46	NC	GND	
	TXOP	43	NC	GND	
	XTALNPHY <sup>a</sup>	17	NC	NC	
	XTALPPHY <sup>a</sup>	16	NC	GND	
GPIO	All unused GPIOs	-	NC	GND	
No Connects	NC	-	NC	NC	

Table 24-12. Connections for Unused Signals (100-Pin LQFP) (continued)

Function	Signal Name	Pin Number	Acceptable Practice	Preferred Practice	
	OSC0 48		NC	GND	
System	OSC1	49	NC	NC	
Control	RST 64		Pull up as shown in Figure 5-1 on page 195	Connect through a capacitor to GND as close to pin as possible	
	USB0DM	70	NC	GND	
USB	USBODP 71		NC	GND	
	USB0RBIAS	73	Connect to GND through 10-k $\Omega$ resistor.	Connect to GND through 10-kΩ resistor.	

a. Note that the Ethernet PHY is powered up by default. The PHY cannot be powered down unless a clock source is provided and the MDIO pin is pulled up through a  $10\text{-}k\Omega$  resistor.

Table 24-13 on page 1315 shows how to handle signals for functions that are not used in a particular system implementation for devices that are in a 108-ball BGA package. Two options are shown in the table: an acceptable practice and a preferred practice for reduced power consumption and improved EMC characteristics. If a module is not used in a system, and its inputs are grounded, it is important that the clock to the module is never enabled by setting the corresponding bit in the **RCGCx** register.

Table 24-13. Connections for Unused Signals (108-Ball BGA)

Function	Signal Name	Pin Number	Acceptable Practice	Preferred Practice	
	erbias J3		Connect to GND through 12.4-kΩ resistor.	Connect to GND through 12.4- $k\Omega$ resistor.	
	RXIN	L7	NC	GND	
	RXIP	M7	NC	GND	
Ethernet	TXON	L8	NC	GND	
	TXOP	M8	NC	GND	
	XTALNPHY <sup>a</sup>	J1	NC	NC	
	XTALPPHY <sup>a</sup>	J2	NC	GND	
GPIO	All unused GPIOs	-	NC	GND	
No Connects	NC	-	NC	NC	
	osc0	L11	NC	GND	
System	OSC1	M11	NC	NC	
Control	RST H11		Pull up as shown in Figure 5-1 on page 195	Connect through a capacitor to GND as close to pin as possible	
	USBORBIAS B12		Connect to GND through 10-k $\Omega$ resistor.	Connect to GND through 10-k $\Omega$ resistor.	
USB	USB0DM	C11	NC	GND	
	USB0DP	C12	NC	GND	

a. Note that the Ethernet PHY is powered up by default. The PHY cannot be powered down unless a clock source is provided and the MDIO pin is pulled up through a  $10\text{-}k\Omega$  resistor.

# 25 Operating Characteristics

**Table 25-1. Temperature Characteristics** 

Characteristic	Symbol	Value	Unit
Industrial operating temperature range	T <sub>A</sub>	-40 to +85	°C
Unpowered storage temperature range	T <sub>S</sub>	-65 to +150	°C

#### **Table 25-2. Thermal Characteristics**

Characteristic	Symbol	Value	Unit
Thermal resistance (junction to ambient) <sup>a</sup>	$\Theta_{JA}$	33 (100LQFP)	°C/W
		31 (108BGA)	
Junction temperature, -40 to +125 <sup>b</sup>	T <sub>J</sub>	$T_A + (P \cdot \Theta_{JA})$	°C

a. Junction to ambient thermal resistance  $\theta_{\text{JA}}$  numbers are determined by a package simulator.

Table 25-3. ESD Absolute Maximum Ratings<sup>a</sup>

Parameter Name	Min	Nom	Max	Unit
V <sub>ESDHBM</sub>	-	-	2.0	kV
V <sub>ESDCDM</sub>	-	-	500	V

a. All Stellaris® parts are ESD tested following the JEDEC standard.

b. Power dissipation is a function of temperature.

### 26 Electrical Characteristics

### 26.1 Maximum Ratings

The maximum ratings are the limits to which the device can be subjected without permanently damaging the device. Device reliability may be adversely affected by exposure to absolute-maximum ratings for extended periods.

**Note:** The device is not guaranteed to operate properly at the maximum ratings.

Table 26-1. Maximum Ratings

Parameter	Parameter Name <sup>a</sup>	٧	Unit	
	raiametei Name	Min	Max	Oill
$V_{DD}$	V <sub>DD</sub> supply voltage	0	4	V
$V_{DDA}$	V <sub>DDA</sub> supply voltage	0	4	V
	Input voltage <sup>b</sup>	-0.3	5.5	V
$V_{IN\_GPIO}$	Input voltage for PB0 and PB1 when configured as GPIO	-0.3	V <sub>DD</sub> + 0.3	V
I <sub>GPIOMAX</sub>	Maximum current per output pin	-	25	mA
V <sub>NON</sub>	Maximum input voltage on a non-power pin when the microcontroller is unpowered	-	300	mV

a. Voltages are measured with respect to GND.

Important: This device contains circuitry to protect the inputs against damage due to high-static voltages or electric fields; however, it is advised that normal precautions be taken to avoid application of any voltage higher than maximum-rated voltages to this high-impedance circuit. Reliability of operation is enhanced if unused inputs are connected to an appropriate logic voltage level (see "Connections for Unused Signals" on page 1314).

### **26.2** Recommended Operating Conditions

For special high-current applications, the GPIO output buffers may be used with the following restrictions. With the GPIO pins configured as 8-mA output drivers, a total of four GPIO outputs may be used to sink current loads up to 18 mA each. At 18-mA sink current loading, the  $V_{OL}$  value is specified as 1.2 V. The high-current GPIO package pins must be selected such that there are only a maximum of two per side of the physical package or BGA pin group with the total number of high-current GPIO outputs not exceeding four for the entire package.

**Table 26-2. Recommended DC Operating Conditions** 

Parameter	Parameter Name	Min	Nom	Max	Unit
V <sub>DD</sub>	V <sub>DD</sub> supply voltage	3.0	3.3	3.6	V
$V_{DDA}$	V <sub>DDA</sub> supply voltage	3.0	3.3	3.6	V
V <sub>DDC</sub>	V <sub>DDC</sub> supply voltage, run mode	1.235	1.3	1.365	V
V <sub>IH</sub>	High-level input voltage	2.1	-	5.0	V
V <sub>IL</sub>	Low-level input voltage	-0.3	-	1.2	V
V <sub>OH</sub>	High-level output voltage	2.4	-	-	V

b. Applies to static and dynamic signals including overshoot.

**Table 26-2. Recommended DC Operating Conditions (continued)** 


Parameter	Parameter Name	Min	Nom	Max	Unit
V <sub>OL</sub>	Low-level output voltage	-	-	0.4	V
	High-level source current, V <sub>OH</sub> =2.4 V <sup>a</sup>				
l	2-mA Drive	-2.0	-	-	mA
Іон	4-mA Drive	-4.0	-	-	mA
	8-mA Drive	-8.0	-	-	mA
	Low-level sink current, V <sub>OL</sub> =0.4 V <sup>a</sup>				
	2-mA Drive	2.0	-	-	mA
I <sub>OL</sub>	4-mA Drive	4.0	-	-	mA
	8-mA Drive	8.0	-	-	mA
	8-mA Drive, V <sub>OL</sub> =1.2 V	18.0	-	-	mA

a. I<sub>O</sub> specifications reflect the maximum current where the corresponding output voltage meets the V<sub>OH</sub>/V<sub>OL</sub> thresholds. I<sub>O</sub> current can exceed these limits (subject to absolute maximum ratings).

#### 26.3 Load Conditions

Unless otherwise specified, the following conditions are true for all timing measurements.

Figure 26-1. Load Conditions



### 26.4 JTAG and Boundary Scan

**Table 26-3. JTAG Characteristics** 

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
J1	F <sub>TCK</sub>	TCK operational clock frequency <sup>a</sup>	0	-	10	MHz
J2	T <sub>TCK</sub>	TCK operational clock period	100	-	-	ns
J3	T <sub>TCK_LOW</sub>	TCK clock Low time	-	t <sub>TCK</sub> /2	-	ns
J4	T <sub>TCK_HIGH</sub>	TCK clock High time	-	t <sub>TCK</sub> /2	-	ns
J5	T <sub>TCK_R</sub>	TCK rise time	0	-	10	ns
J6	T <sub>TCK_F</sub>	TCK fall time	0	-	10	ns
J7	T <sub>TMS_SU</sub>	TMS setup time to TCK rise	20	-	-	ns
J8	T <sub>TMS_HLD</sub>	TMS hold time from TCK rise	20	-	-	ns
J9	T <sub>TDI_SU</sub>	TDI setup time to TCK rise	25	-	-	ns
J10	T <sub>TDI_HLD</sub>	TDI hold time from TCK rise	25	-	-	ns

**Table 26-3. JTAG Characteristics (continued)** 

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
		TCK fall to Data Valid from High-Z, 2-mA drive		23	35	ns
		TCK fall to Data Valid from High-Z, 4-mA drive		15	26	ns
J11	$T_{TDO\_ZDV}$	TCK fall to Data Valid from High-Z, 8-mA drive	-	14	25	ns
		TCK fall to Data Valid from High-Z, 8-mA drive with slew rate control		18	29	ns
		TCK fall to Data Valid from Data Valid, 2-mA drive		21	35	ns
		TCK fall to Data Valid from Data Valid, 4-mA drive		14	25	ns
J12	$T_{TDO\_DV}$	TCK fall to Data Valid from Data Valid, 8-mA drive	-	13	24	ns
		TCK fall to Data Valid from Data Valid, 8-mA drive with slew rate control		18	28	ns
		TCK fall to High-Z from Data Valid, 2-mA drive		9	11	ns
		TCK fall to High-Z from Data Valid, 4-mA drive		7	9	ns
J13	$T_{TDO\_DVZ}$	TCK fall to High-Z from Data Valid, 8-mA drive	-	6	8	ns
		TCK fall to High-Z from Data Valid, 8-mA drive with slew rate control		7	9	ns

a. A ratio of at least 8:1 must be kept between the system clock and  ${\tt TCK}.$ 

Figure 26-2. JTAG Test Clock Input Timing





Figure 26-3. JTAG Test Access Port (TAP) Timing



### 26.5 Power and Brown-Out

**Table 26-4. Power Characteristics** 

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
P1	$V_{TH}$	Power-On Reset threshold	-	2	-	V
P2	V <sub>BTH</sub>	Brown-Out Reset threshold	2.85	2.9	2.95	V
P3	T <sub>POR</sub>	Power-On Reset timeout	6	-	18	ms
P4	T <sub>BOR</sub>	Brown-Out timeout	-	500	-	μs
P5	T <sub>IRPOR</sub>	Internal reset timeout after POR	-	-	2	ms
P6	T <sub>IRBOR</sub>	Internal reset timeout after BOR	-	-	2	ms
P7	T <sub>VDDRISE</sub>	Supply voltage (V <sub>DD</sub> ) rise time (0V-3.0V)	-	-	10	ms
P8	T <sub>VDD2_3</sub>	Supply voltage (V <sub>DD</sub> ) rise time (2.0V-3.0V)	-	-	6	ms

Figure 26-4. Power-On Reset Timing





Figure 26-5. Brown-Out Reset Timing






Figure 26-6. Power-On Reset and Voltage Parameters

#### 26.6 Reset

**Table 26-5. Reset Characteristics** 

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
R1	$T_IRHWR$	Internal reset timeout after hardware reset ( $\overline{\mathbb{RST}}$ pin)	-	-	2	ms
R2	T <sub>IRSWR</sub>	Internal reset timeout after software-initiated system reset	-	-	2	ms
R3	$T_{IRWDR}$	Internal reset timeout after watchdog reset	-	-	2	ms
R4	T <sub>IRMFR</sub>	Internal reset timeout after MOSC failure reset	-	-	2	ms
R5	$T_{MIN}$	Minimum RST pulse width <sup>a</sup>	2	-	1	μs

a. This specification must be met in order to guarantee proper reset operation.

Figure 26-7. External Reset Timing (RST)




Figure 26-8. Software Reset Timing




Figure 26-9. Watchdog Reset Timing





Figure 26-10. MOSC Failure Reset Timing



### 26.7 On-Chip Low Drop-Out (LDO) Regulator

**Table 26-6. LDO Regulator Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
C <sub>LDO</sub>	External filter capacitor size for internal power supply <sup>a</sup>	1.0	-	3.0	μF
$V_{LDO}$	LDO output voltage	1.235	1.3	1.365	V

a. The capacitor should be connected as close as possible to pin 86.

#### 26.8 Clocks

The following sections provide specifications on the various clock sources and mode.

#### 26.8.1 PLL Specifications

The following tables provide specifications for using the PLL.

Table 26-7. Phase Locked Loop (PLL) Characteristics

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>REF_XTAL</sub>	Crystal reference <sup>a</sup>	3.579545	-	16.384	MHz
F <sub>REF_EXT</sub>	External clock reference <sup>a</sup>	3.579545	-	16.384	MHz
F <sub>PLL</sub>	PLL frequency <sup>b</sup>	-	400	-	MHz
T <sub>READY</sub>	PLL lock time	0.562 <sup>c</sup>	-	1.38 <sup>d</sup>	ms

a. The exact value is determined by the crystal value programmed into the XTAL field of the **Run-Mode Clock Configuration** (RCC) register.

b. PLL frequency is automatically calculated by the hardware based on the XTAL field of the RCC register.

c. Using a 16.384-MHz crystal

d. Using 3.5795-MHz crystal

Table 26-8 on page 1323 shows the actual frequency of the PLL based on the crystal frequency used (defined by the XTAL field in the **RCC** register).

Table 26-8. Actual PLL Frequency

XTAL	Crystal Frequency (MHz)	PLL Frequency (MHz)	Error
0x04	3.5795	400.904	0.0023%
0x05	3.6864	398.1312	0.0047%
0x06	4.0	400	-
0x07	4.096	401.408	0.0035%
0x08	4.9152	398.1312	0.0047%
0x09	5.0	400	-
0x0A	5.12	399.36	0.0016%
0x0B	6.0	400	-
0x0C	6.144	399.36	0.0016%
0x0D	7.3728	398.1312	0.0047%
0x0E	8.0	400	-
0x0F	8.192	398.6773333	0.0033%
0x10	10.0	400	-
0x11	12.0	400	-
0x12	12.288	401.408	0.0035%
0x13	13.56	397.76	0.0056%
0x14	14.318	400.90904	0.0023%
0x15	16.0	400	-
0x16	16.384	404.1386667	0.010%

### 26.8.2 PIOSC Specifications

**Table 26-9. PIOSC Clock Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>PIOSC25</sub>	Internal 16-MHz precision oscillator frequency variance, factory calibrated at 25 °C	-	±0.25%	±1%	-
F <sub>PIOSCT</sub>	Internal 16-MHz precision oscillator frequency variance, factory calibrated at 25 °C, across specified temperature range	-	-	±3%	-
F <sub>PIOSCUCAL</sub>	Internal 16-MHz precision oscillator frequency variance, user calibrated at a chosen temperature	-	±0.25%	±1%	-

#### 26.8.3 Internal 30-kHz Oscillator Specifications

Table 26-10. 30-kHz Clock Characteristics

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>IOSC30KHZ</sub>	Internal 30-KHz oscillator frequency	15	30	45	KHz

### 26.8.4 Main Oscillator Specifications

**Table 26-11. Main Oscillator Clock Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>MOSC</sub>	Main oscillator frequency	1	-	16.384	MHz
T <sub>MOSC_PER</sub>	Main oscillator period	61	-	1000	ns
T <sub>MOSC_SETTLE</sub>	Main oscillator settling time <sup>a</sup>	17.5	-	20	ms
F <sub>REF_XTAL_BYPASS</sub>	Crystal reference using the main oscillator (PLL in BYPASS mode) <sup>b</sup>	1	-	16.384	MHz
F <sub>REF_EXT_BYPASS</sub>	External clock reference (PLL in BYPASS mode) <sup>b</sup>	0	-	50	MHz
DC <sub>MOSC_EXT</sub>	External clock reference duty cycle	45	-	55	%

a. This parameter is highly sensitive to PCB layout and trace lengths, which may make this parameter time longer. Care must be taken in PCB design to minimize trace lengths and RLC (resistance, inductance, capacitance).

Table 26-12. Supported MOSC Crystal Frequencies<sup>a</sup>

Crystal Frequency (MHz) Not Using the PLL	Crystal Frequency (MHz) Using the PLL						
1.000 MHz	reserved						
1.8432 MHz	reserved						
2.000 MHz	reserved						
2.4576 MHz	reserved						
3.57954	45 MHz						
3.6864	4 MHz						
4 MHz	(USB)						
4.096	MHz						
4.9152	2 MHz						
5 MHz	(USB)						
5.12	MHz						
6 MHz (reset	value)(USB)						
6.144	MHz						
7.372	8 MHz						
8 MHz	(USB)						
8.192	MHz						
10.0 MH	Iz (USB)						
12.0 MH	Iz (USB)						
12.28	B MHz						
13.56	13.56 MHz						
14.318	18 MHz						
16.0 MH	16.0 MHz (USB)						
16.384	4 MHz						

a. Frequencies that may be used with the USB interface are indicated in the table.

b. If the ADC is used, the crystal reference must be 16 MHz  $\pm$  .03% when the PLL is bypassed.

#### 26.8.5 System Clock Specification with ADC Operation

Table 26-13. System Clock Characteristics with ADC Operation

Parameter	Parameter Name	Min	Nom	Max	Unit
Joysauc	System clock frequency when the ADC module is operating (when PLL is bypassed). <sup>a</sup>	15.9952	16	16.0048	MHz

a. Clock frequency (plus jitter) must be stable inside specified range. ADC can be clocked from the PLL or directly from an external clock source, as long as frequency absolute precision is inside specified range.

#### 26.8.6 System Clock Specification with USB Operation

Table 26-14. System Clock Characteristics with USB Operation

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>sysusb</sub>	System clock frequency when the USB module is operating (note that MOSC must be the clock source, either with or without using the PLL)	30	-	-	MHz

### 26.9 Sleep Modes

Table 26-15. Sleep Modes AC Characteristics<sup>a</sup>

Parameter No	Parameter	Parameter Name	Min	Nom	Max	Unit
D1	T <sub>WAKE_S</sub>	Time to wake from interrupt in sleep mode, not using the PLL <sup>b</sup>	-	-	2	system clocks
	T <sub>WAKE_DS</sub>	Time to wake from interrupt deep-sleep mode, not using the PLL <sup>b</sup>	-	-	7	system clocks
D2	T <sub>WAKE_PLL_S</sub>	Time to wake from interrupt in sleep or deep-sleep mode when using the PLL <sup>b</sup>	-	-	T <sub>READY</sub>	ms
D3	T <sub>ENTER_DS</sub>	Time to enter deep-sleep mode from sleep request	-	0	35 <sup>c</sup>	ms

a. Values in this table assume the IOSC is the clock source during sleep or deep-sleep mode.

### 26.10 Flash Memory

**Table 26-16. Flash Memory Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
PE <sub>CYC</sub>	Number of guaranteed program/erase cycles before failure <sup>a</sup>	15,000	-	-	cycles
T <sub>RET</sub>	Data retention, -40°C to +85°C	10	-	-	years
T <sub>PROG</sub>	Word program time	-	-	1	ms
T <sub>BPROG</sub>	Buffer program time	-	-	1	ms
T <sub>ERASE</sub>	Page erase time	-	-	12	ms
T <sub>ME</sub>	Mass erase time	-	-	16	ms

a. A program/erase cycle is defined as switching the bits from 1-> 0 -> 1.

b. Specified from registering the interrupt to first instruction.

c. Nominal specification occurs 99.9995% of the time.

### 26.11 Input/Output Characteristics

**Note:** All GPIO signals are 5-V tolerant when configured as inputs except for PB0 and PB1, which are limited to 3.6 V. See "Signal Description" on page 407 for more information on GPIO configuration.

Table 26-17. GPIO Module Characteristics<sup>a</sup>

Parameter	Parameter Name	Min	Nom	Max	Unit
R <sub>GPIOPU</sub>	GPIO internal pull-up resistor	100	-	300	kΩ
R <sub>GPIOPD</sub>	GPIO internal pull-down resistor	200	-	500	kΩ
I <sub>LKG</sub>	GPIO input leakage current <sup>b</sup>	-	-	2	μΑ
	GPIO rise time, 2-mA drive <sup>c</sup>		14	20	ns
т	GPIO rise time, 4-mA drive <sup>c</sup>		7	10	ns
T <sub>GPIOR</sub>	GPIO rise time, 8-mA drive <sup>c</sup>	_	4	5	ns
	GPIO rise time, 8-mA drive with slew rate control <sup>c</sup>		6	8	ns
	GPIO fall time, 2-mA drive <sup>d</sup>		14	21	ns
_	GPIO fall time, 4-mA drive <sup>d</sup>		7	11	ns
T <sub>GPIOF</sub>	GPIO fall time, 8-mA drive <sup>d</sup>	] -	4	6	ns
	GPIO fall time, 8-mA drive with slew rate control <sup>d</sup>		6	8	ns

a.  $\ensuremath{V_{DD}}$  must be within the range specified in Table 26-2 on page 1317.

### 26.12 External Peripheral Interface (EPI)

When the EPI module is in SDRAM mode, the drive strength must be configured to 8 mA. Table 26-18 on page 1326 shows the rise and fall times in SDRAM mode with 16 pF load conditions. When the EPI module is in Host-Bus or General-Purpose mode, the values in "Input/Output Characteristics" on page 1326 should be used.

Table 26-18. EPI SDRAM Characteristics

Parameter	Parameter Name	Condition	Min	Nom	Max	Unit
T <sub>SDRAMR</sub>	EPI Rise Time (from 20% to 80% of $V_{DD}$ )	8-mA drive, C <sub>L</sub> = 16 pF	-	2	3	ns
T <sub>SDRAMF</sub>	EPI Fall Time (from 80% to 20% of V <sub>DD</sub> )	8-mA drive, $C_L = 16 pF$	-	2	3	ns

Table 26-19. EPI SDRAM Interface Characteristics<sup>a</sup>

Parameter No	Parameter	Parameter Name	Min	Nom	Max	Unit
E1	T <sub>CK</sub>	SDRAM Clock period	20	-	-	ns
E2	T <sub>CH</sub>	SDRAM Clock high time	10	-	-	ns
E3	T <sub>CL</sub>	SDRAM Clock low time	10	-	-	ns
E4	T <sub>COV</sub>	CLK to output valid	-5	-	5	ns
E5	T <sub>COI</sub>	CLK to output invalid	-5	-	5	ns
E6	T <sub>COT</sub>	CLK to output tristate	-5	-	5	ns

b. The leakage current is measured with GND or V<sub>DD</sub> applied to the corresponding pin(s). The leakage of digital port pins is measured individually. The port pin is configured as an input and the pullup/pulldown resistor is disabled.

c. Time measured from 20% to 80% of  $V_{DD}$ .

d. Time measured from 80% to 20% of  $V_{DD}$ .

Table 26-19. EPI SDRAM Interface Characteristics (continued)

Parameter No	Parameter	Parameter Name	Min	Nom	Max	Unit
E7	T <sub>S</sub>	Input set up to CLK	10	-	-	ns
E8	T <sub>H</sub>	CLK to input hold	0	-	-	ns
E9	T <sub>PU</sub>	Power-up time	100	-	-	μs
E10	T <sub>RP</sub>	Precharge all banks	20	-	-	ns
E11	T <sub>RFC</sub>	Auto refresh	66	-	-	ns
E12	T <sub>MRD</sub>	Program mode register	40	-	1	ns

a. The EPI SDRAM interface must use 8-mA drive.

Figure 26-11. SDRAM Initialization and Load Mode Register Timing





Figure 26-12. SDRAM Read Timing








Table 26-20. EPI Host-Bus 8 and Host-Bus 16 Interface Characteristics

Parameter No	Parameter	Parameter Name	Min	Nom	Max	Unit
E14	T <sub>ISU</sub>	Read data set up time	10	-	-	ns
E15	T <sub>IH</sub>	Read data hold time	0	-	-	ns
E16	T <sub>DV</sub>	WEn to write data valid	-	-	5	ns
E17	T <sub>DI</sub>	Data hold from WEn invalid	2	-	-	EPI Clocks
E18	T <sub>OV</sub>	CSn to output valid	-5	-	5	ns
E19	T <sub>OINV</sub>	CSn to output invalid	-5	-	5	ns
E20	T <sub>STLOW</sub>	WEn / RDn strobe width low	2	-	-	EPI Clocks
E21	T <sub>FIFO</sub>	FEMPTY and FFULL setup time to clock edge	2	-	-	System Clocks
E22	T <sub>ALEHIGH</sub>	ALE width high	-	1	-	EPI Clocks
E23	T <sub>CSLOW</sub>	CSn width low	4	-	-	EPI Clocks
E24	T <sub>ALEST</sub>	ALE rising to WEn / RDn strobe falling	2	-	-	EPI Clocks
E25	T <sub>ALEADD</sub>	ALE falling to ADn tristate	1	-	-	EPI Clocks





Figure 26-14. Host-Bus 8/16 Mode Read Timing

Figure 26-15. Host-Bus 8/16 Mode Write Timing



<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.

<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.





Figure 26-16. Host-Bus 8/16 Mode Muxed Read Timing

Figure 26-17. Host-Bus 8/16 Mode Muxed Write Timing



<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.

Table 26-21. EPI General-Purpose Interface Characteristics

Parameter No	Parameter	Parameter Name	Min	Nom	Max	Unit
E25	T <sub>CK</sub>	General-Purpose Clock period	20	-	-	ns
E26	T <sub>CH</sub>	General-Purpose Clock high time	10	-	-	ns
E27	T <sub>CL</sub>	General-Purpose Clock low time	10	-	-	ns
E28	T <sub>ISU</sub>	Input signal set up time to rising clock edge	10	-	-	ns
E29	T <sub>IH</sub>	Input signal hold time from rising clock edge	0	-	-	ns
E30	$T_DV$	Falling clock edge to output valid	-5	-	5	ns
E31	T <sub>DI</sub>	Falling clock edge to output invalid	-5	-	5	ns
E32	T <sub>RDYSU</sub>	iRDY assertion or deassertion set up time to falling clock edge	10	-	-	ns

<sup>&</sup>lt;sup>a</sup> BSEL0n and BSEL1n are available in Host-Bus 16 mode only.





Figure 26-18. General-Purpose Mode Read and Write Timing

The above figure illustrates accesses where the FRM50 bit is clear, the FRMCNT field is 0x0, the RD2CYC bit is clear, and the WR2CYC bit is clear.





## 26.13 Analog-to-Digital Converter (ADC)

Table 26-22. ADC Characteristics<sup>a</sup>

Parameter	Parameter Name	Min	Nom	Max	Unit
V <sub>ADCIN</sub>	Maximum single-ended, full-scale analog input voltage, using internal reference	-	-	3.0	V
	Maximum single-ended, full-scale analog input voltage, using external reference	-	-	V <sub>REFA</sub>	V
	Minimum single-ended, full-scale analog input voltage	0.0	-	-	V
	Maximum differential, full-scale analog input voltage, using internal reference	-	-	1.5	V
	Maximum differential, full-scale analog input voltage, using external reference	-	-	V <sub>REFA</sub> /2	V
	Minimum differential, full-scale analog input voltage	0.0	-	-	V
N	Resolution	12			bits
F <sub>ADC</sub>	ADC internal clock frequency <sup>b</sup>	15.9952	16	16.0048	MHz
T <sub>ADCCONV</sub>	Conversion time <sup>c</sup>	1			μs
F <sub>ADCCONV</sub>	Conversion rate <sup>c</sup>	1000			k samples/s
T <sub>ADCSAMP</sub>	Sample time	125	-	-	ns
T <sub>LT</sub>	Latency from trigger to start of conversion	-	2	-	system clocks
ΙL	ADC input leakage	-	-	2.0	μΑ
R <sub>ADC</sub>	ADC equivalent resistance	-	-	10	kΩ
C <sub>ADC</sub>	ADC equivalent capacitance	0.9	1.0	1.1	pF
E <sub>L</sub>	Integral nonlinearity (INL) error, 12-bit mode	-	-	±8	LSB
	Integral nonlinearity (INL) error, 10-bit mode	-	-	±2	LSB
E <sub>D</sub>	Differential nonlinearity (DNL) error, 12-bit mode	-	-	±4	LSB
	Differential nonlinearity (DNL) error, 10-bit mode	-	-	±2	LSB
E <sub>O</sub>	Offset error, 12-bit mode	-	-	±40	LSB
	Offset error, 10-bit mode	-	-	±10	LSB
E <sub>G</sub>	Full-scale gain error, 12-bit mode	-	-	±100	LSB
	Full-scale gain error, 10-bit mode	-	-	±25	LSB
E <sub>TS</sub>	Temperature sensor accuracy <sup>d</sup>	-	-	±5	°C

a. The ADC reference voltage is 3.0 V. This reference voltage is internally generated from the 3.3 VDDA supply by a band gap circuit.

b. The ADC must be clocked from the PLL or directly from an external clock source to operate properly.

c. The conversion time and rate scale from the specified number if the ADC internal clock frequency is any value other than 16 MHz.

d. Note that this parameter does not include ADC error.




Figure 26-20. ADC Input Equivalency Diagram

Table 26-23. ADC Module External Reference Characteristics<sup>a</sup>

Parameter	Parameter Name	Min	Nom	Max	Unit
V	External voltage reference for ADC, when the VREF field in the <b>ADCCTL</b> register is $0x1^{b}$	2.97	-	3.03	V
V <sub>REFA</sub>	External voltage reference for ADC, when the <code>VREF</code> field in the <code>ADCCTL</code> register is $0x3^{\text{c}}$	0.99	-	1.01	V
ال	External voltage reference leakage current	-	-	2.0	μΑ

a. Care must be taken to supply a reference voltage of acceptable quality.

**Table 26-24. ADC Module Internal Reference Characteristics** 

Parameter Parameter Name		Min	Nom	Max	Unit
$V_{REFI}$	Internal voltage reference for ADC	-	3.0	-	V

# 26.14 Synchronous Serial Interface (SSI)

Table 26-25. SSI Characteristics

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
S1	T <sub>CLK_PER</sub>	SSIC1k cycle time <sup>a</sup>	40	-	-	ns
S2	T <sub>CLK_HIGH</sub>	SSIC1k high time	-	0.5	-	t clk_per
S3	T <sub>CLK_LOW</sub>	SSIC1k low time	-	0.5	-	t clk_per
S4	T <sub>CLKRF</sub>	SSIClk rise/fall time <sup>b</sup>	-	4	6	ns
S5	T <sub>DMD</sub>	Data from master valid delay time	0	-	1	system clocks
S6	T <sub>DMS</sub>	Data from master setup time	1	-	-	system clocks
S7	T <sub>DMH</sub>	Data from master hold time	2	-	-	system clocks

b. Ground is always used as the reference level for the minimum conversion value.

c. Ground is always used as the reference level for the minimum conversion value.

Table 26-25. SSI Characteristics (continued)

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
S8	T <sub>DSS</sub>	Data from slave setup time	1	-	-	system clocks
S9	T <sub>DSH</sub>	Data from slave hold time	2	-	-	system clocks

a. In master mode, the system clock must be at least twice as fast as the SSIClk; in slave mode, the system clock must be at least 12 times faster than the SSIClk.

Figure 26-21. SSI Timing for TI Frame Format (FRF=01), Single Transfer Timing Measurement





Figure 26-22. SSI Timing for MICROWIRE Frame Format (FRF=10), Single Transfer



b. Note that the delays shown are using 8-mA drive strength.




Figure 26-23. SSI Timing for SPI Frame Format (FRF=00), with SPH=1

## 26.15 Inter-Integrated Circuit (I<sup>2</sup>C) Interface

Table 26-26, I<sup>2</sup>C Characteristics


Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
I1 <sup>a</sup>	T <sub>SCH</sub>	Start condition hold time	36	-	-	system clocks
I2 <sup>a</sup>	T <sub>LP</sub>	Clock Low period	36	-	-	system clocks
I3 <sup>b</sup>	T <sub>SRT</sub>	I2CSCL/I2CSDA rise time (V $_{IL}$ =0.5 V to V $_{IH}$ =2.4 V)	-	-	(see note b)	ns
I4 <sup>a</sup>	T <sub>DH</sub>	Data hold time	2	-	-	system clocks
I5 <sup>c</sup>	T <sub>SFT</sub>	I2CSCL/I2CSDA fall time (V $_{IH}$ =2.4 V to V $_{IL}$ =0.5 V)	-	9	10	ns
I6 <sup>a</sup>	T <sub>HT</sub>	Clock High time	24	-	-	system clocks
I7 <sup>a</sup>	T <sub>DS</sub>	Data setup time	18	-	-	system clocks
I8 <sup>a</sup>	T <sub>SCSR</sub>	Start condition setup time (for repeated start condition only)	36	-	-	system clocks
I9 <sup>a</sup>	T <sub>SCS</sub>	Stop condition setup time	24	-	-	system clocks

a. Values depend on the value programmed into the TPR bit in the I<sup>2</sup>C Master Timer Period (I2CMTPR) register; a TPR programmed for the maximum I2CSCL frequency (TPR=0x2) results in a minimum output timing as shown in the table above. The I<sup>2</sup>C interface is designed to scale the actual data transition time to move it to the middle of the I2CSCL Low period. The actual position is affected by the value programmed into the TPR; however, the numbers given in the above values are minimum values.

b. Because I2CSCL and I2CSDA operate as open-drain-type signals, which the controller can only actively drive Low, the time I2CSCL or I2CSDA takes to reach a high level depends on external signal capacitance and pull-up resistor values.

c. Specified at a nominal 50 pF load.

Figure 26-24. I<sup>2</sup>C Timing



# 26.16 Inter-Integrated Circuit Sound (I<sup>2</sup>S) Interface

Table 26-27. I<sup>2</sup>S Master Clock (Receive and Transmit)

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
M1	T <sub>MCLK_PER</sub>	Cycle time	20.3	-	-	ns
M2	T <sub>MCLKRF</sub>	Rise/fall time	See "Input/Output Characteristics" on page 1326.		ns	
M3	T <sub>MCLK_HIGH</sub>	High time	10	-	-	ns
M4	T <sub>MCLK_LOW</sub>	Low time	10	-	-	ns
M5	T <sub>MDC</sub>	Duty cycle	48	-	52	%
M6	T <sub>MJITTER</sub>	Jitter	-	-	2.5	ns

Table 26-28. I<sup>2</sup>S Slave Clock (Receive and Transmit)

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
M7	T <sub>SCLK_PER</sub>	Cycle time	80	-	-	ns
M8	T <sub>SCLK_HIGH</sub>	High time	40	-	-	ns
M9	T <sub>SCLK_LOW</sub>	Low time	40	-	-	ns
M10	T <sub>SDC</sub>	Duty cycle	-	50	-	%

Table 26-29. I<sup>2</sup>S Master Mode

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
M11	T <sub>MSWS</sub>	SCK fall to WS valid	-	-	10	ns
M12	T <sub>MSD</sub>	SCK fall to TXSD valid	-	-	10	ns
M13	T <sub>MSDS</sub>	RXSD setup time to SCK rise	10	-	-	ns
M14	T <sub>MSDH</sub>	RXSD hold time from SCK rise	10	-	-	ns

Figure 26-25. I<sup>2</sup>S Master Mode Transmit Timing




Figure 26-26. I<sup>2</sup>S Master Mode Receive Timing




Table 26-30. I<sup>2</sup>S Slave Mode

Parameter No.	Parameter	Parameter Name	Min	Nom	Max	Unit
M15	T <sub>SCLK_PER</sub>	Cycle time	80	-	-	ns
M16	T <sub>SCLK_HIGH</sub>	High time	40	-	-	ns
M17	T <sub>SCLK_LOW</sub>	Low time	40	-	-	ns
M18	T <sub>SDC</sub>	Duty cycle	-	50	-	%
M19	T <sub>SSETUP</sub>	WS setup time to SCK rise	-	-	25	ns
M20	T <sub>SHOLD</sub>	WS hold time from SCK rise	-	-	10	ns
M21	T <sub>SSD</sub>	SCK fall to TXSD valid	-	-	20	ns
M22	T <sub>SLSD</sub>	Left-justified mode, WS to TXSD	-	-	20	ns
M23	T <sub>SSDS</sub>	RXSD setup time to SCK rise	10	-	-	ns
M24	T <sub>SSDH</sub>	RXSD hold time from SCK rise	10	-	-	ns

Figure 26-27. I<sup>2</sup>S Slave Mode Transmit Timing





Figure 26-28. I<sup>2</sup>S Slave Mode Receive Timing



### 26.17 Ethernet Controller

**Table 26-31. Ethernet Controller DC Characteristics** 

Parameter	Parameter Name	Value	Unit
R <sub>EBIAS</sub>	Value of the pull-down resistor on the ERBIAS pin	12.4K ± 1 %	Ω

Table 26-32. 100BASE-TX Transmitter Characteristics<sup>a</sup>

Parameter Name	Min	Nom	Max	Unit
Peak output amplitude	950	-	1050	mVpk
Output amplitude symmetry	98	-	102	%
Output overshoot	-	-	5	%
Rise/Fall time	3	-	5	ns
Rise/Fall time imbalance	-	-	500	ps
Duty cycle distortion	-	-	±250	ps
Jitter	-	-	1.4	ns

a. Measured at the line side of the transformer.

Table 26-33. 100BASE-TX Transmitter Characteristics (informative)<sup>a</sup>

Parameter Name	Min	Nom	Max	Unit
Return loss	16	-	-	dB
Open-circuit inductance	350	-	-	μH

a. The specifications in this table are included for information only. They are mainly a function of the external transformer and termination resistors used for measurements.

Table 26-34. 100BASE-TX Receiver Characteristics

Parameter Name	Min	Nom	Max	Unit
Signal detect assertion threshold	600	700	-	mVppd
Signal detect de-assertion threshold	350	425	-	mVppd
Differential input resistance	-	3.6	-	kΩ
Jitter tolerance (pk-pk)	4	-	-	ns
Baseline wander tracking	-80	-	+80	%
Signal detect assertion time	-	-	1000	μs
Signal detect de-assertion time	-	-	4	μs

Table 26-35. 10BASE-T Transmitter Characteristics<sup>a</sup>

Parameter Name	Min	Nom	Max	Unit
Peak differential output signal	2.2	-	2.7	V
Harmonic content	27	-	-	dB
Link pulse width	-	100	-	ns
Start-of-idle pulse width, Last bit 0	-	300	-	ns
Start-of-idle pulse width, Last bit 1	-	350	-	ns

a. The Manchester-encoded data pulses, the link pulse and the start-of-idle pulse are tested against the templates and using the procedures found in Clause 14 of *IEEE 802.3*.

Table 26-36. 10BASE-T Transmitter Characteristics (informative)<sup>a</sup>

Parameter Name	Min	Nom	Max	Unit
Output return loss	15	-	-	dB
Output impedance balance	29-17log(f/10)	-	-	dB
Peak common-mode output voltage	-	-	50	mV
Common-mode rejection	-	-	100	mV

Table 26-36. 10BASE-T Transmitter Characteristics (informative) (continued)

Parameter Name	Min	Nom	Max	Unit
Common-mode rejection jitter	-	-	1	ns

a. The specifications in this table are included for information only. They are mainly a function of the external transformer and termination resistors used for measurements.

Table 26-37, 10BASE-T Receiver Characteristics

Parameter Name	Min	Nom	Max	Unit
Jitter tolerance (pk-pk)	30	26	-	ns
Input squelched threshold	340	440	540	mVppd
Differential input resistance	-	3.6	-	kΩ
Common-mode rejection	25	-	-	V

Table 26-38. Isolation Transformers<sup>a</sup>

Name	Value	Condition
Turns ratio	1 CT : 1 CT	+/- 5%
Open-circuit inductance	350 uH (min)	@ 10 mV, 10 kHz
Leakage inductance	0.40 uH (max)	@ 1 MHz (min)
Inter-winding capacitance	25 pF (max)	
DC resistance	0.9 Ohm (max)	
Insertion loss	0.4 dB (typ)	0-65 MHz
HIPOT	1500	Vrms

a. Two simple 1:1 isolation transformers are required at the line interface. Transformers with integrated common-mode chokes are recommended for exceeding FCC requirements. This table gives the recommended line transformer characteristics.

Note: The 100Base-TX amplitude specifications assume a transformer loss of 0.4 dB.

Table 26-39. Ethernet Reference Crystal

Parameter	Parameter Name	Min	Nom	Max	Unit
F <sub>XTALPHYOSC</sub>	Ethernet PHY oscillator frequency	-	25	-	MHz
TOL <sub>XTALPHYOSC</sub>	Ethernet PHY oscillator frequency tolerance <sup>a</sup>	-	±50	-	PPM
MODE <sub>XTALPHYOSC</sub>	Ethernet PHY oscillation mode	Parallel resonance, fundamental mode		-	

a. This tolerance provides a guard band for temperature stability and aging drift.

T<sub>clkper</sub>

Figure 26-29. External XTLP Oscillator Characteristics

Table 26-40. External XTLP Oscillator Characteristics

Parameter	Parameter Name	Min	Nom	Max	Unit
XTLN <sub>ILV</sub>	XTLN Input Low Voltage	-	-	0.8	-
XTLP <sub>F</sub>	XTLP Frequency <sup>a</sup>	-	25.0	-	-
T <sub>CLKPER</sub>	XTLP Period <sup>a</sup>	-	40	-	-
XTLP <sub>DC</sub>	XTLP Duty Cycle	40	-	60	%
		40		60	
$T_R$ , $T_F$	Rise/Fall Time	-	-	4.0	ns
T <sub>JITTER</sub>	Absolute Jitter	-	-	0.1	ns

a. IEEE 802.3 frequency tolerance ±50 ppm.

## 26.18 Universal Serial Bus (USB) Controller

The Stellaris<sup>®</sup> USB controller electrical specifications are compliant with the *Universal Serial Bus Specification Rev. 2.0* (full-speed and low-speed support) and the *On-The-Go Supplement to the USB 2.0 Specification Rev. 1.0*. Some components of the USB system are integrated within the LM3S9D96 microcontroller and specific to the Stellaris microcontroller design. An external component resistor is needed as specified in Table 26-41.

**Table 26-41. USB Controller Characteristics** 

Parameter	Parameter Name	Value	Unit
R <sub>UBIAS</sub>	Value of the pull-down resistor on the USBORBIAS pin	9.1K ± 1 %	Ω

## 26.19 Analog Comparator

**Table 26-42. Analog Comparator Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
$V_{\rm INP}, V_{\rm INN}$	Input voltage range	GND	-	$V_{DD}$	V
V <sub>CM</sub>	Input common mode voltage range	GND	-	V <sub>DD</sub> -1.5	V
V <sub>OS</sub>	Input offset voltage	-	±10	±25	mV

Table 26-42. Analog Comparator Characteristics (continued)

Parameter	Parameter Name	Min	Nom	Max	Unit
C <sub>MRR</sub>	Common mode rejection ratio	50	-	-	dB
T <sub>RT</sub>	Response time	-	-	1.0	μs
T <sub>MC</sub>	Comparator mode change to Output Valid	-	-	10	μs

**Table 26-43. Analog Comparator Voltage Reference Characteristics** 

Parameter	Parameter Name	Min	Nom	Max	Unit
R <sub>HR</sub>	Resolution in high range	-	V <sub>DDA</sub> /31	-	V
R <sub>LR</sub>	Resolution in low range	-	V <sub>DDA</sub> /23	-	V
A <sub>HR</sub>	Absolute accuracy high range	-	-	±R <sub>HR</sub> /2	V
A <sub>LR</sub>	Absolute accuracy low range	-	-	±R <sub>LR</sub> /4	V

### 26.20 Current Consumption

This section provides information on typical and maximum power consumption under various conditions. Unless otherwise indicated, current consumption numbers include use of the on-chip LDO regulator and therefore include  $I_{DDC}$ .

#### 26.20.1 Nominal Power Consumption

The following table provides nominal figures for current consumption.

**Table 26-44. Nominal Power Consumption** 

Parameter	Parameter Name	Conditions	Nom	Unit
I <sub>DD_RUN</sub>	Run mode 1 (Flash loop)	V <sub>DD</sub> = 3.3 V	101 <sup>a</sup>	mA
		Code= while(1){} executed out of Flash	159 <sup>b</sup>	
		Peripherals = All ON		
		System Clock = 80 MHz (with PLL)		
		Temp = 25°C		
I <sub>DD_SLEEP</sub>	Sleep mode	V <sub>DD</sub> = 3.3 V	20	mA
		Peripherals = All clock gated		
		System Clock = 80 MHz (with PLL)		
		Temp = 25°C		
I <sub>DD_DEEPSLEEP</sub>	Deep-sleep mode	Peripherals = All OFF	550	μΑ
		System Clock = IOSC30KHZ/64 Temp = 25°C		

a. Ethernet MAC and PHY powered down by software.

#### 26.20.2 Maximum Current Consumption

The current measurements specified in the table that follows are maximum values under the following conditions:

b. Auto-negotiate enabled. If an Ethernet cable is attached to the connector, the consumption increases by 7-10 mA.

- V<sub>DDA</sub> = 3.6 V
- Temperature = 25°C
- Clock source (MOSC) = 16.348-MHz crystal oscillator

#### **Table 26-45. Detailed Current Specifications**

Parameter	Parameter Name	Conditions	Max	Unit
I <sub>DD_RUN</sub>	Run mode 1 (Flash loop)	V <sub>DD</sub> = 3.6 V	210 <sup>a</sup>	mA
		Code= while(1){} executed out of Flash	138 <sup>b</sup>	
		Peripherals = All ON		
		System Clock = 80 MHz (with PLL)		
		Temperature = 85°C		
I <sub>DD_SLEEP</sub>	Sleep mode	V <sub>DD</sub> = 3.6 V	46	mA
		Peripherals = All Clock Gated		
		System Clock = 80 MHz (with PLL)		
		Temperature = 85°C		
I <sub>DD_DEEPSLEEP</sub>	Deep-Sleep mode	V <sub>DD</sub> = 3.6 V	1.8	mA
		Peripherals = All Clock Gated		
		System Clock = IOSC30/64		
		Temperature = 85°C		

a. Auto-negotiate enabled. If an Ethernet cable is attached to the connector, the consumption increases by 7-10 mA.

b. Ethernet MAC and PHY powered down by software.

# A Register Quick Reference

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
The Co	rtex-M3	Process	or												
	R/W, , reset														
ito, type i	vv, , reset	- (see page	, 10)				DA	λΤΑ							
								TA.							
R1, type I	R/W, , reset	- (see page	e 78)												
							DA	ATA .							
							DA	ATA .							
R2, type I	R/W, , reset	- (see page	e 78)												
								ATA							
							DA	ATA							
R3, type I	R/W, , reset	- (see page	e 78)												
								ATA ATA							
R4 type I	R/W, , reset	- (see page	78)				<i>DF</i>	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\							
··, type i	, , reset	(SCC paye	,				D.A	ιΤΑ							
								TA							
R5, type I	R/W, , reset	- (see page	e 78)												
							DA	λΤΑ							
							DA	λΤΑ							
R6, type I	R/W, , reset	- (see page	e 78)												
								ATA .							
							DA	ATA							
R7, type I	R/W, , reset	- (see page	e 78)												
								ATA ATA							
P8 type I	R/W, , reset	- (see page	78)				DF	NIA							
ito, type i	VV, , 16361	- (see page	, 10)				DA	λΤΑ							
								TA.							
R9, type I	R/W, , reset	- (see page	e 78)												
							DA	ATA .							
							DA	ATA .							
R10, type	R/W, , rese	t - (see pag	ge 78)												
								λΤΑ							
							DA	ATA							
R11, type	R/W, , rese	t - (see pag	je 78)					т.							
								TA TA							
R12, type	R/W, , rese	t - (see nac	ne 78)				DF-	u/1							
<u>.</u> , .ype	, , 1636	. Joe pag	,,				DA	ιΤΑ							
								TA.							
SP, type F	R/W, , reset	- (see page	e 79)												
							S	P							
							S	P							
LR, type I	R/W, , reset	0xFFFF.FF	FF (see pag	ge 80)											
								NK							
							LII	NK							
PC, type	R/W, , reset	- (see page	e 81)												
								C							
							Р	· ·							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
PSR, type	e R/W, , rese	t 0x0100.0	0000 (see pa	age 82)											
N	Z	С	V	Q	ICI	/ IT	THUMB								
		ICI	/ IT									ISRNUM			
PRIMASH	K, type R/W,	, reset 0x0	0000.0000 (	see page 86	6)										
															PRIMASK
FAULTMA	ASK, type R	/W, , reset	0x0000.000	00 (see pag	e 87)										
															FAULTMASK
BASEPR	I, type R/W,	, reset 0x0	000.0000 (s	see page 88	3)										
									BASEPRI						
CONTRO	L, type R/W	, , reset 0x	0000.0000	(see page 8	39)										
														ASP	TMPL
Cortex	-M3 Perip	herale													
	n Timer (		\ Pogist	ore											
	E000.E000		) Regist	815											
	type R/W, o		n rosot Ovi	2000 0004											
STOTKE,	type K/VV, O	IISEL UXU II	U, TESEL UAL												COUNT
													CLK SRC	INTEN	ENABLE
STRELO	AD, type R/V	V offeet ()	v014 rooot	0~0000 000	00								OLI\_OI\O	IIVILIV	LIVADEL
SIKELO	ND, type K/V	v, onset o	KU 14, 1656L		00						DEI	.OAD			
							REL				KEL	.UAD			
STOUDD	ENT, type R	NAC office	4.02040		0000		INLL	OAD							
SICURK	ENI, type K	wc, onse	UXU 10, 108	Set uxuuuu.	.0000						CLIB	RENT			
							CURI	DENIT			CUR	KENI			
• •							0011	VEIVI							
	-M3 Perip														
	Vectore		upt Cont	roller (N	VIC) Reg	jisters									
	E000.E000														
ENO, type	R/W, offset	t 0x100, re	set 0x0000	.0000											
								IT ·-							
							יוו	IT							
EN1, type	R/W, offset	t 0x104, re	set 0x0000	.0000											
								. <del>.</del>				INT			
							II	IT							
DIS0, typ	e R/W, offse	t 0x180, re	eset 0x0000	0.0000											
								IT -							
							II.	IT							
DIS1, typ	e R/W, offse	t 0x184, re	eset 0x0000	0.0000											
												INT			
							II.	IT							
PEND0, t	ype R/W, off	set 0x200,	reset 0x00	000.0000											
								IT -							
							IN.	IT							
PEND1, t	ype R/W, off	set 0x204,	reset 0x00	000.000											
												INT			
							IN.	IT							
	0 4 DAM	offeet Ov?	000 #0004 0	~^^^	1										
UNPEND	u, type R/vv,	Oliset UX2	ou, reset u	X0000.0000	,										
UNPEND	u, type ĸ/w,	Oliset UX2	ou, reset u	X0000.0000	,			IT IT							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
UNPEND1	1, type R/W	offset 0x2	284, reset 0	x0000.0000											
												INT			
							11	NT.							
ACTIVE0,	type RO, o	ffset 0x30	0, reset 0x0	000.0000											
							11	IT.							
							11	NT .							
ACTIVE1,	type RO, o	ffset 0x30	4, reset 0x0	000.0000											
												INT			
							11	NT .							
PRI0, type	e R/W, offse	et 0x400, re	eset 0x0000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI1, type	e R/W, offse	et 0x404, re	eset 0x0000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI2, type	e R/W, offse	et 0x408, re	eset 0x0000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI3, type	e R/W, offse	et 0x40C, r	eset 0x0000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI4, type	e R/W, offse	et 0x410, re	eset 0x0000	1.0000				I				1			
	INTD								INTC						
DDIE 6	INTB								INTA						
PRI5, type	e R/W, offse	et UX414, re	eset uxuuuu	1.0000				ı	INTO			I			
	INTD								INTC						
DDIE tun	e R/W, offse	+ 0×410 ×	2001 0×0000	10000					INIA						
PKIO, type	INTD	st UX410, 16	Set uxuuut	1.0000					INTC						
	INTB								INTA						
DRI7 type	e R/W, offse	ot 0v41C r	eset OvOOO	0000					IIVIA						
FIXI7, type	INTD	, UX410, I	eset uxuuut	1				I	INTC						
	INTB								INTA						
PRIS type	e R/W, offse	ot 0x420 re	set OxOOO	0000				<u> </u>							
, . , , , ,	INTD								INTC						
	INTB								INTA						
PRI9. type	e R/W, offse	et 0x424. re	eset 0x0000	0.0000				l							
-, 31	INTD	,							INTC						
	INTB								INTA						
PRI10, typ	pe R/W, offs	set 0x428,	reset 0x000	0.0000				l———							
	INTD								INTC						
	INTB								INTA						
PRI11, tyr	pe R/W, offs	et 0x42C,	reset 0x000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI12, typ	pe R/W, offs	set 0x430,	reset 0x000	0.0000											
	INTD								INTC						
	INTB								INTA						
PRI13, typ	pe R/W, offs	set 0x434,	reset 0x000	0.0000											
	INTD								INTC						
	INTB								INTA						

					1	1								1	1
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
SWTRIG,	type WO, o	ffset 0xF0	0, reset 0x0	0000.0000											
												IN.	TID		
Cortex	-M3 Peri	pherals													
	Contro		(SCB) Re	gisters											
	ype R/W, of		, reset 0x00	000.000											
													DISFOLD	DISWBUF	DISMCY
CPUID, ty	pe RO, offs	set 0xD00,	reset 0x412	2F.C230											
			IN	ЛР					V	AR			C	ON	
					PAR	TNO							RI	ΕV	
INTCTRL	, type R/W,	offset 0xD	04, reset 0x	0000.0000											
NMISET				UNPENDSV	PENDSTSET	PENDSTCLR		ISRPRE	ISRPEND					VECPEND	
	VECI	PEND		RETBASE								VECACT			
VTABLE.	type R/W, c		08, reset 0×												
,	.,,	BASE	, , , , , , ,						OFFSET						
		D/102	OFFSET						002.						
APINT tv	pe R/W, offs	set 0xD0C		.05 0000											
Ai iiti, ty	pe 1011, 011.	SEL OXDOO	, leset oxi P	.00.0000			VEC <sup>-</sup>	IKEY							
ENDIANESS						PRIGROUF		INLI					SYSPESPEO	VECTCLRACT	VECTRESE
	_, type R/W,	offeet Ovi	210, recet 0	×0000 0000		- NONOOI							OTOREGREG	VECTOBACT	VEOTREGE
STOCIKI	_, type K/vv,	onset uxi	Jiu, reset u	X0000.0000											
											OF (ONDEND		OI FERREER	OI FEDEVIT	
											SEVONPEND		SLEEPDEEP	SLEEPEXII	
CFGCTR	L, type R/W	, offset uxi	D14, reset u	X0000.0200	)										
						STRALIGN	BFHFNMIGN				DIV0	UNALIGNED		MAINPEND	BASETH
SYSPRI1	, type R/W,	offset 0xD	18, reset 0x	0000.0000								1			
									USAGE						
	BUS								MEM						
SYSPRI2	, type R/W,	offset 0xD	1C, reset 0	c0000.0000											
	SVC														
SYSPRI3	, type R/W,	offset 0xD	20, reset 0x	0000.0000											
	TICK								PENDSV						
									DEBUG						
SYSHND	CTRL, type	R/W, offse	t 0xD24, re	set 0x0000.	0000										
													USAGE	BUS	MEM
SVC	BUSP	MEMP	USAGEP	TICK	PNDSV		MON	SVCA				USGA		BUSA	MEMA
FAULTST	AT, type R/\	N1C, offse	t 0xD28, re	set 0x0000.	0000										
						DIV0	UNALIGN					NOCP	INVPC	INVSTAT	UNDEF
BFARV			BSTKE	BUSTKE	IMPRE	PRECISE	IBUS	MMARV			MSTKE	MUSTKE		DERR	IERR
HFAULTS	STAT, type R	W1C, offs	set 0xD2C,	reset 0x000	0.0000						_				
DBG	FORCED														
														VECT	
MMADDE	R, type R/W,	offset 0xE	)34, reset -												
							AD	DR							
								DR							
FAULTAD	DR, type R	/W. offset	0xD38. rese	ıt -											
	, ., po 10	., 5501	50,1000	-			ΔD	DR							
								DR							
							AD	<i>Σ</i> 1.							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	-M3 Perip	horale													
	y Protect		t (MPU) F	Reaiste	rs										
	E000.E000		- (		_										
MPUTYPE	≣, type RO,	offset 0xD9	90, reset 0x	0080.0000	ı										
											IRE	GION			
			DREC												SEPARATE
MPUCTR	L, type R/W,	offset 0xD	094, reset 0	×0000.000	0										
														HFNMIENA	FALADI F
MOUNTIN	DED time I	1/1A/ -ff4	0×D00 ===	-4 0×0000	0000								PRIVDEFEN	HENMIENA	ENABLE
MPUNUM	BER, type F	K/VV, OTTSET	UXD98, res	et uxuuuu.	0000										
														NUMBER	
MPUBAS	E, type R/W	offset 0x0	D9C. reset 0	)×0000.000	00										
	, yp= 1831		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				AD	DR							
					ADDR						VALID			REGION	
MPUBAS	E1, type R/V	V, offset 0x	cDA4, reset	0x0000.00	000										
							AD	DR							
					ADDR						VALID			REGION	
MPUBAS	E2, type R/V	V, offset 0x	cDAC, reset	0x0000.0	000										
							AD	DR							
					ADDR						VALID			REGION	
MPUBAS	E3, type R/V	V, offset 0x	DB4, reset	0x0000.00	000										
							AD	DR						===::	
					ADDR						VALID			REGION	
MPUALIF	R, type R/W,	offset UXL		X0000.000	0	AD					TEV			С	В
			XN	SD		AP					TEX	SIZE	S	C	B ENABLE
МРПАТТЕ	R1, type R/W	/ offset Ox			00							OIZE			LIVIBLE
071.11	., . <b>, ., po</b>	, 0001 0	XN			AP					TEX		s	С	В
			SF	RD								SIZE			ENABLE
MPUATTE	R2, type R/W	/, offset 0x	DB0, reset	0x0000.00	00										
			XN			AP					TEX		S	С	В
			SF	RD								SIZE			ENABLE
MPUATTE	R3, type R/W	, offset 0x	DB8, reset	0x0000.00	00										
			XN			AP					TEX		S	С	В
			SF	RD								SIZE			ENABLE
	Control 400F.E000														
DID0, typ	e RO, offset	0x000, res	set - (see pa	age 210)											
		VER									CL	ASS			
			MAJ	JOR							MIM	NOR			
PBORCTI	L, type R/W,	offset 0x0	30, reset 0x	k0000.0002	2 (see page	212)									
														BORIOR	
RIS, type	RO, offset (	)x050, rese	et 0x0000.00	000 (see pa	age 213)										
							MOSCPUPRIS	USBPLLLRIS	PLLLRIS					BORRIS	
IMC, type	R/W, offset	0x054, res	set 0x0000.0	0000 (see	page 215)										
									DILLING					DCD":	
							MOSCPUPIM	USBPLLLIM	PLLLIM					BORIM	

				1				1							
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
MISC, typ	e R/W1C, o	offset 0x058	, reset 0x0	000.0000 (s	see page 21	7)									
							MOSCPUPMIS	USBPLLLMIS	PLLLMIS					BORMIS	
RESC, typ	e R/W, offs	set 0x05C, r	reset - (see	page 219)											
			,												MOSCFAIL
										WDT1	SW	WDT0	BOR	POR	EXT
BCC tune	D/M offer	et 0x060, re:	001 0v079E	2AD1 (000	nogo 221)					WBIT	011	WBTO	BOIL	1 010	EXI
RCC, type	K/W, OIISE	et uxuou, re	Set uxu/oc	. `	page 221)		2011					ı	DIA (1.4D.I) (		
		DIMPDM		ACG		513	SDIV		USESYSDIV	000	USEPWMDIV		PWMDIV	IOOODIO	14000DIG
		PWRDN		BYPASS			XTAL			OSC	SRC			IOSCDIS	MOSCDIS
PLLCFG,	type RO, o	ffset 0x064,	, reset - (se	e page 226	)										
						F							R		
<b>GPIOHBC</b>	TL, type R	/W, offset 0:	x06C, rese	t 0x0000.00	000 (see pa	ge 227)									
							PORTJ	PORTH	PORTG	PORTF	PORTE	PORTD	PORTC	PORTB	PORTA
RCC2. tvn	e R/W. offs	set 0x070, r	eset 0x070	0.6810 (see	e page 229)										
USERCC2						DIV2			SYSDIV2LSB						
JOLI 1002		PWRDN2		BYPASS2	010					OSCSRC2					
MODOOTI			70		. /	000)				00001102					
MOSCCII	∟, type κ/w	, offset 0x0	76, reset t	)XUUUU.UUU(	(see page	232)									
															CVAL
DSLPCLK	CFG, type	R/W, offset	0x144, res	set 0x0780.	0000 (see p	age 233)									
					DSDIV	ORIDE									
									ſ	DSOSCSRO					
PIOSCCA	L, type R/V	V, offset 0x1	150, reset (	0x0000.000	(see page	235)									
UTEN															
							UPDATE					UT			
I2SMCI K	CEG type I	R/W, offset	0x170 res	et OxOOOO O	000 (see na	ane 236)									
RXEN	o. o, type .	levi, onoci	OX 17 0, 100	ot 0x0000.0	ooo (see pe		XI						D	XF	
TXEN							XI							XF	
						'	^1						1.	ΛΓ	
DID1, type		t 0x004, res	set - (see pa	age 238)											
	VI	ER			FA	AM					PAR	TNO			
	PINCOUNT	Г							TEMP		Pł	(G	ROHS	QL	IAL
DC0, type	RO, offset	0x008, res	et 0x017F.0	OFF (see p	age 240)										
							SRA	MSZ							
							FLAS	SHSZ							
DC1, type	RO, offset	0x010, res	et - (see pa	ige 241)											
			WDT1			CAN1	CAN0				PWM			ADC1	ADC0
	MINS	YSDIV		MAXAD	C1SPD		COSPD	MPU		TEMPSNS	PLL	WDT0	SWO	SWD	JTAG
DC2, type		0x014, res	et 0x570F									I.			
, type	EPI0		1280	(000 pr	COMP2	COMP1	COMP0					TIMER3	TIMER2	TIMER1	TIMER0
					OCIVIF 2					0014	2010	IIIVILIN			
	I2C1		12C0			QEI1	QEI0			SSI1	SSI0		UART2	UART1	UART0
	RO, offset	0x018, res										1			
32KHZ		CCP5	CCP4	CCP3	CCP2	CCP1	CCP0	ADC0AIN7	ADC0AIN6	ADC0AIN5	ADC0AIN4	ADC0AIN3	ADC0AIN2	ADC0AIN1	ADC0AIN0
PWMFAULT	C2O	C2PLUS	C2MINUS	C10	C1PLUS	C1MINUS	C0O	C0PLUS	COMINUS	PWM5	PWM4	PWM3	PWM2	PWM1	PWM0
DC4, type	RO, offset	0x01C, res	et 0x5104.	F1FF (see p	age 249)										
	EPHY0		EMAC0				E1588						PICAL		
CCP7	CCP6	UDMA	ROM				GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
		0x020, res		00FF (see n	age 251)		1				1	I	I.		
	, 5.1000					PWMFAULT1	PWMFAI II TO			PWMEFLT	PWMESYNC				
				. TTIMI MULIS	. TTIMI AULIZ	. THE AULI	. TTIMI AULIU	D\A/\ 47	D\A/\ 40			D)A/A42	DIAMAG	DIA/NA4	D\A/840
								PWM7	PWM6	PWM5	PWM4	PWM3	PWM2	PWM1	PWM0

21	20	20	20	27	26	25	24	22	22	21	20	10	10	17	16
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20 4	19 3	18	17	16 0
		0x024, res			-	9	0		0	3	4		2	'	
БСС, туре	KO, onset	0.024, 165	et uxuuuu.t	<b>στο</b> (see ρ	age 233)										
											USB0PHY			LIS	B0
DC7 type	RO offset	0x028, res	et OxFFFF	FFFF (see r	nage 254)						0020				
Бол, сурс		DMACH29		· · · ·		DMACH25	DMACH24	DMACH23	DMACH22	DMACH21	DMACH20	DMACH19	DMACH18	DMACH17	DMACH16
DMACH15		DMACH13							DMACH6				DMACH2		
		0x02C, res				2112 10110	211210110	2.1.2.101.11	211210110	211210110	2.00.000	2.1	211210112	2	2.1.2.10
ADC1AIN15	ADC1AIN14	ADC1AIN13	ADC1AIN12	ADC1AIN11	ADC1AIN10	ADC1AIN9	ADC1AIN8	ADC1AIN7	ADC1AIN6	ADC1AIN5	ADC1AIN4	ADC1AIN3	ADC1AIN2	ADC1AIN1	ADC1AIN0
ADC0AIN15	ADC0AIN14	ADC0AIN13	ADC0AIN12	ADC0AIN11	ADC0AIN10	ADC0AIN9	ADC0AIN8	ADC0AIN7	ADC0AIN6	ADC0AIN5	ADC0AIN4	ADC0AIN3	ADC0AIN2	ADC0AIN1	ADC0AIN0
		0x190, res		l				1				1			
, ,,,,,	,				ugo 20 . /			ADC1DC7	ADC1DC6	ADC1DC5	ADC1DC4	ADC1DC3	ADC1DC2	ADC1DC1	ADC1DC0
									ADC0DC6				ADC0DC2		
NVMSTAT	type RO.	offset 0x1A	O reset Ox	0000.0011	see page 2	63)									
	, type ito,		lo, reset ex		occ page 2										
											TPSW				FWB
RCGC0 to	vne R/W of	ffset 0x100,	reset flyfir	1 1000040 (e4	e nage 264	)									
	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		WDT1		.c page 204	CAN1	CAN0				PWM			ADC1	ADC0
			WDIT	MAXAE	C1SPD	MAXAD					1 44141	WDT0		ADOT	ADOU
SCGC0 to	uno P/M of	ffset 0x110,	rosot OvOO	l								11010			
3000, 1	ype K/VV, OI	iset ox i io,	WDT1		e page 207	CAN1	CAN0				PWM			ADC1	ADC0
			WDII	MAYAE	C1SPD	MAXAD					FVVIVI	WDT0		ADCT	ADCO
DCCC0 4	ma D/M at	F4 0×420	0×00	L			COSFD					VVDTO			
טכטכט, ויַ	ype R/W, O	ffset 0x120,	1	1000040 (SE	e page 270		CANO				DIAMA			A D O 4	4000
			WDT1			CAN1	CAN0				PWM	WDTO		ADC1	ADC0
20004	D.011				070							WDT0			
RCGC1, ty		ffset 0x104,		1000000 (se			001100						TIMEDO	TIMED 4	TIMEDO
	EPI0		1280		COMP2	COMP1	COMP0			0014	0010	TIMER3	TIMER2	TIMER1	TIMER0
	I2C1		I2C0			QEI1	QEI0			SSI1	SSI0		UART2	UART1	UART0
SCGC1, ty		ffset 0x114,	1	1 <b>000000</b> (se				I				I	I	I	
	EPI0		1280		COMP2	COMP1	COMP0					TIMER3	TIMER2	TIMER1	TIMER0
	I2C1		I2C0			QEI1	QEI0			SSI1	SSI0		UART2	UART1	UART0
DCGC1, ty	ype R/W, of	ffset 0x124,	reset 0x00	000000 (se	e page 280										
	EPI0		1280		COMP2	COMP1	COMP0					TIMER3	TIMER2	TIMER1	TIMER0
	I2C1		12C0			QEI1	QEI0			SSI1	SSI0		UART2	UART1	UART0
RCGC2, ty	ype R/W, of	ffset 0x108,	reset 0x00	000000 (se	e page 284	•)									
	EPHY0		EMAC0												USB0
		UDMA					GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
SCGC2, ty	ype R/W, of	ffset 0x118,	reset 0x00	000000 (se	e page 287	)									
	EPHY0		EMAC0												USB0
		UDMA					GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
DCGC2, ty	ype R/W, of	ffset 0x128,	reset 0x00	000000 (se	e page 290	)									
	EPHY0		EMAC0												USB0
		UDMA					GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
SRCR0, ty	pe R/W, of	fset 0x040,	reset 0x00	000000 (se	e page 293	)									
			WDT1			CAN1	CAN0				PWM			ADC1	ADC0
												WDT0			
SRCR1, ty	pe R/W, of	fset 0x044,	reset 0x00	000000 (se	e page 295	)									
	EPI0		1280		COMP2	COMP1	COMP0					TIMER3	TIMER2	TIMER1	TIMER0
	I2C1		I2C0			QEI1	QEI0			SSI1	SSI0		UART2	UART1	UART0
SRCR2, tv	pe R/W, of	fset 0x048,	reset 0x00	000000 (se	e page 298	)	1			1	1		1	1	
	EPHY0		EMAC0	,											USB0
		UDMA					GPIOJ	GPIOH	GPIOG	GPIOF	GPIOE	GPIOD	GPIOC	GPIOB	GPIOA
							100		00			: .05	00	05	

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	I Memory														
	Memory F		s (Flash	Control	Offset)										
	400F.D000														
FMA, type	e R/W, offse	t 0x000, re	set 0x0000	.0000				1				1			
							055							OFFSET	
FMD from	e R/W, offse	4.02004 ==		0000			UFI	SET							
гию, туре	e K/VV, onse	t UXUU4, re	set uxuuuu	.0000			D	ATA							
								ATA							
FMC. type	e R/W, offse	t 0x008. re	set 0x0000	.0000											
, 31	, , , , , ,						WR	KEY							
												COMT	MERASE	ERASE	WRITE
FCRIS, ty	pe RO, offs	et 0x00C,	reset 0x000	0.0000											1
														PRIS	ARIS
FCIM, typ	e R/W, offse	et 0x010, r	eset 0x0000	0.0000											
														PMASK	AMASK
FCMISC,	type R/W1C	, offset 0x	014, reset 0	x0000.000	0										
														PMISC	AMISC
FMC2, typ	pe R/W, offs	et 0x020, ı	eset 0x000	0.0000											
							WR	KEY							WEBLIE
E14/E1/41	1 504														WRBUF
FWBVAL,	, type R/W, o	mset uxus	u, reset uxt	0000.0000			EW	/D[n]							
								/B[n] /B[n]							
FCTL. tvn	e R/W, offs	et 0x0F8. r	eset 0x000	0.0000				- J							
, . , ,															
														USDACK	USDREQ
FWBn, ty	pe R/W, offs	et 0x100 -	0x17C, res	et 0x0000.	0000										
							D/	ATA							
							D	ATA							
Interna	l Memory	,													
	y Registe		tem Con	trol Off	set)										
	400F.E000				·										
RMCTL, t	ype R/W1C,	offset 0x0	F0, reset -												
															BA
FMPRE0,	type R/W, o	ffset 0x13	0 and 0x20	0, reset 0x	FFFF.FFFF										
								ENABLE							
							READ_	ENABLE							
FMPPE0,	type R/W, o	ttset 0x13	4 and 0x400	), reset 0x	FFFF.FFFF		DDGG	ENIAD: E							
								ENABLE							
POOTOE	G tune D/M	offerst Com	100 #2226	vecer re	=		PRUG_	ENABLE							
NW	G, type R/W	, onset ux	וטט, reset 0	xFFFF.FF1	- =										
INVV	PORT			PIN		POL	EN							DBG1	DBG0
USFR PF	EG0, type R/	W. offset	)x1E0. rese		FFF	1 . 02	-14							2201	2200
NW	, .,pe iv	, 511361	, 1636	. • 1 1 1 1				DATA							
							יח	ATA							

24	20	20	20	07	26	25	24	22	22	24	20	10	40	17	10
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20	19	18	17	16 0
	EG1, type R								Ů					<u>'</u>	
NW		71, 011501	JX 12-1, 1000					DATA							
							DA	ATA							
USER_RI	EG2, type R	/W, offset (	0x1E8, rese	t 0xFFFF.F	FFF										
NW								DATA							
							DA	ATA							
USER_RI	EG3, type R	/W, offset (	0x1EC, rese	et 0xFFFF.F	FFF										
NW								DATA							
							DA	ATA							
FMPRE1,	type R/W, o	offset 0x20	4, reset 0xF	FFFF.FFFF											
								ENABLE							
							READ_I	ENABLE							
FMPRE2,	type R/W, o	offset 0x20	8, reset 0xF	FFFF.FFFF											
								ENABLE							
	Bass		0				READ_I	ENABLE							
FMPRE3,	type R/W, o	orrset 0x20	ر, reset 0x	rrrr.FFFF			DEAD !	ENIADIE							
								ENABLE ENABLE							
FMPRF4	type R/W, o	offset Ox21	O. reset Ove	FFFFFFF				LINCULL							
1 MII IXL-4,	type it ii, t	JIISEL UXZ I	0, 1636t 0XI				READ I	ENABLE							
								ENABLE							
FMPRE5,	type R/W, o	offset 0x21	4, reset 0xF	FFFF.FFFF											
	,		<u>,                                      </u>				READ I	ENABLE							
								ENABLE							
FMPRE6,	type R/W, o	offset 0x21	8, reset 0xF	FFFF.FFFF											
							READ_I	ENABLE							
							READ_I	ENABLE							
FMPRE7,	type R/W, o	offset 0x21	C, reset 0x	FFFF.FFFF											
							READ_I	ENABLE							
							READ_I	ENABLE							
FMPPE1,	type R/W, o	offset 0x40	4, reset 0xF	FFF.FFFF											
								ENABLE							
		·					PROG_	ENABLE							
гмРРЕ2,	type R/W, o	ortset 0x40	o, reset 0xF	-rrr.FFFF			DDOO	ENIAD! E							
								ENABLE ENABLE							
FMPPF3	type R/W, o	offset 0x40	C reset Oxi	FFFF FFFF			1100_	LIVADEL							
20,	туро тотт, с	moet ox-to	o, 10001 0x1				PROG	ENABLE							
								ENABLE							
FMPPE4,	type R/W, o	offset 0x41	0, reset 0xF	FFF.FFFF											
							PROG_	ENABLE							
							PROG_	ENABLE							
FMPPE5,	type R/W, o	offset 0x41	4, reset 0xF	FFF.FFFF											
							PROG_	ENABLE							
							PROG_	ENABLE							
FMPPE6,	type R/W, o	offset 0x41	8, reset 0xF	FFF.FFFF											
							PROG_	ENABLE							
							PROG_	ENABLE							
FMPPE7,	type R/W, o	offset 0x41	C, reset 0xl	FFFF.FFFF											
								ENABLE							
							PROG_	ENABLE							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
		emory A													
μ <b>DMA</b> (Base n/a		Control	Structu	re (Offse	et from C	Channel	Control	Table B	ase)						
DMASRC	ENDP, type	R/W, offse	et 0x000, re	set -											
							Al	DDR							
							Al	DDR							
DMADST	ENDP, type	R/W, offse	t 0x004, res	set -											
							Al	DDR							
							Al	DDR							
DMACHC	TL, type R	/W, offset 0	x008, reset	:-											
DS.	TINC	DST	SIZE	SRO	CINC	SRC	SIZE							ARE	BSIZE
												RST			
ARE	BSIZE					XFE	RSIZE					SEBL	:	XFERMOD	E
												NXTUSEBURST			
Micro F	Direct M	emory A	ccess (u	DMA)											
		s (Offse			se Addr	ess)									
	400F.F000		ι ο μι	DIVIA Da	oc Addit	,									
DMASTA	T, type RO,	offset 0x00	00, reset 0x	001F.0000											
													DMACHAN	S	
									S.	TATE					MASTEN
DMACFG	, type WO,	offset 0x00	)4, reset -												
															MASTEN
DMACTLI	BASE, type	R/W, offse	t 0x008, re:	set 0x0000	.0000			1							
							Al	DDR							
		AD	DDR												
DMAALTE	BASE, type	RO, offset	0x00C, res	et 0x0000.	0200										
							Al	DDR							
							Al	DDR							
DMAWAIT	TSTAT, type	RO, offset	0x010, res	et 0xFFFF.	FFC0										
							WAIT	REQ[n]							
							WAIT	REQ[n]							
DMASWR	REQ, type V	VO, offset 0	x014, reset	t -											
							SWF	REQ[n]							
							SWI	REQ[n]							
DMAUSE	BURSTSE	Γ, type R/W,	offset 0x0	18, reset 0	c0000.0000										
							SE	ET[n]							
							SE	ET[n]							
DMAUSE	BURSTCLI	R, type WO,	offset 0x0	1C, reset -											
								-R[n]							
							Cl	-R[n]							
DMAREQ	MASKSET	type R/W,	offset 0x02	0, reset 0x	0000.0000										
								ET[n]							
							SE	ET[n]							
DMAREQ	MASKCLR	, type WO,	offset 0x02	4, reset -											
								-R[n]							
							Cl	-R[n]							
DMAENA	SET, type I	R/W, offset	0x028, rese	et 0x0000.0	000										
								ET[n]							
							SE	ET[n]							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
DMAENA	CLR, type V	VO, offset	0x02C, res	et -				Dr. 1							
								R[n] R[n]							
DMAALTC	SET, type R	/M -ff4 (	N.020	4 0~0000 00	100		CLI	Kliij							
DIVIAALIS	o⊏i, type K	/ww, onset u	JXUSU, TESE	t 0x0000.00	100		CE.	Tinl							
								T[n] T[n]							
DMAALTO	CLR, type V	VO offect (	0v034 roso	•				1111							
DINALIC	JEIN, type V	vo, onser c	JA054, 1636				CLI	R[n]							
								R[n]							
DMAPRIC	SET, type I	R/W. offset	0x038. res	et 0x0000.0	000										
	, . , , , ,	,	,				SE	T[n]							
								T[n]							
DMAPRIC	CLR, type	WO. offset	0x03C, res	set -											
	7.31		, , ,				CLI	R[n]							
								R[n]							
DMAERR	CLR, type F	R/W, offset	0x04C, res	et 0x0000.0	0000										
	-														
															ERRCLR
DMACHA	SGN, type I	R/W, offset	0x500, res	et 0x0000.0	0000										
							CHAS	GN[n]							
							CHAS	GN[n]							
DMACHIS	s, type R/W	1C, offset 0	0x504, rese	t 0x0000.00	000										
							CHI	S[n]							
							CHI	S[n]							
DMAPerip	ohID0, type	RO, offset	0xFE0, res	et 0x0000.0	0030										
											Р	ID0			
DMAPerip	ohID1, type	RO, offset	0xFE4, res	et 0x0000.0	00B2										
											P	ID1			
DMAPerip	ohID2, type	RO, offset	0xFE8, res	et 0x0000.0	000B										
											P	ID2			
DMAPerip	ohID3, type	RO, offset	0xFEC, res	set 0x0000.	0000										
<b>D111</b> -				10							P	ID3			
DMAPerip	ohID4, type	RO, offset	0xFD0, res	et 0x0000.0	0004							1			
DMADO-I	UDO tomo F			4.00000.00							Р	ID4			
DMAPCel	IID0, type F	KO, offset 0	DXFFU, rese	t 0x0000.00	100							1			
												ID0			
DMARCAL	IID1, type F	O offeet 0	VEE4 ****	t 0×0000 00	)En							וטטו			
DIMAPORI	וטו, type א.	, onset 0	,,, , 4, rese		,, U										
											C	l ID1			
DMAPCal	IID2, type F	RO. offset f	)xFF8 rese	t OxOOOO oo	005			L							
SWAL CAI	bz, type r	, onset t	, ai i o, rese		.55										
											C	ID2			
DMAPCal	IID3, type F	RO. offset f	xFFC res	et OxOnnn n	0B1			L							
	, ., pe r		5, 1636												
											C	I ID3			

						1					I				
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
Genera GPIO Po GPIO Po	II-Purpos ort A (APB; ort A (AHB) ort B (AHB) ort B (AHB) ort C (APB) ort C (AHB) ort C (AHB) ort C (AHB) ort C (AHB) ort E (AHB) ort E (AHB) ort F (AHB) ort F (AHB) ort G (APB) ort G (AHB) ort H (AHB)	be Input/be base: 0xb base	Coutputs 4000.4000 4005.8000 4005.9000 4000.6000 4000.7000 4000.7000 4000.5000 4002.4000 4002.5000 4002.5000 4002.6000 4002.7000 4002.7000 40005.F000 40003.D000	(GPIOs											
			4006.0000												
	• ,		000, reset 0		0 (see page	2 420)									
			, ,,,,,,		, , , , , , ,	,									
											DA	I			
GPIODIR	tyne R/W	offset 0x40	0, reset 0x0	0000 0000	see nage 4	.21)									
Oi lobiit,	typo ioti, t	J11001 0X-10	, reser exe		occ page 4										
												l IR			
ODIOIO 4	DAM	f4 0404		00 0000 /-	40	0)						IIX			
GPIOIS, t	ype R/W, of	rset ux4u4,	, reset 0x00	00.0000 (s	ee page 42	2)									
-															
											Į:	S			
GPIOIBE,	type R/W, o	offset 0x40	8, reset 0x0	0000.0000	see page 4	23)									
											IE	BE			
GPIOIEV,	type R/W, c	offset 0x40	C, reset 0x0	0000.0000	(see page 4	24)									
											IE	V			
GPIOIM, t	ype R/W, of	fset 0x410	, reset 0x00	000.0000 (s	ee page 42	5)									
											IN	1E			
GPIORIS,	type RO, o	ffset 0x414	l, reset 0x00	000.0000 (s	see page 42	26)									
											R	I IS			
GPIOMIS	type RO. o	ffset 0x418	3, reset 0x0	000.0000 (	see page 42	27)									
	,	221 421 10	,			,									
											M	l IS			
GPIOICE	type W1C	offeet Ov 4	1C, reset 0x	,0000 0000	(see page	420)		<u> </u>			IVI				
GFIOICK,	type wite,	Oliset UX4	io, reset ux		(see page	743)									
											1.				
ODIC 155	FI 4: 5:	A		1	400)							C			
GPIOAFS	∟∟, type R/	vv, offset 0	x420, reset	- (see page	e 430)										
											AFS	SEL			
GPIODR2	R, type R/W	/, offset 0x	500, reset 0	x0000.00F	F (see page	e 432)									
											DF	RV2			
GPIODR4	R, type R/W	, offset 0x	504, reset 0	x0000.000	0 (see page	e 433)									
											DF	RV4			
GPIODR8	R, type R/W	, offset 0x	508, reset 0	x0000.000	0 (see page	e 434)									
											DF	1 RV8			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
GPIOODR	R, type R/W	offset 0x5	UC, reset 0	X0000.0000	(see page	435)		I							
											01				
ODIODUD	D.04/	- ff4 0F	10 1		20)						OI	)E			
GPIOPUR	R, type R/W,	offset ux5	10, reset - (	see page 4.	36)			I							
											DI				
											Pl	JE			
GPIOPDR	R, type R/W,	offset 0x5	14, reset 0x	0000.0000	(see page	438)									
											PI	)E			
GPIOSLR	, type R/W,	offset 0x5	18, reset 0x	0000.0000	(see page	440)									
											SI	RL			
GPIODEN	I, type R/W,	offset 0x5	1C, reset -	(see page 4	41)										
											DI	EN			
GPIOLOC	K, type R/V	V, offset 0x	520, reset (	0x0000.000	1 (see page	e 443)									
							LC	CK							
							LC	CK							
GPIOCR,	type -, offs	et 0x524, re	eset - (see p	age 444)											
											C	R			
GPIOAMS	SEL, type R	/W, offset 0	x528, reset	0x0000.00	<b>00</b> (see pa	ge 446)									
											GPIO/	MSEL			
GPIOPCT	L, type R/W	, offset 0x	52C, reset -	(see page	448)										
	PM	IC7			PN	<b>ЛС</b> 6			PM	IC5			PM	IC4	
	PM	IC3			PN	/IC2			PM	IC1			PM	1C0	
GPIOPeri	phID4, type	RO, offset	0xFD0, res	set 0x0000.	0000 (see	page 450)									
											PI	D4			
GPIOPeri	phID5, type	RO, offset	0xFD4, res	set 0x0000.	0000 (see )	page 451)									
											PI	L D5			
GPIOPeri	phID6, type	RO. offset	0xFD8. res	set 0x0000.	0000 (see i	page 452)		l							
	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,			(										
											PI	D6			
												-			
<b>GPIOPerio</b>	phID7. tvne	RO, offset	0xFDC re-	set 0x0000	0000 (see	page 4531									
GPIOPeri	phID7, type	RO, offset	0xFDC, re	set 0x0000.	0000 (see	page 453)									
GPIOPeri	phID7, type	RO, offset	0xFDC, re	set 0x0000.	0000 (see	page 453)					PI	D7			
											PI	D7			
	phID7, type										PI	D7			
GPIOPeri	phID0, type	RO, offset	0xFE0, res	set 0x0000.	0061 (see l	page 454)						D7			
GPIOPeri		RO, offset	0xFE0, res	set 0x0000.	0061 (see l	page 454)									
GPIOPeri	phID0, type	RO, offset	0xFE0, res	set 0x0000.	0061 (see l	page 454)					PI	D0			
GPIOPeri <sub>l</sub> GPIOPeri <sub>l</sub>	phID0, type	RO, offset	0xFE0, res	set 0x0000.	0061 (see p	page 454)						D0			
GPIOPeri <sub>l</sub> GPIOPeri <sub>l</sub>	phID0, type	RO, offset	0xFE0, res	set 0x0000.	0061 (see p	page 454)					PI	D0			
GPIOPeri <sub>l</sub> GPIOPeri <sub>l</sub>	phID0, type	RO, offset	0xFE0, res	set 0x0000.	0061 (see p	page 454)					PI PI	D0			
GPIOPeri GPIOPeri GPIOPeri	phID0, type	RO, offset	0xFE4, res	set 0x0000.	0001 (see p	page 454) page 455) page 456)					PI PI	D0			
GPIOPeri GPIOPeri GPIOPeri	phID0, type	RO, offset	0xFE4, res	set 0x0000.	0001 (see p	page 454) page 455) page 456)					PI PI	D0			
GPIOPeri GPIOPeri GPIOPeri	phID0, type	RO, offset	0xFE4, res	set 0x0000.	0001 (see p	page 454) page 455) page 456)					PI	D0			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
GPIOPCe	IIID0, type F	RO, offset	0xFF0, reso	et 0x0000.0	100D (see pa	age 458)									
						,									
											CI	J			
											CI	D0			
GPIOPCe	IIID1, type F	RO, offset	0xFF4, rese	et 0x0000.0	00F0 (see pa	ige 459)									
											CI	D1			
GPIOPCe	IIID2. type F	RO. offset	0xFF8, reso	et 0x0000.0	005 (see pa	ne 460)									
00. 00		10, 0001	J 0, . 00.		(осо ра	.90 .00)									
											CI	D2			
GPIOPCe	IIID3, type F	RO, offset	0xFFC, res	et 0x0000.0	<b>00B1</b> (see page	age 461)									
											CI	D3			
	al Davissla		f (F	'DI\		<u> </u>									
	400D.0000		erface (E	PI)											
EPICFG, 1	type R/W, o	ffset 0x00	0, reset 0x0	000.0000 (	see page 49	4)									
											BLKEN		MO	DE	
EDIRALID	type P/M	offeet Ov0	M4 reset 0	/0000 0000	(see page /	105)									
LFIDAUD	, type rav,	Onset UXU			(see page 4	100)									
								UNT1							
							СО	UNT0							
EPISDRA	MCFG, type	R/W, offs	set 0x010, re	eset 0x82E	E.0000 (see	page 497)									
FR	REQ									RFSH					
						SLEEP								SIZ	ΖE
EDILIDOCI	EC tupo B/	M offoot (	)v010 rocot	0×0000 EE	=00 (aaa naa	100)									
ЕРІПВОСІ	rG, type K/	vv, onset t	JXU1U, resei	UXUUUU.FF	F00 (see pag	je 499)						ı			
								XFFEN	XFEEN	WRHIGH	RDHIGH				
			MAX	WAIT				WR	:WS	RD	WS			MO	DE
EPIHB160	CFG, type R	/W, offset	0x010, res	et 0x0000.F	F00 (see pa	age 502)									
								XFFEN	XFEEN	WRHIGH	RDHIGH				
			MAX	WAIT					:WS	RD			BSEL	MO	DE
EDIODOS	G toma Des	1 065			0 (000 ===	. EO6'					-			0	_
		, oitset 0x			00 (see page	(סטט)						I <u> </u>			
CLKPIN	CLKGATE		RDYEN	FRMPIN	FRM50		FRI	MCNT		RW		WR2CYC	RD2CYC		
			MAX	WAIT						AS	IZE			DSI	ZE
EPIHB8C	FG2, type R	/W, offset	0x014, res	et 0x0000.0	0000 (see pa	ige 511)									
WORD					CSBAUD	CSC	CFG			WRHIGH	RDHIGH				
					113,.05	330	-	WR	WS	RD					
		D.044			2000 :	<b>_</b>		VVI	.,,,	ND	,,,,				
					.0000 (see p										
WORD					CSBAUD	CSC	FG			WRHIGH	RDHIGH				
								WR	:WS						
EPIGPCF	G2, type R/	W, offset 0	)x014, reset	0x0000.00	000 (see pag	e 517)									
WORD															
EPIADDR	MAP, type I	R/W, offse	t 0x01C, res	set 0x0000.	.0000 (see p	age 518)									
								EP	SZ	EPA	DR	EF	RSZ	ERA	DR
FPIRSIZE	0. type R/W	/. offset 0x	020. reset (	0x0000.000	3 (see page	520)									
	, ., po 1011	, 5500 07	,		- (ooo page	,									
														SIZ	<u>L</u>
EPIRSIZE	1, type R/W	l, offset 0x	(030, reset (	0x0000.000	3 (see page	520)									
														SIZ	ZE
EDID 4 DC	P0 +	W cffc-4	1v024	0.0000	100 /225 -:	10 E24\								312	-
CPIKAUU	κυ, type R/	vv, oitset (	JAU24, Fese	. UXUUUU.UU	000 (see pag	JE 321)									
									ADDR						
							Al	DDR							

0.1	00	00	60	l 67		65	6.		00	64	60	40	40	4-	- 40
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20	19	18	17	16
	R1, type R/						0	'	U	3	-	3		1	
CFIKADD	K I, type K/	vv, onset o	XU34, 16561	0.0000.00	oo (see paç	je 521)			ADDR						
							AD	DR	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
EPIRPSTI	D0, type R/V	V, offset 0x	(028, reset	0x0000.000	00 (see pag	e 522)									
		,	.,			,									
									POSTCNT						
EPIRPSTI	D1, type R/V	V, offset 0x	(038, reset	0x0000.000	00 (see pag	e 522)									
						'	'		POSTCNT						
EPISTAT,	type RO, of	fset 0x060	, reset 0x00	<b>000.0000</b> (s	ee page 52	4)									
						CELOW	XFFULL	XFEMPTY	INITSEQ	WBUSY	NBRBUSY				ACTIVE
EPIRFIFO	CNT, type F	RO, offset (	0x06C, rese	et - (see pag	ge 526)										
													CO	UNT	
EPIREAD	FIFO, type I	RO, offset	0x070, rese	et - (see paç	ge 527)										
								ATA							
							DA	ATA							
EPIREAD	FIFO1, type	RO, offset	t 0x074, res	set - (see pa	age 527)										
								ATA							
							DA	ATA							
EPIREAD	FIFO2, type	RO, offset	t 0x078, res	set - (see pa	age 527)										
								ATA							
	=====	DO 11			507)		DF	ATA							
EPIREAD	FIFO3, type	RO, offset	t 0x07C, res	set - (see p	age 527)										
								ATA							
FDIDEAD	FIFO4 towns	DO -#	. 0000		507)		DF	ATA							
EPIKEAD	FIFO4, type	RO, oπse	t uxusu, res	set - (see pa	age 527)		D/	\ <b>T</b> A							
								ATA ATA							
EDIDEAD	FIFO5, type	BO offeet	1 0×004 ros	net (200 n	200 527)		- Dr	NA .							
LFIRLAD	i ii O3, type	KO, Olisei	1 0 1 0 0 4 , 1 6 5	<b>set -</b> (see pa	age 321)		D/	ATA							
								ATA							
EDIREAD	FIFO6, type	PO offeet	t 0v088 res	ent - (see na	age 527)		Dr.								
LINCAD	i ii Oo, type	110, 01136	1 0,000, 163	<b>300</b> - (300 pe	agc 321)		D/	ATA							
								ATA							
EPIREAD	FIFO7, type	RO. offset	t 0x08C. re:	set - (see p	age 527)										
	, ., ,,	,		(	-9 /		D.A	ATA							
								ATA							
EPIFIFOL	VL, type R/\	N, offset 0:	x200, reset	0x0000.00	33 (see pag	je 528)									
														WFERR	RSERR
										WRFIFO				RDFIFO	
EPIWFIFO	OCNT, type	RO, offset	0x204, rese	et 0x0000.0	<b>004</b> (see pa	age 530)			-				-		
														WTAV	
EPIIM, typ	e R/W, offs	et 0x210, r	eset 0x000	0.0000 (see	e page 531)			•					-		
													WRIM	RDIM	ERRIM
EPIRIS, ty	pe RO, offs	set 0x214, i	reset 0x000	00.0004 (see	e page 532	)									_
													WRRIS	RDRIS	ERRRIS

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
EPIMIS, ty	pe RO, offs	et 0x218, r	reset 0x000	00.0000 (se	e page 534	)									
													WRMIS	RDMIS	ERRMIS
EPIEISC, t	ype R/W1C	, offset 0x2	21C, reset	0x0000.000	0 (see pag	e 535)									
													WTFULL	RSTALL	TOUT
	-Purpos		s												
	ase: 0x40														
Timer 2 b	ase: 0x40	03.2000													
	ase: 0x40														
GPTMCFG	i, type R/W,	offset 0x0	100, reset 0	X0000.0000	(see page	: 554)		1							
														ODTMOS	
CDTMTAM	ID toma D/V	V affaat 0:	.004 ====	0::0000 000	20 /222 22	ro FFF\								GPTMCFG	1
GPIWIAW	IR, type R/V	v, onset ux	tou4, reset	UXUUUU.UUI	o (see pag	je ooo)									
								TASNAPS	TAWOT	TAMIE	TACDIR	TAAMS	TACMR	ΤΛ	MR
GPTMTRM	IR, type R/V	V. offset Ox	x008, reset	0x0000 00	00 (see nad	ne 557)		INGINALO	IAVVOI	IAMIL	IAODIK	IAANIG	IAOIVIIX	IA	1411 /
J. 111111111	, type K/V	., 511361 07	, 16361		- J (SCC PA(	50 001 )									
								TBSNAPS	TBWOT	TBMIE	TBCDIR	TBAMS	TBCMR	TR	MR
GPTMCTL	, type R/W,	offset 0x0	0C, reset 0	x0000.0000	(see page	: 559)		1		=		1			
	, ,,		,			,									
	TBPWML	TBOTE		TBE	/ENT	TBSTALL	TBEN		TAPWML	TAOTE	RTCEN	TAE\	VENT	TASTALL	TAEN
GPTMIMR,	type R/W,	offset 0x0	18, reset 0	x0000.0000	(see page	562)								.1	
				ТВМІМ	CBEIM	СВМІМ	TBTOIM				TAMIM	RTCIM	CAEIM	CAMIM	TATOIM
GPTMRIS,	type RO, o	ffset 0x01	C, reset 0x	0000.0000	see page 5	564)									
				TBMRIS	CBERIS	CBMRIS	TBTORIS				TAMRIS	RTCRIS	CAERIS	CAMRIS	TATORIS
GPTMMIS,	type RO, o	ffset 0x02	0, reset 0x	0000.0000	see page 5	567)									
				TBMMIS	CBEMIS	CBMMIS	TBTOMIS				TAMMIS	RTCMIS	CAEMIS	CAMMIS	TATOMIS
GPTMICR,	type W1C,	offset 0x0	24, reset 0	x0000.0000	(see page	570)									
				l		CBMCINT	TBTOCINT				TAMCINT	RTCCINT	CAECINT	CAMCINT	TATOCINT
GPTMTAIL	.R, type R/V	V, offset 0>	x028, reset	0xFFFF.FF	FF (see pa	ige 572)									
								ILR							
COTMTO	R, type R/V	N offeet 0	×03C ====	+ 0×0000 FF	EE (800 50	nge 572\	1A	ILR							
OF INITIBIL	is, type R/V	v, onset 0	AUZO, 1656	L UNUUUU.FF	ii (see pa	ige 3/3)	TD	ILR							
								ILR							
GPTMTAM	IATCHR, ty	oe R/W. off	fset 0x030	reset 0xFF	FF.FFFF (s	see page 57									
		, 511			(0			MR							
								MR							
GPTMTBM	IATCHR, ty	pe R/W, off	fset 0x034,	reset 0x00	00.FFFF (s	see page 57									
					`	<u> </u>		MR							
							ТВ	MR							
GPTMTAP	R, type R/W	l, offset 0x	038, reset	0x0000.000	0 (see pag	je 576)									
											TAI	PSR			
GPTMTBP	R, type R/V	V, offset 0x	03C, reset	0x0000.00	00 (see pag	ge 577)									
											ТВІ	PSR			

31 15	20	00	00	07	00	0.5	0.4	00	00	0.4	00	40	40	47	40
	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20	19	18	17	16 0
	PMR, type R			1			0	,	0	3			2	'	0
GFIMIA	rwin, type n	J vv, Oliset	0.040, 165		(see pa	age 370)									
											TAF	 PSMR			
GPTMTR	PMR, type F	R/W offset	NyN44 res	et OxOOOO (	1000 (see n:	age 579)					17.0	OWIT			
0	init, typo i		0.044, 100		(occ p	lage or or									
											TBF	I PSMR			
GPTMTAI	R, type RO,	offset 0x0	48. reset 0	L KFFFF.FFF	see page	580)									
	7 71 7		.,		(		T/	AR							
								AR							
GPTMTB	R, type RO,	offset 0x0	4C, reset 0	x0000.FFFI	F (see page	581)									
							TI	3R							
							TI	3R							
GPTMTA\	/, type RW,	offset 0x0	50, reset 0x	FFFF.FFF	(see page	582)									
							T	AV							
							T	AV							
GPTMTB	V, type RW,	offset 0x0	54, reset 0	x0000.FFFF	(see page	583)									
							Т	3V							
							Т	3V							
Watcho	dog Time	rs													
	ase: 0x400 ase: 0x400														
WDTLOA	D, type R/W	, offset 0x	000, reset (	0xFFFF.FFF	F (see pag	e 588)									
							WDT	LOAD							
							WDT	LOAD							
WDTVAL	UE, type RO	), offset 0x	004, reset	0xFFFF.FFI	FF (see pag	e 589)									
							WDT	/A							
							WDI	/ALUE							
								/ALUE							
WDTCTL,	, type R/W, o	offset 0x00	08, reset 0x	0000.0000	(WDT0) and	d 0x8000.00	WDT	/ALUE	590)						
WDTCTL,	, type R/W, o	offset 0x00	08, reset 0x	0000.0000	(WDT0) and	d 0x8000.00	WDT	/ALUE	590)						
	, type R/W, o	offset 0x00	08, reset 0x	0000.0000	(WDT0) and	d 0x8000.00	WDT	/ALUE	590)					RESEN	INTEN
WRC	type WO, o					d 0x8000.00	WDT	/ALUE	590)					RESEN	INTEN
WRC						d 0x8000.00	WDT\	/ALUE	590)					RESEN	INTEN
WRC	type WO, o	ffset 0x00	C, reset - (s	see page 59	)2)		WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	INTEN
WRC		ffset 0x00	C, reset - (s	see page 59	)2)		WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	INTEN
WRC	type WO, o	ffset 0x00	C, reset - (s	see page 59	)2)		WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	
WRC WDTICR, WDTRIS,	type WO, o	ffset 0x00	C, reset - (s	see page 59	see page 59	3)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	
WRC WDTICR, WDTRIS,	type WO, o	ffset 0x00	C, reset - (s	see page 59	see page 59	3)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	
WRC WDTICR, WDTRIS,	type WO, o	ffset 0x00	C, reset - (s	see page 59	see page 59	3)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, of	ffset 0x000	C, reset - (s	000.0000 (s	see page 59	3)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, o	ffset 0x000	C, reset - (s	000.0000 (s	see page 59	3)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, of	ffset 0x000	C, reset - (s	000.0000 (s	see page 59	3)	WDT1	/ALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, of type RO, of type RO, of	ffset 0x000 ffset 0x010 ffset 0x014 offset 0x4	C, reset - (s 0, reset 0x0 4, reset 0x0	000.0000 (s	see page 59 see page 59 see page 59 0 (see page	3) 34) 595)	WDT\ 000 (WDT1)	/ALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, of	ffset 0x000 ffset 0x010 ffset 0x014 offset 0x4	C, reset - (s 0, reset 0x0 4, reset 0x0	000.0000 (s	see page 59 see page 59 see page 50 0 (see page	3) 34) 595)	WDT1	VALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS,	type WO, of type RO, of type RO, of	ffset 0x000 ffset 0x010 ffset 0x014 offset 0x4	C, reset - (s 0, reset 0x0 4, reset 0x0	000.0000 (s	see page 59 see page 59 see page 50 0 (see page	3) 34) 595)	WDT1	VALUE (see page  NTCLR  NTCLR  LOCK	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS, WDTTES	type WO, of type RO, of type RO, of	offset 0x014	C, reset - (s 0, reset 0x0 4, reset 0x0 L18, reset 0	000.0000 (s	see page 59 see page 59 0 (see page	(3) (4) (595) (e 596)	WDT1	VALUE (see page	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS, WDTTES	type WO, of type RO, of type RO, of	offset 0x014	C, reset - (s 0, reset 0x0 4, reset 0x0 L18, reset 0	000.0000 (s	see page 59 see page 59 0 (see page	(3) (4) (595) (e 596)	WDT1	VALUE (see page  NTCLR  NTCLR  LOCK	590)					RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS, WDTTES	type WO, of type RO, of type RO, of	offset 0x014	C, reset - (s 0, reset 0x0 4, reset 0x0 L18, reset 0	000.0000 (s	see page 59 see page 59 0 (see page	(3) (4) (595) (e 596)	WDT1	VALUE (see page  NTCLR  NTCLR  LOCK	590)		D			RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS, WDTTES'	type WO, of type RO, of type RO, of T, type R/W, K, type R/W	offset 0x014 offset 0x4 v, offset 0x4 RO, offset	C, reset - (s 0, reset 0x0 4, reset 0x0 118, reset 0 C00, reset	000.0000 (s 000.0000 (s 000.0000 (s 00000.0000	see page 59 see page 59 (see page 59 (see page 50)	595) e 596)	WDT1	VALUE (see page  NTCLR  NTCLR  LOCK	590)		P	ID4		RESEN	WDTRIS
WRC WDTICR, WDTRIS, WDTMIS, WDTTES'	type WO, of type RO, of type RO, of	offset 0x014 offset 0x4 v, offset 0x4 RO, offset	C, reset - (s 0, reset 0x0 4, reset 0x0 118, reset 0 C00, reset	000.0000 (s 000.0000 (s 000.0000 (s 00000.0000	see page 59 see page 59 (see page 59 (see page 50)	595) e 596)	WDT1	VALUE (see page  NTCLR  NTCLR  LOCK	590)		P	ID4		RESEN	WDTRIS

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	21 5	4	3	2	17	0
					-	-	0	,	0	5	4	] 3		1	U
WDIPerip	niD6, type i	RO, offset	0xFD8, res	et uxuuuu.u	ooo (see p	age 599)						I			
											PI	ID6			
WDTPerip	hID7, type I	RO, offset	0xFDC, res	et 0x0000.0	<b>0000</b> (see p	age 600)						1			
											PI	D7			
WDTPerip	hID0, type I	RO, offset	0xFE0, res	et 0x0000.0	<b>005</b> (see p	age 601)									
											Pl	D0			
WDTPerip	hID1, type I	RO, offset	0xFE4, res	et 0x0000.0	<b>018</b> (see page 1	age 602)									
											Pl	ID1			
WDTPerip	hID2, type l	RO, offset	0xFE8, res	et 0x0000.0	<b>018</b> (see page	age 603)									
											PI	D2			
WDTPerip	hID3, type l	RO, offset	0xFEC, res	et 0x0000.0	0001 (see p	age 604)									
											PI	ID3			
WDTPCelli	ID0, type R	O, offset 0	xFF0, reset	t 0x0000.00	<b>0D</b> (see pa	ge 605)									
	, ,,	<u> </u>	,		` .	,									
											C	ID0			
WDTPCell	ID1. type R	O. offset 0	xFF4, reset	0×0000.00	F0 (see par	ne 606)									
11211 0011	ID I, type It	0, 011001 0	7, 1000	- CXCCCC.CC	· • (occ pa	gc 000)									
											C	l ID1			
WDTBCall	ID2 tupo B	O offeet 0	xFF8, reset	. 02000 00	06 (222 22	20 607)									
WDTPCell	ID2, type K	O, onset u	xrro, reset	UXUUUU.UU	<b>uo</b> (see pa	ge 607)									
											0	ID2			
						>						ID2			
WDTPCell	ID3, type R	O, offset 0	xFFC, rese	t 0x0000.00	B1 (see pa	ige 608)						1			
											С	ID3			
ADC0 bas	to-Digita se: 0x4003 se: 0x4003	3.8000	erter (AD	)C)											
			OOO rosot	0×0000 000	<b>0</b> (see page	2 632)									
YDOW019	o, type R/V	, Uniset U	(000, reset	0.0000.000	v (see page	J 002)									
												ACENIO	ACENIO	ACENIA	ACENIO
4 D O D I O						.,						ASEN3	ASEN2	ASEN1	ASEN0
ADCRIS, ty	ype KO, off	set uxuu4,	reset 0x00		e page 633	)									IN INC.
													11.75	11.17	INRDC
												INR3	INR2	INR1	INR0
ADCIM, typ	pe R/W, off	set 0x008,	reset 0x000	00.0000 (se	e page 635	)						1			
													DCONSS2		
												MASK3	MASK2	MASK1	MASK0
ADCISC, ty	ype R/W1C	, offset 0x	00C, reset 0	0x0000.000	(see page	637)									
												DCINSS3	DCINSS2	DCINSS1	DCINSS0
												IN3	IN2	IN1	IN0
ADCOSTA	T, type R/W	1C, offset	0x010, rese	et 0x0000.0	000 (see pa	age 640)									
												OV3	OV2	OV1	OV0
ADCEMUX	, type R/W,	offset 0x0	014, reset 0	x0000.0000	(see page	642)						-			
	EM	13			EN	/12			Е	M1			EI	M0	

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ADCUSTA	AT, type R/W	V1C, offset	0x018, res	et 0x0000.0	0000 (see p	age 647)									
												111/0	111/0	1074	111/0
						0.40)						UV3	UV2	UV1	UV0
ADCSSPF	RI, type R/W	/, offset 0x0	020, reset (	0x0000.321	0 (see page	e 648)									
			S3				S2				24				S0
ADCCDC	ture D/M			0000 0000	(222 222 (		52			SS	) i			3	30
ADCSPC,	type R/W,	onset uxuz	4, reset ux	1	(see page t	50)									
													DU	ASE	
ADCDSSI	, type R/W,	offeet 0v03	18 rosot (	see page 6	52)								1117	- TOL	
GSYNC	, type K/VV,	Uliset UAU2	.o, reset - (	SYNCWAIT	J2)										
GSTNC				STINCWAIT								SS3	SS2	SS1	SS0
ADCSAC	type R/W,	offeet 0v03	0 rosot 0v	0000 0000	(see page 6	\$54)						000	002	001	000
ADCOAC,	, type ivv,	Oliset UXUS	o, reset ox		(see page (	)54)									
														AVG	
ADCDCIS	C, type R/V	V1C. offset	0x034 res	et Oxnono	0000 (see r	age 655)									
	-, ., ,,	, 511081			(July 1										
								DCINT7	DCINT6	DCINT5	DCINT4	DCINT3	DCINT2	DCINT1	DCINT0
ADCCTL.	type R/W, o	offset 0x03	B. reset 0x	0000.0000	see page 6	57)									
,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		,		, ,9										
											RES			VF	REF
ADCSSMI	UX0, type R	Z/W. offset (	)x040. rese	et 0x0000.0	000 (see pa	age 658)									
		JX7	,			JX6			ML	JX5			ML	JX4	
		JX3				JX2				JX1				JX0	
ADCSSCT	TL0, type R	/W. offset 0	x044. rese	t 0x0000.00	000 (see pa	ge 660)									
TS7	IE7	END7	D7	TS6	IE6	END6	D6	TS5	IE5	END5	D5	TS4	IE4	END4	D4
TS3	IE3	END3	D3	TS2	IE2	END2	D2	TS1	IE1	END1	D1	TS0	IE0	END0	D0
ADCSSFII	FO0, type R	RO, offset 0	x048, rese	t - (see pag	e 663)										
	7.5.	,	,												
									DA	ATA					
ADCSSFII	FO1, type R	RO, offset 0	x068, rese	t - (see pag	e 663)										
									DA	ATA					
ADCSSFII	FO2, type R	RO, offset 0	x088, rese	t - (see pag	e 663)										
									DA	ATA					
ADCSSFII	FO3, type R	RO, offset 0	x0A8, rese	t - (see pag	je 663)										
									DA	ATA					
ADCSSFS	STAT0, type	RO, offset	0x04C, res	set 0x0000.	0100 (see	page 664)									
			FULL				EMPTY		HP	TR			TP	TR	
ADCSSFS	STAT1, type	RO, offset	0x06C, res	set 0x0000.	<b>0100</b> (see	page 664)									
ADCSSFS	STAT1, type	RO, offset	0x06C, res	set 0x0000.	0100 (see	page 664)									
ADCSSFS	STAT1, type	RO, offset	0x06C, res	set 0x0000.	0100 (see	page 664)	EMPTY		HP	PTR			TP	TR	
	STAT1, type		FULL				EMPTY		HP	PTR			TP	TR	
			FULL				EMPTY		HP	PTR			TP	TR	
			FULL				EMPTY			PTR				TR PTR	
ADCSSFS		RO, offset	FULL 0x08C, res	set 0x0000.	0100 (see	page 664)									
ADCSSFS	STAT2, type	RO, offset	FULL 0x08C, res	set 0x0000.	0100 (see	page 664)									

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ADCSSO	P0, type R/\	N, offset 0:	x050, reset	0x0000.00	00 (see pag	je 666)								1	
			S7DCOP				S6DCOP				S5DCOP				S4DCOP
			S3DCOP				S2DCOP				S1DCOP				SODCOP
ADCSSD	C0, type R/\	N, offset 0:	x054, reset	0x0000.00	00 (see pag	je 668)									
	S7D0	CSEL			S6D	CSEL			S5D	CSEL			S4D	CSEL	
	S3D0	CSEL			S2D	CSEL			S1D	CSEL			SOD	CSEL	
ADCSSM	UX1, type R	R/W, offset	0x060, rese	t 0x0000.0	0000 (see pa	age 670)									
	MU	JX3			М	UX2			MU	JX1			MU	JX0	
ADCSSM	UX2, type R	R/W, offset	0x080, rese	t 0x0000.0	0000 (see pa	age 670)									
	MU	JX3			M	UX2			MU	JX1			MU	JX0	
ADCSSC	TL1, type R	/W, offset	0x064, rese	0x0000.0	000 (see pa	ige 671)									
TS3	IE3	END3	D3	TS2	IE2	END2	D2	TS1	IE1	END1	D1	TS0	IE0	END0	D0
ADCSSC	TL2, type R	/W, offset (	0x084, rese	0x0000.0	000 (see pa	ige 671)									
TS3	IE3	END3	D3	TS2	IE2	END2	D2	TS1	IE1	END1	D1	TS0	IE0	END0	D0
ADCSSO	P1, type R/\	N, offset 0:	x070, reset	0x0000.00	00 (see pag	je 673)		1				1			
			S3DCOP				S2DCOP				S1DCOP				SODCOP
ADCSSO	P2, type R/\	N, offset 0:	x090, reset	0x0000.00	00 (see pag	je 673)									
			000000				000000				040000				000000
40000	04 4	N - 55 4 O	S3DCOP	00000.00	00 /	074)	S2DCOP				S1DCOP				SODCOP
ADCSSD	U1, type K/	ν, oπset υ	x074, reset	UXUUUU.UU	uu (see pag	je 674)									
	6300	CSEL			830	CSEL			910	CSEL			SUDI	CSEL	
ADCSSD			x094, reset	0~0000 00					310	OOLL			300	JOLL	
ADCOOD	Cz, type Ki	v, onset o	A034, 1656t		(see pag	Je 074)									
	S3D(	CSEL			S2D	CSEL			S1D	CSEL			SOD	CSEL	
ADCSSM			0x0A0, rese	et 0x0000.0					0.5	0022					
ADOCOM	United type in				) (Jee p	uge or or									
													ML	JX0	
ADCSSC	TL3. type R	/W. offset (	0x0A4, rese	t 0x0000.0	002 (see pa	age 677)						l			
	., ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,,,,,,,,				,									
												TS0	IE0	END0	D0
ADCSSO	P3, type R/\	N, offset 0:	x0B0, reset	0x0000.00	100 (see pag	ge 678)		ı						1	
															SODCOP
ADCSSD	C3, type R/\	N, offset 0:	x0B4, reset	0x0000.00	00 (see pag	ge 679)									-
													SOD	CSEL	
ADCDCR	IC, type R/V	V, offset 0	D00, reset	0x0000.00	00 (see pag	je 680)									
								DCTRIG7	DCTRIG6	DCTRIG5	DCTRIG4	DCTRIG3	DCTRIG2	DCTRIG1	DCTRIGO
								DCINT7	DCINT6	DCINT5	DCINT4	DCINT3	DCINT2	DCINT1	DCINT0
ADCDCC	TL0, type R	/W, offset	0xE00, rese	t 0x0000.0	000 (see pa	age 685)									
			CTE	С	TC	C	TM				CIE	C	IC	C	IM
ADCDCC	TL1, type R	/W, offset	0xE04, rese	t 0x0000.0	000 (see pa	age 685)									
			CTE	C	TC	C	TM				CIE	C	IC	C	MI

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ADCDCCT	L2, type R	W, offset	0xE08, rese	t 0x0000.00	000 (see pa	age 685)		1							
			CTE	C <sup>-</sup>	гс	C	TM				CIE	С	IC	С	IM
ADCDCCT	L3, type R	W, offset	0xE0C, rese	et 0x0000.0	<b>000</b> (see pa	age 685)									
			CTE	C <sup>-</sup>	ГС	C	TM				CIE	С	IC	С	IM
ADCDCCT	L4, type R	W, offset	0xE10, rese	t 0x0000.00	000 (see pa	age 685)									
			CTE		rc		TM				CIE		IC	C	IM
ADCDCCI	L5, type K	w, onset	0xE14, rese	t 0x0000.00	Juu (see pa	age 685)									
			CTE	C-	ГС	C	TM				CIE		IC	C	:IM
ADCDCCT	L6. type R	W. offset	0xE18, rese	l							0.2				
	., ., ,,	,	,		, , , , , , , , , , , , , , , , , , ,	J. 723,									
			CTE	C-	ГС	C	TM				CIE	С	IC	С	IM
ADCDCCT	L7, type R	W, offset	0xE1C, rese	et 0x0000.0	000 (see pa	age 685)									
			CTE	C <sup>-</sup>	гс	C	TM				CIE	С	IC	С	IM
ADCDCCM	/IP0, type R	/W, offset	0xE40, rese	et 0x0000.0	<b>000</b> (see pa	age 688)									
										MP1					
									СО	MP0					
ADCDCCN	/IP1, type R	/W, offset	0xE44, rese	et 0x0000.0 	000 (see pa	age 688)									
										MP1 MP0					
ADCDCCM	/IP2_type R	/W offset	0xE48, rese	et OxOOOO O	000 (see n	age 688)				TWII O					
ABOBOOII	<u>-</u> , type it		UXE-10, 1000		ooo (occ pi	age ooo,			CO	MP1					
										MP0					
ADCDCCN	/IP3, type R	/W, offset	0xE4C, res	et 0x0000.0	0000 (see p	age 688)									
									СО	MP1					
									СО	MP0					
ADCDCCM	/IP4, type R	/W, offset	0xE50, rese	et 0x0000.0	<b>000</b> (see pa	age 688)									
										MP1					
									СО	MP0					
ADCDCCN	/IP5, type R	/W, offset	0xE54, rese	et 0x0000.0 	000 (see pa	age 688)				MD4					
										MP1 MP0					
ADCDCCM	IP6. type P	/W. offset	0xE58, rese	et OxOOOO o	000 (see n	age 688)				11.11 0					
	о, суре К	, 011361	-A-00, 1650	0.0000.0	eee (ace p	age 000 <i>)</i>			CO	MP1					
										MP0					
ADCDCCN	/IP7, type R	/W, offset	0xE5C, res	et 0x0000.0	0000 (see p	age 688)									
					· · · ·	•			СО	MP1					
									СО	MP0					
UART0 b	al Asyno ase: 0x40 ase: 0x40 ase: 0x40	00.C000 00.D000	us Receiv	vers/Trai	nsmitter	rs (UAR	ſs)								
UARTDR,	type R/W, o	offset 0x00	00, reset 0x0	0000.0000	see page 7	705)									
				OE	BE	PE	FE				DA	ATA			
JARTRSR	/UARTECR	type RO	offset 0x00	04, reset 0x	0000.0000	(Read-Onl	y Status R	egister) (se	e page 707	')					
												OE	BE	PE	FE

31 30 29 28 27 26 25 24 23 22 21 20 19 18 17 19 10 15 15 14 13 12 11 10 9 8 6 7 6 5 5 4 4 3 2 2 1 10 0 10 18 17 19 10 14 15 15 14 10 18 15 7 6 5 4 4 3 2 2 1 10 0 14 15 17 19 10 14 14 15 15 14 15 15 14 16 15 14 16 15 14 16 15 14 16 15 14 16 15 14 16 15 14 16 15 14 16 14 16 14																
MARTERS, Type RW, offset 0x000, reset 0x0000, 0000 (eep page 710)   RI TXFE   RXFF   TXFF   RXFE   BUSY   DCD   DSR   CTS																
DATA  LIARTER, type RO, offset bx018, reset 0x0000 0000 (see page 710)  RI TXFE RXFF TXFF RXFE BUSY DCD DSR CTS  LIARTER, type RW, offset 0x024, reset 0x0000 0000 (see page 714)  DIVINT  DIV									L			4	<u> </u>	2	1	U
UARTERD, type RW, offset 0x026, reset 0x0000.0000 (see page 714)  LIPOVSR	UARTRSE	VUARTECE	k, type wo,	omset uxu	iu4, reset u I	X0000.0000	(write-On	ly Error Cie	ear Registe	r) (see page	e 707)					
UARTERD, type RW, offset 0x026, reset 0x0000.0000 (see page 714)  LIPOVSR												D/	 			
RI   TXFE   RXFF   TXFF   RXFE   BUSY   DCD   DSR   CTS	IIADTED	tuno PO o	ffeat 0v018	rosot OvO	000 0000 /6	200 0200 71	10)					- DF	**************************************			
LIPDUSR   LIPD	OAKII IX,	type ito, o	III JOE OXO IO	, 16361 020		ecc page 7	10)									
LIPDUSR   LIPD								RI	TXFF	RXFF	TXFF	RXFF	BUSY	DCD	DSR	CTS
ILPDVSR	UARTILPE	R. type R/W	l. offset 0x0	)20. reset 0	x0000.000	) (see page	713)									
DIVINT		, ,,,,	,			(444 )434										
DIVINT												ILPE	I VSR			
UARTERD, type RW, offset 0x028, reset 0x0000,0000 (see page 716)   SPS   WLEN   FEN   STP2   EPS   PEN   BRK	UARTIBR	D, type R/V	V, offset 0x0	024, reset (	0x0000.000	0 (see page	⇒ 714)									
UARTERD, type RW, offset 0x028, reset 0x0000,0000 (see page 716)   SPS   WLEN   FEN   STP2   EPS   PEN   BRK																
DIVFRAC   DIVF								DIV	/INT							
UARTICRH, type RIW, offset 0x02C, reset 0x0000.0000 (see page 716)	UARTFBR	RD, type R/\	N, offset 0x	028, reset	0x0000.00	00 (see pag	je 715)									
UARTICRH, type RIW, offset 0x02C, reset 0x0000.0000 (see page 716)																
UARTICIT., type RIW, offset 0x030, reset 0x0000.0300 (see page 718)  CTSEN RISEN RTS DTR RXE TXE LBE LIN HSE EOT SMART SIRLP SIREN UARTEN UARTIFLS, type RIW, offset 0x034, reset 0x0000.0012 (see page 722)  RXIFLSEL TXIFLSEL  UARTIM, type RIW, offset 0x035, reset 0x0000.0000 (see page 724)  LMESIM LMESIM LMSBIM DEBIM PEIM FEIM RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM UARTINS, type RO, offset 0x03C, reset 0x0000.0000 (see page 728)  LMESRIS LMESRIS LMSBRIS DERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS  UARTIMS, type RO, offset 0x044, reset 0x0000.0000 (see page 732)  LMESRIS LMESRIS LMSBRIS DERIS PERIS FEID RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM  LMESIM LMSBIM DSRRIS DERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS  UARTIMS, type RO, offset 0x044, reset 0x0000.0000 (see page 732)  LMESRIS LMESRIS LMSBRIS DERIS PERIS FEID RTIM TXIM RXIM DSRIM DCDIM CTSMIS RIMIS  UARTICR, type WIC, offset 0x044, reset 0x0000.0000 (see page 738)  LMESRIC LMSBIC DERIC DERIC PEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC  UARTIDMACTL, type RIW, offset 0x044, reset 0x0000.0000 (see page 738)  BLEN MASTER  UARTLCTL, type RIW, offset 0x094, reset 0x0000.0000 (see page 740)  TIMER  UARTLTIM, type RO, offset 0x094, reset 0x0000.0000 (see page 741)  TIMER													DIVE	RAC		
UARTICT, type R/W, offset 0x030, reset 0x0000.0300 (see page 718)  CTSEN RTSEN RTSE DTR RXE TXE LBE LIN HSE EOT SMART SIRLP SIREN UARTEN UARTIFLS, type R/W, offset 0x034, reset 0x0000.0012 (see page 722)  RXIFLSEL TXIFLSEL  UARTIM, type R/W, offset 0x038, reset 0x0000.0000 (see page 724)  LMESIM LME-IIM LMSBIM OEIM BEIM PEIM FEIM RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM UARTIRS, type RO, offset 0x03C, reset 0x0000.0000 (see page 728)  LMESRIS LME-IRIS LMSBIMS OERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS UARTIGR, type RO, offset 0x040, reset 0x0000.0000 (see page 732)  LMESRIS LME-IRIS LMSBIMS OEMIS BEMIS PEMIS FEMIS RTMIS TXMIS RXMIS DSRMIS DCDMIS CTSMIS RIMIS UARTICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIS LME-IIII LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIS LME-IIII LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 740)  TIMER  UARTLETH, type R/W, offset 0x094, reset 0x0000.0000 (see page 741)  TIMER	UARTLCR	RH, type R/\	N, offset 0x	02C, reset	0x0000.00	00 (see pag	ge 716)									
UARTICT, type R/W, offset 0x030, reset 0x0000.0300 (see page 718)  CTSEN RTSEN RTSE DTR RXE TXE LBE LIN HSE EOT SMART SIRLP SIREN UARTEN UARTIFLS, type R/W, offset 0x034, reset 0x0000.0012 (see page 722)  RXIFLSEL TXIFLSEL  UARTIM, type R/W, offset 0x038, reset 0x0000.0000 (see page 724)  LMESIM LME-IIM LMSBIM OEIM BEIM PEIM FEIM RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM UARTIRS, type RO, offset 0x03C, reset 0x0000.0000 (see page 728)  LMESRIS LME-IRIS LMSBIMS OERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS UARTIGR, type RO, offset 0x040, reset 0x0000.0000 (see page 732)  LMESRIS LME-IRIS LMSBIMS OEMIS BEMIS PEMIS FEMIS RTMIS TXMIS RXMIS DSRMIS DCDMIS CTSMIS RIMIS UARTICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIC LME-IIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIS LME-IIII LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 739)  LMESRIS LME-IIII LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTIDMACTL, type R/W, offset 0x044, reset 0x0000.0000 (see page 740)  TIMER  UARTLETH, type R/W, offset 0x094, reset 0x0000.0000 (see page 741)  TIMER																
CTSEN RTSEN RTS DTR RXE TXE LBE LIN HSE EOT SMART SIRLP SIREN UARTEN UARTEN LARTIFLS, type RW, offset 0x034, reset 0x0000.0012 (see page 722)  RXIFLSEL TXIFLSEL  UARTIM, type RW, offset 0x038, reset 0x0000.0000 (see page 724)  LMEGIM LMEIIM LMSBIM OEIM BEIM PEIM FEIM RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM UARTRIS, type RO, offset 0x03C, reset 0x0000.0000 (see page 728)  LMESRIS LMEIRIS LMSBRIS OERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS UARTMIS, type RO, offset 0x040, reset 0x0000.0000 (see page 732)  LMESMIS LMEINIS LMSBRIS OEMIS BEMIS PEMIS FEMIS RTMIS TXMIS RXMIS DSRMIS DCDMIS CTSMIS RIMIS UARTRICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LMESIC LMEIIC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC UARTDMACTL, type RW, offset 0x048, reset 0x0000.0000 (see page 739)  LMESIC LMEITC, type RW, offset 0x094, reset 0x0000.0000 (see page 739)  TISS  UARTLUTH, type RO, offset 0x094, reset 0x0000.0000 (see page 741)  TIMER  TIMER									SPS	WL	.EN	FEN	STP2	EPS	PEN	BRK
DARTIFLS, type R/W, offset 0x034, reset 0x0000.0000 (see page 724)	UARTCTL	., type R/W,	offset 0x0	30, reset 0:	x0000.0300	(see page	718)		1				1			
DARTIFLS, type R/W, offset 0x034, reset 0x0000.0000 (see page 724)														0.5.5		
MARTIM, type RIW, offset 0x038, reset 0x0000.0000 (see page 724)   LMESIM								IXE	LBE	LIN	HSE	EOI	SMARI	SIRLP	SIREN	UARTEN
LMESIM	UARTIFLS	5, type R/W	, offset 0x0	34, reset 0	x0000.0012	2 (see page	722)		I				1			
LMESIM												DVIEL SEL			TVIEI SEI	
LMESIM LMEIIM LMSBIM OEIM BEIM PEIM FEIM RTIM TXIM RXIM DSRIM DCDIM CTSIM RIIM  UARTRIS, type RO, offset 0x03C, reset 0x0000.0000 (see page 728)  LMESRIS LMETRIS LMSBRIS OERIS BERIS PERIS FERIS RTRIS TXRIS RXRIS DSRRIS DCDRIS CTSRIS RIRIS  UARTMIS, type RO, offset 0x040, reset 0x0000.0000 (see page 732)  LMESMIS LMETRIS LMSBRIS OERIS BEMIS PEMIS FEMIS RTMIS TXMIS RXMIS DSRMIS DCDMIS CTSMIS RIMIS  UARTICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LMESIC LMETIC LMSBIC OEIC BEIC PEC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC  UARTDMACTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 739)  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x094, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphiD4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	IIADTIM 1	type P/M e	effect 0v038	rosot OvO	000 0000 (	500 page 7	24)					TOTAL LOCAL			TAII LOLL	
LMESRIS   LME1RIS   LMSBRIS   OERIS   BERIS   PERIS   FERIS   RTRIS   TXRIS   DSRRIS   DCDRIS   CTSRIS   RIRIS	UAKTIWI,	type K/vv, c	iiset uxuso	, reset uxu		see page 7.	24)									
LMESRIS   LME1RIS   LMSBRIS   OERIS   BERIS   PERIS   FERIS   RTRIS   TXRIS   DSRRIS   DCDRIS   CTSRIS   RIRIS	LME5IM	LME1IM	LMSBIM			OEIM	BEIM	PEIM	FEIM	RTIM	TXIM	RXIM	DSRIM	DCDIM	CTSIM	RIIM
LME5RIS   LME1RIS   LMSBRIS   OERIS   BERIS   PERIS   FERIS   RTRIS   TXRIS   RXRIS   DSRRIS   DCDRIS   CTSRIS   RIRIS				C. reset 0x	0000.0000				1							
LME5MIS   LME1MIS   LMSBMIS   DEMIS   BEMIS   PEMIS   FEMIS   RTMIS   TXMIS   RXMIS   DSRMIS   DCDMIS   CTSMIS   RIMIS				,			,									
LME5MIS LME1MIS LMSBMIS	LME5RIS	LME1RIS	LMSBRIS			OERIS	BERIS	PERIS	FERIS	RTRIS	TXRIS	RXRIS	DSRRIS	DCDRIS	CTSRIS	RIRIS
UARTICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LME5IC LME1IC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC  UARTDMACTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 738)  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARTMIS	, type RO,	offset 0x04	0, reset 0x(	0000.0000	see page 7	'32)									
UARTICR, type W1C, offset 0x044, reset 0x0000.0000 (see page 736)  LME5IC LME1IC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC  UARTDMACTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 738)  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)																
LMESIC LME1IC LMSBIC OEIC BEIC PEIC FEIC RTIC TXIC RXIC DSRMIC DCDMIC CTSMIC RIMIC  UARTDMACTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 738)  DMAERR TXDMAE RXDMAE  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	LME5MIS	LME1MIS	LMSBMIS			OEMIS	BEMIS	PEMIS	FEMIS	RTMIS	TXMIS	RXMIS	DSRMIS	DCDMIS	CTSMIS	RIMIS
UARTLCTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 738)  DMAERR TXDMAE RXDMAE  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphiD4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARTICR	, type W1C	, offset 0x0	44, reset 0	x0000.0000	(see page	736)									
UARTLCTL, type R/W, offset 0x048, reset 0x0000.0000 (see page 738)  DMAERR TXDMAE RXDMAE  UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphiD4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)																
UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	LME5IC	LME1IC	LMSBIC			OEIC	BEIC	PEIC	FEIC	RTIC	TXIC	RXIC	DSRMIC	DCDMIC	CTSMIC	RIMIC
UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARTDMA	ACTL, type	R/W, offset	t 0x048, res	set 0x0000	.0000 (see	page 738)									
UARTLCTL, type R/W, offset 0x090, reset 0x0000.0000 (see page 739)  BLEN MASTER  UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)														D14:===	TV	DV2:::
UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)							700							DMAERR	IXDMAE	RXDMAE
UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARTLCT	L, type R/V	V, offset 0x	090, reset (	0x0000.000	(see pag	e 739)									
UARTLSS, type RO, offset 0x094, reset 0x0000.0000 (see page 740)  TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)											D.	EN				MACTED
TSS  UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	IIADTI CO	tune BC	offeet Over	A rocat for	0000 0000	(see sees	740)				BL	LIN.				ININOTER
UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARILOS	, type KU,	OHSEL UXUS	⊶, reset UX		(see page i	+0)									
UARTLTIM, type RO, offset 0x098, reset 0x0000.0000 (see page 741)  TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)								T:	l SS							
TIMER  UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	UARTI TIN	/I. type R∩	offset 0x00	98. reset N	k0000 0000	(see page	741)									
UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)	<b>.</b>	, ., , , , , , , , , , , , , , , , , ,	330. UAU.	,		, pago	,									
UARTPeriphID4, type RO, offset 0xFD0, reset 0x0000.0000 (see page 742)								TIN	/IER							
	UARTPeri	phID4, type	e RO, offset	t 0xFD0, re	set 0x0000	.0000 (see	page 742)									
PID4																
												PI	D4			

		I										1			
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
UARTPer	iphID5, type	e RO, offse	t 0xFD4, re	eset 0x0000	.0000 (see	page 743)									
											DI	D5			
HADTDar	iphID6, type	. DO effec	4 0×FD0 ==	0.0000	0000 (000	744)					PI	פטו			
UARTPER	ірпіре, туре	e KO, onse	t uxrbo, re	set uxuuuu 	.0000 (see	page 744)		1				1			
											DI	D6			
HARTRAE	iphID7, type	BO offor	t OvEDC #		0000 (000	page 745)									
UAINTE	ipilibr, type	ro, onse	t uxi bc, it		.0000 (see	page 743)									
											PI	  D7			
UARTPer	iphID0, type	RO offse	t 0xFF0, re	  set 0x0000	0060 (see	nage 746)									
		,			(000	page : io;									
											PI	ID0			
UARTPer	iphID1, type	RO. offse	t 0xFE4. re	set 0x0000	.0000 (see	page 747)		1							
	.,	,			(000	pago:,									
											PI	I ID1			
UARTPer	iphID2, type	RO, offse	t 0xFE8. re	set 0x0000	.0018 (see	page 748)		1							
	, -, -, -,	.,			(230	, , , , , , , , ,									
											PI	I D2			
UARTPer	iphID3, type	RO, offse	t 0xFEC, re	eset 0x0000	.0001 (see	page 749)		1							
	1	,			,										
											PI	ID3			
UARTPC	ellID0, type	RO, offset	0xFF0, res	et 0x0000.0	00D (see p	age 750)									
											CI	ID0			
UARTPC	ellID1, type	RO, offset	0xFF4, res	et 0x0000.0	OFO (see p	age 751)									
									1		CI	ID1			
UARTPC	ellID2, type	RO, offset	0xFF8, res	et 0x0000.0	005 (see p	age 752)									
											CI	ID2			
UARTPC	ellID3, type	RO, offset	0xFFC, res	set 0x0000.0	00B1 (see	page 753)		•							
											CI	ID3			
Synchr	onous S	erial Inte	erface (S	SSI)											
SSI0 bas	se: 0x4000	.8000													
	se: 0x4000														
SSICR0, t	type R/W, of	ffset 0x000	, reset 0x0	<b>000.0000</b> (s	ee page 76	i9)									
										_					
				CR				SPH	SPO	F	RF		D:	SS	
SSICR1, t	type R/W, of □	rrset 0x004	, reset 0x0	<b>u00.0000</b> (s	ee page 77	1)									
0015-	D#**					\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \					EOT	SOD	MS	SSE	LBM
SSIDR, ty	pe R/W, off	set 0x008,	reset 0x00	UU.0000 (se	e page 773	5)									
							_	1							
00107							DA	ATA							
SSISR, ty	pe RO, offs	et 0x00C, r	eset 0x000	JU.0003 (see	page 774	)									
											DC:		DI:-		
											BSY	RFF	RNE	TNF	TFE
SSICPSR	, type R/W,	offset 0x01	iu, reset 0x	.0000.0000	(see page	776)									
											CPS	DVSR			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
SSIIM, typ	e R/W, offs	et 0x014, ı	reset 0x000	0.0000 (see	e page 777)			1							
												TXIM	RXIM	RTIM	RORIM
SSIRIS, ty	pe RO, offs	set 0x018,	reset 0x00	00.0008 (se	e page 778)							_			
												TXRIS	RXRIS	RTRIS	RORRIS
SSIMIS, ty	pe RO, offs	set 0x01C,	reset 0x00	00.0000 (se	e page 780)	)									
												TXMIS	RXMIS	RTMIS	RORMIS
SSIICR, ty	pe W1C, of	fset 0x020	), reset 0x0	000.0000 (s	ee page 782	2)									
														RTIC	RORIC
SSIDMAC	TL, type R/	W, offset 0	)x024, rese	t 0x0000.00	00 (see pag	e 783)									
														TXDMAE	RXDMAE
SSIPeriph	ID4, type R	O, offset 0	xFD0, rese	et 0x0000.0	000 (see pag	ge 784)									
•	, ,,,					, ,									
											P	l PID4			
SSIPerinh	ID5 type R	O offset (	NYFD4 rese	ot 0x0000 0	000 (see pag	ne 785)					· ·				
oon onpii	ibo, type it	0, 011001	, , , , , , , , , , , , , , , , , , ,		occ pag	<i>je 100)</i>									
											P	ID5			
CCIDarinh	IDC time D	0	\v_FD0 ====	4 00000 0	200 (222 22	706)					•	100			
SSIPERIPRI	ibe, type K	o, onset t	JXFD6, rese	T UXUUUU.UI	000 (see pag	je 700)									
												I De			
2012 : 1	.n					707)					P	PID6			
SSIPeripn	ID7, type R	O, offset C	DXFDC, res	et 0x0000.0	000 (see pa	ge /8/)									
											Р	PID7			
SSIPeriph	ID0, type R	O, offset 0	)xFE0, rese	t 0x0000.00	)22 (see pag	je 788)									
											_				
											P	PID0			
SSIPeriph	ID1, type R	O, offset 0	xFE4, rese	t 0x0000.00	000 (see pag	je 789)									
											P	PID1			
SSIPeriph	ID2, type R	O, offset 0	xFE8, rese	t 0x0000.00	018 (see pag	je 790)									
											Р	PID2			
SSIPeriph	ID3, type R	O, offset 0	xFEC, res	et 0x0000.0	<b>001</b> (see pa	ge 791)									
											Р	PID3			
SSIPCellIC	00, type RC	, offset 0x	FF0, reset	0x0000.000	D (see page	792)		<del></del>							
											С	ID0			
SSIPCellIC	01, type RC	), offset 0x	FF4, reset	0x0000.00F	0 (see page	793)									
											С	ID1			
SSIPCellI	D2, type RC	), offset 0x	FF8, reset	0x0000.000	5 (see page	794)		•							
											C	ID2			
SSIPCellIC	03, type RC	), offset 0x	FFC, reset	0x0000.00	B1 (see page	e 795)		1							
			,		, -, -, -, -,	,									
											0	ID3			
								1							

24	20	20	20	27	26	05	24	20	20	24	20	10	40	47	10
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20 4	19	18	17	16
			(I <sup>2</sup> C) Inte		10	3			, ,	J	7			'	0
nter-int   <sup>2</sup> C Mas		Sircuit	(1 0) 1116	er race											
	i <b>ter</b> se: 0x4002	2.0000													
	se: 0x4002														
2CMSA, ty	ype R/W, o	ffset 0x000	), reset 0x0	000.0000											
											SA				R/S
2CMCS, ty	ype RO, of	fset 0x004	, reset 0x00	00.0020 (R	ead-Only S	tatus Reg	ister)								
									DUODOV	IDLE	ADDLOT	DATACK	ADDAOK	EDDOD	DUOV
IOCMOS A		Stant 0x/00/4		200 0020 (4	frita Only	Cameral Da			BUSBSY	IDLE	ARBLST	DATACK	ADRACK	ERROR	BUSY
ZCIVICS, ty	ype wo, or	iset uxuu4	, reset 0x00	JUU.UU2U (V	rrite-Only	Control Re	gister)								
												ACK	STOP	START	RUN
2CMDR. fv	ype R/W. o	ffset 0x008	B, reset 0x0	000.0000								1			
, •,	,0		, , , , , , , , , ,												
											DA	ATA			
2CMTPR,	type R/W,	offset 0x00	DC, reset 0x	0000.0001											
												TPR			
2CMIMR, 1	type R/W, o	offset 0x01	0, reset 0x0	0000.0000											
															IM
IZCMRIS, t	type RO, of	rtset 0x014	l, reset 0x00	000.0000											
															RIS
I2CMMIS t	type BO o	ffeet NyN18	3, reset 0x0	000 0000											1/10
ZOMINIO, C	type ito, o	IISEL UXU IC	, 16361 020												
															MIS
I2CMICR, t	type WO, o	ffset 0x01	C, reset 0x0	0000.0000											
															IC
I2CMCR, ty	ype R/W, o	ffset 0x020	0, reset 0x0	000.0000											
										SFE	MFE				LPBK
		Circuit	(I <sup>2</sup> C) Inte	erface											
I <sup>2</sup> C Slav															
	se: 0x4002 se: 0x4002														
			00, reset 0x	0000.0000											
												OAR			
2CSCSR,	type RO, o	ffset 0x80	4, reset 0x0	0000.000 (F	Read-Only	Status Re	gister)								
													FBR	TREQ	RREQ
2CSCSR,	type WO, o	offset 0x80	4, reset 0x0	0000.0000 (	Write-Only	Control R	egister)								
															DA
2CSDR, ty	ype R/W, of	rtset 0x808	3, reset 0x00	000.0000											
												) TA			
DCSIMD 4	tyne D/M -	offect fiven	C, reset 0x0	0000 0000							U/	ATA			
ZOSINIK, T	ype R/VV, C	mset uxdu	o, reset uxt												
													STOPIM	STARTIM	DATAIN
													O I OI IIVI	O DALVI HAI	PAIAII

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ı2CSRIS,	type RO, of	fset 0x810	, reset 0x0	000.000											
													STOPRIS	STARTRIS	DATARIS
I2CSMIS,	type RO, of	ffset 0x814	, reset 0x0	000.0000											
													STOPMIS	STARTMIS	DATAMIS
I2CSICR,	type WO, o	ffset 0x818	3, reset 0x0	000.0000											
													STOPIC	STARTIC	DATAIC
	tegrated 4005.4000		Sound (	l <sup>2</sup> S) Inte	rface										
I2STXFIF	O, type WO	, offset 0x0	000, reset 0	×0000.000	(see page	847)									
							TX	FIFO							
							TX	FIFO							
12STXFIF	OCFG, type	R/W, offse	et 0x004, re	set 0x0000	.0000 (see	page 848)									
														CSS	LRS
12STXCF	G, type R/W	, offset 0x0	008, reset 0	x1400.7DF	0 (see page	e 849)									
		JST	DLY	SCP	LRP	W	/M	FMT	MSL						
		S	SZ					SI	OSZ						
12STXLIM	IIT, type R/V	V, offset 0x	00C, reset	0x0000.000	00 (see pag	e 851)									
													LIMIT		
12STXISM	I, type R/W,	offset 0x0	10, reset 0	k0000.0000	(see page	852)									
															FFI
															FFM
I2STXLE\	V, type RO,	offset 0x01	8, reset 0x	0000.0000	(see page 8	353)									
													LEVEL		
12SRXFIF	O, type RO,	offset 0x8	00, reset 0	x0000.0000	(see page	854)									
								FIFO							
							RX	FIFO							
I2SRXFIF	OCFG, type	R/W, offse	et 0x804, re	set 0x0000	0.0000 (see	page 855)									
													FMM	CSS	LRS
12SRXCF	G, type R/W			1		e 856)									
		JST	DLY	SCP	LRP		RM		MSL						
1000000			SZ			055;		SI	OSZ						
12SRXLIN	/IIT, type R/V	v, offset 0x	ασC, reset	UX0000.7F	FF (see pag	ge 859)									
1000:05			40 ::	*****		200)							LIMIT		
12SKXISN	/I, type R/W,	offset 0x8	10, reset 0	XUUUU.0000	(see page	860)									
															FFI
INCOV: T	V 400 = 20	-#+ C C	10	0000 0000	(222	264)									FFM
12SKXLE\	V, type RO,	Ontset 0x81	ıö, reset 0x	.0000.0000	(see page 8	501)									
													LEVE!		
120000	tura Dati d	SE4 0001		000 0000 1	ns 01	20)							LEVEL		
ızəcFG, f	type R/W, of	nset uxC00	J, reset 0x0		see page 86	DZ)									
										DVOLV	TVOLV			DVEN	T)/C1:
										RXSLV	TXSLV			RXEN	TXEN

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	17	0
	oe R/W, offs			1							-	Ū			
, .,,					page ee ./										
										RXREIM	RXSRIM			TXWEIM	TXSRIM
I2SRIS, ty	/pe RO, offs	et 0xC14,	reset 0x00	00.0000 (s∈	e page 866)	)									
										RXRERIS	RXSRRIS			TXWERIS	TXSRRIS
I2SMIS, ty	ype RO, offs	set 0xC18,	reset 0x00	00.0000 (se	e page 868	)									
										RXREMIS	RXSRMIS			TXWEMIS	TXSRMIS
I2SIC, typ	e WO, offse	et 0xC1C, i	reset 0x000	00.0000 (se	e page 870)										
										RXREIC				TXWEIC	
	ller Area		k (CAN)	Module											
	ase: 0x400 ase: 0x400														
CANCTL,	type R/W,	offset 0x00	0, reset 0x	0000.0001	(see page 8	93)									
								TEST	CCE	DAR		EIE	SIE	IE	INIT
CANSTS,	type R/W, o	offset 0x00	04, reset 0x	0000.0000	(see page 8	95)									
								DOFF	EWA DV	ED400	DVOV	TVOV		150	
CANEDD	tura BO a	ff4 0×00	0 =====================================	2000 0000 /	222 222 20	)O)		BOFF	EWARN	EPASS	RXOK	TXOK		LEC	
CANERR	, type RO, o	iiset uxuu	o, reset uxt	) 0000.0000 (	see page os	90) 									
RP				REC							TE				
	type R/W, o	ffset 0x000	C. reset 0x0		see nage 89	19)									
,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		_,		lar page or										
		TSEG2			TSE	EG1		S	JW			BF	RP		
CANINT, 1	type RO, of	fset 0x010	, reset 0x00	000.0000 (s	ee page 900	))									
							IN	ITID							
CANTST,	type R/W, c	ffset 0x01	4, reset 0x0	0000.0000	see page 90	01)									
								RX	7	ГХ	LBACK	SILENT	BASIC		
CANBRP	E, type R/W	, offset 0x	018, reset 0	0000.000	0 (see page	903)									
													BF	RPE	
CANIF1C	RQ, type R/	W, offset (	)x020, rese	t 0x0000.00	001 (see pag	je 904)									
<b>-</b> 1/															
BUSY												MN	UM		
CANIF2C	RQ, type R/	vv, offset (	JXU8U, rese	t UXUUOO.00	u1 (see pag	je 904)									
BUSY												MN	LIM		
	MSK, type I	R/W offeat	0x024 res	et Oxonon	2000 (see 20	ane 905)						IVIN	OIVI		
SANIF IC	mon, type i	www, onset	. JAU24, 165		Jood (See pa	age auu)									
													<u> </u>		
								WRNRD	MASK	ARB	CONTROL	CLRINTPND	NEWDAT / TXRQST	DATAA	DATAB
													NEWD,		

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
CANIF2CI	MSK, type F	R/W, offset	0x084, rese	et 0x0000.0	<b>000</b> (see p	age 905)									
								WRNRD	MASK	ARB	CONTROL	CLRINTPND	NEWDAT / TXRQST	DATAA	DATAB
													2		
CANIF1MS	SK1, type F	k/W, offset	0x028, rese	t 0x0000.FI	FFF (see p	age 908)									
							M	SK							
CANIF2MS	SK1, type F	k/W, offset	0x088, rese	t 0x0000.FI	FFF (see p	age 908)									
							M	SK							
CANIF1MS	SK2, type F	/W, offset	0x02C, rese	et 0x0000.F	FFF (see p	age 909)									
MXTD	MDIR				/				MSK						
CANIF2MS	SK2, type F	/W, offset	0x08C, rese	et 0x0000.F	FFF (see p	age 909)									
MYTE	MDID								MOU						
MXTD	MDIR								MSK						
CANIF1AF	RB1, type R	/W, offset	0x030, rese	t 0x0000.00	)00 (see pa	age 911)									
							l	D							
CANIF2AF	RB1, type R	/W, offset	0x090, rese	t 0x0000.00	)00 (see pa	age 911)		ı		I				I	I
							Į	D							
CANIF1AF	RB2, type R	/W, offset	0x034, rese	t 0x0000.00	)00 (see pa	age 912)									
MOOVAL	VTD	DID							ID						
MSGVAL	XTD	DIR							ID						
CANIF2AF	RB2, type R	/W, offset	0x094, rese	t 0x0000.00	)00 (see pa	age 912)									
MOOVAL	VTD	DID							ID						
MSGVAL	XTD	DIR				014)			ID						
CANIFIMO	LIL, type F	/W, offset	0x038, rese	t 0x0000.00	Juu (see pa	age 914)		I							
NEWBAT	MOOLOT	INITENIE		T)//F	DV/E	DIATEN	TYPOOT	505							
	MSGLST		UMASK	TXIE	RXIE	RMTEN	TXRQST	EOB					DI	LC	
CANIF2M0	CIL, type F	vv, offset	0x098, rese	τ υχυσου.οί	JUU (see pa	age 914)									
NEWDAT	MOCLOT	INITONIO	LIMACK	TVIE	DVIE	DMTEN	TYPOST	FOR					D	1.0	
	MSGLST		UMASK (03C, reset	TXIE	RXIE	RMTEN	TXRQST	EOB				<u> </u>		LC	
CANIFIDA	-ti, type R/\	v, onset 0)	www.reset	UXUUUU.UU(	o (see pa	Je 91/)									
							L,	ATA							
CANIESE	A2 time P*	N offers o	(040 ===================================	0~0000 000	0 (000 75-	ıo 017\	DF.	·.Λ							
CANIFIDA	بد, type K/۱	v, onset 0)	(040, reset	UAUUUU.UUU	v (see pag	Je 91/)									
							D/	ATA							
CANIEAD	21 tuno 124	N offcet 0	(044, reset	0~0000 000	0 (000 000	ıo 017\	DF.	·.Λ							
CANIFIDE	, type R/	v, onset 0)	to44, reset	UXUUUU.UUU	v (see pag	c 91/)									
							D.	ATA							
CANIFAR	22 tura D4	N offers	048, reset	0~0000 000	0 (000 75	o 017\	DF	·.Λ							
CANIFIDE	ב, נype K/\	v, onset 0)	v4o, reset	UAUUUU.UUU	v (see pag	Je 91/)									
							L,	)TA							
CANIFOR	A4 4 D2	N -554-2	.0001	0-0000	0 (00	~ 017\	DF	ATA							
CANIF2DA	41, type R/\	v, orrset 0x	(09C, reset	UXUUUU.U0(	υ (see paç	je 91/)									
							F.	1							
							D/	ATA							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
CANIF2DA	A2, type R/M	/, offset 0x	0A0, reset	0x0000.00	<b>00</b> (see paç	ge 917)									
							DA	TA							
CANIESDE	P4 tupo D/M	L offeet Ov	OA4 rooot	0~0000 00	00 (000 00)	70 017)									
CANIFZDE	B1, type R/W	, onset ux	UA4, Teset	0x0000.00	oo (see paç	Je 917)									
							DA	TA							
CANIF2DE	B2, type R/W	/, offset 0x	0A8, reset	0x0000.00	<b>00</b> (see pag	ge 917)									
							DA	TA							
CANTYPO	Q1, type RO,	offeet Ov1	IOO rocat O	~0000 0000	) (coe page	018)									
CANTARG	ai, type NO,	Oliset ux i	loo, reset o	X0000.000	(see page	910)		I							
							TXR	QST							
CANTXRO	Q2, type RO,	offset 0x1	104, reset 0	x0000.0000	(see page	918)									
							TXR	QST							
CANNWD	A1, type RO	offeat Ov	120 reset 0	~0000 000	nen aas) N	۵10۱									
37,11110	, . <del>, pe</del>	, 511561 01	0, 16361 0		- (occ pay	0 0 10)									
							NEV	/DAT							
CANNWD	A2, type RO	, offset 0x	124, reset 0	0000.000x0	0 (see pag	e 919)									
							NEW	/DAT							
CANMSG	1INT, type R	O. offset 0	x140. reset	0x0000.00	000 (see pa	ae 920)									
	, .,	-,			(	J,									
							INITI					j			
							IIVII	PND							
CANMSG	2INT, type R	O, offset 0	x144, reset	0x0000.00	000 (see pa	ge 920)									
							INT	PND							
CANMSG	1VAL, type F	RO, offset	0x160, rese	t 0x0000.0	000 (see p	age 921)									
							MSG	I SVAL							
						004)	10100	) V/ (L							
CANMSG	2VAL, type F	RO, offset	UX164, rese	et 0x0000.0	000 (see p	age 921)		1							
							MSC	SVAL							
Etherne	et Contro	ller													
	et MAC (E		Offeat)												
	1004.8000	-111611161	Olisetj												
		D.0444.0													
MACRIS/N	MACIACK, ty	pe R/W1C	, offset uxu	100, reset C	X0000.000	U		1							
									PHYINT	MDINT	RXER	FOV	TXEMP	TXER	RXINT
MACIM, ty	pe R/W, offs	set 0x004,	reset 0x000	00.007F											
									PHYINTM	MDINTM	RXERM	FOVM	TXEMPM	TXERM	RXINTM
MACRCTI	tuno D/M	offoot OvO	100 recet 0x	40000 000g											
MACRUIL	_, type R/W,	Oliset UXU	oo, reset ux												
											RSTFIFO	BADCRC	PRMS	AMUL	RXEN
MACTCTL	, type R/W,	offset 0x0	OC, reset 0x	×0000.0000	)										
											DUPLEX		CRC	PADEN	TXEN
MACDATA	A, type RO, o	offset 0x01	0. reset 0x1	0000.0000	(Reads)										
	, -,, -, -, -, -, -, -, -, -, -, -, -, -		.,		,		DYF	DATA							
1							KXL	ATA							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
MACDAT	A, type WO	, offset 0x0	)10, reset 0)	c0000.0000	(Writes)										
								DATA							
		<b></b>					IXL	DATA							
MACIAU,	type R/W, c	offset UXU14	4, reset 0x0								1440	2072			
			MAC								MAC				
MACIA1	tuno P/M o	offect Ov019	8, reset 0x0								WAC	5011			
MIAOIA1,	type rate, c	JIISEL UXU I	, 16361 020												
			MAC	CT6							MAC	CT5			
MACTHR	. type R/W.	offset 0x01	1C, reset 0x												
	, ,,,		,												
												THR	ESH		
МАСМСТ	L, type R/W	V, offset 0x	020, reset 0	×0000.0000	)										
										REGADR	1			WRITE	START
MACMD	, type R/W,	offset 0x02	24, reset 0x	0800.0000											
											D	IV			
MACMTX	D, type R/V	V, offset 0x	02C, reset (	0000.000×0	0										
							ME	TX							
MACMR	(D, type R/V	V, offset 0x	030, reset 0	0x0000.000	0										
							ME	)RX							
MACNP, 1	type RO, of	fset 0x034,	reset 0x000	00.0000				1							
												NI	PR		
MACIR,	type R/W, o	rrset uxu38	3, reset 0x00	100.0000				I							
															NEWTX
MACTS	type P/W o	ffeet OvO3C	c, reset 0x0	000 0000											NEWIX
WIAC13,	type Krvv, o	IISEL UXUSC	, reset uxu												
															TSEN
MACLED	. type R/W.	offset 0x04	10, reset 0x	0000.0100											
	, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1, 1,		,												
					LE	D1							LE	D0	
MDIX, typ	e R/W, offs	et 0x044, r	eset 0x0000	0.0000											
															EN
Ethern	et Contro	oller													
			ssed thro	ough the	MACM	CTL rea	ister)								
			reset 0x100				,								
RESET			ANEGEN		ISO	RANEG	DUPLEX	COLT							
			eset 0x7809		130	RAINEG	DOPLEX	COLI							
wiiti, typ	100X_F			10T_H						ANEGC	RFAULT	ANEGA	LINK	JAB	EXTD
MR2 tvn			eset 0x0161									, 1LOA	-1141	57.15	
	, addie	UAUE, 16	200. 000 101				OLUI	[21:6]							
MR3. tvn	e RO, addre	ess 0x03. re	eset 0xB410	)			001	1							
, -, -, -, -, -, -, -, -, -, -, -, -,	.,		I[5:0]					N	IN .				F	RN	
MR4. tvp	e R/W. addr		reset 0x01E	1		1							•		
NP	,	RF					A3	A2	A1	A0			S		

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
MR5, type	e RO, addre	ss 0x05, re	eset 0x0001												
NP	ACK	RF					A						S		
MR6, type	e RO, addre	ss 0x06, re	eset 0x0000												
											PDF	LPNPA		PRX	LPANEGA
MR16, typ	pe RO, addr	ess 0x10,	reset 0x004	0											
							(	SR							
MR17, typ	pe R/W, add	ress 0x11,	reset 0x000	02											
	FASTRIP	EDPD		LSQE			FASTEST						FGLS	ENON	
MR27, typ	pe RO, addr	ess 0x1B,	reset -												
											XPOL				
MR29, typ	pe RO, addr	ess 0x1D,	reset 0x000	00											
								EONIS	ANCOMPIS	RFLTIS	LDIS	LPACKIS	PDFIS	PRXIS	
MR30, typ	pe R/W, add	ress 0x1E	, reset 0x00	00											
								EONIM	ANCOMPIM	RFLTIM	LDIM	LPACKIM	PDFIM	PRXIM	
MR31, typ	pe R/W, add	ress 0x1F,	reset 0x004	40								1			
		,	AUTODONE									SPEED			SCRDIS
Univer	aal Saria	l Buo /II		troller											
	4005.0000		ISB) Con	troner											
			x000, reset	0x00 (see )	nage 1011)										
	, <b>., p</b>	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	<b>UNCO</b> (000)	pago .o,							FUNCADDE	2		
LISBPOW	/FR tyne R/	W offset (	0x001, reset	0x20 (OT	3 Δ / Host N	Mode) (see	nage 1012	)				TONORDE			
OOD! O!!	Lit, type it	vv, onset c	7,001,16361	0,20 (01)	3 A / 1103t II	noue) (see	page 1012	,				RESET	RESLIME	SUSPEND	PWRDNPHY
HEBBOW	IED tupo Di	NA office (	1v001 rocot	0×20 (OT	C P / Dovice	Mode) (or	20 2000 10	12\				INLOCI	KLSOWL	303FLIND	TWICHTII
USBFUW	EK, type K	vv, onset c	0x001, reset	. UX2U (UTC	3 B / Device	e wode) (Se	ee page 10		COLLCONN			DECET	DECLIME	CLICDENID	DWDDNDI N
HODTYIO	t BO -	£4 000	0 4 0 0	000 /	1015\			ISOUP	SOFTCONN			RESET	RESUIVIE	SUSPEND	PWRDNPHI
			2, reset 0x0			FDO	EDO		EDO	EDE		_ FD0	EDO	ED4	FDO
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	EP0
			4, reset 0x0									T			
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	
			06, reset 0xl												
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	EP0
			08, reset 0x												
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	
USBIS, ty	pe RO, offs	et 0x00A,	reset 0x00 (	OTG A / H	ost Mode) (	(see page 1	023)								
								VBUSERR	SESREQ	DISCON	CONN	SOF	BABBLE	RESUME	
USBIS, ty	pe RO, offs	et 0x00A,	reset 0x00 (	OTG B / D	evice Mode	) (see page	1023)								
										DISCON		SOF	RESET	RESUME	SUSPEND
USBIE, ty	pe R/W, off	set 0x00B,	, reset 0x06	(OTG A / H	lost Mode)	(see page	1026)								
								VBUSERR	SESREQ	DISCON	CONN	SOF	BABBLE	RESUME	
USBIE, ty	pe R/W, off	set 0x00B,	, reset 0x06	(OTG B / E	Device Mod	e) (see pag	e 1026)								
										DISCON		SOF	RESET	RESUME	SUSPEND
USBFRAI	ME, type RC	), offset 0x	(00C, reset (	0x0000 (se	e page 102	9)									
										FRAME					
USBEPID	X, type R/W	/, offset 0x	00E, reset 0	)x00 (see p	age 1030)										
													EP	IDX	
USBTEST	Γ, type R/W,	offset 0x0	0F, reset 0x	00 (OTG A	/ Host Mod	de) (see pag	ge 1031)								
								FORCEH	FIFOACC	FORCEFS					
USBTEST	Γ, type R/W.	offset 0x0	0F, reset 0x	00 (OTG B	/ Device M	ode) (see r	page 1031)								
			,	, <del>-</del>		, ,,,	3/		FIFOACC						
USBEIFO	0. type R/W	offset Ovi	020, reset 0:	×0000 000	) (see nage	1033)			27.00						
	-, -, -, -, -, -, -, -, -, -, -, -, -, -	, 5	,		, coo page	.000)	ED	DATA							
								DATA							
							LF	2/3//							

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBFIFO <sup>2</sup>	1, type R/W	, offset 0x0	)24, reset 0:	x0000.0000	(see page	1033)									
								DATA							
HEBEIEO	2 turns D/M	- ff t 0 · r	20		2 /222 222	1022)	EPI	DATA							
USBFIFUZ	2, type R/W	, onset uxt	120, Teset 0	X0000.0000	(see page	1033)	EDI	DATA							
								DATA							
USBFIFO	3, type R/W	. offset 0x0	2C. reset 0	x0000.000	0 (see page	1033)									
	-, 31-	,	,		. (		EPI	DATA							
							EPI	DATA							
USBFIFO4	4, type R/W	, offset 0x0	30, reset 0	x0000.000	(see page	1033)									
							EPI	DATA							
							EPI	DATA							
USBFIFO	5, type R/W	, offset 0x0	034, reset 0	×0000.0000	(see page	1033)									
								DATA							
HODELEC	0.6	-#		-0000 000	<b>3</b> /	4000;	EPI	DATA							
OSREILO(	6, type R/W	, offset 0x0	ເວຣ, reset 0:	xUUUU.000(	(see page	1033)	FD	DATA							
								DATA							
USBFIFO	7, type R/W	. offset 0x1	3C. reset 0	x0000.000	0 (see page	1033)									
	., .,	,	-,		- ( p-9-	,	EPI	DATA							
								DATA							
USBFIFO	8, type R/W	, offset 0x0	)40, reset 0:	x0000.0000	(see page	1033)									
							EPI	DATA							
							EPI	DATA							
USBFIFO	9, type R/W	, offset 0x0	)44, reset 0:	x0000.0000	(see page	1033)									
								DATA							
	10 / 50					1000)	EPI	DATA							
USBFIFO	10, type R/V	v, offset ux	(U48, reset (	UXUUUU.UU	Ju (see page	e 1033)	EDI	DATA							
								DATA							
USBFIFO <sup>2</sup>	11, type R/V	V. offset 0x	04C. reset	0x0000.00	00 (see page	e 1033)		5,11,1							
	, ., po	.,	,	0,0000.00	oo (ooo pag	0 .000)	EPI	DATA							
								DATA							
USBFIFO <sup>2</sup>	12, type R/\	V, offset 0x	(050, reset (	0x0000.000	00 (see page	e 1033)									
							EPI	DATA							
							EPI	DATA							
USBFIFO <sup>2</sup>	13, type R/V	V, offset 0x	(054, reset (	0x0000.000	00 (see page	e 1033)									
								DATA							
HEBEICO	44 tura Da	N offert o	,0E0 rage 1	020000 000	20 (202 22	1022\	EPI	DATA							
USBFIFU'	14, type R/\	v, onset 0)	luso, reset (	UXUUUU.UU	u (see page	= 1033)	FDI	DATA							
								DATA							
USBFIFO <sup>2</sup>	15, type R/\	V, offset 0x	05C, reset	0x0000.00	00 (see pag	e 1033)									
							EPI	DATA							
							EPI	DATA							
USBDEVO	CTL, type R	/W, offset (	0x060, reset	t 0x80 (see	page 1035)	)									
								DEV	FSDEV	LSDEV	VE	BUS	HOST	HOSTREQ	SESSION
USBTXFIF	FOSZ, type	R/W, offse	t 0x062, res	et 0x00 (s	ee page 103	37)									
											DPB		S	IZE	
USBRXFII	FOSZ, type	R/W, offse	t 0x063, res	set 0x00 (s	ee page 103	37)						1			
											DPB		S	IZE	

				T								T			
31	30	29	28 12	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13		11	10	9 - 4000)	8	7	6	5	4	3	2	1	0
USBIXE	IFOADD, typ	e R/VV, OTT	set uxu64, i	reset uxuuu 	(see page	e 1038)					ADDR				
HEDDAE	IEOADD tur	o B/M off	ant Ovoce	rooot Ov000	)() (aaa naa	0 1029)					ADDR				
USBKAF	FIFOADD, typ	e K/VV, OII	Set uxuoo,	reset uxuut	(see pag	1036)					ADDR				
HERCON	NTIM tuno B	IM offeet	0×074 roos	t OvEC (oo	2 2000 1030	2)					ADDR				
USBCUR	NTIM, type R	w, onset	JXU/A, rese	et uxac (see	e page 103	9)			\A/T/	CON			10/	TID	
HEDVDI	EN tura DA	V -ff4 0:	.07D	0×20 /222	222 1040				VVIC	JON			VV	טוו	
USBVPL	.EN, type R/V	v, onset u	(U/B, reset	UX3C (See	page 1040)						VE	LEN			
Hebrer	OF 6 ma D/M	/ offeet Ov	.07D ====4	0.77 (000 1	2000 1011)						VP	LEIN			
USBFSE	OF, type R/V	v, onset ox	tord, reset	uxii (see p	Jage 1041)						ESE	EOFG			
HEDI EE	OF tune B/M	/ offeet Ox	.07E #00.0t	0×72 (000 n	2000 1042)						1 31	-OI G			
USBLSE	OF, type R/V	v, onset ox	tu/⊑, reset	<b>UX72</b> (See p	Jage 1042)						1 00	EOFG			
HEDTYE	INCADDBO	tuno B/M	offoot 0v0	90 rooot 0v	,00 (aaa na	ao 1042)					LOD	OFG			
USBIAF	UNCADDR0,	type K/vv,	Oliset uxu	ou, reset ux	(see pa	ge 1043)						ADDR			
IISBTYE	UNCADDR1,	type P/W	offeet 0v0	88 reset Ny	<b>/00</b> (see na	ne 1043)						ADDIX			
OODIXI	ONOADDIKI,	type it.	Oliset Oxo	00, 16361 02	(see pa	gc 1040)						ADDR			
USRTYF	UNCADDR2,	type R/W	offset Ovo	90. reset Ov	(00 (see na	ae 1043)									
JUDIA	CHOADDINE,	.Jpc 1044,	J.1001 0X0	- J, 10361 UX	tocc pa	30 1040)						ADDR			
USBTXF	UNCADDR3,	type R/W	offset 0x0	98. reset 0x	( <b>00</b> (see na	ge 1043)									
				,	(200 pa	J. 12.0)						ADDR			
USBTXF	UNCADDR4,	type R/W.	offset 0x0	A0. reset 0:	x00 (see pa	ige 1043)									
		<b>7</b> , <b>7</b>		,	(							ADDR			
USBTXF	UNCADDR5,	type R/W.	offset 0x0	A8, reset 0	<b>x00</b> (see pa	ige 1043)									
												ADDR			
USBTXF	UNCADDR6,	type R/W,	offset 0x0	B0, reset 0	x00 (see pa	ige 1043)									
												ADDR			
USBTXF	UNCADDR7,	type R/W,	offset 0x0	B8, reset 0	x00 (see pa	ige 1043)									
												ADDR			
USBTXF	UNCADDR8,	type R/W,	offset 0x0	C0, reset 0	x00 (see pa	ige 1043)									
												ADDR			
USBTXF	UNCADDR9,	type R/W,	offset 0x0	C8, reset 0	x00 (see pa	ige 1043)									
												ADDR			
USBTXF	UNCADDR1	0, type R/V	V, offset 0x	0D0, reset (	0x00 (see p	age 1043)									
												ADDR			
USBTXF	UNCADDR11	I, type R/V	v, offset 0x	0D8, reset (	<b>0x00</b> (see p	age 1043)									
						4						ADDR			
USBIXF	UNCADDR1	z, type R/V	v, offset üx	u⊑u, reset (	uxuu (see p	age 1043)						ADDD			
HEDTYF	IINC ADDD4	tuna DA	V offort 0	0E8 ====+1	1v00 /000 -	age 1043)						ADDR			
CODIAL	UNCADDR1	, type r/v	, onset ux	o⊑o, reset t	oauu (see p	age 1043)						ADDR			
USRTYF	UNCADDR1	1. type R/V	V. offset Nv	OFO, reset (	)x00 (see n	age 1043)						,,,,,,,,,,			
222171		., ., po 104	., 5.1551 08	, 100011	(occ p	_gc 10-10 <i>)</i>						ADDR			
USBTXF	UNCADDR1	5, type R/V	V, offset 0×	0F8, reset 0	0x00 (see n	age 1043)									
			,	-,	( P	3: -:-/						ADDR			
USBTXH	IUBADDR0, t	ype R/W, o	offset 0x08	2, reset 0x0	0 (see pag	e 1045)			1			<u> </u>			
		<u> </u>				· · ·						ADDR			
USBTXH	IUBADDR1, t	ype R/W, o	offset 0x08	A, reset 0x0	00 (see pag	e 1045)									
												ADDR			
USBTXH	IUBADDR2, t	ype R/W, o	offset 0x09	2, reset 0x0	00 (see pag	e 1045)									
					<u>.                                 </u>							ADDR			
USBTXH	IUBADDR3, t	ype R/W, o	offset 0x09	A, reset 0x0	00 (see pag	e 1045)									
						-						ADDR			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBTXHI	JBADDR4,	type R/W. o	offset 0x0A	2. reset 0x0	00 (see pag	e 1045)		l				1			
	•	, ,		,	(***   *** )	,						ADDR			
USBTXHI	JBADDR5,	type R/W. o	offset 0x0A	A. reset 0x	00 (see pag	ie 1045)									
002.7		.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	ee (ooo pag	,						ADDR			
IISRTYHI	JBADDR6,	type R/W c	offeet OvOR	2 reset fly(	ner ees) ne	o 1045)						ADDIT			
COBTAIN	DADDING,	typo rati, c	MOUL OXOD.	L, 10001 0X1	(occ pag	0 1040)						ADDR			
HEDTYHI	JBADDR7,	tuno D/M o	ffoot OvOP	A rooot Ov	00 (000 000	1045)						ADDIX			
USBIAIR	JBADDK1,	type K/vv, C	JIISEL UXUDA	H, TESEL UX	oo (see pag	1043)						ADDR			
HEDTYHI	IDADDD0	tuno D/M o	ffoot 0v0C	2 rooot Ov	<b>10</b> (222 pag	o 1045)						ADDR			
USBIANC	JBADDR8,	type R/vv, c	JIISEL UXUC	z, reset uxt	(see pag	e 1045)						ADDR			
HEDTYHI	IBADDB0	tura DAM a		A was at 0w	00 /222 222	- 101F)						ADDR			
USBIAR	JBADDR9,	type R/vv, c	onset uxuc	A, reset ux	oo (see pag	e 1045)						ADDD			
HODEVIII	IDADDD40	4 D/M	- ff 4 001	20 4 0-	-00 /	4045)						ADDR			
USBIXH	JBADDR10	, type R/vv,	OTTSET UXUL	J2, reset ux	(uu (see pa	ge 1045)						ADDD			
						1015)						ADDR			
USBIXH	JBADDR11	, type R/W,	offset UXUL	DA, reset U	xuu (see pa	ge 1045)						4000			
												ADDR			
USBTXHI	JBADDR12	, type R/W,	offset 0x0E	E2, reset 0x	(00 (see pag	ge 1045)									
												ADDR			
USBTXH	JBADDR13	, type R/W,	offset 0x0E	EA, reset 0	<b>k00</b> (see pa	ge 1045)									
												ADDR			
USBTXHI	JBADDR14	, type R/W,	offset 0x0F	2, reset 0x	00 (see pag	ge 1045)									
												ADDR			
USBTXH	JBADDR15	, type R/W,	offset 0x0F	A, reset 0	(00 (see pa	ge 1045)									
												ADDR			
USBTXHI	JBPORT0, 1	type R/W, o	ffset 0x083	, reset 0x0	0 (see page	1047)									
												PORT			
USBTXHI	JBPORT1, 1	type R/W, o	ffset 0x08E	3, reset 0x0	00 (see page	e 1047)									
												PORT			
USBTXHI	JBPORT2, 1	type R/W, o	ffset 0x093	, reset 0x0	0 (see page	1047)									
												PORT			
USBTXHI	JBPORT3, 1	type R/W, o	ffset 0x09E	3, reset 0x0	00 (see page	e 1047)									
												PORT			
USBTXHI	JBPORT4, 1	type R/W, o	ffset 0x0A3	3, reset 0x0	00 (see page	e 1047)									
												PORT			
USBTXHI	JBPORT5, 1	type R/W, o	ffset 0x0Al	3, reset 0x(	00 (see pag	e 1047)									
												PORT			
USBTXH	JBPORT6, 1	type R/W, o	ffset 0x0B3	3, reset 0x0	0 (see page	e 1047)									
												PORT			
USBTXH	JBPORT7, 1	type R/W, o	ffset 0x0BI	3, reset 0x0	00 (see pag	e 1047)									
												PORT			
USBTXHI	JBPORT8, 1	type R/W, o	ffset 0x0C3	3, reset 0x0	0 (see page	e 1047)									
												PORT			
USBTXHI	JBPORT9, 1	type R/W, o	ffset 0x0Cl	3, reset 0x0	00 (see pag	e 1047)									
												PORT			
USBTXHI	JBPORT10,	type R/W,	offset 0x0E	3, reset 0x	00 (see pag	ge 1047)									
												PORT			
USBTXHI	JBPORT11,	type R/W,	offset 0x0D	B, reset 0	(00 (see pa	ge 1047)									
												PORT			
USBTXHI	JBPORT12,	type R/W,	offset 0x0E	3, reset 0x	.00 (see pag	ge 1047)									
						<u> </u>						PORT			
USBTXHI	JBPORT13,	type R/W.	offset 0x0E	B, reset 0	(00 (see pa	ge 1047)									
		/				- '						PORT			

				1 07		0.5		T 00		0.1		1 40	40	4=	
31 15	30 14	29 13	28 12	27	26 10	25 9	24 8	23 7	22 6	21 5	20 4	19	18	17	16
			offset 0x0F	l		_	0	1 '	0	3	-	] 3		'	
USBIAIIU	JBFORT 14,	type K/VV,	Oliset Oxol	J, leset ux	ioo (see pa	ge 1047)						PORT			
USBTXHU	IBPORT15	type R/W	offset 0x0F	FB. reset 0x	(00 (see na	ge 1047)						1 01(1			
		, t <b>y p</b> 0 ,	0.1001 0.01	2,1000101	100 (000 pa	90 .0,						PORT			
USBRXFU	JNCADDR1	. type R/W	, offset 0x0	8C. reset 0	x00 (see pa	age 1049)									
		, 31	,	,		3,						ADDR			
USBRXFU	JNCADDR2	, type R/W	, offset 0x0	94, reset 0	x00 (see pa	ge 1049)									
						· /						ADDR			
USBRXFU	JNCADDR3	, type R/W	, offset 0x0	9C, reset 0	<b>x00</b> (see pa	age 1049)									
												ADDR			
USBRXFU	JNCADDR4	, type R/W	, offset 0x0	A4, reset 0	x00 (see pa	age 1049)									
												ADDR			
USBRXFU	INCADDR5	, type R/W	, offset 0x0	AC, reset 0	x00 (see pa	age 1049)									
												ADDR			
USBRXFU	INCADDR6	, type R/W	, offset 0x0	B4, reset 0	<b>x00</b> (see pa	age 1049)									
												ADDR			
USBRXFU	JNCADDR7	, type R/W	, offset 0x0	BC, reset 0	x00 (see pa	age 1049)									
												ADDR			
USBRXFU	INCADDR8	, type R/W	, offset 0x0	C4, reset 0	x00 (see pa	age 1049)									
												ADDR			
USBRXFU	INCADDR9	, type R/W	, offset 0x0	CC, reset 0	x00 (see pa	age 1049)									
												ADDR			
USBRXFU	JNCADDR1	0, type R/V	V, offset 0x	0D4, reset	<b>0x00</b> (see p	age 1049)									
												ADDR			
USBRXFU	JNCADDR1	1, type R/V	V, offset 0x	ODC, reset	<b>0x00</b> (see p	page 1049)			1			4000			
HODDYFI	ING A DDDA	0 to D.0	N - 55 4 O	054	000 /	4040)						ADDR			
USBRAFU	INCADDR1	2, type R/V	V, offset 0x	UE4, reset (	uxuu (see p	age 1049)						ADDR			
HERRYEH	INCADDB1	3 type P/V	V, offset 0x	OEC rosot	0×00 (see r	2200 1040)						ADDR			
OODICKI O	MOADDIKI	o, type to	v, onset ox	.000, 16361	0,00 (300 )	Jage 1043)						ADDR			
USBRYFU	INCADDR1	4 type R/V	V, offset 0x	0F4 reset (	N <b>yNN</b> (see n	ane 1049)						ABBIT			
		., ., po	.,	,	enee (000 p	.ugo 1010/						ADDR			
USBRXFU	JNCADDR1	5, type R/V	V, offset 0x	0FC, reset	0x00 (see p	page 1049)									
						,						ADDR			
USBRXHL	JBADDR1,	type R/W,	offset 0x08	E, reset 0x0	00 (see pag	je 1051)									
												ADDR			
USBRXHL	JBADDR2,	type R/W,	offset 0x09	6, reset 0x0	00 (see pag	e 1051)									
												ADDR			
USBRXHU	JBADDR3,	type R/W,	offset 0x09	E, reset 0x0	00 (see pag	je 1051)									
												ADDR			
USBRXHU	JBADDR4,	type R/W,	offset 0x0A	6, reset 0x	00 (see pag	je 1051)									
												ADDR			
USBRXHL	JBADDR5,	type R/W,	offset 0x0A	E, reset 0x	00 (see pag	ge 1051)									
												ADDR			
USBRXHU	JBADDR6,	type R/W,	offset 0x0B	6, reset 0x	00 (see pag	je 1051)			I						
				_								ADDR			
USBRXHU	JBADDR7,	type R/W,	offset 0x0B	BE, reset 0x	00 (see pag	ge 1051)									
												ADDR			
USBRXHU	JBADDR8,	type R/W,	offset 0x0C	6, reset 0x	00 (see pag	je 1051)			I						
				_								ADDR			
USBRXHL	JBADDR9,	type R/W,	offset 0x0C	∟, reset 0x	เบบ (see pag	ge 1051)						ADDD			
												ADDR			

31	30	29	20	27	26	25	24	23	22	21	20	10	10	17	16
15	14	13	28 12	27	26 10	25 9	24 8	7	6	21 5	4	19	18	17	16
			, offset 0x0l	l				<u> </u>	ŭ		,			<u>'</u>	•
CODICATIO	DADDIKIO,	, type Idit	, onset oxo	D0, 16361 0.	AUU (SCC PA	igc 1001)						ADDR			
USBRXHU	BADDR11.	type R/W.	, offset 0x0l	DE. reset 0	x00 (see pa	ae 1051)						7.55.1			
			,	,		J ,						ADDR			
USBRXHU	BADDR12,	, type R/W	, offset 0x0I	E6, reset 0:	x00 (see pa	ge 1051)									
						· ·						ADDR			
USBRXHU	BADDR13,	, type R/W	, offset 0x0l	EE, reset 0	x00 (see pa	ige 1051)									
												ADDR			
USBRXHU	BADDR14,	, type R/W	, offset 0x0l	F6, reset 0	x00 (see pa	ge 1051)		1							
												ADDR			
USBRXHU	BADDR15,	, type R/W	, offset 0x0l	FE, reset 0	<b>x00</b> (see pa	ige 1051)									
												ADDR			
USBRXHU	BPORT1, t	ype R/W,	offset 0x08F	F, reset 0x0	0 (see page	e 1053)									
												PORT			
USBRXHU	BPORT2, t	type R/W, o	offset 0x097	7, reset 0x0	00 (see page	e 1053)			1						
						1055						PORT			
USBRXHU	BPORT3, t	ype R/W, o	offset 0x09F	⊦, reset 0x0	(see page	e 1053)						DODT			
HEDDAMII	PROPTA 6	uno D/M	offoot OvO A	7 rooot 0v/	00 (000 pag	o 10E3)						PORT			
USBRAHU	BFOK 14, t	ype R/vv, c	offset 0x0A	i, reset uxt	(see pag	e 1055)						PORT			
USBRXHU	BPORT5. t	vne R/W. o	offset 0x0Al	F. reset 0x0	00 (see page	e 1053)						101(1			
COBIONIO	D. 0.11.0, t	урс гат, с	onoct oxort	1,10001001	o (occ pag	C 1000)						PORT			
USBRXHU	BPORT6, t	type R/W, o	offset 0x0B	7, reset 0x0	00 (see page	e 1053)									
	·			<u>,                                      </u>								PORT			
USBRXHU	BPORT7, t	ype R/W,	offset 0x0Bl	F, reset 0x0	00 (see page	e 1053)									
												PORT			
USBRXHU	BPORT8, t	ype R/W,	offset 0x0C	7, reset 0x0	00 (see pag	e 1053)									
												PORT			
USBRXHU	BPORT9, t	ype R/W,	offset 0x0Cl	F, reset 0x0	00 (see page	e 1053)									
												PORT			
USBRXHU	BPORT10,	type R/W,	, offset 0x0[	D7, reset 0	x00 (see pa	ge 1053)									
												PORT			
USBRXHU	BPORT11,	type R/W,	offset 0x0E	DF, reset 0>	(00 (see pa	ge 1053)			I			DODT			
HEDDAIII	DDODT42	4.ma D/M	offe of OvO	F7 ==== 1 0:	·00 /222 72	~~ 10F2\						PORT			
USBKARU	BPURI12,	type R/vv,	, offset 0x0E	E7, reset 02	(see pag	ge 1053)						PORT			
USBRXHII	BPORT13	type R/W	offset 0x0E	EF, reset Λ	(00 (see nad	ge 1053)						. 51(1			
322.0010		.,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,	.,	oce pay	J - 1000)						PORT			
USBRXHU	BPORT14,	type R/W,	, offset 0x0F	F7, reset 0>	(00 (see pag	ge 1053)			1						
	<u> </u>	,										PORT			
USBRXHU	BPORT15,	type R/W,	, offset 0x0F	FF, reset 0x	(00 (see pag	ge 1053)									
												PORT			
USBTXMA	XP1, type	R/W, offse	t 0x110, res	et 0x0000	(see page 1	055)									
										MAXLOAD					
USBTXMA	XP2, type	R/W, offse	t 0x120, res	set 0x0000	(see page 1	055)				MAXLOAD					
USBTXMA	XP3, type	R/W, offse	t 0x130, res	set 0x0000	(see page 1	055)									
										MAXLOAD					
USBTXMA	XP4, type	R/W, offse	t 0x140, res	set 0x0000	(see page 1	055)									
										MAXLOAD					
USBTXMA	XP5, type	R/W, offse	t 0x150, res	set 0x0000	(see page 1	055)									
										MAXLOAD					

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBTXMA	AXP6, type	R/W, offset	t 0x160, res	et 0x0000	(see page 1	1055)									
										MAXLOAD					
USBTXM/	AXP7, type	R/W, offset	t 0x170, res	et 0x0000	(see page 1	1055)									
										MAXLOAD					
USBTXM/	AXP8, type	R/W, offset	t 0x180, res	et 0x0000	(see page 1	1055)									
										MAXLOAD					
USBTXM	AXP9, type	R/W, offset	t 0x190, res	et 0x0000	(see page 1	1055)									
										MAXLOAD					
USBTXM	AXP10, typ	e R/W, offse	et 0x1A0, re	eset 0x000	0 (see page	1055)									
										MAXLOAD					
USBTXM/	AXP11, type	R/W, offse	et 0x1B0, re	set 0x000	) (see page	1055)									
	7.31					,				MAXLOAD					
USBTXM/	AXP12, type	e R/W. offse	et 0x1C0. re	eset 0x000	0 (see page	1055)									
						,				MAXLOAD					
USBTYM	AXP13, type	R/W offs	et 0x1D0 re	eset OxOOO	n (see nage	1055)									
1701117		, 01131			- (ooo page	,				MAXLOAD					
USBTYM	AXP14, type	R/W offer	et Oy1E0	set Ovono	n (see page	1055)				0.2000					
CODIANI		o ita vv, oiis	5t 0x 1E0, 16		(see page	1000)				MAXLOAD					
LICRTYM	AXP15, type	o P/M offer	ot Ov1EO ro	eat Ov000	) (see page	1055)				WARLOAD					
OODIANI		o raw, ons	J. O. 11 0, 10		(see page	1000)				MAXLOAD					
HEBCEDI	L0, type W1	C offeet 0	v102 rosot	0×00 (OTG	A / Host N	Anda) (see	page 1057)			WARLOAD					
USBCSKI	Lu, type w	ic, onset o	x 102, reset	0000 (010	A / HUSL N	ioue) (see	page 1057)	NAKTO	STATUS	REQPKT	ERROR	SETUP	CTALLED	TXRDY	RXRDY
HEBCEBI	L0, type W1	C offeet 0	v102 rooot	0×00 (OTC	P / Davier	Mode) (se	0 2000 10E		31A103	REQFNI	ERROR	SETUP	STALLED	IARDI	KARDI
USBUSKI	Lu, type w	o, onset o	x 102, 1636t	0.00 (010	5 D / Device	s wiode) (se	e page 103		RXRDYC	STALL	SETEND	DATAEND	STALLED	TXRDY	RXRDY
HEBCEBI	H0, type W	IC offeet 0	v402 rooot	0×00 (OT	A / Hoot I	Mada) (aaa	nogo 1061)		IXIXDIC	STALL	SETEND	DAIALND	STALLED	TANDI	IXINDT
USBUSKI	ilo, type vv	ic, onset o	X 103, 16361	0,000 (010	A/HOSCI	vioue) (see	page 1001)						DTWE	DT	FLUSH
HEBCEBI	H0, type W	IC offeet 0	v102 rooot	0×00 (OT	P / Dovie	Mode) (or	20 2000 106	:1\					DIWL		1 20011
CODOCIN	ilo, type W	10, 011361 0	X100, 16361	0.00 (010	J D / Device	s wode) (se	ce page 100	, 1,							FLUSH
USBCOU	NT0, type F	O offeet 0	v108 reset	. NvNN (see	nage 1063	1									1 20011
	itio, type i	10, 011001 0	x 100, 10001	OXOO (SCC	page 1000,							COUNT			
LISRTYPE	≣0, type R/V	V offset Ox	10A reset	N <b>y</b> NN (see r	nage 1064)										
0051112	_0, type 101	i, onoci ux	102, 10001	oxoo (occ )	ougo 1004)			SDI	EED						
IISBNAKI	LMT, type F	P/W offeet I	Nv10R rose	at NvNN (se	nage 106	5)		011							
OODIVAIN	Limit, type i	uv, onserv	ож го <b>д</b> , гезе	30,000 (30)	c page 100.	<i>5</i> )							NAKLMT		
LISBTYCS	SRL1, type	P/W offeet	0v112 ros	et UvUU (O	TG A / Host	Mode) (se	e nage 106	6)					IVAILUIT		
OODIXOO	JILLI, type	1011, 011361	OX112, 163	O) 00x0 13	I O A / IIO3	inioue) (sc	c page 100	NAKTO	CLEDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
LISBTYCE	SRL2, type	R/M offect	0v122 roo	ot Oven (O	TG A / Hoos	t Mode) (co	e nage 106		OLIND!	J./ LEELD	52.01	1 . 20011	LIMON	. II OINE	TAILD I
CODIAGO	J. L. L. Lype	, 511361	VA 144, 185	O. 0200 (O	. 5 A / 1105	. modej (Se	o page 100	NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTYC	SRL3, type	R/W offect	0x132 roo	et U^U (C.	TG A / Hoos	t Mode) (so	e nace 10e		OLINDI	JIALLED	JL I UF	1 1 1 1 1 1 1 1 1	LIMON	I II ONE	IANDI
CODIACO	JILJ, LYPE	IVVV, UIISEL	UA 132, 188	or 0000 (O	I G A / HUS	(Se	c page 100	NAKTO	CLEDT	STALLED	SETUP	FLUSH	EDDUD	FIFONE	TXRDY
HEBTYC	2DI 4 +	D/M offers	0v142	ot Oron (C	TG A / !!==	t Mode\ /a-	e nace 100		CLRDT	STALLED	SLIUF	I LUSH	ERROR	I II ONE	IVIOI
USBIACS	SRL4, type	ravv, onset	UX 142, FBS	er 0x00 (O	I G A / HOS	. wioue) (Se	e page 106		CLEDT	STALLED	SETUP	FLUSH	EDDUD	FIEONE	TYDDV
HEBTYC	PDI E 4	DAN offer-	0v4E2	ot 0v00 (O	TC A / U.s	Model /c-	0 0000 100	NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBIACS	SRL5, type	IN/VV, UITSET	UX IO∠, FeS	er nxnn (O	I G A / HOS	. wiode) (Se	e page 106		CLEDT	CTALLED	CETUD	ELLIGIA	EDDOD	EIEONE	TVDDV
HEBTYC	CDI 6 4	DAN offer-	0v460	ot 0v00 (O	TC A / U.s	Model /c-	0 0000 100	NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBIACS	SRL6, type	IN/VV, UITSET	UX I D∠, FeS	er nxnn (O	I G A / HOS	. wiode) (Se	e page 106		CLDDT	CTALLED	CETUD	ELLICIT	EDDOD	EIEONE	TYDDY
HEDTYC	PDI 7 5	DAM -#- 1	0.470	-4 002 (2)	TO A /!!-	• Mad - \ /	a nag- 400	NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
OSBIXCS	SRL7, type	K/W, offset	ux1/2, res	et uxuu (O	IG A / Hos	tivlode) (se	e page 106		01555	0741:	057::-	F111011		FIEC.:-	TVEST
HODEYC	DDI 0 :	DA4 # :	0100	-4.000 (=:			155	NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
OPRIXCS	SRL8, type	r./vv, offset	ux182, res	et uxuu (O	IG A / Hos	(se	e page 106		OI DDT	OTAL: 55	OFTUD	FLUOU	EDECE	FIECUS	TVPPV
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL9, type	K/W, offset	ux192, res	et 0x00 (O	IG A / Hos	t Mode) (se	e page 106		01555	0741: =5	057::-	E		FIEC.:-	TVEST
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
				l	_				0	3	7			'	U
USBIACS	SRL10, type	R/W, OHS	et ux iAz, re	set uxuu (	JIG A / HO	st wode) (s	ee page 10		OL DDT	0741150	OFTUD	Leuron	EDDOD	FIFONE	TVDDV
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL11, type	R/W, offse	et 0x1B2, re	set 0x00 (0	OTG A / Ho	st Mode) (s	ee page 10	,				ı			
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL12, type	R/W, offse	et 0x1C2, re	eset 0x00 (	OTG A / Ho	st Mode) (s	ee page 10	066)							
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL13, type	R/W, offse	et 0x1D2, re	set 0x00 (	OTG A / Ho	st Mode) (s	ee page 10	066)							
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL14, type	R/W, offse	et 0x1E2, re	set 0x00 (0	OTG A / Ho	st Mode) (s	ee page 10	066)							
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL15, type	R/W, offse	et 0x1F2, re	set 0x00 (0	OTG A / Hos	st Mode) (s	ee page 10	066)							
								NAKTO	CLRDT	STALLED	SETUP	FLUSH	ERROR	FIFONE	TXRDY
USBTXCS	SRL1, type I	R/W, offset	0x112, res	et 0x00 (O	TG B / Devi	ce Mode) (s	see page 1	066)				1			
				•		, ,		,	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL2, type I	R/W, offset	0x122. res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)			I			I	I
	, -5   -5	,	_, . 30	,•		/(	- 13	,	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
HSBTYCS	SRL3, type I	R/W offers	0x132 ree	et UXUU (O.	TG B / Davi	ce Mode) (	see nage 1	066)	02.001	J LLLD	J., 1LL	1 . 23011	J.151114	5112	
CODIACO	Jiteo, type i	. rr, 011361	. 0.102, 165	O. 0200 (O	. 5 5 / 56/1	os moue) (	Jee page 1	550)	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
HEBTYCE	CDI 4 from a	7/M -ff4	0.442	-4 0×00 (O	TC D / David	as Mada\ (	1	000)	CLRD1	STALLED	STALL	FLUSH	UNDRIN	FIFONE	IARDI
USBIACS	SRL4, type I	K/VV, Olisei	UX142, res	et uxuu (O	IG B / Devi	ce wode) (	see page 1	000)	OL DDT	OTALLED	OTALL	FLUOU	LINDDN	FIFONE	TVDDV
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL5, type I	R/W, offset	0x152, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL6, type I	R/W, offset	0x162, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL7, type I	R/W, offset	0x172, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL8, type I	R/W, offset	0x182, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL9, type I	R/W, offset	0x192, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page 1	066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL10, type	R/W, offse	et 0x1A2, re	set 0x00 (	OTG B / De	vice Mode)	(see page	1066)							
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL11, type	R/W, offse	et 0x1B2, re	set 0x00 (0	OTG B / Dev	vice Mode)	(see page	1066)				ı			
									CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL12, type	R/W, offse	et 0x1C2, re	set 0x00 (	OTG B / De	vice Mode)	(see page	1066)				l			
				•		<u> </u>		,	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USBTXCS	SRL13, type	R/W. offse	et 0x1D2, re	set 0x00 (	OTG B / De	vice Mode)	(see page	1066)							
	, .,,	,	,, v,, 1, 2, 1, 0				(occ page	.000)	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
USRTYCE	SRL14, type	R/W offer	at 0x1F2 ra	set Oyno (	OTG B / Do	vice Mode)	(see nage	1066)	02.001	3 LLLD	J., 1LL	1 . 23011	551414	5112	.,
CODIAGO	∟.∍, type	, 01130	VA I E E, 16			141046)	,see page	. 300,	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	TXRDY
HERTYCE	SRL15, type	D/M cff	ot 0 v 1 E 2 · · ·	ent nunn "	TG P / D	vico Meda'	(see naa-	1066)	OLIVDI	SIALLED	UIALL	1 20011	OIADIXIA	I II ONE	IANDI
OBLINCS	∍r⊾ia, type	RAVV, OHS	st UX IF∠, Γθ	sei uxuu (C	ישעום טוע	vice Wiode)	(see page	1000)	CLEDT	QTALLED	QTALL	FLUSH	HNDDN	EIEONE	TXRDY
HODEYA	SDUC 6	D/M - **	L 0::440	-4.000.10	TC 4 //:	· Made :		74)	CLRDT	STALLED	STALL	FLUSH	UNDRN	FIFONE	ואאטז
OPRIXCS	SRH1, type	K/VV, OTTSE	UX113, res	et uxuu (O	IG A / HOS	(se	e page 107			MOD =	D1445::	- FD-	DMANGE	D.T.4:-	<b></b>
	anus :							AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	SRH2, type	K/W, offset	t Ux123, res	et 0x00 (O	IG A / Hos	t Mode) (se	e page 107	,							
								AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	SRH3, type	R/W, offset	t 0x133, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 107	,							
								AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	SRH4, type	R/W, offset	t 0x143, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 107	71)							
								AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	SRH5, type	R/W, offset	t 0x153, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 107	71)							
								AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
			t 0x163, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10	71)							
	, .,,,					,, (	- 1-3	AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH7. type I	R/W. offset	t 0x173, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10								
	, ., ,,					, , , , ,	- 1-3	AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH8. type	R/W. offset	t 0x183, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10								
	, .,,,					, , , , ,	- 1-3	AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH9, type I	R/W. offset	t 0x193, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10								
	, .,,,					,, (	- 1-3	AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH10. type	R/W. offs	et 0x1A3, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1								
	, ,,	,	.,	•				AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH11, type	R/W, offse	et 0x1B3, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1	071)							
	, ,,,,	,	.,					AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH12, type	R/W, offs	et 0x1C3, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1								
		•	,	•		, ,		AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH13, type	R/W, offs	et 0x1D3, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1								
		· · ·		•		, (		AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH14, type	R/W, offs	et 0x1E3, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1								
		· · · · · · · · · · · · · · · · · · ·		•				AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH15, type	R/W, offs	et 0x1F3, re	set 0x00 (0	OTG A / Ho	st Mode) (s	see page 1	071)							
								AUTOSET		MODE	DMAEN	FDT	DMAMOD	DTWE	DT
USBTXCS	RH1, type	R/W, offset	t 0x113, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH2, type	R/W, offset	t 0x123, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH3, type	R/W, offset	t 0x133, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH4, type	R/W, offset	t 0x143, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH5, type	R/W, offset	t 0x153, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH6, type	R/W, offset	t 0x163, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH7, type	R/W, offset	t 0x173, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH8, type	R/W, offset	t 0x183, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH9, type	R/W, offset	t 0x193, res	et 0x00 (O	TG B / Dev	ice Mode) (	see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH10, type	R/W, offs	et 0x1A3, re	eset 0x00 (	OTG B / De	vice Mode)	(see page	1071)							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH11, type	R/W, offse	et 0x1B3, re	eset 0x00 (	OTG B / De	vice Mode)	(see page								
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH12, type	R/W, offs	et 0x1C3, re	eset 0x00 (	OTG B / De	vice Mode)	(see page								
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH13, type	R/W, offs	et 0x1D3, re	eset 0x00 (	OTG B / De	vice Mode)	(see page								
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH14, type	R/W, offs	et 0x1E3, re	eset 0x00 (	OTG B / De	vice Mode)	(see page								
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBTXCS	RH15, type	R/W, offs	et 0x1F3, re	set 0x00 (0	OTG B / De	vice Mode)	(see page	· ·							
								AUTOSET	ISO	MODE	DMAEN	FDT	DMAMOD		
USBRXMA	AXP1, type	R/W, offse	t 0x114, res	et 0x0000	(see page 1	1075)									
										MAXLOAD	)				

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	XP2, type	R/W. offse	t 0x124. res	set 0x0000	(see page			1	-						
					(	,				MAXLOAD					
USBRXMA	XP3, type	R/W, offse	t 0x134, res	set 0x0000	(see page	1075)									
		· ·				,				MAXLOAD					
USBRXMA	XP4, type	R/W, offse	t 0x144, res	set 0x0000	(see page	1075)									
		<u> </u>	<u>, , , , , , , , , , , , , , , , , , , </u>			· ·				MAXLOAD					
USBRXMA	XP5, type	R/W, offse	t 0x154, res	set 0x0000	(see page	1075)									
			<u> </u>							MAXLOAD					
USBRXMA	XP6, type	R/W, offse	t 0x164, res	set 0x0000	(see page	1075)									
										MAXLOAD					
USBRXMA	XP7, type	R/W, offse	t 0x174, res	set 0x0000	(see page	1075)									
										MAXLOAD					
USBRXMA	XP8, type	R/W, offse	t 0x184, res	set 0x0000	(see page	1075)									
										MAXLOAD					
USBRXMA	XP9, type	R/W, offse	t 0x194, res	set 0x0000	(see page	1075)									
										MAXLOAD					
USBRXMA	XP10, type	R/W, offs	et 0x1A4, r	eset 0x000	00 (see page	e 1075)									
										MAXLOAD					
USBRXMA	XP11, type	R/W, offs	et 0x1B4, re	eset 0x000	0 (see page	e 1075)									
										MAXLOAD					
USBRXMA	XP12, type	R/W, offs	et 0x1C4, r	eset 0x000	00 (see page	e 1075)									
										MAXLOAD					
USBRXMA	XP13, type	R/W, offs	et 0x1D4, r	eset 0x000	00 (see page	e 1075)									
										MAXLOAD					
USBRXMA	XP14, type	R/W, offs	et 0x1E4, re	eset 0x000	0 (see page	e 1075)									
										MAXLOAD					
USBRXMA	XP15, type	R/W, offs	et 0x1F4, re	eset 0x000	0 (see page	1075)									
										MAXLOAD					
USBRXCS	RL1, type I	R/W, offset	t 0x116, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 107	7)							
												و			
												DATAERR / NAKTO			
								CLRDT	STALLED	REQPKT	FLUSH	H. A.	ERROR	FULL	RXRDY
												DATA			
USBRXCS	RL2, type f	R/W, offset	t 0x126, res	set 0x00 (O	TG A / Hos	t Mode) (se	ee page 107	7)				I			
												0			
												NAKT			
								CLRDT	STALLED	REQPKT	FLUSH	RR V	ERROR	FULL	RXRDY
												DATAERR / NAKTO			
USBRYCS	RI3 type !	R/W. offers	1 0x136 rec	set OxOo (O	TG A / Hos	t Mode) (se	e nage 107	7)							
202.000	, type i	, 511361		0.00 (0			.5 page 107	·,							
												IAKTC			
								CLRDT	STALLED	REQPKT	FLUSH	۳. ۲.	ERROR	FULL	RXRDY
												DATAERR / NAKTO			
UODE://o-												٥			
USBRXCS	KL4, type I	k/W, offset	t UX146, res	set 0x00 (O	IGA/Hos	t Mode) (se	ee page 107	7)							1
												¥KT0			
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
												TAER			
												5			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
JSBRXC	SRL5, type	R/W, offset	t 0x156, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	77)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL6, type	R/W, offset	t 0x166, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	77)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL7, type	R/W, offset	t 0x176, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	77)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
JSBRXC	SRL8, type	R/W, offset	t 0x186, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	77)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL9, type	R/W, offset	t 0x196, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	77)							
	7.21			•			, 0		STALLED	REQPKT	FLUSH	DATAERR/ NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL10, typ	e R/W, offs	et 0x1A6, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1	077)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL11, type	e R/W, offse	et 0x1B6, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1	077)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXC	SRL12, typ	e R/W, offs	et 0x1C6, re	eset 0x00 (	OTG A / Ho	st Mode) (	see page 1	077)		1		1			
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
JSBRXC	SRL13, typ	e R/W, offs	et 0x1D6, re	eset 0x00 (	OTG A / Ho	st Mode) (	see page 1	077)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBRXCS	SRL14, type	R/W, offse	et 0x1E6, re	eset 0x00 (0	OTG A / Ho	st Mode) (	see page 1	077)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXCS	SRL15, type	R/W, offse	et 0x1F6, re	set 0x00 (0	OTG A / Ho	st Mode) (	see page 1	077)							
								CLRDT	STALLED	REQPKT	FLUSH	DATAERR / NAKTO	ERROR	FULL	RXRDY
USBRXCS	SRL1, type	R/W, offset	t 0x116, res	et 0x00 (O	ΓG B / Devi	ce Mode) (	see page 1	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL2, type	R/W, offset	t 0x126, res	et 0x00 (O	ΓG B / Devi	ce Mode)	(see page	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL3, type	R/W, offset	t 0x136, res	et 0x00 (O	ΓG B / Devi	ce Mode)	(see page					1			
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL4, type	R/W, offset	t 0x146, res	et 0x00 (O	TG B / Devi	ce Mode)	(see page		OTALL ED	OTALL	FLUCII	DATAEDD	OVED.	F	DVDDV
HEDDYC	CDI F franci	7/M -ff4	1 0×450 ×22	-4 0×00 (O	FC B / David	aa Mada)	(222 222 1	CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRACS	SRL5, type	K/VV, OTISEI	( UX156, res	et uxuu (O	IG B / Devi	ce Mode)	(see page	CLRDT	CTALLED	CTALL	FLUCII	DATAERR	OVED.	FULL	DVDDV
HEBBYC	SRL6, type I	D/M offect	10v166 ros	ot 0×00 (O	TG B / Dovi	co Modo)	(see page )		STALLED	STALL	FLUSH	DAIAERR	OVER	FULL	RXRDY
OSBRACE	SICEO, type	VVV, Olisei	0 0 100, 165	O) 00x0 19	IG B / Devi	ce wiode)	see page	CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
LISBRYCS	SRL7, type	P/W offeet	10v176 ros	et UVUU (O.	TG B / Devi	ce Mode)	(see nage 1		STALLED	STALL	1 20311	DAIALINI	OVER	TOLL	IXXIDI
OODICAGO	JILLY, LYPE	VVI, 011361	0.000	0) 0000 10	I G B / Bevi	ce mode,	(see page	CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL8, type	R/W offset	10x186 res	et 0x00 (O	TG B / Devi	ce Mode)	see nage '		OTALLED	OTALL	1 20011	Dr tir Li ti t	OVER	1 OLL	1000
		211, 01100		0,000			(ccc page	CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL9, type	R/W. offset	t 0x196. res	et 0x00 (O	TG B / Devi	ce Mode)	see page					1			1
		<u> </u>	· · ·	•				CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL10, type	R/W, offse	et 0x1A6, re	eset 0x00 (	OTG B / De	vice Mode	) (see page	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL11, type	R/W, offse	et 0x1B6, re	eset 0x00 (0	DTG B / De	vice Mode	) (see page	: 1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL12, type	R/W, offse	et 0x1C6, re	eset 0x00 (	OTG B / De	vice Mode	) (see page	1077)		1		1			-
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL13, type	R/W, offse	et 0x1D6, re	eset 0x00 (	OTG B / De	vice Mode	) (see page	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL14, type	R/W, offse	et 0x1E6, re	eset 0x00 (0	OTG B / De	vice Mode	(see page	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRL15, type	R/W, offse	et 0x1F6, re	eset 0x00 (0	OTG B / De	vice Mode)	(see page	1077)							
								CLRDT	STALLED	STALL	FLUSH	DATAERR	OVER	FULL	RXRDY
USBRXCS	SRH1, type	R/W, offse	t 0x117, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH2, type	R/W, offse	t 0x127, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH3, type	R/W, offse	t 0x137, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH4, type	R/W, offse	t 0x147, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH5, type	R/W, offse	t 0x157, res	et 0x00 (O	TG A / Hos	t Mode) (se	ee page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBRXCS	SRH6, type	R/W, offset	t 0x167, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10	82)			1				
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH7, type	R/W, offset	t 0x177, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10	82)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH8, type	R/W, offset	t 0x187, res	set 0x00 (O	TG A / Hos	t Mode) (se	e page 10								
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH9, type	R/W, offset	t 0x197, res	et 0x00 (O	TG A / Hos	t Mode) (se	e page 10								
									AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH10, type	e R/W, offs	et UX1A7, re	eset uxuu (	DIG A / Ho	St Mode) (S	see page 1		ALITORO	DMAEN	DIDEDD	DMAMOD	DTWE	DT	
HEDDAG	SDUM tom	D/M offer	-4 0×4D7 ×		OTC A /IIa	at Mada) (a	1		AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRACS	SRH11, type	e R/VV, OTIS	et ux1B7, re	eset uxuu (	JIG A / Ho	st wode) (s	see page 1		AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
LISBRYCS	SRH12, type	P/W offer	et 0v1C7 re	seat OvOO (	OTG A / Ho	et Mode) (s	see nage 1		AUTORQ	DIVIACIN	FIDERK	DIVIAIVIOD	DIWE	Di	
	<u>-</u> , typt	, 01131	J. J. 101, 10		210A/110	J. 111Jub) (3	oo pago i		AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH13, type	R/W, offse	et 0x1D7, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1					1			
			· · · · · ·	•					AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH14, type	R/W, offse	et 0x1E7, re	eset 0x00 (	OTG A / Ho	st Mode) (s	see page 1	082)			1				
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH15, type	R/W, offs	et 0x1F7, re	eset 0x00 (0	OTG A / Ho	st Mode) (s	ee page 1	082)							
								AUTOCL	AUTORQ	DMAEN	PIDERR	DMAMOD	DTWE	DT	
USBRXCS	SRH1, type	R/W, offset	t 0x117, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	SRH2, type	R/W. offset	t 0x127. res	set 0x00 (O	TG B / Devi	ce Mode) (	see page	1082)							
	, <b>y</b> pc	,	· · · · · · · · · · · · · · · · · · ·				ooo pago	AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	SRH3, type	R/W, offset	t 0x137, res	set 0x00 (O	TG B / Devi	ce Mode) (	see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	SRH4, type	R/W, offset	t 0x147, res	et 0x00 (O	TG B / Devi	ce Mode) (	see page	1082)			1				
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	SRH5, type	R/W, offset	t 0x157, res	set 0x00 (O	TG B / Devi	ce Mode) (	see page	1082)			I.				
				· .			. •	AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBRXCS	RH6, type	R/W, offset	t 0x167, res	et 0x00 (O	TG B / Devi	ice Mode)	(see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH7, type	R/W, offset	t 0x177, res	et 0x00 (O	TG B / Devi	ice Mode)	(see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH8, type	R/W, offset	t 0x187, res	et 0x00 (O	TG B / Devi	ice Mode)	(see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH9, type	R/W, offset	t 0x197, res	et 0x00 (O	TG B / Devi	ice Mode)	(see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCSI	RH10, type	R/W, offse	et 0x1A7, re	eset 0x00 (	OTG B / De	vice Mode	) (see page	e 1082)							
		·	<u>, , , , , , , , , , , , , , , , , , , </u>	<u> </u>			<u> </u>	AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH11, type	R/W, offse	et 0x1B7, re	set 0x00 (0	OTG B / De	vice Mode	) (see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH12, type	R/W, offs	et 0x1C7, re	eset 0x00 (0	OTG B / De	vice Mode	) (see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH13, type	R/W, offs	et 0x1D7, re	eset 0x00 (0	OTG B / De	vice Mode	) (see page	1082)							
								AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXCS	RH14, type	R/W, offs	et 0x1E7, re	set 0x00 (0	OTG B / De	vice Mode	) (see page	1082)				1			
		·		,				AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
	SRH15, type								_	-					-
		·	,	,			, , , ,	AUTOCL	ISO	DMAEN	DISNYET / PIDERR	DMAMOD			
USBRXC	OUNT1, type	e RO, offse	et 0x118, re	set 0x0000	(see page	1087)									
									COUNT						
USBRXC	OUNT2, type	e RO, offse	et 0x128, re	set 0x0000	(see page	1087)									
HODBYO	0111170 /	DO "			,	1007)			COUNT						
USBRXC	OUNT3, type	e RO, offse	et 0x138, re	set uxuuuu	(see page	1087)			COUNT						
USBRXC	OUNT4, type	e RO. offse	ot 0x148. re	set 0x0000	(see page	1087)			COUNT						
OODITAG			7. 02 140, 10	301 02000	(occ page	1001)			COUNT						
USBRXC	OUNT5, type	e RO, offse	et 0x158, re	set 0x0000	(see page	1087)									
									COUNT						
USBRXC	OUNT6, type	e RO, offse	et 0x168, re	set 0x0000	(see page	1087)									
									COUNT						
USBRXC	OUNT7, type	e RO, offse	et 0x178, re	set 0x0000	(see page	1087)									
HEDDAC	OUNT8, type	o BO offer	t 0v100 ro	aat 0×0000	/000 page	1007)			COUNT						
USBRAC	OUNTO, type	e RO, onse	et ux 166, re	set uxuuuu	(see page	1067)			COUNT						
USBRXC	OUNT9, type	e RO, offse	et 0x198, re	set 0x0000	(see page	1087)									
	, ,	,	,						COUNT						
USBRXC	OUNT10, ty	pe RO, offs	set 0x1A8, r	reset 0x000	00 (see pag	e 1087)									
									COUNT						
USBRXC	OUNT11, typ	pe RO, offs	et 0x1B8, r	eset 0x000	00 (see pag	e 1087)									
									COUNT						
USBRXC	OUNT12, ty <sub>l</sub>	pe RO, offs	set ux1C8, r	reset uxuuu	(see pag	e 1087)			COUNT						
USBRXC	OUNT13, ty	pe RO, offs	set 0x1D8, r	reset 0x000	00 (see pag	e 1087)			000111						
	1, 3,	, ,							COUNT						
USBRXC	OUNT14, ty	pe RO, offs	set 0x1E8, r	eset 0x000	0 (see pag	e 1087)									
									COUNT						
USBRXC	OUNT15, ty	pe RO, offs	set 0x1F8, r	eset 0x000	0 (see pag	e 1087)									
HODTYT	VDE4 time F	2/M -ff4	0:444	-t 0×00 (oo	a nama 100	10)			COUNT						
USBIAI	YPE1, type F	t/vv, onset	UXTIA, IES	et uxuu (se	e page 100	19)		SPI	EED	PRO	OTO		Т	EP	
USBTXT	YPE2, type F	R/W, offset	0x12A, res	et 0x00 (se	e page 108	39)						1	•		
			<u> </u>	,				SPE	EED	PRO	ОТО		Т	EP	
USBTXT	YPE3, type F	R/W, offset	0x13A, res	et 0x00 (se	e page 108	39)									
								SPE	EED	PRO	ОТО		Т	EP	
USBTXT	YPE4, type F	R/W, offset	0x14A, res	et 0x00 (se	e page 108	39)									
HODTYT	VDEE tomas	DAN offers	0v4EA ====	at 0v00 /c -	o noga 100	20)		SPE	EED	PRO	טוט		Т	EP	
USDIXI	YPE5, type F	ww, onset	ux ioA, res	et uxuu (se	e page 108	າອ)		SPI	EED	PPC	OTO		т	EP	
USBTXT	YPE6, type F	R/W, offset	0x16A. res	et 0x00 (se	e page 108	39)		JFI		FRC	,,,,		<u>'</u>	<u></u>	
	., JF	,	. ,	. , , , , , ,	, 5	•		SPE	EED	PRO	ОТО		Т	EP	
USBTXT	YPE7, type F	R/W, offset	0x17A, res	et 0x00 (se	e page 108	39)		1		-		1			
								SPE	EED	PRO	ОТО		Т	EP	
USBTXT	YPE8, type F	R/W, offset	0x18A, res	et 0x00 (se	e page 108	39)		_							
								SPE	EED	PRO	OTO		Т	EP	

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBTXTY	PE9, type F	R/W, offset	0x19A, res	et 0x00 (se	ee page 108	39)		-				1			
								SPI	EED	PRO	ОТО		Tf	ΕP	
USBTXTY	PE10, type	R/W, offse	et 0x1AA, re	eset 0x00 (	see page 10	089)									
								SPI	EED	PRO	ОТО		TE	ΕP	
USBTXTY	PE11, type	R/W, offse	t 0x1BA, re	set 0x00 (	see page 10	089)									
								SPI	EED	PRO	ОТО		TE	ΕP	
USBTXTY	PE12, type	R/W, offse	et 0x1CA, re	eset 0x00 (	see page 10	089)									
								SPI	EED	PRO	ОТО		TE	ΕP	
USBTXTY	PE13, type	R/W, offse	et 0x1DA, re	eset 0x00 (	see page 10	089)									
								SPI	EED	PRO	ОТО		TE	EP	
USBTXTY	PE14, type	R/W, offse	et 0x1EA, re	set 0x00 (	see page 10	089)		0.00		DD	270			-n	
HERTYTY	DE15 type	D/M offer	et 0x1FA, re	eat OvOO (s	200 page 10	180)		581	EED	PRO	ОТО			EP	
USBIXIII	r L 13, type	IVVV, OIISE	t uxii A, ie	Set UXUU (S	see page 10	J09)		SPI	EED	PRO	ОТО		T	ΕP	
USBTXINT	FRVAL1. ft	vne R/W. o	offset 0x11B	3. reset 0x0	00 (see pag	e 1091)		011		110	310				
	, •,	,, , 0		,	, pwg	/					TXPOLL	/ NAKLMT			
USBTXINT	ΓERVAL2, t	ype R/W, o	ffset 0x12B	3, reset 0x0	00 (see pag	e 1091)		-							
											TXPOLL	/ NAKLMT			
USBTXINT	ΓERVAL3, t	ype R/W, o	ffset 0x13B	3, reset 0x0	00 (see pag	je 1091)		'							
											TXPOLL	/ NAKLMT			
USBTXINT	ΓERVAL4, t	ype R/W, o	ffset 0x14B	3, reset 0x0	00 (see pag	e 1091)									
											TXPOLL	/ NAKLMT			
USBTXINT	TERVAL5, t	ype R/W, o	ffset 0x15B	3, reset 0x0	00 (see pag	e 1091)									
											TXPOLL	/ NAKLMT			
USBTXINT	rerval6, t	ype R/W, o	ffset 0x16B	3, reset 0x0	00 (see pag	e 1091)					TYPOLI	/ NIAIZI NAT			
HEDTVINT	FFDVAL 7 4	D/M -	ffeet 0×470		20 /222 222	- 1001)					TXPOLL	/ NAKLMT			
USBIAINI	IERVALI, U	ype R/vv, o	offset 0x17B	s, reset uxt	o (see pag	le 1091)					TYPOLI	/ NAKLMT			
USBTXINT	ΓERVAL8. t	vpe R/W. o	ffset 0x18B	3. reset 0x0	00 (see pag	ie 1091)					TAI OLL	7 147 (IXEIVIT			
	-, ,	, , ,		,		,					TXPOLL	/ NAKLMT			
USBTXINT	ΓERVAL9, t	ype R/W, o	ffset 0x19B	3, reset 0x0	00 (see pag	je 1091)									
											TXPOLL	/ NAKLMT			
USBTXINT	ΓERVAL10,	type R/W,	offset 0x1A	AB, reset 0	x00 (see pa	age 1091)									
											TXPOLL	/ NAKLMT			
USBTXINT	TERVAL11,	type R/W,	offset 0x1B	BB, reset 0	x00 (see pa	ige 1091)									
											TXPOLL	/ NAKLMT			
USBTXINT	TERVAL12,	type R/W,	offset 0x1C	B, reset 0	x00 (see pa	age 1091)									
HODE:	FED. 44: 46	Bas:	-#/ 2 /=	ND 1-	00 /-	4004					TXPOLL	/ NAKLMT			
OSBIXINI	ı ⊨RVAL13,	type R/W,	offset 0x1D	של, reset 0	xuu (see pa	age 1091)					TYDOLL	/ NIA VI * 4 T			
HSBTYINT	TERVAL 14	type P/M	offset 0x1E	R reent 0	v00 (see no	nge 1001)					IAPULL	/ NAKLMT			
OSDIVINI	LINVAL 14,	ype R/W,	OHSEL UX IE	.b, 16561 0	nou (acc pa	igc 1081)					TXPOLL	/ NAKLMT			
USBTXINT	TERVAL15.	type R/W.	offset 0x1F	B, reset 0	<b>x00</b> (see pa	ige 1091)					522				
	-,				, <u>IT 70</u>	/					TXPOLL	/ NAKLMT			
USBRXTY	PE1, type F	R/W, offset	0x11C, res	et 0x00 (se	ee page 109	93)		1							
								SPI	EED	PRO	ОТО		TE	ΕP	
USBRXTY	PE2, type F	R/W, offset	0x12C, res	et 0x00 (se	ee page 109	93)									
								SPI	EED	PRO	ОТО		TE	ΕP	
USBRXTY	PE3, type F	R/W, offset	0x13C, res	et 0x00 (se	ee page 109	93)									
								SPI	EED	PRO	ОТО		TE	ΕP	
USBRXTY	PE4, type F	R/W, offset	0x14C, res	et 0x00 (se	ee page 109	93)									
								SPI	EED	PRO	ОТО		TE	EP	

31	20	20	20	27	26	25	24	1 22	22	24	20	10	40	17	16
15	30 14	29 13	28 12	27 11	26 10	25 9	8	7	6	21 5	20	19	18	17	16 0
	/PE5, type I	R/W, offset	0x15C, res	l set 0x00 (se	ee page 109	93)									-
								SP	EED	PR	ОТО		TI	P	
USBRXTY	PE6, type I	R/W, offset	0x16C, res	set 0x00 (se	ee page 109	93)									
								SP	EED	PR	ото		TI	ΕP	
USBRXTY	PE7, type I	R/W, offset	0x17C, res	set 0x00 (se	ee page 109	93)									
								SP	EED	PR	ото		TI	ΕP	
USBRXTY	PE8, type I	R/W, offset	0x18C, res	set 0x00 (se	ee page 109	93)									
								SP	EED	PR	ОТО		TI	EP	
USBRXTY	PE9, type I	R/W, offset	0x19C, res	set 0x00 (se	ee page 109	93)		CD	FED	DD	OTO		т.	-D	
HERRYTY	/PE10, type	D/M offer	ot 0v1AC re	osat OvOO /	see page 10	103)		5P	EED	PR	ОТО		- 11	EP	
USBRATT	ir Lio, type	K/VV, Olise	st ux IAC, It	eset uxuu (	see page 10	J93)		SP	EED	PR	ОТО		Т	EP.	
USBRXTY	PE11, type	R/W. offse	et 0x1BC. re	eset 0x00 (	see page 10	093)		0.		110			•		
	, 5,6-		,	(	,			SP	EED	PR	ОТО		TI	ΕP	
USBRXTY	PE12, type	R/W, offse	et 0x1CC, re	eset 0x00 (	see page 10	093)		1		1		1			
								SP	EED	PR	ОТО		Т	P	
USBRXTY	PE13, type	R/W, offse	et 0x1DC, re	eset 0x00 (	see page 10	093)									
								SP	EED	PR	ОТО		ТІ	P	
USBRXTY	PE14, type	R/W, offse	et 0x1EC, re	eset 0x00 (	see page 10	093)									
								SP	EED	PR	ОТО		TI	EP	
USBRXTY	PE15, type	R/W, offse	et 0x1FC, re	eset 0x00 (	see page 10	)93)									
HEDDYINI	TEDVAL 4 4	····· DAM		2	20 /222 222	- 100F)		SP	EED	PR	ОТО			P	
USBRXIN	TERVAL1, t	ype ĸ/w, c	omset ux11L	J, reset uxt	(see pag	e 1095)					TYPOLL	/ NAKLMT			
USBRXIN	TERVAL2, t	vpe R/W. c	offset 0x12[	D. reset 0x0	00 (see pag	e 1095)					TAPOLL	/ NAKLIVII			
	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,			ee (ooo pag	0 .000)					TXPOLL	/ NAKLMT			
USBRXIN	TERVAL3, t	ype R/W, c	offset 0x13[	D, reset 0x0	00 (see pag	e 1095)									
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL4, t	ype R/W, c	offset 0x14I	D, reset 0x0	00 (see pag	e 1095)									
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL5, t	ype R/W, c	offset 0x15I	D, reset 0x0	00 (see pag	e 1095)									
											TXPOLL	/ NAKLMT			
USBRXINT	TERVAL6, t	ype R/W, c	offset 0x16I	D, reset 0x	00 (see pag	e 1095)									
HODDYINI	TED\/A1 7 4	DAM .		D 4 O 4	00 /	- 4005)					TXPOLL	/ NAKLMT			
USBRXIN	TERVAL7, t	ype ĸ/w, c	omset ux171	D, reset uxi	υυ (see pag	e 1095)					TYPOLL	/ NAKLMT			
LISBRYINT	TERVAL8, t	vne R/W o	offset Ox18I	D reset fly	00 (see nag	e 1095)					TAPOLL	/ NAKLIVII			
	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		2, 10001 07.	ee (ooo pag	0 .000)					TXPOLL	/ NAKLMT			
USBRXIN	TERVAL9, t	ype R/W, c	offset 0x19[	D, reset 0x0	00 (see pag	e 1095)									
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL10,	type R/W,	offset 0x1/	AD, reset 0	x00 (see pa	ige 1095)		,							
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL11,	type R/W,	offset 0x1E	BD, reset 0	x00 (see pa	ge 1095)									
											TXPOLL	/ NAKLMT			
USBRXINT	TERVAL12,	type R/W,	offset 0x10	CD, reset 0	x00 (see pa	ige 1095)					TXPOLL	/ NAKLMT			
USBRXIN	TERVAL13,	type R/W,	offset 0x1[	DD, reset 0	x00 (see pa	ige 1095)		1							
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL14,	type R/W,	offset 0x1	ED, reset 0	x00 (see pa	ge 1095)									
											TXPOLL	/ NAKLMT			
USBRXIN	TERVAL15,	type R/W,	offset 0x1	FD, reset 0	x00 (see pa	ge 1095)									
											TXPOLL	/ NAKLMT			

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBRQP	KTCOUNT1	, type R/W,	, offset 0x3	04, reset 0:	x0000 (see	page 1097)									
							COL	JNT							
USBRQP	KTCOUNT2	, type R/W,	offset 0x3	08, reset 0:	x0000 (see	page 1097)									
							COL	JNT							
USBRQP	KTCOUNT3	, type R/W,	, offset 0x3	0C, reset 0	x0000 (see	page 1097)	ı								
							COL	JNT							
USBROPE	KTCOUNT4	. type R/W.	, offset 0x3	10. reset 0:	x0000 (see	page 1097)									
		, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,	,		p=9= ::/	COL	INT							
LISBRODE	KTCOUNTS	type P/W	offset 0x3	14 reset 0:	v0000 (see	nage 1007)									
COBINGIL		, 1900 1011,	, 011001 020	14, 10001 0	2220)	page 1007)	COL	INIT							
HEBBORK	/TCOUNTS	tuno B/M	, offset 0x3	10 recet 0	×0000 (000	nogo 1007)		5111							
USBRUFF	KICOUNIO	, type K/vv,	, onset uxs	io, reset u	xuuuu (see	page 1097)	001	INIT							
						4007	COL	JINI							
USBRQP	KICOUNI/	, type R/W,	, offset UX3	1C, reset 0	xuuuu (see	page 1097)									
							COL	JNT							
USBRQP	KTCOUNT8	, type R/W,	, offset 0x3	20, reset 0:	x0000 (see	page 1097)									
							COL	JNT							
USBRQP	KTCOUNT9	, type R/W,	, offset 0x3	24, reset 0:	x0000 (see	page 1097)									
							COL	JNT							
USBRQP	KTCOUNT1	0, type R/V	V, offset 0x	328, reset (	0x0000 (see	e page 1097	)								
							COL	JNT							
USBRQP	KTCOUNT1	1, type R/V	V, offset 0x	32C, reset	0x0000 (se	e page 1097	<b>'</b> )								
							COL	JNT							
USBRQP	KTCOUNT1	2, type R/V	V, offset 0x	330, reset (	0x0000 (see	e page 1097	')								
							COL	JNT							
USBRQP	KTCOUNT1	3, type R/V	V, offset 0x	334, reset (	0x0000 (see	e page 1097	')								
							COL	JNT							
USBRQP	KTCOUNT1	4, type R/V	V, offset 0x	338, reset (	0x0000 (see	e page 1097	')								
							COL	JNT							
USBRQP	KTCOUNT1	5, type R/V	V, offset 0x	33C, reset	0x0000 (se	e page 1097	7)								
							COL	JNT							
USBRXDE	PKTBUFDIS	s, type R/W	, offset 0x3	40, reset 0	x0000 (see	page 1099)	)								
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	
USBTXDP	KTBUFDIS	type R/W	, offset 0x3	42, reset 0	x0000 (see	page 1101)									
EP15	EP14	EP13	EP12	EP11	EP10	EP9	EP8	EP7	EP6	EP5	EP4	EP3	EP2	EP1	
USBEPC,	type R/W,	offset 0x40	0, reset 0x0	0000.0000	(see page 1	103)									
						PFL1	TACT		PFLTAEN	PFLTSEN	PFLTEN		EPENDE	EF	PEN
USBEPCR	RIS. type R	D. offset 0x	(404, reset	0x0000.000	00 (see pag										
	7 31	,	,		, , ,										
															PF
USBEPCII	M. type R/V	V. offset 0×	408, reset (	0x0000.000	0 (see page	e 1107)									
3022, 311	, ., ,, ,, , , , , , , , , , , , , ,	., 5501 5%			- (ooo page	,									
															PF
USBEPCI	SC, type P/	W. offset N	x40C, rese	t Oxnon no	000 (see na	ge 1108)									
3022, 31	, .,po 10	, 0.1000			(300 pa	33									
															PF
USBDRPI	S type PO	offset 0×4	110, reset 0:	×0000 0000	(see nage	1109)									
JOBBRA	o, type RO	, Jiisel UX4	, 16561 0		, (see page	1109)									
															DECLIME
Hebbbin	hama Darr	-#+ 0- 1	44	.0000 0000	/222	1110)									RESUME
OSBURIM	i, type R/W,	offset UX4	14, reset 0		(see page	1110)									
															DE0:::-
															RESUME

45	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
USBDRIS	SC, type W1	C, offset 0:	x418, reset	0x0000.00	00 (see pag	ge 1111)									
															RESUME
USBGPC	S, type R/W	, offset 0x4	41C, reset	0x0000.000	1 (see pag	e 1112)									
														DEVMODOTG	DEVMOD
USBVDC	type R/W,	offset 0x43	30, reset 0x	0000.0000	(see page	1113)									
															VBDEN
USBVDC	RIS, type R	O, offset 0	x434, reset	0x0000.00	00 (see pag	ge 1114)									
															VD
USBVDC	IM, type R/V	V, offset 0x	438, reset	0x0000.000	00 (see pag	e 1115)									
															VD
USBVDC	ISC, type R/	W, offset 0	x43C, rese	et 0x0000.0	000 (see pa	age 1116)									
															1.75
						444=									VD
USBIDVR	RIS, type RO	, offset 0x	444, reset (	UX0000.000	v (see pag	e 1117)									
					• /	1110)									ID
USBIDVII	M, type R/W	, offset 0x4	148, reset (	0x0000.0000	0 (see page	1118)									
															ID.
	20.4				2222 (	4440)									ID
OSBIDVIS	SC, type R/V	V1C, oπse	t ux44C, re	Set UXUUUU	.0000 (see	page 1119)		1							
															ID
LICEDMA	ASEL, type R	AN offeet	0×450 roo	ot 0v0022 2	2244 (222 p	200 1120)									ID
USBDINA	COLL, type N	JVV, Oliset	0,430, 163		ZII (See p	age 1120)		1	DM	ACTX			DMA	ACRX	
					DM	ABRX				AATX				AARX	
	DMA	BTX							<b>D</b>				5.11.2		
Analog		BTX			DIVI	15.01									
_	g Compar	ators			DIVI										
Base 0x	g Compar 4003.C000	ators	OO reset O	×0000 0000											
Base 0x	g Compar	ators	00, reset 0:	×0000.0000											
Base 0x	g Compar 4003.C000	ators	00, reset 0:	×0000.0000									IN2	IN1	INO
Base 0x4	Compar (4003.C000 (ype R/W1C,	offset 0x0			(see page	1129)							IN2	IN1	IN0
ACMIS, ty	g Compar 4003.C000	offset 0x0			(see page	1129)							IN2	IN1	INO
ACMIS, ty	Compar (4003.C000 (ype R/W1C,	offset 0x0			(see page	1129)							IN2	IN1	INO
Base 0x- ACMIS, ty	Compar (4003.C000 (ype R/W1C,	offset 0x0	reset 0x000	00.0000 (see	e page 113	1129)									
Base 0x- ACMIS, ty	g Compar 4003.C000 ype R/W1C, ype RO, offs	offset 0x0	reset 0x000	00.0000 (see	e page 113	1129)									
ACMIS, ty	g Compar 4003.C000 ype R/W1C, ype RO, offs	offset 0x0	reset 0x000	00.0000 (see	e page 113	1129)									
Base 0x- ACMIS, ty  ACRIS, ty	g Compar 4003.C000 ype R/W1C, ype RO, offs	offset 0x00	08, reset 02	00.0000 (see	e page 113	1129)							IN2	IN1	IN0
Base 0x- ACMIS, ty  ACRIS, ty	g Compar 44003.C000 ype R/W1C, ype RO, offs	offset 0x00	08, reset 02	00.0000 (see	e page 113	1129)							IN2	IN1	IN0
Base 0x- ACMIS, ty  ACRIS, ty	g Compar 44003.C000 ype R/W1C, ype RO, offs	offset 0x00	08, reset 02	00.0000 (see	e page 113	1129)	RNG						IN2	IN1	IN0
Base 0x- ACMIS, ty  ACRIS, ty  ACINTEN  ACREFC	g Compar 44003.C000 ype R/W1C, ype RO, offs	offset 0x00  offset 0x004, i	08, reset 0x00000000000000000000000000000000000	00.0000 (see	e page 113 (see page 213 (see page 200) (see page 200)	1129) 0) 1131) 1141) 1151) 1151) 1151) 1151) 1151) 1151) 1151)	RNG						IN2	IN1	INO
Base 0x- ACMIS, ty  ACRIS, ty  ACINTEN  ACREFC	ype RO, offs N, type R/W,	offset 0x00  offset 0x004, i	08, reset 0x00000000000000000000000000000000000	00.0000 (see	e page 113 (see page 213 (see page 200) (see page 200)	1129) 0) 1131) 1141) 1151) 1151) 1151) 1151) 1151) 1151) 1151)	RNG						IN2	IN1	INO
Base 0x- ACMIS, ty  ACRIS, ty  ACINTEN  ACREFC	ype RO, offs N, type R/W,	offset 0x00  offset 0x004, i	08, reset 0x00000000000000000000000000000000000	00.0000 (see	e page 113 (see page 213 (see page 200) (see page 200)	1129) 0) 1131) 1141) 1151) 1151) 1151) 1151) 1151) 1151) 1151)	RNG						IN2	IN1	INO
Base 0x- ACMIS, ty  ACRIS, ty  ACRISTON  ACREFC	ype RO, offs N, type R/W,	offset 0x00 offset 0x004, i	08, reset 00 000, reset 00 0010, reset	00.0000 (see	e page 113  (see page 200 (see	1129) 0) 1131) e 1132) EN	RNG						IN2	IN1 IN1 REF	IN0
Base 0x- ACMIS, ty  ACRIS, ty  ACRISTON  ACREFC	ype RO, offs N, type R/W, TL, type R/W	offset 0x00 offset 0x004, i	08, reset 00 000, reset 00 0010, reset	00.0000 (see	e page 113  (see page 200 (see	1129) 0) 1131) e 1132) EN	RNG						IN2	IN1 IN1 REF	IN0
Base 0x- ACMIS, ty  ACRIS, ty  ACRISTON  ACREFC	ype RO, offs N, type R/W, TL, type R/W	offset 0x00 offset 0x004, i	08, reset 00 000, reset 00 0010, reset	00.0000 (see	e page 113  (see page 200 (see	1129) 0) 1131) e 1132) EN	RNG						IN2	IN1 IN1 REF	IN0
Base 0x- ACMIS, ty  ACRIS, ty  ACINTEN  ACREFC  ACSTATO	ype RO, offs N, type R/W, TL, type R/W	offset 0x00  offset 0x004, in the control offset 0x004  offset 0x004  offset 0x02  offset 0x04	000, reset 0x000, reset 0x00,	00.0000 (see	(see page of see p	1129) 0) 1131) EN 1133)	RNG						IN2	IN1 IN1 OVAL	IN0
Base 0x- ACMIS, ty  ACRIS, ty  ACINTEN  ACREFC  ACSTATO	ype RO, offs  N, type R/W,  TL, type R/W,  1, type RO, c	offset 0x00  offset 0x004, in the control offset 0x004  offset 0x004  offset 0x02  offset 0x04	000, reset 0x000, reset 0x00,	00.0000 (see	(see page of see p	1129) 0) 1131) EN 1133)	RNG						IN2	IN1 IN1 OVAL	IN0

				T				T							
31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
ACCTL0,	type R/W, o	offset 0x024	4, reset 0x0	0000.0000 (	see page 1	134)									
				TOEN		RCP		TSLVAL	18	EN	ISLVAL	l is	EN	CINV	
ACCTL1,	type R/W, o	offset 0x044	4, reset 0x(	0000.0000 (	see page 1	134)		1				1			
				TOEN		RCP		TSLVAL	TS	EN	ISLVAL	IS	EN	CINV	
ACCTL2,	type R/W, o	offset 0x064	4, reset 0x(	0000.0000 (	see page 1	134)		1				1			
				TOEN	ASI	RCP		TSLVAL	TS	EN	ISLVAL	IS	EN	CINV	
	Nidth Mo		(PWM)												
PWM0 b	ase: 0x40	02.8000													
PWMCTL	, type R/W,	offset 0x00	00, reset 0x	0000.0000	(see page 1	1151)		_							
												NC3	NC2	NC1	NCO
												GLOBALSYNC3	GLOBALSYNC2	GLOBALSYNC1	(SALS)
												GLOE	GLOE	GLOE	GLOBALSYNC0
PWMSYN	IC, type R/V	V, offset 0x	004, reset	0x0000.000	0 (see page	e 1153)		-							
												SYNC3	SYNC2	SYNC1	SYNC0
PWMEN#	ABLE, type I	R/W, offset	0x008, res	et 0x0000.0	0000 (see pa	age 1154)									
								PWM7EN	PWM6EN	PWM5EN	PWM4EN	PWM3EN	PWM2EN	PWM1EN	PWM0EN
PWMINVI	ERT, type R	/W, offset 0	x00C, rese	et 0x0000.0	000 (see pa	ige 1156)									
								PWM7INV	PWM6INV	PWM5INV	PWM4INV	PWM3INV	PWM2INV	PWM1INV	PWM0IN\
PWMFAU	ILT, type R/\	N, offset 0x	(010, reset	0x0000.000	00 (see pag	e 1158)									
	1					<u>, , , , , , , , , , , , , , , , , , , </u>									
								FAULT7	FAULT6	FAULT5	FAULT4	FAULT3	FAULT2	FAULT1	FAULT0
PWMINT	EN, type R/\	V. offset Ox	014 reset	0×0000.000	0 (see pag	e 1160)					_			_	
	., ., ,	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	1	(	,						INTFAULT3	INTFAULT2	INTFAULT1	INTFAULT0
													INTPWM2		
PWMRIS	type RO, o	ffset OxO18	reset 0x0	 	ee nage 11	62)									
	type ito, e	I GOT GROTE	, 10001 020		lee page 11	102)						INTFAULT3	INTFAULT2	INTFAULT1	INTFAULT0
													INTPWM2		
DWMISC	type R/W1	C offeet fly	O1C reset	. 0~0000 001	<b>10</b> (see pag	no 1165)							II VII VIIVIZ		
	, .3 po 10 14 l	_, 0.1361 07	, 16361		t (occ pay	(5 1100)						INTFAULT3	INTFAULT2	INTFAULT1	INTFAULTO
													INTPWM2		
DWWGTA	TUS, type F	O offect o	x020 roso	t Oxonon on	00 (see no	ne 1168)						1	"TIT VVIVIZ	TII VVIVII	VVIVIC
I WINISTA	JJ, type r	CO, UNISEL U	,,uzu, 1686		oo (see pag	yc 1100)									
												FAULT3	FAULT2	FAULT1	FAULT0
DWAEAT	II T\/A! 6	o D/W off-	ot 0x024 =	neat 0×000	0000 (000	page 1170	\					ITAULIS	IAULIZ	IAULII	IAULIU
FVVIVIFAU	ILTVAL, typ	e ravv, oits	e. UXU24, F	eset uxuuut 	J.JUUU (See	page 1170	,								
								PWM7	PWM6	PWM5	PWM4	PWM3	PWM2	DIA/NA4	PWM0
DIA/AZZA:	IDD 4 7	NAL CES - 1.0	V020 ===	+ 0×0000 00	00 (225 =	ao 1170\		F VVIVI/	LAAINIO	CIVIVV	F VVIVI4	LANINIS	F VVIVI∠	PWM1	FVVIVIU
PVVIVIENU	JPD, type R	vv, oitset 0	JAU∠O, FESE	L UXUUUU.00	(see pag	ye 11/2)									
E	UPD7	EN::	JPD6	EN.:	IDDE	E***	JPD4	E	IDD2	EN::	IDD2		IDD1		JPD0
			-		IPD5		JE'D4	ENU	JPD3	EINC	JPD2	EINC	JPD1	EINC	יוי טט
PWM0CT	L, type R/W	, offset 0x0	J4U, reset 0	XUUU0.000(	(see page	11/6)								I	FI TOD -
555	LLUSS	555	) EUDS	5-1-	LUBB		DUES		ALIDS	ON FOOT TO	ON FOR I TO	10451:55	LATCH	MINFLTPER	FLTSRC
	LLUPD		SEUPD		LUPD		BUPD	GEN	AUPD	CMPBUPD	CMPAUPD	LOADUPD	DEBUG	MODE	ENABLE
PWM1CT	L, type R/W	, offset 0x0	)80, reset (	00000.0000	(see page	1176)								I	l
													LATCH	MINFLTPER	
DBFA	LLUPD	DBRIS	SEUPD	DBCT	LUPD	GEN	BUPD	GEN	AUPD	CMPBUPD	CMPAUPD	LOADUPD	DEBUG	MODE	ENABLE

31	30 14	29 13	28 12	27	26	25 9	24 8	23	22	21	20	19	18	17	16
15				11	10		0	7	6	5	4	3	2	1	0
PWWZCII	L, type R/W	, onset uxt	JCU, reset t	0x0000.000	(see page	1176)							LATCH	MINFLTPER	FLTCDC
DREAL	LLUPD	DRDIS	SEUPD	DBCT	TIDD	GENE	RIJDD	CEN	AUPD	CMDRI IDD	CMPAUPD	LOADUPD	DEBUG	MODE	FLTSRC
							BUFD	GEN	AUFD	CIVIFBUFD	CIVIFAUED	LOADOFD	DEBUG	WODE	ENABLE
PVVIVISCII	L, type K/W	, onset ux	ioo, reset o	x0000.0000	(see page	1170)							LATCH	MINFLTPER	ELTERC
DREAL	LLUPD	DRDIS	SEUPD	DBCT	TIDD	GENE	RIJDD	CEN	AUPD	CMDRI IDD	CMPAUPD	LOADUPD		MODE	FLTSRC
						GENBUPD		GLIV	AOFD	CIVIFBOFD	CIVIFACIFE	LOADOFD	DLBOG	WODL	LIVABLE
PANIOINI	EN, type K	/ww, onset c	78044, 1656	t 0x0000.00	(See pa	ge i ioi)									
		TROMPRO	TRCMPRI I	TRCMPAD	TRCMPALL	TRONTI OAD	TPCNTZEPO			INTCMPRD	INTCMPRII	INTCMPAD	INTOMPALL	INTCNTLOAD	INTONTZERO
DWM1INT	EN type P			t 0x0000.00			mornizatio					1.410715		III OII LOVE	III OI II E
. ************	Lit, type it	/vv, onset c	7,004,1636		(see pa	gc 1101)									
		TRCMPBD	TRCMPBU	TRCMPAD	TRCMPAU	TRCNTI OAD	TRCNTZERO			INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM2INT	FN type R			et 0x0000.00										1	
	Lit, type it	, onser e	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		occ pa	gc 1101)									
		TRCMPBD	TRCMPBU	TRCMPAD	TRCMPAU	TRCNTI OAD	TRCNTZERO			INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
DWM3INT	EN type P			t 0x0000.00			mornizatio					1.410715		III OII LOVE	III OII EEI
	Lit, type it	, onset e	7, 104, 1050		(occ pa	90 1101)									
		TRCMPBD	TRCMPBU	TRCMPAD	TRCMPAU	TRCNTLOAD	TRCNTZERO			INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM0RIS	tyne RO.			0000.0000											
	, type ito,	11001 0204	, reser ex		occ page 1	10-1)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM1RIS	tyne RO	offset 0x08	18 reset Ox	0000.0000	see nage 1	184)								1	
1 WWITTE	, type ito,	Oliset Oxoc	0, 16361 02		(See page 1	104)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM2RIS	tyne RO	offset 0x00	28 reset Ox	0000.0000	(see nage 1	184)								1	
	, type ito,	11001 0200	, 10001 02		(occ page	104)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM3RIS	tyne RO.	offset 0x10	18. reset 0x	0000.0000	see nage 1	184)									
	, type ito,	- Index ox re	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		occ page 1	10-1)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWMOISC	tyne R/W	1C offset (	NOAC rese	t 0x0000.00	100 (see na	ge 1186)								1	
	, type ratt	, onser e	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		occ pa	90 1100)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM1ISC	type R/W	1C. offset 0	)x08C, rese	t 0x0000.00	000 (see na	ge 1186)									
	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,			(000 pa	90 1100)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM2ISC	type R/W	1C. offset 0	)x0CC. rese	et 0x0000.0	000 (see pa	ae 1186)						l			
	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,				( p-	g,									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM3ISC	type R/W	1C. offset 0	)x10C. rese	t 0x0000.00	000 (see na	ge 1186)									
	, ,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		(000 pa	90 1100)									
										INTCMPBD	INTCMPBU	INTCMPAD	INTCMPAU	INTCNTLOAD	INTCNTZERO
PWM0I O	AD, type R	/W. offset 0	x050, reset	t 0x0000.00	00 (see nad	ne 1188)									
	,,,,,,				( p	,,									
							LO	AD							
PWM1I O	AD, type R	/W. offset ∩	x090, reset	t 0x0000.00	00 (see nad	ie 1188)									
	, type K	, 511361 0	, 16361		-5 (occ pa	,5 1100)									
							LO	AD							
DWM2L O	AD type B	/W offeet 0	vnDn roso	t 0x0000.00	00 (see po	ne 1188\									
. WINIZEO/	nυ, type κ	TT, UIISELU	AUDU, IESE		(see pa	yo 1100)									
							10	۸D							
							LO	ער							

24	20	20	20	07	26	25	24	22	22	24	20	10	10	47	16
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	23 7	22 6	21 5	20 4	19	18	17	16 0
							9	,	U	J	+	3		'	U
PVVIVI3LO	AD, type R/	vv, onset u	x110, reset	UXUUUU.UU 	oo (see pag	je 1100)									
							10	AD							
DWMOCO	UNT toma D	0 -#	Dv054 ****	4 0~0000 00	200 /222 22	~~ 1100\	LO	IAD .							
PVVIVIUCO	UNT, type R	o, onset t	7,054, 1656		(see pa	ge 1169)									
							001	LINIT							
DIAMAAAAA	UNIT 4 D	0 - 55 4 /	2004	4.00000.00	200 (	4400\	COI	UNI							
PWWTCO	UNT, type R	to, onset t	JXU94, rese	 	oo (see pa	ge 1169)									
							COI	LINIT							
DWW	UNT toma D	0 -#	2×0D4 ****	4 0~0000 0	000 (222 22	an 1100)		UNI							
PVVIVIZCO	UNT, type R	to, onset t	JXUD4, rese		ooo (see pa	ige (169)									
							COI	LINIT							
DWWACO	UNT toma D	0 -#	Dv444 ****	4 020000 00	100 /222 72	~~ 1100\		UNI							
PWW3CO	UNT, type R	O, onset (	JX114, rese	T UXUUUU.UU	(see pa	ge 1189)									
							COL	LINIT							
DIAMAGON	DA 4 5."	M 055	WAER	. 0.0000 00	00 (005 =	70 1100		UNT							
- WINDCINI	PA, type R/	vv, orrset 0	AUDO, FESEI	UXUUUU.UU 	υυ (see paç	ye 1190)									
							001	MDA							
DIA/R44 CT-	DA 4: 5:	M -#	w000 - :	0	00 (	~~ 1100`	COI	MPA							
PWW1CM	PA, type R/	vv, orrset 0	xuyo, resei	UXUUUU.00	υυ (see paç	ge 1190)									
							001	MPA							
						1100)		WIPA							
PWM2CM	PA, type R/	w, offset u	XUD8, rese	t 0x0000.00	ou (see pa	ge 1190)									
							001	I I							
							COI	MPA							
PWM3CM	PA, type R/	w, offset u	x118, reset	0x0000.00	uu (see pag	ge 1190)									
							001	I I							
D14/140014						4404)	COI	MPA							
PWMUCM	PB, type R/	w, offset u	IXU5C, rese	t 0x0000.00	ou (see pa	ge 1191)									
							001	MDD							
DIAMAGNA	DD 4 D/	NA - 55 4 C		4.00000.00	200 /	4404)		MPB							
PWM1CM	PB, type R/	w, offset u	IXU9C, rese	t 0x0000.00	ou (see pa	ge 1191)									
DIAMEGOS	DD 4 5:	NA - 65 - 7 -	AD.C	4.00000	000 /-	4404	COI	MPB							
PWM2CM	PB, type R/	vv, offset (	IXUDC, rese	et UXUOOO.0	ບບບ (see pa	ige 1191)									
							001	MDD							
D14440014						4404)	COI	MPB							
PWM3CM	PB, type R/	w, offset u	1x11C, rese	t 0x0000.00	ou (see pa	ge 1191)									
							200	MDD							
DWGGG	NA /	M - ** · ·			<b></b>	4400:	COI	MPB							
PWM0GEI	NA, type R/	vv, offset 0	xu60, reset	UXUUU0.00	υυ (see pa	ge 1192)									
				4070	MDDD	AOTO	MDDL	ACTO	IDAD	AOTO	4DAL!	4.07	LOAD	4.07	7500
DIAGON	NA : -	M - **	-040		MPBD	ACTC	INIPBU	ACTCM	IPAU	ACTC	VIPAU	ACT	LOAD	ACT	ZERO
PWM1GEI	NA, type R/	vv, offset 0	XUAU, rese	τ υχυυοο.00 	יייט (see pa	ge 1192)									
				4070	MDDD	AOTO	MDDL	ACTO	IDAD	AOTO	4DAL!	4.07	LOAD	ACT	ZEDO
DIAMESS	NA 4 5	M - 62 - 1 -	-050		MPBD	ACTC	INIPBU	ACTCM	IPAU	ACTC	VIPAU	ACT	LOAD	ACT	ZERO
PWM2GEI	NA, type R/	vv, offset 0	xu⊑u, rese	t UXUUOO.00	(see pa	ge 1192)									
				4070	MDDD	AOTO	MDDL	ACTO	IDAD	AOTO	4DAL!	407	LOAD	ACT	ZEDO
D			100		MPBD	ACTC	INIPBU	ACTCM	IPAU	ACTC	VIPAU	ACT	LOAD	ACIZ	ZERO
PWM3GEI	NA, type R/	vv, offset 0	x120, reset	UX0000.00	ໜ (see pa	ge 1192)									
					MADDE		MDDI:		10.40		4541:		1015		7500
				ACTC	MPBD	ACTC	MPBU	ACTCM	IPAD	ACTC	VIPAU	ACT	LOAD	ACT	ZERO

24	20	20	20	27	26	25	24	1 22	22	24	20	10	10	17	10
31 15	30 14	29 13	28 12	27 11	26 10	25 9	24 8	7	22 6	21 5	20	19	18	17	16 0
	NB, type R/						0		0	J J	-			'	0
	ND, type it	11, 011001	, 1000		oo (occ pa	190 1100)									
				ACTC	MPBD	ACTO	MPBU	ACTO	CMPAD	ACTO	CMPAU	ACTI	LOAD	ACT	ZERO
PWM1GE	NB, type R/	W, offset 0	0x0A4, rese	t 0x0000.00	000 (see pa	age 1195)									
	7.71	,				]									
				ACTC	MPBD	ACTO	MPBU	ACTO	MPAD	ACTO	CMPAU	ACTI	_OAD	ACT	ZERO
PWM2GE	NB, type R/	W, offset 0	0x0E4, reset	0x0000.00	000 (see pa	ige 1195)									
				ACTC	MPBD	ACTO	MPBU	ACTO	MPAD	ACTO	CMPAU	ACTI	OAD	ACT	ZERO
PWM3GE	NB, type R/	W, offset 0	0x124, reset	0x0000.00	<b>00</b> (see pa	ige 1195)									
				ACTC	MPBD	ACTO	MPBU	ACTO	MPAD	ACTO	CMPAU	ACTI	LOAD	ACT	ZERO
PWM0DB	CTL, type R	R/W, offset	0x068, rese	t 0x0000.0	<b>000</b> (see p	age 1198)									
															ENABLE
PWM1DB	CTL, type R	R/W, offset	0x0A8, res	et 0x0000.0	000 (see p	age 1198)									
															ENABLE
PWM2DB	CTL, type R	R/W, offset	0x0E8, rese	et 0x0000.0	000 (see p	age 1198)									
															ENABLE
PWM3DB	CTL, type R	R/W, offset	0x128, rese	et 0x0000.0	<b>000</b> (see p	age 1198)									
															ENABLE
PWM0DB	RISE, type	R/W, offse	t 0x06C, res	et 0x0000.	0000 (see	page 1199)									
									DISE	DELAY					
DWM1DB	DISE type	P/M offee	t OvOAC ro	cot OvOOOO	0000 (see	page 1199)			NIOL	DELAI					
r WWW 1DB	KIGE, type	IVV, Olise	UXUAC, 16:		.0000 (see	page 1199)									
									RISE	DELAY					
PWM2DB	RISF, type I	R/W. offse	t 0x0FC, res	set 0x0000	0000 (see	page 1199)									
	, ., po	,			(000	page 1100)									
									RISE	DELAY					
PWM3DB	RISE, type	R/W. offse	t 0x12C. res	et 0x0000.	0000 (see	page 1199)									
	, ,,		,		,	, ,									
								1	RISE	DELAY		1			
PWM0DB	FALL, type	R/W, offse	t 0x070, res	et 0x0000.	0000 (see	page 1200)									
									FALL	DELAY					
PWM1DB	FALL, type	R/W, offse	t 0x0B0, res	set 0x0000	.0000 (see	page 1200)									
									FALL	DELAY					
PWM2DB	FALL, type	R/W, offse	t 0x0F0, res	set 0x0000.	0000 (see	page 1200)									
									FALL	DELAY					
PWM3DB	FALL, type	R/W, offse	t 0x130, res	et 0x0000.	0000 (see	page 1200)									
									FALL	DELAY					
PWM0FL1	rsrco, type	R/W, offs	et 0x074, re	set 0x0000	).0000 (see	page 1201	)								
												FAULT3	FAULT2	FAULT1	FAULT0

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
PWM1FLT	SRC0, type	R/W, offse	et 0x0B4, re	eset 0x0000	.0000 (see	page 1201	)								
												FAULT3	FAULT2	FAULT1	FAULT0
PWM2FLT:	SRC0, type	R/W, offse	et 0x0F4, re	set 0x0000	.0000 (see	page 1201)									
						. • ,									
												FAULT3	FAULT2	FAULT1	FAULT0
DIAMAGE! T	0000 6	D/M -#-	-40-404		0000 /	4004)						TAGETS	TAOLIZ	TAGETT	TAGETO
PVVIVISFLI	SRC0, type	R/VV, OIIS	et ux134, re	set uxuuuu	.uuuu (see	page (201)		1							
												FAULT3	FAULT2	FAULT1	FAULT0
PWM0FLT:	SRC1, type	R/W, offse	et 0x078, re	set 0x0000	.0000 (see	page 1203)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWM1FLT:	SRC1, type	R/W, offse	et 0x0B8, re	eset 0x0000	.0000 (see	page 1203	)								
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
DWM2ELT	SDC1 fun-	D/M off-	ot 0v0E0	sot Ovene	0000 (222	nage 1202)		1 2 3 1411 7	2 3.411 0	20.111 0	20.411 4	20.411 0	2 0.411 E	20.411 1	231111 0
r vvivi∠FLI:	SRC1, type	ravv, ons	et UXUFO, FE	SEL UXUUUU	.oooo (see	paye 1203)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWM3FLT	SRC1, type	R/W, offs	et 0x138, re	set 0x0000	.0000 (see	page 1203)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWMOMIN	FLTPER, ty	pe R/W, of	fset 0x07C	, reset 0x00	000.0000 (s	ee page 12	06)								
				,	`										
							Λ.	   IFP							
DIA/RA4 RAINI	FLITPED 4	D/M	Staat OvODO		000 0000 /	10									
PWWITWIIN	FLTPER, ty	pe R/vv, or	TSET UXUBC	, reset uxu	000.0000 (S	see page 12	106)	1							
								1FP							
PWM2MIN	FLTPER, ty	pe R/W, of	ffset 0x0FC	, reset 0x00	000.0000 (s	ee page 12	06)								
							N	1FP							
PWM3MIN	FLTPER, ty	pe R/W, of	ffset 0x13C	, reset 0x00	000.0000 (s	ee page 12	06)								
								.I							
DWM0ELT	SEN, type I	D/M offect	.0v800 ros	ot Ovonon o	1000 (see n	age 1207)									
· WINIOI EI	OLIN, type i	W 11, O11361	. 0,000, 163		(see p	age 1207)									
												FALU TO	E4111 TO	FA111 T4	FALU TO
												FAULT3	FAULT2	FAULT1	FAULT0
PWM1FLT:	SEN, type I	R/W, offset	0x880, res	et 0x0000.0	0000 (see p	age 1207)									
												FAULT3	FAULT2	FAULT1	FAULT0
PWM2FLT	SEN, type I	R/W, offset	0x900, res	et 0x0000.0	000 (see p	age 1207)									
												FAULT3	FAULT2	FAULT1	FAULT0
PWM3FI T	SEN, type I	R/W offers	0x980 res	et Oxnoon o	000 (see s	age 1207)									
	on, type i	, 511361	163		, сес р	.gc (201)									
												FAL!! TO	FALUTO	FALUE?	FAL!! TO
												FAULT3	FAULT2	FAULT1	FAULT0
PWM0FLT:	STAT0, typ	e -, offset (	0x804, rese	t 0x0000.00	00 (see pa	ge 1208)									
												FAULT3	FAULT2	FAULT1	FAULT0
PWM1FLT	STAT0, typ	e -, offset (	0x884, rese	t 0x0000.00	00 (see pa	ge 1208)									
												FAULT3	FAULT2	FAULT1	FAULT0
												152.13	17.0612	ITAGELL	17.5210

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
PWM2FL	TSTAT0, typ	e -, offset	0x904, rese	t 0x0000.0	000 (see pa	age 1208)		1							
												FAULT3	FAULT2	FAULT1	FAULT0
PWM3FL	TSTAT0, typ	e -, offset	0x984, rese	t 0x0000.0	000 (see pa	age 1208)									
												FAULT3	FAULT2	FAULT1	FAULT0
PWM0FL	TSTAT1, typ	e -, offset	0x808, rese	et 0x0000.0	<b>000</b> (see pa	age 1210)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWM1FL	TSTAT1, typ	e -, offset	0x888, rese	et 0x0000.0	000 (see pa	age 1210)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWM2FL	TSTAT1, typ	e -, offset	0x908, rese	et 0x0000.0	000 (see pa	age 1210)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
PWM3FL	TSTAT1, typ	e -, offset	0x988, rese	et 0x0000.0	000 (see pa	age 1210)									
								DCMP7	DCMP6	DCMP5	DCMP4	DCMP3	DCMP2	DCMP1	DCMP0
QEI0 ba	se: 0x4002 se: 0x4002 se: 0x4002	2.C000	terface (	QEI)											
QEICTL,	type R/W, of	ffset 0x000	, reset 0x0	000.0000 (	see page 12	220)									
													FILT	CNT	
		FILTEN	STALLEN	INVI	INVB	INVA		VELDIV		VELEN	RESMODE	CAPMODE	SIGMODE	SWAP	ENABLE
QEISTAT,	type RO, o	ffset 0x004	l, reset 0x0	000.0000 (	see page 12	223)									
														DIRECTION	ERROR
QEIPOS,	type R/W, o	ffset 0x008	8, reset 0x0	000.0000 (	see page 1	224)									
							POS	SITION							
							POS	SITION							
QEIMAXE	POS, type R	/W, offset (	0x00C, rese	et 0x0000.0	000 (see pa	age 1225)									
								XPOS							
							MA	XPOS							
QEILOAD	), type R/W,	offset 0x0	1U, reset 0>	cu000.0000	(see page	1226)		240							
								DAD DAD							
OFITIME	type PO ==	ffeat Nynd 4	L reent nun	000 0000 /	200 0000 11	227)	L	JAU							
≪∟ıılıvı⊏,	, type RO, o		, 1636t UXU		Joe paye 12	/	т	IME							
								IME							
QEICOUN	NT, type RO,	offset 0x0	018, reset 0	x0000.0000	) (see page	1228)	•	· <del>-</del>							
	, ,,,,,,,,,,,	•	.,		, page	-/	CC	UNT							
								DUNT							
QEISPEE	D, type RO,	offset 0x0	1C, reset 0	×0000.000	0 (see page	1229)									
					3-	•	SF	PEED							
								PEED							
		offset 0x0	20, reset 0:	x0000.0000	(see page	1230)									
QEIINTE	N, type R/W,														
QEIINTE	N, type R/W,														
QEIINTE	N, type R/W,											INTERROR	INTDIR	INTTIMER	INTINDEX
	N, type R/W,		reset 0x000	00.0000 (se	ee page 123	32)						INTERROR	INTDIR	INTTIMER	INTINDEX
			reset 0x000	00.0000 (se	ee page 123	32)						INTERROR	INTDIR	INTTIMER	INTINDEX

### Register Quick Reference

31	30	29	28	27	26	25	24	23	22	21	20	19	18	17	16
15	14	13	12	11	10	9	8	7	6	5	4	3	2	1	0
QEIISC, ty	QEIISC, type R/W1C, offset 0x028, reset 0x0000.0000 (see page 1234)														
												INTERROR	INTDIR	INTTIMER	INTINDEX

# **B** Ordering and Contact Information

## **B.1** Ordering Information




Table B-1. Part Ordering Information<sup>a</sup>

Orderable Part Number	Description
LM3S9D96-IQC80-A2	Stellaris® LM3S9D96 Microcontroller Industrial Temperature 100-pin LQFP
LM3S9D96-IBZ80-A2	Stellaris LM3S9D96 Microcontroller Industrial Temperature 108-ball BGA
LM3S9D96-IQC80-A2T	Stellaris LM3S9D96 Microcontroller Industrial Temperature 100-pin LQFP Tape-and-reel
LM3S9D96-IBZ80-A2T	Stellaris LM3S9D96 Microcontroller Industrial Temperature 108-ball BGA Tape-and-reel

a. NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

# **B.2** Part Markings

The Stellaris microcontrollers are marked with an identifying number. This code contains the following information:

- The first line indicates the part number, for example, LM3S9B90.
- In the second line, the first eight characters indicate the temperature, package, speed, revision, and product status. For example in the figure below, IQC80C0X indicates an Industrial temperature (I), 100-pin LQFP package (QC), 80-MHz (80), revision C0 (C0) device. The letter immediately following the revision indicates product status. An X indicates experimental and requires a waiver; an S indicates the part is fully qualified and released to production.
- The remaining characters contain internal tracking numbers.



#### B.3 Kits

The Stellaris Family provides the hardware and software tools that engineers need to begin development quickly.

- Reference Design Kits accelerate product development by providing ready-to-run hardware and comprehensive documentation including hardware design files
- Evaluation Kits provide a low-cost and effective means of evaluating Stellaris microcontrollers before purchase
- Development Kits provide you with all the tools you need to develop and prototype embedded applications right out of the box

See the website at www.ti.com/stellaris for the latest tools available, or ask your distributor.

### **B.4** Support Information


For support on Stellaris products, contact the TI Worldwide Product Information Center nearest you: http://www-k.ext.ti.com/sc/technical-support/product-information-centers.htm.

# C Package Information

# C.1 100-Pin LQFP Package

## C.1.1 Package Dimensions

Figure C-1. Stellaris LM3S9D96 100-Pin LQFP Package Dimensions




**Note:** The following notes apply to the package drawing.

- 1. All dimensions shown in mm.
- 2. Dimensions shown are nominal with tolerances indicated.
- 3. Foot length 'L' is measured at gage plane 0.25 mm above seating plane.

В	ody +2.00 mm Footprint, 1.4 mm packag	e thickness
Symbols	Leads	100L
Α	Max.	1.60
A <sub>1</sub>	-	0.05 Min./0.15 Max.
A <sub>2</sub>	±0.05	1.40
D	±0.20	16.00
D <sub>1</sub>	±0.05	14.00
Е	±0.20	16.00
E <sub>1</sub>	±0.05	14.00
L	+0.15/-0.10	0.60
е	Basic	0.50
b	+0.05	0.22
θ	-	0°-7°
ddd	Max.	0.08
ccc	Max.	0.08
JEDEC Re	eference Drawing	MS-026
Variation	on Designator	BED

### C.1.2 Tray Dimensions

Figure C-2. 100-Pin LQFP Tray Dimensions



## C.1.3 Tape and Reel Dimensions

**Note:** In the figure that follows, pin 1 is located in the top right corner of the device.

Original drawing REV. DETAIL OF CHANGE

0.30±0.05 .\_\_0.3 1.75±0.1 4.0±0.1 Ø1.55±0.05 2.0±0.1 0.5 (Measure at #1.35 plane) plane> (10.75) 13.45±0.1 (measure at 1.55 (12.0) (9:0) A 16.6±0.1 \ø2.05±0.05 20.0±0.1 14.66±0.08 ( 1.00±0.1 \*1,35 1,55 2,1±0,1 ⚠ 16.85±0.1 (12.0) 14.66±0.08 (Measure at \*1.35 plane) 13.81±0,08 (Measure at \*1.35 plane) (12,0) 1.00±0.1 \*1.35 (9.0) 1.00±0.1 13,45±0,1 \*1.35 1.55 POCKET VIEW (10/1) 13.45±0.1 (measure at 1.55 plane) SECTION B-B (6/1) <u> 16.6±0.1</u> No. 300D THIS IS A COMPUTER GENERATED UNCONTROLLED DOCUMENT TITLE LQFP-14\*14\*1.4 DRAWN 06.01.2003 W.L.CHEK SCALE PRINTED ON 06.01.2003 2/1 (6/1, 11/1) SECTION A-A (6/1) 06.01.2003 W.L.CHEK MATERIAL 06.01.2003 DESIGNED PS CHECKED [REMARKS]
Acoumulated 10-aprooket hole pitch is "40±0.2mm".
Not indicated corner radius is "MAX 0.3mm".
Not indicated tolerance is ±0.2mm".
(\*) Indicating measuring plane for "Fence". Removed anti-nesting design.

Change dlm 17.3 ->16.85 & 17.0 ->16.6. 06.01.2003 W.L. CHEK

DRAWING No.

88E-T-525-C

21.11.2002 W.L. CHEK 31.07.2002 W.L. CHEK


DATE SIGNATURE

Figure C-3. 100-Pin LQFP Tape and Reel Dimensions

# C.2 108-Ball BGA Package

## C.2.1 Package Dimensions

Figure C-4. Stellaris LM3S9D96 108-Ball BGA Package Dimensions




**Note:** The following notes apply to the package drawing.

- 1. ALL DIMENSIONS ARE IN MILLIMETERS.
- 2. 'e' REPRESENTS THE BASIC SOLDER BALL GRID PITCH.
- "M" REPRESENTS THE BASIC SOLDER BALL MATRIX SIZE. AND SYMBOL 'N' IS THE NUMBER OF BALLS AFTER DEPOPULATING.
- $\triangle$  'b' is measurable at the maximum solder ball diameter after reflow parallel to primary daium  $\boxed{c}$  .
- ⚠ DIMENSION 'ccc' IS MEASURED PARALLEL TO PRIMARY DATUM [].
- PRIMARY DATUM [] AND SEATING PLANE ARE DEFINED BY THE SPHERICAL CROWNS OF THE SOLDER BALLS.
- 7. PACKAGE SURFACE SHALL BE MATTE FINISH CHARMILLES 24 TO 27.
- 8. SUBSTRATE MATERIAL BASE IS BT RESIN.
- 9. THE OVERALL PACKAGE THICKNESS "A" ALREADY CONSIDERS COLLAPSE BALLS
- 10. DIMENSIONING AND TOLERANCING PER ASME Y14.5M 1994.
- A EXCEPT DIMENSION b.

Symbols	MIN	NOM	MAX
Α	1.22	1.36	1.50
A1	0.29	0.34	0.39
A3	0.65	0.70	0.75
С	0.28	0.32	0.36
D	9.85	10.00	10.15
D1		8.80 BSC	
E	9.85	10.00	10.15
E1		8.80 BSC	
b	0.43	0.48	0.53
bbb		.20	
ddd		.12	
е		0.80 BSC	
f	-	0.60	-
M		12	
n		108	
	REF: C	JEDEC MO-219F	


### C.2.2 Tray Dimensions

Figure C-5. 108-Ball BGA Tray Dimensions



#### C.2.3 **Tape and Reel Dimensions**

Figure C-6. 108-Ball BGA Tape and Reel Dimensions







16-Nov-2013

#### **PACKAGING INFORMATION**

Orderable Device	Status	Package Type	_	Pins	_		Lead/Ball Finish	MSL Peak Temp	Op Temp (°C)	Device Marking	Samples
	(1)		Drawing		Qty	(2)	(6)	(3)		(4/5)	
LM3S9D96-IBZ80-A2	NRND	NFBGA	ZCR	108	184	Green (RoHS & no Sb/Br)	SNAGCU	Level-3-260C-168 HR	-40 to 85	LM3S9D96 IBZ80	
LM3S9D96-IBZ80-A2T	NRND	NFBGA	ZCR	108	1500	Green (RoHS & no Sb/Br)	SNAGCU	Level-3-260C-168 HR	-40 to 85	LM3S9D96 IBZ80	
LM3S9D96-IQC80-A2	NRND	LQFP	PZ	100	90	Green (RoHS & no Sb/Br)		Level-3-260C-168 HR	-40 to 85	LM3S9D96 IQC80	
LM3S9D96-IQC80-A2T	NRND	LQFP	PZ	100	1000	Green (RoHS & no Sb/Br)		Level-3-260C-168 HR	-40 to 85	LM3S9D96 IQC80	

(1) The marketing status values are defined as follows:

**ACTIVE:** Product device recommended for new designs.

LIFEBUY: TI has announced that the device will be discontinued, and a lifetime-buy period is in effect.

NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

PREVIEW: Device has been announced but is not in production. Samples may or may not be available.

**OBSOLETE:** TI has discontinued the production of the device.

(2) Eco Plan - The planned eco-friendly classification: Pb-Free (RoHS), Pb-Free (RoHS Exempt), or Green (RoHS & no Sb/Br) - please check http://www.ti.com/productcontent for the latest availability information and additional product content details.

TBD: The Pb-Free/Green conversion plan has not been defined.

**Pb-Free (RoHS):** TI's terms "Lead-Free" or "Pb-Free" mean semiconductor products that are compatible with the current RoHS requirements for all 6 substances, including the requirement that lead not exceed 0.1% by weight in homogeneous materials. Where designed to be soldered at high temperatures, TI Pb-Free products are suitable for use in specified lead-free processes.

Pb-Free (RoHS Exempt): This component has a RoHS exemption for either 1) lead-based flip-chip solder bumps used between the die and package, or 2) lead-based die adhesive used between the die and leadframe. The component is otherwise considered Pb-Free (RoHS compatible) as defined above.

Green (RoHS & no Sb/Br): TI defines "Green" to mean Pb-Free (RoHS compatible), and free of Bromine (Br) and Antimony (Sb) based flame retardants (Br or Sb do not exceed 0.1% by weight in homogeneous material)

- (3) MSL, Peak Temp. The Moisture Sensitivity Level rating according to the JEDEC industry standard classifications, and peak solder temperature.
- (4) There may be additional marking, which relates to the logo, the lot trace code information, or the environmental category on the device.
- (5) Multiple Device Markings will be inside parentheses. Only one Device Marking contained in parentheses and separated by a "~" will appear on a device. If a line is indented then it is a continuation of the previous line and the two combined represent the entire Device Marking for that device.
- (6) Lead/Ball Finish Orderable Devices may have multiple material finish options. Finish options are separated by a vertical ruled line. Lead/Ball Finish values may wrap to two lines if the finish value exceeds the maximum column width.



#### **PACKAGE OPTION ADDENDUM**

16-Nov-2013

**Important Information and Disclaimer:** The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.

In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.

#### IMPORTANT NOTICE

Texas Instruments Incorporated and its subsidiaries (TI) reserve the right to make corrections, enhancements, improvements and other changes to its semiconductor products and services per JESD46, latest issue, and to discontinue any product or service per JESD48, latest issue. Buyers should obtain the latest relevant information before placing orders and should verify that such information is current and complete. All semiconductor products (also referred to herein as "components") are sold subject to TI's terms and conditions of sale supplied at the time of order acknowledgment.

TI warrants performance of its components to the specifications applicable at the time of sale, in accordance with the warranty in TI's terms and conditions of sale of semiconductor products. Testing and other quality control techniques are used to the extent TI deems necessary to support this warranty. Except where mandated by applicable law, testing of all parameters of each component is not necessarily performed.

TI assumes no liability for applications assistance or the design of Buyers' products. Buyers are responsible for their products and applications using TI components. To minimize the risks associated with Buyers' products and applications, Buyers should provide adequate design and operating safeguards.

TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right relating to any combination, machine, or process in which TI components or services are used. Information published by TI regarding third-party products or services does not constitute a license to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property of the third party, or a license from TI under the patents or other intellectual property of TI.

Reproduction of significant portions of TI information in TI data books or data sheets is permissible only if reproduction is without alteration and is accompanied by all associated warranties, conditions, limitations, and notices. TI is not responsible or liable for such altered documentation. Information of third parties may be subject to additional restrictions.

Resale of TI components or services with statements different from or beyond the parameters stated by TI for that component or service voids all express and any implied warranties for the associated TI component or service and is an unfair and deceptive business practice. TI is not responsible or liable for any such statements.

Buyer acknowledges and agrees that it is solely responsible for compliance with all legal, regulatory and safety-related requirements concerning its products, and any use of TI components in its applications, notwithstanding any applications-related information or support that may be provided by TI. Buyer represents and agrees that it has all the necessary expertise to create and implement safeguards which anticipate dangerous consequences of failures, monitor failures and their consequences, lessen the likelihood of failures that might cause harm and take appropriate remedial actions. Buyer will fully indemnify TI and its representatives against any damages arising out of the use of any TI components in safety-critical applications.

In some cases, TI components may be promoted specifically to facilitate safety-related applications. With such components, TI's goal is to help enable customers to design and create their own end-product solutions that meet applicable functional safety standards and requirements. Nonetheless, such components are subject to these terms.

No TI components are authorized for use in FDA Class III (or similar life-critical medical equipment) unless authorized officers of the parties have executed a special agreement specifically governing such use.

Only those TI components which TI has specifically designated as military grade or "enhanced plastic" are designed and intended for use in military/aerospace applications or environments. Buyer acknowledges and agrees that any military or aerospace use of TI components which have *not* been so designated is solely at the Buyer's risk, and that Buyer is solely responsible for compliance with all legal and regulatory requirements in connection with such use.

TI has specifically designated certain components as meeting ISO/TS16949 requirements, mainly for automotive use. In any case of use of non-designated products, TI will not be responsible for any failure to meet ISO/TS16949.

#### Products Applications

Audio www.ti.com/audio Automotive and Transportation www.ti.com/automotive Communications and Telecom **Amplifiers** amplifier.ti.com www.ti.com/communications **Data Converters** dataconverter.ti.com Computers and Peripherals www.ti.com/computers **DLP® Products** www.dlp.com Consumer Electronics www.ti.com/consumer-apps

DSP **Energy and Lighting** dsp.ti.com www.ti.com/energy Clocks and Timers www.ti.com/clocks Industrial www.ti.com/industrial Interface interface.ti.com Medical www.ti.com/medical logic.ti.com Logic Security www.ti.com/security

Power Mgmt power.ti.com Space, Avionics and Defense www.ti.com/space-avionics-defense

Microcontrollers microcontroller.ti.com Video and Imaging www.ti.com/video

RFID www.ti-rfid.com

OMAP Applications Processors <a href="www.ti.com/omap">www.ti.com/omap</a> TI E2E Community <a href="e2e.ti.com">e2e.ti.com</a>

Wireless Connectivity <u>www.ti.com/wirelessconnectivity</u>